



APPENDIX A

STATEMENT OF WORK

“Landscape Maintenance, Irrigation System Maintenance, and Irrigation System Minor Repairs”

February 17, 2026

1) Background:

The National Laboratory of the Rockies (NLR) is a national laboratory owned by the U.S. Department of Energy (DOE). NLR is managed and operated for DOE’s Office of Energy Efficiency and Renewable Energy by the Alliance for Energy Innovation (Alliance), the “M&O Contractor”.

NLR takes pride in its world-class research, talented staff, sustainable campus and results that positively impact our local, national and global communities. On the NLR sites there are state-of-the-art facilities available to industry entrepreneurs, engineers, scientists, and universities for researching and developing their energy technologies.

NLR’s property extends over 476 acres. There are 164 acres on the South Table Mountain (STM) Campus, 305 acres at the Flatirons Campus, and approximately seven acres at the South Table Energy Park. Of the total acreage, approximately 197 total acres require landscape maintenance as follows: 116 acres on STM Campus, 76 acres on Flatirons Campus, and 5 acres on STEP Campus.

1. The STM Campus includes four (4) distinctive cover types, three of which are vegetated areas:
 - a. Conservation area –
 - i. Conservation areas do not require landscape maintenance.
 - b. Impervious area
 - i. Impervious areas do not require landscape maintenance.
 - c. Natural area – including detention pond, arroyos, and open grassland.
 - i. Natural areas require landscape maintenance.
 - d. Transitional area - including vegetation communities banded around building perimeters;
 - i. Transitional areas require landscape maintenance
2. The Flatirons Campus open space (305 acres) has one dominant open grassland landscape area (entire acreage is natural area). Landscaping services will be

required around building perimeters, and all irrigated landscape areas shall be properly maintained and managed.

3. The South Table Energy Park (STEP) Campus (7 acres) is a predominantly developed area with portions of landscaped areas comprising grass and native vegetation, gravel areas and transitional areas.
 - a. Approximately 5 acres require landscape maintenance. Of the 5 acres, approximately 1.7 acres is turf/gras/sod. Approximately 2 acres of the STEP Campus comprise impervious areas and do not require landscape maintenance.

The primary objective of landscaping and grounds maintenance at NLR is to preserve and maintain its campus open space areas to minimize the negative impacts on the environment and maximize the efficient use of resources to enhance the native and naturalized vegetation communities and wildlife habitat. The Subcontractor shall assist NLR's Site Operations Team to provide various landscaping and irrigation services in the cultivation of both established and improvement project landscape areas. Landscaping and grounds maintenance activities shall be performed using environmentally responsible and sustainable practices, including water-efficient irrigation methods, integrated pest management, soil health preservation, and the use of native or climate-adapted plant species where feasible.

The Subcontractor shall actively and continuously monitor all landscape areas to proactively identify emerging or potential issues, including but not limited to increasing weed pressures, turf stress or decline, irrigation system inefficiencies, soil degradation, erosion risks, and accumulation of vegetative fuels that may contribute to fire hazards. The Subcontractor shall not wait for direction from NLR to identify these conditions. Upon identification, the Subcontractor shall promptly develop and submit written recommendations to the NLR Technical Monitor that describe the issue, proposed corrective or preventive actions, recommended timing, anticipated outcomes, and any associated cost impacts. These recommendations shall be provided early enough to allow corrective actions to be implemented before site conditions deteriorate or result in increased maintenance costs, safety risks, or environmental impacts.

2) NLR Applicable Maintenance Plans:

The Subcontractor shall perform the work with compliance to the following NLR Maintenance Plans and subsequent revisions to the NLR Maintenance Plans:

- a. 2026 NLR Weed Management Plan dated 02-05-2026 – Exhibit 1
- b. Landscape Restoration and Maintenance Guide – Exhibit 7
- c. Wildland/Urban Interface Defensible Space Management Plan – Exhibit 8
- d. Site Maintenance Plan Worksheet (8.1) – Exhibit 9

3) Description of Work: Landscaping Maintenance

The Subcontractor shall provide all supervision, labor, materials, equipment, tools, supplies, chemicals, plants, project management oversight, transportation, safety measures, temporary signage and support services to maintain in a superior condition across all NLR Landscape Areas as outlined below. All work shall be performed in a professional manner,

using quality equipment and sustainable landscaping methods and materials. All Subcontractor staff must have fire extinguishers on-hand for all mowing equipment, trucks, and other motorized equipment utilized on-site.

The Subcontractor shall comply with all requirements of Colorado Air Pollution Control Division (APCD) Regulation No. 29.

Regulation No. 29 establishes seasonal restrictions on the operation of small hand-held lawn and garden equipment during the period of June 1 through August 31, when ozone pollution levels in Colorado are typically elevated.

NLR strongly prefers the use of electric-powered landscaping equipment whenever such equipment is commercially available and suitable for the work being performed. The Subcontractor may utilize gasoline-powered equipment when necessary; however, during the restricted period of June 1 through August 31, the Subcontractor shall comply with all applicable reporting and recordkeeping requirements of Regulation No. 29.

The Subcontractor shall maintain accurate records for all gasoline-powered equipment operated during the restricted period, including, at a minimum, the equipment type, manufacturer, model, and horsepower rating for each piece of equipment. Required reports shall be submitted in accordance with Regulation No. 29 and shall be submitted monthly.

a. Weed Control

1. Prior to the start of each maintenance season (approximately April 1st of each year of the period of performance), the Subcontractor shall provide recommendations that offer approaches and remedies specific to plant species to the NLR Technical Monitor for review and approval. These recommendations shall also include a recommended schedule of services. The NLR Technical Monitor may request additional services on an as-needed basis.
2. The Subcontractor shall use hand removal, mowing, and other mechanical means to remove weeds.
3. Plant waste resulting from weed control shall be bagged and disposed of in dumpsters on-site at NLR or hauled away and disposed of offsite.
 - i. If disposing off-site, the Subcontractor is responsible for disposal fees and complying with legal disposal procedures.

b. Mowing

1. The Subcontractor shall mow for assisting in the establishment, health and timely weed control of grassland areas and lawn grass.
2. Prior to the start of each maintenance season (approximately April 1st of each year of the period of performance), the Subcontractor shall provide recommendations on the schedule for mowing to the NLR Technical Monitor for review and approval. The NLR Technical Monitor may request additional services on an as-needed basis.
3. All trash and debris shall be removed prior to mowing. All trash and debris shall be bagged and disposed of in dumpsters on-site at NLR or hauled away and disposed

- of offsite.
- i. If disposing off-site, the Subcontractor is responsible for disposal fees and complying with legal disposal procedures.
 4. Prior to the mowing or weed eating of any areas other than strips along roads, NLR ESHQ will be contacted to conduct a ground-nesting bird survey prior to mowing activities. NLR's nesting bird season is from March 15th to September 15th.
 5. Mowing shall be performed at times that will have minimal impact to the operations of the facility and provide the greatest safety for the tenants of the facilities, typically between 6:00am and 5:00pm.
 6. Mowing equipment shall be well maintained and cutting blades shall be sharpened as required to prevent safety hazards. All equipment utilized should be in like-new condition. Properly sized mowing equipment shall be used throughout the NLR Campus. Mowers and other Landscape equipment shall not be used close to the stems or trunks of shrubs and trees. For sloping surfaces, equipment manufacturer guidelines must be followed. Slopes exceeding manufacturer guidelines will be hand trimmed or push mowed.
 7. Only mulching and/or bagging mowers shall be used by the Subcontractor; however, mulching mowers are preferred.
 - ii. In the event clippings become too heavy, such as in the spring, the Subcontractor shall use bagging devices to remove the excessive clippings.
 - iii. All grass clippings shall be bagged and disposed of in dumpsters on-site at NLR or hauled away and disposed of offsite.
 1. If disposing off-site, the Subcontractor is responsible for disposal fees and complying with legal disposal procedures.
 - iv. Clippings shall not be dumped in weeds along the edge of the property at any time, or around the base of trees and shrubs.
 - v. Mowers shall not leave ruts.
 8. The Subcontractor shall be responsible for all damage to plants, structures, vehicles, and irrigation systems caused by their efforts. Mowing shall precede string trimming or rotating disc trimming.
 9. Mowing shall be conducted per Subcontractor's recommended schedule, with a maximum trigger point of:
 - i. Natural Grass – 6 inch maximum to start mowing.
 - ii. Lawn Grass – 3 to 4 inch maximum to start mowing.
 10. Mowing shall be conducted at 10 feet from all roadways and parking lots.
 - i. The NLR TM may request that mowing for fire protection may be extended to a larger area in the future. Any change to this policy would be completed via mutually agreed to modification to the Subcontract.
 11. Mowing conducted around buildings shall be up to 30 feet.
 - i. The NLR TM may request that mowing for fire protection may be extended to a larger area in the future. Any change to this policy would be completed via mutually agreed to modification to the Subcontract.
 12. Subcontractor shall provide as-needed mowing for the PV/solar array fields located at all NLR facilities.
 - i. Areas located underneath PV/solar array fields will need to be mowed in late

spring/early summer for weed control.

c. String Trimming, Disc Trimming and Edging

1. Prior to the start of each maintenance season (approximately April 1st of each year of the period of performance), the Subcontractor shall provide recommendations on the schedule for String Trimming, Disc Trimming and Edging to the NLR Technical Monitor for review and approval. The NLR Technical Monitor may request additional services on an as-needed basis.
2. String trimming activities are only permitted when operation is performed more than 50-feet away from pedestrians, windows, buildings, vehicles, PV panels and other equipment subject to damage. In the event that service is needed within 50-feet of these factors, the Subcontractor is only authorized to use a rotating disc trimmer or alligator type clipper.
3. All areas bordering the native grass areas and lawn grass shall be edged at each cutting. This includes all curbs bordering all roadways and drive lanes. A string trimmer or a steel blade edger may be used to edge.
4. Areas where rock planters exist next to grass shall be walked prior to trimming to ensure that any rocks that have fallen out of the planter bed are returned so that they are not hit by string or blade.
5. All grass areas around structures or trees rings shall be string trimmed to mowing height each time the turf is mowed.
6. At the time of the first mowing of the season, all beds and tree rings shall be defined and edged at a right angle. Edging debris shall not be placed in the beds or rings. They shall be physically removed from the bed and ring. All tree rings shall be evenly concentric around the tree and all bed edges shall be maintained as a smooth and continuous line.
5. Waste from edging and trimming shall be shall be bagged and disposed of in dumpsters on-site at NLR or hauled away and disposed of offsite.
 - i. If disposing off-site, the Subcontractor is responsible for disposal fees and complying with legal disposal procedures.
 - ii. Clippings shall not be dumped in weeds along the edge of the property at any time, or around the base of trees and shrubs.

d. Fertilize and Add Soil Amendments

1. Prior to the start of each maintenance season (approximately April 1st of each year of the period of performance), the Subcontractor shall provide recommendations to the NLR Technical Monitor for fertilizer and soil amendment product approval and a schedule for the application for soil and plant nutrition. The NLR Technical Monitor may, at their discretion, seek approval of chemicals used in fertilizers or soil amendments, from the ESHQ Office. The schedule and products used shall enhance conditions favoring native plants without encouraging the growth of weeds. The NLR Technical Monitor may request additional services on an as-needed basis.
2. Specification sheets for all fertilizers and chemical applications are to be submitted to NLR ESHQ for approval prior to use.
3. Application of fertilizer to lawn areas shall be according to manufacturers' instructions for lawn grass type and needs.
4. The Subcontractor shall deliver fertilizers and soil amendments to the appropriate

NLR location in the original, unopened bags bearing Manufacturer's guaranteed analysis, name, trade name, trademark, and conformance to state law, bearing name, and warranty of producer.

e. Soil Aeration & Overseeding

1. All lawn grass areas shall be core aerated at a minimum one time per year between August 15th and September 30th. The NLR Technical Monitor may request additional services on an as-needed basis.
 - i. Core aeration shall be done prior to over seeding, fall fertilization and irrigation winterization.
 - ii. Regular lawn mowing services shall commence after core aeration so that plugs can be mulched back into the lawn grass bed.
2. All lawn grass areas shall be over seeded, between August 15th and September 30th, with a mixture and rate that is specified by the NLR Technical Monitor.
3. Aeration and overseeding do not apply to native grassland areas.
4. The Subcontractor shall comply with U.S. Department of Agriculture Rules and Regulations under Federal Seed Act (<https://www.ams.usda.gov/rules-regulations/fsa>) and equal in quality to Colorado Department of Agriculture certified seed standards (<https://www.colorado.gov/pacific/agplants/cda-approved-certified-seed>)
5. Certification of Grass Seed: Seed tag from seed vendor for each grass-seed mixture stating the botanical and common name, percentage by weight of each species and variety, and percentage of purity, germination and weed seed. Include the year of production and date of packaging. Submit a copy of the seed tag for the seed lot to be used for approval by the NLR ESHQ Office prior to purchase of seed materials. In addition, the presence of the seed of domesticated grasses that can be weeds including smooth brome (*Bromus inermis*) and intermediate wheatgrass (*Thinopyrum intermedium*) must be disclosed. Hard copy and electronic copies are required.
6. The Subcontractor shall deliver seed in sealed standard containers, with seed tags stating scientific and variety name of all species, % germination, year of seed harvest, name of project, and acreage to be seeded by this shipment, and mixture of seed.
 - i. Seed damaged in transit or storage will not be accepted. Bags (or other containers) of seed that are wet or water-stained or are torn will be rejected.
 - ii. Notify the NLR TM and the NLR ESHQ Office of delivery schedule in advance so that material may be inspected upon arrival at the project site, as required. Seed tags are to be given to the NLR TM or the NLR ESHQ Office.
 - iii. Hydroseeding is not permitted on NLR sites without written permission from the NLR TM.

f. Plants, Shrubs and Tree Maintenance

1. Prior to the start of each maintenance season (approximately April 1st of each year of the period of performance), the Subcontractor shall provide recommendations on the schedule for general Pruning of Plants, Shrubs and Trees and Winter Watering to the NLR Technical Monitor for review and approval. The NLR Technical Monitor may request additional services on an as-needed basis as outlined below.
2. The Subcontractor shall complete selective pruning and trimming of shrubs and trees

- for general health, and promote longevity done in a manner that mimics natural growth as opposed to a hedge or other unnatural shapes.
3. Pruning shall be performed as outlined below to establish invigoration to all plants, shrubs and trees.
 - i. Plants around buildings shall be pruned to remove dead heads, leaves, and branches to promote healthy growth and a uniform appearance.
 - ii. Massed shrubs shall be pruned to maintain a neat appearance, improve sight distance, and to remove dead wood and/or improve plant condition.
 - iii. Shrubs shall be pruned to ensure proper growth and maintain appropriate spacing. Shrub trimming shall be timed appropriately for shrub type and shall be performed to ensure an aesthetically pleasing appearance. Shrubs shall be trimmed at a minimum in the spring and in the fall to help maintain shape and overall health of the plant.
 - iv. The only trimming of trees will be the removal of suckers/shooters. Structural tree trimming will be performed by others.
 - v. Groundcover shall be pruned by hand regularly, at least once per month between April 1st and September 30th, in an effort to maintain a neat and manicured appearance. Groundcover shall be maintained within the bed boundaries and not allowed to grow over paved areas or on structures. Groundcover shall be maintained 4-6 inches away from the trunks of all trees and shrubs.
 - vi. In order to maintain an attractive appearance and promote additional blooms, perennials and roses shall be deadheaded on a routine basis throughout the landscape season.
 - vii. The Subcontractor shall cut back and or divide all ornamental grasses, perennials as appropriate in the fall to prevent overcrowding of bed areas and promote healthy growth of the plant.
 4. All diseased, dying, or dead shrubs, groundcover, and perennials shall be removed and replaced upon approval by the Technical Monitor. The Subcontractor shall provide recommendations on replacement plants that may fair better in the identified problem locations.
 5. The Subcontractor shall provide recommendations on winter watering of trees, shrubs, and grasses.
 - i. Based on climatic conditions experienced throughout the fall and winter months, the Subcontractor shall recommend when winter watering would be advantageous to NLR and submit that recommendation to the Technical Monitor for approval.
 - ii. Upon approval from the NLR Technical Monitor, the Subcontract shall perform winter watering needs as identified in the Subcontractor's recommendations.
 - iii. The Subcontractor shall report any recommendations on winter watering on a monthly basis between September and April of each year.
 6. All debris shall be properly disposed by the Subcontractor. All debris shall be bagged and disposed of in dumpsters on-site at NLR or hauled away and disposed of offsite.

- i. If disposing off-site, the Subcontractor is responsible for disposal fees and complying with legal disposal procedures.
- ii. Debris shall not be dumped anywhere on or near the edges of NLR property.

g. Organic Mulch and Rock

1. Organic mulch, free of any dyes, shall be placed at a minimum once per year in the Spring around tree, shrub, and perennial beds at a minimum thickness of three inches.
 - i. Mulch shall be redistributed in the planter beds in the spring and mulch shall cover any exposed fabric areas. All areas where mulch has blown away or been removed by others, shall be covered with existing mulch.
 - ii. In the event additional mulch is needed to cover and refresh the beds, Subcontractor shall notify the Technical Monitor and obtain approval prior to installing any additional bark.
 - iii. Edges of the planter areas shall be raked back approximately 1" to accommodate new layer of mulch. The mulch must be kept at least two (2) inches away from the base of tree trunks and at least at two (2) inches from the crown of all shrubs.
2. Subcontractor shall refresh rock beds at a minimum once per year in the Spring by raking rock evenly throughout the beds to cover any exposed fabric areas or areas where traffic has moved rock.
 - i. Rock beds shall be maintained on a weekly basis by covering areas where fabric is exposed, placing rocks back into the bed that have been moved out of the planter bed, and clearing landscape debris and other trash from the bed.
 - ii. In the event additional rock is needed to cover and refresh the beds, Subcontractor shall notify the Technical Monitor and obtain approval prior to installing any additional rock.
3. Do not dump or store bulk materials near structures, utilities, walkways and pavements, or on existing turf areas or plants.
 - i. Provide erosion-control measures to prevent erosion or displacement of bulk materials, discharge of soil-bearing water runoff, and airborne dust reaching adjacent properties, water conveyance systems, or walkways.
 - ii. Accompany each delivery of bulk fertilizers, lime, and soil amendments with appropriate certificates.

h. Flowering Plant Maintenance

1. The Subcontractor shall plant flowers including annual or perennial flowers at the request of the NLR Technical Monitor, typically once per Spring, Summer, and Fall season each year. Prior to the start of each maintenance season (approximately April 1st of each year of the period of performance), the Subcontractor shall provide recommendations on annual or perennial seasonal planting for NLR Technical Monitor review and approval.
2. The Subcontractor shall remove the existing soil and dispose it in compliance with all the local industrial waste disposal codes and regulations.
3. The Subcontractor shall deliver the required amount of fresh soil and put it into the planters and beds to fill up to the top. The Subcontractor shall calculate the required amount of additional soil required during a site visit prior to delivery of soil and plants.

4. The Subcontractor shall deliver and apply proper amounts of mineral fertilizer(s) and compost as approved by EHS&Q.
5. The Subcontractor shall lay landscaping fabric to fit the planting areas in each planter and flower bed.
6. The Subcontractor shall deliver and plant the necessary type and quantity of annual and perennial flowering plants required to provide blooming and presentative look of the planter during the vegetation period.
 - i. The Subcontractor shall deliver packaged materials in original, unopened containers showing weight, certified analysis, name and address of manufacturer, and indication of conformance with state and federal laws, as applicable.
 - ii. Do not dump or store bulk materials near structures, utilities, walkways and pavements, or on existing turf areas or plants.
 - iii. Provide erosion-control measures to prevent erosion or displacement of bulk materials, discharge of soil-bearing water runoff, and airborne dust reaching adjacent properties, water conveyance systems, or walkways.
 - iv. Accompany each delivery of bulk fertilizers, lime, and soil amendments with appropriate certificates.
7. General Guidelines on Types of Plants:
 - i. When it comes to planting flowers in a Colorado spring (mid-March to mid-June), cold-resistant plants must be utilized due to Colorado late frosts and unexpected snowfall.
 - ii. A Colorado summer (mid-June to mid-September) can be dry, so native drought-tolerant flowers/plants should be utilized.
 - iii. In the fall, the Subcontractor should plant cold-hearty flowers for autumn in Colorado (mid-September to mid-December).
- i. Debris Removal from Central Arroyo Detention Pond**
 1. The Subcontractor shall remove sediment every three to five years as determined by the NLR Technical Monitor. The NLR Technical Monitor may request additional services on an as-needed basis.
 2. Prior to any removal the Subcontractor will walk down the area with the NLR Technical Monitor to evaluate boundaries and keep to designated pathways identified during evaluation. Subcontractor to be aware of existing irrigation system to avoid any damage during removal.
 3. Remove sediment, vegetation, and dredge from the 3 forebays in the Central Arroyo Detention Pond.
 4. All debris shall be shall be bagged and disposed of in dumpsters on-site at NLR or hauled away and disposed of offsite.
 - i. If disposing off-site, the Subcontractor is responsible for disposal fees and complying with legal disposal procedures.
 - ii. Debris shall not be dumped anywhere on NLR property or around perimeter at any time.
- j. Leaf Removal**
 1. Subcontractor shall provide leaf removal services throughout the year based on the conditions present each time the Subcontractor comes on-site for services.

2. Leaves shall be removed from lawn areas, building entrances, planter bed areas, sidewalks and parking surfaces, native grass, and bare ground areas.
3. Leaves shall be collected, shall be bagged and disposed of in dumpsters on-site at NLR or hauled away and disposed of offsite.
 - i. If disposing off-site, the Subcontractor is responsible for disposal fees and complying with legal disposal procedures.
 - ii. Debris shall not be dumped anywhere on NLR property or around perimeter at any time.
4. NOTE: Leaf Blower equipment cannot be utilized on-site at NLR. Leaves shall be removed via raking or leaf suction/vacuuming equipment that automatically bags leaves.
 - i. STEP Campus may allow leaf blower equipment in the future, but it is not currently approved for use on-site at any locations at NLR.

4) Description of Work: Irrigation System Maintenance and Repairs

The Subcontractor shall collaborate with the NLR Technical Monitor to monitor irrigation delivery from WeatherTRAK smart irrigation system to ensure plant needs are being met. The Subcontractor shall provide all supervision, labor, materials, equipment, tools, project management oversight, transportation, and support services to maintain the existing WeatherTRAK smart irrigation system.

a. Irrigation Maintenance – General

1. The Subcontractor shall provide all management, supervision, administrative support, labor, materials, tools, parts, supplies, equipment, and transportation required to successfully perform winterization, spring start up, inspection, installation, and repair services for all irrigation systems at NLR.

The Subcontractor shall be responsible for all inspection, monitoring, oversight, preventive maintenance and corrective maintenance for all irrigation systems and components.

2. During the months in which irrigations systems are active, the Subcontractor shall inspect each zone for which they are responsible ensuring proper operation of each system.
3. The Subcontractor shall document all work and/or inspections performed. Documentation shall include maintaining a written list of needed repairs, potential repairs, and breaks.

b. Irrigation System Winterization Services

1. Winterization shall be performed in September, October, or November annually; the exact start date will be determined by the NLR Technical Monitor.
2. The contractor shall provide a minimum of one crew for winterization. The contractor shall have the capacity to provide a second crew for support and to make all as needed repairs in timely manner.
3. Neither Winterization nor required repairs shall be delayed or postponed due to a lack of contractor manpower.
4. Winterization for each zone shall include the following procedures:
 - i. Blow out water using appropriate size air compressor. The Subcontractor shall take measures to preclude excessive friction and heat build-up, due in part, to the rapid induction of forced pressurized air into the irrigation system during blowout.

- ii. Reseal piping to prevent infiltration of ground water.
 - iii. The Subcontractor shall tag out the irrigation main line valves.
- c. Irrigation System Spring Start-up Services**
- 1. Spring start-up shall be performed annually between April 1st and May 30th, the exact start date will be determined by the NLR Technical Monitor.
 - 2. The Subcontractor shall provide a minimum of one crew for Spring Start-up. The Subcontractor shall provide a second crew to make needed repairs.
 - 3. Neither Spring Start-up nor repairs shall be delayed or postponed due to a lack of Subcontractor manpower.
 - 4. Spring Start-Up for each zone shall include the following procedures:
 - i. Check the system for obvious external damage and missing heads.
 - ii. Fill the system and check for breaks/leaks, proper operation, and water distribution.
 - iii. Remove, clean, and replace clogged heads.
 - iv. Recalibrate and adjust all aspects of each system and zone.
 - v. Provide documentation of the conditions found and the work performed.
- d. Irrigation Control and Monitoring**
- 1. The Subcontractor shall manage all of the evapotranspiration (ET) programming related to the WeatherTRAK irrigation system on-site at NLR.
 - i. The Subcontractor shall make the necessary changes to the WeatherTRAK irrigation system to ensure all microclimate settings such as locations, slope, soil type, sun exposure, plant type, root depth, head/drip type, etc.
 - ii. The Subcontractor shall perform all adjustments to the WeatherTRAK settings in the web platform.
 - 2. The Subcontractor shall tone and locate all valves to and create an irrigation map for the WeatherTRAK controllers at the request of the NLR Technical Monitor.
 - i. The Subcontractor shall provide electronic copies of the map as requested by the NLR Technical Monitor.
 - ii. The Subcontractor shall provide printed copies of the map as requested by the NLR Technical Monitor.
 - 3. Points of Connection with WeatherTRAK ET Pro3 Controllers
 - i. The Subcontractor shall coordinate setup of an account with the WeatherTRAK system manufacturer (Hydpoint Data Systems) upon Subcontract Award with the NLR Technical Monitor.
 - ii. The Subcontractor shall monitor email messages from the WeatherTRAK Irrigation System and respond to any alerts. In response to the email messages, the Subcontractor shall have the system repaired and working within 48 hours or timeline as approved by the NLR Technical Monitor.
 - iii. The Subcontractor shall visually monitor, in the field, every zone and every head of each point of connection every 2 weeks, when the systems are operating. This can be completed using the WeatherTRAK App. All adjustments shall be done in the field during the monitoring. All repairs shall be completed within 48 hours of detection.
 - 4. Regulation of Watering Times
 - i. The Subcontractor shall be responsible for the regulation of all the controllers.

This includes setting the program, current depletion, station run time, daily run time, and days of watering.

- ii. The Subcontractor shall be responsible for programming the Auto Mode Setting including sprinkler type, precipitation rate, sprinkler efficiency, soil type, plant type, root depth, microclimate, slope, location of slope, percentage adjustment, and Target Maximum Allowable Deficiency (MAD).
- iii. The Subcontractor shall be responsible for programming the User Mode Setting including station cycle time, number of cycles, soak time, reference ET, percentage adjustment, and reference month. Controller regulation shall be done according to the specific watering requirements in the field.
- iv. The Subcontractor shall monitor field conditions and adjust controllers as necessary.
- v. The Subcontractor shall also consult with the NLR Technical Monitor and any designated representatives to aid with regulating the controllers.
- vi. The Subcontractor shall have staff that is knowledgeable with the existing WeatherTRAK irrigation controller equipment. The Subcontractor shall have staff trained to use the WeatherTRAK irrigation controllers and utilize all the features of the equipment including but not limited to; internet communications and messaging with each controller, alert notification, monitoring of system status, troubleshooting tools, advanced scheduling, use of weather data that is downloaded to each controller.

e. Irrigation System Repair Standards

1. The Subcontractor shall repair, install and maintain all equipment covered under this Subcontract in compliance with the requirements of all local codes and manufacturers installation specifications and guidelines.
2. The Subcontractor shall perform all services utilizing, at a minimum, the following guidelines:
 - i. Monitoring – All underground irrigation zones shall be operated and visually checked for leaks, broken heads, heads out of adjustment and improperly functioning electric valves.
 - ii. Broken Irrigation Lines – Broken underground irrigation lines shall be repaired in accordance with all applicable local-plumbing codes.
 - iii. Broken Heads – Broken heads shall be replaced with new identical heads or repaired with original manufacturer's parts, to function according to the manufacturer's specifications.
 - iv. Faulty Valves – Faulty valves shall be replaced with new identical valves or repaired to original manufacturer's specifications.
 - v. Clogged Heads – Any head that is not properly functioning shall be examined for material(s) lodged in the head. The head shall be disassembled, cleaned, reassembled, and checked.
 - vi. Wiring Problems - An underground wire tracer shall be used to locate wiring breaks. Breaks shall be repaired in accordance with all applicable local codes and with waterproof connectors.
 - vii. Underground Installations – New underground main pipe installations shall be marked with metallic tape or low voltage wires prior to backfill. New

underground irrigation shall be installed in accordance with local plumbing codes.

- viii. The Subcontractor shall restore all landscaping to its original condition, including re-seeding, replanting shrubs, mulching, and providing straw as needed.
- ix. The Subcontractor shall remove all debris resulting from installation and repair of irrigation systems.
- x. Trenching and Backfilling - Minimum depths shall be measured from the soil surface to the top of the pipe. Piping shall be buried at the following depth – open areas: Main lines – 24”, Lateral lines – 18”, and under paving – 36” utilizing a 4” sleeve. All backfilled trenches shall be adequately settled, and/or compacted as per code requirements.
- xi. Fittings - All polyvinyl chloride (PVC) pipes shall be cut evenly and wiped clean without any burrs or rough edges before fitting. Primer and solvent shall be applied per manufacturer’s specifications. The pipe and fitting shall be assembled and allowed to cure according to manufacturer specifications before lines are charged with water.
- xii. Threaded Connections – All threaded connections shall be made watertight without leakage. Teflon tape or approved pipe joint compound shall be used where appropriate.
- xiii. Valves – All valves shall be set at least 18” deep (measured from the soil surface to the top of the valve stem) and positioned so that the top of the valve can be easily removed and serviced. The valve box shall be set to cover all valves so that there is sufficient space to service the valves and so that the top of the valve box is even with the surrounding grade. The bottom of the valve box shall be a minimum of 4” above the top of irrigation pipe.
- xiv. Gate Valves – All gate valves shall be at least 18” deep (measured from the top of the valve casing to the soil surface) and shall have a valve box placed over the valve with the top of the box even with the surrounding grade. The bottom of the valve box shall be a minimum of 4” above the top of the irrigation pipe.
- xv. Wiring - Wire shall be color-coded so that the common wire is the same color throughout the site, and the individual zone wires shall be a different color from the common wire. The wire shall be run in the pipe trenches and buried a minimum of 18” deep. Loose wire shall be bundled together with plastic “keepers” or electric friction tape every 24”. Outdoors from irrigated area to controller, the control wires shall be run through PVC electrical conduit. Two extra wires shall be included in the bundle. Indoors, wiring shall be run through PVC electrical conduit.
- xvi. Electrical Connections – All electrical connections shall be made with waterproof King one-step connectors or approved equivalent. All splices of wiring shall have a valve box installed around the splices. The wiring connections at the valve shall be made so that at least eight (8) extra inches of wire is left for each connection. The bottom of the valve box shall be a minimum of 4” above the top of the irrigation pipe.
- xvii. Cleaning of Pipes – All main and lateral lines shall be thoroughly blown out with water before connecting any sprinkler heads.

- xviii. Installation of Sprinkler Heads - Heads shall be connected to the lateral lines with flexible pipe and threaded adapters.
- xix. Setting and Adjustment of Sprinkler Heads – All heads shall be set so that they can adequately/properly cover the area. Heads shall be adjusted to cover the areas according to manufacturer’s specifications.
- xx. Location of in-ground utilities – Prior to making repairs or installation of in-ground irrigation systems, the contractor shall contact the NLR Technical Monitor.

f. Irrigation System - Equipment List

1. The following is a list of twelve (12) current locations for WeatherTRAK Controllers. Additional locations and equipment may be added via mutual agreement to modify the Subcontract.
- i. 09110253 – STM Campus – (A) Ingress/Egress
 - ii. 09110035 – STM Campus – (B) Ingress/Egress
 - iii. 09110030 – STM Campus – Detention Pond
 - iv. 09110248 – STM Campus – Café
 - v. 09110258 – STM Campus – NLR RSF 1
 - vi. 09110029 – STM Campus – NLR RSF 2
 - vii. 09106399 – STM Campus – S&TF
 - viii. 09103231 – STM Campus – FTLB West
 - ix. 10051028 – STM Campus – FTLB East
 - x. 10059168 – STM Campus – SEB East
 - xi. 10050818 – STM Campus – ESIF
 - xii. 09108244 – Flatirons Campus – Building 251
 - xiii. 10064414 – STM Campus – RAIL
 - xiv. 10068699 – Control Center Facility – Flatirons Campus
 - xv. Add Option: STEP (estimated early 2027)

5) Description of Work: ADD OPTION: Landscape Improvements

The Subcontractor’s Project Manager and Landscape Architect will coordinate landscape improvement projects with the NLR Technical Monitor prior to starting any improvements. All plant material shall be inspected and approved by the NLR Technical Monitor or their representatives, prior to the installation of improvements. All planting bed areas shall be laid out in the field.

a. Examination of Site

1. Examine areas to be planted for compliance with requirements and other conditions affecting installation and performance.
 - i. Verify that no foreign or deleterious material or liquid such as paint, paint washout, concrete slurry, concrete layers or chunks, cement, plaster, oils, gasoline, diesel fuel, paint thinner, turpentine, tar, roofing compound, or acid has been deposited in soil within a planting area.
 - ii. Do not mix or place soils and soil amendments in frozen, wet, or muddy conditions.
 - iii. Suspend soil spreading, grading, and tilling operations during periods of excessive soil moisture until the moisture content reaches acceptable levels to

attain the required results.

- iv. Uniformly moisten excessively dry soil that is not workable, and that is too dusty.
2. Proceed with installation only after unsatisfactory conditions have been corrected.
3. If contamination by foreign or deleterious material or liquid is present in soil within a planting area, remove the soil and contamination as directed by the Architect and replace with new planting soil.

b. Preparation of Site

1. Prior to installation, the Subcontractor shall protect structures, utilities, sidewalks, pavements, and other facilities, trees, shrubs, turf areas, and existing plantings from damage caused by planting operations.
 - i. Protect grade stakes set by others until directed to remove them.
2. When applicable, the Subcontractor shall install erosion-control measures to prevent erosion or displacement of soils and discharge of soil-bearing water runoff or airborne dust to adjacent properties and walkways.
3. The application of 4" - 6" of approved topsoil may also be specified in areas where existing soil cannot be conditioned with pine bark.
 - i. If utilizing imported topsoil, the Subcontractor must include product label and manufacturer's application instructions. Statement as to the source of imported soil, if any, and the assurance if any that such soil has been stored without weed cover. If it has been weed covered, the identity of weeds must be disclosed.

c. Potential Improvement Project Components

1. All plants shall be inspected for size, trueness to name, and health and rejected if not supplied as specified.
2. Any soil located around the top of the root ball shall be removed to expose the crown of the stems or trunk.
3. Trees shall be installed so that the crown is 4" - 5" above the surrounding grade. Shrub shall be installed so that the crown is 3" above the surrounding grade.
4. Ornamental grasses and perennials shall be installed with outer edge of root ball 1" above the surrounding grade.
5. Ground covers shall be installed with the edge of the root ball slightly above the surrounding grade.
6. Soil shall be banked around the outer edge of root balls, but not placed on top of the root ball.
7. Plants shall be thoroughly watered the same day of installation.
8. All planting bed areas shall be edged and 2" of mulch applied to the tops of the beds.
9. Mulch shall be kept away from the trunks of trees and shrubs.
10. A complete fertilizer with a slow-release form of nitrogen shall be applied to all planting bed areas.

d. Delivery, Storage, and Handling

1. Packaged Materials: Deliver packaged materials in original, unopened containers showing weight, certified analysis, name and address of manufacturer, and indication of conformance with state and federal laws, as applicable.
2. Bulk Materials
 - i. Do not dump or store bulk materials near structures, utilities, walkways and pavements, or on existing turf areas or plants.
 - ii. Provide erosion-control measures to prevent erosion or displacement of bulk materials, discharge of soil-bearing water runoff, and airborne dust reaching

adjacent properties, water conveyance systems, or walkways.

- iii. Accompany each delivery of bulk fertilizers, lime, and soil amendments with appropriate certificates.

e. Quoting and Landscape Improvement Project Approval Process

1. The Subcontractor shall submit a firm fixed price quote to the NLR Technical Monitor with all labor hours, materials, equipment, and other direct costs associated with the landscape improvement in the pricing format included in the Subcontract Schedule.
2. Quotes must be provided and approved by NLR Technical Monitor or their designee prior to the start of work for the Landscape Improvement. The Subcontractor shall provide all required replacement parts.
 - i. Quotes shall include an estimated scheduling timeline for start date and completion date of the proposed Landscape Improvement.
3. The cost of all requested Landscape Improvements must be approved by NLR's Technical Monitor prior to performance on-site or off-site for project management purposes.

6) Project Management, Deployment, and Staffing

a. Project Management Plan

1. The Subcontractor shall provide to the Technical Monitor a Project Management Plan and Deployment Schedule that should clearly explain how the Subcontractor will manage the work required under the Subcontract.
2. The Project Management Plan should demonstrate a knowledge of the process and impediments that must be overcome and ensure that sufficient staffing, equipment, and materials will be provided.
3. The Project Management Plan shall outline the activities, mechanisms, functions, and actions that the contractor shall employ for communication with NLR.
4. The Project Management Plan shall outline quarterly site assessments.
5. The Project Management Plan should also include the following:
 - i. Identify the key personnel and their specific roles in managing the Project;
 - ii. Provide a description of the equipment and materials that is available and a description of where such equipment is stored;
 - iii. A description of the Subcontractor workforce/lower-tier subcontractors and how its crews/lower-tier Subcontractors will be mobilized (i.e. phone tree, etc.) so as to ensure that work will be accomplished during the triggers;
 - iv. A description of how and where the equipment and workers or subcontractors will be marshalled; and
 - v. A staffing plan which describes how crews/lower-tier subcontractors will be dispatched.

b. Documentation and Reporting

1. The Subcontractor shall remain in communication with the Technical Monitor pursuant to its Project Management Plan, prior to, at the onset of, during, and after each date of service.
2. The Subcontractor shall be required to complete a report documenting challenges or problems encountered during the operations and a corrective action plan to ensure it

- is not repeated.
3. Subcontractor shall provide a written quarterly seasonal site condition report.
 4. Subcontractor shall provide record keeping documents in accordance with APCD Regulation No. 29.
 5. The Subcontractor shall utilize a computerized maintenance management system to manage and document all maintenance and repair activities performed under the Subcontract. The Subcontractor shall provide copies of reported activities, as outlined below, within 5 business days of the Technical Monitor request.
 6. The Subcontractor shall report all requests for work, scheduled work, completion of work activities, including the following:
 - i. Name of the Subcontractor's Employee(s) working on site for each work requirement.
 - ii. Date of Service.
 - iii. Duration of work performance on each task.
 - iv. Specific maintenance or repairs accomplished.
 - v. Part numbers for irrigation system repairs.
 - vi. Labor.
 - vii. Completion Dates.
 - viii. Any other comments necessary to explain corrective actions or work performed.
 7. The Subcontractor shall notify the Technical Monitor of all scheduled activities that are incomplete within 5 business days of the end of each month, in a "Work Order Status Report."
 - i. The Work Order Status Report shall outline a summary of all tasks requested, scheduled, and whether each task is complete or incomplete.
 - ii. The Subcontractor shall submit a Plan of the Week (POW) every week and a Plan of the Month every month for all planned landscape activities.
- c. Performance, Codes and Standards:**
1. The Subcontractor shall be responsible for complying with all state and federal regulations having jurisdiction over any portion of the work to be performed under this work effort.
 2. While at NLR, all work performed shall be performed in accordance with NLR Policies and Procedures outlined in the Safe Work Permit (SWP) provided by NLR ESHQ.
 3. The Subcontractor shall provide proper personal protection equipment for all employees working on this project and shall ensure that equipment is properly used.
 4. Quality Assurance:
 - i. NLR will evaluate the Subcontractor's performance under this work effort by the Technical Monitor conducting random inspections.
 - ii. All observations will be recorded by NLR.
 - iii. The Subcontractor shall provide to the NLR Technical Monitor a corrective action plan to meet any corrective actions necessary.
 - iv. Successive months of unsatisfactory performance may result in other appropriate actions(s) by the Subcontract Administrator in accordance with the Standard Terms and Conditions.

d. Personnel Requirements:

1. Key Personnel Designations

- i. The Subcontractor shall have at least two Key Personnel with a minimum of ten (10) years' experience in the business of providing comprehensive services of the size and scope described in this SOW.
- ii. The Subcontractor will not be permitted to reassign any of the key personnel unless both the NLR Technical Monitor and NLR Subcontract Administrator approves the proposed reassignment and the proposed replacement.
- iii. The Subcontractor shall designate two Key Personnel to be available to communicate with NLR by telephone and email during regular business hours, Monday through Friday throughout the period of performance on the contract.
- iv. The Subcontractor's Key Personnel shall be a member in good standing of either the Professional Landcare Network or the American Nursery and Landscape Association.
- v. The Subcontractor's Key Personnel may be members of the Supervisory Staff listed below, or in addition to the Supervisory Staff.

ii. Supervisory Staff

- i. The Subcontractor shall provide competent supervisory staff authorized by the NLR Technical Monitor to act for the Subcontractor.
 - a. The Subcontractor shall promptly remove from the work site and NLR premises any supervisor or employee whose work conduct is not satisfactory to the NLR Technical Monitor.
- ii. The Subcontractor's supervisory staff shall include, at a minimum:
 - a. Project Manager
 - i. The Subcontractor shall provide at least one Primary and one Backup Project Manager. The Project Manager shall have full authority to act for the Subcontractor and serve at all times to carry out all the provisions of the Subcontract.
 - ii. The Project Manager shall have a minimum of five (5) years' experience in successfully managing Landscape and Irrigation Contracts or Subcontracts of the size and scope described in this Statement of Work.
 - iii. The names of the Project Manager and an alternate who shall assume the Project Managers duties when the primary Project Manager is absent shall be designated in writing to NLR fifteen (15) business days prior to the change in responsibilities between primary and backup.
 - iv. The Project Manager shall possess sufficient computer software skills for the purpose of creating and receiving electronic reports, notices, requests, and communications to/from the NLR Technical Monitor. The Project Manager shall be available for phone calls during all working hours. The project manager shall meet as promptly as possible with NLR Technical Monitor to discuss the performance of the work or other provisions of the contract.

- v. The Project Manager shall coordinate quarterly site assessments with the Landscape Architect, On-Site Managers, and NLR TM's, Facilities Managers, or their designees.
- b. On-Site Manager
 - i. As a minimum, the Subcontractor must provide at least one Primary and one Backup On-Site Manager to direct all contract personnel and maintenance operations. The on-site manager shall have a minimum of five (5) years' experience managing landscape maintenance and irrigation maintenance contracts at similar size facilities and quality standards as stated in the contract documents. The manager shall remain on-site during all scheduled work activities between 6:00am 5:00pm Monday through Friday, including holidays.
 - ii. The on-site manager shall represent the interests of the Subcontractor with regards to all matters involving work performance under this contract.
 - iii. The on-site manager shall be fluent in the English language to effectively communicate with the contractor's employees and/or subcontractors as well as the NLR Technical Monitor and other NLR personnel. NLR reserves the right to require the contractor to replace the on-site manager who cannot meet this requirement.
 - iv. If the on-site manager is not on site or absent due to illness or other reasons, the Subcontractor shall provide an alternate manager to be on site managing and directing all contract personnel and maintenance operations. The alternate manager shall have similar job qualifications to those required for the on-site manager.
 - v. The onsite manager shall be available for phone calls during all working hours.
- c. Landscape Architect
 - i. As a minimum, the Subcontractor shall provide at least one Primary and one Backup Landscape Architect or be able to obtain a lower-tier subcontractor for Landscape Architecture. NLR will review the qualifications of this subcontractor prior to the execution of work to deem their engagement acceptable.
 - ii. The Landscape Architect shall meet with the NLR Technical Monitor, engineers, and building architects to understand the requirements of landscaping projects including:
 - 1. Prepare site plans, specifications, and cost estimates
 - 2. Coordinate the arrangement of existing and proposed landscape plantings, conditions and structures
 - 3. Prepare graphic representations of plans using computer-aided design and drafting (CADD) software
 - 4. Select appropriate hardscape and softscape materials applicable to each project initiative
 - 5. Analyze environmental reports on land conditions, such as drainage and energy usage

- 6. Inspect landscape project progress to ensure implementation adheres to construction plans
- iii. The Landscape Architect shall work with the goal of enhancing the natural beauty of project areas that foster environmental and wildlife habitat benefits in line with the requirements of this Statement of Work.
- iv. The Landscape Architect shall work in-tandem with the Project Manager, On-Site Managers, and NLR TM's, Facilities Managers, or their designees to complete quarterly site assessments.
- iii. On-Site Staffing
 - i. The Subcontractor agrees to utilize responsible, capable employees in the performance of all Services of this contract.
 - ii. Irrigation technicians shall be experienced and knowledgeable with all of the irrigation equipment at NLR sites.
 - iii. The Subcontractor shall provide all the management, supervision, labor, and administrative support necessary to fulfill the requirements of the SOW.

7) Site Access and Care of NLR Facilities:

The Subcontractor's personnel shall always obtain proper security clearance and wear NLR authorized subcontract badge when on-site.

- a. US Citizens will be issued either hard badges or one-day badges.
- b. Foreign nationals require a separate form for each worker that shall be submitted at least six-weeks in advance and shall be approved by NLR prior to being onsite. The Subcontractor shall ensure that any of the Subcontractor's employees (or its lower-tier Subcontractors' employees), officers, and agents who will enter onto NLR operated facilities and who are not U.S. citizens meet the requirements set forth in NLR's Foreign National Management Policy and Program, including: (a) appropriate work authorization documentation (i.e. Visa); (b) completion of an NLR Foreign National Data Card; and (c) NLR Manager-level approval.
- c. Please refer to the Appendix B-3 Standard Terms and Conditions for Supplies and Services (Where Service Contract Act Applies) clause 70-08.100-02 labeled "SECURITY AND ACCESS REQUIREMENTS (SPECIAL) (DEC 2018)" for additional information on badging and site access requirements.
 - i. Upon commencement of work, the Subcontractor shall take full responsibility for the care, custody and control of the work until it has been completed.
 - ii. When working on site, the Subcontractor shall protect property from all potential hazards.
 - iii. The Subcontractor shall provide safety barriers, as required, to clearly identify the working area and to prevent others from accessing the work area. This safety zone shall be sufficiently sized to prevent damage to existing facilities and structures. Upon completion of the work, the Subcontractor shall remove the safety barriers from the work area. If any holes are excavated, they shall be covered with plywood or some other material or fenced to the ground surface using orange construction fencing (or something similar) to prevent wildlife from falling

- into the hole.
- iv. Any accidents, injuries, fires or other incidents of a serious nature or incidents requiring emergency response must be reported to NLR **Central Monitoring Station**. Call x1234 from an NLR on-site phone or 303-384-6811.
 - v. Accomplish work with minimum interference to pedestrian and vehicular traffic on adjacent streets, sidewalk, or courtyard areas.
 - vi. The Subcontractor shall always keep the work area clean and shall promptly remove waste materials or rubbish. Trees, shrubs, grasslands, pavement, site furniture, site lighting, irrigation systems, and building structures damaged due to the Subcontractors operations, chemicals or negligence shall be repaired or replaced at no expense to NLR.
 - vii. Concealed lines for such utilities as water, power, lighting, sanitary waste, gas, broadband, security cable, etc. which may be uncovered during progress of the work and which are essential for NLR services and functions shall be adequately protected in order to prevent any interruption of required services. If the Subcontractor must disturb the ground or excavate, the Subcontractor must contact the Site Facility Manager for an excavation permit prior to any digging. If any holes are excavated, they will be covered with plywood or some other material or fenced to the ground surface using orange construction fencing (or something similar) to prevent wildlife from falling into the hole.
- d. Unauthorized Use of NLR Facilities and Equipment:
- i. The Subcontractor shall be responsible for misuse of NLR facilities and equipment by subcontractor employees. Unauthorized use of NLR facilities and equipment includes the following:
 - ii. Making phone calls on NLR phones that are not authorized and are not directly related to the performance of the work effort.
 - iii. Storage of personal property in NLR facilities.
 - iv. Storage of Subcontractor supplies and equipment in unauthorized locations.
 - v. Use of computers, copiers, fax machines, and other NLR office and laboratory equipment.
- e. Security:
- i. All Subcontractor employees are to wear a NLR identification badge on their outer garment, upper portion of their body at all times while on the premises.
 - ii. Subcontractors will not be allowed on site without badges.
 - iii. All issued badges must be returned immediately to the Site Entrance Building upon termination of the work at NLR.
 - iv. The Subcontractor shall comply with all safety requirements as applicable at the following website: <https://www.nlr.gov/about/ehs-construction.html>

8) **Locations:**

Specific project areas to be addressed for landscape maintenance services are illustrated in Exhibit 1.

- a. South Table Mountain Site (STM), 15013 Denver West Pkwy, Golden, CO 80401.
- b. Flatirons Campus, 19001 W. 119th Ave., Arvada, CO 80007.
- c. South Table Energy Park (STEP), 15445 S Golden Road, Golden CO 80401.

9) Maps:

Please reference the maps located on the NLR website links below. Specific project areas to be addressed for landscape maintenance services are illustrated in Exhibit 1.

- a. Golden STM Campus: <https://www.nlr.gov/about/golden.html>
- b. Flatirons Campus: <https://www.nlr.gov/about/flatirons-campus.html>
- c. STEP Campus: [South Table Mountain Energy Park Map](#)

10) Scheduled Tasks:**Regularly Monthly Requirements:**

Task #	Description	Due Date
3.a.	Weed Control	In accordance with the approved pre-season schedule. Additional services to be completed within 1 week or 7 calendar days from NLR TM Request.
3.b.	Mowing	In accordance with the approved pre-season schedule. Additional services to be completed within 1 week or 7 calendar days from NLR TM Request.
3.c.	String Trimming & Edging	In accordance with the approved pre-season schedule. Additional services to be completed within 1 week or 7 calendar days from NLR TM Request.
3.d.	Fertilize and Add Soil Amendments	In accordance with the approved pre-season schedule. Additional services to be completed within 1 week or 7 calendar days from NLR TM Request.
3.e.	Soil Aeration & Overseeding	In accordance with the approved pre-season schedule. Additional services to be completed within 1 week or 7 calendar days from NLR TM Request.
3.f.	Plants, Shrubs and Tree Maintenance	In accordance with the approved pre-season schedule. Additional services to be completed within 1 week or 7 calendar days from NLR TM Request.
3.g.	Organic Mulch/Rock	Annually between March to June (Spring) or within 1 week or 7 calendar days from NLR TM Request.
3.h.	Flowering Plant Maintenance	Annually between March to June (Spring) or within 1 week or 7 calendar days from NLR TM Request.
3.i.	Debris Removal from Central Arroyo Detention Pond	In accordance with the approved pre-season schedule. Additional services to be completed within 1 week or 7 calendar days from NLR TM Request.
3.j.	Leaf Removal	To be completed when Subcontractor is on-site, as-needed, or at the request of the NLR TM.
4.a.	Irrigation Maintenance	Within 1 week or 7 calendar days from Request
4.a.	Inspections of Irrigation System	Once per month during months when irrigation system is active.
4.b.	Winterization of Irrigation System	Annually between September and November each year, as determined by the NLR TM.
4.c.	Spring Start-Up of Irrigation System	Annually between April 1-May 30th each year, as determined by the NLR TM.
4.d.	Irrigation Control and Monitoring	Notifications of repairs required to TM as soon as WeatherTRAK system notifies Subcontractor.
4.e.	Irrigation System Repairs	Repairs to be completed within 48 hours of initial request or approval from NLR TM.

Project Management and Reporting Requirements:

6.a.	Project Management Plan	Prior to the start of each maintenance season April 1st of each year.
6.b.	Documentation and Reporting	Within 5 business days of NLR TM request.
6.b.3	Quarterly Seasonal Site Report	To be provided to the NLR TM quarterly

ADD OPTION: Landscape Improvements

5.	Landscape Improvements - New Projects	Quotes to be provided for NLR TM Approval prior to start of work. Specifics to be determined based on the requirements of the project, as provided by the NLR TM.
----	---------------------------------------	---

11) Points of Contact:

a. NLR Technical Monitor

1. The Primary Technical Monitor for this requirement is Elizabeth Latino, Elizabeth.Latino@nlr.gov, (303) 598-9745.
2. The Secondary Technical Monitor for this requirement is Matthew Lynch, Matthew.Lynch@nlr.gov, (303) 598-2772.
3. The Subcontractor is responsible for coordinating all questions, problems, or operational technical matters of this subcontract with the NLR Technical Monitor. In the event the NLR Technical Monitor is not available at the time of the request, operational questions can be requested through the NLR Work Control Center.

b. Standard Performance Scheduling

1. The point of contact for **scheduling** on this subcontract is NLR Work Control Center (WCC) at (303) 384-7344.

12) Environmental, Safety, Health, and Quality (ESHQ):

- a. The Subcontractor shall submit an Environmental, Safety, and Health Risk Evaluation Worksheet.
- b. The Subcontractor shall provide proper personal protection equipment.
- c. The Subcontractor shall attend a NLR Contractor Safety Orientation meeting with an NLR ESHQ representative.

13) Working Hours:

- a. NLR regular business hours are 8:00am to 5:00pm., Monday through Friday except NLR recognized holidays. Subcontractor personnel scheduled to work during non-working hours must notify the Site Entrance Building at (303) 384-6811.
- b. The days designated as NLR holidays (i.e., New Year's Day, Martin Luther King Jr. Day, Memorial Day, Juneteenth, Independence Day, Labor Day, Thanksgiving Day, Day after Thanksgiving, and Christmas Day) are not NLR workdays. If a NLR holiday falls on a Saturday or Sunday, the preceding Friday or the following Monday may not be a NLR workday. Subcontractor is not authorized to work on NLR Holidays unless approved by the NLR Technical Monitor.

EXHIBITS LIST – SEE ATTACHED:

EXHIBIT 1 – 2026 NLR Weed Management Plan dated 02-05-2026
EXHIBIT 2 – Noxious Weed Species Identified at the South Table Mountain and Flatirons Campus
EXHIBIT 3 – Native Sod and Grasses (Seed Tables) dated 10-28-2021
EXHIBIT 4 – Soil Amendments List dated 2-4-2021
EXHIBIT 5 – STM Campus Fire Management Mow Map 2026
EXHIBIT 6 – Flatirons Campus Fire Management Mow Map January 2026
EXHIBIT 7 – Landscape Restoration and Maintenance Guide dated 7-26-2021
EXHIBIT 8 – Wildland/Urban Interface Defensible Space Management Plan dated August 2014
EXHIBIT 9 – Site Maintenance Plan Worksheet (8.1)
EXHIBIT 10 – STM Campus Irrigation Map dated 5-2022
EXHIBIT 11 – Flatirons Campus Irrigation Map dated 5-2022
EXHIBIT 12 – FC Conservation Areas