

Continuation Sheet – Amendment “006”

eProjects Work Order Number: 1625040
Construction Contract Number: N4008524F6462
Building: Building 368
Project Title: Q1075 SOF Operations Building 368 Addition
Date: 6 February 2026

DRAWINGS:

REVISE the following sections:

GI011 FIRST FLOOR LIFE SAFETY PLAN & GI012 SECOND FLOOR LIFE SAFETY PLAN

Replace general life safety drawings sheets GI011 and GI012 with provided sheets.

AD107 ROOF DEMOLITION PLAN, AE111 & AE202 WALL ELEVATIONS

Replace architecture drawings sheets AD107, AE111, and AE202 with provided sheets.

AE302 WALL SECTIONS

Replace architecture drawings sheet AE302 with provided sheet.

AE601 DOOR SCHEDULE & HARDWARE SETS

Replace architecture drawings sheet AE601 with provided sheet.

AE704 CURTAIN WALL & STOREFRONT DETAILS

Replace architecture drawings sheet AE704 with provided sheet.

SPECIFICATIONS:

REVISE the following sections:

Section 13 49 20.00 10 RFI/EMI SHIELDING

Replace entire section.

Section 08 71 00 DOOR HARDWARE

Replace Door Hardware Sets insert.

Section 01 57 19 TEMPARY ENVIORNMENTAL CONTROLS

Add the attached report as an attachment: Enthalpy Analytical Test Report

Section 01 30 02.00 22 DESIGN, PROCUREMENT, AND INSTALLATION OF AUDIOVISUAL EQUIPMENT

Replace paragraph 1.3 GENERAL REQUIREMENTS (second paragraph after 1.3.1.) with the following:

The design and documentation of the AV system shall be funded as the AV Services Option. The purchase and installation of the AV Package shall be funded separately as the AV Option. The Government AV budget on the Bid Schedule/Price Proposal Form for the AV Option is **\$672,800.00** and does NOT include the Contractor's Handling and Administration Rate (HAR). This Government AV estimate shall not be altered by Contractors during the bid process.

Section 08 11 13 STEEL DOORS AND FRAMES

Replace paragraph 2.1 with the following:

SDI/DOOR A250.8, except as specified otherwise. Prepare doors to receive door hardware as specified in Section 08 71 00 DOOR HARDWARE. Undercut where indicated. Provide exterior doors with top edge closed flush and sealed to prevent water intrusion. Provide doors at 1-3/4 inch thick, unless otherwise indicated. Provide door material that uses a minimum of 25 percent recycled content. Provide data indicating percentage of recycled content for steel door product.

Section 09 29 00 GYPSUM BOARD

Replace paragraph 3.4 FINISHING OF GYPSUM BOARD with the following:

Tape and finish gypsum board in accordance with ASTM C840, GA 214 and GA 216. Finish plenum areas above ceilings to Level 1 in accordance with GA 214. Finish water resistant gypsum backing board, ASTM C1396/C1396M, to receive ceramic tile to Level 2 in accordance with GA 214. Unless otherwise specified, finish all gypsum board walls, partitions and ceilings to Level 4 in accordance with GA 214. Provide joint, fastener depression, and corner treatment. Tool joints as smoothly as possible to minimize sanding and dust. Do not use self-adhering fiber glass mesh tape with conventional drying type joint compounds; use setting or hardening type compounds only. Provide treatment for water-resistant gypsum board as recommended by the gypsum board manufacturer. Protect workers, building occupants, and HVAC systems from gypsum dust.