

STATEMENT OF WORK
Type of Service or Construction (NAICS)
Fiber Optic Cable Installation

PR Number:

Instructions: Complete all Bold Elements below and mark N/A for elements that are not applicable and delete sub elements. This will ensure that each element is considered.

1. General:

1.1 Describes the project in general terms:

The Contractor shall provide and install underground fiber optic cabling to supply high-speed internet connectivity to the Seney NWR new Headquarters and Visitor Center and existing Maintenance Shop.

1.2 Purpose/End Application:

Highline Internet has agreed to provide monthly service to Seney NWR. To enable this service, the Refuge requires new direct-burial fiber optic cable connecting the Highline-owned distribution line at highway M-77 to the new Headquarters and Visitor Center, and an additional run from the Headquarters building to the existing Maintenance Shop.

1.3 Product reviewed and selected:

The Contractor shall provide all parts and pieces necessary for a fully functioning fiber optic line including but not limited to:

- Armored, direct-burial rated, singlemode custom fiber optic cable (Corning glass).
- LC UPC connectors on both lead and termination ends.
- Any protective conduit required to meet safety and regional construction standards.

1.4 Contractor Qualifications:

Highline is the preferred contractor due to unique service capability. Alternative contractors must be state-licensed general contractors with demonstrated experience installing underground fiber optic cable and industry-standard termination practices.

1.5 Other:

No additional items noted.

2. Place of Performance and Period of Performance (Where and When)

2.1 Location:

Seney National Wildlife Refuge
1674 Refuge Entrance Road
Seney, MI 49883

2.2 Performance start and end date:

Work may begin when ground conditions allow trenching (estimated May 1, 2026).
All work must be completed by June 12, 2026.

2.3 Normal duty hours:

Monday–Friday, 8:00 a.m. – 4:30 p.m.

Contractor must provide emergency contact information.

2.4 Non-duty hours:

Evenings, weekends, and all Federal holidays.

3. Scope

3.1 The Contractor shall:

- Coordinate all work with the FWS Infrastructure Management Division (IMD) and Refuge.
- Install fiber optic cable capable of supporting 2 GB service.
- Avoid disturbance of existing utilities; perform utility locates before excavation.
- Obtain FWS approval for the proposed fiber route (expected along refuge entrance road or service road). See attachment.
- Use the existing empty conduit beneath the new Headquarters and Visitor Center parking lot to avoid trenching through paved areas.
- Install fiber from the Highline-owned highway M-77 line to the new Headquarters and Visitor Center Technology/Security Room.
- Install secondary fiber from HQ to the Maintenance Shop Office.
- Ensure all connections meet Highline service requirements and are compatible with Seney NWR owned equipment.
- Submit all materials for FWS approval prior to installation.
- Provide a final as-built map showing exact fiber routing and burial depth.

4. Deliverables and/or Delivery Schedule: (for extended list a bid schedule and/or use of line item detail on the PR is recommended)

4.1 Clearly state the deliverables required, the schedule for delivery, the quantities, schedule (for multiple items):

Fully installed fiber optic system:

- Highway M-77 to New Headquarters and Visitor Center
- New Headquarters and Visitor Center to Maintenance Shop
- All connectors properly terminated and tested.
- Restoration of disturbed grounds.
- Delivery schedule consistent with Section 2.

4.2 Identify the type of documentation (printed and electronic-such as manuals) to be provided, as well as those quality indicators desired by the Government:

- As-built fiber route map in digital .pdf format.
- Material submittals for Government review and approval.
- Fiber testing results demonstrating signal performance and continuity

5. Data Management Plan (DMP) for Science Data Agency Reference:

Not applicable. No new scientific data is being created.

6. Government-Furnished Equipment (GFE) / Government-Furnished Information (GFI):

None.

7. Evaluation and Acceptance

7.1 The contractor will be evaluated as detailed herein. Government acceptance is contingent upon: [Either state generally or reference the table in 8.2 if used:

Preferred vendor is Highline. See sole source justification. If this isn't approved the Government will evaluate the Contractor's proposal based on:

- Technical capability and experience,
- Qualification of personnel,
- Cost reasonableness and justification,
- Compliance with SOW requirements.

8. Quality Control/Quality Assurance:

8.1 For commercial supplies reference clauses for inspection and acceptance:

Contractor shall implement QC procedures according to industry standards for fiber optic installation.

8.2 Identify and detail measures for assessing quality control and acceptance; each requirement is unique and a table format is visually friendly and may be desirable:

Proper installation depth and routing,

- Clean terminations with verified optical performance,
- Accurate final documentation and mapping,
- Compliance with conduit-use requirements at the new Headquarters and Visitor Center.

9. Technical Coordinator:

9.1 Identify the primary individual responsible for the final product or service:

Sara Siekierski

Refuge Manager

1674 Refuge Entrance Road

Seney, MI 49883

Email: sara_siekierski@fws.gov

Phone: (906) 630-2015

9.2 Identify the secondary or co-individual responsible with same pertinent information:

Timothy Fuller

Architect

5600 American Boulevard West

Suite 990

Bloomington, MN 55437

Email: timothy_fuller@fws.gov

Phone: (612) 713-5186

Attachment #1

Approximate beginning of empty buried conduit to New Headquarters and Visitor Center.

New Headquarters and Visitor Center, install fiber optic to IT room.

Proposed fiber route between New Headquarters and Visitor Center and Maintenance Shop

Existing Maintenance Shop, terminate fiber optic in IT room (maintenance office).

Proposed Fiber Route #2: Service Road

Proposed Fiber Route #1: Refuge Entrance Road

Highway M-77

US Refuge Headquarters

Refuge Entrance Rd

Refuge Entrance Rd

Refuge Entrance Rd

Holland Creek

Seney Natl

