

Design Revision 1

eProjects Work Order Number: 1673784
Construction Contract Number: N40085-26-R-0105
Building: Q-58
Project Title: Data Concentrator Shed Restoration
Date: 17 April 2026

Design Revision Purpose

1. Drawings and Executable Scope of Work revised in response to Pre-Proposal Inquiries.
2. Front end Division 01 Specifications added in response to Pre-Proposal Inquiries.
3. Attachment 1 added in response to Pre-Proposal Inquiries.

Executable Scope of Work Revisions

The following changes, dated 4/17/2026, have been made to the EXSOW accompany this Design Revision:

On EXSOW Page No. 2

Contractor Requirements part 12:

Removed references to separate CLINS (12a, 12b, 12c, and 12d) not called out in and the Supplementary Instructions to Offerors and the Price proposal Form.

On EXSOW Page No. 4

Docking platform and Fender Frame bullet 7 revised to read "Provide (8) W6x20 beams. Weld all around to existing C12x30 vertical channels at the two elevations shown in the drawings."

On EXSOW Page No. 5

Steel bollard cleaning description removed completely. Refer to steel bollard section on page 4 instead.

On EXSOW Page No. 6

Specifications part 6c:

Revise section to remove reference to ASTM A307 grade A bolts, and replace with ASTM A325 type 1 high strength bolts. PPI response to use ASTM 307 bolts was incorrect, use ASTM A325 bolts instead. Revise washers to comply with ASTM F844. Remove all references to stainless steel.

Drawing Revisions

The following drawings, dated 4/17/2026, are revised and in the list of drawings and accompany this Design Revision:

SHEET NO.		NAVFAC DRAWING NO.	SHEET TITLE
NO.	SHEET		
STRUCTURAL			
2	S-001	12,937,904	STRUCTURAL SYMBOLS, LEGENDS, ABBREVIATIONS, AND NOTES
3	S-101	12,937,905	DOCKING PLATFORM
4	S-102	12,937,906	CANNISTER IMPROVEMENTS
5	S-103	12,937,907	SOUTH ELEVATION

On NAVFAC Drawing No. 12,937,904 (S-001)

STRUCTURAL SYMBOLS, LEGENDS, ABBREVIATIONS, AND NOTES:

STRUCTURAL STEEL NOTES: Removed all references to stainless steel. Removed ASTM 307 grade A bolts and replaced with ASTM 325 type 1 bolts.

STEEL DECK NOTES: Removed all references to stainless steel. Added "HOT DIPPED GALVANIZED PER ASTM A653, G90"

FIXED METAL LADDER NOTES: Removed all references to stainless steel. Added "LADDER COMPONENTS MUST BE HOT DIPPED GALVANIZED IN ACCORDANCE WITH ASTM A123."

On NAVFAC Drawing No. 12,937,905 (S-101)

SECTION B3 – SMALL VESSEL DOCK: Revise to add detail reference D3/S-301 to show channel connection.

On NAVFAC Drawing No. 12,937,906 (S-102)

KEYNOTE 8: Add verbiage of "FOR BIDDING PURPOSES, ASSUME BASE BID OF CLEAN UP IS FOR 5 CUBIC YARDS OF GUANO, DEBRIS, AND OTHER WASTE MATERIAL."

On NAVFAC Drawing No. 12,937,907 (S-301)

KEYNOTE 2: Add verbiage of "HOT DIPPED GALVANIZED."

KEYNOTE 10: Add verbiage of "5/16" FILLET WELDED."

Added Detail D3 – CHANNEL CONNECTION

Specification Revisions

The following specifications have been added as of 4/17/2026 and accompany this Design Revision:

DIVISION 01 – GENERAL REQUIREMENTS

00 01 15 –LIST OF DRAWINGS

01 11 00 – SUMMARY OF WORK

01 14 00 – WORK RESTRICTIONS

01 20 00 – PRICE AND PAYMENT PROCEDURES

01 30 00 – ADMINISTRATIVE REQUIREMENTS

01 31 23.13 20 – ELECTRONIC CONSTRUCTION AND FACILITY SUPPORT CONTRACT MANAGEMENT SYSTEM (eCMS)

01 32 17.00 20 – COST-LOADED NETWORK ANALYSIS SCHEDULES (NAS)

01 33 00 – SUBMITTAL PROCEDURES

01 35 13 – SPECIAL PROJECT PROCEDURES

01 35 26 – GOVERNMENTAL SAFETY REQUIREMENTS

01 42 00 – SOURCES FOR REFERENCE PUBLICATIONS

01 45 00 – QUALITY CONTROL

01 45 35 – SPECIAL INSPECTIONS

01 50 00 – TEMPORARY CONSTRUCTION FACILITIES AND CONTROLS

01 57 19 – TEMPORARY ENVIRONMENTAL CONTROLS

01 74 19 – CONSTRUCTION WASTE MANAGEMENT AND DISPOSAL

01 78 00 – CLOSEOUT SUBMITTALS

Attachment Revisions

The following attachment has been added as of 4/17/2026 and accompany this Design Revision:

Attachment 1 Spud Barge Location