

Performance Work Statement for Maui Base Support Services (MBSS) and Information
Technology (IT) Cor COMM Services

Xx xxx 20xx

DRAFT

Table of Contents

Part I Description of Services

0.1 Scope.....

1.0 General.....

2.0 Safety.....

3.0 Security.....

4.0 Logistics.....

5.0 Core Communications

6.0 Civil Engineering – Project Engineering, Execution and Support Services

7.0 Civil Engineering – Facility Operations and Maintenance

8.0 Fuels

9.0 Civil Engineering Environmental Management

10.0 Phase I/ Phase out

Part II Service Summary

Part 1

Description of Services

.1 Scope

0.1.1 This is a non-personal services contract as defined in Federal Acquisition Regulation (FAR) 37.101 Performance Based Contracting. The requirement of this contract is the seamless and effective operation of all 15 SPSS current owned buildings and sites at time of award MBSS provides facility, Infrastructure, information technology, and logistics support.

0.2.1 The scope of MBSS includes all management personnel, equipment and services necessary to operate the facilities, and provide logistics and information technology support. Facilities requirements include but not limited to administration management and customer support, facility and infrastructure repair, demolition of real property/Real Property Installed equipment (PR/RPIE), maintenance and support, operations (physical plant operations), grounds maintenance, refuse collection and disposal architect/engineer services (planning, programming and design construction management) Logistics support includes central shipping and receiving, property control and accountability, vehicle control, pickup and delivery, warehouse storage and other logistics support for 15th Space Surveillance Squadron (SPSS) and mission partners working on site. All core communication IT services include all services required to support the operation, maintenance, and logistics of 15 SPSS Maui Base Support Services Information Technology (MBSS-IT) systems. This effort includes the ability to provide support to various Maui site information and communication systems and associated tenant organizations. The performance of this contract is in support of operations, maintenance logistics management, testing, and all other requirements within the MBSS-IT Performance Work Statement (PWS). Support includes potential future requirements, emerging technologies, system growth, and new/upgraded equipment as needed.

.3 Maui Mission. Discover, Refine, and implement emerging ground-based optical technology and computational analysis to lead U.S. Space Force (USSF) Space Domain Awareness (SDA) capabilities, as well as manage and provide for computation support, research, development, maintenance, operations and management for the Maui High Performance Computing Center.

.4 The unit is home to 15 SPSS, Mission Delta 2 and Air Force Research Laboratory (AFRL), and Directed Energy Directorate. The unit is also the host to several visiting experiments throughout the year, both long and short term.

1.0 GENERAL

This section describes the general requirements for this effort. The following sub-sections provide details of various considerations on this effort.

1.1 The Contractor's performance shall meet all PWS requirements. Service requirements identified as Performance Objectives (PO) have a minimum performance threshold that must be met.

1.1.1 Non-Personal Services: The Government shall neither supervise contractor employees nor control the method by which the contractor performs the required tasks. Under no circumstances shall the Government assign tasks to or prepare work schedules for individual contractor employees. It shall be the responsibility of the contractor to manage its employees and to guard against any actions that are of the nature of personal services or give the perception of personal services. If the contractor believes that any actions constitute, or are perceived to constitute personal services, it shall be the contractor's responsibility to notify the contracting officer immediately.

1.1.2 Unless otherwise required within the PWS Sections 4 through 9, the contractor shall provide support Monday through Friday 0700-1600, except Federal Holidays to include Federal Holidays designated by the President of the United States. On-call capability shall be established and response may be required when mission dictates or when an emergency arises. Please see PWS section x through x for response times. For IT requirements, reference IT PWS xxx

1.2 Key Staffing Requirements Qualifications

To demonstrate understanding of scope and magnitude of PWS requirements, workload and manpower coverage at multiple geographical job sites, the Contractor shall submit evidence of individual qualifications of Key Personnel (annotated below by asterisk*) and an organizational chart outlining proposed staffing, lines of authority and labor categories within 15 days of contract start and as changes to Key Personnel occur. Furthermore, the Contractor shall ensure Key Personnel are not dual-hatted in any other position and that vacancies be filled within 45 days. The Government will furnish the training identified in Appendix xxxxxx.

SS-1 Performance Standard:

a) Standard: Contractor maintains a qualified workforce capable of accomplishing all tasks identified in the PWS.

AQL: Contractor shall submit evidence of individual qualifications of Key Personnel (annotated below by asterisk*) and an organizational chart outlining proposed staffing, lines of authority and labor categories within 15 days of contract start and as changes to Key Personnel occur. Furthermore, the Contractor shall ensure Key Personnel are not dual-hatted in any other position and that vacancies be filled within 45 days.

Deliverable

CDRL M001 Organizational Chart/List of Key Personnel

1.2.1 *Program Manager: Key integration. Coordinates with all disciplines: CE (Engineering Tech V), logistics (Supply Tech), IT (IT Project Manager), and all others to ensure proper execution of all Maui BOS projects. Also acts as the one-stop POC to the Government regarding all affairs with contract operations.

1.2.2 *Engineering Tech V, Project Manager (PM): The PM shall have a bachelor's degree in engineering, architecture, or construction management from a program certified by the Accreditation Board for Engineering and Technology (ABET) or from a program certified by the National Architecture Accrediting Board and a Project Management Professional (PMP) certification.). US military/Air Force Experience preferred. The PM shall have a minimum of 5 years of experience with sustainment, renovation, and minor construction project scoping, estimating, and scheduling related to the following concentrations: Heating, Ventilation, and Air Conditioning Systems (HVAC), plumbing, electrical, fire alarm and suppression, and interior and exterior architecture-related systems.

1.2.3 Production Control Clerk, Operations & Maintenance Manager (OMM): The OMM shall have a minimum of 5 years' experience with Department of Defense Civil Engineering facilities, maintenance, repair, and operations, to include a minimum of 2 years' experience directly managing/supervising within an Operations Function. The OMM is responsible for carrying out Section 7 of this document.

1.2.4 General Clerk III: Work request review board, Real property/facility/BE asset recording, equipment failure reporting, facility project management, requirements management, in-service work plan/meetings, fuels.

1.2.5 *Drafter/ CAD Operator, CAD/IGI&S Drafter: The Drafter must have an Associate's Degree in Applied Science (Architectural/Engineering Drafting Technology) and shall have completed the Environmental Science Research Institute (ESRI) Certified Introduction and Intermediate training in ArcGIS. The CAD/IGI&S (Installation Geospatial Information & Services) Drafter shall have a minimum of 5 years' experience in:

1.2.5.1 Computer aided drafting and design, especially drawing and modeling in an Autodesk AutoCAD software environment.

1.2.5.2 Drawing configuration management workflow processes in an Autodesk Vault software environment.

1.2.5.3 Geographic Information Systems (GIS) data editing, map composition and geographic analysis with ESRI ArcGIS software. ArcGIS software will be provided by the Government if required.

1.2.5.4 Editing and maintaining GIS data in a Spatial Data Standards for Facilities, Infrastructure and Environment (SDS/FIE) compliant Spatial Database Engine (SDE) Geodatabase.

1.2.6 *Quality Control (QC) Manager: The QCM must have a Bachelor's degree in science or business-based programs or 5-years' experience in facilities O&M and strong attention to detail, observation, organizational, and leadership skills. Additionally, the QCM shall possess an in-depth knowledge of quality control procedures and legal standards, have strong background in mathematics, data analysis and statistical methods, and demonstrate excellent communication and listening skills.

1.2.7 *Logistics (Supply Tech) Senior Logistics Coordinator: shall have knowledge of Air Force material accounting procedures, principles of inventory control, fundamentals of distribution, storage, and receipt management of property, and a broad understanding of an interrelated chain of activities involving logistics. Due to the nature of Research and Development (R&D), the Senior Logistics Technician must exercise considerable judgment in applying local decisions that may deviate from normal Air Force supply policy, as permitted in AFI/AFMAN 23-series publications and AFRLI 61-101.

1.2.8 *Environmental Technician, Qualified Environmental Professional (QEP): shall have a Bachelor's of Science degree in environmental science or engineering with minimum 5-years' experience in the environmental field and is corporately trained on applicable Federal and State requirements regarding environmental protection, environmental compliance, environmental conservation, transportation of hazardous waste, and spill response requirements IAW 7 CFR 355-356; 29 CFR 1910.120 and 1910.1200; 32 CFR 989; 40 CFR 112, 260-280, 302, 355, 370, and 700-799; 49 CFR 105-180, and 383; 50 CFR 17-453; Hawaii Administrative Rules (HAR) 11-260 thru 280; and HAR 11-58.1. In the event environmental laws/regulations change during the term of this contract, the Contractor is required to comply as such laws come into effect.

1.2.9 *IT Manager: Shall have a Bachelor's degree in Information Technology Management or Information Technology-based program or 5-years' experience in planning, designing, developing, implementing, evaluating and maintaining information technology systems and networks. The IT manager must have strong problem-solving, critical thinking and leadership

skills. Additionally, the IT Manager shall possess an in-depth knowledge of unclassified and classified network operations to include IT best practices, policies and regulations and a clear understanding of client/server technology and network architecture.

1.2.10 * Information System Security Officer (ISSO) / Primary Communications Security Responsible Officer (CRO) / Primary Secure Voice Responsible Officer (SVRO) / Primary Cryptographic Access Program (CAP) Administrator: shall be certified and cleared IAW DoDM 8100.03, Cyberspace Workforce Qualification and Management Program, DAFMAN 17-1305, Department of the Air Force Cybersecurity Workforce Management Program and AFMAN 17-1302-O, Communications Security (COMSEC) Operations. The ISSO/CRO/SVRO/CAP shall have a minimum of 5 years' experience in:

1.2.10.1 Information security, cybersecurity or a related field.

1.2.10.2 Security protocols, procedures and technologies, such as network security (firewalls, intrusion

detection/prevention systems), cryptography (encryption, decryption), access control (authentication,

authorization) and incident response and management.

1.2.10.3 Security frameworks and regulations, such as NIST Special Publication 800-53 (or superseded

regulation), DoD Instruction 8500.02 (or superseded regulation), and Risk Management Framework

(RMF).

1.2.11 The Contractor shall ensure at least two Warehouse Specialists possess and maintain a Commercial Driver License with Hazardous Materials endorsement. Warehouse specialists, general maintenance workers, HVAC mechanics, electricians, maintenance (mx) scheduler, GC's and Supply Tech must have current state driver's licenses and other certification qualifications to operate general, specialized and forklifts in performance of this contract. Contractor provides COR documentation (letter) certifying contractor personnel are qualified to operate GOVs (general, specialized and forklifts) assigned under this contract. Operator certification will be provided by and at the expense of the contractor and documentation of operator qualifications shall be provided to the contracting officer before any contract employee engages in any mode of equipment operation. This letter will be updated as necessary and remain on file with the COR and 15SPSS Logistics Manager.

1.2.12 * Generator Technician: Technician needs to be certified in on site Generator specific qualification. (CAT/Cummins). Duties will be referenced by section xx

1.3 General Staffing Requirements

This section describes the general Staffing Requirements for non-key staffed positions for the duration of the contract.

1.3.1 The contractor shall in their best effort adhere to staffing proposed in their offers. Any position with a vacancy greater than 3 months will be subject to consideration by the government.

1.3.2 The contractor shall report to the COR/CO monthly any current/ongoing vacancy and the reason why it is empty, actions they are pursuing to fill the vacancy, and the current time it has been unfilled.

Deliverable

CDRL G001 Ongoing Vacancies

1.4 Service Contract requirements

1.4.1 All personnel must be U.S citizens with the ability to speak, read, and write English at the level necessary to perform the tasks in this PWS. All correspondence and communication between the Contractor and the Government pertaining to this contract will be in English.

1.4.2 Mission performance shall not be affected by declared crises, states of emergency, or work stoppages.

1.4.3 Any BOS employee who endangers life, property, or security, or where such employee violates reasonable and necessary regulations or local policy of the FD shall be removed from the site. Categories of violations or misconduct, which may cause employees to be removed from the site include, but are not limited to:

- Security violations.
- Negligence or willful damage to or destruction of property.
- Injuries inflicted upon other personnel.
- Illicit safety violations.
- Creating a hostile work environment.
- Alcohol or drug abuse.
- Engagement in unauthorized private business transactions

1.4.4 Develop and maintain a Strike Plan. The Strike Plan shall address how the contractor will provide required services in the case of a labor dispute. Submit the Strike Plan for acceptance no later than thirty (30) days after the start of the transition period. The Contracting Officer (CO) will consider accepting any changes to the plan within thirty (30) days of occurrence.

Deliverable

CDRL M002 Strike Plan

1.4.5. Contract Line Item Number (CLIN) X006 Over and Above shall be used for the following: Services, construction, and commodities that are both irregularly occurring and exceeding the thresholds in tables 7.1 & 7.2 of section 7.3, shall utilize CLIN X006. CLIN X006 also includes Critical Spares inherently as Over & Above Commodities. The Contractor shall perform Over and Above services/projects and acquire project materials when and as directed by the Contracting Officer (CO) via Notice to Proceed (NTP) in support of Base Support Services (MBSS). Irregularly occurring travel and travel related to training, validated by the COR and authorized by the CO in writing via NTP. To the maximum extent practicable, all requested travel with supporting documentation shall be submitted for review 60 days prior to the first travel day. All travel shall be subject to the Joint Travel Regulation (JTR).

1.5 Public Release of Information

1.5.1 The Contractor is not authorized to release any information regarding performance of this PWS without following the appropriate procedures IAW AFI 35-102 Public Affairs - Security and Policy Review Process. This information includes, but is not limited to, photographs, films, public announcements, internet transmissions, or the denial or confirmation of any of the preceding.

1.5.2 Forward all requests for information regarding the MSSC, RME, or DRDC missions to the 15 SPSS/CC prior to developing a response. All responses must be approved by the 15 SPSS/CC prior to release.

1.6 Funding Status Reports

1.6.1 The Contractor shall provide a monthly funding status report (Funds Log) containing current information on total funding, funds remaining, and total billing (per SLIN) for each contract line-item number (CLIN) of the current performance period to include all status' on built in quantities. The Contractor shall provide supporting information as requested by the CO, COR and PM.

Deliverable

CDRL M003 Funding Status Report

1.7 Organizational Administration

1.7.1 In the course of executing this PWS the contractor is not authorized and shall not take license to make any configuration changes without first gaining pre-approved Government concurrence. Repairs and replacements will use Original Equipment Manufacturer (OEM) parts with exact specifications of existing configurations/items unless specifically stated by the COR. This includes no changes in size, shape, capacity, color, etc., to RP and RPIE systems, subassemblies, parts or components.

1.7.2 Report any MBSS problems affecting the Air Force mission accomplishment to the PM/COR immediately.

1.7.3 Information and documentation generated or maintained (to include government-furnished documents) by this contract shall be maintained on the Government Installation Support Share Drive.

1.8 Emergency Management

1.8.1 Participate in Site Emergency Management exercises and contingency operations.

1.8.2 Exercises requiring Contractor participation will take place within MBSS established working hours.

1.8.3 The Contractor shall provide trusted agents via a primary and alternate representative to participate in the planning of exercises. Trusted agents will not reveal exercise planning information to non-trusted agents.

1.8.4 Unforeseen Events. The scope of this contract includes services in response to requirements resulting from unforeseen events, such as hurricanes, tsunamis, floods, fire, and other disasters (man-made or otherwise) that are detrimental to the mission, reduces operational effectiveness or endangers life, health or safety. The Contractor shall be responsible to coordinate any work with the Site CE, the COR and the CO, and comply with section 6.0 of the PWS and applicable approval procedures for any notice to proceed.

1.8.5 Support the implementation of the 15 SPSS Emergency Management Plan to ensure continued operations during declared crises, states of emergency, work stoppages, or storm conditions.

1.8.7 The MBSS representative shall report immediately to the Crisis Action Team (CAT)/Unit Control Center (UCC) when it is formed and participate until released. Exercises and real-world

events may involve all elements of the scope of this PWS. Exercises requiring Contractor participation will take place within MBSS established working hours. CAT members attend on-line, government-furnished training within sixty (60) days of assuming position, and annual refresher training. On-site training will also be provided at the Government's discretion.

1.8.8 The Government Program Manager (GPM)/COR and CO shall be notified of any cost impacts resulting from declared crises and states of emergencies within twenty-four (24) hours of declaration via cost estimates. Specific costs shall be provided within three (3) business days of the end of declared crises or state of emergency.

Deliverable

CDRL M004 Cost Impact – Declared Crises/State of Emergency (SOE)

1.9 Quality Control

1.9.1 The Quality Control Manager (QCM) shall ensure that all products, inspections, data, and site-wide activities destined for the government comply with applicable standards and remain free of errors or inaccuracies. Furthermore, the QCM shall be responsible for maintaining a high level of workmanship across all aforementioned areas.

1.9.2 Develop and implement a Quality Control Plan (QCP) IAW FAR 52.246-4 Inspection of Services - Fixed Price. The Contractor shall develop and implement procedures to identify, prevent and ensure non-performance and continual repeat of defective service does not occur. Submit initial QCP to the CO and PM/COR for acceptance within thirty (30) days after contract award. Update and distribute as required to the CO and PM/COR within ten (10) days of changes.

Deliverable

CDRL M005 Quality Control Plan

1.9.2 The QCP shall include:

1.9.2.1 A description of the inspection system to cover all tasks and services listed in the PWS outlining the specifics of the areas to be inspected on a scheduled and unscheduled basis, frequency of inspections, submission of quality control inspection schedule, surveillance methodologies; e.g., One-Hundred Percent, Periodic Inspections, Customer Complaints, etc. and the title and organization placement of the inspectors.

1.9.2.2 A description of quality control processes in place to ensure all contract programs, plans, reports, and other submittals are tracked and submitted to the government IAW the specific and technical requirements for each submittal. Data shall include all types of

documentation regardless of format (electronic, hardcopy, photographic, or any other format utilized by the contractor).

1.9.2.3 A description of the data analysis to be performed on all collected data to identify, for all areas of performance, levels of performance above, below, or at required thresholds and positive, negative, and neutral trends in the levels of performance.

1.9.2.4 A description of the method(s) to be used for identifying and preventing defects in the quality of service performed.

1.9.2.5 Five (5) duty days prior to the end of month, the Contractor's QCM shall submit a quality control surveillance schedule to the PM/COR for the following month. The PM/COR will notify the contractor within 2 duty days following schedule submission which scheduled activities the government will attend. The Contractor shall allow government personnel to accompany and observe the inspection/surveillance activity.

1.9.2.6 The contractor shall schedule a quarterly Quality Control meeting and present meaningful QC metrics, trend analysis, deficiency root cause and status of corrective action plans. The meeting shall be attended by the PM/COR, key government stakeholders and the contractor's key personnel.

1.9.2.7 All records generated by the contractor's quality control program as described in the QCP shall be kept and made available to the government throughout the contract performance period and for the period after contract completion until final settlement of any claims under this contract, but not less than 180 calendar days after contract completion.

1.9.2.8 The Contractor's QCP shall be in effect at contract start and at the first day of each option period with no late submittals allowed. Once accepted by the Contracting Officer/Administrative Contracting Officer, the contractor's QCP shall become part of the requirements of this contract. All change(s) to the QCP must be accepted by the government prior to the implementation of the change(s).

1.9.3 The contractor's QCM, working in tandem with the contractor's PM, shall ensure a project-specific quality control plan is developed detailing the plan to control all areas of project execution requirements performed under Sections 4, 5 and 6 of the PWS. To ensure quality and customer requirements are met, the QC plan shall address:

1.9.3.1 Designating a qualified subject matter expert quality control manager overseeing the construction project effort.

1.9.3.2 Identifying lines of communication throughout the project; e.g., project start-up meeting, routine production control meetings, providing inspection forms and test reports to the government, etc.

1.9.3.3 Implementing a quality assurance surveillance to ensure project quality controls are running the way that they should.

1.9.3.4 Documenting key suppliers and sub-contracted work.

1.9.3.5 Meeting customer specifications and determining which building codes or industry standards that apply to the scope of work.

1.9.3.6 Inspecting and documenting phases of work (like steel erection) and performing tests that verify material quality (like concrete strength). Inspection procedures shall ensure that work is ready to begin and address the handling material receiving and inspections, monitoring work in progress and verifying that completed work meets project specifications.

1.9.3.7 Controlling of non-conformance: The quality plan should discuss how the contractor will handle situations where things may go wrong in construction. Make clear how the contractor will control nonconformance to prevent cover-ups and protect the overall quality of the project.

1.9.3.8 Conducting project completion inspections. Describe how the contractor will conduct inspections and punch out near the end of the project to assure that all the contracted work is completed to specifications.

1.9.3.9 1.9.4 Reference the Core Communications PWS Appendix section 2.9.1 for specific IT, QC requirements.

1.10 Government Inspections

1.10.1 Cooperate with and participate in internal and external inspections to include the regularly scheduled inspections identified in Appendix 10, and any others deemed necessary by the government. Summary workload data regarding the dates, purpose, and size of each inspection team shall be maintained.

1.10.2 Notify the Government of any local inspections being driven by the Contractor's corporate offices for internal Contractor requirements no later than (NLT) thirty (30) days prior to the inspection date. Contractor inspections for the purpose of internal validation, quality control, or other corporate requirements shall not take priority over contract requirements or interfere with mission requirements. The contractor's inspection is subject to the discretion of the 15 SPSS/CC and can be denied.

1.11 Meetings

Support meetings, briefings, working groups and technical interchange meetings in coordination with Government functional representatives. Provide required input and participation in regularly scheduled meetings and unscheduled meetings for planning, site improvements, and

all ad-hoc meetings deemed necessary by the COR/CO as well as supply meeting minutes. Format and content for these meetings will include cost, schedule and performance metrics. For MBSS hosted/run meetings, contractor personnel shall be fully prepared at the start of each meeting to include activation of video/teleconferences, presentations systems, computer systems and have briefings, presentations, documentation, etc. up and running. MBSS personnel in attendance shall be versed in the content/subject matter of each meeting and prepared to respond to queries. Regularly scheduled meetings are listed in Appendix 8.

1.12 Publications

1.12.1 Contractor operations shall comply with the current version of all referenced publications.

1.12.2 Comply with all applicable directives cited in this PWS and Appendix 4. In the event the directives change during the terms of this contract, the contractor is required to comply as the changes come into effect if they do not impact cost or delivery schedules or if a conflict does not arise in implementation of the new procedures. If any of these conditions occur, a written evaluation along with specific backup data and estimated cost data for those changes which impact the contractor's performance shall be provided to the CO. Do not incorporate publication changes until approved by the CO. In the event there is a conflict between two (2) or more publications, provide written evaluation along with specific backup data to the CO and the PM/COR within fourteen (14) days of knowledge of conflict. The CO will provide conflict resolution to the contractor. Ensure that all technical orders, regulations, instructions, manuals, pamphlets, engineer technical letters (ETLs), and forms are current and available or on order to perform all requirements of this PWS.

1.12.3 Review future updates to 15 SPSS created instructions, policies, checklists and plans for content and contract impact prior to initial publication or revision.

1.13 Transportation

1.13.1 The contractor will provide necessary transportation for all MBSS employees to and from MSSC unless otherwise provided by the government.

1.13.2 Follow applicable federal, state, and local driving laws and regulations when driving through Haleakala National Park.

1.13.3 The contractor shall obtain the required National Park Services special access permit through the Haleakala National Park commercial manager. The cost of permit shall be projected in the firm fixed price CLIN.

1.13.4. Separately, all subcontractors performing work under this contract shall obtain the required National Park Service special access permits through the Haleakalā National Park as described in paragraph 1.12.3

1.13.5 At MSSC, the contractor shall be limited to six (6) daily use parking spaces for MBSS vehicles at the government's discretion.

1.14 Contractor Work Space

1.14.1 Work space deemed usable by the government may be provided by the USSF at MSSC on Haleakala, RME, and MILCON Facility at sea level as applicable/available. RME office space is set aside for MBSS use. MSSC office and storage space set aside for MBSS use in the Butler Building. This facility is a multi-use facility with a small shop area set aside for R&D contractor use. Any additional space required will be the responsibility of the contractor at the summit site. Space requests will be authorized by the government sparingly if possible.

1.14.2 The contractor shall provide warehouse and storage space needed to execute PWS requirements outlined in Section 4.

1.14.3 The Government may provide workspace at the MILCON's Log Center for all work defined in section 4 of this PWS.

1.15 Organizational Equipment

The contractor will be allowed to use the Government-leased flat bed for pickup and delivery services outlined in paragraph 4.3. Furthermore, the contractor shall have access to the 6K electric forklift located at MSSC under a "joint use" arrangement in addition to the two Government-furnished forklifts identified in Appendix 5. Vehicle usage shall be IAW the most recent versions of:

41 CFR 101-39.202

41 CFR 101-39.300

41 CFR 102-34

AFI 24-301

AFMAN 24-306

AFRL 15SPSS SOP 24-1

All city, county, state and federal traffic laws

1.15.1 Refer to Appendices 5 and 14 for additional information on organizational tools and equipment available to the MBSS contractor.

1.16 Non-Secure Communications

Ensure MBSS personnel comply with local and AF Non-Secure Communications requirements. The Contractor shall:

1.16.1 Pacific Land Mobile Radios

1.16.1.1 Use the AF provided Pacific Land Mobile Radio (PLMR) hand-held and mobile (vehicle mounted) radios for communication during travel as needed for communication while working at the site and the contractor office facility. Government provided PLMR systems are detailed in Appendix 9.

1.16.1.2 Abide by the 15 SPSS Chief Information Officer (CIO) developed local training guide for use of radios.

1.16.1.3 Ensure all MBSS personnel are fully trained on the use and limitations of the PLMR systems. PLMR training is provided on the local file storage. Maintain PLMR training records.

1.16.1.4 With the written approval of the 15 SPSS CIO, the contractor shall have mobile radios installed/uninstalled in MBSS vehicles. Government approved installation vendors are listed in Appendix 9.

1.16.1.5 All problems with the PLMR systems shall be reported immediately to the CIO.

1.16.1.6 PLMR handheld radios will not be used in certain areas of the facilities at MSSC during normal operations due to security concerns. These areas have been identified and signs are in place. Note: During emergency operations, the PLMRs may be used anywhere in the facilities as needed.

1.16.2 Telephone

Ensure appropriate use of Government provided telephone service IAW AFMAN 17-1202, Collaboration Services & Voice Systems Management and MPTO 00-33A-1108, AFIN Voice Systems Management.

1.16.3 Computer Network Access

1.16.3.1 Access to the af.mil network shall be granted only after specified criteria have been met as defined in AFI 17-100, Air Force Information Technology Service Management.

1.16.3.2 Network access will be approved IAW AFMAN 17-1301, Computer Security (COMPUSEC).

1.16.3.3 Ensure MBSS personnel accomplish the necessary training as prescribed by AFMAN 17-1301, Computer Security (COMPUSEC) (or superseded regulation). All authorized users of DoD Information Systems /Platform Information Technology systems such as those requiring access to the Air Force Network (AFNet) consisting of the Non- Classified Internet Protocol Router (NIPR) network, must receive initial and annual cybersecurity user awareness training as a condition of access to an IS IAW AFMAN 17-1301, Computer Security (COMPUSEC) (or superseded regulation).

1.16.3.4 Use the site helpdesk to resolve all computer/network problems. Helpdesk contact info will be provided at award.

1.16.3.5 No contractor owned specific or other outside networks shall be installed at the site or hardware or software shall be used on the Air Force network without the written permission of the CIO.

1.16.4 External Devices

1.16.4.1 The following devices are not allowed in any secured/closed/classified locations at the 15th under any circumstances:

1.16.4.1.1 Cell phones.

1.16.4.1.2 Still or video cameras.

1.16.4.1.3 Radios, MP3 players or other audio recording devices.

1.15.4.1.4 Personal data assistants (PDA), smart watches or blue-tooth enabled devices (e.g., Fitbits).

1.16.4.1.5 Memory storage devices (USB memory stick/thumb drives/USB hard drives, etc.)

1.16.4.2 Government equipment may be made available if required in the performance of work contained in the PWS.

2.0 Safety

The Contractor Shall:

2.1 Develop and maintain a safety and health program where occupational injury rates are below national average and employee participation and ownership are the hallmarks of the program. Improve safety and occupational health accountability at all organizational levels by

obtaining a “Star” site certification IAW the guidance found at the Voluntary Protection Program (VPP) website: <http://www.osha.gov/dcsp/vpp/index.html>.

2.1.2 Ensure all employees fully comply with OSHA requirements and AFI 91-202, The US Air Force Mishap Prevention Program.

2.1.3 Contractors, to include subcontractors, whether regularly involved in routine site operations or engaged in temporary projects such as construction or repair, must follow the safety and health rules of the VPP site.

2.2 Comply with OSHA (29 USC 651 et al.) and the resulting standards, OSHA Standard 29 CFR Parts 1910-1926, as applicable, and be responsible for the protection and safety of contractor and subcontractor employees. Immediately report any accidents involving contractor personnel occurring on the job to the CO and the 15SPSS Safety Office.

2.3 Safety Program/Plan.

2.3.1 Establish and maintain an acceptable Safety Program IAW AFFARS 5352.223-9001 Health and Safety on Government Installations.

2.3.2 Submit a Safety Plan to the COR and Site Safety Officer (SSO) within ten (10) days after phase-in start; concurrently submit a letter to the CO certifying the safety program/plan meets all Federal, State, and local laws, regulations, and standards listed in Appendix 4. The plan will be reviewed and must be either accepted or rejected by the government prior to the end of the transition period. All changes to the plan must be submitted to the COR and Site Safety Officer (SSO) no later than (NLT) fifteen (15) days prior to the implementation of the change(s). No changes to the plan will be implemented in advance of government acceptance.

Deliverable

CDRL S001 Safety Plan

2.3.3 The Safety Plan shall include appropriate measures to promptly investigate, correct, and track alleged safety and health violations and/or uncontrolled hazards in contractor work areas. Additionally, the Contractor shall be responsible for ensuring employees are knowledgeable and comply with Occupational Safety and Health Standards when on working on IT and electronic equipment.

2.3.4 Establish safety requirements for all subcontractors who qualify as applicable contractors.

2.4 Contractor Safety Manager. Assign a contractor safety manager and identify on the organizational chart who will administer the safety requirements of this PWS and will be the Government’s primary POC.

2.5 Mishaps. In the event of an accident/mishap, as described in AFI 91-204, Safety Investigation and Hazard Reporting, take reasonable and prudent action to establish control of the accident/mishap scene, prevent further damage to persons or property, and preserve evidence until released by the accident/mishap investigative authority through the CO.

2.5.1 In the event of an accident on government property, or involving government personnel or property, the Contractor shall submit a report within seventy-two (72) hours to the CO in letter form that shall include the following: 1. The time and date of occurrence. 2. The place of occurrence. CUI 1-2-2 CUI CUI 1-2-2 CUI CUI CUI 3. A list of personnel directly involved. 4. A narrative or description of the accident to include chronological order of the accident and circumstances.

2.5.2 If the government elects to conduct an investigation of the accident/mishap, all employees must cooperate fully (to include toxicology testing) and assist government personnel in the conduct of investigation.

2.5.3 Provide data collection support to the Installation Safety Office for mishaps investigation.

2.6 Inspections. Comply with inspectors from OSHA and/or any AF inspection agency making routine inspections of contract operations and work sites checking for regulatory compliance to standards.

2.7 Annual Reports. Provide the COR, SSO, and Installation Safety Office the Total Case Incidence Rate (TCIR); Days Away, Restricted, and/or Transfer Case Incident Rate (DART); and OSHA Form 300A, Summary of Work-Related Injuries and Illnesses, by the 15th of January every year for annual submission in the site annual VPP self-evaluation report.

Deliverable

CDRL S002 Total Case Incidence Rate (TCIR)

CDRL S003 Days Away, Restricted, and/or Transferred Case Incidence Rate (DART)

CDRL S004 OSHA Form 300A, Summary of Work-Related Injuries and Illnesses

2.8 Safety Equipment and Medical Assistance Supplies.

2.8.1 Provide first aid kits throughout the site to assist in case of an accident or injury. Ensure enough kits are available and appropriately placed to allow for quick and easy access.

2.8.2 Provide one AED throughout per building to assist in case of a medical emergency. Ensure enough systems are available and appropriately placed to allow for quick and easy access.

2.8.3 Provide portable oxygen systems throughout MSSC to assist in case of medical need. Ensure enough systems are available and appropriately placed to allow for quick and easy access.

2.8.4 Inspect all first aid kits, AEDs, and oxygen systems IAW product manufacturer's specifications, AFI 44- 177, Public Access Defibrillation Program, and OSHA 29 CFR 1910 as listed on Appendix 19. Check for any recalls or manufacturer identified failures and replace unit, as required. Replace items on a non-reimbursable basis as required due to use or expiration.

2.8.5 Develop and maintain an inventory of all, first aid kits, AEDs, and oxygen systems. Provide initial inventory to the COR and AFSSO NLT sixty (60) days after contract award. Provide an updated inventory, to include expiration date, to the COR and AFSSO annually.

Deliverable

CDRL S005 First Aid Kit, AED and Oxygen System Inventory

2.8.6 Provide up-to-date site maps with the locations of all first aid kits, AED, and oxygen systems to the 15SPSS AFSSO within 30 days of after contract start, then annually, or when major locations change, and post maps throughout the facilities.

Deliverable

CDRL S006 Site Maps ID location of First Aid Kits, AED and Oxygen Systems

3.0 SECURITY:

Requirements, restrictions, and other safeguards required to prevent unauthorized disclosure of classified information. The Contractor shall:

3.1 Site Physical Security.

3.1.1 Comply with Government provided physical measures IAW AFI 31-101 Integrated Defense (FOUO), and Intelligence Community Directive (ICD) 705 Physical Security Standards for Sensitive Compartmented Information Facilities and other Maui Site specific guidance.

3.1.2 Comply with the 15 SPSS Antiterrorism/Integrated Defense Plan (A/IDP). Comply with local security requirements established by the government for the site.

3.2 Personnel Security. Ensure that all personnel have appropriate clearances and access credentials at contract start date. The minimum level of security clearance required for this contract is U.S Secret. An interim Secret is acceptable for newly hired contractor personnel awaiting final adjudication.

3.2.1 The government will identify the applicable IT personnel required to hold a TS Clearance. All TS cleared personnel are required by the Government to have access to TS information and must have current TS clearance at the time contract performance begins.

3.2.2 The Key Personnel identified by the contractor must have required security clearances NLT the first day of the transition period.

3.2.3 Maintain a workforce capable of accomplishing all tasks outlined in this PWS with the security clearances required. The Contractor shall provide an updated Defense Information System for Security (DISS) visit certification of all new employees upon hiring actions for cross-reference with DISS and provide status on e-QIP investigations on new hires that do not possess a clearance. Maintain records of all employees' security clearances until the end of the contract.

3.2.4 Enter into a Visitor Group Security Agreement with the Government that will be reviewed and updated annually by the Government Site Security Officer. The Contractor shall support and comply with security inspections conducted and/or requested by Air Force personnel.

3.2.5 Access to Government computer systems and secured facilities requires additional clearance checks through DISS. Common Access Cards (CACs) require background checks prior to issuance to contractor personnel.

The process for this includes submitting personal information for each applicant to the government's Trusted Agent for input into the Contractor Verification System. The contractor employee must clear the background security checks before being issued a CAC. Additionally, the Government will issue site access badges to contractor personnel for facility access. To avoid delays in starting work, be proactive in submitting applications for personnel security clearances.

3.2.5.1 Ensure that in/out processing documentation is completed for all new hires and personnel departing. This needs to be accomplished during the 1st week of employment and employees' last days prior to departure. Such actions occur at the duty location with respective government offices.

3.2.5.2 Ensure CACs from personnel no longer working on the installation are collected and returned to the Government within three (3) days of departure.

3.2.5.3 Ensure site access badges are immediately collected and turned in to Security Forces (SF) when an employee is terminated or suspended. In exigent circumstances when a badge cannot be collected, SF will be notified in order to electronically disable badge.

3.3 Uses and Safeguarding of Information.

3.3.1 Information from the secure web site is considered to be proprietary in nature when the contract number and contractor identity are associated with the direct labor hours and direct labor dollars. At no time will any data be released to the public with the contractor name and contract number associated with the data.

3.4 Facility Security Officer (FSO).

3.4.1 The appointed FSO must be a US citizen who is cleared as part of the facility clearance. The FSO will, as part of the facility clearance, obtain a DISS account through the cognizant Defense Security Service (DSS) office. FSO and facility clearance must be obtained NLT the start of transition period.

3.4.2 This individual shall be the single point of contact for complying with security programs and procedures IAW with security regulations listed in Appendix 4. This individual is not required to be located at the site or solely dedicated to the MBSS.

3.4.3 The FSO will supervise and direct security measures necessary for complying with applicable requirements of the NISPOM and related Federal requirements for the protection of classified information.

3.4.4 The FSO, or on-site designated representative, shall complete security training as specified in the NISPOM.

3.5 Security Training.

3.5.1 Contract and subcontract personnel shall complete security training IAW the security regulations listed in Appendix 4.

3.5.2 Maintain documentation of all security training to include date, method, topics, and administrator; if applicable, include computer based or handwritten signature from trainee and/or administrator. Maintain a copy upon completion of each training element IAW Appendix 11.

3.6 Anti-Terrorism (AT).

3.6.1 Ensure all contractor employees complete Antiterrorism Level 1 training within 30 days of employment start and annually thereafter. Certificates showing completion of training shall be distributed to the 15SPSS AT Officer. Training can be accessed at: <https://jko.jten.mil/>

3.6.2 Upon initial notification from the Antiterrorism Officer ATO or ATO representative throughout Force Protection Condition (FPCON) duration, comply with FPCON measures for the current FPCON level.

3.6.3 During exercise and real-world events, all personnel will implement FPCON measures and Random Anti-Terrorism Measures (RAMs) within areas and processes under their control IAW FPCON checklists and the guidance of the ATO. These measures will include, but not be limited to, moving vehicles at least twenty-five (25) meters from any critical facilities, conducting random checks of trash receptacles and storage containers, securing all facilities/storage areas not in regular use, inspecting interiors and exteriors of work areas for suspicious articles, screening incoming mail and commercial deliveries.

3.6.3.1 During increased FPCON levels (BRAVO and CHARLIE) expect delays upon entering the MSSC area. All personnel (100%) will be screened for positive identification and gym bags and backpacks will be inspected. Vehicles will not be permitted on the MSSC. Non-essential meetings/visits will be cancelled.

3.6.3.2 During the highest FPCON level (DELTA) only essential Key Personnel will be permitted to enter the site. Non-essential personnel will not be permitted entry to the site.

3.7 Active Shooter.

3.7.1 Ensure all contractor personnel complete the annual Active Shooter classroom training provided locally by the Government.

3.8 Any MBSS employee who endangers life, property, or security, or where such employee violates reasonable and necessary regulations or local policy of 15 SPSS/CC shall be removed from the site. Categories of violations or misconduct, which may cause employees to be removed from the site include, but are not limited to:

3.8.1 Security violations.

3.8.2 Negligence or willful damage to or destruction of property.

3.8.3 Injuries inflicted upon other personnel.

3.8.4 Illicit safety violations.

3.8.5 Creating a hostile work environment.

3.8.6 Alcohol or drug abuse.

3.8.7 Engagement in unauthorized private business transactions.

4.0 LOGISTICS

Logistics/supply workload factors are provided in Appendix 28. Unless otherwise specified, all labor, supplies/materials, third-party inspections, shipments (postage/mailing), vehicle add-on equipment (install and removal) and non-organic equipment calibration costs and minor repair

(commercial) shall be under the firm fixed price Logistics CLIN. The Contractor shall perform supply, transportation, vehicle fleet management and property control functions as defined in this PWS in support of 15 SPSS mission and all partners associated to the site, applying the applicable references listed below and 23/24-series 15 SPSS Standard Operating Guides or successor local instruction(s). Where formal appointment of a logistics role is required, the Contractor shall ensure an Alternate person is appointed and qualified to fill the role. With the exception of Over and Above projects covered under PWS Section 6.0 and unless specifically specified by the COR, all this section's work is executed through the firm fixed price CLIN X003 as this work is regularly scheduled/anticipated/reasonably accountable. This includes materials, labor, and other direct costs (ODCs). The Government reserves the right to utilize CLIN X003 for the assistance of CLIN X006 material deliveries.

The Contractor shall:

4.1 Property Accountability.

4.1.1 The Senior Logistics Coordinator (SLC) shall serve as the first (1st) Alternate Property Custodian to the Primary Property Custodian (15 SPSS/CC) and Primary Supply Liaison to the 15 SPSS Accountable Property Officer

(APO):

4.1.1.1 Serve as 1st Alternate Property Custodian for centrally-managed equipment (excluding weapons), maintained by the 647th LRS, DPAS FE5260/AD2302/638PL and RDTE support equipment maintained in DPAS AFRLHQ/MAFB61.

4.1.2 The SLC shall:

4.1.2.1 Assume the role of Alternate Property Custodian within fifteen (15) days after contract start (or upon new hire start date) and complete all required training and joint inventory of assigned equipment.

4.1.2.2 Account for all property within prescribed inventory intervals, sign the Custodian Inventory Report (CIR) and staff for 15 SPSS/CC signature.

SS-2 Performance Standard

a) Standard: Account for all property within prescribed inventory intervals, sign the Custodian Inventory Report

(CIR) and staff for 15 SPSS/CC signatures.

AQL: 100% of the time

4.1.2.3 Lead annual floor-to-book inventories and notify the responsible ECF/ECO of equipment found on base (FOB) within three (3) workdays.

Deliverable

L001 List of FOBs for DPAS Entry

SS-3 Performance Standard

a) Standard: The SLC shall report FOBs to the responsible ECF/ECO within three (3) workdays for equipment that meets mandatory DPAS accountability criteria in DPAS Site ID AFRLHQ/MAFB61.

AQL: 100% of the time

4.1.2.4 Comply with all tasks related to Property Custodian duties IAW AFI 23-101, Materiel Management Policy, DAFI 23-111, Accountability and Management of DoD Equipment and Other Accountable Property, DAFMAN 23- 119, Government Furnished Property, AFMAN 23-122, Materiel Management Procedures, and AFRLI 61-101, AFRL Equipment and Other Laboratory Asset Management.

4.1.2.5 Coordinate on all other key supply and transportation matters with the host LRS, to include performing/signing annual inventory, reconciling Controlled Cryptographic Item (CCI) serialized reporting, submitting item catalog requests and providing accurate asset location to aid in the physical accountability of assigned equipment.

4.1.2.6 Participate in the joint inventory of Government Furnished Property (GFP)/Contractor Acquired Property (CAP) being delivered to the Government from other contracts assigned to 15 SPSS. Upon acceptance by the (GPM), the SLC shall coordinate the creation or update of property records in the applicable DPAS Site ID.

4.1.3 The Contractor shall establish a robust Organizational Visibility List (OVL)--formerly known as R15, to track 15 SPSS/RDSM-owned equipment valued under \$5,000. If equipment is tracked within the TMDE or CTK programs, it does not need to be duplicated in the OVL. OVL line-item updates shall occur upon receipt of purchase (additions), location movement (changes) and turn-in (removals). Minimum requirements should identify manufacturer/model (or part) number, unit cost, location and date of record entry.

Deliverable

L002 OVL Equipment Tracker

4.1.4 The Contractor shall appoint Contractor personnel to serve as Property Coordinators for all site TMDE items and OVL equipment issued to the MBSS Contractor.

4.1.5 The Contractor shall appoint a Logistics Support Stock (LSS) Monitor to manage all 15SPSS facilities and mission support and component stock.

4.1.5.1 Maintain shop stock and work order residue for day-to-day facility operations.

4.1.5.2 Process excess support or shop stock for turn-in through the host LRS or DLADS.

4.1.6 Contractor personnel filling the roles described herein shall notify the Primary Custodian and APO of lost, damaged or missing equipment within two workdays of discovery.

4.2 Equipment Control Function/Officer

4.2.1 Appoint Contractor personnel to serve as the Equipment Control Function/Officer (ECF/ECO) IAW AFMAN 17-1203, AFRLI 61-101, AFRL Equipment and Other Laboratory Asset Management, and 15SPSS operating guidance(s). The ECO/ECF shall maintain accurate property records in DPAS Site IDs FF-GEIT/FU2350 and DFRDTE/MAFB61.

4.2.2 Process all property record transactions to ensure data/inventory balance accuracy of government property records maintained in DPAS, to include receipts, loans, turn-ins, transfers, shipments, records adjustments, reversals, location updates, date of inventory updates, financial data, date of procurement and other miscellaneous updates within seven (7) workdays.

SS-4 Performance Standard

a) Standard: Process all property record transactions to ensure data/inventory balance accuracy of government property records maintained in DPAS, to include receipts, loans, turn-ins, transfers, shipments, records adjustments, reversals, location updates, date of inventory updates, financial data, date of procurement and other miscellaneous updates within seven (7) workdays of date requested or upon discovery; e.g., FOBs, turn-ins, incoming receipts, etc.

AQL:

a) Property record transactions are accurately processed within seven (7) workdays 90% of the time for:

1) DPAS FF-GEIT/FU2350

2) DPAS DF-RDTE/MAFB61

4.2.3 Create and maintain item cataloguing for L&P stock-numbers assigned to property records in DPAS Site ID DF-RDTE using the H2 Federal Supply Classification and H6 Item Name Directory tools to properly assign Federal Stock Class.

4.2.4 Maintain a current custodial equipment jacket folder for each equipment account. Custodian jacket folders shall include a current signed Custodian Inventory Report (CIR), appointment letter, training certificates and key supporting documents (KSD) for capitalized equipment.

SS-5 Performance Standard

a) Standard: Maintain a current custodial equipment jacket folder for each equipment account. Custodian jacket folders shall include a current signed Custodian Inventory Report (CIR), appointment letter, training certificates and key supporting documents (KSD) for capitalized equipment.

AQL: 100% of the time

4.2.5

Provide Property Coordinators with DPAS-generated inventory listings, labels, and bar-code readers, as necessary, to complete inventory and Item Unique Identification (IUID) marking requirements.

4.2.6

Assist the Primary Property Custodian and SLC in the reconciliation of equipment record additions, deletions and changes involving CIRs produced from DPAS Site ID FH-AFHAF/AD2302/638PL.

4.2.7

Reserved.

4.2.8

Process DPAS reports necessary to maintain data integrity, inventory control, and cataloging information. Provide 15 SPSS Logistics Manager with monthly DPAS records list and a documented quarterly inventory increases/decreases report.

Deliverable

L003 Monthly & Quarterly DPAS Reports

4.2.9

Conduct and document initial/refresher training covering roles and responsibilities of equipment custodian and property coordinators.

4.3 Pickup and Delivery .4.3.1

Deliver supplies and equipment to, from, and between all site locations in support of the Government requirements outlined by 15 SPSS..

4.3.1.1

Deliveries made to MSSC are subject to quarterly inspections by National Park Environmental Protection personnel to mitigate impact of invasive species transiting through Haleakala National Park.

4.3.1.2

The Contractor shall coordinate inspection date/time/location with National Park and set-up method of payment to the National Park for cost recovery of Environmental Protective Specialist's time and travel.

4.3.2

Pickup equipment and supplies, including those downgraded to scrap or electronic waste from all site locations.

4.3.3

Pickup materiel from various commercial, DoD contractor(s) and government locations limited to the island of Maui to include but not limited to the Port of Kahului, Air National Guard, Bldg. 535 and local vendors providing compressed gases, recurring uniform/coverall cleaning exchanges and other locally procured items requiring use of P&D services.

4.3.4

Transport equipment and supplies approved for on-Island disposal.

4.3.5

Obtain and provide signature to acknowledge receipt and delivery of equipment.

4.3.6

Provide forklift operator support for loading/unloading oversized items and during site projects performed by subcontractors or visiting experimenters, as identified by Base Civil Engineering Office or sponsoring Program Manager.

4.4 Central Receiving

4.4.1

Serve as the central receiving point for all supplies and equipment purchased or acquired through the Integrated Logistics System-Supply (ILS-S), local purchase sources, returned from repair or calibration, redistributed from other AF units, withdrawn from DLA, or temporary supplies and equipment in support of 15 SPSS.

4.4.2

Process and handle all materiel receipts with appropriate protection to preserve the reliability and maintainability built into the material.

4.4.3

Ensure an auditable system is in place to determine date materiel received, in-checker identification and ultimate consignee.

4.4.4

Upon delivery of materiel from commercial carrier, verify and off-load material, segregate, in-check, label, process, and deliver materiel to end user IAW AFI 24-602V2, Cargo Movement. Property purchased by or with government funds shall be marked as Government Property and/or assigned an Asset Identification label, as required for DPAS reporting. Receive, sort and distribute incoming mail addressed to Bldg. 550.

4.5 Warehouse and Stockroom Operations (Para 4.3.4 includes support to VEs).

4.5.1

Provide sound and effective warehouse circulation control to protect government resources and to ensure the accuracy of the inventory held in storage, to include items in locked containers, and designated storage areas at AEOS and MSSC.

4.5.2

Ensure that all inventory in storage is: 1) properly tagged with item identification, condition and stock number/part number and; 2) protected to preserve the serviceability from the elements.

4.5.3

Manage property approved for temporary and courtesy storage and document list of requesters, purpose and duration of storage.

4.5.4

Perform annual inspection to assess good housekeeping, appropriate stock levels, storage markings and uniformity of Logistics Support Stock and Operating Materials and Supplies in support of RDT&E.

4.5.5

Manage the Reusable Container Program IAW AFI 24-602V2.

4.6 Excess Materiel (Includes support to VEs).

4.6.1

Serve as the primary point of contact (POC) for all organizational and site-directed materiel transfers approved for disposition through the Defense Logistics Agency Disposition Services (DLADS) as described in AFI 23-101, Air Force Materiel Management, Chapter 6 and AFMAN 23-122, Materiel Management Procedures, Chapter 6.

4.6.2

Prepare disposition turn-in documents (DTID) and process all excess equipment and supplies through the DLADS, when excess materiel is not otherwise eligible for redistribution to other Air Force units.

4.6.3

Perform "Generator" responsibilities outlined in the latest version of the Memorandum of Agreement between the USSF and DLA Disposition Services.

4.6.4

Establish and manage shred bin collection points for paper records/correspondence screened by and approved for local destruction by 15 SPSS.

4.6.4.1

Ensure shred bin contents is controlled by lock.

4.6.4.2

Schedule and deliver periodic mass shredding with local vendor.

4.6.4.3

Act as authorized Agent(s) for 15 SPSS to witness the complete destruction (shredding) of paper records.

4.6.4.4

Provide the COR with a destruction summary report listing total weight, method of destruction, date, vendor location and name of authorized Agent who witnessed the destruction.

4.6.4.5

Personnel identified as Agent(s) shall sign a non-disclosure agreement.

4.7 Shipments.

4.7.1

Plan non-MILSTRIP shipments using best modes/methods consistent with cargo classification/level of protection, delivery requirements, receiving location and receiving capabilities IAW AFI 24-602V2.

4.7.1.1

Coordinate cargo pick-up with 647th LRS Vehicle Dispatch for shipments sent through Port of Honolulu and marked-for JBPHH agencies IAW Intra-Agency Support Agreement between NAVSUP FLC Pearl Harbor and 15SPSS.

4.7.2

Verify shipment packaging, documentation and notification requirements to prevent damage, misrouting or other discrepancies involved in the handling of shipments.

4.7.2.1

Shipments sent to the 647th LRS, DLADS, and 15th Wing Test, Measurement and Diagnostic Equipment (TMDE) Flight are non-MILSTRIP shipments and require the DD Form 1149, Requisition and Invoice/Shipping Document, created within the USAF Logistics Tool Suite (LTS). For LTS enrollment/access, visit: <https://lts.wpafb.af.mil/>

4.7.2.2

Pre-coordinate the outbound shipment of CCI and Arms, Ammunition and Explosives (AA&E) to ensure recipient is equipped to receive CCI and AA&E and follow-up with a Notification Report of Shipment (REPSHIP) at least one (1) workday in advance of the scheduled shipment. Similarly, acknowledge REPSHIP notification for all CCI and AA&E planned for shipment to 15SPSS.

SS-6 Performance Standard

a) Standard: Pre-coordinate the outbound shipment of CCI and Arms, Ammunition and Explosives (AA&E) to ensure recipient is equipped to receive CCI and AA&E and follow-up with a Notification Report of Shipment (REPSHIP) at least one (1) workday in advance of the scheduled shipment.

AQL: 100% of the time

4.7.2.3

For hazardous material shipped by air, ground or ocean, provide at least one qualified individual to certify and sign dangerous goods declaration forms.

4.7.2.3.1

Provide 49CFR, IATA, IMDG training certification to the COR within 30 days of contract start.

4.7.2.3.2

Provide a 24-hour emergency response telephone number on shipment declaration forms for use in the event of an emergency involving the shipment of hazardous material originating from the site.

4.7.3

Establish and maintain transportation control numbers that enable traceability of shipments from origin to destination.

4.7.4

As primary POC for all inbound shipments, including Det 3 tenant unit and VEs, resolve discrepancies for all inbound cargo in “frustrated” status.

4.7.5

Provide mailing and shipping services for official Government correspondence and packages up to 150 pounds, including items that require special-handling; e.g., courier service or registered mail.

4.8 Document Control.

4.8.1

Establish and maintain an effective document control filing record for all supporting documentation involving receipts, DLADS transfers, shipments, and internal customer deliveries using a six year and three-month retention period.

4.8.2

Research document control records as requested.

4.9 Precious Metals.

4.9.1

Appoint a Precious Metals Recovery Program (PMRP) Monitor to interact with the PMRP Manager at JBPHH.

4.9.2

Perform unit PMRP responsibilities as identified in and IAW AFI 23-101, Chapter 6, and JBPHH local operating instructions.

4.10 Customer Support.

4.10.1

Perform item research using D043, FED-LOG or successor program to convert part (model) numbered item requests to national stock numbered items, as necessary to properly identify in-use items.

4.10.2

Prepare and submit issue requests through normal Air Force supply channels (ILS-S) managed by the host LRS.

4.10.3

Monitor the status of items ordered through ILS-S and follow up with the host LRS until items are received.

4.10.4

Process requests to establish and maintain current DoD Activity Address Codes to support requisition and shipment transactions IAW AFI 24-230, Maintaining Air Force DoD Activity Address Codes (DODAAC).

4.11 Tool Control.

4.11.1

Appoint a Tool Control Monitor (TCM) to manage the 15SPSS tool control program IAW AFRLI 21-101, Logistics Maintenance Management and 15SPSS SOG 21-01, Tool Control Program.

4.11.2

Act as the single procurement channel for ordering tools approved by designated AF personnel.

4.11.3

Ensure all tools are properly etched and assigned to a Master Inventory List/Composite Tool Kits (CTK) prior to use.

4.11.4

Perform and document 100-percent annual inspection of all site CTKs and track deficiencies to confirm completion of corrective actions. Provide a copy of inspection report to the COR within fifteen (15) calendar days of inspection.

SS-7 Performance Standard

a) Standard: Perform and document 100-percent annual inspection of all site CTKs and track deficiencies to confirm completion of corrective actions. Provide a copy of inspection report to the COR within fifteen (15) calendar days of inspection.

AQL: 90% of the time

4.11.5

Report, investigate and document lost or missing tools.

4.12 Test, Measurement and Diagnostic Equipment.

4.12.1

Appoint a TMDE coordinator NLT fifteen (15) days after the start of the phase-in period to coordinate shipments and manage all TMDE assigned to 15SPSS. The TMDE coordinator must accomplish required TMDE training prior to assuming duties.

4.12.2

Track and process all TMDE for organic and non-organic calibration within prescribed schedule at JBPHH Precision Measurement Equipment Laboratory (PMEL) or approved commercial vendor source IAW the TMDE Master ID Report, TO 00-20-14, Air Force Metrology and Calibration Program, (Section 3) and AFI 21- 113, Air Force Metrology and Calibration (AFMETCAL) Management.

SS-8 Performance Standard

a) Standard: Track and process all TMDE for organic and non-organic calibration within prescribed schedule at JBPHH Precision Measurement Equipment Laboratory (PMEL) or approved commercial vendor source IAW the TMDE Master ID Report, TO 00-20-14, Air Force Metrology and Calibration Program, (Section 3) and AFI 21- 113, Air Force Metrology and Calibration (AFMETCAL) Management.

AQL: 100% of the time

4.12.2.1

Calibration performed by PMEL is covered via support agreement between 15th Wing and 15SPSS.

4.12.2.2

For commercial calibration, the Contractor shall arrange and pay for calibration services with an approved commercial vendor source. See Appendices A12.3 and 28 for additional information.

4.12.3

Comply with the Technical Order (TO) 33K-1-100-2, Test, Measurement, and Diagnostic Equipment (TMDE) Calibration Interval, in the use, care, handling, and transportation of TMDE equipment.

4.12.4

Ensure calibration certificates is kept with equipment.

4.12.5

Verify calibration intervals and requirements for new procurements using the Air Force Calibration Authority Viewer (AFCAV).

4.12.6

Provide physical accountability of all site TMDE, not otherwise tracked in DPAS.

4.12.7

Provide a quarterly listing of all site TMDE requiring commercial calibration to the 15 SPSS Logistics Manager. Data required is TMDE label identifier, make, model number, serial number, commercial calibration vendor source, calibration frequency, date of last/next calibration, calibration costs, tax and shipping charges.

4.13 Vehicle Control.

4.13.1

Appoint a Vehicle Control Officer (VCO), who shall perform VCO duties IAW AFI 24-301, Ground Transportation, AFI 24-302, Vehicle Management and AFMAN 24-306, Operations of Air Force Government Motor Vehicles.

4.13.2

Serve as the liaison between 15SPSS and the host Vehicle Management Flight/Vehicle Operations on matters involving vehicle authorizations, mileage reporting, add-on equipment, unit vehicle inspections and operator licensing requirements.

4.13.3

Coordinate and deliver Government Motor Vehicles (GMVs) for scheduled and unscheduled maintenance with approved vendors, to include the installation and removal of add-on equipment; e.g., mobile radios.

SS-9 Performance Standard

a) Standard: Coordinate and deliver Government Motor Vehicles (GMVs) for scheduled and unscheduled maintenance with approved vendors, to include the installation and removal of add-on equipment; e.g., mobile radios.

AQL: GMVs are delivered to approved vendor within three (3) workdays of notification of mechanical maintenance issues for unscheduled maintenance and within thirty (30) calendar days for scheduled maintenance 100% of the time.

4.13.4

Ensure assigned GMVs are equipped with the necessary forms and accessories for operator use to: inspect, document, operate and otherwise maintain good order of official GMV records. This includes the AF Form 1800, Operator's Inspection Guide and Trouble Report, 15SPSS SOP 24-01, Official GMV Use, GSA Accident Report Kit, GSA credit card, manufacturer-provided owner's manual and accessories, which may include tire gauges, pens, pouches and binders. Refer to Appendix 28 for comprehensive vehicles accessory kit and historical replacement frequency.

4.13.5

Document and update monthly mileage through GSA.

4.13.6

Perform and document semi-annual vehicle inspection of GMV fleet IAW AFI 24-302 and provide results to AF Logistics Manager.

4.13.7

Maintain vehicle lesson plan(s) and provide operator training for special purpose vehicles IAW AFMAN 24-306.

4.13.8

Maintain close rapport with AF Security Forces section, CORs and AF Logistics Manager to determine changes in unit driver status; e.g., revocation or suspension of state-issued driver's license or inability to drive due to physical conditions.

4.13.9

Document and report on suspected cases of vehicle abuse and damage through 15SPSS chain of command and provide assistance with investigation.

4.13.10

Maintain GMVs in a clean and inspection ready condition.

6.0 CIVIL ENGINEERING – PROJECT DESIGN, EXECUTION AND SUPPORT SERVICES

The Contractor shall provide escort, planning, design, management and services in support of the maintenance, repair, demolition and construction of facilities and infrastructure as described herein and IAW all AF Civil Engineering Center (AFCEC) Playbooks.

URL: <https://usaf.dps.mil/teams/10041/ceplaybooks/pages/default.aspx>

The Contractor shall:

6.1 Escort.

Provide escort services for all events to include, but not limited to surveys, inspections, design investigations, sustainment, modifications, repairs, replacements, upgrades, renovations, new construction and demolition projects and events performed on real property regardless of the execution agent. Escorts are required during all phases of the project from feasibility, survey, design, construction and any other escort requirements for the projects. Including the coordination with the visitors and all parts of the visitor notification submission process. Escorts must also be provided for some projects that are not classified real property.

6.2 Project Planning and Design.

Facility and infrastructure projects shall be thoroughly planned, surveyed, designed and engineered to ensure effective use of Air Force real property and equipment in support of the mission. All projects shall be IAW applicable AF title 2 equivalent documents or industry standards when applicable.

6.2.1 Planning.

The contractor's planning efforts shall culminate in a Project Package provided to the Government for review for content. The contractor is fully responsible for the accuracy of the project in meeting the customer's requirements and all Federal, State, and Local codes and requirements. In addition to code all relevant AFIs, AFMANs, and UFCs shall be followed. The NexGen IT Service Request (SR) is the initiating document for each project. The SR is not a "how to" document; it describes "what" the customer is requesting and will not typically include sufficient details to execute the project. The contractor shall accept the SR as the beginning point in their effort to fully develop the requirements and specifications regardless of the SR description provided. The following paragraphs provide a summary of the package requirements.

6.2.1.1 The Contractor Project Manager (PM) shall draft a well-written and detailed description of the project to create the foundation for the SOW. If a requirement requires a design to develop the scope of work, refer to para 6.2.2 on the requirement for a design.

6.2.1.2 The Contractor PM shall meet with CE/User as a kick-off to validate the level of effort, scope, and all specifications for the project delivery and any other special considerations that must be met.

6.2.1.3 The Contractor PM shall create a Statement of Work (SOW) that defines project criteria and specifications within 2 weeks after AF332 is approved by CE. The PM shall consult with Gov't CE/User and functional experts to gather and document details about the project's requirements. Each SOW shall be tailored and include only applicable requirements and specifications for the associated project.

SS-25 Performance Standard

a) Standard: The Contractor PM shall create a Statement of Work (SOW) that defines project criteria and specifications within 2 weeks of project identification.

b) AQL: 95% of the time

6.2.1.3.1 The SOW shall clearly define requirements, communicate expectations, provide a scope, cost, and schedule and serve as the foundation for quality delivery.

6.2.1.3.2 The SOW shall contain sufficient information to accurately define the requirement in terms of functions to be performed, Performance required, and Essential physical characteristics.

6.2.1.3.3

The contractor shall provide all efforts for the requirement as specified in the AF332. The Contractor shall verify site conditions and conduct all surveys, testing, sampling and measurements as necessary to complete the required SOW. These efforts to verify site conditions are included in the FFP of this contract. The Contractor shall provide a SOW including all labor, materials, equipment and any other information necessary to complete the SOW to ensure a complete and usable product.

6.2.2

Design. The Contractor Project Manager (CPM) shall evaluate all project requests; and when necessary, provide a Professional Engineering (PE) design by engineer(s) licensed and registered in the state of Hawaii. All engineering work shall result in a PE stamped design/package and include calculations, when necessary. The design will also include surveys and any other investigations deemed necessary to define the scope of the project. When applicable, the contractor shall receive all RAW CAD files to turn in to the government. The design and required designer's surveys are not included in the FFP portion of the contract.

6.2.3

Deliver Facilities Project package. The CPM shall compile the Facilities Project package; include required attachments, designs, photos, etc., and validate all documents are in the share drive project work control folder. The CPM shall submit the assembled package to CE for approval. The final package shall be a direct reflection of the original SOW and the aforementioned attachments.

6.2.4

Provide written reviews and input for government responses to bidders' technical questions by qualified MBSS subject matter experts in the administration of Government and/or third party awarded contracts.

6.3

Project Execution. The CPM shall perform construction/services coordination for all construction/services projects in alignment with the approved Statement of Work and original Government intent regardless of execution agent IAW the AFCEC Project Execution Playbook, and applicable references in Appendix 4.

6.3.2

The CPM Shall ensure proper sub-contractor management through quality control, surveillance, and contractual obligations assigned from the Project Manager and Prime MBSS contractor.

6.3.2.1

The CPM shall ensure compliance to the approved schedule, that work is quality assured in accordance with all applicable construction clauses, and follow all recommended Project Management Institute (PMI) PMP guidelines.

6.3.3

Within 60 days of project closeout, the contractor shall submit their Letter of acceptance to be reviewed by the Government to ensure proper payments. The Government reserves the right to deny the LOA for uncompleted sow tasks.

SS-26 Performance Standard

a) Standard: LOA must not have mistakes upon first iteration, include all applicable files to include updates to RAW CAD files and meet the 60 day timeline threshold.

b) AQL: 95% of the time.

6.3..3.1

Update Preventive Maintenance (PM) Program. As part of the project closeout process, the contractor shall update maintenance requirements for added, deleted or modified components, equipment, systems, etc., within twenty (20) business days. The contractor shall continue to track projects in the WRRB until PMs, CAD as-builts, or any other required closeout documentation required is completed. Preventative maintenance updates are required in APIMS if applicable, NEXGEN and BUILDER. Preventative Maintenance Closeout guidance from the AFCEC/COOM SharePoint found here shall be followed:

<https://usaf.dps.mil/sites/11252/24048/CO%20Support%20TRIRIGA%20Deploy/TRIRIGA%20Ops%20Wiki/Closeout%20Checklist.aspx>

6.3.3.2

If a project required changes to RP and if applicable the contractor shall create and adhere to AF form 1354.

6.3.5

Configuration Management: Contractor shall maintain a log of configuration settings and maintain close control of system access to ensure settings are only changed by authorized

technicians. All settings shall be according to systems standard configuration manuals, as-built drawings or otherwise referenced in this document and any overrides or changes shall be approved by the site CE office. Systems that require configuration control shall include but not limited to Building Management Controls Systems to include sub-systems such as temperature settings, AHU's, CRAC's, FCU's, dampers, etc; irrigation controls, lighting controls, UPS settings, etc.

6.4

Support Services. Provide a variety of support services as described in the following subparagraphs.

6.4.1

Project Programming Support

6.4.1.1

Provide inputs and support to Government planning of proposed and/or unfunded projects. Information requested may include, but not limited to creation of CAD drawings, CAD concepts, photos, project descriptions, estimated schedules and cost estimations.

6.4.2

Siting/Space management

The contractor shall support the CE lead with CAD updates and applicable program documentation for all siting and spacing requests IAW applicable siting/spacing documents.

6.4.3

Facility Project (FP) Management.

6.4.3.1

Facility Project (FP) management is the local process that defines the life-cycle, workflow and the associated documentation and approvals required for a project. The process begins with creation/generation of a request to the Requirements Section and ends with acceptance of the work by the Government. The process requires effort from CE, MBSS contractor, Contracting Officer, and the COR. See Appendix 33, 15SPSS MBSS Service Request (SR) Process, , for process flow and guidelines.

6.4.3.2

MBSS Line Item Review (LIR).

6.4.3.2.1

LIR meetings are scheduled weekly. The contractor shall present updates on cost, schedule, and performance for all work and projects in-progress as well as updates on the progress of work in planning. Meetings shall be conducted in-person with also a dial-in number and using MS Teams for remote screen sharing.

6.4.3.2.3

The LIR will be chaired by the Site CE or designated representative and the final method of accomplishment decision will be made by the Site CE or designated representative.

6.4.4

Drafting Services. For all CAD services provided under this PWS to include submissions of all RAW CAD files the Contractor shall follow the latest version of the US Army Corps of Engineers A/E/C CAD Standard and A/E/C Graphics Standard located on the Whole Building Design Guide website (wbdg.org). Exception, the contractor shall follow 15 SPSS CE's local guidance for CAD file naming convention and file configuration management.

6.4.4.1

Create, modify, update, and maintain accurate and up-to-date CAD models and CAD record drawing sheet sets that are representative of existing conditions (as-built) of facilities, infrastructure, and leased property for all RP and RPIE for past, present, and future projects to include contracted and subcontracted work. Facility as- builds must be updated within 60 days of beneficial occupancy after facility as-built baselining is completed or if facility as-builts are not baselined, then submit project as-builts of work accomplished in 60 days. Project as-builts for projects including mission critical and life health safety components must be submitted prior to beneficial occupancy.

SS-27 Performance Standard

a) Standard: Facility as-builts must be updated within 60 days of beneficial occupancy after facility as-built baselining is completed or if facility as-builts are not baselined, then submit project as-builts of work accomplished in 60 days.

b) AQL: 90% of the time.

SS-28 Performance Standard

a) Standard: Project as-builts for projects including mission critical and life health safety components must be submitted prior to beneficial occupancy.

b) AQL: 95% of the time.

6.4.4.2

Baseline all CAD drawings for the site by end of contract. This will include a comprehensive survey of the facilities, land and utilities and old project documentation to the level appropriate for building accurate as-builts of all the facilities, utilities and land. A progress/milestone meeting will be held semi-annually to track progress.

Deliverable

CDRL G001 Baseline CAD As-Builts

6.4.4.3

Create new CAD models in cases where previous reference drawings (electronic & hardcopy) do not exist to support the functional needs of CE by performing field work to gather required model data and measurements.

6.4.4.4

Create standardized as-built CAD sheet sets and plot files to accurately produce prints with accurate line weights and colors to support the routine functional needs of CE. Sheet sets include but are not limited to:

Site plans Floor Plans Roof Plans Utility Plans Irrigation Plans

Landscape Plans Pavements Plans Fire Alarm Plans Storm Water Plans Site Security Plans
Facility HVAC Plans

Custodial Floor Plans Electrical Single-lines Facility Lighting Plans Facility Controls Plans
Facility Security Plans Facility Electrical Plans Facility Plumbing Plans Fire Sprinkler
System Plans

Designated Tobacco Area Plans Facility Emergency Lighting Plans Facility Evacuation & Rally Point Plans

Chilled Water Systems and Process Water Loops

6.4.4.5

Create standardized CAD drawing file templates with pre-defined aspects including layer standards, plot configurations, annotation styles, etc., as defined by CE.

6.4.4.6

Create new CAD models and drawing sets that accurately represent conceptual ideas and plans for RP and Building Equipment (BE) or Asset Record modifications, upgrades, and construction as requested by CE and/or to support planning of Work Tasks (WT) and Facility Projects (FP). These new drawings are often in support of Government planning efforts and may require several revisions/iterations to reach a final concept and may require changes over time to reflect updates/modifications from the Government's planning activities.

6.4.4.7

Create new CAD models from pre-existing CAD models by altering, updating, merging, or transferring data to a new accurate as-built model of RP and Building Equipment (BE) or Asset Record.

6.4.4.8

Validate accuracy of CAD models by accomplishing thorough detailed field verifications and measurements. Validate model accuracy by cross referencing or utilizing previously verified and historically known accurate as-built models and data sets.

6.4.4.9

Scan paper/hardcopy drawing sets to discernible, high-resolution electronic Adobe PDF format. While handling "paper only" drawing sets, the contractor shall exercise concerted care to prevent damage or deterioration of these mission critical records. When details of these scanned drawing sets are not discernible on the PDFs the contractor shall create supplemental CAD models/drawings to capture the undiscernible details and attach/correlate the models/drawings to the PDF copies.

6.4.4.10

Facility records drawings for all real property and Building Equipment (BE) or Asset Record, including a master index of drawings, are updated to include new or changed conditions within sixty (60) days of completion of work.

6.4.4.11

CAD models and as-built record drawings (hard copy and electronic) are maintained and stored on the Government's network CAD repository and on-site hard copy repository. Follow CE's CAD file structure and file naming conventions. The management of the CAD repository and the accuracy of the data within is the responsibility of the Contractor.

6.4.4.12

Basic CAD Requirements.

6.4.4.12.1

The digital representation of the common boundaries for all geometric features shall be exactly the same, regardless of feature layer. Each feature within a feature class shall be represented by a single graphic element (e.g., polygon, line, or point).

6.4.4.12.2

Lines, which represent the same graphic element, shall be continuous (i.e., not broken or segmented), unless that segmentation reflects a specific visual line type. Lines representing the same type of data shall not cross except at intersections.

6.4.4.12.3

Polygons shall be closed (i.e., the first x- and y-coordinates shall exactly match the last x- and y-coordinates). Polygons of the same layer shall not overlap and shall cover the area of interest completely (i.e., have no gaps in coverage).

6.4.4.12.4

Straight lines shall be represented by only the beginning and ending x- and y coordinate points. Line strings shall not cross back on themselves or be of zero length.

6.4.4.13

Record Drawing (as-built) Delivery Format.

6.4.4.13.1

No deviations from the government's established standards shall be permitted unless prior written approval of such deviation has been issued by the government.

6.4.4.13.2

The following procedures shall be performed before a file is placed on the delivery media:

6.4.4.13.2.1 Include all files, both graphic and non-graphic, required for the project.

6.4.4.13.2.2

Make sure all files are in the same directory, and that references to those files do not include device or directory specifications.

6.4.4.13.2.3

Ensure all reference (external reference) files are attached and without device or directory specifications.

6.4.4.13.2.4

Remove all extraneous graphics/text outside the project border area and set the active parameters to a standard setting (or the setting contained in the seed or prototype file).

6.4.4.13.2.5

Include any standards sheets (abbreviations, symbols libraries, font libraries, color tables, pen tables, plot configuration files, user command files, etc.) necessary for a complete project.

7.0 CIVIL ENGINEERING – FACILITY OPERATIONS AND MAINTENANCE

The Contractor shall operate and maintain real property (RP), utilities, Building Equipment (BE) or Asset Record and infrastructure as delineated in the PWS sections below. With the exception of Over and Above projects covered under PWS Section 6.0 and unless specifically specified by the COR, all of this section's work is executed through the firm fixed price CLIN X002 as this work is regularly scheduled, anticipated, and reasonably accountable. This includes materials, labor, and other direct costs (ODCs)

7.1 Operations, Maintenance and Repair.

The Contractor shall:

7.1.1 Real Property (RP) Facilities, BE or Asset Record, infrastructure, and utilities are operated, maintained and repaired.

7.1.2 Mission-essential RP/BE is operated and maintained to ensure maximum operational availability. CDRL A013 Quarterly Log of Mission Critical Equipment Downtime shall be submitted to COR on a quarterly basis using excel spreadsheet and shall contain the following information:

Complete list of all mission essential RP/BE that has had an outage, inoperable period, and reason for inoperable periods. A listing of mission-essential system/equipment is provided in Appendix 6.

Deliverable

CDRL G002 Quarterly Log of Mission Critical Equipment Downtime

CDRL G003 System Narrative and Outages Report for each Mission-essential RP/BE

7.1.3 Configuration changes to any RP/BE or Asset Record is unacceptable without prior CE approval. A plan for all new work must be presented for CE approval. The contractor shall not take license to make any changes or modifications to Government facilities or RP/BE or Asset Record without CE approval.

7.1.4 The complete BUILDER database shall be baselined to determine the existing conditions within 6 months after the end of the phase-in period. After baselining, BUILDER data shall be maintained to ensure RP, facility, BE or Asset Record and infrastructure changes made are added to the baseline. Builder Remote Entry Database (BRED) including remote tablet hardware requirements shall be implemented to report BUILDER findings back into the BUILDER database.

7.1.5 Contractor shall conduct a Facility Condition Assessment (FCA) on a schedule consistent with AFCEC standard frequency, each facility requires an FCA assessment once every 5 years, using the US Army Corps of Engineers (USACE) Construction Engineering Research Laboratory (CERL) Builder SMS methodology. Inventory input shall be carried out for systems to ASTM-E1557-09 Uniformat II, Level 4 system detail with specific equipment information input in the BUILDER "section details" dialogue box. BUILDER data shall be 90% maintained to include updating assessments upon conclusion of maintenance/repair actions. The contractor shall perform the Facility Condition Assessment (FCA) with in-house manpower.

SS-29 Performance Standard

a) Standard: Contractor shall conduct a Facility Condition Assessment (FCA) annually using the US Army Corps of Engineers (USACE) Construction Engineering Research Laboratory (CERL) Builder SMS methodology.

AQL: FCA is completed annually and BUILDER database is 90% accurately maintained.

7.1.6 NexGen IT or its successor shall be used to execute a Preventive Maintenance (PM) Program to prevent deterioration of RP, facilities, BE or Asset Record and infrastructure beyond normal wear and tear IAW AFI 32-1001. PM is given priority over routine WTs and FPs during scheduling of the in-service work plan (IWP).

7.1.7 NexGen IT shall be used to manage repair, construction, demolition, etc. and unscheduled maintenance of real property IAW AFI 32-1001. This shall include NexGen IT Service Requests (SR). Obtain and maintain NexGen IT accounts and applicable NexGen IT roles for Requirements Section personnel, maintenance personnel, Project Managers, etc., within fifteen (15) days of the start of the transition period.

7.1.8 The Tracer ES building automation system at MSSC and the Johnson Controls Facility Explorer building automation system in Bldg. 550 shall be used to operate and manage facility support systems. If the automation systems are changed re-configured or moved to a different server, the new system will be in scope of this contract. Perform programming and configuration changes to the building automation systems to support mission requirements, as needed and/or requested. Provide electronic/softcopy history reports and trend logs in multiple formats such as graphs, charts, and tables for all points to CE on an as requested basis. Configure the building automation system to send SMS notifications to MBSS personnel for equipment malfunctions or system conditions that require immediate technician response, including non-business hours. Maintain, repair and update the building automation and control systems (or successor systems) and their components, to include recurring software updates, software upgrades as required by the manufacturer, ensuring software license is current and the server that it is operated on meets AF requirements for servers. Implement and maintain an approval process and tracking method to control access to system server for administration and operational functions. Create and/or update the building automation system architecture CAD models to mirror as-built conditions. All modifications to the system and components must meet Air Force Information Assurance requirements and be approved by the 15SPSS CIO.

7.1.9 Provide an equipment failure report to the Site CE or designated representative on all equipment where the replacement cost, including labor, is valued over \$50,000 for each instance of premature catastrophic failure. The report shall include the preventative

maintenance performed, warranty expiration date (if any), equipment expected life, date of equipment installation, date of equipment failure, and explanation for failure. Reports must be provided within five (5) business days of failure/incident. Provide a corrective action report for all primary support system repairs (HVAC, Electrical, Plumbing, Fire Protection, etc.) that occur due to an operational failure of systems or components. Corrective action template is provided by CE and located on shared drive.

7.1.10 Maintenance and Repair work shall not disrupt utilities to occupied areas and other facilities unless previously coordinated with the Base Civil Engineering (BCE) Work Clearance Request, AF Form 103 process and approved by CE/Users.

7.1.11 Coordinate and disseminate all site AF 103's to ensure all impacts are communicated to the site populace. This includes attendance of various site wide coordination meetings to include the Monday deconflict meeting. The Base Civil Engineering (BCE) Work Clearance Request (AF Form 103) shall be used for any work (contract, third-party contracts, or in-house) that may disrupt vehicular traffic flow, base utility services, protection provided by fire and intrusion-detection alarm systems, or routine activities of the installation. Work Clearance Requests AF 103 also applies to all excavation or disruption that may affect concealed utilities. Approval of the AF Form 103 will be provided by the Site CE or designated representative. Approved permits are only valid for thirty (30) days prior to project start. All permits are maintained on the Installation Support shared drive for a minimum of two (2) years or until the project is complete. Once a project is complete, the AF Form 103 will be moved to the appropriate folder on the Installation Support Drive for completed projects.

7.1.12 The contractor shall provide qualified subject matter experts to troubleshoot malfunctions of RP, Building Equipment (BE) or Asset Record and systems and shall be included within the firm-fixed price of this contract. Troubleshooting malfunctions of equipment and systems shall be a predecessor to any repair Over & Above Facility Project (FP) Proposals. Troubleshooting shall continue until the effort results in a conclusive root cause of the malfunction. The troubleshooting analysis shall be included and explained in detail as part of the Over & Above Facility Project (FP) repair proposal. The MBSS contractor shall be responsible for all troubleshooting costs for malfunctions of existing Building Equipment (BE) and systems within the scope of this contract, regardless if they have in-house subject matter experts or not. The cost of troubleshooting (either in-house or contracted) is included in the FFP of this contract and is not subject to the micro purchase threshold determinations. Troubleshooting occurs before an in-house/DSW/FP determination is made in the IWP meeting. If for some reason (sometimes during an emergency when troubleshooting happens simultaneously as

executing a repair) troubleshooting is performed during the execution of an in-house, DSW or FP, that cost of troubleshooting shall be removed from the cost of the execution.

7.2 Preventative Maintenance (PM) Program.

7.2.1 Maintain a comprehensive PM Program that establishes priorities and categories for all preventative maintenance tasks IAW AFI 32-1001 and AFCEC Preventative Maintenance Playbook. Perform preventative maintenance as specified by the Preventative Maintenance Task List (PMTL) in NexGen IT. Procedure will be as approved by AFCEC or as specified by the current RS MEANS or local supplement PMTL if AFCEC procedures do not exist. Current PM equipment list is provided in Appendix 26 as the baseline for PM however, this list shall not be used as a basis of scope. Within 3 months after the end of the phase-in period, the complete maintenance Preventative Maintenance, PM PMTL and Work Task (WT) data shall be loaded into NEXGEN IT. All alibis must be approved by the COR prior to schedule modification. Alibi's will be identified with sufficient notice before the work is planned and a thorough get-well plan shall be provided. Preventative maintenance shall be performed on all existing and newly installed real property and existing and newly installed non-real property referenced in this document.

SS-30 Performance Standard

a) Standard: Perform PMs as specified by the Preventative Maintenance Task List (PMTL) in NexGen IT

within the scheduled frequency.

AQL: 95% of the time.

Deliverable

CDRL G004 Baseline Nexgen Data

7.2.2 Ensure that all Building Equipment (BE) or Asset Record and systems are maintained to sustain an operational capability unless otherwise directed by the Site CE. Recommendations for changes to level of maintenance to ensure the appropriate asset life-cycle cost per the (Preventative Maintenance) PM Playbook may be submitted to the Site CE for review and approval.

7.2.3 Changes to PM frequencies, schedules, and equipment additions and deletions will be approved by the Site CE or designated representative prior to implementation. Update the NexGen IT PM requirements to match/reflect all changes in RP, BE or Asset Record inventory.

7.2.4 Provide a monthly report that specifies the on-time completion rate by shop for all PM.

7.2.5 Provide an annual review of the PM Program using the AFCEC PM Playbook as a guide for evaluating PM investment and developing a balanced PM schedule. Changes must be coordinated and approved by the CE section.

7.3 Requirements Section.

7.3.1 A Civil Engineering (CE) Requirements Section function shall be provided to support CE Service Requests (SR) requests, service calls, Work Tasks (WT), Facilities Projects (FP) (Covered in PWS Section 6.0), and inquires on all CE work requests IAW AFI 32-1001 and AF CE Work Management Playbook.

7.3.2 Maintain a physical presence M-F during standard business hours, as defined in Appendix 3, and an “on-call” capability during non-business hours for customer support and response to emergencies. All non-business hour calls for support shall be answered on first attempt. The contractor shall be prepared for immediate dispatch of technician support, for non-business hour requirements with subject matter expertise commensurate to the emergency situation or condition per coordination with the COR. Maintain daily presence during prescribed business hours at 550 & MSSC in order to respond to emergency and urgent WTs at these facilities and RME. The contractor shall observe the standard federal holiday schedule as well. Business hours and holiday schedule are listed in Appendix 3.

7.3.3 Service Requests (SR) for CE work are assigned one (1) of the following classifications:

Work Task (WT) and Facility Project (FP); as defined in Table 7.1: CE Work Categories. Prior to CE Work Category being chosen, contractor shall develop estimate for hours and cost of execution. If troubleshooting needs to take place to develop the estimate for hours and cost, the cost of troubleshooting shall not be added to the overall cost of execution and the cost of troubleshooting is included in the FFP of the contract. Once execution path is chosen, work will be executed in the chosen manner unless there is scope change that exceeds the category threshold.

TABLE 7.1 – CE WORK CATEGORIES

<u>TITLE</u>	<u>DEFINITION</u>	<u>Labor Hours</u>	<u>Material Value</u>
Work Task (WT)	RP, BE or Asset Record maintenance or repair, including repair by replacement. Does not require detailed planning. These work tasks are small and require less than 50 man-hours. Direct scheduled work is immediate or routine and can be maintenance, repair, or minor construction not requiring capitalization.	Less than 50	\$10,000 Commodities/ \$2,500 Services/ \$2,000 Construction
Facility Project (FP) (Over and Above) Covered in PWS Section 6.)	RP, BE or Asset Record, repair, and minor construction including repair by replacement, and/or new facility requirements that may require capitalization	Greater than 50	Greater than amounts listed above

7.3.4 For Service Requests (SR) in support of Core Communications, SRs are assigned one (1) of the following classifications: Work Task (WT) and Facility Project (FP); as defined in Table 7.2: Core Comm Work Categories. Prior to the Core Comm Work Category being chosen, contractor shall develop estimate for hours and cost of execution. If troubleshooting needs to take place to develop the estimate for hours and cost, the cost of troubleshooting shall not be added to the overall cost of execution and the cost of troubleshooting is included in the FFP of the contract. Once execution path is chosen, work will be executed in the chosen manner unless there is scope change that exceeds the category threshold.

7.3.4.1 Over and Above (O&A) (see FP in Table 7.1 & 7.2 above): Typically unplanned work that the Government determined is not a part of the firm fixed price of this contract due to unforeseen predictability, not regularly anticipated, nor reasonably accountability. In coordination with the CO, the COR evaluates the primary requirement to determine which respective value factor the requirement will follow per FAR 2.101. The Government reserves the right to perform O&A work with Air Force in-house resources, third party Contractors, or award it to the MBSS Contractor. The Government also reserves the right to not perform the work until a later date. All O&A planned work shall be submitted via the NexGen IT/AF Form 332 process IAW AFI 32-1001, AFCEC WM Playbook and section 6.6 of the PWS.

7.3.4.2 Repair versus Maintenance: Repair is defined as restoring to a good or sound condition after decay or damage. Maintenance is defined as keeping in an appropriate condition, operation, or force.

7.3.5 Maintain records using the AF Form 1081 BCE Work Request/Work Order Register for CE work requests submitted via NexGen IT Service Request (SR) along with their supporting documentation for each associated WT or FP resulting from the request for a minimum of five (5) years. Current WT and FP status shall be updated on the AF Form 1081 prior to the WRRB. Projects that are transitioned to FP must be shown on the next available weekly 1081 form.

SS-31 Performance Standard

a) Standard: Current WT and FP status shall be updated on the AF Form 1081 prior to the WRRB.

AQL: 100% of the time

7.3.6 The Contractor shall submit a proposal package for each FP (to the CO within the timeframe specified). The Contractor must obtain competition to the maximum extent practicable for all subcontracted work. The Contractor must solicit a competitive quotation from at least three (3) independently competing firms. The request for quotations must, to the maximum extent practical, solicit from different manufacturers or producers. If the Contractor is unable to obtain quotes for competing items from three (3) or more independently competing firms, the Contractor is required to seek out an alternative method for price comparison. There are a variety of ways the Contractor can achieve this:

- Cost estimating programs such as RSmeans/eGordian/E4Clicks for materials and job costs. RS MEANS cost books/software to be provided by the government if required.
- Davis-Bacon wage rates.
- Service Contract Act labor categories can be found on the Department of Labor website.

- Material costs and items that are only available from one (1) on-island vendor can be compared to costs from the mainland and inflated according to shipping.

Substantiated document trail is required to demonstrate due diligence in obtaining a minimum of 3 quotes. The following price reasonableness and documentation requirements are applicable to all purchases, regardless of dollar value:

- A price is reasonable if it does not exceed a price incurred by a prudent person in the conduct of competitive business. The CO will examine the prices with particular care in connection with FPs that may not be subject to effective competition restraints. The Contractor's price will not be presumed to be reasonable. If an initial review of the facts results in a challenge of a specific price by the CO or the COR, the burden of proof must be upon the Contractor to establish that the price is reasonable under the standards of FAR subpart 15.4 and FAR 31.201-3. Price quotes for supplies must be broken down by individual items, shipping costs, and any other included expenses. Price quotes for subcontracted services which are not pre-priced in the contract must include labor hours and costs or prices as applicable, including the total price of the job, individual pricing for portions of the work, if applicable, materials, and all other elements of cost, overhead, and profit. This price breakdown documentation must be made for each subcontractor performing work on FPs. See appendix 33 for competitive proposal process.

7.3.7 Upon initiation of a NexGen IT Service Request (SR), ensure the customer and facility manager are provided a tracking number, status information, and work schedules. All work is tracked until completion. Record the total actual material and labor cost information in NexGen IT for all Work Tasks (WT), and Facility Projects (FP).

7.3.7.1 Process existing Service Request (SR) change orders and cancellations IAW AFI 32-1001 and AFCEC Work Management Playbook.

7.3.8 WT is accomplished in the priority order as defined by in Table 7.2. Note: Preventative Maintenance (PM) Program requirements have priority over routine WT and Facility Projects. Definitions of work priority categories can be found in AFI 32-1001.

TABLE 7.2 – WORK PRIORITIES and TYPES

<u>Work Priority</u>	<u>Work Type</u>
1	Emergency Work
2A	Preventative Maintenance (PM and Physical Plant Operations)
2B	Contingency Projects
3A (High)	Scheduled Sustainment Work (Corrective Maintenance (CM))
3B (Medium)	Scheduled Sustainment Work (CM)
3C (LOW)	Scheduled Sustainment Work (CM)
4A	Scheduled Enhancement Work
4B	All other Enhancement work

7.3.9 Receive requests via telephone, in-person, or email.

7.3.10 Emergency requests shall be responded to by the contractor and acknowledged twenty-four (24) hours a day seven (7) days a week. Conditions that degrade the mission or reduce operational effectiveness are responded to immediately and corrected as soon as possible with coordination from the COR, within prescribed timelines once parts arrive.

7.3.10.1 During normal business hours, the contractor shall be onsite at MSSC, RME, and Facility 550 within 15 minutes of notification.

7.3.10.2 During non-business hours, the contractor shall be onsite at MSSC, RME, and Facility 550 within 3 hours of notification.

7.3.10.3 Emergency WT shall be completed or stabilized and materials on order within 24 hours of notification.

7.3.11 Notify the Site CE or Designated Representative immediately upon discovery of all emergencies. Provide response status, (i.e., “technician has been dispatched and is in route”). Provide an estimated time of arrival and follow up with periodic updates.

7.3.12 Receive 3A corrective maintenance requests and correct conditions within seven (7) days; or order materials within forty-eight (48) hours and correct repairs within seven (7) days of receipt of materials. Metrics showing compliance to this paragraph shall be submitted and discussed on a weekly basis in the IWP meeting. If non-compliant, a clear concise justification shall be provided for each task out of compliance.

7.3.13 Receive 3C corrective maintenance requests and correct conditions within thirty (30) days. If non-stock material is required, it shall be ordered within fourteen (14) days and the work shall be completed within thirty (30) days of receipt of material. 3C shall not be consolidated for the purpose of converting them into a planned work order. Coordinate Work Tasks (WT) and inspections with the facility manager. All WT will be prioritized by the Requirements Section and/or the Site CE or designated representative. Metrics showing compliance to this paragraph shall be submitted and discussed on a weekly basis in the IWP meeting. If non-compliant, a clear concise justification shall be provided for each task out of compliance.

7.3.14 Summary workload data regarding corrective maintenance and requests and actions is maintained and provided to the Site CE. Summary data shall include WT volume of work by category and completion rate by shop. Summary workload data will be provided and reviewed with the government quarterly.

7.4 In-service Work Plan (IWP).

7.4.1 A weekly In-service Work Plan (IWP) is developed and maintained for a rolling three-month period utilizing the NexGen IT or other approved method/system. The IWP shall include PM Program, WTs, and FPs, along with a list of all open WTs and FPs for review and possible reprioritization within the IWP. The IWP shall identify total hours of PM by shop scheduled on a weekly basis for the plan period. The initial IWP shall be provided to the Site CE for review and coordination NLT thirty (30) days after the start of the phase-in period.

Deliverable

CDRL G005 In-service Work Plan

7.4.2 Preventative Maintenance (PM) Program requirements are programmed in the In-Service Work Plan.

7.4.3 Preventative Maintenance (PM) Program requirements have precedence over all other work except emergency work.

7.4.4 The three-month plan shall be available electronically for review by the government at all times.

Deliverable

CDRL G005 In-service Work Plan

7.4.5 Facility Project (FP) approved and prioritized by the WRRB are programmed in the In-Service Work Plan.

7.4.6 Coordinate with the Site CE or designated representative for approval prior to removing mission-essential systems/equipment from service for any reason.

7.5 Reserved.

7.6 Heating and Cooling.

7.6.1 Heating and cooling components and distribution systems are operated and maintained. Maintenance is performed IAW manufacturer's technical manuals and warranties per PMTL. Document all maintenance actions.

7.6.2 Mission areas are heated, cooled and humidity controlled to sustain mission requirements.

7.6.3 All heating and cooling set points shall be approved by the Site CE or designated representative.

7.7 Electrical.

7.7.1 Electrical systems, lighting, and installed appliances are maintained to ensure safe operation and stable power distribution. Document discrepancies with electrical systems and recommend solutions. All employees must follow safe electrical practices IAW UFC 3-560-01 Operation and Maintenance: Electrical Safety and AFMAN 32-1065 Grounding and Electrical Systems.

7.7.2 Detailed up-to-date and accurate electrical one-lines and panel schedules are posted in main electrical distribution rooms/areas IAW AFMAN 32-1062 Electrical Systems, Power Plants and Generators.

7.7.3 Emergency generators are operated, maintained and repaired. Maintenance is performed IAW manufacturer's technical manuals and warranties per PMTL. Maintain maintenance actions records on the share drive.

7.7.4 Up-to-date step-by-step operating procedures for electrical generating equipment shall be maintained and readily available.

7.7.5 AF Form 719, Historical Record, is maintained for the life of the generator IAW AFI 32-1062. Records shall be maintained and stored on the Installation Support shared drive.

7.7.6 Generators are exercised under actual facility load each month IAW AFMAN 32-1062.

7.7.7 Generator readings are entered on AF Form 487 Emergency Generator Operating Log, and forms are maintained for three (3) years and stored on the Installation Support shared drive. Generator operating hours shall be tracked, recorded, and provided to the Site CE.

7.7.8 Site CE or designated representative shall be notified immediately of utility outages and status updates are provided periodically. Power glitch checklists, Appendix 24, shall be performed and records shall be maintained and stored on the Installation Support shared drive.

7.7.9 Electrical power distribution systems and associated equipment, from point of origin to point of use, shall be maintained IAW NFPA 70 National Electric Code (NEC). Document maintenance actions in NEXGEN IT.

7.7.10 Identify electrical switchgear and connections that need to be scheduled for a thermographic scan IAW manufacturer's recommendations. Perform thermographic scans on required systems and note any deficiencies. All deficiencies shall be corrected.

7.7.11 Work on or near energized electrical equipment is prohibited except in circumstances when justified and approved by the Site CE. An AF Form 269, Electrical Facilities Safe Clearance, must be submitted to the 15SPSS Safety Officer and the Site CE and approved prior to the start of any work. All workers will be thoroughly familiar and comply with safe clearance procedures IAW NFPA 70E Standard for Electrical Safety in the Workplace, DAFMAN 91-203 Air Force Occupational Safety, Fire, and Health Standards, and posted materials at the job location before starting work.

7.8 Grounding and Lightning Protection System (LPS). Maintain, test and repair the grounding and LPS as required IAW AFMAN 32-1065 Grounding and Electrical Systems and NFPA 780 Standard for Installation of Lightning Protection Systems. Inspect the LPS at required intervals IAW PMTL.

7.9 Power Conditioning and Continuation Interfacing Equipment (PCCIE). PCCIE must be operated and maintained IAW manufacturer's instructions to accommodate mission requirements per PMTL. A listing of PCCIE is provided in Appendix 31.

7.10 Lift Equipment.

7.10.1 Operate, maintain, repair, and test elevator systems and passenger and heavy-lift inclinator systems IAW ASME A17.1/CSA B44, Handbook on Safety Code for Elevators and Escalators, and ASME A17.7/CSA B44.7, Performance-Based Safety Code for Elevators and Escalators per PMTL.

7.10.2 Perform all required recurring maintenance and testing of elevators and inclinator. Records shall be readily available. All records and documentation remain Government property.

7.10.3 Elevators and inclinators shall be kept in an operational condition to meet mission requirements.

7.10.4 Operate, maintain, repair, test, and certify on-site cranes systems, chain hoists, and winches IAW DAFMAN 91-203 Air Force Occupational Safety, Fire, and Health Standards, and manufacturer requirements.

7.10.5 Required recurring maintenance, testing, and certifications of crane systems, chain hoists, and winches are scheduled and completed. Records shall be maintained on the Installation Support shared drive. All records and documentation remain as Government property.

7.10.6 Crane systems, chain hoists, and winches shall be kept in an operational condition to meet mission requirements.

7.11 Unfired Pressure Vessels. Inspect unfired pressure vessels that meet pressure and volume levels specified in AFMAN 32-1068 Heating Systems and Unfired Pressure Vessels every 3 years IAW AFMAN 32-1068. See Appendix 18 for list of unfired pressure vessels.

7.12 Refrigerant Management.

7.12.1 Manage refrigerant and refrigerant equipment IAW AFMAN 32-7002 Environmental Compliance and Pollution Prevention.

7.12.2 Up-to-date service records are maintained for the past three years on all equipment with refrigerant charges greater than 50 lbs. Records indicate type of service, quantity of refrigerant added, and leakage rate as prescribed by AFMAN 32-7002 Environmental Compliance and Pollution Prevention.

7.12.3 Refrigerant equipment leaks on equipment greater than 50 lbs. that exceeds 15% of the equipment charge shall be repaired within 30 days IAW section 114 of the Clean Air Act and AFMAN 32-7002 Environmental Compliance and Pollution Prevention.

7.12.4 Records shall be maintained indicating the type of equipment used to recover, recycle, or reclaim refrigerants contained in appliances during the service.

7.12.5 Maintenance, repair, or disposal of any appliances is tested IAW AFMAN 32-7002 Environmental Compliance and Pollution Prevention.

7.12.6 Copies of technician EPA certifications to service CFC and HCFC equipment shall be readily available IAW AFMAN 32-7002 Environmental Compliance and Pollution Prevention.

7.12.7 Records shall be maintained showing a complete inventory and maintenance history of all HVAC equipment IAW AFMAN 32-7002 Environmental Compliance and Pollution Prevention.

7.12.8 Provide copies of all service invoices for any service, maintenance, repair or disposal performed on appliances at the facilities IAW AF- Refrigerant Management Handbook and section 114 of Clean Air Act § 601-618; 42 USC§ 7671-7671q.

7.13 Fire Safety.

7.13.1 Ensure fire evacuation routes are clear at all times. Create and post up-to-date facility maps with evacuation routes, fire extinguisher locations, and rally points.

7.13.2 Personnel shall complete government provided fire extinguisher training within thirty (30) days of the start of the transition period and annually thereafter.

7.13.3 Provide fire extinguishers throughout the site and record monthly inspection on xtinguishers

7.13.4 Perform monthly testing to ensure fire pumps start instantly with 100% reliability. All fire pump flow tests must be scheduled with Site CE or designated representative. All pump test records shall be provided to the Site CE and maintained for five (5) years.

7.13.5 Inspect, test, maintain, and repair fire alarm, detection and suppression systems (including the system of fire pumps and underground water mains) to ensure they are operational and able to protect the site personnel and resources. Fire alarm detection and suppression systems are maintained IAW UFC 3-601-02 Fire Protection Systems Inspection, Testing, and Maintenance, NFPA 72 National Fire Alarm Code, NFPA 25 Inspection Testing and Maintenance of Water Based Fire Protection Systems, NFPA 24 Standard for the Installation of Private Fire Service Mains and their Appurtenances, NFPA 20 Standard for the Installation of Stationary Pumps for Fire Protection, NFPA 2001 Clean Agent Fire Extinguishing Systems, and NFPA 17 Standard for Dry Chemical Extinguishing Systems. Maintenance is performed IAW manufacturer's technical manuals and warranties per PMTL.

7.13.6 Maintain detailed records of all maintenance and testing in NEXGEN and/or the Installation Support shared drive.

7.13.7 Operational availability of detection and suppression systems is maintained at 100% on a monthly basis to prevent false alarms due to lack of maintenance. Any system impairments will be handled IAW UFC 3-601-02.

7.13.8 Respond to requests for fire alarm support from 15SPSS Security Forces (SF), Site CE, or designated representative.

7.13.9 Coordinate alarm system maintenance and test activities with SF, facility managers, and Site CE or designated representative. Ensure Central Station monitored systems are placed in test mode when potential for accidental alarm initiation is present from work activity. Advise SF

when systems are in test mode. Ensure Central Station monitored systems are removed from test mode as soon as appropriate.

7.13.10 Support annual Government Fire Department led facilities inspections for fire safety.

7.13.11 Fire-safety hazards and deficiencies are corrected as quickly as possible and IAW AFI 32-10141 Planning and Programming Fire Safety Deficiency Correction Projects. Notify the Site CE of all fire hazards within one (1) business day of initial identification. For hazards or deficiencies that are outside the maintenance responsibility of the Contractor, make special note to the Site CE or designated representative. Resolution of hazards and deficiencies are tracked and documented.

7.13.12 Submit AF Form 592, USAF Hot Work Permit, for welding, cutting, and brazing operations to the Site CE for approval. Maintain an electronic log of all issued AF Form 592s on the Installation Support shared drive. Operations shall be inspected to ensure fire-safe practices are being observed. If unsafe practices are observed or identified, suspend operations until fire safety hazards and/or deficiencies are corrected, and the Site CE or designated representative is notified.

7.13.13 Hand-held fire extinguishers shall meet facility requirements IAW NFPA 10, Standard for Handheld Fire Extinguisher. Extinguishers shall be maintained, tested, operated, and replaced IAW NFPA 10 and manufacturer's recommendations. Document maintenance actions.

7.14 Potable Water.

7.14.1 Implement, execute, and maintain the 15SPSS water operating instruction (OI) document.

Deliverable: CDRL A0052 Water OI. Operate, maintain, and repair potable water treatment and distributions systems at MSSC and RME IAW DAFMAN 32-1067, Water and Fuel Systems. Potable water is continuously available to meet mission requirements.

7.14.2 CDRL A052 Water Operating Instruction (OI)

7.14.3 Water deliveries shall be scheduled and performed in order to preclude water levels falling below the minimum water levels necessary for facility operations and fire suppression. Monitor meter readings during deliveries and maintain a meter log on the government Installation Support shared drive. Minimum water level for the MSSC potable water tank is 60,000 gallons. Minimum water level for the RME tank is 400 gallons.

7.14.3.1 The water tanker used shall have a Water Tank Certification IAW Hawaii Administrative Rules (HAR) 11-20-31. No lapse in certification and provide new cert. annually. This certification will be accessible to the Government upon request.

7.14.3.2 Water point of connection is a 3-inch male camlock. A food grade pump is required when transferring water.

7.14.3.3 The water supplier will need their own Haleakalā National Park permit. The water supplier's truck shall be inspected before each visit by the Department of the Air Force Civilian Police (DAF CP).

7.14.3.4 The key to the camlock at the summit will be kept in the Alternate Base Defense Operations Center (ABDOC) with Security Forces and the key to the camlock at RME will be kept in the RME key box. During working hours, the subcontractor will sign out the key from the ABDOC prior to water delivery and have it returned to ABDOC upon completion. During non-working hours, Security Forces will issue the key to the subcontractor at time of vehicle inspection with instructions for the subcontractor to return the key to ABDOC upon completion.

7.14.4 Detailed maintenance and repair records are maintained for each major piece of equipment in the water supply and distribution system.

7.14.5 All control valves on water mains are exercised twice a year. Records are maintained.

7.14.6 Water storage tanks are inspected as required IAW UFC 3-230-02, O&M - Water Supply Systems, paragraph 2.1.4.

7.14.7 Water tanks are cleaned every three (3) years as prescribed by UFC 3-230-02, Table 10-14. Supply a backup water supply while the tanks are being cleaned to ensure continuous fire suppression support.

7.14.8 Water is tested per DAFMAN 32-1067 and 15SPSS AFRL Operating Instruction (OI) 32-1067 to ensure water is safe.

7.14.9 Unsafe potable water containing elements outside of established standards is reported to the Site CE or designated representative immediately. The contractor shall take corrective actions, IAW 15SPSS AFRL OI 32-1067, to ensure the safety of all personnel.

7.14.10 Suspected consumption of unsafe potable water containing elements outside of established standards is reported to the Site CE or designated representative immediately.

7.14.11 Hydrant flow tests are conducted every year and after system repairs or modifications IAW UFC 3-230-02. All hydrant flow tests must be scheduled with Site CE or designated representatives. Results shall be recorded on AF Form 1027, Water Flow Test Record, and maintained on the government Installation Support shared drive. A copy shall be forwarded to the Site CE or designated representative within five (5) business days of testing. Notify the Site CE of any significant degradation in the water distribution system capability within three (3) business days.

7.14.12 Water system logs, records and drawings are maintained IAW DAFMAN 32-1067. Records are maintained on the government Installation Support shared drive.

7.15 Wastewater Collection Systems.

7.15.1 The Contractor shall maintain the wastewater collection system and associated systems and document all maintenance actions.

7.15.2 The Contractor shall monitor the wastewater systems to ensure proper operation and to prevent clogging of the seepage pits at MSSC and prevent tank overflow at RME. The contractor shall schedule and support pumping for the sewage systems and notify the Site CE or designated representative of the scheduled pump date.

7.15.3 Water and sewage estimates can be found in Appendix 35.

7.16 Storm Water Systems.

7.16.1 Storm Water Systems are inspected and maintained debris free to ensure functionality.

7.17 Backflow Prevention.

7.17.1 Backflow prevention devices shall be monitored, inspected, and tested to prevent cross connections and ensure safe drinking water. Support government personnel during the 5-year Survey of Cross-Connection Control and Backflow Prevention Devices by assisting in locating devices and providing technical data.

7.17.2 A cross connection and backflow prevention program shall be implemented IAW DAFMAN 32-1067.

7.17.3 Appoint a Backflow Program Manager in writing IAW DAFMAN 32-1067.

7.17.4 Technicians shall be certified to install, test and inspect backflow devices. Training records are maintained.

7.17.5 Installation, inspection, and testing records and manuals shall be maintained.

7.17.6 Test and inspect backflow prevention devices and document results on AF Form 843, Backflow Prevention Device Inspection Data; AF Form 845, Cross-Connection and Device Information; and AF Form 848, Survey of Cross-Connection Control and Backflow Prevention Devices. All documentation shall be electronically stored on the government Installation Support shared drive as well as paper records in CE official files.

7.18 Locks and Security Devices.

7.18.1 Facility and container security devices shall be maintained and repaired to meet mission requirements.

7.18.1.1 The contractor shall provide services for maintenance and upgrades (if needed) to the existing Intrusion Detection System (IDS), Automated Entry Control System, and Closed-Circuit Camera network (CCTV).

7.18.2 MBSS personnel will follow the requirements of the key control program maintained by Security Forces. For regular key distribution requirements, contact Security Forces in Room 208 at MSSC or Room 120 at 550 Facility to sign out a key from the key cabinet.

7.18.3 Locksmith service is provided to maintain, repair, and retrofit secure and general-purpose locks.

7.18.4 Summary workload data regarding locksmith service is maintained.

7.19 Signs and Markers.

7.19.1 Maintain existing outdoor signs and markers to facilitate mission accomplishment and personnel safety. Signs and markers are refurbished or replaced as needed.

7.19.2 Make sure signs are legible and approved by the Site CE or designated representative.

7.19.3 Have driveway reflective markers in place to ensure road safety.

7.20 Grounds Maintenance.

7.20.1 Comply with the site Integrated Natural Resource Management Plan (INRMP).

7.20.2 MSSC, RME

7.20.2.1 Keep pavements and grounds in passable condition.

7.20.2.2 Remove litter from the grounds of MSSC and RME Sites on a quarterly basis.

7.20.2.3 Implement snow and ice control to ensure personnel safety and mission operations as required by the conditions at MSSC.

7.20.3 550 Facility

7.20.3.1 Provide grounds maintenance at the discretion of the contractor, (i.e., during, before, or after business hours). These maintenance actions will ensure facilities are presentable and safe IAW Appendix 34.

7.20.3.2 Develop and implement a grounds maintenance plan for the facilities IAW the standards provided in Appendix 34 for CE approval.

7.20.3.3 Coordinate large grounds maintenance endeavors with building occupants to prevent disruption of mission.

7.20.3.4 All chemicals and other potentially dangerous products shall be stored in their original, labeled container.

7.20.3.5 Emergency grounds maintenance to include irrigation system repair and removal of downed trees and other debris from a major wind event is to be performed upon request.

7.20.3.6 Litter is removed from the grounds of the site on a monthly basis.

7.21 Custodial Services.

7.21.1 Provide custodial services to ensure facilities are presentable, safe, and sanitary.

7.21.2 Develop and implement a cleaning plan for facilities at MSSC, RME, and 550 Facility. Offices, public use areas, restrooms, and break rooms are maintained IAW the custodial standards provided in Appendix 7.

7.21.3 Coordinate custodial services with affected occupants to prevent disruption of mission.

7.21.4 Janitorial closets will be available for use by the Contractor, without cost, for the purpose of storing materials and equipment, excluding flammable materials. The Contractor will be required to maintain odorless and clean closets free of clutter and debris. Cleaning supplies and tools shall be stored and organized in such a manner as to allow easy access and movement within the closet.

7.21.5 All chemicals and other potentially dangerous products (except bleach water solution) shall be stored in their original, labeled container.

7.21.6 Perform emergency cleaning upon request.

7.22 Facility Access Control System.

7.22.1 Maintain and repair the Access Control System for MSSC, RME, and 550 Facility to allow personnel access to facilities at all times.

7.22.2 Maintenance responsibilities for MBSS include the control panels, batteries, door access devices (prox readers, prox & pin readers, magnetic locks, electronic door strikes etc.) and the low voltage wiring between the control panels and the door access devices.

8.0 FUELS

The Contractor Shall: Monitor, order, and coordinate fuel deliveries. Operate, maintain, and repair petroleum storage and distribution systems and equipment. 8.1 Above-ground storage tanks.

8.1.1 Refer to Paragraph 9.19 for tank management.

8.1.1.1 Ensure current step-by-step operating procedures for fuel transfer equipment are maintained and readily available. Ensure equipment and procedures to transfer fuel via alternate backup means in the event of a pump failure are also maintained and readily available.

8.1.2 Existing storage tank sizes, locations, and type of fuel contained is provided in Appendix 15.

8.2 Fuel Ordering. The Contractor shall order and make available petroleum product to meet mission requirements. The Contractor shall monitor and maintain generator fuel tanks at 75% or greater fuel level.

8.3 Fuel Spills and Spill Prevention.

8.3.1 Receive and store fuel without incident. Deploy secondary containment and spill prevention measures during fuel deliveries IAW Appendix 16.

8.3.2 Report all fuel spills and leaks to the Site CE Environmental Section or designated representative immediately.

8.3.3 For all spills or leaks, submit required reports within twenty-four (24) hours IAW AFI 23-201.

9.0 CIVIL ENGINEERING - ENVIRONMENTAL MANAGEMENT

With the exception of Over and Above projects covered under PWS Section 6.0 and unless specifically specified by the COR, all of this section's work is executed through the firm fixed price CLIN X004 as this work is regularly scheduled/anticipated/reasonably accountable. This includes materials, labor, and other direct costs (ODCs). The Contractor shall:

9.1 Environmental Quality Program. Comply with federal, state, and local environmental regulations and standards. Implement, execute and maintain the installation environmental quality program including compliance, conservation and pollution prevention. Provide environmental services and qualified manpower to accomplish all Section 9 requirements. The contractor upholds the upmost authority physically at 15 SPSS for all accompanying

offices/programs/organizations. Subject matter expert support is received to the contractor through 21 CES, AFCEC, and AFIMSC.

SS-32 Performance Standards

a) Standard: Comply with federal, state, and local environmental regulations and standards. Implement, execute and maintain the installation environmental quality program including compliance, conservation and pollution prevention. Provide environmental services and qualified manpower to accomplish all Section 9 requirements.

AQL: Environmental Quality Program shall be 100% compliant with federal, state, and local environmental regulations/standards AQL: Provide notification of conflict with requirements or noncompliance to 21 CES/CEIE within 1 business day of identification

Reference: DAFI 32-7001

9.2 Environmental Management System (EMS). All installations/sites shall comply with the spirit and intent of the EMS. Personnel shall be made aware of the Installations Environmental Policy and Commitment Statement. Maintain and identify environmental aspects, impacts and action plans in EMS. Site will need to utilize eDASH in accordance with DAFI 32-7001. An independent EMS is not required since they are part of the SBD 1 Peterson EMS program.

SS-33 Performance Standard a) Standard: Maintain and identify environmental aspects, impacts and action plans in EMS.

AQL: 100% of the time Reference: D AFI 32-7001

9.2.1 Tool for Environmental Management Plans (T-EMP). Complete environmental management plans in the T-EMP tool through eDASH or similar enterprise level platform. Plans included in standard format to be managed through T-EMP are Hazardous Waste (HWMP), Solid Waste (ISWMP), Cultural Resources (ICRMP), Natural Resources (INRMP) and Storm Water (SWPPP).

SS-34 Performance Standard

a) Standard: Complete environmental management plans in the T-EMP tool through eDASH or similar enterprise level platform. Plans included in standard format to be managed through T-EMP are Hazardous Waste Management Plan (HWMP), Integrated Solid Waste Management Plan (ISWMP), Integrated Cultural Resources Management Plan (ICRMP), Integrated Natural Resources Management Plan (INRMP) and Storm Water Pollution Prevention Plan (SWPPP).

AQL: 100% of required plans shall be updated through T-EMP.

Deliverable CDRL E001 Hazardous Waste Management Plan (HWMP) CDRL E002 Integrated Solid Waste Management Plan ISWM CDRL E003 Integrated Cultural Resources Management Plan (ICRMP) CDRL E004 Integrated Natural Resources Management Plan (INRMP) CDRL E005 Storm Water Pollution Prevention (SWPP)

9.3 Environmental Management System Cross Functional Team (EMS CFT). Attend (via telecon) EMS CFT meetings semi-annually chaired by the Installation Commander (contractor personnel participate as non-voting members). Also, the Contractor shall attend (via telecon) the Environmental Safety and Occupational Health Council (ESOHC) meetings held at Peterson Spaceforce Base. Prepare briefing materials (Maui location slides) for input to the SBD-1 Environmental Quality Chief.

Deliverable

CDRL E006 EMS CFT Briefing Slides and Meeting Minutes

Reference: D AFI 90-801

9.4 Environmental Planning, Programming and Budgeting. Submit environmental quality requirements, including compliance, conservation, and pollution prevention. Track the execution of environmental funds and submit an Environmental Execution Report. The funds tracked include costs for labor, other direct costs, consumables, and other costs directed by the COR.

Deliverable CDRL E007 Annual 5-year forecast for Environmental Program Budget CDRL E008 Environmental Execution Report

Reference: D AFI 32-7001

9.5 Defense Environmental Programs Annual Report to Congress. Complete data call via the Environmental Safety and Occupational Health Management Information System (EESOH-MIS).

SS-35 Performance Standard a) Standard: Complete data call via the Environmental Safety and Occupational Health Management Information System (EESOH-MIS). AQL: Complete data call semi-annually

AQL: Shall respond no later than (NLT) 15 days after the data call opens or as requested by 21 CES/CEIE Deliverable

CDRL E009 EESOH-MIS Website Data Call

9.6 Environmental Education and Awareness. Educate Installation personnel on the SBD 1 EMS to include environmental compliance, pollution prevention, conservation goals, aspects and impacts. Education is considered a one-time training for installation personnel. Document attendance, upload to government sharedrive and provide upon request to the GPM or COR.

Reference: D AFI 32-7001

9.7 Environmental Education Occupation Specific. Ensure all contractor employees who handle toxics, hazardous materials and waste, and POLs are trained in site specific procedures, RCRA, and Spill prevention and Response. Education is required annually for all installation personnel and as needed for all new employees. Document attendance, upload to government sharedrive and provide upon request to the GPM or COR.

Deliverable

CDRL E031 Environmental Education Occupational Specific Training records and rosters

Reference: DAFI 32-7001

9.8 Environmental Inspection Process. Implement the Environmental Inspection Process to include Shop-Level Inspections and Program-Level Compliance Assessments. Assimilate them into the Commanders Inspection Management Board. Reference: DoDI 4715.06, DAFI 90-302, DAFI 90-801, DAFI 32-7001, and Environmental Inspection Process Playbook (eDASH)

9.8.1 Shop-Level Inspections. Document program discrepancies utilizing the "Shop-Level Inspections checklist" provided by 21 CES/CEIE or 15 SPSS and upload to government sharedrive and provide upon request. This includes managing inputs into Management Internal Control Toolset (MICT) for functional programs within this contract's scope as directed by the COR.

Deliverable

CDRL M006 MICT inputs

Reference: DoDI 4715.06, DAFI 90-302, DAFI 90-801, DAFI 32-7001, and Internal Compliance Self-Assessment Playbook

9.8.2 Program-Level Compliance Assessment. Conduct Program-Level Compliance assessments and shop inspections and document findings in EASIER (eDash). Provide updates for all areas assessed, findings, recommended improvement areas, and strengths along with closure actions. Document all shop inspections, even if no discrepancies are found. This should be performed

for each environmental Program every third year. Conduct an Internal Compliance Self-Assessments annually.

Deliverable

CDRL E010 Program Level Assessment (EASIER inputs) CDRL M006 Internal Compliance Self-Assessment Reference: DoDI 4715.06, DAFI 90-302, DAFI 90-801, DAFI 32-7001, and Internal Compliance Self-Assessment Playbook

9.9 Environmental Impact Analysis Process (EIAP) (NEPA). Manage the EIAP program and submit all EIAP documents, for example, environmental impact statements, environmental assessments, and categorical exclusions to the to 21 CES for EPF/BCE approval/signature. Prepare EIAP planning, analysis, air conformity analysis and documentation to support all Installation activities including engineering work orders, projects, real property actions and in-house work plans. Document air conformity utilizing the Air Conformity Analysis Model (ACAM). Maintain records of all EIAP documents in the Civil Engineering (CE) Project folders. Participate in and provide feedback or required information in all NEPA activities for the installation. Utilize the AF 813 tool.

Deliverable CDRL E011 AF Form 813s

9.10 Environmental Project Reviews and Coordination. Review and coordinate on all work performed at 15 SPSS that has environmental implications and provide feedback to ensure incorporation of all applicable environmental requirements.

Deliverable CDRL E012 Environmental Reviews and Coordination.

Reference: AFI 32-1015

9.11 Environmental Review of Permits. Upon notification and annually, ensure new construction or modifications to existing sources are not initiated until appropriate permits) are received from cognizant regulatory authorities. Review all permits and permitting requirements and potentially applicable federal, state, and local requirements as necessary, minimum annually, to ensure compliance conditions are met and meets current regulations, for both current mission operations and projected missions. Request permit updates as appropriate.

Deliverable CDRL E012 Environmental Reviews and Coordination References: D AFI32-7001, AFMAN 32-1067, 32-7002, and DAFMAN 32-7003

9.12 Environmental Reviews and Coordination. Ensure comments on federal, state, and local proposed rules, revisions, plans, protocols, permits, and negotiations with federal, state, and

local regulatory agencies regarding installation-specific issues (e.g., variances, permit limits and operating conditions) are coordinated with Installation Commander and COR prior to external communication.

Deliverable CDRL E012 Environmental Reviews and Coordination

References: DAFI,32-7001, AFMANs 32-1067, 32-7002, and DAFMAN 32-7003

9.13 Environmental Baseline Surveys (EBS). Perform EBS or EBS Waiver for Real Estate transactions, ensuring protection of human health and the environment, and determining the possible effects of contamination on property valuation. Serve as the basis for notice of environmental condition when required and report suspect conditions to COR. Submit to 21 CES for signature.

Deliverable CDRL E013 Environmental Baseline Survey Report or Waiver

Reference: DAFI 32-7020

9.14 Air Quality Program. Implement, execute and maintain the Air Quality Program. Coordinate all regulatory issues and audits with Installation Commander and COR prior to external communication. Establish local reporting procedures and provide technical expertise with regard to air quality compliance. Also includes Refrigerant Management tracking and reporting, and Employee-vehicle Certification and Reporting System (ECARS) (if locally required). Maintain all records in the Air Pollution Information Management System (APIMS).

Deliverable CDRL E014 Air Emissions Inventory (Initial and 3-year cycle)

CDRL E015 APIMS Inputs and Updates

Reference: AFMAN32-7002

9.14.1 Air Quality Education and Training. Provide annual education and training, to include Air Management Training, Air Source Operator Training, and shop level training to meet applicable federal, state, and local air quality compliance requirements. Document attendance and provide it upon request to the GPM or COR.

Reference: AFMAN 32-7002

9.15 Enforcement Actions, Spills, and Inspections Environmental Reporting (EASIER). Comply with Installation policies and programs. Report all EASIER to the host installation and COR. Input and update the EASIER database.

SS-36 Performance Standard

a) Standard: Report actions, spills and inspections to the Installation/Site Commander/USAFLO and COR within one hour. Refer to Spill Prevention Control and Countermeasures (SPCC) for further standards of reporting.

AQL: 100% of the time

Deliverable CDRL E016 EASIER Spill Inputs and Updates

Reference: D AFI 32-7001

9.16 Hazardous Material (HAZMAT) Program. Implement, execute and maintain the Installation Hazardous Material Management Process (HMMP). Chair, implement and maintain existing HMMP Team and Charter. Ensure personnel receive EESOH-MIS user training prior to use. Maintain access authorization and system access privileges for EESOH-MIS users. Develop, implement, maintain and review a Hazardous Materials Management Plan (HMMP) in T-EMP.

Deliverable CDRL E017 Hazardous Materials Management Plan

Reference: DAFI 32-7001, AFMAN 32-7002

9.16.1 HAZMART. Operate a HAZMART, the only entity on an installation authorized to issue Government-owned HAZMAT from any source (e.g., GPC, AF Form 9, or any DoD standard supply system). Account for and track all HAZMAT on the Installation at a level sufficient to meet environmental reporting requirements and support fire protection, ESOH, and disaster response efforts. Obtain approved AF Form 3952 prior to requisition of items in Federal Standard 313 classes. Manage inventory receipt and issue data to include AF Form 3952s and Safety Data Sheets (SDS) in EESOH-MIS. Complete installation Emergency Planning and Community Right-to-Know Act (EPCRA) reporting requirements.

SS-37 Performance Standard:

a) Standard: Operate a HAZMART IAW the Installation HMMP.

AQL: Account for all HAZMAT within three (3) duty days of receipt in EESOH-MIS.

Deliverable CDRL E018 EESOH-MIS Inputs and Updates

CDRL E019 EPCRA Reporting Requirements (Tier II)

Reference: AFMAN 32-7002 9.16.2 HAZMART Resources. Plan, Program and Budget for all necessary HAZMART resources. Submit environmental-eligible HMMP funding requirements through the environmental programming/budgeting system.

Deliverable CDRL E018 EESOH-MIS Inputs and Updates

9.17 Hazardous Waste (HW) Program. Implement, execute, and maintain the Hazardous Waste Management Plan (HWMP) including Site Waste Stream Process Descriptors, Initial Accumulation Points (IAP) locations, Appointment of IAP Managers and Waste Profile Information. Perform all Sampling Analysis for all waste streams, petroleum, oil, lubricants, and fluids. Manage the installation HW program including control and oversight of HW disposal. Creation of manifests, shipping of HAZWASTE off site and final disposition of waste is not in the scope of this contract (non-applicability excludes labeling). Provide a trained POC to sign for HW manifest and landfill disposal records. Coordinate the HWMP with the approval of the Installation ESOHC. Ensure the Installation hazardous waste generators including base organizations, tenant organizations, and other contractor operations comply with the HWMP. Maintain HW related records in the approved environmental reporting system, currently the EESOH-MIS. Note: Only cost estimates that could be included for disposal requirements could be associated costs such as labeling and containerizing. Labeling and containerizing normally would be done through DLA.

Deliverable CDRL E001 HWMP

Reference: AFMAN 32-7002

9.18 Baseline EESOH-MIS database. The complete EESOH-MIS database shall be baselined within 3 months after the end of the phase-in period. After baselining, EESOH-MIS data shall be maintained to ensure accuracy.

Deliverable CDRL E020 Baseline of EESOH-MIS database Reference: AFMAN 32-7002

9.19 Integrated Solid Waste Management (ISWM). Implement, execute, and maintain the ISWM. Manage the installation environmental program including control and oversight of Solid Waste (SW) disposal, management of landfills and required sampling and analysis. Coordinate the ISWM with the approval of the EMS CFT and ESOHC as required. ISWM Plan shall be completed using the T-EMP Tool. Maintain all SW records for active and closed landfills.

Deliverable CDRL E002 ISWM Plan

Reference: AFMAN 32-7002

9.20 Storage Tanks. Appoint a POL Tank Compliance single point of contact to track compliance of Aboveground Storage Tanks (ASTs). Maintain all above-ground storage tanks IAW applicable federal, state and local regulations. Ensure applicable registration, permits and notifications are completed for all storage tanks. Update and maintain the storage tank inventory in the real property record and in the AF network approved Storage Tank Accounting and Reporting (STAR) system. Inspect ASTs (including organizational tanks) and record in STAR.

SS-38 Performance Standard:

a) Standard: Inspect ASTs (including organizational tanks) and record in STAR. b) AQL: Inspect ASTs monthly and annually and record in STAR IAW environmental regulations.

Deliverable CDRL E021 STAR System Records Reference: AFMAN 32-1067 and AFMAN 32-7002

9.21 Spill Prevention Control and Countermeasures (SPCC) Program. Implement, execute and maintain the SPCC. Respond to all spills of POL and hazardous substances and perform containment, recovery, disposal and restoration activities. Provide and document training for all oil-handlers annually. Report all Spills in EASIER. Review and update SPCC on an annual basis. If changes require Professional Engineer (PE) stamp, contractor will provide PE service. SPCC Program shall be executed IAW 40 CFR 112.

Deliverable CDRL E022 SPCC Annual Review

9.22 Asbestos Containing Material (ACM). Implement, execute, and maintain the Asbestos Operations and Management Plan. Maintain an inventory of known friable and non-friable ACM. Notify Installation CE and 21 CES/CEIE if ACM requires repair, maintenance, or removal. Review all WT and FP requests to confirm if the project impacts known ACM.

Deliverable CDRL E023 Asbestos Operations and Management Plan

Reference: AFI 32-1001

9.23 Lead-Based Paint (LBP). Implement, execute, and maintain the LBP Management Plan. Maintain an inventory of known LBP on the Installation. Notify Installation CE and 21 CES/CEIE if LBP requires repair, maintenance, or removal. Review all WT and FP requests to confirm if the project impacts known LBP.

Deliverable CDRL E024 LBP Management Plan

9.24 Polychlorinated Biphenyl (PCB) Program. Maintain an inventory of known PCBs on the Installation in the HWMP. Dispose of PCBs IAW Federal, State and Local laws. Review all WT and FP requests to confirm if the project impacts known PCBs.

Deliverable CDRL E001 HWMP 9.25 Integrated Natural Resources Management Plan (INRMP). Reserved as of 1 July 2025.

Deliverable

CDRL E025 5-year INRMP (In T-EMP) CDRL E026 107 Documentation Reference: D AFMAN 32-7003

9.26 Integrated Cultural Resources Management Plan (ICRMP). Implement and maintain the ICRMP. Prepare coordination documents for Installation Commander's signature. Coordinate draft documents with COR prior to signature. Assist the Installation Tribal Liaison Officer (ITLO) and CRM in preparation and coordination of required communications and meetings. Maintain records of communications, meeting minutes and tribal contacts. Support the CRM as required in all Cultural related functions including 106, 110 and management of and all cultural resources environmental related projects for 15 SPSS. Support the CRM as required to execute a fully updated and revised ICRMP.

Deliverable CDRL E003 ICRMP (In T-EMP)

CDRL E027 Other Cultural Compliance Reference: D AFMAN 32-7003 and DAFI 90-2002 9.27 Environmental Restoration Program (ERP). Maintain the administrative record. Provide information to 21 CES/CEIE as requested. Reference: D AFI 32-7020 9.28 Environmental Correspondence and Permits. Provide copies of all federal, state, and local environmental correspondence received to COR and upload to government sharedrive and provide upon request. Coordinate all outgoing correspondence to federal, state and local officials with the Installation Commander and 21 CES/CEIE prior to sending. Copies of correspondence shall be provided to the COR within four days of receipt.

Deliverable CDRL E028 Environmental Correspondence and Permits

9.29 Integrated Pest Management Plan. Implement, execute, and maintain the Pest Management Plan. Coordinate changes with COR prior to signature. Collect and report data on all installation pesticide use in the Integrated Pest Management Information System (IPMIS). Review contract specifications and serve as the primary POC for all installation pesticide compliance. Utilize certified pesticide applicators.

Deliverable CDRL E029 Pest Management Plan

CDRL E030 IPMIS Inputs and Updates

Reference: DoDI 4150.07 and AFMAN 32-1053

10.0 Transition

10.1 The Contractor shall deliver a Phase-In Transition Plan for assuming the contract from the incumbent and a Phase-Out Transition Plan for passing responsibility to another Contractor at the end of the performance period. The Contractor shall follow the transition plan submitted as part of the proposal and keep the Government fully informed of status throughout the transition period. Throughout the phase-in/phase-out periods, it is essential that attention be given to minimize interruptions or delays to work in progress that would impact the mission. The Contractor must plan for the transfer of work control, delineating the method for processing and assigning tasks during the phase-in/phase-out periods. During phase-in the Contractor shall provide weekly briefings to the Government discussing problems encountered in accomplishing the phase-in, categorized as minor or major issues, progress-to-date, with schedule updates to reflect the actual progress, any variances from plans contained in the phase-in plan, any work-around plans being implemented to resolve problems, and clearly identify any support needed from the Government.

Deliverable

CDRL A050 Phase In Plan

CDRL A051 Phase Out Plan

10.2 Phase In.

10.2.1 A sixty (60) day transition period is projected in support of Phase-In. The Contractor shall be allowed access to the facilities to familiarize contractor personnel to include supervisors, Key Personnel, and staff with equipment, facilities, and requirements. However, such access shall not interfere with contract performance of the incumbent contractor. To preclude such interference, arrangements for access to government facilities shall be made with the PM/COR.

10.2.2 Accomplish all security requirements for contractor personnel IAW Chapter 3 of this PWS.

10.2.3 A joint inventory of property and documentation shall be accomplished with the Government within the transition period. Documents necessary for transfer of accountability

shall be executed. A list of Government furnished property that the Contractor takes possession of and maintains shall be documented and updated annually prior to the exercise of each option.

10.2.4 A joint survey of facilities, infrastructure, and RPIE is accomplished to establish and document a baseline condition. Conditions that could affect the Contractor's ability to accomplish contract requirements shall be documented and submitted to the CO and the PM.

10.2.5 Participate in a full site orientation at the beginning of the phase in period. Ensure all contractor and subcontractor personnel receive the information provided during the site orientation.

10.2.6 Contractor is prepared to assume contract requirements upon completion of phase in period.

10.3 Phase Out.

10.3.1 If there is a change in the contractor or if the operation reverts to in-house, the incumbent contractor shall provide familiarization, as described in paragraph 10.1 to the government or the phase in contractor as appropriate. During the phase out period, the incumbent contractor shall be fully responsible for operation of all functions included in this PWS.

10.3.2 The government reserves the right to conduct site visits in all contractor-operated facilities in conjunction with the solicitation of offers for the follow-on contract. In the event the follow-on contract is awarded to a contractor other than the incumbent, the incumbent (phase out) contractor shall cooperate to the extent required to permit an orderly change over to the phase in contractor. With regard to the phase in contractor's access to incumbent (phase out) employees, a recruitment notice may be placed in each facility.

10.3.3 In the event the re-competed contract is awarded to other than the incumbent, the incumbent (phase out) contractor shall turn over all the existing government furnished property, government data, user manuals, continuity/best practices/SOPs and maintained records/documentation.