

Project #8: McChord Runway Lighting Overt/Covert

Project: Repair Assault Overt/Covert Lights, McChord Field

1. Overview

The McChord Airfield overt/covert lighting system is currently in a failing state. Scope is to replace the entire overt/covert lighting system, replacement of the SFL system, and the training for the JBLM Airfield Lighting technicians.

2. Safety

All appropriate safety protocols will be followed, referencing the guidelines in FAA 150/5340-26(x), Chapter 2.

3. Tasks: This project includes two main tasks detailed below.

Task 1: Lighting system Replacement.

An example replacement system is detailed below:

Logi Track Device Hardware Upgrade

- Runway 16/34:
 - Forty-eight (48) Logi Track Remotes (P/N: T6540-03-01-00 CLD, 2XLAMP, ON/OFF PROGR 11768824)
 - Forty-four (44) to be installed.
 - Four (4) units designated as spares.

Task 2: Sequence Flasher Remote Control Replacement

An example replacement system is detailed below:

- Sequencer Flasher Remote Control Hardware:
 - Runway 16:
 - One (1) Remote Control Unit (P/N: 1500867-2-C), which includes:
 - One (1) IP 66 Enclosure
 - One (1) I/O Unit
 - One (1) Managed Gigabit Ethernet Switch
 - One (1) Single Mode SFP Module
 - Runway 34:

- One (1) Remote Control Unit (P/N: 1500867-2-C), which includes:
 - One (1) IP 66 Enclosure
 - One (1) I/O Unit
 - One (1) Managed Gigabit Ethernet Switch
 - One (1) Single Mode SFP Module
- Vault:
 - Two (2) Single Mode SFP Modules for Runway 16/34 SFL communications.
- Software:
 - New Communication Protocol for the new SFL interface.
 - Database Modification for the new SFL configuration.
 - Factory Test.

4. Maintenance & Service Responsibilities

- Perform and record testing and evaluation results before services begin.
- Coordinate commissioning tasks with the product manufacturer's representative, including new enclosure installation support, new software installation, onsite testing, and drawing updates.
- Support and log the completion of all equipment updates, software updates, and manufacturer-specified testing.
- Advise the JBLM representatives of any deviations or discrepancies from approved services.
- Provide a final trip/maintenance report for review and signature upon service completion.
- Organize, provide, and retain copies of all relevant project documentation.
- Provide training for all JBLM technicians.