

STATEMENT OF OBJECTIVES (SOO)

FOR

ADVANTOR Intrusion Detection System (IDS) within the Geographically Separated Unit (GSU) at North Smithfield.

1.0 Purpose and Scope: The contractor shall provide all personnel, equipment, tools, materials, supervision, and quality control necessary to perform Install for the required IDS, as defined in this SOO.

2.0 Background: The 282d Combat Communications Squadron (CBCS), North Smithfield GSU, requires a security system installed in order to meet security standards required to maintain wartime readiness.

3.0 Period of Performance (PoP): The Period of Performance shall be 30 Days after receipt of order (ARO).

3.1 Place and Performance of Installation: The contractor shall provide install between the hours of 0800-1630 on Monday through Friday, except on recognized US holidays or when the Government facility/installation is closed due to local or national emergencies, administrative closings, or similar Government-directed facility/installation closings. Installation shall be at the 282d CBCS, 274 Old Oxford Rd North Smithfield, RI 02896.

4.0 Performance Objectives

4.1 Provide and install a new Advantor IG2 Processor with ITK Keypad to replace in place GFE Acct. 3015 to manage building 108 Intrusion Detection System to annunciate to Advantor Central Station assumed to be located at SFS BDOC as described and depicted in attached Design Concept Drawing. Advantor to replace in place GFE IDS devices within building 108 as described in design concept drawing.

4.2 Provide and install a new Advantor IG2 FIPS Processor with ITK Keypad to replace in place GFE Acct. 3016 to manage building 102 Intrusion Detection System to annunciate to Advantor Central Station assumed to be located at SFS BDOC as described and depicted in attached Design Concept Drawing. Advantor to replace in place GFE IDS devices within building 108 as described in design concept drawing.

4.3 Provide and install a new Advantor IG2 Processor with ITK Keypad to manage building 102 communication room Intrusion Detection System to annunciate to the Advantor Central Station assumed to be located at SFS BDOC.

4.4 Provide and install a new network firewall and 12 Port switch within a GFE Network Rack in the 1st floor comm room of building 102 for system communication and encryption as described and depicted in the design concept drawing.

4.5 Replace in place the GFE ASN switch assumed to be located within the BDOC of Quonset ANG with a new 48pt switch and install a new network firewall.

4.6 Provide a Design Drawing package in PDF format.

4.7 Provide all required system cabling.

DRAFT