

Project #9: Repair Taxiway H, McChord Field

1.0 Project Overview

The work under this contract consists of the repair of Taxiway 'H' (South Package) at McChord Field, Joint Base Lewis-McChord, WA. The Contractor shall furnish all labor, materials, equipment, and supervision necessary to perform the work as detailed in the construction drawings and technical specifications. The project is to be completed in phases to minimize disruption to airfield operations.

2.0 General Requirements & Coordination

- **Compliance:** All work shall conform to applicable building codes, regulations, and ordinances, including UFC 3-260-01 for airfield operations. The Contractor is responsible for obtaining all required permits.
- **Field Verification:** The Contractor is responsible for field verifying all existing conditions and dimensions prior to the start of work.
- **Safety & Security:** The Contractor is solely responsible for construction means, methods, sequences, and the safety of all personnel. This includes adherence to all airfield safety, security, and vehicle/equipment marking requirements as detailed in the drawings (Sheets CI001-CI005, C1004).
- **Access & Staging:**
 - Contractor access to the site will be through Gate 63V and along the route specified in the drawings.
 - A designated staging area is provided for material stockpiling and vehicle parking. The Contractor must maintain this area and restore it to its original condition upon project completion.
- **FOD Control:** The Contractor shall be responsible for the prevention and continuous removal of any Foreign Object Debris (FOD) from all active and construction pavement areas.

3.0 Demolition and Removals

- **Pavement Removal:** Saw-cut, demolish, and remove existing Portland Cement Concrete (PCC) pavement and Asphalt Concrete (AC) shoulders within the limits defined on Demolition Plans (Sheets CD101-CD107).
- **Base Course Removal:** Excavate and remove the existing base course material to the depths specified in the Pavement Removal Details (Sheet CD501).

- Protection: The Contractor must protect all existing utilities, taxiway edge lights, and other airfield appurtenances from damage during construction. Any damage shall be repaired at the Contractor's expense.
- Disposal: All demolition rubble, debris, and excess excavated material shall be removed from government property and disposed of at an approved off-site location.

4.0 Earthwork and Grading

- Grading: Grade the site to the lines, elevations, and profiles indicated on the Grading Plans (Sheets CG101-CG107) and Taxiway Profiles (Sheets CG201-CG209).
- Subgrade Preparation: Prepare and compact the subgrade in preparation for the new base course and pavement. Subgrade must be compacted to 95% or 100% of ASTM D1557, as specified in the typical sections (Sheet CP501).

5.0 Paving and Surfacing

- Aggregate Base Course: Install a 6-inch layer of Aggregate Base Course (ABC), compacted to 100%, as the foundation for new pavement sections.
- PCC Pavement: Place new 14.5-inch thick PCC pavement as shown on the Paving Plans (Sheets CP101-CP107).
- Asphalt Pavement: Place new 3-inch thick AC shoulders and 6.5-inch thick AC pavement for the E Ramp Taxiway connection as detailed.
- Joints: Construct all pavement joints (doweled contraction, construction, expansion, and thickened edge joints) in strict accordance with the Pavement Jointing Details on Sheet CP502. This includes drilling and grouting dowel bars into existing adjacent pavement.

6.0 Pavement Maintenance and Repair

- Crack Sealing: Clean and seal all designated cracks in existing asphalt and concrete pavements that are to remain, as shown on the Pavement Maintenance Plans (Sheets CP201-CP208).
- PCC Panel Replacement: Perform full-depth replacement of specified PCC panels, including installation of dowel bars on all sides as per details on Sheet CP503.
- Partial-Depth Patching: Execute partial-depth PCC patch repairs for spalls and other surface distresses as directed by the COR and detailed on Sheet CP503.

7.0 Pavement Markings

- Re-stripe all pavement markings that were removed or damaged during construction to match their original configuration, color, and width.
- New markings include, but are not limited to, the taxiway centerline, taxiway edge stripes, and deceptive shoulder striping, as per details on Sheets CP504-CP506.

8.0 Site Restoration and Demobilization

- Upon completion of all construction activities, remove all contractor equipment, temporary facilities, and trash from the site.
- Restore the contractor staging area and any other disturbed areas to their original condition or better.

