

Project #10: Repair Taxiway D, McChord Field

Project Title: Repair Taxiway D, McChord Field

Project Location: Asphalt pavement sections T28C1 and T28C2 of Taxiway D, adjacent to the main runway at McChord Field, as visually detailed in the attached aerial images.

1.0 Project Summary

The primary objective of this project is to repair two deteriorating sections of Taxiway D, identified as T28C1 and T28C2. The Pavement Condition Index (PCI) for both sections (64 and 54, respectively) is below the minimum requirement for primary taxiways. The work involves crack sealing, milling the existing asphalt surface, and applying a new asphalt overlay to restore the taxiway to a safe and effective operational condition.

2.0 Scope of Work

The Contractor shall provide all labor, materials, equipment, and supervision necessary to perform the following tasks:

- 2.1 Final Repair Plan: Based on site investigations and the provided documents, develop and submit a final repair plan and construction specifications for review and approval by the customer.
- 2.2 Pavement Preparation:
 - Crack Sealing: Clean and seal all medium-severity longitudinal and transverse (L&T) cracks within sections T28C1 and T28C2. The sealant used must be a high-quality product that meets the agency's qualifying material list.
 - Shallow Patching (Section T28C2): Repair areas of high-severity weathering as required prior to the overlay.
- 2.3 Asphalt Milling: Mill the entire surface of both sections T28C1 (21,618 sq. ft.) and T28C2 (15,154 sq. ft.) to a depth of 2 inches.
- 2.4 Asphalt Overlay: Place a 2-inch hot-mix asphalt (HMA) overlay on the entire milled surface of both sections, ensuring a smooth and durable final pavement surface.
- 2.5 Pavement Markings: (Assumption) Re-stripe all existing pavement markings disturbed or covered during the overlay process to match pre-existing layouts and conform to airfield standards.

3.0 Airfield Coordination & Site Constraints

The Contractor must adhere to the following strict operational requirements:

- 3.1 Airfield Management: All site survey, staging, scheduling, and construction activities must be coordinated with and receive prior approval from the McChord Airfield Manager (Eileen Rodriguez, 253-273-6113).
- 3.2 Scheduling: The construction schedule must prioritize weekend work to minimize interruptions to the adjacent active runway.
- 3.3 Airfield Operations:
 - Plan for regular disruptions to construction activities due to aircraft operations.
 - All contractor personnel, equipment, and materials must be completely evacuated from the airfield safety areas during all incoming and outgoing flights.
 - Use of a displaced threshold on the active runway is not permitted.
- 3.4 Site Access:
 - Construction escorts are required for all personnel and vehicles unless personnel have completed the required airfield training and certification.
 - Airfield access requires approved daily scheduling.
 - Designated and qualified personnel must maintain airfield radio communication at all times while on site.

