

DOCUMENT 00 01 15

LIST OF DRAWINGS
02/24

PART 1 GENERAL

1.1 SUMMARY

This section lists the drawings for the project pursuant to contract clause "DFARS 252.236-7001, Contract Drawings and Specifications."

1.2 CONTRACT DRAWINGS

Contract drawings are as follows:

DWG NO.	NAVFAC DWG	TITLE
G-001	17361624	COVER SHEET
G-002	17361625	SHEET INDEX
G-003	17361626	SHEET INDEX
GI001	17361627	LOCATION MAP AND HAUL ROUTE
GI002	17361628	TYPICAL SYMBOLS AND ABBREVIATIONS
GI003	17361629	ABBREVIATIONS CONTINUED
GI108	17361630	PHASING PLAN
GI109	17361631	AIRFIELD PHASING PLAN
V-101	17361632	OVERALL EXISTING CONDITIONS
V-102	17361633	EXISTING CONDITIONS - AREA 1
V-103	17361634	EXISTING CONDITIONS - AREA 2
V-104	17361635	EXISTING CONDITIONS - AREA 3
V-105	17361636	EXISTING CONDITIONS - AREA 4
V-106	17361637	EXISTING CONDITIONS - AREA 5
V-107	17361638	EXISTING CONDITIONS - AREA 6
V-108	17361639	EXISTING CONDITIONS - AREA 7
V-109	17361640	EXISTING CONDITIONS - AREA 8
V-110	17361641	EXISTING CONDITIONS - AREA 9
V-111	17361642	EXISTING CONDITIONS - AREA 10
V-112	17361643	EXISTING CONDITIONS - AREA 11
V-113	17361644	EXISTING CONDITIONS - AREA 12
V-114	17361645	EXISTING CONDITIONS - AREA 13
V-115	17361646	EXISTING CONDITIONS - AREA 14
V-116	17361647	EXISTING CONDITIONS - AREA 15
V-117	17361648	EXISTING CONDITIONS - AREA 16
V-118	17361649	EXISTING CONDITIONS - AREA 17
V-119	17361650	EXISTING CONDITIONS - AREA 18
V-120	17361651	EXISTING CONDITIONS - AREA 19
V-121	17361652	EXISTING CONDITIONS - AREA 20
V-122	17361653	EXISTING CONDITIONS - AREA 21
V-123	17361654	EXISTING CONDITIONS - AREA 22
V-124	17361655	EXISTING CONDITIONS - AREA 23
V-125	17361656	EXISTING CONDITIONS - AREA 24
V-126	17361657	EXISTING CONDITIONS - AREA 25
V-127	17361658	EXISTING CONDITIONS - AREA 26
V-128	17361659	SURVEY CONTROL PLAN

BB101	17361660	LIMITED GEOTECHNICAL FIELD WORK PLAN
BB102	17361661	PHASE 2 GEOTECHNICAL FIELD WORK
BB103	17361662	BORING LOGS
BB104	17361663	BORING LOGS
BB105	17361664	BORING LOGS
BB106	17361665	BORING LOGS
BB107	17361666	BORING LOGS
BB108	17361667	BORING LOGS
BB109	17361668	BORING LOGS
BB110	17361669	BORING LOGS
BB111	17361670	BORING LOGS
BB112	17361671	BORING LOGS
BB113	17361672	BORING LOGS
BB114	17361673	BORING LOGS
BB115	17361674	BORING LOGS
BB116	17361675	BORING LOGS
BB117	17361676	BORING LOGS
BB118	17361677	BORING LOGS
BB119	17361678	BORING LOGS
BB120	17361679	BORING LOGS
C-001	17361680	GENERAL NOTES
CD101	17361681	OVERALL DEMOLITION PLAN
CD102	17361682	DEMOLITION PLAN - AREA 1
CD103	17361683	DEMOLITION PLAN - AREA 2
CD104	17361684	DEMOLITION PLAN - AREA 3
CD105	17361685	DEMOLITION PLAN - AREA 4
CD106	17361686	DEMOLITION PLAN - AREA 5
CD107	17361687	DEMOLITION PLAN - AREA 6
CD108	17361688	DEMOLITION PLAN - AREA 7
CD109	17361689	DEMOLITION PLAN - AREA 8
CD110	17361690	DEMOLITION PLAN - AREA 9
CD112	17361691	DEMOLITION PLAN - AREA 11
CD113	17361692	DEMOLITION PLAN - AREA 12
CD114	17361693	DEMOLITION PLAN - AREA 13
CD115	17361694	DEMOLITION PLAN - AREA 14
CD116	17361695	DEMOLITION PLAN - AREA 15
CD117	17361696	DEMOLITION PLAN - AREA 16
CD118	17361697	DEMOLITION PLAN - AREA 17
CD119	17361698	DEMOLITION PLAN - AREA 18
CD120	17361699	DEMOLITION PLAN - AREA 19
CD121	17361700	DEMOLITION PLAN - AREA 20
CD122	17361701	DEMOLITION PLAN - AREA 21
CD123	17361702	DEMOLITION PLAN - AREA 22
CD124	17361703	DEMOLITION PLAN - AREA 23
CD125	17361704	DEMOLITION PLAN - AREA 24
CD126	17361705	DEMOLITION PLAN - AREA 25
CD127	17361706	DEMOLITION PLAN - AREA 26
CD130	17361707	NOT USED
CD131	17361708	NOT USED
CD132	17361709	NOT USED
CD134	17361710	NOT USED
CD135	17361711	NOT USED
CD136	17361712	NOT USED
CD137	17361713	NOT USED

CD138	17361714	NOT USED
CD139	17361715	NOT USED
CS101	17361716	OVERALL SITE & PAVING PLAN
CS102	17361717	SITE & PAVING PLAN - AREA 1
CS103	17361718	SITE & PAVING PLAN - AREA 2
CS104	17361719	SITE & PAVING PLAN - AREA 3
CS105	17361720	SITE & PAVING PLAN - AREA 4
CS106	17361721	SITE & PAVING PLAN - AREA 5
CS107	17361722	SITE & PAVING PLAN - AREA 6
CS108	17361723	SITE & PAVING PLAN - AREA 7
CS109	17361724	SITE & PAVING PLAN - AREA 8
CS110	17361725	SITE & PAVING PLAN - AREA 9
CS111	17361726	SITE & PAVING PLAN - AREA 10
CS112	17361727	SITE & PAVING PLAN - AREA 11
CS113	17361728	SITE & PAVING PLAN - AREA 12
CS114	17361729	SITE & PAVING PLAN - AREA 13
CS115	17361730	SITE & PAVING PLAN - AREA 14
CS120	17361731	SITE & PAVING PLAN - AREA 20
CS121	17361732	SITE & PAVING PLAN - AREA 21
CS122	17361733	SITE & PAVING PLAN - AREA 22
CS123	17361734	SITE & PAVING PLAN - AREA 23
CS124	17361735	SITE & PAVING PLAN - AREA 24
CS125	17361736	SITE & PAVING PLAN - AREA 25
CS126	17361737	SITE & PAVING PLAN - AREA 26
CS130	17361738	OVERALL PAVEMENT MARKING PLAN
CS131	17361739	PAVEMENT MARKING PLAN - AREA 1
CS132	17361740	PAVEMENT MARKING PLAN - AREA 2
CS133	17361741	PAVEMENT MARKING PLAN - AREA 3
CS134	17361742	PAVEMENT MARKING PLAN - AREA 5
CS135	17361743	PAVEMENT MARKING PLAN - AREA 6
CS136	17361744	PAVEMENT MARKING PLAN - AREA 7
CS137	17361745	PAVEMENT MARKING PLAN - AREA 11
CS138	17361746	PAVEMENT MARKING PLAN - AREA 12
CS139	17361747	PAVEMENT MARKING PLAN - AREA 13
CS140	17361748	PAVEMENT MARKING PLAN - AREA 20
CS141	17361749	PAVEMENT MARKING PLAN - AREA 21
CS142	17361750	PAVEMENT MARKING PLAN - AREA 22
CS143	17361751	PAVEMENT MARKING PLAN - AREA 23
CS144	17361752	PAVEMENT MARKING PLAN - AREA 24
CS145	17361753	PAVEMENT MARKING PLAN - AREA 25
CS146	17361754	PAVEMENT MARKING PLAN - AREA 26
CS201	17361755	ROADWAY PLAN & PROFILE RW01 STA 0+00-6+25 - AREA 22
CS202	17361756	ROADWAY PLAN & PROFILE RW01 STA 6+25-12+50 - AREA 22 & 23
CS203	17361757	ROADWAY PLAN & PROFILE RW01 STA 12+50-18+75 - AREA 23 & 24
CS204	17361758	ROADWAY PLAN & PROFILE RW01 STA 18+75-25+00 - AREA 24 & 25
CS205	17361759	ROADWAY PLAN & PROFILE RW01 STA 25+00-31+25 - AREA 25 & 26
CS206	17361760	ROADWAY PLAN & PROFILE RW01 STA 31+25-37+50 - AREA 21 & 26
CS207	17361761	ROADWAY PLAN & PROFILE RW01 STA 37+50-44+00 - AREA 21
CS212	17361762	TAXILANE PLAN & PROFILE L2 STA 00+00-06+50
CS213	17361763	TAXILANE PLAN & PROFILE L2 STA 06+50-13+00
CS215	17361764	TAXILANE PLAN & PROFILE L3 STA 00+00-06+50
CS216	17361765	TAXILANE PLAN & PROFILE L3 STA 06+50-13+00
CS301	17361766	ROADWAY SECTIONS - SAMPLE LINE PLAN

CS302	17361767	ROADWAY SECTIONS - RW01
CS303	17361768	ROADWAY SECTIONS - RW01
CS304	17361769	ROADWAY SECTIONS - RW01
CS305	17361770	ROADWAY SECTIONS - RW01
CS306	17361771	ROADWAY SECTIONS - RW01
CS307	17361772	ROADWAY SECTIONS - RW01
CS308	17361773	ROADWAY SECTIONS - RW01
CS309	17361774	ROADWAY SECTIONS - RW01
CS310	17361775	APRON SECTIONS - A01
CS311	17361776	APRON SECTIONS - A02
CS312	17361777	APRON SECTIONS - A03
CS501	17361778	SITE DETAILS
CS502	17361779	SITE DETAILS
CS503	17361780	SITE DETAILS
CS504	17361781	SITE DETAILS
CS505	17361782	SITE DETAILS
CS506	17361783	SITE DETAILS
CS507	17361784	SITE DETAILS
CT101	17361785	OVERALL JOINTING PLAN
CT102	17361786	JOINTING PLAN - AREA 1
CT103	17361787	JOINT ELEVATION PLAN - AREA 1
CT104	17361788	JOINTING PLAN - AREA 2
CT105	17361789	JOINT ELEVATION PLAN - AREA 2
CT106	17361790	JOINTING PLAN - AREA 3
CT107	17361791	JOINT ELEVATION PLAN - AREA 3
CT108	17361792	JOINTING PLAN - AREA 6
CT109	17361793	JOINT ELEVATION PLAN - AREA 6
CT110	17361794	JOINTING PLAN - AREA 7
CT111	17361795	JOINT ELEVATION PLAN - AREA 7
CT112	17361796	JOINTING PLAN - AREA 12
CT113	17361797	JOINT ELEVATION PLAN - AREA 12
CT114	17361798	JOINTING PLAN - AREA 13
CT115	17361799	JOINT ELEVATION PLAN - AREA 13
CG101	17361800	OVERALL GRADING AND DRAINAGE PLAN
CG102	17361801	GRADING AND DRAINAGE PLAN - AREA 1
CG103	17361802	GRADING AND DRAINAGE PLAN - AREA 2
CG104	17361803	GRADING AND DRAINAGE PLAN - AREA 3
CG105	17361804	GRADING AND DRAINAGE PLAN - AREA 4
CG106	17361805	GRADING AND DRAINAGE PLAN - AREA 5
CG107	17361806	GRADING AND DRAINAGE PLAN - AREA 6
CG108	17361807	GRADING AND DRAINAGE PLAN - AREA 7
CG109	17361808	GRADING AND DRAINAGE PLAN - AREA 8
CG110	17361809	GRADING AND DRAINAGE PLAN - AREA 9
CG112	17361810	GRADING AND DRAINAGE PLAN - AREA 11
CG113	17361811	GRADING AND DRAINAGE PLAN - AREA 12
CG114	17361812	GRADING AND DRAINAGE PLAN - AREA 13
CG115	17361813	GRADING AND DRAINAGE PLAN - AREA 14
CG116	17361814	GRADING AND DRAINAGE PLAN - AREA15
CG117	17361815	GRADING AND DRAINAGE PLAN - AREA 16
CG118	17361816	GRADING AND DRAINAGE PLAN - AREA 17
CG119	17361817	GRADING AND DRAINAGE PLAN - AREA 18
CG120	17361818	GRADING AND DRAINAGE PLAN - AREA 19
CG121	17361819	GRADING AND DRAINAGE PLAN - AREA 20
CG122	17361820	GRADING AND DRAINAGE PLAN - AREA 21

CG123	17361821	GRADING AND DRAINAGE PLAN - AREA 22
CG124	17361822	GRADING AND DRAINAGE PLAN - AREA 23
CG125	17361823	GRADING AND DRAINAGE PLAN - AREA 24
CG126	17361824	GRADING AND DRAINAGE PLAN - AREA 25
CG127	17361825	GRADING AND DRAINAGE PLAN - AREA 26
CG130	17361826	NOT USED
CG131	17361827	NOT USED
CG132	17361828	NOT USED
CG134	17361829	NOT USED
CG135	17361830	NOT USED
CG136	17361831	NOT USED
CG137	17361832	NOT USED
CG138	17361833	NOT USED
CG139	17361834	NOT USED
CG140	17361835	LIMITS OF GEOSYNTHETIC CLAY LINER
CG141	17361836	LIMITS OF GEOSYNTHETIC CLAY LINER
CG142	17361837	LAWN RESTORATION PLAN
CG143	17361838	NOT USED
CG144	17361839	KARST FEATURES PLAN
CG145	17361840	NOT USED
CG146	17361841	KARST FEATURES DETAIL
CG147	17361842	TURF REINFORCEMENT PLAN
CG148	17361843	NOT USED
CG201	17361844	DRAINAGE PROFILES
CG202	17361845	DRAINAGE PROFILES
CG203	17361846	DRAINAGE PROFILES
CG204	17361847	DRAINAGE PROFILES
CG205	17361848	DRAINAGE PROFILES
CG206	17361849	DRAINAGE PROFILES
CG207	17361850	DRAINAGE PROFILES
CG208	17361851	DRAINAGE PROFILES
CG209	17361852	DRAINAGE PROFILES
CG210	17361853	DRAINAGE PROFILES
CG211	17361854	DRAINAGE PROFILES
CG212	17361855	DRAINAGE PROFILES
CG501	17361856	DRAINAGE DETAILS
CG502	17361857	DRAINAGE DETAILS
CG503	17361858	DRAINAGE DETAILS
CG504	17361859	DRAINAGE DETAILS
CG505	17361860	DRAINAGE DETAILS
CG506	17361861	DRAINAGE DETAILS
CG507	17361862	SAND FILTER DETAILS
CU101	17361863	OVERALL UTILITY PLAN
CU102	17361864	UTILITY PLAN - AREA 1
CU103	17361865	UTILITY PLAN - AREA 6
CU104	17361866	UTILITY PLAN - AREA 7
CU105	17361867	UTILITY PLAN - AREA 8
CU106	17361868	UTILITY PLAN - AREA 23
CU107	17361869	UTILITY PLAN - AREA 24
CU108	17361870	UTILITY PLAN - AREA 25
CU109	17361871	UTILITY PLAN - AREA 26
CU201	17361872	UTILITY PROFILES
CU202	17361873	UTILITY PROFILES
CU203	17361874	UTILITY PROFILES

CU501	17361875	UTILITY DETAILS
CU502	17361876	UTILITY DETAILS
S-001	17361877	STRUCTURAL GENERAL NOTES
S-002	17361878	STRUCTURAL GENERAL NOTES
S-101	17361879	FOUNDATION PLANS
S-501	17361880	TYPICAL CONCRETE DETAILS
S-502	17361881	TYPICAL CONCRETE DETAILS
S-503	17361882	CONCRETE SECTIONS AND DETAILS
A-001	17361883	GENERAL NOTES, SYMBOLS, AND EXTERIOR PERSPECTIVE VIEWS
A-406	17361884	DETACHED EQUIPMENT YARD
E-001	17361885	ELECTRICAL LEGEND 1 OF 2
E-002	17361886	ELECTRICAL LEGEND 2 OF 2
ED101	17361887	ELECTRICAL DEMOLITION PLAN 1
ED102	17361888	ELECTRICAL DEMOLITION PLAN 2
ED601	17361889	EXISTING DISTRIBUTION ONE LINE DIAGRAM - DEMOLITION PLAN
ES101	17361890	ELECTRICAL SITE PLAN 1
ES102	17361891	ELECTRICAL SITE PLAN 2
ES103	17361892	ELECTRICAL SITE PLAN 3
ES104	17361893	ELECTRICAL SITE PLAN 4
ES105	17361894	ENLARGED ELECTRICAL SITE PLAN
ES201	17361895	EXISTING SWITCHING STATION - 13.8KV SWITCHGEAR ARRANGEMENT
ES501	17361896	ELECTRICAL SITE DETAILS
ES502	17361897	ELECTRICAL SITE DETAILS
ES503	17361898	ELECTRICAL SITE DETAILS
ES504	17361899	ELECTRICAL SITE DETAILS
ES505	17361900	ELECTRICAL SITE DETAILS
ES506	17361901	ELECTRICAL SITE DETAILS
ES701	17361902	HIGH MAST LIGHT POLE LOCATIONS
EP601	17361903	EXISTING DISTRIBUTION ONE LINE DIAGRAM - NEW WORK
EP602	17361904	ONE-LINE DIAGRAMS
EP701	17361905	PANELBOARD SCHEDULES
EA101	17361906	AIRFIELD ELECTRICAL PLAN 1
EA102	17361907	AIRFIELD ELECTRICAL PLAN 2
EA501	17361908	AIRFIELD LIGHTING DETAILS
EA502	17361909	AIRFIELD LIGHTING DETAILS
EA503	17361910	AIRFIELD LIGHTING DETAILS
EA504	17361911	AIRFIELD LIGHTING DETAILS
EA701	17361912	AIRFIELD LIGHTING POINTS SCHEDULE
EA702	17361913	AIRFIELD LIGHTING ONE-LINE DIAGRAMS
TS001	17361914	TELECOMMUNICATIONS SITE LEGEND
TD101	17361915	TELECOMMUNICATIONS SITE DEMOLITION PLAN 1
TD102	17361916	TELECOMMUNICATIONS SITE DEMOLITION PLAN 2
TS101	17361917	TELECOMMUNICATIONS SITE PLAN 1
TS102	17361918	TELECOMMUNICATIONS SITE PLAN 2
TS103	17361919	TELECOMMUNICATIONS SITE PLAN 3
TS104	17361920	TELECOMMUNICATIONS SITE PLAN 4
TS105	17361921	TELECOMMUNICATIONS SITE PLAN 5
TS106	17362001	TELECOMMUNICATIONS SITE PLAN 6
TS107	17362002	TELECOMMUNICATIONS SITE PLAN 7
TS108	17362003	TELECOMMUNICATIONS SITE PLAN 8
TS109	17362004	TELECOMMUNICATIONS SITE PLAN 9
TS501	17361922	TELECOMMUNICATIONS SITE DETAILS
TS502	17361923	TELECOMMUNICATIONS SITE DETAILS
TS701	17361924	TELECOMMUNICATIONS INTERBUILDING BACKBONE RISER

CF101	17361925	OVERALL FUELING PLAN
CF102	17361926	OVERALL COMM PLAN
CF201	17361927	FUEL PLAN AND PROFILE - AREA 1
CF202	17361928	FUEL PLAN AND PROFILE - AREA 2
CF203	17361929	FUEL PLAN AND PROFILE - AREA 3
CF204	17361930	FUEL PLAN AND PROFILE - AREA 4
CF205	17361931	FUEL PLAN AND PROFILE - AREA 5
CF206	17361932	FUEL PLAN AND PROFILE - AREA 6
CF207	17361933	FUEL PLAN AND PROFILE - AREA 7
CF208	17361934	FUEL PLAN AND PROFILE - AREA 8
CF209	17361935	FUEL PLAN AND PROFILE - AREA 9
CF210	17361936	FUEL PLAN AND PROFILE - AREA 10
CF211	17361937	FUEL PLAN AND PROFILE - AREA 11
CF212	17361938	FUEL PLAN AND PROFILE - AREA 12
CF221	17361939	COMM PLAN - AREA 1
CF222	17361940	COMM PLAN - AREA 2
CF223	17361941	COMM PLAN - AREA 3
CF224	17361942	COMM PLAN - AREA 4
CF225	17361943	COMM PLAN - AREA 5
CF226	17361944	COMM PLAN - AREA 6
CF227	17361945	COMM PLAN - AREA 7
CF228	17361946	COMM PLAN - AREA 8
CF229	17361947	COMM PLAN - AREA 9
CF230	17361948	COMM PLAN - AREA 10
CF231	17361949	COMM PLAN - AREA 11
CF232	17361950	COMM PLAN - AREA 12
CF233	17361951	COMM PLAN - AREA 13
CF234	17361952	COMM PLAN - AREA 14
CF501	17361953	FUELING DETAILS
CF502	17361954	FUELING DETAILS
SF001	17361955	STRUCTURAL GENERAL NOTES - SHEET 1
SF002	17361956	STRUCTURAL GENERAL NOTES - SHEET 2
SF003	17361957	LEGENDS AND ABBREVIATIONS
SF101	17361958	OVERALL STRUCTURAL LAYOUT
SF111	17361959	ISOLATION VALVE VAULT 1 - PLANS
SF112	17361960	ISOLATION VALVE VAULT 2 - PLANS - SHEET 1
SF113	17361961	ISOLATION VALVE VAULT 2 - PLAN - SHEET 2
SF114	17361962	HYDRANT PIT - PLANS AND SECTIONS
SF115	17361963	HPV PITS - PLANS AND SECTIONS
SF501	17361964	STANDARD STRUCTURAL DETAILS - SHEET 1
SF502	17361965	STANDARD STRUCTURAL DETAILS - SHEET 2
SF511	17361966	ISOLATION VALVE VAULT - SECTIONS - SHEET 1
SF512	17361967	ISOLATION VALVE VAULT - SECTIONS - SHEET 2
SF513	17361968	ISOLATION VALVE VAULT - SECTIONS AND DETAILS
SF521	17361969	ROLLING COVER - SHEET 1
SF522	17361970	ROLLING COVER - SHEET 2
SF523	17361971	ROLLING COVER - SHEET 3
SF524	17361972	ROLLING COVER - SHEET 4
SF525	17361973	ROLLING COVER - SHEET 5
SF551	17361974	PIPE SUPPORT DETAILS
MF001	17361975	FUELING MECHANICAL LEGEND
MF002	17361976	FUELING MECHANICAL GENERAL NOTES
MF011	17361977	FUELING MECHANICAL FLOW DIAGRAM - OVERALL
MF101	17361978	FUELING MECHANICAL OVERALL SITE PLAN

MF501	17361979	FUELING MECHANICAL DETAILS - ISOLATION VALVE VAULT (IVV-1)
MF502	17361980	FUELING MECHANICAL DETAILS - ISOLATION VALVE VAULT (IVV-2)
MF503	17361981	FUELING MECHANICAL DETAILS
MF504	17361982	FUELING MECHANICAL DETAILS
MF505	17361983	FUELING MECHANICAL DETAILS
MF506	17361984	FUELING MECHANICAL DETAILS
MF601	17361985	FUELING MECHANICAL P&ID
EF001	17361986	ELECTRICAL FUELING LEGEND - 1
EF002	17361987	ELECTRICAL FUELING LEGEND - 2
EF011	17361988	OVERALL FUELING HAZARDOUS AREA PLAN
EF101	17361989	OVERALL FUELING ELECTRICAL SITE PLAN
EF401	17361990	ENLARGED PLAN - PUMPHOUSE
EF501	17361991	ELECTRICAL DETAILS - EPDS
EF502	17361992	ELECTRICAL DETAILS - GROUNDING
EF503	17361993	ELECTRICAL SITE DETAILS - HANDHOLES
EF504	17361994	ELECTRICAL SITE DETAILS - DUCT BANKS
EF511	17361995	ELEVATION - PUMP CONTROL PANEL
EF611	17361996	PCP - CONTROL DIAGRAM
EF621	17361997	NORTH APRON EPDS - FRONT LAYOUT
EF622	17361998	NORTH ARON EPDS WIRING - 1
EK501	17361999	CATHODIC PROTECTION DETAILS
EK501	17362000	CATHODIC PROTECTION DETAILS

1.3 REFERENCE DRAWINGS

The following reference drawings are intended only to show the original construction. Drawing are the property of the Government and must not be used for any purpose other than that intended by the contract.

NAVFAC DWG NO.	TITLE
<u>3201807</u>	<u>REPAIR/REPLACE OIL/WATER SEPARATORS BUILDING NO. 2550 JET ENGINE TEST FACILITY</u>
<u>7320181</u>	<u>REPAIR/REPLACE OIL/WATER SEPARATORS BLDG NO. 2550 JET ENGINE TEST FACILITY</u>
<u>AND-W-122</u>	<u>CONSTRUCT OIL SEPARATOR WET ENGINE TEST STAND (BLG 2550)</u>

<u>NAVFAC DWG NO.</u>	<u>TITLE</u>
<u>AND B-230</u>	<u>CONSTRUCT JET TEST STAND READY ROOM</u>
<u>AND-R-60</u>	<u>AIR CONDITIONING SHAW ESTES JET ENGINE TEST CELL CONTROL RM.</u> <u>BLDG. 2551</u>

-- End of Document --

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 01 57 19

TEMPORARY ENVIRONMENTAL CONTROLS

08/22, CHG 2: 08/25

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

U.S. ENVIRONMENTAL PROTECTION AGENCY (EPA)

EPA SW-846 (Third Edition; Update VII) Test Methods
for Evaluating Solid Waste:
Physical/Chemical Methods

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

29 CFR 1910.1053	Respirable Crystalline Silica
29 CFR 1910.1200	Hazard Communication
29 CFR 1926.1153	Respirable Crystalline Silica
40 CFR 50	National Primary and Secondary Ambient Air Quality Standards
40 CFR 60	Standards of Performance for New Stationary Sources
40 CFR 63	National Emission Standards for Hazardous Air Pollutants for Source Categories
40 CFR 64	Compliance Assurance Monitoring
40 CFR 82	Protection of Stratospheric Ozone
40 CFR 112	Oil Pollution Prevention
40 CFR 122.26	Storm Water Discharges (Applicable to State NPDES Programs, see section 123.25)
40 CFR 241	Guidelines for Disposal of Solid Waste
40 CFR 243	Guidelines for the Storage and Collection of Residential, Commercial, and Institutional Solid Waste
40 CFR 258	Subtitle D Landfill Requirements
40 CFR 260	Hazardous Waste Management System: General
40 CFR 261	Identification and Listing of Hazardous Waste

40 CFR 261.7	Residues of Hazardous Waste in Empty Containers
40 CFR 262	Standards Applicable to Generators of Hazardous Waste
40 CFR 262.11	Hazardous Waste Determination and Recordkeeping
40 CFR 263	Standards Applicable to Transporters of Hazardous Waste
40 CFR 264	Standards for Owners and Operators of Hazardous Waste Treatment, Storage, and Disposal Facilities
40 CFR 265	Interim Status Standards for Owners and Operators of Hazardous Waste Treatment, Storage, and Disposal Facilities
40 CFR 266	Standards for the Management of Specific Hazardous Wastes and Specific Types of Hazardous Waste Management Facilities
40 CFR 268	Land Disposal Restrictions
40 CFR 273	Standards for Universal Waste Management
40 CFR 279	Standards for the Management of Used Oil
40 CFR 300	National Oil and Hazardous Substances Pollution Contingency Plan
40 CFR 300.125	National Oil and Hazardous Substances Pollution Contingency Plan - Notification and Communications
40 CFR 355	Emergency Planning and Notification
40 CFR 372	Toxic Chemical Release Reporting
40 CFR 403	General Pretreatment Regulations for Existing and New Sources of Pollution
40 CFR 745	Lead-Based Paint Poisoning Prevention in Certain Residential Structures
40 CFR 761	Polychlorinated Biphenyls (PCBs) Manufacturing, Processing, Distribution in Commerce, and Use Prohibitions
49 CFR 171	General Information, Regulations, and Definitions
49 CFR 172	Hazardous Materials Table, Special Provisions, Hazardous Materials Communications, Emergency Response Information, and Training Requirements

49 CFR 172.101	Hazardous Material Regulation-Purpose and Use of Hazardous Material Table
49 CFR 173	Shippers - General Requirements for Shipments and Packagings
49 CFR 178	Specifications for Packagings

GUAM CODE ANNOTATED (GCA)

10 GCA CH47	Water Pollution Control
10 GCA CH49	Air Pollution Control Act
10 GCA CH50	Guam Pesticides Act
10 GCA CH51	Solid Waste Management and Litter Control
10 GCA CH76	Storage of Hazardous Materials
22 GCA CH32	Professional Engineers, Architects, and Land Surveyors Law

GUAM ADMINISTRATIVE RULES AND REGULATIONS (GAR)

22 GAR DIV1 CH1	Guam Air Pollution Control Act
22 GAR DIV2 CH5	Guam Water Quality Standards
22 GAR DIV2 CH10	Guam Soil Erosion and Sediment Control Regulations
22 GAR DIV3 CH15	Pesticides
22 GAR DIV4 CH20	Solid Waste Disposal Regulations
22 GAR DIV2 CH30	Hazardous Waste Management
22 GAR DIV9 CH45	Soil Erosion and Sedimentation Control
22 GAR DIV10 CH50	Underground Storage Tanks

Department of the Air Force

Final EIS	(2025) Final Environmental Impact Statement for F-15 Beddown and Infrastructure Upgrade at Andersen Air Force Base, Guam
ICRMP	(2015) Andersen Air Force Base Integrated Cultural Resources Management Plan
Data Recovery Plan	(2025) Data Recovery Plan for Sites 66-07-2113, 66-07-2117, 66-07-2118, and 66-08-2981 (Fafalog), Andersen Air Force Base, Guam

U.S. Fish and Wildlife Service

2025 BO

Biological Opinion for Expansions of
Aircraft Operations Area at Northwest
Field, and Munitions Storage Area (MSA-1),
Andersen Air Force Base, Guam, 25 February
2025

HACCP Manual

(2019) HACCP Hazard Analysis and Critical
Control Point Planning to Prevent the
Spread of Invasive Species

1.2 DEFINITIONS

1.2.1 State

"State" when used in reference to states of the United States, also includes the Territory of Guam.

1.2.2 Class I and II Ozone Depleting Substance (ODS)

Class I ODS is defined in Section 602(a) of The Clean Air Act. A list of Class I ODS can be found on the EPA website at the following weblink.
<https://www.epa.gov/ozone-layer-protection/ozone-depleting-substances>.

Class II ODS is defined in Section 602(s) of The Clean Air Act. A list of Class II ODS can be found on the EPA website at the following weblink.
<https://www.epa.gov/ozone-layer-protection/ozone-depleting-substances>.

1.2.3 Contractor Generated Hazardous Waste

Contractor generated hazardous waste is materials that, if abandoned or disposed of, may meet the definition of a hazardous waste. These waste streams would typically consist of material brought on site by the Contractor to execute work, but are not fully consumed during the course of construction. Examples include, but are not limited to, excess paint thinners (i.e., methyl ethyl ketone, toluene), waste thinners, excess paints, excess solvents, waste solvents, excess pesticides, and contaminated pesticide equipment rinse water.

1.2.4 Electronics Waste

Electronics waste is discarded electronic devices intended for salvage, recycling, or disposal.

1.2.5 Environmental Pollution and Damage

Environmental pollution and damage is the presence of chemical, physical, or biological elements or agents which adversely affect human health or welfare; unfavorably alter ecological balances of importance to human life; affect other species of importance to humankind; or degrade the environment aesthetically, culturally or historically.

1.2.6 Environmental Protection

Environmental protection is the prevention/control of pollution and habitat disruption that may occur to the environment during construction. The control of environmental pollution and damage requires consideration of land, water, and air; biological and cultural resources; and includes

management of visual aesthetics; noise; solid, chemical, gaseous, and liquid waste; radiant energy and radioactive material as well as other pollutants.

1.2.7 Hazardous Debris

As defined in paragraph SOLID WASTE, debris that contains listed hazardous waste (either on the debris surface, or in its interstices, such as pore structure) in accordance with 40 CFR 261. Hazardous debris also includes debris that exhibits a characteristic of hazardous waste in accordance with 40 CFR 261.

1.2.8 Hazardous Materials

Hazardous material is any material that: Is defined in 49 CFR 171, listed in 49 CFR 172, regulated as a hazardous material in accordance with 49 CFR 173; or requires a Safety Data Sheet (SDS) in accordance with 29 CFR 1910.1200; or during end use, treatment, handling, packaging, storage, transportation, or disposal meets or has components that meet or have potential to meet the definition of a hazardous waste as defined by 40 CFR 261 Subparts A, B, C, or D. Designation of a material by this definition, when separately regulated or controlled by other sections or directives, does not eliminate the need for adherence to that hazard-specific guidance which takes precedence over this section for "control" purposes. Such material includes ammunition, weapons, explosive actuated devices, propellants, pyrotechnics, chemical and biological warfare materials, medical and pharmaceutical supplies, medical waste and infectious materials, bulk fuels, radioactive materials, and other materials such as asbestos, mercury, and polychlorinated biphenyls (PCBs).

1.2.9 Hazardous Waste

Hazardous Waste is any material that meets the definition of a solid waste and exhibits a hazardous characteristic (ignitability, corrosivity, reactivity, or toxicity) as specified in 40 CFR 261, Subpart C, or contains a listed hazardous waste as identified in 40 CFR 261, Subpart D, or meets a state, local, or host nation definition of a hazardous waste.

1.2.10 Land Application

Land Application means spreading or spraying discharge water at a rate that allows the water to percolate into the soil. No sheeting action, soil erosion, discharge into storm sewers, discharge into defined drainage areas, or discharge into the "waters of the United States" must occur. Comply with federal, state, and local laws and regulations.

1.2.11 Municipal Separate Storm Sewer System (MS4) Permit

MS4 permits are those held by municipalities or installations to obtain NPDES permit coverage for their stormwater discharges.

1.2.12 National Pollutant Discharge Elimination System (NPDES)

The NPDES permit program controls water pollution by regulating point sources that discharge pollutants into waters of the United States.

1.2.13 Oily Waste

Oily waste are those materials that are, or were, mixed with Petroleum,

Oils, and Lubricants (POLs) and have become separated from that POLs. Oily wastes also means materials, including wastewaters, centrifuge solids, filter residues or sludges, bottom sediments, tank bottoms, and sorbents which have come into contact with and have been contaminated by, POLs and may be appropriately tested and discarded in a manner which is in compliance with other state and local requirements.

This definition includes materials such as oily rags, "kitty litter" sorbent clay and organic sorbent material. These materials may be land filled provided that: It is not prohibited in other state regulations or local ordinances; the amount generated is "de minimus" (a small amount); it is the result of minor leaks or spills resulting from normal process operations; and free-flowing oil has been removed to the practicable extent possible. Large quantities of this material, generated as a result of a major spill or in lieu of proper maintenance of the processing equipment, are a solid waste. As a solid waste, perform a hazardous waste determination prior to disposal. As this can be an expensive process, it is recommended that this type of waste be minimized through good housekeeping practices and employee education.

1.2.14 Regulated Waste

Regulated waste are solid wastes that have specific additional federal, state, or local controls for handling, storage, or disposal.

1.2.15 Sediment

Sediment is soil and other debris that have eroded and have been transported by runoff water or wind.

1.2.16 Solid Waste

Solid waste is a solid, liquid, semi-solid or contained gaseous waste. A solid waste can be a hazardous waste, non-hazardous waste, or non-Resource Conservation and Recovery Act (RCRA) regulated waste. Types of solid waste typically generated at construction sites may include:

1.2.16.1 Debris

Debris is non-hazardous solid material generated during the construction, demolition, or renovation of a structure that exceeds 2.5-inch particle size that is: a manufactured object; plant or animal matter; or natural geologic material (for example, cobbles and boulders), broken or removed concrete, masonry, and rock asphalt paving; ceramics; roofing paper and shingles. Inert materials may be reinforced with or contain ferrous wire, rods, accessories and weldments. A mixture of debris and other material such as soil or sludge is also subject to regulation as debris if the mixture is comprised primarily of debris by volume, based on visual inspection.

1.2.16.2 Green Waste

Green waste is the vegetative matter from landscaping, land clearing and grubbing, including, but not limited to, grass, bushes, scrubs, small trees and saplings, tree stumps and plant roots. Marketable trees, grasses and plants that are indicated to remain, be re-located, or be re-used are not included.

1.2.16.3 Material Not Regulated As Solid Waste

Material not regulated as solid waste is nuclear source or byproduct materials regulated under the Federal Atomic Energy Act of 1954 as amended; suspended or dissolved materials in domestic sewage effluent or irrigation return flows, or other regulated point source discharges; regulated air emissions; and fluids or wastes associated with natural gas or crude oil exploration or production.

1.2.16.4 Non-Hazardous Waste

Non-hazardous waste is waste that is excluded from, or does not meet, hazardous waste criteria in accordance with 40 CFR 261.

1.2.16.5 Recyclables

Recyclables are materials, equipment and assemblies such as doors, windows, door and window frames, plumbing fixtures, glazing and mirrors that are recovered and sold as recyclable, wiring, insulated/non-insulated copper wire cable, wire rope, and structural components. It also includes commercial-grade refrigeration equipment with Freon removed, household appliances where the basic material content is metal, clean polyethylene terephthalate bottles, cooking oil, used fuel oil, textiles, high-grade paper products and corrugated cardboard, stackable pallets in good condition, clean crating material, and clean rubber/vehicle tires. Metal meeting the definition of "lead contaminated" or "lead based paint contaminated" may be included as recyclable only if the metal is handled and transported in accordance with regulations, and the facility receiving the material is permitted and authorized to accept and process lead contaminated materials. Paint cans that meet the definition of empty containers in accordance with 40 CFR 261.7 may be included as recyclable if sold to a scrap metal company.

1.2.16.6 Surplus Soil

Surplus soil is existing soil that is in excess of what is required for this work, including aggregates intended, but not used, for on-site mixing of concrete, mortars, and paving. Contaminated soil meeting the definition of hazardous material or hazardous waste is not included and must be managed in accordance with paragraph HAZARDOUS MATERIAL MANAGEMENT.

1.2.16.7 Scrap Metal

This includes scrap and excess ferrous and non-ferrous metals such as reinforcing steel, structural shapes, pipe, and wire that are recovered or collected and disposed of as scrap. Scrap metal meeting the definition of hazardous material or hazardous waste is not included.

1.2.16.8 Wood

Wood is dimension and non-dimension lumber, plywood, chipboard, hardboard. Treated or painted wood that meets the definition of lead contaminated or lead based contaminated paint is not included. Treated wood includes, but is not limited to, lumber, utility poles, crossties, and other wood products with chemical treatment.

1.2.17 Surface Discharge

Surface discharge means discharge of water into drainage ditches, storm

sewers, or creeks meeting the definition of "waters of the United States". Surface discharges from construction sites are discrete, identifiable sources and require a permit from the governing agency. Comply with federal, state, and local laws and regulations.

1.2.18 Wastewater

Wastewater is the aqueous liquid waste generated by a project, to include both domestic wastewater (sewage) and industrial wastewater.

1.2.18.1 Stormwater

Stormwater is any precipitation in an urban or suburban area that does not evaporate or soak into the ground, but instead collects and flows into storm drains, rivers, and streams.

1.2.19 Waters of the United States

Waters of the United States means Federally jurisdictional waters, including wetlands, that are subject to regulation under Section 404 of the Clean Water Act or navigable waters, as defined under the Rivers and Harbors Act.

1.2.20 Wetlands

Wetlands are those areas that are inundated or saturated by surface or groundwater at a frequency and duration sufficient to support, and that under normal circumstances do support, a prevalence of vegetation typically adapted for life in saturated soil conditions.

1.2.21 Universal Waste

The universal waste regulations streamline collection requirements for certain hazardous wastes in the following categories: batteries, pesticides, mercury-containing equipment (for example, thermostats), and lamps (for example, fluorescent bulbs). The rule is designed to reduce hazardous waste in the municipal solid waste (MSW) stream by making it easier for universal waste handlers to collect these items and send them for recycling or proper disposal. These regulations can be found at [40 CFR 273](#). The Guam Environmental Protection Agency (Guam EPA or GEPA) has not adopted the Universal Regulation Rule. Comply with the GEPA regulations and requirements.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. [Submittals not having a "G" or "S" classification are for Contractor Quality Control approval.](#) Submit the following in accordance with Section [01 33 00](#) SUBMITTAL PROCEDURES:

[SD-01 Preconstruction Submittals](#)

[Contractor Hazardous Material Inventory Log; G](#)

[Storage Material Inventory](#)

[Preconstruction Survey](#)

[Regulatory Notifications](#)

Environmental Manager Qualifications

Employee Training Records

Environmental Protection Plan; G

Dirt and Dust Control Plan

Solid Waste Management Permit

Stormwater Pollution Prevention Plan (SWPPP); G

Stormwater Notice of Intent (for NPDES coverage under the general permit for construction activities)

Spill Prevention Control and Countermeasure (SPCC) Plan; G

Hazard Analysis and Critical Control Point (HACCP) Plan; G

GEPA Clearing, Grubbing, Grading, and Stockpiling Permit / General Permit Application; G

Final Work Plan for Tarague Forest Enhancement Area; G

Draft Work Plan for Tarague Forest Enhancement Area; G

Draft Natural Resource Work Plan; G

Final Natural Resource Work Plan; G

Natural Resource Field Assessment Report for P-012 Construction Footprint; G

Natural Resource Field Assessment Report for Tarague Forest Enhancement Area; G

Archaeological Monitoring and Discovery Plan; G

SD-02 Shop Drawings

Alignment of Ungulate Fence; G

SD-06 Test Reports

Monthly Solid Waste Disposal Report; G

SWPPP Inspection Reports

Laboratory Analysis

SD-07 Certificates

ECATTS Certificate of Completion; G

Employee Training Records; G

Erosion and Sediment Control Inspector Qualifications

Qualification of Qualified Biologist(S); G

Qualification of Archaeologist(s); G

SD-10 Operation and Maintenance Data

Weekly Natural Resources Conservation Status Report; G

Monthly Natural Resources Conservation Progress Report; G

Annual Natural Resources Conservation Progress Report; G

Reports and Submittals required by Data Recovery Plan; G

End of Field (EOF) Letter for Archaeological Monitoring - Tarague
FEA; G

SD-11 Closeout Submittals

Contractor Hazardous Material Inventory Log; G

Regulatory Notifications; G

Assembled Employee Training Records; G

Solid Waste Management Permit; G

Stormwater Pollution Prevention Plan Compliance Notebook; G

Stormwater Notice of Termination (for NPDES coverage under the
general permit for construction activities); G

As-Built Topographic Survey

Waste Determination Documentation; G

Project Solid Waste Disposal Documentation Report; G

Sales Documentation; G

Contractor Certification

Hazardous Waste/Debris Management; G

Disposal Documentation for Hazardous and Regulated Waste; G

Draft Natural Resources Conservation Report; G

Final Natural Resources Conservation Report; G

Weekly archaeological monitoring report-Tarague FEA; G

Draft Archaeological Monitoring Report-Tarague FEA; G

Final Archaeological Monitoring Report-Tarague FEA; G

1.4 ENVIRONMENTAL PROTECTION REQUIREMENTS

Provide and maintain, during the life of the contract, environmental

protection as defined. Plan for and provide environmental protective measures to control pollution that develops during construction practice. Plan for and provide environmental protective measures required to correct conditions that develop during the construction of permanent or temporary environmental features associated with the project. Protect the environmental resources within the project boundaries and those affected outside the limits of permanent work during the entire duration of this Contract. Comply with federal, state, and local regulations pertaining to the environment, including water, air, solid waste, hazardous waste and substances, oily substances, and noise pollution.

Tests and procedures assessing whether construction operations comply with Applicable Environmental Laws may be required. Analytical work must be performed by qualified laboratories; and where required by law, the laboratories must be certified.

1.4.1 Training in Environmental Compliance Assessment Training and Tracking System (ECATTS)

1.4.1.1 Personnel Requirements

The Environmental Manager is responsible for environmental compliance on projects. The Environmental Manager and other environmental staff, must complete applicable ECATTS training modules (installation specific or general) prior to starting respective portions of on-site work under this Contract. If personnel changes occur for any of these positions after starting work, replacement personnel must complete applicable ECATTS training within 14 days of assignment to the project.

1.4.1.2 Certification

Submit an ECATTS certificate of completion for personnel who have completed the required ECATTS training. This training is web-based and can be accessed from any computer with Internet access using the following instructions.

Register for NAVFAC Environmental Compliance Assessment, Training, and Tracking System, by logging on to <https://environmentaltraining.ecatts.com/>. Obtain the password for registration from the Contracting Officer.

1.4.1.3 Refresher Training

This training has been structured to allow contractor personnel to receive credit under this contract and to carry forward credit to future contracts. Ensure the Environmental Manager review their training plans for new modules or updated training requirements prior to beginning work. Some training modules are tailored for specific state regulatory requirements; therefore, Contractors working in multiple states will be required to retake modules tailored to the state where the contract work is being performed.

1.4.2 Conformance with the Environmental Management System

Perform work under this contract consistent with the policy and objectives identified in the installation's Environmental Management System (EMS). Perform work in a manner that conforms to objectives and targets of the environmental programs and operational controls identified by the EMS. Support Government personnel when environmental compliance and EMS audits are conducted by escorting auditors at the Project site, answering

questions, and providing proof of records being maintained. Provide monitoring and measurement information as necessary to address environmental performance relative to environmental, energy, and transportation management goals. In the event an EMS nonconformance or environmental noncompliance associated with the contracted services, tasks, or actions occurs, take corrective and preventative actions. In addition, employees must be aware of their roles and responsibilities under the installation EMS and of how these EMS roles and responsibilities affect work performed under the contract.

Coordinate with the installation's EMS coordinator to identify training needs associated with environmental aspects and the EMS, and arrange training or take other action to meet these needs. Provide training documentation to the Contracting Officer. The Installation Environmental Office will retain associated environmental compliance records. Make EMS Awareness training completion certificates available to Government auditors during EMS audits and include the certificates in the Employee Training Records. See paragraph EMPLOYEE TRAINING RECORDS.

1.5 SPECIAL ENVIRONMENTAL REQUIREMENTS

Comply with the special environmental requirements listed here and attached at the end of this section.

Attachment B. **Data Recovery Plan** for Sites 66-07-2113, 66-07-2117, 66-07-2118, and 66-08-2981 (Fafalog), Andersen Air Force Base, Guam. Conduct data recovery for the archaeological sites that will be impacted/disturbed by the project.

Attachment C. P-012 Permits Record of Decision (PROD): Obtain all required environmental or construction permits and approvals listed in the PROD. Obtain any additional permits or approvals needed but not listed in the PROD at no cost to the Government.

Attachment D. Environmental Mitigations presented in the 2025 Final Environmental Impact Statement (**Final EIS**) for F-15 Beddown and Infrastructure Upgrade at Andersen Air Force Base, Guam. Comply with the environmental mitigation requirements.

Attachment E. Natural Resources Requirements specified in the Biological Opinion (**2025 B0**) for Expansions of Aircraft Operations Area at Northwest Field, and Munitions Storage Area (MSA-1), Andersen Air Force Base, Guam, 25 February 2025.

Attachment F. Natural Resources Performance Work Statement (PWS)

1.5.1 Abandoned Waste Debris

Refer to the Project Demolition Plan (CD-series). Remove and dispose of stockpiles and waste debris. Refer to the Visual Stockpile Observation Report included in Section **02 61 13 EXCAVATION AND HANDLING OF CONTAMINATED MATERIAL**. The site includes abandoned waste debris. Waste debris contains asbestos transite pipes and lead paints. Refer to the Hazardous Material Survey Report for the asbestos transite pipes and lead paints. The report is provided at the end of Section **02 82 00 ASBESTOS REMEDIATION**.

1.5.2 PFAS Contamination and G-RAM/LLRW

Refer to Section 02 61 13 EXCAVATION AND HANDLING OF CONTAMINATED MATERIAL; Attachment A, Soil Management Plan; and Attachment B, G-RAM/LLRW Performance Work Statement.

The project site include PFAS-impacted areas and potential General Radioactive Material (G-RAM)/Low-Level Radioactive Waste (LLRW) Area. Implement Section 02 61 13 and Section Attachments A and B.

1.5.3 Sinkhole Protection

Sinkholes are present in the vicinity of project sites. Provide the sinkhole mitigation plan and submittals for Government and GEPA review and approval. Obtain Class V Underground Injection Control (UIC) Permits for three existing sinkholes.

1.5.4 Pacific

Comply with the following state, regional and local requirements.

1.5.4.1 Control and Disposal of Ionization Smoke Detectors or Tritium Exit Signs

1.5.4.1.1 Material Bagging

Remove existing ionization smoke detectors and tritium exit signs, and place like types, together (that is same manufacturer and model number) in a plastic bag. Label the bag with the following data:

Manufacturer:	Activity:
MODEL No.:	Contract No.:
Isotope and Quantity (if known):	

1.5.4.1.2 Material Storage

Store plastic bags in 55 gallon covered drum(s). Do not seal the drum(s). Provide a label with a description of the contents and note on the label "TO BE DISPOSED OF BY RASO". Apply the label to the exterior surface of the cover and site of the drum(s). Provide a record copy of the label for each drum storage material inventory to the Contracting Officer, and the RASO.

1.5.4.2 Guam

Comply with all applicable Guam regulations, requirements, and guidance including but are not limited to: HACCP Manual; 10 GCA CH47; 10 GCA CH49; 10 GCA CH50; 10 GCA CH51; 10 GCA CH76; 22 GCA CH32; 22 GCA CH32; 22 GAR DIV1 CH1; 22 GAR DIV1 CH1; 22 GAR DIV2 CH5; 22 GAR DIV2 CH10; 22 GAR DIV3 CH15; 22 GAR DIV4 CH20; 22 GAR DIV2 CH30; 22 GAR DIV9 CH45; 22 GAR DIV10 CH50; and the CNMI and Guam Stormwater Management Manual, prepared by Horsley Witten Group Inc, dated (October 2006, as amended).

1.5.4.2.1 Demarcate Project Limits

Under General Provision section of 22 GCA CH 32, use a Professional Land Surveyor in order to layout/demarcate the project limits. Demarcate the limits of construction and use a licensed professional land surveyor to delineate project limits. The limits of construction are to be clearly

marked in the field and must be maintained throughout the duration of construction. Use durable, high-visibility tape/rope (unless a physical feature exists at the limit e.g. fence). The marked limits must be on or within the project boundary presented in the project plan.

1.6 QUALITY ASSURANCE

1.6.1 Preconstruction Survey and Protection of Features

This paragraph supplements the Contract Clause PROTECTION OF EXISTING VEGETATION, STRUCTURES, EQUIPMENT, UTILITIES, AND IMPROVEMENTS. Prior to start of any onsite construction activities, perform a [Preconstruction Survey](#) of the project site with the Contracting Officer, and take photographs showing existing environmental conditions in and adjacent to the site. Submit a report for the record. Include in the report a plan describing the features requiring protection under the provisions of the Contract Clauses, which are not specifically identified on the drawings as environmental features requiring protection along with the condition of trees, shrubs and grassed areas immediately adjacent to the site of work and adjacent to the Contractor's assigned storage area and access route(s), as applicable. The Contractor and the Contracting Officer will sign this survey report upon mutual agreement regarding its accuracy and completeness. Protect those environmental features included in the survey report and any indicated on the drawings, regardless of interference that their preservation may cause to the work under the Contract.

1.6.2 Regulatory Notifications

Provide regulatory notification requirements in accordance with federal, state and local regulations. In cases where the Government will also provide public notification (such as stormwater permitting), coordinate with the Contracting Officer. Submit copies of regulatory notifications to the Contracting Officer at least 30 days prior to commencement of work activities. Typically, regulatory notifications must be provided for the following (this listing is not all-inclusive): demolition, renovation, NPDES defined site work, construction, removal or use of a permitted air emissions source, and remediation of controlled substances (asbestos, hazardous waste, lead paint).

1.6.3 Environmental Brief

Attend an environmental brief to be included in the preconstruction meeting. Provide the following information: types, quantities, and use of hazardous materials that will be brought onto the installation; and types and quantities of wastes/wastewater that may be generated during the Contract. Discuss the results of the Preconstruction Survey at this time.

Prior to initiating any work on site, meet with the Contracting Officer and installation Environmental Office to discuss the proposed Environmental Protection Plan (EPP) or equipment local requirement. Develop a mutual understanding relative to the details of environmental protection, including measures for protecting natural and cultural resources, required reports, required permits, permit requirements (such as mitigation measures), and other measures to be taken.

1.6.4 Environmental Manager

Appoint in writing an Environmental Manager for the project site. The Environmental Manager is directly responsible for coordinating contractor

compliance with federal, state, local, and installation requirements. The Environmental Manager must ensure compliance with Hazardous Waste Program requirements (including hazardous waste handling, storage, manifesting, and disposal); implement the EPP; ensure environmental permits are obtained, maintained, and closed out; ensure compliance with Stormwater Program requirements; ensure compliance with Hazardous Materials (storage, handling, and reporting) requirements; and coordinate any remediation of regulated substances (lead, asbestos, PCB transformers, PFAS-contaminated soil, G-RAM/LLRW). This can be a collateral position; however, the person in this position must be trained to adequately accomplish the following duties: ensure waste segregation and storage compatibility requirements are met; inspect and manage Satellite Accumulation areas; ensure only authorized personnel add wastes to containers; ensure Contractor personnel are trained in 40 CFR requirements in accordance with their position requirements; coordinate removal of waste containers; and maintain the Environmental Records binder and required documentation, including environmental permits compliance and close-out. Submit [Environmental Manager Qualifications](#) to the Contracting Officer.

1.6.5 Employee Training Records

Prepare and maintain [Employee Training Records](#) throughout the term of the contract meeting applicable 40 CFR requirements. Provide Employee Training Records in the Environmental Records Binder. Ensure every employee completes a program of classroom instruction or on-the-job training that teaches them to perform their duties in a way that ensures compliance with federal, state and local regulatory requirements for RCRA Large Quantity Generator. Provide a Position Description for each employee, by subcontractor, based on the Davis-Bacon Wage Rate designation or other equivalent method, evaluating the employee's association with hazardous and regulated wastes. This Position Description will include training requirements as defined in [40 CFR 265](#) for a Large Quantity Generator facility. Submit these [Assembled Employee Training Records](#) to the Contracting Officer at the conclusion of the project, unless otherwise directed.

Train personnel to meet EPA and state requirements. Conduct environmental protection/pollution control meetings for personnel prior to commencing construction activities. Conduct additional meetings for new personnel and when site conditions change. Include in the training and meeting agenda: methods of detecting and avoiding pollution; familiarization with statutory and contractual pollution standards; installation and care of devices, vegetative covers, and instruments required for monitoring purposes to ensure adequate and continuous environmental protection/pollution control; anticipated hazardous or toxic chemicals or wastes, and other regulated contaminants; recognition and protection of archaeological sites, artifacts, waters of the United States, and endangered species and their habitat that are known to be in the area. Provide copy of the [Erosion and Sediment Control Inspector Qualifications](#) as defined by EPA Certification as required by state.

1.6.6 Non-Compliance Notifications

The Contracting Officer will notify the Contractor in writing of any observed noncompliance with federal, state or local environmental laws or regulations, permits, and other elements of the Contractor's EPP. After receipt of such notice, inform the Contracting Officer of the proposed corrective action and take such action when approved by the Contracting Officer. The Contracting Officer may issue an order stopping all or part

of the work until satisfactory corrective action has been taken. FAR 52.242-14 Suspension of Work provides that a suspension, delay, or interruption of work due to the fault or negligence of the Contractor allows for no adjustments to the contract for time extensions or equitable adjustments. In addition to a suspension of work, the Contracting Officer may use additional authorities under the contract or law.

1.7 ENVIRONMENTAL PROTECTION PLAN

The purpose of the EPP is to present an overview of known or potential environmental issues that must be considered and addressed during construction. Incorporate construction related objectives and targets from the installation's EMS into the EPP. Include in the EPP measures for protecting natural and cultural resources, required reports, and other measures to be taken. Meet with the Contracting Officer or Contracting Officer Representative to discuss the EPP and develop a mutual understanding relative to the details for environmental protection including measures for protecting natural resources, required reports, and other measures to be taken. Submit the EPP within 15 days after award of the contract ~~notice to proceed~~ and not less than 10 days before the preconstruction meeting. Submit the EPP not less than 60 calendar days before scheduled final site or building design approval. Revise the EPP throughout the project to include any reporting requirements, changes in site conditions, or contract modifications that change the project scope of work in a way that could have an environmental impact. No requirement in this section will relieve the Contractor of any applicable federal, state, and local environmental protection laws and regulations. During Construction, identify, implement, and submit for approval any additional requirements to be included in the EPP. Maintain the current version onsite.

The EPP includes, but is not limited to, the following elements:

1.7.1 General Overview and Purpose

1.7.1.1 Descriptions

A brief description of each specific plan required by environmental permit or elsewhere in this Contract such as but is not limited to:

- a. stormwater pollution prevention plan,
- b. spill control plan,
- c. solid waste management plan,
- d. wastewater and hydrostatic/hydrotesting water management plan,
- e. air pollution control plan,
- f. contaminant prevention plan,
- g. historical, archaeological, cultural resources including data recovery and archaeological monitoring,
- h. biological, natural resources, and compliance with 2025 BO
- i. sinkhole mitigation plan,

- j. traffic control plan,
- k. Hazardous, Toxic and Radioactive Waste (HTRW) Plan (PFAS-contaminated soil, G-RAM/LLRW),
- l. Non-Hazardous Solid Waste Disposal Plan including abandoned waste debris and green waste management,
- m. borrowing material plan,
- n. surplus soil management plan.

1.7.1.2 Duties

The duties and level of authority assigned to the person(s) on the job site who oversee environmental compliance, such as who is responsible for adherence to the EPP, who is responsible for spill cleanup and training personnel on spill response procedures, who is responsible for manifesting hazardous waste to be removed from the site (if applicable), and who is responsible for training the Contractor's environmental protection personnel.

1.7.1.3 Procedures

A copy of any standard or project-specific operating procedures that will be used to effectively manage and protect the environment on the project site.

1.7.1.4 Communications

Communication and training procedures that will be used to convey environmental management requirements to Contractor employees and subcontractors.

1.7.1.5 Contact Information

Emergency contact information contact information (office phone number, cell phone number, and e-mail address).

1.7.2 General Site Information

1.7.2.1 Drawings

Drawings showing locations of proposed temporary excavations or embankments for haul roads, stream crossings, jurisdictional wetlands, material storage areas, structures, sanitary facilities, storm drains and conveyances, and stockpiles of excess soil.

1.7.2.2 Work Area

Work area plan showing the proposed activity in each portion of the area and identify the areas of limited use or nonuse. Include measures for marking the limits of use areas, including methods for protection of features to be preserved within authorized work areas and methods to control runoff and to contain materials on site, and a traffic control plan.

Show where any hazardous materials or waste (e.g., asbestos, G-RAM/LLRW, contaminated soil), fuels, hazardous substances, solvents, or lubricants

will be stored. Provide a spill plan to address any releases of those materials.

1.7.2.3 Documentation

A letter signed by an officer of the firm appointing the Environmental Manager and stating that person is responsible for managing and implementing the Environmental Program as described in this contract. Include in this letter the Environmental Manager's authority to direct the removal and replacement of non-conforming work.

1.7.3 Management of Natural Resources

- a. Land resources
- b. Natural resources and tree protection including Endangered Species Act (ESA)-listed Endangered and Threatened (T&E) species
- c. Replacement of damaged landscape features
- d. Temporary construction
- e. Sinkhole protection
- f. Fish and wildlife resources (e.g., Mariana fruit bats)

1.7.4 Protection of Historical and Archaeological Resources

- a. Objectives
- b. Methods

1.7.5 Stormwater Management and Control

- a. Ground cover
- b. Erodible soils
- c. Temporary measures
 - (1) Structural Practices
 - (2) Temporary and permanent stabilization
- d. Effective selection, implementation and maintenance of Best Management Practices (BMPs).
- e. Stormwater Pollution Prevention Plan (SWPPP).

1.7.6 Protection of the Environment from Waste Derived from Contractor Operations

This item consists of the management procedures for hazardous waste to be generated. The elements of those procedures will coincide with the Installation Hazardous Waste Management Plan when within an installation. The Contracting Officer will provide a copy of the Installation Hazardous Waste Management Plan as applicable.

As a minimum, include the following:

- a. List of the types of hazardous wastes expected to be generated
- b. Procedures to ensure a written waste determination is made for appropriate wastes that are to be generated
- c. Sampling/analysis plan, including laboratory method(s) that will be used for waste determinations and copies of relevant laboratory certifications
- d. Methods and proposed locations for hazardous waste accumulation/storage (that is, in tanks or containers)
- e. Management procedures for storage, labeling, transportation, and disposal of waste (treatment of waste is not allowed unless specifically noted)
- f. Management procedures and regulatory documentation ensuring disposal of hazardous waste complies with Land Disposal Restrictions (40 CFR 268)
- g. Management procedures for recyclable hazardous materials such as lead-acid batteries, used oil, and similar
- h. Used oil management procedures in accordance with 40 CFR 279; Hazardous waste minimization procedures
- i. Plans for the disposal of hazardous waste by permitted facilities; and Procedures to be employed to ensure required employee training records are maintained.
- j. Plans for off-site reuse or disposal of surplus soil.

1.7.7 Prevention of Releases to the Environment

Procedures to prevent releases to the environment

Notifications in the event of a release to the environment

1.7.8 Regulatory Notification and Permits

List what notifications and permit applications must be made. Some permits require up to 240 days to obtain. Demonstrate that those permits have been obtained or applied for by including copies of applicable environmental permits. The EPP will not be approved until the permits have been obtained.

1.7.9 Clean Air Act Compliance

1.7.9.1 Haul Route

Submit truck and material haul routes along with a [Dirt and Dust Control Plan](#) for controlling dirt, debris, and dust on Installation roadways. As a minimum, identify in the plan the subcontractor and equipment for cleaning along the haul route and measures to reduce dirt, dust, and debris from roadways.

1.7.9.2 Pollution Generating Equipment

Identify air pollution generating equipment or processes that may require federal, state, or local permits under the Clean Air Act. Determine requirements based on any current installation permits and the impacts of the project. Provide a list of all fixed or mobile equipment, machinery or operations that could generate air emissions during the project to the Installation Environmental Office (Air Program Manager). Ensure required permits are obtained prior to installing and operating applicable equipment/processes.

1.7.9.3 Stationary Internal Combustion Engines

Identify portable and stationary internal combustion engines that will be supplied, used or serviced. Comply with 40 CFR 60 Subpart IIII, 40 CFR 60 Subpart JJJJ, 40 CFR 63 Subpart ZZZZ, and local regulations as applicable. At minimum, include the make, model, serial number, manufacture date, size (engine brake horsepower), and EPA emission certification status of each engine. Maintain applicable records and log hours of operation and fuel use. Logs must include reasons for operation and delineate between maintenance/testing, emergency, and non-emergency operation.

1.7.9.4 Refrigerants

Identify management practices to ensure that heating, ventilation, and air conditioning (HVAC) work involving refrigerants complies with 40 CFR 82 requirements. Technicians must be certified, maintain copies of certification on site, use certified equipment and log work that requires the addition or removal of refrigerant. Any refrigerant reclaimed is the property of the Government, coordinate with the Installation Environmental Office to determine the appropriate turn in location.

1.7.9.5 Air Pollution-engineering Processes

Identify planned air pollution-generating processes and management control measures (including, but not limited to, concrete batch plants, generators, spray painting, abrasive blasting, demolition, material handling, fugitive dust, and fugitive emissions). Log hours of operations and track quantities of materials used.

1.7.9.6 Compliant Materials

Provide the Government a list of SDSs for all hazardous materials proposed for use on site. Materials must be compliant with all Clean Air Act regulations for emissions including solvent and volatile organic compound contents, and applicable National Emission Standards for Hazardous Air Pollutants requirements. The Government may alter or limit use of specific materials as needed to meet installation permit requirements for emissions.

1.8 LICENSES AND PERMITS

Obtain licenses and permits required for the construction of the project and in accordance with FAR 52.236-7 Permits and Responsibilities. Notify the Government of all equipment that may require permits or special approvals that the Contractor plans to use on site. This paragraph supplements the Contractor's responsibility under FAR 52.236-7 Permits and Responsibilities.

1.9 ENVIRONMENTAL RECORDS BINDER

Maintain on-site a separate three-ring Environmental Records Binder and submit at the completion of the project. Make separate parts within the binder that correspond to each submittal listed under paragraph CLOSEOUT SUBMITTALS in this section.

1.10 SOLID WASTE MANAGEMENT PERMIT

Provide the Contracting Officer with written notification of the quantity of anticipated solid waste or debris that is anticipated or estimated to be generated by construction. Include in the report the locations where various types of waste will be disposed or recycled. Include letters of acceptance from the receiving location or as applicable; submit one copy of the receiving location state and local Solid Waste Management Permit or license showing such agency's approval of the disposal plan before transporting wastes off Government property.

1.10.1 Monthly Solid Waste Disposal Report

Monthly, submit a solid waste disposal report to the Contracting Officer. For each waste, the report will state the classification (using the definitions provided in this section), amount, location, and name of the business receiving the solid waste.

1.11 FACILITY HAZARDOUS WASTE GENERATOR STATUS

AAFB is designated as a Large Quantity Generator. Meet the regulatory requirements of this generator designation for any work conducted within the boundaries of this Installation. Comply with provisions of federal, state, and local regulatory requirements applicable to this generator status regarding training and storage, handling, and disposal of construction derived wastes.

PART 2 PRODUCTS

Not Used

PART 3 EXECUTION

3.1 PROTECTION OF NATURAL RESOURCES

Minimize interference with, disturbance to, and damage to fish, wildlife, and plants, including their habitats. Prior to the commencement of activities, consult with the Installation Environmental Office as applicable, regarding rare species or sensitive habitats that need to be protected. The protection of rare, threatened, and endangered animal and plant species identified, including their habitats, is the Contractor's responsibility. The following species are known and could be affected within the construction area:

- a. *Cycas micronesica*
- b. *Tabernaemontana rotensis* (T. rotensis)
- c. *Bulbophyllum guamense*, *Dendrobium guamense*, and *Tuberolabium guamense*
- d. Mariana fruit bats

Preserve the natural resources within the project boundaries and outside the limits of permanent work. Restore to an equivalent or improved

condition upon completion of work that is consistent with the requirements of the Installation Environmental Office or as otherwise specified. Confine construction activities to within the limits of the work indicated or specified.

3.1.1 2025 BO and NR PWS

Comply with and implement the natural resources requirements, including conservation measures and Best Management Practices (BMP), specified in Attachment E, Biological Opinion (2025 BO) and Attachment F, Natural Resources Performance Work Statement (PWS) for the project. Comply with and implement all requirements for the P-012 project site, Tarague Forest Enhancement Area (Tarague FEA), and Habitat Management Unit (HMU). The locations of Tarague FEA and HMU are presented in Attachment F1, Figures for Natural Resources Conservation. The Contractor must review, understand, and execute the 2025 BO. Prepare a Hazard Analysis and Critical Control Point (HACCP) Plan for Government review and approval.

Submit the plans and reports specified in the PWS.

- a. Qualification of qualified biologist(s)
- b. Draft Natural Resource Work Plan
- c. Final Natural Resource Work Plan
- d. Natural Resource Field Assessment Report for P-012 Construction footprint
- e. Natural Resource Field Assessment Report for Tarague Forest Enhancement Area
- f. Alignment of Ungulate Fence
- g. Draft Work Plan for Tarague Forest Enhancement Area
- h. Final Work Plan for Tarague Forest Enhancement Area
- i. Weekly Natural Resources Conservation Status Report
- j. Monthly Natural Resources Conservation Progress Report
- k. Annual Natural Resources Conservation Progress Report
- l. Draft Natural Resources Conservation Report
- m. Final Natural Resources Conservation Report

3.1.2 Flow Ways

Do not alter water flows or otherwise significantly disturb the native habitat adjacent to the project and critical to the survival of fish and wildlife, except as specified and permitted.

3.1.3 Vegetation

Except in areas to be cleared, do not remove, cut, deface, injure, or destroy trees or shrubs without the Contracting Officer's permission. Do not fasten or attach ropes, cables, or guys to existing nearby trees for

anchorages unless authorized by the Contracting Officer. Where such use of attached ropes, cables, or guys is authorized, the Contractor is responsible for any resultant damage.

Protect existing trees and critical root zones (CRZ) that are to remain to ensure they are not injured, bruised, defaced, or otherwise damaged by construction operations. Remove displaced rocks from uncleared areas. Coordinate with the Contracting Officer and Installation Environmental Office to determine appropriate action for trees and other landscape features scarred or damaged by equipment operations.

3.2 STORMWATER

Do not discharge stormwater from construction sites to the sanitary sewer. If the water is noted or suspected of being contaminated, it may only be released to the storm drain system if the discharge is specifically permitted. Obtain authorization in advance from the Installation Environmental Office for any release of contaminated water.

3.2.1 Construction General Permit

Provide a Construction General Permit as required by [40 CFR 122.26](#) or EPA General Permit. Under the terms and conditions of the permit, install, inspect, maintain BMPs, prepare stormwater erosion and sediment control inspection reports, and submit SWPPP inspection reports. Maintain construction operations and management in compliance with the terms and conditions of the general permit for stormwater discharges from construction activities.

3.2.1.1 Stormwater Pollution Prevention Plan

Submit a project-specific [Stormwater Pollution Prevention Plan](#) (SWPPP) to the Contracting Officer for approval, within 30 days of [award of the contract](#) ~~notice to proceed~~ and prior to the commencement of work. The SWPPP must meet the requirements of [40 CFR 122.26](#) and the EPA General Permit for stormwater discharges from construction sites.

Include the following:

- a. Comply with terms of the EPA general permit for stormwater discharges from construction activities. Prepare SWPPP in accordance with EPA requirements. Use EPA guide Developing your Stormwater Pollution Prevention Plan located at <https://www.epa.gov/npdes/developing-stormwater-pollution-prevention-plan-swppp> to prepare the SWPPP.
- b. Select applicable BMPs from EPA Fact Sheets located at <https://www.epa.gov/npdes/national-menu-best-management-practices-bmps-stormwater#constr> or in accordance with applicable state or local requirements.
- c. Include a completed copy of the Notice of Intent, BMP Inspection Report Template, and Stormwater Notice of Termination, except for the effective date.
- d. Comply with local additional requirements including the Commonwealth of the Northern Marianas Islands (CNMI) and the Territory of Guam, Stormwater Management Manuals (2006 or as amended). Apply and obtain a GEPA Clearing, Grubbing, Grading, and Stockpiling Permit / General

Permit Application for Earthmoving Work & Full Construction prior to relevant construction activities. The permit requires an Environmental Protection Plan.

3.2.1.2 Stormwater Notice of Intent for Construction Activities

Prepare and submit the Notice of Intent for NPDES coverage under the general permit for construction activities to the Contracting Officer for review and approval.

Submit the approved NOI and appropriate permit fees onto the appropriate federal or state agency for approval. No land disturbing activities may commence without permit coverage. Maintain an approved copy of the SWPPP at the onsite construction office, and continually update as regulations require, reflecting current site conditions.

Comply with additional state and local requirements.

3.2.1.3 SWPPP Inspection Reports

Submit "SWPPP Inspection Reports" to the Contracting Officer in accordance with EPA Construction General Permit.

3.2.1.4 Stormwater Pollution Prevention Plan Compliance Notebook

Create and maintain a three ring binder of documents that demonstrate compliance with the Construction General Permit. Include a copy of the permit Notice of Intent, proof of permit fee payment, SWPPP and SWPPP update amendments, inspection reports and related corrective action records, copies of correspondence with the EPA and GEPA Permitting Agency, and a copy of the permit Notice of Termination in the binder. At project completion, the notebook becomes property of the Government. Provide the compliance notebook to the Contracting Officer.

3.2.1.5 Stormwater Notice of Termination for Construction Activities

Submit a Notice of Termination to the Contracting Officer for approval once construction is complete and final stabilization has been achieved on all portions of the site for which the permittee is responsible. Once approved, submit the Notice of Termination to the appropriate state or federal agency. Prepare [as-built topographic survey](#) information required by the permitting agency for certification of the stormwater management system, and provide to the Contracting Officer.

3.2.2 Erosion and Sediment Control Measures

Provide erosion and sediment control measures in accordance with state and local laws and regulations. Preserve vegetation to the maximum extent practicable.

Erosion control inspection reports may be compiled as part of a stormwater pollution prevention plan inspection reports.

3.2.2.1 Erosion Control

Prevent erosion by mulching, Compost Blankets, Geotextiles, temporary slope drains. Stabilize slopes by chemical stabilization, sodding, seeding, or such combination of these methods necessary for effective erosion control. Use of hay bales is prohibited. Use of sandbags as

stormwater BMPs is not allowed.

3.2.2.2 Sediment Control Practices

Implement sediment control practices to divert flows from exposed soils, temporarily store flows, or otherwise limit runoff and the discharge of pollutants from exposed areas of the site. Implement sediment control practices prior to soil disturbance and prior to creating areas with concentrated flow, during the construction process to minimize erosion and sediment laden runoff. Include the following devices: silt fence, temporary diversion dikes, storm drain inlet protection. Location and details of installation and construction are indicated on the drawings.

3.2.3 Work Area Limits

Mark the areas that need not be disturbed under this Contract prior to commencing construction activities. Mark or fence isolated areas within the general work area that are not to be disturbed. Protect monuments and markers before construction operations commence. Where construction operations are to be conducted during darkness, all markers must be visible in the dark. Personnel must be knowledgeable of the purpose for marking and protecting particular objects.

3.2.4 Contractor Facilities and Work Areas

Place field offices, staging areas, stockpile storage, and temporary buildings in areas designated on the drawings or as directed by the Contracting Officer. Move or relocate the Contractor facilities only when approved by the Government. Provide erosion and sediment controls for onsite borrow and spoil areas to prevent sediment from entering nearby waters. Control temporary excavation and embankments for plant or work areas to protect adjacent areas.

3.2.5 Municipal Separate Storm Sewer System (MS4) Management

Comply with the Installation's MS4 permit requirements. [Comply with local requirements.](#)

3.3 SURFACE AND GROUNDWATER

3.3.1 Cofferdams, Diversions, and Dewatering

Construction operations for dewatering, removal of cofferdams, tailrace excavation, and tunnel closure must be constantly controlled to maintain compliance with existing state water quality standards and designated uses of the surface water body. Comply with the Guam water quality standards and anti-degradation provisions. Do not discharge excavation ground water to the sanitary sewer, storm drains, or to surface waters without prior specific authorization in writing from the Installation Environmental Office or Contracting Officer. Discharge of hazardous substances will not be permitted under any circumstances. Use sediment control BMPs to prevent construction site runoff from directly entering any storm drain or surface waters.

If the construction dewatering is noted or suspected of being contaminated, it may only be released to the storm drain system if the discharge is specifically permitted. Obtain authorization for any contaminated groundwater release in advance from the Installation Environmental Officer and the federal or state authority, as applicable.

Discharge of hazardous substances will not be permitted under any circumstances.

3.3.2 Waters of the United States

Do not enter, disturb, destroy, or allow discharge of contaminants into waters of the United States.

3.4 PROTECTION OF CULTURAL RESOURCES

3.4.1 Archaeological Resources

Existing archaeological resources within the work area are shown on Attachment B, [Data Recovery Plan](#).

Protect these resources and be responsible for their preservation during the life of the Contract. If, during excavation or other construction activities, any previously unidentified or unanticipated historical, archaeological, and cultural resources are discovered or found, activities that may damage or alter such resources will be suspended. Resources covered by this paragraph include, but are not limited to: any human skeletal remains or burials; artifacts; shell, midden, bone, charcoal, or other deposits; rock or coral alignments, pavings, wall, or other constructed features; and any indication of agricultural or other human activities. Upon such discovery or find, immediately notify the Contracting Officer so that the appropriate authorities may be notified and a determination made as to their significance and what, if any, special disposition of the finds must be made. Cease all activities that may result in impact to or the destruction of these resources. Secure the area and prevent employees or other persons from trespassing on, removing, or otherwise disturbing such resources. The Government retains ownership and control over archaeological resources.

3.4.2 Qualified Archaeologists

Provide qualified archaeologists. Archaeologists must have a graduate degree in archaeology, anthropology, or closely related field and meet the Secretary of the Interior's Professional Qualifications for Archaeology. The qualified archaeologist(s) can be one person or more than one person who meets the qualifications listed above. Submit the [Qualification of Archaeologist\(s\)](#).

3.4.3 P-012 Project Site

3.4.3.1 Archaeological Monitoring: Not Required

Archaeological monitoring is not required. However, in the event that unidentified archaeological resources or human remains are discovered, the archaeologist retained by the Contractor, Contracting Officer, and AAFB Cultural Resources Manager (CRM) must be immediately notified.

The on-site manager must halt all action in the vicinity of the discovery and secure the area per the guidance of the archaeological monitors.

The AAFB CRM and archaeologist will assess the discovery and make the appropriate notifications and follow-up actions. Any archaeological resources discovered during the project and construction must be reported and documented in accordance with the [ICRMP](#) SOP 8 and 9. The area will be released back for construction activities by the Contracting Officer once

AAFB CRM has made the notification that the inadvertent discovery has been mitigated.

3.4.3.2 Data Recovery

The qualified archaeologist retained by the Contractor must execute and implement Attachment B, Data Recovery Plan for Sites 66-07-2113, 66-07-2117, and 66-07-2118 for the archaeological sites. Conduct data recovery for the archaeological sites that will be impacted/disturbed by the P-012 project. Provide the [Reports and Submittals required by Data Recovery Plan](#).

3.4.4 Tarague Forest Enhancement Area (FEA)

Tarague FEA is likely to contain significant subsurface deposits. Provide archaeological monitoring for all ground disturbing activities, including vegetation clearance, installation of ungulate fencing, T&E transplanting, and invasive species clearance. The qualified archaeologists must provide monitoring. Submit an [Archaeological Monitoring and Discovery Plan](#) (AMDP) for the Government review and approval. Anticipate review by the Guam State Historic Preservation Office (Guam SHPO).

If subsurface deposits are encountered during archaeological monitoring, note the observation. Additional testing is not required. Install the ungulate fence and transplant plants nearby areas without subsurface deposits.

Provide an [End of Field \(EOF\) Letter for Archaeological Monitoring - Tarague FEA](#) within 5 working days after completion of ungulate fencing. Submit a [Draft Archaeological Monitoring Report-Tarague FEA](#) within 30 calendar days after completion of ungulate fencing. Submit the [Final Archaeological Monitoring Report-Tarague FEA](#) within 30 calendar days after receipt of Government comments.

Provide a [weekly archaeological monitoring report-Tarague FEA](#).

3.5 AIR RESOURCES

Equipment operation, activities, or processes will be in accordance with [40 CFR 64](#) and state air emission and performance laws and standards. Use ultra-low sulfur diesel fuel.

3.5.1 Preconstruction Air Permits

Notify the Air Program Manager, through the Contracting Officer, at least 6 months prior to bringing equipment, assembled or unassembled, onto the Installation, so that air permits can be secured. Necessary permitting time must be considered in regard to construction activities. Clean Air Act (CAA) permits must be obtained prior to bringing equipment, assembled or unassembled, onto the Installation.

Confirm that these permits have been obtained.

3.5.2 Oil or Dual-fuel Boilers and Furnaces

Provide product data and details for new, replacement, or relocated fuel fired boilers, heaters, or furnaces to the Installation Environmental Office (Air Program Manager) through the Contracting Officer. Data to be

reported include: equipment purpose (water heater, building heat, process), manufacturer, model number, serial number, fuel type (oil type, gas type) size (MMBTU heat input). Provide in accordance with paragraph PRECONSTRUCTION AIR PERMITS.

3.5.3 Burning

Burning is prohibited on the Government premises.

3.5.4 Class I and II ODS Prohibition

Class I and II ODS are Government property and must be returned to the Government for appropriate management. Coordinate with the Installation Environmental Office to determine the appropriate location for turn in of all reclaimed refrigerant.

3.5.5 Venting of Refrigerant

Accidental venting of a refrigerant is a release and must be reported immediately to the Contracting Officer. Intentional venting of refrigerants (including most Non-ODS substitute refrigerants) is prohibited per 40 CFR 82.

3.5.6 EPA Certification Requirements

Heating and air conditioning technicians must be certified through an EPA-approved program. Maintain copies of certifications at the employees' places of business; technicians must carry certification wallet cards, as provided by environmental law.

3.5.7 Dust Control

Keep dust down at all times, including during nonworking periods. Sprinkle or treat, with dust suppressants, the soil at the site, haul roads, and other areas disturbed by operations. Dry power brooming will not be permitted. Instead, use vacuuming, wet mopping, wet sweeping, or wet power brooming. Air blowing will be permitted only for cleaning nonparticulate debris such as steel reinforcing bars. Only wet cutting will be permitted for cutting concrete blocks, concrete, and bituminous concrete. Do not unnecessarily shake bags of cement, concrete mortar, or plaster. Since these products contain Crystalline Silica, comply with the applicable OSHA standard, 29 CFR 1910.1053 or 29 CFR 1926.1153 for controlling exposure to Crystalline Silica Dust.

3.5.7.1 Particulates

Dust particles, aerosols and gaseous by-products from construction activities, and processing and preparation of materials (such as from asphaltic batch plants) must be controlled at all times, including weekends, holidays, and hours when work is not in progress. Maintain excavations, stockpiles, haul roads, permanent and temporary access roads, plant sites, spoil areas, borrow areas, and other work areas within or outside the project boundaries free from particulates that would exceed 40 CFR 50, state, and local air pollution standards or that would cause a hazard or a nuisance. Sprinkling, chemical treatment of an approved type, baghouse, scrubbers, electrostatic precipitators, or other methods will be permitted to control particulates in the work area. Sprinkling, to be efficient, must be repeated to keep the disturbed area damp. Provide sufficient, competent equipment available to accomplish these tasks.

Perform particulate control as the work proceeds and whenever a particulate nuisance or hazard occurs. Comply with state and local visibility regulations.

3.5.7.2 Abrasive Blasting

Blasting operations cannot be performed without prior approval of the Installation Air Program Manager. The use of silica sand is prohibited in sandblasting.

Provide tarpaulin drop cloths and windscreens to enclose abrasive blasting operations to confine and collect dust, abrasive agent, paint chips, and other debris. Perform work involving removal of hazardous material in accordance with 29 CFR 1910.

3.5.8 Odors

Control odors from construction activities. The odors must be in compliance with state regulations and local ordinances and may not constitute a health hazard.

3.6 WASTE MINIMIZATION

Minimize the use of hazardous materials and the generation of waste. Include procedures for pollution prevention/ hazardous waste minimization in the Hazardous Waste Management Section of the EPP. Obtain a copy of the installation's Pollution Prevention/Hazardous Waste Minimization Plan for reference material when preparing this part of the EPP. If no written plan exists, obtain information by contacting the Contracting Officer. Describe the anticipated types of the hazardous materials to be used in the construction when requesting information.

3.6.1 Salvage, Reuse and Recycle

Identify anticipated materials and waste for salvage, reuse, and recycling. Describe actions to promote material reuse, resale or recycling. To the extent practicable, all scrap metal must be sent for reuse or recycling and will not be disposed of in a landfill.

Include the name, physical address, and telephone number of the hauler, if transported by a franchised solid waste hauler. Include the destination and, unless exempted, provide a copy of the state or local permit (cover) or license for recycling.

3.6.2 Nonhazardous Solid Waste Diversion Report

Maintain an inventory of nonhazardous solid waste diversion and disposal of construction and demolition debris. Submit a report to Installation Environmental Office through the Contracting Officer on the first working day after each fiscal year quarter, starting the first quarter that nonhazardous solid waste has been generated. Include the following in the report:

Construction and Demolition (C&D) Debris Disposed	cubic yards or tons, as appropriate
C&D Debris Recycled	cubic yards or tons, as appropriate
C&D Debris Composted	cubic yards or tons, as appropriate
Total C&D Debris Generated	cubic yards or tons, as appropriate
Waste Sent to Waste-To-Energy Incineration Plant (This amount must not be included in the recycled amount)	cubic yards or tons, as appropriate

3.7 WASTE MANAGEMENT AND DISPOSAL

3.7.1 Waste Determination Documentation

Complete a Waste Determination form (provided at the pre-construction conference) for Contractor-derived wastes to be generated. All potentially hazardous solid waste streams that are not subject to a specific exclusion or exemption from the hazardous waste regulations (e.g., scrap metal, domestic sewage) or subject to special rules, (lead-acid batteries and precious metals) must be characterized in accordance with the requirements of [40 CFR 262.11](#) or corresponding applicable state or local regulations. Base waste determination on user knowledge of the processes and materials used, and analytical data when necessary. Consult with the Installation environmental staff for guidance on specific requirements. Attach support documentation to the Waste Determination form. As a minimum, provide a Waste Determination form for the following waste (this listing is not exhaustive): oil- and latex-based painting and caulking products, solvents, adhesives, aerosols, petroleum products, and containers of the original materials.

3.7.1.1 Sampling and Analysis of Waste

3.7.1.1.1 Waste Sampling

Sample waste in accordance with [EPA SW-846](#). Clearly mark each sampled drum or container with the Contractor's identification number, and cross reference to the chemical analysis performed.

3.7.1.1.2 Laboratory Analysis

Follow the analytical procedure and methods in accordance with the [40 CFR 261](#). Provide analytical results and reports performed to the Contracting Officer. Coordinate all activities with Installation Hazardous Waste Manager.

3.7.1.1.3 Analysis Type

Identify hazardous waste by analyzing for the following characteristics: ignitability, corrosivity, reactivity, toxicity based on TCLP results. Laboratory must be certified by the National Environmental Laboratory Accreditation Program (NELAP) or DoD Environmental Laboratory Accreditation Program (ELAP).

3.7.2 Solid Waste Management

3.7.2.1 Project Solid Waste Disposal Documentation Report

Provide copies of the waste handling facilities' weight tickets, receipts, bills of sale, and other sales documentation. In lieu of sales documentation, a statement indicating the disposal location for the solid waste that is signed by an employee authorized to legally obligate or bind the firm may be submitted. The sales documentation Contractor certification must include the receiver's tax identification number and business, EPA or state registration number, along with the receiver's delivery and business addresses and telephone numbers. For each solid waste retained for the Contractor's own use, submit the information previously described in this paragraph on the solid waste disposal report. Prices paid or received do not have to be reported to the Contracting Officer unless required by other provisions or specifications of this Contract or public law.

3.7.2.2 Control and Management of Solid Wastes

Pick up solid wastes, and place in covered containers that are regularly emptied. Do not prepare or cook food on the project site. Prevent contamination of the site or other areas when handling and disposing of wastes. At project completion, leave the areas clean. Employ segregation measures so that no hazardous or toxic waste will become co-mingled with non-hazardous solid waste. Transport solid waste off Government property and dispose of it in compliance with 40 CFR 260, state, and local requirements for solid waste disposal. A Subtitle D RCRA permitted landfill is the minimum acceptable offsite solid waste disposal option. Verify that the selected transporters and disposal facilities have the necessary permits and licenses to operate. Segregate and separate treated wood components disposed at a lined landfill approved to accept this waste in accordance with local and state regulations. Solid waste disposal offsite must comply with most stringent local, state, and federal requirements, including 40 CFR 241, 40 CFR 243, and 40 CFR 258.

Manage hazardous material used in construction, including but not limited to, aerosol cans, waste paint, cleaning solvents, contaminated brushes, and used rags, in accordance with 49 CFR 173.

3.7.3 Control and Management of Hazardous Waste

Do not dispose of hazardous waste on Government property. Do not discharge any waste to a sanitary sewer, storm drain, or to surface waters or conduct waste treatment or disposal on Government property without written approval of the Contracting Officer and Installation Hazardous Waste Manager.

3.7.3.1 Hazardous Waste/Debris Management

Identify construction activities that will generate hazardous waste or debris. Provide a documented waste determination for resultant waste streams. Identify, label, handle, store, and dispose of hazardous waste or debris in accordance with federal, state, and local regulations, including 40 CFR 261, 40 CFR 262, 40 CFR 263, 40 CFR 264, 40 CFR 265, 40 CFR 266, and 40 CFR 268.

Manage hazardous waste in accordance with the approved Hazardous Waste

Management Section of the EPP. Store hazardous wastes in approved containers in accordance with 49 CFR 173 and 49 CFR 178. Hazardous waste generated within the confines of Government facilities is identified as being generated by the Government. Prior to removal of any hazardous waste from Government property, hazardous waste manifests must be signed by personnel from the Installation Environmental Office. Do not bring hazardous waste onto Government property. Provide the Contracting Officer with a copy of waste determination documentation for any solid waste streams that have any potential to be hazardous waste or contain any chemical constituents listed in 40 CFR 372-SUBPART D.

3.7.3.2 Waste Storage/Satellite Accumulation/90 Day Storage Areas

Accumulate hazardous waste at satellite accumulation points and in compliance with 40 CFR 262 and applicable state or local regulations. Individual waste streams will be limited to 55 gallons of accumulation (or one quart for acutely hazardous wastes). If the Contractor expects to generate hazardous waste at a rate and quantity that makes satellite accumulation impractical, the Contractor may request a temporary 90-day or 180-day, as appropriate, accumulation point be established. Submit a request in writing to the Contracting Officer and provide the following information (Attach Site Plan to the Request):

Contract Number	_____
Contractor	_____
Haz/Waste or Regulated Waste POC	_____
Phone Number	_____
Type of Waste	_____
Source of Waste	_____
Emergency POC	_____
Phone Number	_____
Location of the Site	_____

Attach a Waste Determination form for the expected waste streams. Allow 10 working days for processing this request. Additional compliance requirements (e.g., training and contingency planning) that may be required are the responsibility of the Contractor. Barricade the designated area where waste is being stored and post a sign identifying as follows:

"DANGER - UNAUTHORIZED PERSONNEL KEEP OUT"

3.7.3.3 Hazardous Waste Disposal

3.7.3.3.1 Responsibilities for Contractor's Disposal

Provide hazardous waste manifest to the Installations Environmental Office for review, approval, and signature prior to shipping waste off Government property.

3.7.3.3.1.1 Services

Provide service necessary for the final treatment or disposal of the hazardous material or waste in accordance with 40 CFR 260 - 40 CFR 279, local, and state, laws and regulations, and the terms and conditions of the Contract within 60 days after the materials have been generated. These services include necessary personnel, labor, transportation, packaging, detailed analysis (if required for disposal or transportation, include manifesting or complete waste profile sheets, equipment, and compile documentation).

3.7.3.3.1.2 Samples

Obtain a representative sample of the material generated for each job done to provide waste stream determination.

3.7.3.3.1.3 Analysis

Analyze each sample taken and provide analytical results to the Contracting Officer. See paragraph WASTE DETERMINATION DOCUMENTATION.

3.7.3.3.1.4 Labeling

During waste accumulation label all containers in accordance with 40 CFR 262. Prior to offering a waste for off-site transport, determine the Department of Transportation's (DOT's) proper shipping names for waste in accordance with 49 CFR 172 (each container requiring disposal) and demonstrate to the Contracting Officer how this determination is developed and supported by the sampling and analysis requirements contained herein. Label all containers of hazardous waste with the words "Hazardous Waste" or other words to describe the contents of the container in accordance with 40 CFR 262 and applicable state or local regulations.

3.7.3.3.2 Contractor Disposal Turn-In Requirements

Hazardous waste generated must be disposed of in accordance with the following conditions to meet installation requirements:

- a. Drums must be compatible with waste contents and drums must meet DOT requirements for 49 CFR 173 for transportation of materials.
- b. Band drums to wooden pallets.
- c. No more than three 55 gallon drums or two 85 gallon over packs are to be banded to a pallet.
- d. Band using 1-1/4 inch minimum band on upper third of drum.
- e. Provide label in accordance with 49 CFR 172.101.
- f. Leave 3 to 5 inches of empty space above volume of material.

3.7.3.4 Universal Waste Management

GEPA has not adopted the Universal Regulation Rule. Comply with the Guam EPA regulations and installation specific requirements.

Mercury is prohibited in the construction of this facility, unless specified otherwise, and with the exception of mercury vapor lamps and

fluorescent lamps. Dumping of mercury-containing materials and devices such as mercury vapor lamps, fluorescent lamps, and mercury switches, in rubbish containers is prohibited. Remove without breaking, pack to prevent breakage, and transport out of the activity in an unbroken condition for disposal as directed.

3.7.3.5 Electronics End-of-Life Management

Recycle or dispose of electronics waste, including, but not limited to, used electronic devices such computers, monitors, hard-copy devices, televisions, mobile devices, in accordance with 40 CFR 260-262, state, and local requirements, and installation instructions.

3.7.3.6 Disposal Documentation for Hazardous and Regulated Waste

Contact the Contracting Officer or designated representative for the facility RCRA identification number that is to be used on each manifest.

Submit a copy of the applicable EPA and or state permit(s), manifest(s), or license(s) for transportation, treatment, storage, and disposal of hazardous and regulated waste by permitted facilities. Hazardous or toxic waste manifests must be reviewed, signed, and approved by the Contracting Officer before the Contractor may ship waste. To obtain specific disposal instructions, coordinate with the Installation Environmental Office. Refer to location special requirements for the Installation Point of Contact information.

3.7.4 Releases/Spills of Oil and Hazardous Substances

3.7.4.1 Response and Notifications

Exercise due diligence to prevent, contain, and respond to spills of hazardous material, hazardous substances, hazardous waste, sewage, regulated gas, petroleum, lubrication oil, and other substances regulated in accordance with 40 CFR 300. Maintain spill cleanup equipment and materials at the work site. In the event of a spill, take prompt, effective action to stop, contain, curtail, or otherwise limit the amount, duration, and severity of the spill/release. In the event of any releases of oil and hazardous substances, chemicals, or gases; immediately (within 15 minutes) notify the Installation Fire Department, the Installation Command Duty Officer, the Installation Environmental Office, the Contracting Officer and the state or local authority.

Submit verbal and written notifications as required by the federal (40 CFR 300.125 and 40 CFR 355), state, local regulations and instructions. Provide copies of the written notification and documentation that a verbal notification was made within 20 days. Spill response must be in accordance with 40 CFR 300 and applicable state and local regulations. Contain and clean up these spills without cost to the Government.

3.7.4.2 Clean Up

Clean up hazardous and non-hazardous waste spills. Reimburse the Government for costs incurred including sample analysis materials, clothing, equipment, and labor if the Government will initiate its own spill cleanup procedures, for Contractor- responsible spills, when: Spill cleanup procedures have not begun within one hour of spill discovery/occurrence; or, in the Government's judgment, spill cleanup is

inadequate and the spill remains a threat to human health or the environment.

3.7.5 Mercury Materials

Immediately report to the Environmental Office and the Contracting Officer instances of breakage or mercury spillage. Clean mercury spill area to the satisfaction of the Contracting Officer.

Do not recycle a mercury spill cleanup; manage it as a hazardous waste for disposal.

3.7.6 Wastewater

3.7.6.1 Disposal of Wastewater

Disposal of wastewater must be as specified below.

3.7.6.1.1 Treatment

Do not allow wastewater from construction activities, such as onsite material processing, concrete curing, foundation and concrete clean-up, water used in concrete trucks, and forms to enter water ways or to be discharged. Dispose of the construction- related waste water off-Government property in accordance with 40 CFR 403, state, regional, and local laws and Prior to disposal, submit a WIS to the Installation Environmental Office and have the results reviewed and approved by the Contracting Officer prior to being discharged or disposed of off-Government property.

3.7.6.1.2 Surface Discharge

For discharge of ground water, obtain a state or federal permit specific for pumping and discharging ground water prior to surface discharging. Surface discharge in accordance with federal, state, and local laws and regulations. Surface discharge in accordance with the requirements of the NPDES or state STORMWATER DISCHARGES FROM CONSTRUCTION SITES permit.

3.7.6.1.3 Land Application

Water generated from the flushing of lines after disinfection or hydrostatic testing must be land- applied in accordance with federal, state, and local laws and regulations for land application upon receiving approval from the Installation Environmental Office.

3.8 HAZARDOUS MATERIAL MANAGEMENT

Include hazardous material control procedures in the Accident Prevention Plan (APP), in accordance with Section 01 35 26 GOVERNMENTAL SAFETY REQUIREMENTS. Address procedures and proper handling of hazardous materials, including the appropriate transportation requirements. Do not bring hazardous material onto Government property that does not directly relate to requirements for the performance of this contract. Submit an SDS and estimated quantities to be used for each hazardous material to the Contracting Officer prior to bringing the material on the installation. Typical materials requiring SDS and quantity reporting include, but are not limited to, oil and latex based painting and caulking products, solvents, adhesives, aerosol, and petroleum products. Use hazardous materials in a manner that minimizes the amount of hazardous waste

generated. Containers of hazardous materials must have National Fire Protection Association labels or their equivalent. Certify that hazardous materials removed from the site are hazardous materials and do not meet the definition of hazardous waste, in accordance with 40 CFR 261 and state and installation requirements.

3.8.1 Contractor Hazardous Material Inventory Log

Submit the "Contractor Hazardous Material Inventory Log"(found at: <https://www.wbdg.org/dod/ufgs/forms-graphics-tables>), which provides information required by (EPCRA Sections 312 and 313) along with corresponding SDS, to the Contracting Officer at the start and at the end of construction (30 days from final acceptance), and update no later than January 31 of each calendar year during the life of the contract. Keep copies of the SDSs for hazardous materials onsite. At the end of the project, provide the Contracting Officer with copies of the SDSs, and the maximum quantity of each material that was present at the site at any one time, the dates the material was present, the amount of each material that was used during the project, and how the material was used.

The Contracting Officer may request documentation for any spills or releases, environmental reports, or off-site transfers.

3.9 PREVIOUSLY USED EQUIPMENT

Clean previously used construction equipment prior to bringing it onto the project site. Equipment must be free from soil residuals, egg deposits from plant pests, noxious weeds, and plant seeds. Consult with the U.S. Department of Agriculture jurisdictional office for additional cleaning requirements.

3.10 CONTROL AND MANAGEMENT OF ASBESTOS-CONTAINING MATERIAL (ACM)

Manage and dispose of asbestos- containing waste in accordance with all applicable federal, state, and local (or Host Nation) requirements. Refer to Section 02 82 00 ASBESTOS REMEDIATION. Manifest asbestos-containing waste and provide the manifest to the Contracting Officer. Notifications to the regulatory authorities and Installation Air Program Manager are required before starting any asbestos work.

3.11 CONTROL AND MANAGEMENT OF LEAD-BASED PAINT (LBP)

Manage and dispose of lead-contaminated waste in accordance with 40 CFR 745 and Section 02 83 00 LEAD REMEDIATION. Manifest any lead-contaminated waste and provide the manifest to the Contracting Officer.

3.12 CONTROL AND MANAGEMENT OF POLYCHLORINATED BIPHENYLS (PCBs)

Manage and dispose of PCB-contaminated waste in accordance with 40 CFR 761 and Section 02 84 33 REMOVAL AND DISPOSAL OF POLYCHLORINATED BIPHENYLS (PCBs).

3.13 CONTROL AND MANAGEMENT OF LIGHTING BALLAST AND LAMPS CONTAINING PCBs

Manage and dispose of contaminated waste in accordance with 40 CFR 761. Refer to Section 02 84 16 HANDLING OF LIGHTING BALLASTS AND LAMPS CONTAINING PCBs AND MERCURY.

3.14 MILITARY MUNITIONS

In the event military munitions, as defined in 40 CFR 260, are discovered or uncovered, immediately stop work in that area and immediately inform the Contracting Officer.

~~Provide Munitions and Explosives of Concern (MEC) screening and escort for any ground-disturbing activities, including vegetation clearance at Tarague FEA.~~

3.15 PETROLEUM, OIL, LUBRICANT (POL) STORAGE AND FUELING

POL products include flammable or combustible liquids, such as gasoline, diesel, lubricating oil, used engine oil, hydraulic oil, mineral oil, and cooking oil. Store POL products and fuel equipment and motor vehicles in a manner that affords the maximum protection against spills into the environment. Manage and store POL products in accordance with EPA 40 CFR 112, and other federal, state, regional, and local laws and regulations. Use secondary containments, dikes, curbs, and other barriers, to prevent POL products from spilling and entering the ground, storm or sewer drains, stormwater ditches or canals, or navigable waters of the United States. Describe in the EPP (see paragraph ENVIRONMENTAL PROTECTION PLAN) how POL tanks and containers must be stored, managed, and inspected and what protections must be provided. Storage of fuel on the project site must be in accordance with EPA, state, and local laws and regulations and paragraph OIL STORAGE INCLUDING FUEL TANKS.

3.15.1 Used Oil Management

Manage used oil generated on site in accordance with 40 CFR 279. Determine if any used oil generated while onsite exhibits a characteristic of hazardous waste. Used oil containing 1,000 parts per million of solvents is considered a hazardous waste and disposed of at the Contractor's expense. Used oil mixed with a hazardous waste is also considered a hazardous waste. Dispose in accordance with paragraph HAZARDOUS WASTE DISPOSAL.

3.15.2 Oil Storage Including Fuel Tanks

Provide secondary containment and overfill protection for oil storage tanks. A berm used to provide secondary containment must be of sufficient size and strength to contain the contents of the tanks plus 5 inches freeboard for precipitation. Construct the berm to be impervious to oil for 72 hours that no discharge will permeate, drain, infiltrate, or otherwise escape before cleanup occurs. Use drip pans during oil transfer operations; adequate absorbent material must be onsite to clean up any spills and prevent releases to the environment. Cover tanks and drip pans during inclement weather. Provide procedures and equipment to prevent overfilling of tanks. If tanks and containers with an aggregate aboveground capacity greater than 1320 gallons will be used onsite (only containers with a capacity of 55 gallons or greater are counted), provide and implement a Spill Prevention Control and Countermeasure (SPCC) plan meeting the requirements of 40 CFR 112. Do not bring underground storage tanks to the installation for Contractor use during a project. Submit the SPCC plan to the Contracting Officer for approval.

Monitor and remove any rainwater that accumulates in open containment dikes or berms. Inspect the accumulated rainwater prior to draining from a containment dike to the environment, to determine there is no oil sheen

present.

3.16 INADVERTENT DISCOVERY OF PETROLEUM-CONTAMINATED SOIL OR HAZARDOUS WASTES

If petroleum-contaminated soil, or suspected hazardous waste is found during construction that was not identified in the Contract documents, immediately notify the Contracting Officer. Do not disturb this material until authorized by the Contracting Officer.

3.17 CHLORDANE

Evaluate excess soils and concrete foundation debris generated during the demolition of housing units or other wooden structures for the presence of chlordane or other pesticides prior to reuse or final disposal.

3.18 SOUND INTRUSION

Make the maximum use of low-noise emission products, as certified by the EPA. Blasting or use of explosives are not permitted without written permission from the Contracting Officer, and then only during the designated times. Confine pile-driving operations to the period between 8 a.m. and 4 p.m., Monday through Friday, exclusive of holidays, unless otherwise specified.

Keep construction activities under surveillance and control to minimize environment damage by noise. Comply with the provisions of the Guam rules.

3.19 POST CONSTRUCTION CLEANUP

Clean up areas used for construction in accordance with Contract Clause: "Cleaning Up". Unless otherwise instructed in writing by the Contracting Officer, remove traces of temporary construction facilities such as haul roads, work area, structures, foundations of temporary structures, stockpiles of excess or waste materials, and other vestiges of construction prior to final acceptance of the work. Grade parking area and similar temporarily used areas to conform with surrounding contours.

3.20 ATTACHMENTS

Attachment A. Contractor Hazardous Material Inventory Log

Attachment B. Data Recovery Plan for Sites 66-07-2113, 66-07-2117, 66-07-2118, and 66-08-2981 (Fafalog), Andersen Air Force Base, Guam

Attachment C. P-012 Permits Record of Decision

Attachment D. 2025 Final Environmental Impact Statement (**Final EIS**) for F-15 Beddown and Infrastructure Upgrade at Andersen Air Force Base, Guam.

Attachment E. Biological Opinion (**2025 BO**) for Expansions of Aircraft Operations Area at Northwest Field, and Munitions Storage Area (MSA-1), Andersen Air Force Base, Guam, 25 February 2025.

Attachment F. Natural Resources Performance Work Statement (NR PWS)

Attachment G. Low Impact Development (LID) Data Cards

-- End of Section --

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 01 57 19
TEMPORARY ENVIRONMENTAL CONTROLS

ATTACHMENT F.
NATURAL RESOURCES
PERFORMANCE WORK STATEMENT (NR PWS)

9 January 2026

Amendment Log	
3/5/2026	Section 5.2 Tarague FEA, Item f: Delete “and Munitions and Explosives of Concern (MEC) screening.”

Applied Biology Department. The applicator must have a DoD certification or Guam certification in Pest Control. All use must be reported using the NAVFAC Online Pesticide Reporting System.

- c. To avoid cross contamination between each specimen harvested, wash down all equipment (10% bleach solution) prior to each subsequent removal.
- d. Once the specimen has been removed, rid the plant specimen of any remaining debris and loose plant material, followed by the remaining treatments in this order: AUL fungicide, AUL insecticide, a cycad base wash (10% bleach solution), followed by application of a plant sealant (aerosol tree sealant), and root hormone.
- e. Once harvested and treated as specified, pot each specimen into potting containers using Government-approved rooting media. Salvaged basal shoots must be processed and transplanted in the nursery in less than one week of salvage. Once potted, ensure safe transport and offload of all potted specimens to a secure Government approved nursery location.
- f. During transportation, basal shoots must be covered for protection from sun and wind exposure. A clean blanket can be used to avoid damage during transport.
- g. Invasive species within a 20-foot radius around salvaged plants must be removed and maintained to ensure no more than 15 percent of vegetation is invasive species within the plots.

If plants do not meet the survival criteria, implement adaptive management techniques to include, but not limited to, seed collection, tissue germination, and plant division and/or stem cuttings, as suitable to the species, to meet outplanting success targets.

5.1.4.2.2 Transplanting/Maintenance

Determine when plants are ready to be outplanted. Plants must be outplanted before they become root bound in their containers to promote new growth. After transplanting, maintenance of ESA-listed species may include watering, fertilizing, pesticide treatment, use of support structures, or invasive species removal. Invasive species must be removed within a 20-ft (6-m) radius around transplanted vegetation. The maximum percent cover of invasive understory, overstory, and vine plants permitted within the Tarague FEA and details of removal will be determined following the field assessment.

If outplanted plants do not survive, notify the Contracting Officer and AAFB Natural Resource Specialist immediately and provide an explanation for why they died. Alternative techniques may be implemented if it is determined that the Natural Resource Work Plan approved methodology is not successful. Any remaining plant material at the completion of the performance period must be turned over to the AAFB.

5.1.5 Protect and Monitor ESA-Listed Species to be Remained

Protect and monitor the ESA-listed plant species that are not salvaged within 10 ft (3 m) of the construction perimeter once every 6 months during the entire construction period, including site preparation.

5.2 Tarague FEA

Implementing all conservation measures and BMPs for Tarague FEA specified in the 2025 BO. The requirements include the following, but are not limited to:

- a. Prepare a work plan for forest enhancement that describes the forest enhancement area preparation, native seed collection, and forest enhancement (transplanting) methods.
- b. Conduct a biological survey for the 151-ac (61-ha) FEA. The biological survey may include recording

existing ESA-listed species (including a health assessment), native and non-native canopy trees, and invasive species.

- c. Install an approximately 2.5-mile-long permanent ungulate-proof fence along the forest enhancement area.
- d. Remove invasive plant species and invasive species (e.g., CRF, LFA, BTS).
- e. After the ungulate-proof fencing is installed, eradicate ungulates (pigs and deer) within the fence limit.
- f. Any ground-disturbing activities at the Tarague FEA require archaeological monitoring and Munitions and Explosives of Concern (MEC) screening (Amend: 3/5/2026).

5.2.1 Draft and Final Work Plans for Tarague Forest Enhancement Area

Provide Draft and Final work plans for Tarague Forest Enhancement Area that describes the forest enhancement area preparation, native seed collection, and forest enhancement (transplanting) methods. The activities associated with forest enhancement (transplanting), such as, installation of ungulate fence including fence route and specifications; removal of vegetation; water lines, or invasive species removal, must adhere to recommended buffer distances (typically 3 ft [1 m]) to avoid adverse impacts to in-situ ESA-listed species.

5.2.2 Install Ungulate-Proof Fence

Install an approximately 2.5-mile-long permanent ungulate-proof fence along the forest enhancement area. Construction of ungulate-proof fencing must occur prior to, or concurrent with, the vegetation removal at the construction footprint.

Provide approximate alignment of the ungulate fence line and include it in the Work Plans for Tarague Forest Enhancement Area. The approximate alignment must be in accordance with the FEA alignment shown in Figure F1; however, the alignment must be adjusted to avoid sensitive environmental areas such as existing ESA-listed T&E species and potential cultural areas. Removal of vegetation for installation of fencing will adhere to recommended buffer distances (3-ft wide on each side of the fence) to avoid adverse impacts to in-situ ESA-listed T&E species. Thus, a 6-ft wide corridor with the fence must be situated.

Fencing must meet the JRM ungulate fencing standards (Refer to Attachment F5). Provide vegetation clearance and maintenance as needed to ensure integrity of the fence. Four (4) pedestrian gates must be provided. The preferred pedestrian gates are presented in the Attachment F1, Figures. No vehicle access gates are required. The ungulate-proof fencing does not require any controlled area signage.

There will be no salvage/transplanting ESA-listed species along the ungulate-proof fencing area/route since disturbing ESA-listed species will be avoided. Within 72 hours after a major storm or high-wind event (wind speeds equal to or greater than 39 miles per hour or 34 knots), ungulate fencing must be inspected for breaches, and fencing must be repaired or replaced immediately after detection until the contract is completed.

5.3 Reporting, GIS Maps, Database

5.3.1 Weekly Natural Resources Conservation Status Report

During the salvage and transplantation phase, a Weekly Natural Resources Status Report to the Contracting Officer on Monday of the previous week. The report must document the Contractor's diligence in salvaging T&E species, task status, anticipated delays, major milestones, and outlook to the following week's tasks.

SECTION 09 96 53.13

SILICONE ELASTOMERIC COATINGS
11/25

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM INTERNATIONAL (ASTM)

ASTM D412 (2016; R 2021) Standard Test Methods for
Vulcanized Rubber and Thermoplastic
Elastomers - Tension

ASTM D1653 (2013; R 2021) Standard Test Methods for
Water Vapor Transmission of Organic
Coating Films

ASTM D6904 (2022) Standard Practice for Resistance to
Wind-Driven Rain for Exterior Coatings
Applied on Masonry

SOCIETY FOR PROTECTIVE COATINGS (SSPC)

SSPC SP 13/NACE No.6 **(2024) Surface Preparation of Concrete**

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for Contractor Quality Control approval. Submit the following in accordance with Section **01 33 00**
SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Equipment List

SD-03 Product Data

Silicone Elastomeric Coating

Primer

Sealants

SD-04 Samples

Color Selection Guide

1.3 QUALITY ASSURANCE

Submit an **equipment list** consisting of a list of proposed equipment to be used in performance of construction work.

1.3.1 Pre-application Meeting

Pre-application meeting scheduling shall be coordinated with the Contracting Officer. The meeting shall be attended by the Contractor, the Contracting Officer's designated personnel, personnel directly responsible for the installation of the wall system, related window/door assembly work, mechanical and electrical work, other trades interfacing with the wall work, and representative of the wall materials manufacturer. Before beginning wall work, provide a copy of meeting notes and action items to all attending parties. Note action items requiring resolution prior to start of wall work.

After approval of submittals and before performing wall system installation work, hold a pre-application conference to review the following:

- a. Drawings and specifications and submittals related to the wall work.
- b. Wall system components installation.
- c. Procedure for the wall manufacturer's technical representative's onsite inspection and acceptance of the wall substrate, the name of the manufacturer's technical representatives, the frequency of the onsite visits, distribution of copies of the inspection reports from the manufacturer's technical representative.
- d. Contractor's plan for coordination of the work of the various trades involved in proving the wall system and other components impacting the walls.
- e. Quality control plan for the wall system installation.
- f. Property protection measures.
- g. Safety requirements.

1.3.2 Silicone Elastomeric Wall Coating System Mock-up

Provide a mockup of the silicone elastomeric wall coating system. Apply product in an area designated by the Contracting Officer in an area of not less than 50 square feet. Include all components specified as representative of the complete system. Notify the Contracting Officer a minimum of 48 hours prior to test the application. Select a test area representative of conditions to be covered including window or door openings, flashings, and penetrations, as applicable.

1.4 DELIVERY, STORAGE, AND HANDLING

Deliver special coating materials to the project in their original containers bearing manufacturer's name, descriptive label, and coating formulations. Provide new and unopened containers.

Store special coating materials in tightly closed containers in a covered, well-ventilated area where they are not exposed to excessive heat, fumes, sparks, flame, or direct sunlight. ~~Protect water-based coatings against freezing.~~

Store solvents, thinners, and equipment cleaners with the same care as the

coating materials with ambient temperatures continuously maintained at a minimum 45 degrees F.

1.5 ENVIRONMENTAL REQUIREMENTS

Application is not recommended when ~~the temperature is below 20 degrees F or if frost or~~ moisture is present on the surfaces to be coated.

Application not recommended to surfaces above 120 degrees F. The time to complete cure of this product is dependent upon temperature and humidity. Under basic conditions 72 degrees F and 50 percent RH this material can attain a tack-free surface in 1-2 hours. ~~As temperatures drop towards freezing, application should proceed with caution due to the possibility of moisture (dew, frost) on surfaces to be coated as well as longer curing times relative to application of a second or touchup coat (recoat), (and vice versa as temperatures increase).~~

When spraying coating in windy conditions, take precautionary measures to avoid excessive overspray. It is suggested to withhold spraying when wind speeds exceed 10 mph.

Contact product technical services for additional time-related precautionary measure when application is proceeding under winter temperatures and conditions.

1.6 WARRANTY

Provide silicone elastomeric wall coating system material and workmanship warranties meeting specified requirements. Provide revision or amendment to manufacturer's standard warranty as required to comply with the specified requirements.

Furnish the silicone elastomeric wall coating manufacturer's 15-year standard wall system materials and installation workmanship warranty, including flashing, components, trim, and accessories necessary for a watertight wall system construction. Make warranty directly to the Government, commencing at the time of Government's acceptance of the wall work.

PART 2 PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

Submit manufacturer's catalog data including manufacturer's name and identification. Include detailed data analysis of each special coating material required for the project, with all the coating constituents measured as percentages of the total weight of the coating. Also provide manufacturer's data concerning application, thinning, and average coverage per gallon

2.2 MATERIALS

2.2.1 Silicone Elastomeric Coating

One-component, elastomeric, silicone, high-solids, UV resistant, wall coating shall have the following values when tested for specified test methods.

Typical Properties - Supplied		
Density	WPSTM P14	11.5 lb/gal
Solids by Volume	WPSTM C19	72 percent
Solids by Weight	WPSTM C19	76 percent
Tack Free Time	WPSTM E86	Less than 2 hours
Skin Over Time		30 minutes
Viscosity	WPSTM C560	15,000 centipoise
Total VOC	EPA Method 24	34 g/L
Typical Properties - Cured		
Tensile Strength	ASTM D412	245 psi
Elongation	ASTM D412	395 percent
Vapor Permeance (10 Mils DFT)	ASTM D1653	8.40 perms
Resistance to Wind Driven Rain	ASTM D6904	Pass

Submit manufacturer's [color selection guide](#). Color to be selected and approved by Contracting Officer

2.3 PRIMER

Primers shall be as recommended by the coating manufacturer for the substrate to be covered. Submit literature including material description, physical properties, recommended storage conditions, Material Safety Data Sheets, and shelf life expiration date.

2.4 SEALANTS

Sealants shall be as recommended by the coating manufacturer. Submit literature including material description, physical properties, recommended storage conditions, Material Safety Data Sheets, and shelf life expiration date.

PART 3 EXECUTION

3.1 EXAMINATION

Exam surfaces and correct defects that may adversely affect the wall system application or performance.

3.2 PREPARATION

3.2.1 Surface Preparation

Protect adjacent materials and equipment against damage from spillage, dripping, and spatter of coating materials. Leave clean building

materials and equipment with all damaged surfaces corrected. Provide "WET PAINT" signs to indicate newly painted surfaces.

Protect work of other trades against damage from coating operation. Correct damage by cleaning, repairing, replacing, and recoating, as approved by the Contracting Officer, and leave in an undamaged condition. At completion of construction activities of other trades, touch up and restore damaged or defaced coated surfaces.

~~Provide forced ventilation for interior spaces during application and drying of coatings to prevent the buildup of toxic or explosive concentrations of solvent vapors.~~

Provide fire extinguishers of the required quantity and correct type to combat flammable liquid fires.

Dispose of rags that are used to wipe up coating materials, solvents, and thinners by drenching with water and placing them in a covered metal container

3.2.2 Cleaning

At end of each workday, remove rubbish, empty cans, rags, and other discarded materials from Project site.

After completing coating application, clean spattered surfaces. Remove spattered coatings by washing, scraping, or other methods. Do not scratch or damage adjacent finished surfaces.

Clean application equipment promptly and thoroughly with a suitable solvent after each use and stored in a clean, covered, well-ventilated container.

3.2.3 Concrete Surfaces

Clean dirt, oil, grease, and incompatible paints from substrates to ensure bonding. Coordination of shop-applied prime coats with silicone elastomerics coatings is critical. Remove incompatible primers. Reprime substrate with compatible primers as required to produce coating systems indicated.

Allow concrete to cure for a minimum of 30 days before coating.

Fill cracks and holes with approved patching materials and sand smooth. All cracks greater than hairline width, approximately 1/16 inch, must be ground out and patch with sealant or an appropriate concrete patching compound approved by coating manufacturer. Structural cracks of any thickness must be repaired with approved material and stabilized to prevent movement.

3.2.3.1 Concrete Substrates

Remove release agents, curing compounds, efflorescence, and chalk. Maximum allowable moisture content of concrete is 12 percent. Measure moisture content with an electronic moisture meter.

Clean surfaces with pressurized water. Use pressure range of 1500 to 4000 psi at 6 inch to 12 inch.

Comply with ~~SSPC 7/NACE No.4 (NACE No. 4), "Brush-Off Blast Cleaning"~~
SSPC SP 13/NACE No.6 for abrasive cleaning.

3.3 APPLICATION

Do not perform application of silicone elastomeric wall coating in damp or rainy weather. Apply coating in accordance with the coating manufacturer's recommendation, ~~and as specified in damp or rainy weather.~~

Ensure coating application is done by skilled applicators. Ensure surfaces to receive coating are clean, dry, and structurally sound, ~~and free of frost and frozen materials. As temperatures drop towards freezing, application should proceed with caution due to the possibility of moisture (dew, frost) on surfaces to be coated as well as longer curing times relative to application of a second or touchup coat (recoat).~~ Apply coating with clean, high-quality application equipment.

Apply uniform, pinhole-free coating in 2 separate coats at spreading rate required to achieve a total minimum dry film thickness of 0.010 inch (10 mils/254 microns). Apply coating in accordance with manufacturer's instructions.

- a. Each application should be applied at a wet thickness of 0.07 inches (7 mils/190 microns) per coat. Wet coating thickness may be estimated by using a wet film thickness gauge. Square foot application rates are theoretical (Maximum 240 ft²/gallon per coat on a smooth surface) and are for estimation purposes only. A mockup must be applied to determine the actual coverage rate needed to provide a pinhole free film at the recommended dry film thickness.
- b. The second coat may be applied when the first coat is tack free to the touch. A tack free condition will usually take at least one hour at 70 to 80 degrees F. (Cooler temperatures will require more time. Complete cure of the coating will typically take 3 to 7 days and can be indicated by absence of odor.
- c. Apply architectural coating from top to bottom of substrate. Work down vertical surface and cover rundown in process. Avoid excessive overlapping.
- d. Apply architectural coating free of cloudiness, spotting, laps, brush marks, roller tracks, and other surface imperfections. Cut in color breaks and terminations with sharp lines.
- e. Apply additional coats as required to provide cured film with uniform coverage, finish, color, and appearance.

Do not dilute coating without consulting with coating manufacturer. Keep containers closed when not in use to avoid contamination. Apply primer, if required, ~~on wood and metallic surfaces in accordance with~~ per manufacturer's required field testing or instructions. Follow manufacturers instructions for application. Allow primer to dry before applying coating.

Avoid over spray of coating. Over spray and misapplied coating should be removed immediately in accordance with manufacturer's instructions while it is still uncured. Repair or replace surfaces damaged by overspray or misapplied coating as determined by Contracting Officer.

3.3.1 Brush Application

Use clean, proper size brushes for high-quality application of the specified coating materials. Brush out slow-dry coatings. Brush out quick-dry coatings only enough to spread out evenly.

3.3.2 Roller Application

Use clean roller covers of the proper nap length, nap texture, and material for high-quality application of the specified coating materials.

Ensure roller application is equivalent in all respects to the same coats applied by high-quality brush application.

3.3.3 Spray Application

Apply spray coatings as equivalent in all respects to the same coats applied by high quality brush application. Permit each spray coat to cure before the succeeding coat is applied. Do not double back with application equipment, for the purpose of building up film thickness of two coats in one operation.

Cover surfaces adjacent to sprayed areas to prevent damage from overspray, coating rebound, and spray drift.

3.4 FIELD QUALITY CONTROL

3.4.1 Field Test

Government may take dry-film tests from time to time on finished surfaces. Apply additional coatings to surfaces where there is less than the minimum specified dry-film thickness.

3.4.2 Repairing

Remove damaged and unacceptable portions of completed work and replace with new work to match adjacent surfaces at no additional cost to the Government.

3.5 CLEANING

Remove temporary coverings and protection of surrounding areas and surfaces.

3.6 PROTECTION

Protect applied coating from rain or damage until fully cured.

-- End of Section --

THIS PAGE INTENTIONALLY LEFT BLANK