

PERFORMANCE WORK STATEMENT
INSTALLATION OF TECHNICAL SERVICES GROUP 501015 IN X-RAY VAULT
BUILDING 536
JOINT BASE CHARLESTON

- **GENERAL REQUIRMENTS:** This performance work statement (PWS) is designed to define the expectations and deliverables for those certified service technicians and the company that will assist the 437th MXS Joint Base Charleston for the installation of the Technical Services Group (TSG) 501015 unit in the x-ray vault. TSG has upgraded LED and conversion of the TSG 501015 interlock and now needs to remove and replace old unit and connect new unit in x-ray vault.
- **SCOPE OF WORK:**
 - The certified service technicians shall perform all repairs and updates as required to get the X-ray vault interlock system, located in Building 536 on Joint Base Charleston operational so we can x-ray machine without a waver. The vendor shall provide all certified service technicians to carry out all work and operations as necessary.
 - TSG technicians will remove the existing monitoring system from the room and replace it with a TSG 501015 wired appropriately.
 - The switches on the doors will be evaluated. They will be replaced with TSG 503008 CDRH switch included with the 501015, if necessary.
 - If necessary, Federal Signal Red Beacons included with the 501015 will be installed to replace existing beacons.
 - The 501015 Interface box will be properly installed as well as the cable set.
 - Technicians will evaluate software and installation to verify proper operation.
 - TSG will remove any unusable components, cabling, etc., and prepare them for base disposal.
 - TSG will leave the area clean upon completion.
 - TSG will provide basic training on the use of the interlock to personnel available at the completion of the installation.
 - Completed installation will be in compliance with US Code of Federal Regulations: 21CFR1020.40
- **GENERAL INFORMATION:** 437 MXS hours of operation are 06:30AM to 12:00AM, Monday through Friday, unless otherwise notified by the Non-Destructive Inspection Supervision.