

Area of Interest (Aol) – FM200 System Inspection and Repairs

Federal Agency: Army

Office: Army Contracting Command – Anniston Army Depot (ACC-ANAD)

Aol Title: FM200 System Inspection and Repairs

CSO Aol Number: Aol #0007

Aol Release Date: 20 April 2026

Responses: See **W911KF-25-S-C002** for procedure details

Questions and Answers:

1. How many of each system is located within the buildings? **Please review the attachments QD89-FM200-Bldg List and QD89-FM200-Inspection Schedule for this information.**

2. What is the “not-to-exceed” repair budget? Are we supposed to give that number, or is that something the gov’t is providing? It says repairs are based on inspection findings, meaning we won’t know what needs to be repaired until an inspection is completed. **This information will not be given award.**

3. What is the “not-to-exceed” emergency budget? Are we supposed to give that number or is that the something the gov’t is providing? **This information will not be given until award.**

4. Other than the cleaning of the detectors, what other “maintenance and repair” items need to be included? **Please review the attachment QD89-FM200-Inspection Schedule for this information. The Activity column has the required Inspection, Test, and Maintenance labeled with the frequency noted under the Periodic Frequency column.**

5. The Aol just says to verify hydro-test dates... Will hydro-testing of the cylinders be required? If so, we will need to know the size and quantity of all the cylinders. **Yes, hydrotesting is required. Please review the attachments QD89-FM200-Bldg List and QD89-FM200-Inspection Schedule for this information.**

6. Is pricing to be included in the form of basic year plus four option years. In other quotes of this type a requirement to price each building individual is that a requirement here. **The brief must include a ROM price sufficient for the Government to assess general affordability per 3.2.1(4) of the Commercial Solutions Opening.**

7. What type of maintenance is required and on what items. **Please review the attachments QD89-FM200-Bldg List and QD89-FM200-Inspection Schedule for this information.**

8. Can you provide detailed information for the suppression systems requiring inspections on this contract. We need to know how much agent, how many detectors, and how many links are on each system to provide an accurate proposal. **Please review the attachments QD89-FM200-Bldg List and QD89-FM200-Inspection Schedule for this information.**

Additional questions will not be accepted in relation to this Aol.

1. Overview

- ACC-ANAD is seeking solutions for **semi-annual inspection, testing, maintenance, and repair** of Clean Agent systems (FM-200/HFC-227), Carbon Dioxide (CO₂) systems, and Kitchen Hood fire extinguishing systems at Anniston Army Depot (ANAD). The resulting contract will include **one base year plus four option years**.
- Interested parties should review the full CSO posting on **SAM.gov** for submission and evaluation procedures.
- ACC-ANAD is not obligated to extend a request for proposal or make an award as a result of this CSO Aol; all awards are subject to the availability of funds and successful negotiations. This CSO Aol is not an authorization to begin performance, and in no way obligates the Government for any costs incurred by the Offeror associated with developing a Response. Prior to commencement of any activities associated with performance under this CSO Aol, the Government will issue a written directive or contractual document signed by the Contracting Officer with appropriate consideration established. ACC-ANAD reserves the right to modify the requirements of this CSO Aol.

2. General & Administrative Requirements

2.1 Contractor Responsibilities & Qualifications

- **Site Familiarization:** Mandatory pre-work site visit.
- **Personnel Qualifications:** Technicians must be licensed and experienced for the testing, inspection, and maintenance in the following systems, Fike, Ansul, Notifier, Pyro-Chem, and all associated peripheral equipment for each product.
- **National Institute for Certifications in Engineering Technologies (NICET) Certification:** Required; proof submitted with proposal.

- **Uniform Standards:** Uniform apparel is required for all personnel.

2.2 Safety & Environmental Compliance

- **OSHA Compliance:** Full adherence to 29CFR1926/1910 and ANAD safety rules.
- **Environmental Regulations:** Must comply with federal, state, local, and Army environmental rules (including AR 200-1).
- **Training:** Visitor safety training and annual RCRA training required.
- **Hot Work:** Requires ANAD Fire Department permit.

2.4 Required Submittals

- **Site-Specific Safety Plan & QC Plan** (30 days prior)
- **Safety Data Sheets** (before work)
- **Work Schedule** (14 days after award; monthly updates)
- **Certifications** (with proposal)
- **Inspection Reports** (within 14 days of inspections)

3. Scope of Work

3.1 System Types & Locations

The contractor will service three system categories across 16 buildings:

System Type	Locations
Kitchen Hood Systems	Bldgs. 47, 78, 141, 1500
FM-200 Systems	Bldgs. 52, 53, 79, 96, 97, 362, 363, 513
HFC-227 / CO ₂ Production Systems	Bldgs. 128, 410, 474, 475

3.2 Inspection & Testing Requirements

All work must comply with **National Fire Protection Association (NFPA) 12, 17A, 72, 96, 2001** and manufacturer guidance.

Tasks include:

- Functional testing of detection, alarm, and releasing devices
- Visual inspection of cylinders, piping, and nozzles

- Verification of cylinder weight, pressure, and hydro-test dates
- Simulation of discharge circuits and manual pulls
- Verification of alarm transmission and equipment shutdown
- Installation of new inspection tags
- Submission of detailed inspection reports with recommendations

3.3 System-Specific Requirements

- **Kitchen Hoods:** Replace fusible links and blow-off caps at first semi-annual inspection.
- **FM-200/CO₂:** Clean detectors, test battery backup, verify shutdown/evacuation circuits.
- **System Shutdowns:** Require ANAD Fire Department approval before any system shutdown for testing.

4. Remediation & Emergency Work

4.1 Remediation (Repairs)

- Annual **not-to-exceed** repair budget.
- Repairs based on inspection findings.
- **Parts over \$500 require prior Contracting Officer approval.**
- Repairs billed as Firm Fixed Price (FFP).

4.2 Emergency Work

- Separate **not-to-exceed** emergency budget.
- Emergency = imminent threat requiring immediate action.
- **Technician must be on-site within 24 hours** of Contracting Officer Representative (COR) request; work completed within 48 hours.
- All emergency work requires COR approval.

5. Aol Constraints

- Offerors must be registered in **SAM.gov**.

6. Submission Instructions

- A written solution must be submitted via email to the Contracting Officer and Contract Specialist listed below **by 4:00 PM CDT Wednesday, 20 May 2026** with the subject line:
 - **SOLUTION for Aol 0007 FM200 System Inspection and Repairs**
- Late submissions will not be evaluated.
- All Aol questions must be submitted **by 4:00 PM CDT, 4 May 2026** with the subject line:
 - **QUESTIONS for Aol 0007 FM200 System Inspection and Repair**
- Late questions will not be answered.
- **Aol Close Date:** 4:00 PM CDT, 20 May 2026

7. Points of Contact

- Aol questions can be sent to:
 - **Contracting Officer:** troy.m.gaddy2.civ@army.mil
 - **Contract Specialist:** katherine.b.fuller2.civ@army.mil
 - **CSO Aol Contracting Officer:** amber.e.burdett.civ@army.mil
 - **CSO Aol POC:** diana.m.pritchettponder.civ@army.mil