

1503060 – Pavement Clearance	
Spec Item	Title
1	General Information
1.1	Concept of Operations
2	Management And Administration
2.1	Definitions and Acronyms
2.2	Personnel
2.2.1	Certification, Training, and Licensing
2.3	Special Requirements
2.3.1	Safety
2.3.2	Equipment Restrictions
2.3.3	Airfield Equipment Restrictions
2.3.4	Work Identification
2.3.5	Communication
2.3.5.1	Airfield Communications
2.4	References and Technical Documents
3	Recurring Work
3.1	Pavement Sweeping Services
3.1.1	Roads and Other Paved Surfaces
3.1.2	Airfield Pavement Surfaces
3.2	Pavement Clearance Service Orders
4	Non-Recurring Work

1503060 - Pavement Clearance		
Spec Item	Title	Description
1	General Information	
1.1	Concept of Operations	The intent of 1503060 Pavement Clearance is to specify the requirements related to pavement sweeping of major paved surfaces, e.g., streets, parking lots and sidewalks and other paved areas located away from building perimeter and removal of periodic volcanic ash deposits resulting from Mt. Etna eruptions, and will include recurring and non-recurring services. Sweeping of exterior surfaces adjacent to buildings is detailed in Technical Specification 1503010 Custodial.

1503060 - Pavement Clearance		
Spec Item	Title	Description
2	Management And Administration	
2.1	Definitions and Acronyms	Definitions and Acronyms are listed in J-1503060-01.
2.2	Personnel	In addition to the Employee Requirements specified in Annex 2, the Contractor shall provide personnel with the qualifications, technical knowledge, experience and skill required to efficiently provide pavement clearance services and as specified below:
2.2.1	Certification, Training, and Licensing	An airfield drivers license is required prior to driving within the airfield boundaries (fenceline). Contractor personnel will complete the Airfield Vehicle Operators Course (AVOC) and pass written test per NAVAIR 00-80T-124, NASSIGINST 3710-1R, and NASSIGINST 3721-16.
2.3	Special Requirements	
2.3.1	Safety	Refer to Annex 0200000, Spec Item 2.9, Contractor Safety Program. The Contractor shall comply with safety requirements for pavement clearance operations on airfields as specified in Advisory Circular (AC) No. 150/5210-23, Ground Vehicle Operations on Airports and Advisory Circular (AC) No., 150/5200-30C Airport Winter Safety and Operations.
2.3.2	Equipment Restrictions	Equipment used shall have rubber type tires, tracks are not acceptable.
2.3.3	Airfield Equipment Restrictions	All equipment used to clear debris, volcanic ashes or snow on the airfield must comply with the Naval Air Station (NAS) and FAA requirements. Equipment specifically designed for airfield and runway clearing shall be used to clear areas on airfield, around radar, airfield taxiway, runway sidelights and over runway center lights.
2.3.4	Work Identification	The Contractor shall identify and recommend non-recurring work as appropriate to the KO.
2. 3.5	Communication	The Contractor shall coordinate all access to performance areas such as airfields with appropriate Government authority, and be in radio contact with the controlling authority during work performance.
2.3.5.1	Airfield Communications	All airfield communications shall be coordinated through the KO. The KO will coordinate with Air Operations (Air Ops) to obtain permission for the Contractor to communicate/operate directly with Air Ops.
2.4	References and Technical Documents	References and Technical Documents are listed in J-1503060-02.

1503060 - Pavement Clearance				
Spec Item	Title	Performance Objective	Related Information	Performance Standard
3	Recurring Work	Contractor shall provide pavement clearance to achieve a cleared appearance and safe use of paved surfaces.	Service Level Standards are defined by Commander, Navy Installations Command (CNIC) for Navy Shore Commands. Service Level Standards for pavement clearance are specified as shown in J-150305003. The Contractor shall comply with the EM-385-1-1 Safety Manual and the Italian Safety norms, and all FAA and DoD requirements to sweep around all aircraft parked on ramp areas. No work shall start prior to obtaining all approvals from the KO. Debris resulting from pavement clearance operations shall be removed and disposed of off station in accordance to current environmental protection rules and regulations. All facilities will remain in operation during pavement clearance operations; therefore, the Contractor shall manage work execution in such way to reduce to the minimum possible work performance impact with facility daily operations. The Contractor shall provide an annual Pavement Sweeping Schedule per Section F. Pavement clearance working areas, frequencies and site maps are included in J-1503060-04.	Paved surfaces are clear, safe, and passable in accordance with the specified Service Level Standards.
3.1	Pavement Sweeping Services	The Contractor shall sweep paved surfaces to ensure paved surfaces are clear.	The Contractor shall provide pavement sweeping to remove volcanic ash, winter abrasives and other debris, improve the appearance of paved areas, improve the safety of paved areas, reduce maintenance costs by keeping the drainage systems clean and, reduce pollutants entering the storm drain system.	Paved surfaces are swept per the schedule and in accordance with specified Service Level Standards.

1503060 - Pavement Clearance				
Spec Item	Title	Performance Objective	Related Information	Performance Standard
3.1.1	Roads and Other Paved Surfaces	The Contractor shall sweep roads and other paved surfaces to ensure they are clear.	Roads and other paved surfaces include roads, parking areas, sidewalks, walkways, aprons, porch areas, smoking areas, entrance/canopy areas, external stairs/steps, recreational areas, bleachers, terraces, running tracks, open storage and other similar areas. The Contractor shall sweep roads per the schedule and frequency specified in J-1503060-04. Informational Note: The Government has found on previous contracts that the frequency and schedule for sweeping of roads and paved surfaces as shown in the Working Areas, Frequencies and Site Maps provided in J-1503060-04 has maintained services at an acceptable level. If the severity of weather makes it impracticable to sweep during the scheduled times, the Contractor shall coordinate with the KO to reschedule services.	Roads and other paved surfaces are clear in accordance with specified Service Level Standards.
3.1.2	Airfield Pavement Surfaces	The Contractor shall sweep airfield pavement to ensure surfaces are clear.	Airfield pavement surfaces include runways, taxiways, and parking aprons, including tie-down points and depressions as shown on Site Maps provided in J-1503060-04 Airfield sweeping shall be accomplished with an airfield certified vacuum sweeper. The use of a standard road sweeper is not authorized. The Contractor shall receive clearance from the airfield operations center and coordinate with Air Ops for FOD walk downs prior to commencing sweeping operations for airfield pavement surfaces. The Contractor shall sweep airfield pavement surfaces per the schedule and frequency specified in J-1503060-04.	Airfield pavement surfaces are swept in accordance with specified operational requirements. Airfield is free of Foreign Object Debris (FOD).

1503060 - Pavement Clearance				
Spec Item	Title	Performance Objective	Related Information	Performance Standard
			The Contractor shall comply with all FAA and DoD requirements to sweep around all aircraft parked on ramp areas. Sweep as scheduled except during periods in which the severity of weather, as deemed by Air Ops and directed by KO, makes it impracticable to sweep. The Contractor shall coordinate with the KO to reschedule services.	
3.2	Pavement Clearance Service Orders	The Contractor shall perform pavement clearance service order work in a timely manner to accomplish any pavement clearance work identified within the entire boundary of the installation to ensure requirements are responded to and completed in accordance with specified standards.	The Contractor shall receive pavement clearance service orders in accordance with the work reception requirements in Annex 2. The Contractor shall schedule and perform pavement clearance service orders in a way that minimize disruptions to customers and Government operations. The Government may issue service orders for work requirements at any location within the defined boundaries of this contract for any reason at the discretion of the KO. Service orders will include a wide variety of work. Anticipated pavement clearance service order data including limits of liability are provided in J-1503050-05. The Contractor may invoice for completed pavement clearance service orders. The Contractor shall not invoice for incomplete pavement clearance service orders and pavement clearance service orders not issued. A modification will be processed at the end of each period of performance to deduct for pavement clearance service orders not issued and incomplete pavement clearance service orders. Deduction will be based on the unit prices specified in Attachment J-0200000-12 ELINs.	Pavement clearance service order work is completed within the period of performance specified in J-1503050-05 or on the pavement clearance service order. Pavement clearance service orders are signed by the original requestor or PAR prior to being closed.

1503060 - Pavement Clearance				
Spec Item	Title	Performance Objective	Related Information	Performance Standard
			The Contractor shall submit a monthly summary of completed pavement clearance service orders per Section F.	

1503060 – Pavement Clearance				
Spec Item	Title	Performance Objective	Related Information	Performance Standard
4	Non-Recurring Work	Non-Recurring work may be ordered utilizing DoD FEDMALL in accordance with Section H or on a task order in accordance with the PROCEDURES FOR ISSUING ORDERS clause in Section G. The order will specify the exact locations and types of work to be accomplished. The period of performance will be specified in each order.	Refer to Non-Recurring Work ELINs for task listings, descriptions and related requirements. All periods of performance are measured from issue date of order to acceptance of the work.	Performance Standards for Non-Recurring work will be the same as those in Spec Item 3 where applicable.