

SECTION J
DOCUMENTS, EXHIBITS, AND OTHER ATTACHMENTS
TABLE OF CONTENTS

ATTACHMENT NUMBER	ATTACHMENT TITLE
J-0200000-01	DEFINITIONS AND ACRONYMS
J-0200000-02	DIRECTIVES, INSTRUCTIONS, AND REFERENCES
J-0200000-03	GOVERNMENT-FURNISHED FACILITIES LIST
J-0200000-04	FORMS
J-0200000-05	SERVICE PROVIDER INFORMATION
J-0200000-06	ASSET INFORMATION
J-0200000-06.a	ASSET SPECIFICATION
J-0200000-07	NAVFAC MAXIMO DATA REPORTING
J-0200000-08	NAVFAC MAXIMO SYSTEM ACCESS PROCEDURES
J-0200000-09	CONTRACTOR HAZARDOUS MATERIAL INVENTORY LOG
J-0200000-10	OIL AND HAZARDOUS SUBSTANCE SPILL RESPONSE PROCEDURES
J-0200000-11	NAVAL HOSPITAL DISASTER EXERCISE SUPPORT REQUIREMENTS
J-0200000-12	EXHIBIT LINE ITEM NUMBERS

ATTACHMENT J-0200000-01
DEFINITIONS AND ACRONYMS

DEFINITION	DESCRIPTION
Assessment	A general term referring to either a survey or inspection of a facility to determine condition.
Asset	A general term used to refer to an item, such as a component, system, building or facility, which is managed by an automated data management program.
Business Management System (BMS)	A web-based tool that provides a systematic method for the management of business processes, common practices, and process quality improvements that produce and support the most efficient and effective delivery of NAVFAC's products and services.
Competent Person	A person who has the professional experience and training necessary to identify existing and predictable hazards at a work or service environment, and who has the authority to take prompt and corrective action to eliminate or remove dangers from the environment. One who can identify existing and predictable hazards in the working environment or working conditions that are dangerous to personnel and who has authorization to take prompt corrective measures to eliminate them.
Component Inventory Management Unit (CIMU)	An organization of like-kind real property into manageable maintenance units. CIMU is a building component, group of components or component assemblies, serving a specific purpose in a facility that can be expected to follow a common and predictable lifecycle behavior. This class of non-equipment will include items such as exterior walls, exterior windows, interior finishing, and roofs. This class of equipment will include items such as fan coil units, air handling units, lighting, and water closets. CIMUs can include one or more items of installed equipment typically subject to routine scheduled maintenance.
Confined Work Space	A space that is large enough and so configured that a person may bodily enter a space (such as in tanks, vessels, silos, storage bins, hoppers, vaults, pits, and like spaces where there is limited means of entry) and is hindered or restricted from escaping during an emergency.
Contracting Officer (KO)	That individual with the authority to enter, administer, and/or terminate contracts and make related determinations and findings. The term includes certain authorized representatives of the Contracting Officer acting within the limits of their authority as delegated by the Contracting Officer.
Contracting Officer's Representative (COR)	The individual appointed by the KO is responsible for monitoring the Contractor's technical compliance and progress, relative to assigned contract(s)/orders(s), based on the contract requirements specified in the PWS and in accordance with the PAP. The COR performs a variety of contract administration duties that include oversight of PA, documenting and rating Contractor performance, reviewing invoices, and acceptance of work. Assignment as a COR is a collateral duty typically performed by the FSCM or SPAR.
Contractor	That entity or its representative is responsible for the delivery of the services or materials specified in this contract, as designated by contract award. The term Contractor as used herein refers to both the prime Contractor and any subcontractors. The prime Contractor shall insure that subcontractors comply with the provision of this contract.
Contractor Representative	That individual appointed by the Contractor, either orally or in writing, who has been assigned responsibility for executing the requirements of this contract.

ATTACHMENT J-0200000-01
DEFINITIONS AND ACRONYMS

DEFINITION	DESCRIPTION
Direct Material Costs	The actual vendor invoice charges for materials used for performance of work under this contract. Direct material costs shall include transportation charges when such charges are included on the invoice by the vendor, as well as any discounts allowed for prompt payment and discounts or rebates for core value or salvage value that accrue to the Contractor. When questions arise concerning the cost of materials, material costs will be based on the lowest of quotes provided by the Contractor from at least three different commercial vendors for the direct material cost. The Government retains the right to obtain additional quotes in questionable situations. The lowest price will be used. All other cost such as sub-contractor cost, costs for pre-expended bin materials, shipping and handling, union agreements, crew sizes, hand tools, universal equipment, mobilization, demobilization, time for job preparation, safety standby personnel, payroll burdens and fringes, overtime, job (field) overhead, clerical support, supervision, inspection, fees, taxes, licenses, permits, and insurance, general and administrative (home office) overhead, profit, and all other associated markups shall not be included in the direct material price since the cost for these items are included in the UPL Hour unit price bid.
Electronic Operation And Maintenance And Support Information (eOMSI)	A set of consultant-prepared data and document files that contain detailed, as-built technical information that describes the efficient, economical and safe operation, maintenance and repair of a facility, plant, equipment or system throughout its life cycle. Generally it is prepared during construction and submitted upon completion of a new facility or major facility upgrade. eOMSI's typically include asset information, staffing and budgeting information, supply support including critical spare parts, operating procedures, troubleshooting and diagnostic guides, extended warranty data, maintenance task frequencies and documentation, technical data, repair procedures and manufacturer's product data. eOMSI data and document files are provided in electronic formats.
Equipment	Tangible asset that is functionally complete for its intended purpose, durable, and non-expendable.
Facility	A building or structure designed and created to serve a particular function.
FedMall	U.S. Government (USG) owned and operated web-based ordering system that enables any Department of Defense (DoD) or Federal activity to search for and order goods and services.
Fixed Burden Rate (FBR)	The additional costs (expressed in percent of direct material cost) for ordering, handling, and stockpiling materials and repair parts. For example, if the offeror's Fixed Burden Rate for materials in the Base Period is 10% then: $\$100,000.00 + (\$100,000.00 \times 10\%) = \$110,000.00$ The Government will compensate the Contractor for the required parts and materials and not the total amount shown in Schedule of Indefinite Delivery Indefinite Quantity Work.
Force Protection Condition (FPCON)	A method of identifying specific security requirements mandated to be implemented during times of increased terrorist threat. FPCONs are identified from lowest to highest threat level as "Alpha", "Bravo", "Charlie" and "Delta".

ATTACHMENT J-0200000-01
DEFINITIONS AND ACRONYMS

DEFINITION	DESCRIPTION
Frequency Of Service	Annual (A). Services performed once during each 12-month period of the contract at intervals of 335 to 395 days. Biennial (B). Services performed once during each 24-month period of the contract at intervals of 670 to 790 days. Daily (D5). Services performed once each calendar day, Monday through Friday, including holidays unless otherwise noted. Daily (D7). Services performed once each calendar day, seven days per week, including weekends and holidays. Monthly (M). Services performed 12 times during each 12-month period of the contract at intervals of 28 to 31 calendar days. Quarterly (Q). Services performed four times during each 12-month period of the contract at intervals of 80 to 100 calendar days. Semiannual (SA). Services performed twice during each 12-month period of the contract at intervals of 160 to 200 calendar days. Semimonthly (SM). Services performed 24 times during each 12-month period of the contract at intervals of 14 to 16 calendar days. Three times weekly (3W). Services are performed three times a week, such as Monday, Wednesday, and Friday. Twice weekly (2W). Services are performed twice a week, such as Monday and Thursday or Tuesday and Friday. Weekly (W). Services performed 52 times during each 12-month period of the contract at intervals of six to eight calendar days.
Government Furnished Property (GFP)	Property in the possession of, or directly acquired by, the Government and subsequently furnished to the contractor for performance of a contract. Government furnished property includes, but is not limited to, spares and property furnished for repairs, maintenance, overhaul, or modification. Government furnished property also includes contractor acquired property if the contractor acquired property is a deliverable under a cost contract when accepted by the Government for continued use under the contract.
Hazardous Material (HM) or (HAZMAT)	A material that because of its quality, concentration, physical, chemical or infectious nature may pose a threat to human health or the environment if released or spilled into the environment or any material designated by the Department of Transportation (DOT) or any materials that require a SDS form as posing a potential threat while being transported. Hazardous materials are listed in 49 CFR Part 172.
Hazardous Waste (HW) or (HAZWASTE)	Any discarded solid waste (liquid, semi-solid, solid, or gaseous) that meets the definition of a hazardous waste by USEPA (U.S. Environmental Protection Agency), local authorities, or the Navy. In accordance with RCRA, a solid waste is a listed hazardous waste if it is specifically listed, or it is a characteristic hazardous waste if it exhibits the characteristics of ignitability, corrosivity, reactivity, or toxicity.

ATTACHMENT J-0200000-01
DEFINITIONS AND ACRONYMS

DEFINITION	DESCRIPTION
Hazardous Waste Management Plan	In accordance with OPNAVINST 5090.1C, every Navy shore activity that generates HW shall develop and use a Hazardous Waste Management Plan or a Hazardous Waste management component in its P2 Plan and EMS. A Hazardous Waste Management Plan shall: • Identify applicable federal, state, and local regulations pertaining to the generation and management of hazardous waste. • Identify training requirements and describe procedures for obtaining training and maintaining training records. • Assign responsibilities for the generation, designation, handling, storage, treatment, disposal, and all documentation. • Describe all hazardous waste generation and management procedures. • Include or reference the hazardous waste minimization plan and goals. • Include or reference contingency plans and emergency response procedures. The plan shall be kept up to date to include changes in hazardous waste generation and management procedures, as well as changes in applicable federal, state, and local hazardous waste regulations. The plan shall include or reference minimization procedures sufficient to achieve DOD minimization goals. Tenant activities are covered by the host CO's Hazardous Waste Management Plan.
Hazardous Waste Manifest	A hazardous waste manifest as defined in 40 CFR 260 is required for the transport of hazardous waste. The installation commanding officer (ICO) or the ICO's designated representative shall retain signature authority for hazardous waste manifests.
Internet Navy Facility Assets Data Store (iNFADS)	The Navy's authoritative real property database where detailed information on each facility is maintained.
Infrastructure Condition Assessment Program (ICAP)	A Navy automated data management program that utilizes historical asset lifecycle data and a structured assessment process to evaluate the condition facilities and their components.
Inspection	A rigorous, detailed assessment of the condition of a facility performed to generate a fundable scope and cost estimate for prioritization and funding of maintenance and repair.
Integrated Maintenance Program (IMP)	IMP is a recurring state-of-the-art, reliability-centered inspection, testing, maintenance and repair program that determines best practices for managing the functions and consequences of failures of facilities equipment and system components. IMP encompasses accepted commercial practices, including reactive, preventive, predictive and proactive maintenance, into one optimal program. The IMP approach gives the Contractor full responsibility to maintain systems and equipment and perform repairs whenever necessary to ensure equipment and systems are operational and remain in a constant state of readiness. Service orders will not be issued for accomplishment of repairs on systems and equipment maintained under IMP.
Job or Work Order	An authorization for work that requires planning and estimating and has an individual line of accounting for financial and performance evaluation.
Life-Cycle Costs	A form of economic analysis that considers the total cost of owning, operating, and maintaining a building or system over its useful life.
Less-than-90-day Accumulation Areas or Storage Facilities	Temporary HW storage areas where HW may be stored for up to 90 days without a RCRA permit.
Load Handling Equipment	A term used to describe cranes, hoists and all other hoisting equipment (hoisting equipment means equipment, including crane, derricks, hoists and power operated equipment used WITH RIGGING to raise, lower and/or horizontally move a load.

ATTACHMENT J-0200000-01
DEFINITIONS AND ACRONYMS

DEFINITION	DESCRIPTION
Maintenance And Repair	The preservation or restoration of a piece of equipment, system, or facility to such condition that it may be effectively used for its designated purposes. Maintenance/repair may be adjustment, overhaul, reprocessing, or replacement of constituent parts or materials that are missing or have deteriorated by action of the elements or usage, or replacement of the entire unit or system if beyond economical repair.
NAVFAC MAXIMO	A specially configured software version of MAXIMO®, a commercially available computerized maintenance management system (CMMS), adopted by NAVFAC for enterprise facility asset data management. The terms “MAXIMO”, “NAVFAC MAXIMO” or “Government’s MAXIMO” shall be used interchangeably in the document.
Non-RCRA Regulated Waste	Waste that is not regulated as a hazardous waste under RCRA (Resource Conservation and Recovery Act); however, is waste may be regulated by other federal, state or local regulations including but not limited to TSCA (Toxic Substances Control Act), Clean Air Act, Clean Water Act or other regulations and statues. Examples include Used Oil, Universal Waste, Oily Water, antifreeze, etc. Non-RCRA regulated waste, while not meeting the definition of a Hazardous Waste, must be managed according to its applicable regulations and may not be discarded into the general trash.
Non-Regulated Solid Waste (Debris and Rubbish)	Waste not associated with an industrial process such as refuse and scraps resulting from preparation, cooking, dispensing, and consumption of food. Non-hazardous construction and demolition waste such as dimension and non-dimension lumber, plywood, chipboard, and hardboard are included.
Partnering	The terms “partnering” and “partnership” used herein shall mean a relationship of open communication and close cooperation that involves both Government and Contractor personnel working together for the purpose of establishing a mutually beneficial, proactive, cooperative environment within which to achieve contract objectives and resolve issues and implementing actions as required.
Performance Assessment	A method used by the Government to provide some measure of control over the quality of purchased goods and services received.
Performance Assessment Representative (PAR)	The individual(s) assigned as a Technical Point of Contact (TPOC) / Subject Matter Expert (SME) to the COR to perform duties as the on-site representative who assesses Contractor performance. The PAR periodically observes Contractor performance, reviews delivered services, reviews quality management corrective actions, periodically assesses and documents Contractor performance on PAWs and the MPAS, and communicates findings as necessary with the Contractor, SPAR, and COR.
Pre-Expended Bin Materials And Supplies	The minor materials and supplies that are incidental to the job, for which the total direct cost of any one material line item shown on the material estimate is \$10.00 or less. Examples of pre-expended bin materials and supplies include, but are not limited to, solder, lead, flux, electrical connectors, electrical tape, fuses, nails, screws, bolts, nuts, washers, spacers, masking tape, sand paper, solvent, cleaners, lubricants, grease, oil, rags, mops, glue, epoxy, spackling compound, joint tape, plumbers tape and compound, clips, welding rods, and touch up paint.
Property Administrator	An authorized representative of the Contracting Officer who is responsible for administering contract property requirements, terms and conditions of the contract
Property Management Program	A Government program established for the purpose of reviewing and approving the Contractor’s Property Management Plan and System through performance of a system analysis whenever government property is in the possession of the Contractor.
Quality Assurance (QA)	The planned and systematic activities implemented in a quality system so that quality requirements for a product or service will be fulfilled.
Quality Control (QC)	The observation techniques and activities used to fulfill requirements for quality.

ATTACHMENT J-0200000-01
DEFINITIONS AND ACRONYMS

DEFINITION	DESCRIPTION
R. S. Means	A data collection and organization system developed by R. S. Means Company which can be used to prepare accurate, dependable construction estimates and budgets in a variety of ways. The Contractor shall use the latest edition. Material prices are based on a national average and computed labor costs are based on a 30-city national average. An estimate prepared using this data is called a "Means estimate"; data may simply be referred to as "Means".
Real Property Inventory Equipment (RPIE)	A Government owned or leased individual pieces of equipment, apparatus, or fixture that are essential to the function of the real property (i.e. plumbing, electrical, heating, cooling and elevators). It is physically attached to, integrated into, and built in or on the property. Individual RPIE's can be combined to make a CIMU to facilitate facilities management. An individual RPIE can also be a CIMU if the equipment is complex enough to require its own management planning.
Regulated Waste	Any hazardous, non-hazardous, industrial process waste (aka special waste), e-waste, and/or off-specification HM, which because of its physical characteristics, chemical make-up or biological nature requires either special handling procedures and permitting, or poses an unusual threat to human health, equipment, property, or the environment. Examples include (but are not limited to) liquid sludge, pastes, and/or filter cakes, chemical compounds and/or petroleum products, fine powders or highly dusty materials, spent blast media and/or grit, demolition wastes from industrial facilities, debris and/or residues from spill cleanup work, underground storage tank remediation materials, pollution control wastes, ash from fires, furnaces, boilers or incinerators, off-specification products, other materials that have the potential to be a hazardous waste. All RW may be used or unused excess hazardous materials. Laboratory analysis may be required to verify the waste is not a RCRA-regulated hazardous waste.
Response Time	The time allowed the Contractor after initial notification of a work requirement to be physically on the premises at the work site with appropriate personnel, tools, equipment, and materials, ready to perform the work required.
Restoration	Restoration of real property to such a condition that it can be used for its intended purpose. Includes repair or replacement work to restore facilities damaged by inadequate sustainment, excessive age, natural disaster, fire, accident or other causes.
Sampling Plan	Plan and procedures to conduct sampling, field testing and laboratory analysis for a defined testing objective.
Satellite Accumulation Areas	Designated approved areas, at or near the point of generation and under the control of the operator generating the waste, where no more than 55 gallons (cumulative total) of all types of HW or 1 quart of acutely HW may be accumulated. The 55-gallon limit does not include non-RCRA regulated waste, universal waste and used oil etc.
Spill Prevention Control and Countermeasure (SPCC) Plan	The SPCC Plan establishes engineering controls including procedures, methods, equipment and other requirements to prevent the discharge of oil into or upon navigable waters. The Plan includes procedures for oil spill prevention, measures to contain spills and an established spill drill exercises to ensure effective countermeasures in the event of oil spill.
Sustainment	Maintenance and repair activities necessary to keep a typical inventory of facilities in "normal working condition". Sustainment includes regularly scheduled maintenance as well as cyclical major repairs or replacement of components that occur periodically over the expected service life of the facilities.
System	An assemblage of mechanically and/or electrically interlocked parts, equipment and/or components forming a unitary whole.

ATTACHMENT J-0200000-01
DEFINITIONS AND ACRONYMS

DEFINITION	DESCRIPTION
Unit Priced Labor (UPL) Hour	The unit price bid by the Contractor to perform one hour of work-in-place. With the exception of direct material and construction equipment costs, the unit price includes all indirect and direct costs associated with performing work. The price includes the Contractor's hourly composite trade wage, adjusted to allow for workforce productivity; costs for pre-expended bin materials, union agreements, crew sizes, hand tools, payroll burdens and fringes, overtime, job (field) overhead (including clerical support, supervision, inspection, fees, taxes, licenses, permits, and insurance), general and administrative (home office) overhead, and profit. Additionally, time for job preparation, safety standby personnel, and similar indirect labor elements are included.
Uniformat Classification	A standard classification of building components established by the National Institute of Standards and Technology.
Universal Equipment	Universal equipment refers to equipment that can cover two or more industries and is commercially employed in execution of operation, maintenance, and repair work, such as: Aerial Work Platforms, Backhoes, Cranes, Dump Trucks, Excavators, Generators, Graders, Lifts, Loaders, Man Lifts, Monitoring and Test Equipment, Pumps, Tractors, Trailers, etc.
Universal Waste (UW)	Universal Waste (UW) (defined in 40 CFR Part 273) means batteries, fluorescent lamps, some pesticides, and mercury-containing equipment formally classified as a HW, but that are now subject to less stringent regulations when recycled, if recycling is available.
Utility Infrastructure Condition Assessment Program (UICAP)	A comprehensive assessment processes for planning, managing, and executing Navy utility infrastructure inspections.

ATTACHMENT J-0200000-01
DEFINITIONS AND ACRONYMS

ACRONYM	TITLE
ACO	Administrative Contracting Officer
BW	Biweekly
CDR	Contract Discrepancy Report
CIA	Controlled Industrial Area
CIMU	Component Inventory Management Unit
CMMS	Computerized Maintenance Management System
COR	Contracting Officer Representative
COR	Condition of Readiness
DBH	Diameter at Breast Height
DCR	Direct Condition Rating
DoD	Department of Defense
DoN	Department of Navy
DRMO	Defense Reutilization Management Office
EPA	Environmental Protection Agency
EPCRA	Emergency Planning and Community Right-to-Know Act
FAR	Federal Acquisition Regulation
FFP	Firm Fixed Price
FIFRA	Federal Insecticide, Fungicide, and Rodenticide Act
FSC	Facility Support Contract
FSCM	Facility Support Contract Manager
GIS	Geospatial Information System
GFE	Government-furnished Equipment
GFF	Government-furnished Facilities
GFM	Government-furnished Materials
HCA	Head Contracting Agency
ICAP	Infrastructure Condition Assessment Program
ICP	Integrated Contingency Plan
IDIQ	Indefinite Delivery Indefinite Quantity
iNFADS	Internet Navy Facilities Asst Data Store
IPM	Integrated Pest Management
IPMIS	Integrated Pest Management Information System
IPMP	Integrated Pest Management Plan
KO	Contracting Officer
LAN	Local Area Network
M	Monthly
MAP	Maintenance Action Plan
MDI	Mission Dependency Index
MEP	Mechanical, Electrical and Plumbing
MPAS	Monthly Performance Assessment Summary
MRI	Mission Readiness Index
SDS	Safety Data Sheet
NAVFAC	Naval Facilities Engineering Command
NMCI	Navy Marine Corps Intranet
NOSC	Navy-On-Scene Coordinator
PAP	Performance Assessment Plan
PAR	Performance Assessment Representative
PAW	Performance Assessment Worksheet
PEO	Program Executive Officer
PM	Project Manager
PM	Planned Maintenance or Preventative Maintenance
PRCSP	Permit Required Confined Space Program

ATTACHMENT J-0200000-01
DEFINITIONS AND ACRONYMS

ACRONYM	TITLE
PWS	Performance Work Statement
PWO	Public Works Officer
Q	Quarterly
QC	Quality Control
RPIE	Real Property Inventory Equipment
RSL	Remaining Service Life
SC	Security Clearances
SM	Semimonthly
SPAR	Senior Performance Assessment Representative
TE	Technical Exhibit
VIQ	Variation in Quantity
WBS	Work Breakdown Structure

ATTACHMENT J-0200000-02
DIRECTIVES, INSTRUCTIONS, AND REFERENCES

The Contractor shall adhere to the applicable portions of the following publications and directives in performing the services required under this contract. This list shall not be considered all-inclusive and does not release the Contractor from all obligations that must be fulfilled in the observance and execution of this contract.

When U.S., European and/or Italian directives, instructions and industry standards are applicable to the work to be performed under this contract, the most stringent directives, instructions and industry standards shall govern.

REFERENCE	TITLE
EM 385-1-1	U.S. Army Corps of Engineers Safety and Health Requirements
P.L. 91-596	Occupational Safety and Health Act
UFGS 01 35 26	Unified Facilities Guide Specifications
FGSI	Final Governing Standards - Italy
N/A	Legislative Decree No. 81 dated 9 April 2008
N/A	Ministerial Decree No. 37 dated 22 January 2008
N/A	Safety at the Workplace as per the Ispettorato di Sicurezza Sul Lavoro (ISPESL) Regulations
NAVFAC Clause 5252.245-9300	Government-Furnished Property, Materials And Services
NAVFAC P-307	Management of Weight Handling Equipment
NAVSUPINST 5100.27	Hazardous Material Safety Program
NAVFACINST 11013.40	Project Partnering Policy
FAR 52.228-5	Insurance – Work on a Government Installation
FAR 52.237-2	Protection Of Government Buildings, Equipment, And Vegetation
BOCA	Building Codes
CFR	Codes of Federal Regulations
NFPA	National Fire Protection Association - Codes and Standards

ATTACHMENT J-0200000-03
GOVERNMENT-FURNISHED FACILITIES LIST

Facility Description	Approx Size	Location	Remarks
NAS I			
Concrete foundation for portable facility		SE of Bldg 273, Naval Hospital	

NOTE: The Government will provide limited space within the various buildings for storage of day-to-day supplies and tools only.

ATTACHMENT J-0200000-04
FORMS

- J-0200000-04. a Contractor Crane Operating Checklist for Critical Lifts
- J-0200000-04. b Crane and Rigging Gear Accident Report
- J-0200000-04. c Crane and Rigging Gear Accident Report Instructions
- J-0200000-04. d Crane and Rigging Gear Near Miss Report
- J-0200000-04. e Crane and Rigging Gear Near Miss Report Instructions
- J-0200000-04. f Invoice Form

ATTACHMENT J-0200000-04.a
CONTRACTOR CRANE OPERATING CHECKLIST FOR CRITICAL LIFTS

ATTACHMENT "A"			
CONTRACTOR CRANE OPERATING CHECKLIST FOR CRITICAL LIFTS		YES	NO
1	Does the operator know the weight of the load to be lifted?		
2	Is the load to be lifted within the crane manufacturer's rated capacity in its present configuration?		
3	Is the crane level and on firm ground?		
4	Are outriggers required?		
5	If so, are outriggers fully extended and down, and the load off the wheels?		
6	If blocking is required, is the entire surface of the outrigger pad supported, and is the blocking material of sufficient strength to safely support the loaded outrigger pad?		
7	If outriggers are not used, is the crane rated for on-rubber lifts by the manufacturer's load chart?		
8	Is the swing radius of the crane counterweight clear of people and obstructions and accessible areas within the swing area barricaded to prevent injury, damage and unplanned encroachment?		
9	Has the hook been centered over the load in such a manner to prevent swing (deflection, side loading, load-moment)?		
10	Is the load well secured and balanced in the sling or lifting device before it is lifted (free and clear) more than a few inches?		
11	Is the lift swing path clear of obstructions?		
12	If rotation of the load being lifted is hazardous, is tag line or restraint line being used?		
13	Are personnel prevented from standing or passing under a suspended load?		
14	Are personnel prevented from entering the load fall zone?		
15	Is the crane operator's attention diverted?		
16	Are proper signals being used at all times?		
17	If radio communications are used is the frequency isolated to the crane team?		
18	Do the operations ensure that side and tip loading is prohibited?		
19	Are start and stop motions in a smooth fluid motion (no sudden acceleration or deceleration)?		
20	If operating near electric power lines, are the rules and guidelines understood and adhered to as specified in NAVFAC P-307?		
21	Is the lift a critical lift?		
22	If so, are critical lift regulations understood, check-off sheets initialed and signed off, and was there an interactive brief conducted with associated personnel?		
23	Is Attachment "A" current, filled out completely, and posted in the crane?		
Contractor Name (Print Legibly):			
Contractor Name (Signature):			
Location:			Date:

ATTACHMENT J-0200000-04.b
CRANE AND RIGGING GEAR ACCIDENT REPORT

CRANE AND RIGGING GEAR ACCIDENT REPORT				
Accident Category: ☐ Crane Accident ☐ Rigging Gear Accident				
From:		To: Navy Crane Center Bldg. 491 NNSY Portsmouth, VA 23709 Fax: 757-967-3808		
UIC:		Report No:		
Activity:				
Crane No:		Category:		Accident Date:
Time: hrs:				
Category of Service: ☐ SPS ☐ GPS		Crane Type:		Crane Manufacturer:
Was Crane/Rigging Gear Being Used in SPS: ☐ Yes ☐ No		Was Crane/Rigging Gear Being Used in a Complex Lift/Critical Non-Crane Rigging Operation: ☐ Yes ☐ No		
Location:		Weather:		
Crane Capacity:		Hook Capacity:		Weight of Load on hook:
Fatality or Permanent Disability? ☐ Yes ☐ No		Material/Property Cost Estimate:		
Reported to NAVSAFECEN? ☐ Yes ☐ No				
Accident Type:				
☐ Personal Injury ☐ Overload ☐ Derail ☐ Damaged Rigging Gear ☐ Load Collision ☐ Two Blocked ☐ Dropped Load ☐ Damaged Crane ☐ Crane Collision ☐ Damaged Load ☐ Other: Specify _____				
Cause of Accident:				
☐ Improper Operation ☐ Equipment Failure ☐ Inadequate Visibility ☐ Improper Rigging ☐ Switch Alignment ☐ Inadequate Communication ☐ Track Condition ☐ Procedural Failure ☐ Other: Specify _____				
Chargeable to:				
☐ Crane Walker ☐ Rigger ☐ Operator ☐ Maintenance ☐ Management/Supervision ☐ Other: Specify _____				
Crane Function:				
☐ Travel ☐ Hoist ☐ Rotate ☐ Luffing ☐ Telescoping ☐ Other ☐ N/A				
Is this accident indicative of a recurring problem? ☐ Yes ☐ No				
If yes, list Accident Report Nos.: _____				
ATTACH COMPLETE AND CONCISE SITUATION DESCRIPTION AND CORRECTIVE/PREVENTIVE ACTIONS TAKEN AS ENCLOSURE (1). Include probable cause and contributing factors. Assess damages and define responsibility. For equipment malfunction or failure, include specific description of the component and the resulting effect or problem caused by the malfunction or failure. List immediate and long term corrective/preventive actions assigned and respective codes.				
Preparer:		Phone:		E-mail:
Concurrences: (Include Code, Signature and Date)				
		Code:		Date:
Certifying Official (Crane Accident Only):		Code:		Date:

ATTACHMENT J-0200000-04.c
CRANE AND RIGGING GEAR ACCIDENT REPORT INSTRUCTIONS

CRANE AND RIGGING GEAR ACCIDENT REPORT INSTRUCTIONS

This form is designed for fax transmission without a cover page or by e-mail and, with enclosures and signatures, shall be the official document. Electronic submission will be accepted without signatures but the names of the preparer, concurring personnel, and certifying official (for crane accidents only) shall be filled in. The e-mail address is m_nfsh_ncc_accident@navy.mil. The fax number is (757) 967-3808.

1. Accident Category: Indicate either crane accident or rigging gear accident.
2. From: The naval activity that is responsible for reporting the accident and UIC number.
3. Activity: The naval activity where the accident took place.
4. Report No.: The activity assigned accident number (e.g., 95-001).
5. Crane No.: The activity assigned crane number (e.g., PC-5), if applicable.
6. Category: Identify category of crane (i.e., 1, 2, 3, or 4), if applicable.
7. Accident Date: The date the accident occurred.
8. Time: The time (24 hour clock) the accident occurred (e.g., 1300).
9. Category of Service: Check the applicable service (SPS as defined by NAVSEA 0989-030-7000).
10. Crane Type: The type of crane involved in the accident (e.g., mobile, bridge), if applicable.
11. Crane Manufacturer: The manufacturer of the crane (e.g., Dravo, Grove, P&H), if applicable.
12. SPS: Was the crane or rigging gear being used in an SPS lift?
13. Complex lift: Was the crane or rigging gear being used in a complex lift?
14. Location: The detailed location where the accident took place (e.g., building 213, dry dock 5).
15. Weather: The weather conditions at time of accident (e.g., wind, rain, cold).
16. Crane Capacity: The certified capacity of the crane (e.g., 120,000 pounds), if applicable.
17. Hook Capacity: The capacity of the hook involved in the accident at the max radius of the operation, if applicable.
18. Weight of Load on Hook: If applicable, the weight of the load on the hook.
19. Fatality or Permanent Disability?: Check yes or no.
20. Material/Property Cost Estimate: Estimate total cost of damage resulting from the accident.
21. Reported to NAVSAFECEN?: Self-explanatory.
22. Accident Type: Check all that apply.
23. Cause of Accident: Check all that apply.
24. Chargeable to: Check all that apply.
25. Crane Function: Check all functions in operation at time of accident. Check N/A if a rigging gear accident.
26. Is this a recurring problem?: Check yes or no. Identify any other similar accidents.
27. Situation Description/Corrective Actions: Self-explanatory.
28. Preparer: Self-explanatory.
29. Concurrences: Self-explanatory.
30. Certifying Official (Crane Accidents Only): Self-explanatory.
31. Brief Description: No more than one paragraph summarizing the resultant incident.
32. Background and Detailed Description: Provide the relevant background in a descriptive timeline of preconditions leading up to the event, as well as a detailed description of the event.
33. Corrective Actions: List all short term and long term corrective actions that are taken to prevent recurrence of the incident. Short Term Corrective Actions are those actions taken that will allow return to work in short time frame. Long Term actions are more 'programmatic' in nature and typically include: process revision, changes in training, 'mistake proofing', etc.

ATTACHMENT J-0200000-04.d
CRANE AND RIGGING GEAR NEAR MISS REPORT

CRANE AND RIGGING GEAR NEAR MISS REPORT

Near Miss Category: ☐ Crane Near Miss ☐ Rigging Gear Near Miss			
From:		To: Navy Crane Center Bldg 491 NNSY Portsmouth, VA 23709 Fax (757) 967-3808 nfsh_ncc_accident@navy.mil	
UIC:			
Activity:			Report No:
Crane/Equipment No:	Category:	Near Miss Date:	Time: hrs
Category of Service: ☐ SPS ☐ GPS		Crane /Equipment Type:	Crane/Equipment Manufacturer:
Location:		Weather:	
Crane/Equipment Capacity:	Hook Capacity:	Weight of Load on Hook:	

Is this near miss indicative of a recurring problem? ☐ Yes ☐ No

If yes, list report numbers: _____

In the space below, include a brief description of the event and corrective actions taken to prevent recurrence:

Preparer:	Phone and email	Code	Date

ATTACHMENT J-0200000-04.e
CRANE AND RIGGING GEAR NEAR MISS REPORT

CRANE AND RIGGING GEAR NEAR MISS INSTRUCTIONS

This form is designed for fax transmission without a cover page or by e-mail and, with enclosures and signatures, shall be the official document. Electronic submission will be accepted without signatures but the names of the preparer, concurring personnel, and certifying official (for crane accidents only) shall be filled in. The e-mail address is nfsh_ncc_accident@navy.mil. The fax number is (757) 967-3808.

1. Near Miss Category: Indicate either crane or rigging gear near miss.
2. From: The naval activity that is responsible for reporting the near miss and UIC number.
3. Activity: The naval activity where the near miss took place.
4. Report No.: The activity assigned near miss number (e.g., 95-001).
5. Crane No.: The activity assigned crane number (e.g., PC-5), if applicable.
6. Category: Identify category of crane (i.e., 1, 2, 3, or 4), if applicable.
7. Near Miss Date: The date the near miss occurred.
8. Time: The time (24 hour clock) the near miss occurred (e.g., 1300).
9. Category of Service: Check the applicable service (SPS as defined by NAVSEA 0989-030-7000).
10. Crane Type: The type of crane involved in the near miss (e.g., mobile, bridge), if applicable.
11. Crane Manufacturer: The manufacturer of the crane (e.g., Dravo, Grove, P&H), if applicable.
12. Location: The detailed location where the near miss took place (e.g., building 213, dry dock 5).
13. Weather: The weather conditions at time of the near miss (e.g., wind, rain, cold).
14. Crane Capacity: The certified capacity of the crane (e.g., 120,000 pounds), if applicable.
15. Hook Capacity: The capacity of the hook involved in the near miss at the maximum radius of the operation, if applicable.
16. Weight of Load on Hook: If applicable, the weight of the load on the hook.
17. Is this a recurring problem?: Check yes or no. Identify any other similar near misses or accidents.
18. Situation Description/Corrective Actions: Self-explanatory.
19. Preparer: Self-explanatory.

ATTACHMENT J-0200000-04. f
INVOICE FORM

1. CONTRACTOR'S INVOICE				CAGE Code	
From				Invoice Date	
				Invoice Number	
				DUNS No.	
Contractor's remittance address					
(if different than mailing address, contract requires Modification)					
Contractor POC/Telephone/email for this invoice:					
To:	Contract Specialist:				
Below is a Statement of Performance under Contract				Task Order #	
for		at			
The enclosure provides breakdown of this statement of performance.					
A.	Total value of contract/task order through modification			\$	
B.	Percentage of performance complete			%	
C.	Value of completed performance			\$	
D.	Less total of prior payments			\$	
E.	Amount of this invoice			\$	
	Signature and Title:				
	Date:			Signature of Authorized Representative	
Taxpayer Identification No. (TIN):					
Electronic funds transfer (EFT) banking information (if applicable):					
Navy Design Project Leader/Technical Point-of-Contact (Contractor, please complete)					
2. FIRST ENDORSEMENT					
From:	Accountable Officials: Activity Operations Director (AOD)				
	Project Leader/Technical POC				
To:	Certifying Officer				
1. Payment is recommended as follows:					
A.	Amount of work completed to (date)			\$	
B.	Less:				
	Retention	\$			
	Other Deductions	\$		\$	
C.	Subtotal			\$	
D.	Less previous payments			\$	
E.	Certified amount for payment #		on TO #	\$	
F.	Elapsed contract time (if applicable)				
(EFA use only)					
	Fund Usage Number				

1. CONTRACTOR'S INVOICE				CAGE Code	
From				Invoice Date	
				Invoice Number	
				DUNS No.	
Contractor's remittance address					
(if different than mailing address, contract requires Modification)					
Contractor POC/Telephone/email for this invoice:					
To:	Contract Specialist:				
Below is a Statement of Performance under Contract				Task Order #	
for		at			
The enclosure provides breakdown of this statement of performance.					
A.	Total value of contract/task order through modification			\$	
B.	Percentage of performance complete			%	
C.	Value of completed performance			\$	
D.	Less total of prior payments			\$	
E.	Amount of this invoice			\$	
	Signature and Title:				
	Date:			Signature of Authorized Representative	
Taxpayer Identification No. (TIN):					
Electronic funds transfer (EFT) banking information (if applicable):					
Navy Design Project Leader/Technical Point-of-Contact (Contractor, please complete)					
2. FIRST ENDORSEMENT					
From:	Accountable Officials: Activity Operations Director (AOD)				
	Project Leader/Technical POC				
To:	Certifying Officer				
1. Payment is recommended as follows:					
A.	Amount of work completed to (date)			\$	
B.	Less:				
	Retention	\$			
	Other Deductions	\$		\$	
C.	Subtotal			\$	
D.	Less previous payments			\$	
E.	Certified amount for payment #		on TO #	\$	
F.	Elapsed contract time (if applicable)				
(EFA use only)					
	Fund Usage Number				

CONTRACTOR'S RELEASE
NAVFAC 4330-7 (6-72)
S/N 0105-LF-001-9100

CONTRACTOR'S RELEASE UNDER CONTRACT _____

KNOW ALL MEN BY THESE PRESENTS: In consideration of the promise and the sum of _____

(\$ _____)

lawful money of the United States of America (hereinafter called the "Government") _____

(\$ _____)

of which has already been paid and _____

(\$ _____) of which is to be paid

by the Government under the above mentioned contract, the undersigned Contractor does, and by the receipt of said sums shall, for itself, its successors and assigns, remise, release and forever discharge the Government, its officers, agents, and employees, of and from all liabilities, obligations and claims whatsoever in law and in equity under or arising out of said contract.

IN WITNESS WHEREOF, this release has been executed this _____ day of _____, 20____

WITNESSES:

(Contractor)

By:

Title:

IN CASE OF CORPORATION WITNESSES NOT REQUIRED, BUT CERTIFICATE BELOW MUST BE COMPLETED.

I, _____, certify that I am the _____ secretary
of the corporation named as Contractor in the foregoing release; that _____
who signed said release on behalf of the Contractor was then _____ of said Corporation
that said release was duly signed for and in behalf of said corporation by authority of its governing body and its within
scope of its corporate powers.

(Corporate Seal)

ATTACHMENT J-0200000-05
SERVICE PROVIDER INFORMATION

Service provider information is provided as a separate attachment. Refer to Microsoft Excel Spreadsheet “J-0200000-05 – SERVICE PROVIDER INFORMATION V1”.

ATTACHMENT J-0200000-06
ASSET INFORMATION

Asset information is provided as a separate attachment. Refer to Microsoft Excel Spreadsheet “J-0200000-06 – ASSET INFORMATION V1”.

ATTACHMENT J-0200000-07
NAVFAC MAXIMO DATA REPORTING

PURPOSE AND OVERVIEW

The purpose of this attachment is to provide guidance on how data is to be recorded and provided by the Contractor in reporting Service Provider, Asset, Specification, and Characteristic Meter Reading Information for NAVFAC MAXIMO. This document outlines the methods that must be utilized by the Contractor and associated NAVFAC business process and procedures for how data is to be submitted.

GENERAL TYPES OF DATA

Work Order Data

Work order data includes all necessary information for the documentation of all completed work orders, including, but not limited to, service orders, preventive maintenance (as performed under the PM program or as part of IMP), and work issued as Non-Recurring (IDIQ). Specific NAVFAC MAXIMO fields required for work order data are listed on the Service Provider Information spreadsheet provided in J-0200000-05.

Asset Data

Asset data includes the specific details necessary for proper identification and tracking of assets when updated for all completed work orders where an asset is repaired, replaced, installed, or otherwise affected. Specific NAVFAC MAXIMO fields required for asset data are listed on the Asset Information spreadsheet provided in J-0200000-06. When replacing existing assets, the Contractor shall change the status of the current asset which will remove it from the maintenance plan and add the new asset.

Condition Rating Data

ICAP Meter reading shall be recorded at a minimum frequency of 1 year on the annual PM for all the equipment under the Integrated Maintenance Program by BOS Contractor. In addition to the scheduled work, the BOS Contractor shall update the ICAP meters every time that a Service is executed on the equipment.

For each equipment category, the attachment J-1501000-03 lists the ICAP meters that shall be updated. Specific NAVFAC MAXIMO fields required for asset data are listed on the Facility Management Procedures provided in 1501000, Facility Management.

METHODS FOR DATA SUBMISSION

The Contractor shall provide work order, asset, specification, and condition assessment data via Direct Entry.

Direct Data Entry

The Contractor directly enters data into NAVFAC MAXIMO in a secure method via the internet or using a ONE-NET workstation. Detailed guidance NAVFAC MAXIMO System Access Procedures is provided in J-0200000-08. All reference value verification is provided by NAVFAC MAXIMO.

All Contractors personnel who obtain authorized access will be granted entry only within the applicable NAVFAC MAXIMO screens necessary to enter work order, asset, specification and condition assessment data. Contractors are only authorized to view, edit, report or otherwise access data related to their work. Any unauthorized attempt to do otherwise may be grounds for removal of access privileges. Contractors will be assigned a specific work center code for their work and shall utilize this code for all such data entry and retrieval.

ATTACHMENT J-0200000-08
NAVFAC MAXIMO SYSTEM ACCESS PROCEDURES

PURPOSE AND OVERVIEW

The Contractor must obtain access to the ONE-NET network and request an account for NAVFAC MAXIMO. There are several steps in receiving approval to access the ONE-NET network and a separate process to request a NAVFAC MAXIMO username and password. The instructions in the following section are accurate at the time of solicitation but are subject to change.

ONE-NET NETWORK ACCESS

If deemed suitable by the Contracting Officer, the Contractor may buy ONE-NET seats directly from ONE-NET to enable the Contractor to staff their resources onsite. The Contracting Officer will provide local assistance to initiate the process to purchase the ONE-NET seat and also to get Common Access Card (CAC) access. Onsite resources must have a CAC card to use the ONE-NET workstation. Contact the Contracting Officer for information on approximate costs. This option may be removed with thirty (30) calendar days notification at no charge to the Government. The Contractor shall be liable for all charges associated with the workstation, including, but not limited to, Move/Add/Change requests.

NAVFAC MAXIMO ACCOUNT REQUEST

The Contractor shall submit a request for NAVFAC MAXIMO account access to the Contracting Officer.

The Contractor must satisfy security requirements of the local Information Assurance Manager (IAM) before access will be granted. Steps will include:

- Submit required SAAR form
- Request a NITC portal SSO account
- Request a STS account Create a STS ticket requesting a new Maximo account
- Take required initial and recurring Information Assurance training
- Complete New User Request Form

The local NAVFAC Business Office will determine level of access and restrictions for users by configuring NAVFAC MAXIMO Work Center access. The Contractor will receive notification that the NAVFAC MAXIMO account has been created, as well as USER ID, password and NAVFAC MAXIMO access URL details.

ATTACHMENT J-0200000-09
SAMPLE OF CONTRACTOR HAZARDOUS MATERIAL INVENTORY LOG

CONTRACTOR HAZARDOUS MATERIAL INVENTORY LOG (EPCRA 312 & 313 Worksheet)									
COMPANY NAME: _____			CONTRACT NO: _____						
PROJECT TITLE: _____									
Product Name or Trade Name	Manufacturer	Max Amount of Product Stored on Site	Amount of Product Used (e.g., Gallons, Pounds)	Specific Gravity (or wt/volume)	Toxic Chemical Ingredient in Product (Refer to MSDS & List Individually)	Toxic Chemical CAS # (Refer to MSDS)	% Toxic Chemical by Weight	Days On Site	

☐ Contractor(s) certifies that no hazardous materials will be brought onto the installation and/or used at the project site.
☐ Contractor(s) certifies that no hazardous waste will be generated from this project.

Submitted By: _____ Phone: _____ Fax: _____ Date: _____
 Contract Administrator: _____ Phone: _____ Fax: _____

Page ____ of ____

ATTACHMENT J-0200000-10
OIL AND HAZARDOUS SUBSTANCE SPILL RESPONSE PROCEDURES

1. General Instructions

a. The Contractor shall provide oil and hazardous substance (OHS) spill response and cleanup to minimize damage to property or risk of human exposure and to ensure the installation complies with Federal statutes and regulations, Host Nation laws and regulations, and DoD policies, instructions and guidance, including, but not limited to, OPNAVINST 5090.1, and DL152/2006.

b. OHS includes hazardous wastes, hazardous materials, petroleum products, e.g., gasoline, diesel, JP-5, hydraulic fluid. Historically, 95 percent of OHS spills are petroleum products. OHS does not include radioactive, medical and infectious wastes and materials, weapons and explosives. Spill containment and cleanup is limited to spills that occur on ground surfaces, in or on soil, in facilities, in Hazardous Waste storage facilities, and on water containing features such as water ditches and rainstorm drainage.

c. The Contractor shall work as part of the Government's Incident Command System and comply with the NAS Sigonella (NASSIG) Spill Prevention and Response Plan. The NASSIG Fire Department acts as the initial Facility Incident Commander (FIC) and is responsible for receiving all initial spills reports. The Fire Department as the FIC will provide initial response and determine procedures for containment, and clean up action. The Government will provide as much information as possible regarding the characteristics of the material spilled, typically identified on the Material Safety Data Sheet (MSDS).

d. When ordered by the Government, the Contractor shall:

- (1) assist the Government in securing and assessing spill conditions;
- (2) contain and clean-up spilled OHS not cleaned-up by Government personnel;
- (3) decontaminate Government and Contractor equipment and property affected by spilled OHS after each use;
- (4) remain on-site until containment and cleanup is complete or as directed by the FIC or their representative.

e. The Contractor shall provide trained personnel for containment and cleanup of OHS spills. The Contractor shall comply with the instructions of the cognizant Navy Medical/Safety Department with respect to avoidance of conditions which create a nuisance or which may be hazardous to the health of military or civilian personnel.

f. The Contractor shall provide the appropriate levels of personnel protective equipment and clean-up equipment for use by their personnel during each response. Required levels of Personal Protective Equipment (PPE) typically include Level 0 through Level B. The Contractor shall be responsible for selection of the appropriate PPE.

g. For each OHS spill response, the Contractor shall provide a Hazardous Substance/Oil Spill Report as follows.

2. OHS Spill Response Requirements

The Contractor shall respond to spill notifications, e.g., telephone, e-mail, fax, and be on site as follows:

(1) Within two hours during regular working hours and commence cleanup within 30 minutes thereafter and work continuously until the spill is contained.

(2) Within four hours outside regular working hours and commence cleanup within 30 minutes thereafter and work continuously until the spill is contained.

3. OHS Spill Containment, Cleanup and Disposal Requirements

- a. The Contractor shall provide a spill assessment to the NASSIG OHS Spill Response Coordinator within thirty minutes of on-site arrival.
- b. The Contractor shall contain spills to minimize damage to property, risk of human exposure, and release to the environment; and to ensure the installation complies with Federal, state and local statutes and regulations, and with DoD policies, instructions and guidance.
- c. The Contractor's spill containment, cleanup and disposal work shall comply with Federal statutes and regulations, Host Nation laws, and DoD policies, instructions and guidance.
- d. The Contractor shall coordinate work with the FIC or their designated representative.
- d. The Contractor shall place spilled materials in Contractor provided ADR approved containers no larger than 200-liter drums and shall manage the handling, transportation, delivery and disposal of all spilled material off base to an appropriate disposal location as per Federal, local and DoD policies, instructions and guidance.
- e. No incidence of spread of contamination outside the containment area due to the Contractor's non-performance, mismanagement or negligence shall be permitted. If such occurs, the Contractor shall take immediate action to further contain such contamination at their own cost.

4. OHS Spill Documentation and Reporting Requirements

- a. The Contractor shall prepare and provide an initial spill/cleanup report to the assigned Government representative within one working day following response to a hazardous spill notification. The initial spill/cleanup report shall contain, as a minimum: spill location, time of spill, spill source, severity and type of spill, responding actions, and test results to the NASSIG Environmental Office.
- b. The Contractor shall provide a written post-cleanup report to the assigned Government representative within three calendar days following the securing of the spill site by the FIC. The report shall detail the amount of spill cleanup, materials used to collect the spill, any neutralizing agents that might have been used, type of container used and any other pertinent information, backfill utilized, amount of absorbents, etc.

ATTACHMENT J-0200000-11
NAVAL HOSPITAL DISASTER EXERCISE SUPPORT

1. Overview. During a disaster exercise, the Contractor shall jointly participate with NAS Sigonella Naval Hospital staff in a simulation of an actual natural or manmade disaster. This will involve the hospital staff closing the blast doors, disengaging the normal electrical power main breaker by the NAS Public Works Department personnel, and the hospital staff enacting various medical tasks that would be representative of an actual disaster.

2. Disaster Exercise Support Requirements. The Government will provide advance notification to the Contractor of an upcoming disaster exercise within five days prior to the planned exercise date. When ordered, the Contractor shall provide one Electrician and one Equipment Mechanic to standby with the Naval Hospital Operating Manager (within the confines of the Hospital, Building 273) during a hospital disaster exercise. During the exercise, the Contractor shall be available to and shall correct any equipment deficiencies that might prevent the continuation of the exercise and note any and all discrepancies involving equipment not performing as intended, e.g., inability to secure a blast door, emergency generators not activating online after the normal power main breaker is disengaged, a fresh air damper on an air handling unit not closing, the direct digital control (DDC) not functioning as intended, the biological and decontamination bypass valves malfunctioning, the failure of any equipment to function as intended once the hospital returns to normal operation at the close of an exercise.

a. Response Requirements. The Contractor shall provide the specified onsite staffing at the scheduled start time of a planned disaster exercise operations or within one hour of an unannounced disaster exercise and complete the entire operation within one working day.

b. Reporting Requirements. The Contractor shall provide a written deficiency summary report to the KO within three working days following completion of the exercise.

ATTACHMENT J-0200000-12
EXHIBIT LINE ITEM NUMBERS

Exhibit Line Item Numbers are provided as a separate attachment. Refer to Microsoft Excel Spreadsheet “J-0200000-12 ELINS”: