

**Presolicitation Notice
(Construction)**

FAR 5.201 & Revolutionary FAR Overhaul (RFO)36.101-4

Agency: Bureau of Reclamation

Notice Id: 140R4026R0006

Title: GCFD POWERPLANT UPS (SCADA EACCS)

PSC: N059 – Installation of Equipment – Electrical and Electronic Equipment Components

NAICS: 238210 – Electrical Contractors and Other Wiring Installation Contractors

Size Standard: \$19.0 M

Set-Aside: Total Small business set-aside

Contract Type: Firm-Fixed-Price

Acquisition Method: FAR Part 15

Place Of Performance: Glen Canyon Dam, Hwy 89, Page, AZ 86040

Period Of Performance: 545 days from NTP

Wage Determination: Construction Wage Rate Requirements (Davis-Bacon) will apply; current WD will be included in the solicitation.

Bonds: Performance and Payment Bonds required per FAR 28.102.

Magnitude of Construction: Between \$1,000,000 and \$5,000,000

Description:

The work primarily involves replacing the SCADA Uninterruptible Power Supply (UPS) at the Glen Canyon Dam facility. This includes demolishing and removing the existing SCADA UPS system and all associated components, as well as removing conduit and conductors that will not be reused. A new SCADA UPS system must be provided and installed along with all necessary components, including new conduit and conductors where existing ones cannot be reused.

Additional requirements:

- Perform all electrical modifications, terminations, labeling, testing, commissioning, and cutover to minimize downtime.
- Provide shop drawings, submittals, factory/start-up support, and training for operations staff.
- Deliver acceptance testing, as-built documentation, O&M manuals, and warranty support.
- UPS is a brand name or equal requirement

Brand Name: Schneider Electric 480V UPS with External-Battery

Equal Characteristics:

A. System Capacity under full rated load at a minimum of 0.9 power factor with batteries fully charged:

1. Power: 80,000 Volt-ampere, minimum.
2. AC power input: 480 VAC, 3 phase, 60 Hz.
3. Voltage Range: Plus 10 percent, minus 15 percent, maximum.
4. Total Harmonic Current Distortion (THD): 5 percent, maximum.
5. Battery Capacity:
 - a. Discharge time to end voltage: 6 hours, minimum.
 - b. Capable of delivering 125 percent of full rated load at start-up.
 - c. Four-strings, minimum.
6. AC Power Output:

- a. 480 VAC, 3 phase, 60 Hz.
- C. Short Circuit Rating: 50 kAIC, minimum.
- D. Bolt and lug size UL recommended and Manufacturer.
- E. External battery bank in separate cabinet.
- F. Enclosure: NEMA 1, or better.
- G. Communications:
 - 1. Remote access via Modbus TCP/IP or DNP3.
 - 2. Five alarm inputs.
 - 3. Three alarm relay outputs.
 - 4. RS-232, RS-485 serial.
- H. Swappable power modules.
- I. Draw-out assemblies.
- J. Voltage Regulation:
 - 1. Balanced Load: Plus or minus 1.0 percent.
 - 2. 100 percent load imbalance, phase-to-phase: Plus, or minus 3 percent.
- K. Provide equipment nameplates.
- L. VPR, UL 1449 listed and shall not exceed the following:
 - 1. 480Y/277 Volt Applications: 1200V L-N, L-G, N-G; 2000V L-L.
 - 2. 480-Volt Delta Applications: 2000V L-G, 2000V L-L.
- M. Nominal Discharge Current in accordance with UL 1449 and IEEE C62.62 for the following applications:
 - 1. Distribution Panelboards: 20 kAIC, minimum.
- N. Short Circuit Current Rating: 200 kAIC, minimum in accordance with UL 1449.
- O. Surge Current Ratings as specified in IEEE C62.41 for the following applications:
 - 1. Distribution Panelboards: 100 kA per mode, 200 kA per phase.
- P. Visual Status Indicators:
 - 1. LCD touch screen or LED line display.
 - 2. Externally visible.
 - 3. Indicate online status.
 - 4. Protection status.
 - 5. Operation Mode:
 - a. NORMAL.
 - b. BYPASS.
 - c. BATTERY.
 - d. ALARM.
- Q. Rectifier shall be solid state and provide direct current to the DC bus.
 - 1. Input Circuit Breaker sized to accept simultaneously the full-rated load and battery recharge current.
 - 2. Bolt and lug size UL recommended by Manufacturer.
- R. Inverter Unit:
 - 1. Solid-state capable of accepting power from the DC bus while providing AC output power within defined limits.
 - 2. Output Overload: The inverter shall withstand and overload across its output terminals.
 - 3. Synchronism: Normal operation in phase-lock with the bypass source.
 - 4. Output Circuit Breaker: Shunt-trip.
- S. Provide protection for the following:
 - 1. Undervoltage.

2. Overvoltage.
 3. Overcurrent.
 4. Transient surges from the AC power source in accordance with IEEE C62.41.1 and C62.41.2.
-

Agency Policies and Procedures

In addition to FAR Part 43 (RFO), Bureau of Reclamation follows internal procedures to ensure timely definitization of equitable adjustments for change orders. These procedures include:

- Prompt negotiation of change orders upon identification of scope changes.
- Use of bilateral modifications whenever practicable.
- Establishment of target definitization timelines in contract administration plans.

Past Performance Data

The Department of the Interior provides a page for Construction Contract Administration that includes definitization data for change orders under construction contracts. It lists the number of change orders and timeframes (e.g., 30 days or less, 31–60 days, etc.) for the past three fiscal years.

DOI Construction Contract Administration:
<https://www.doi.gov/pam/acquisition/policy/constructioncontract>

Anticipated date of award: July 1, 2026

Evaluation:

Offers will be evaluated per FAR Part 15. Factors may include price, technical capability, past performance, and schedule.

Points Of Contact:

- Contract Specialist: Megan Swift, mswift@usbr.gov, 303-445-2722
- Contracting Officer: Lisa Laughbon, llaughbon@usbr.gov, 801-524-3732

Instructions:

This notice is issued under FAR 36.101-4 (RFO) and FAR Subpart 5.2 (RFO). It is not a request for proposals. The complete solicitation will be posted exclusively on SAM.gov and will not be distributed via mail, fax, or in hard copy. All qualified and responsible sources are invited to submit proposals during the solicitation phase, and each submission will receive full consideration by the agency. Offerors must be registered in SAM.gov with valid UEI.