

PERFORMANCE WORK STATEMENT

FOR

**FAIRCHILD AFB
OPTIMIZED REMEDIATION CONTRACT**

AT

FAIRCHILD AFB, WASHINGTON

**CONTRACT NUMBER:
FA8903-25-R-0035**

16 SEPTEMBER 2025

CONTENTS

1.0	SCOPE.....	4
1.1	INTRODUCTION.....	4
1.2	OVERVIEW OF ORC SCOPE AND REQUIREMENTS.....	4
1.2.1	<i>Specific Scope Discussion and Limits</i>	6
1.2.2	<i>Preliminary Assessment/Site Inspection, Remedial Investigation or Remedial Investigation/Feasibility Study (including Supplemental Investigations), and Decision Document</i>	6
1.2.3	<i>Response Complete or Site Closeout</i>	6
1.2.4	<i>Remedial Action-Operation with Optimization</i>	6
1.2.5	<i>Remedial Action-Operation and Reduce Life Cycle Cost; Long Term Management and Reduce Life Cycle Cost</i>	6
1.2.6	<i>Remedial Action-Operation or Long-Term Management (as appropriate)</i>	7
1.2.7	<i>Alternate Objectives</i>	7
1.3	PERFORMANCE REQUIREMENTS.....	10
1.3.1	<i>Table 1: Performance Table</i>	10
1.3.2	<i>Additional Scope Discussion and Limits</i>	15
2.0	APPLICABLE DOCUMENTS.....	17
3.0	GOVERNMENT FURNISHED INFORMATION AND PROPERTY	18
4.0	MANAGEMENT, PLANNING, AND REPORTING REQUIREMENTS.....	18
4.1	PROJECT MANAGEMENT PLAN	19
4.2	SCHEDULE AND PLANNING REQUIREMENTS – INTEGRATED MASTER SCHEDULE	19
4.3	MILESTONE PAYMENT SCHEDULE	21
4.4	COST AND STATUS REPORTING.....	24
4.5	ORC DOCUMENT REPOSITORY.....	24
4.6	MEETING AND CONFERENCE REQUIREMENTS.....	25
4.6.1	<i>Meeting/Teleconference Support</i>	25
4.6.2	<i>Public Meetings and Hearings</i>	26
4.6.2.1	<i>Community Involvement Plan (CIP) Update</i>	26
4.7	SPATIAL DATA (MAP) REQUIREMENTS.....	27
4.8	INFORMATION SECURITY	28
4.8.1	<i>Computer and Network Access Requirements:</i>	28
4.8.2	<i>Cybersecurity Reporting</i>	29
4.9	NOTIFICATION REQUIREMENTS.....	30
4.10	PERMITS.....	30
4.10.1	<i>Environmental Permits</i>	30
4.10.2	<i>Rights of Access to Non-AF Real Property</i>	31
4.11	PHOTO DOCUMENTATION	31
4.12	REMOTE AND/OR AUSTERE SITES.....	32
4.13	SITE ACCESS	32
4.14	WORKSITE ACTIVITIES AND COORDINATION	32
4.14.1	<i>Coordination of Activities</i>	32
4.14.2	<i>Radiological Waste, Hazardous Material, and Hazardous Waste Permitting and Reporting</i>	33
5.0	CHEMISTRY REQUIREMENTS.....	34
5.1	QUALITY ASSURANCE.....	34
5.2	LABORATORY SELECTION	35
5.3	ANALYTICAL DATA MANAGEMENT	35
5.4	RECORD KEEPING.....	36

5.5	PFAS SAMPLING AND ANALYSIS	36
6.0	PLANS AND REPORTS.....	36
6.1	QUALITY PROGRAM PLANS	36
6.1.1	Work Plans.....	36
6.1.2	Health and Safety Plan	36
6.1.3	Construction Quality Plan	37
6.2	TECHNICAL PLANS AND REPORTS	37
7.0	SITE WORK.....	38
7.1	CONSERVATION.....	38
7.2	SITE CHARACTERIZATION AND FIELD INVESTIGATION	39
7.3	SITE PREPARATION.....	39
7.4	DEMOLITION	39
7.5	SITE RESTORATION	39
8.0	ENVIRONMENTAL REQUIREMENTS	40
8.1	ENVIRONMENTAL RESTORATION PROCESS APPLICATION	40
8.1.1	Conceptual Site Model Guidance	41
8.1.2	Exit Strategy.....	42
8.1.3	Performance and Optimization.....	43
8.2	TRANSITION OF WORK	45
8.3	ENVIRONMENTAL CONSTRUCTION	47
8.3.1	Design.....	47
8.3.2	Inspection.....	47
8.3.3	Delivery and Warranty	48
8.4	ENVIRONMENTAL RESOURCES PROGRAM INFORMATION MANAGEMENT SYSTEM.....	48
8.5	INNOVATIVE AND PROVEN TECHNOLOGIES	48
8.6	OPERATIONS AND MAINTENANCE	49
8.7	ORDNANCE REMOVAL AND SUPPORT.....	49
8.8	RADIOLOGICAL AND HAZARDOUS WASTE REMOVAL AND SUPPORT	49
8.9	STUDY EFFORT INCIDENTAL TO REMEDY OR CORRECTIVE ACTION.....	50
8.10	FIVE-YEAR REVIEW SUPPORT.....	50
9.0	PERFORMANCE STANDARDS AND SURVEILLANCE ACTIVITIES.....	50
10.0	SERVICE CONTRACT REPORTING (SCR) REQUIREMENTS	59
11.0	CONTRACTOR LABOR HOURS.....	59
12.0	USES AND SAFEGUARDING OF INFORMATION	59
13.0	POINTS OF CONTACT	59

1.0 SCOPE

This requirement is for environmental remediation activities at Fairchild Air Force Base (AFB). This Performance Work Statement (PWS) defines the scope of environmental services necessary to conduct site restoration under the Optimized Remediation Contract (ORC). The range of activities includes maintenance of established remedies, optimization at applicable sites, and achievement of site-specific objectives. The Contractor shall undertake Environmental Remediation activities to achieve Performance Objectives (POs) at thirteen (13) Installation Restoration Program (IRP) sites.

NOTE: For purposes of this ORC, the term “Government” includes the Air Force (AF) and 772nd ESS. While regulators are a governmental entity, they are also a third party over whom the Air Force has no control and, as such, will be referred to as “regulators.”

1.1 Introduction

Fairchild AFB is in eastern Washington, 12 miles west of the City of Spokane, in Spokane County, and occupies approximately 4,300 acres. Fairchild AFB was established in 1942 as the Spokane Army Depot. In 1950, the name was changed to Fairchild AFB. The 92d Air Refueling Wing (ARW) is the host unit at Fairchild AFB. Fairchild AFB is also home to the 141st ARW; the 336th Training Group, which operates the USAF Survival, Evasion, Resistance, and Escape School; Armed Forces Reserve Center; and the Joint Personnel Recovery Agency. Its primary mission is to maintain and repair aircraft, primarily large aircraft such as bombers and tankers.

Fairchild AFB is regulated by the U.S. Environmental Protection Agency (EPA), Region 10 and the Washington Department of Ecology (WA Ecology) under a Federal Facilities Agreement (FFA) signed in 1990. It has been on the National Priorities List (NPL) since March 1989.

Remediation activities at Fairchild AFB are being conducted pursuant to the Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA), as amended by the Superfund Amendments and Reauthorization Act (SARA), and the State Voluntary Cleanup Program (VCP). Regulatory oversight is provided by EPA Region 10 and the WA Ecology.

1.2 Overview of ORC Scope and Requirements

The Contractor shall perform all the necessary environmental remediation activities needed to achieve the performance requirements described in Section 1.3 of the PWS, inclusive of the POs listed in Table 1, Performance Table, and additional scope in Section 1.3.2. This PWS and the enclosures listed below detail the project requirements needed to meet the AF objectives:

- Enclosure 1 – Acronyms and Definitions
- Enclosure 2 – Government Furnished Information (GFI)
 - Enclosure 2A – Administrative Record Spreadsheet
 - Enclosure 2B – GFI Compact Disc
- Enclosure 3 – Government Furnished Property (GFP)
- Enclosure 4 – Community Involvement Plan (CIP) Guidance version 4

The intent of the ORC initiative is to advance site cleanup during the Period of Performance (POP) in the most efficient and cost-effective manner, as supported by a cost-benefit analysis and exit strategy that achieves the greatest reduction in life-cycle cost (LCC). The AF is interested in substantial reduction of long-term environmental liabilities and total LCC.

Technical approaches that are simply reduced to a minimal level of effort with no well-planned contingencies provide no assurance to the Government that the POs will be achieved without work stoppages or change orders which is not in keeping with the intent of this performance-based contracting effort. The AF is required to implement remedies as necessary to enable the mission, protect human health and the environment, and comply with laws and regulations. The goal of the ORC initiative is to ensure the AF continues to fulfill all facets of its Environmental Restoration Program (ERP) mission by effectively and efficiently managing the program in a performance-based, results-oriented, and cost-conscious framework.

The AF requires that all sites be cleaned up to standards that allow for the current or reasonably anticipated future land use of the property. Accurate documentation and reporting of contaminant removal and cost savings are critical adjuncts to optimization success. In keeping with Defense Environmental Restoration Program (DERP) and Air Force Instruction (AFI) 32-7020, the AF defines optimization under the ORC as the reduction of contaminant mass and concentrations, reduction in LCC, or any combination of activities leading to acceleration of Response Complete (RC)/Site Closeout (SC) as a result of remedial implementation the Contractor undertakes, above and beyond what is required to maintain compliance in accordance with an approved Decision Document (DD).

The Contractor shall maintain compliance with all binding agreements (including but not limited to DDs/Records of Decision (RODs), Proposed Plans, RCRA Permits) that are currently in place until no longer required, or an alternate approach is approved. The contractor shall conduct DD/ROD amendments or Explanation of Significant Differences (ESD) as required to implement new approaches.

The Contractor shall function as an integral team member in support of the Air Force Civil Engineer Center (AFCEC) mission to include the sharing of information with other AFCEC Contractors, and AF personnel, in cooperation with community stakeholders, regulators, and other Government entities.

Requirements for efficient management of this contract include the achievement of the POs in the Performance Period (PP) per Table 1 and work described in Section 1.3.2 of this PWS. Requirements include timely identification and solution of impediments to successful project execution. The Contractor shall provide all personnel, equipment, supplies, tools, materials, and other items necessary to perform the tasks defined in this PWS. The Contractor is solely responsible for reviewing all available information and forming their independent, professional conclusions/interpretations of site conditions and requirements to achieve the POs of this contract within PP specified. AFCEC will rely on the Contractor's expertise in recognizing and addressing problematic issues during the execution of this contract. The Contractor shall perform all work in accordance with federal, state, and local statutes and regulations. The Contractor shall also comply with installation regulations. Remedies shall conform to

environmental permits, DD requirements, and/or other legal requirements. The Contractor shall continue work throughout the entire duration of the POP. The expectation is that the Contractor will complete all field activities within the POP. If reporting on the field activities extends beyond the POP it is expected that the Contractor will turn over all data, native files, field documentation, etc. required for the reporting to be completed under subsequent contracts. Conversely, the Contractor is expected to complete reporting for the field activities completed in the calendar year of the award unless specified otherwise. The Contractor's local office presence will be relied upon to provide rapid-response actions for field activities and on-site meetings.

POs are identified in Section 1.3.1 Table 1: Performance Table and in Section 1.3.2. POs that are in keeping with standard DERP milestones are defined in Enclosure 1. In addition, for certain categories of sites, the AF has set POs based on current site conditions and consistency with the POP of the contract and ORC goals.

1.2.1 Specific Scope Discussion and Limits

The scope of this contract is to perform environmental remediation services listed in Table 1 and Section 1.3.2. The ORC Contractor shall assume contractual liability and responsibility for achieving the POs. If the selected technical approach is not working, as demonstrated by the trends in the performance model, the Contractor shall develop and implement a revised technical approach to achieve the POs, including DD amendments, if required, to implement the remedial approach. This scope includes all known contaminants linked to the specific sites per Table 1 of the PWS (includes contaminants on, under, or sourced at/migrating from the specific sites) without regard to quantity (e.g., plume size, concentrations). See reference to Section 1.3.2.j of the PWS for exclusions. The AF remains statutorily responsible for all sites listed in Table 1 and work described in Section 1.3.2.

1.2.2 Preliminary Assessment/Site Inspection, Remedial Investigation or Remedial Investigation/Feasibility Study (including Supplemental Investigations), and Decision Document

Table 1 of the PWS identifies Preliminary Assessment/Site Inspection (PA/SI), Remedial Investigation (RI) or RI/Feasibility Study (FS), including Supplemental Investigations, and DDs as the PO for selected sites. The Contractor is responsible for achieving these POs as identified in Table 1 and work described in Section 1.3.2. See PO definitions in Enclosure 1, Acronyms and Definitions.

1.2.3 Response Complete or Site Closeout

NOT APPLICABLE

1.2.4 Remedial Action-Operation with Optimization

NOT APPLICABLE

1.2.5 Remedial Action-Operation and Reduce Life Cycle Cost; Long Term Management and Reduce Life Cycle Cost

NOT APPLICABLE

1.2.6 Remedial Action-Operation or Long-Term Management (as appropriate)

Table 1 of the PWS identifies Remedial Action-Operation (RA-O) or Long-term Management (LTM) in accordance with the approved DD/ROD as the PO for selected sites. The Contractor shall achieve the following objectives for each RA-O and LTM site:

- Maintain compliance with all DDs and permits (currently in place or to be approved) throughout the PP. Update or revise site-specific work plans, monitoring plans, and/or DDs, as appropriate.
- For RA-O sites, develop performance models addressing all Contaminants of Concern (COC)s and breakdown products. Refer to Section 8.1.3.1, Performance Models.
- Provide a realistic projection to achieve SC or RC after the POP (the Contractor shall identify which PO is the optimal endpoint).

1.2.7 Alternate Objectives

This section and the subparagraphs below describe the Alternate Objective Sites and a general overview of the work associated with these sites. ***Please see Table 1 and work described in Section 1.3.2 for specific elements of work required for each site with an Alternate Objective PO.*** These sites have complex attributes that have, to date, inhibited progress toward the achievement of RC. For Alternate Objective sites, as for all sites in Table 1 of the PWS where applicable, the Contractor shall maintain compliance throughout the POP of the contract with all existing regulatory requirements, including but not limited to regulations, FFAs, RCRA Permits, final or interim RODs, or other equivalent remedial DDs. The Contractor is responsible for implementing changes to the monitoring program based on activities conducted in the Advanced Site Characterization (PWS Section 1.2.7.1), including the addition and decommissioning of wells in the monitoring well network as agreed by all parties and the addition of new delineation monitoring where new information indicates our understanding of the plumes is changed.

Based on technical review of existing site conditions/activities, the AF placed sites in the category of Alternate Objective if one or more of the following conditions exist:

- Achieving RC is expected to require substantially longer than 30 years.
- Achieving RC is unattainable with standard characterization and/or existing remediation technology due to technical or other limitations related to site conditions.
- Achieving RC is anticipated to require advanced site characterization technologies to improve the Conceptual Site Model (CSM), determine appropriate remedial technology, and/or characterize recently regulated contaminants.

The AF will use data and information obtained during execution of this PWS to determine restoration potential and future investment strategies at Alternate Objective sites. Each Sub-CLIN for the Alternate Objective sites will only be awarded if the activities are needed to determine the future investment strategy for the site. The decision to award each Sub-CLIN resides solely at the discretion of the AF.

The Contractor shall conduct project scoping sessions before work plan development and throughout the planning and execution of the project to meet the PO, including the Installation Point(s) of Contact (POC[s]): the AFCEC Program Manager (PM), Remedial Project Manager (RPM), the AF technical support team, and the Contracting Officer's Representative (COR). Upon approval by the AF and the COR, the Contractor shall participate in scoping sessions with the regulators as appropriate.

1.2.7.1 Advanced Site Characterization

Based on existing data, the AF has determined that the existing remedial approaches at the Alternative Objective sites are not achieving satisfactory remedial progress toward their intended goals. In order for the AF to determine the best path forward for these sites, the Contractor shall conduct Advanced Site Characterization to collect data to update and refine the CSM in order to achieve the following goals: (1) Fill data gaps; and (2) Collect data needed to: (A) Determine why existing and previous remedial actions are not effective at achieving remedial progress; (B) Determine appropriate remedial technology(ies) based on site conditions; C) Develop remediation design parameters for recommended technology(ies); and D) Determine extent and concentrations of recently regulated contaminants, if required.

Advanced Site Characterization includes one or more of the following three activities: (1) Supplemental Site Investigation (SSI), (2) Revised CSM, and (3) Groundwater Monitoring Program Update.

1.2.7.1.1 Supplemental Site Investigation

The Contractor shall conduct a SSI to collect data necessary to improve the CSM, determine appropriate remedial technology, support remediation design and construction, and/or characterize recently regulated contaminants. The Contractor shall implement advanced characterization methods, both established approaches and state-of-science techniques consistent with AF, regulatory, Interstate Technology and Regulatory Council (ITRC), and Strategic Environmental Research and Development Program/Environmental Security Technology Certification Program (SERDP/ESTCP) guidance to attain these objectives. Data collection includes better definition of geology, hydrogeology, geochemistry, and/or source(s) and distribution of COCs, as required. The Contractor shall evaluate the need for, and collect the following data where appropriate: (1) Source Zone Delineation; (2) Source Mass/Extent^{1,2,3}; (3) Vertical and lateral extent of contamination, if not sufficiently defined; (4) Plume Stability⁴; (5) Migration pathway, rates, and fluxes in 3-D; (6) Mass distribution; (7) Biogeochemical conditions and influences on contaminant degradation pathways; (8) Impact of recent and historical remedies on site conditions; and (9) Comprehensive Risk including the vapor intrusion pathway.

¹ ITRC. (2015). *Integrated DNAPL Site Characterization and Tool Selection*.

² SERDP/ESTCP. (2012). *Matrix Diffusion Tool Kit*.

³ USEPA. (2009). *Evaluating Natural Source Zone Depletion at Sites with LNAPL*.

⁴ USEPA. (2014). *High Resolution Site Characterization for Groundwater Short Course, 23rd Annual NARPM Training Program*.

The SSI report shall document data collection efforts to include a risk evaluation, if appropriate. The Contractor shall evaluate and provide recommendations regarding whether additional source control is needed or whether the plume, or portions of the plume, are amenable to natural attenuation by conducting source strength and plume stability evaluations as needed.

1.2.7.1.2 Conceptual Site Model

The Contractor shall develop a revised CSM in 3-D to include establishing or updating existing fate and transport models based on existing data and data gathered during the SSI. The CSM should cover the source area and the distal plume, to include the lateral and vertical extent of the contaminants in the context of geologic/hydrogeological parameters and the remedial actions conducted to date.

1.2.7.1.3 Groundwater Monitoring Program Update

The Contractor shall evaluate the current horizontal and vertical well distribution to determine if the following can be properly evaluated:

- Remedy performance in treatment areas
- Hydrogeology, plume geometry, horizontal and vertical plume stability, and matrix diffusion across site
- Plume migration through use of perimeter/boundary wells and sentinel wells

Based on the well network evaluation, coordinated and approved by the Government and regulators (if required), the Contractor shall optimize the monitoring well network to include adjusting sample collection frequency and the addition of new wells as appropriate. The Contractor shall update the Basewide or Site-Specific Monitoring Plan or other equivalent document, as appropriate.

1.2.7.2 Remedy Evaluation and Recommendation

Based on all existing data and data gathered during the Advanced Site Characterization, the Contractor shall evaluate the existing active and/or passive remedy(ies)^{5,6,7}. The Contractor shall provide recommendations to augment, modify, and/or replace the existing remedy⁸. The evaluation and recommendations will include a cost-benefit analysis and evaluation of the usability, expandability, and/or discontinued use of any existing infrastructure. All remedy recommendations must include a performance model addressing all COCs and breakdown products. Refer to Section 8.1.3.1, Performance Models.

Where necessary to evaluate the proposed technology, the Contractor shall conduct pilot-scale technology demonstrations. The Contractor shall identify appropriate remedial technologies and target zones, design/plan, conduct, and evaluate the pilot and/or field scale technology consistent with AF, regulatory, and ITRC guidance. The Contractor shall determine performance

⁵ USEPA. (2010). *Best Management Practices*.

⁶ USEPA. (2014). *Groundwater Remedy Completion Strategy*.

⁷ ITRC. (2006). *Performance-Based Management*.

⁸ ITRC. (2010). *Use and Measurement of Mass Flux and Mass Discharge*.

monitoring criteria and identify a control sub-site (current state) for comparison and to evaluate results.

In some instances, achievement of RC may not be feasible with currently available technologies within a reasonable timeframe. If this is the case, Contractor shall develop and evaluate alternatives for site management that will be protective of human health and the environment. If this recommendation is made, it must include the rationale, recommended target when active remediation can cease, and a strategy for obtaining regulatory approval.

1.2.7.2.1 Cost/Benefit Analysis

The Contractor shall provide a cost/benefit analysis for proposed alternatives. Alternatives may include optimizing the remedy in the DD or other remedies with the potential for better performance. All alternatives identified shall be evaluated against one another to determine which alternative can achieve RC in the shortest time and has the lowest overall LCC. The cost/benefit analysis shall include:

- A focused analysis of alternative approaches, to include conceptual designs and engineering cost estimates. The analysis shall identify the total cost of executing the optimized remedy (including the plan and reports).
- An estimate of the reduction of LCC of each alternative evaluated.
- Any risk inherent in implementing the alternative optimized remedy.
- A summary comparison of the LCC and risk of each alternative in a cost/benefit analysis that clearly states the recommended alternative.

1.2.7.3 Decision Document Amendment

Based on the results of the remedy evaluation and recommendation, it may be necessary to amend the Decision Document to augment, modify, and/or replace the existing remedy. If warranted, the Contractor shall update the Decision Document.

1.3 Performance Requirements

1.3.1 Table 1: Performance Table

Table 1 presents the POs, PPs, and Performance Standards associated with all installations/sites under this ORC. The PP specified in Table 1 starts from the Obligation Date of the first Sub-CLIN for the site unless otherwise specified. All approvals (both Government and regulator) per the Performance Standard are required in writing. Additional scope discussion and limits can be found in Section 1.3.2.

Table 1: Performance Table

Site	Performance Objective	Performance Period*	Performance Standard
N/A	Project Management Plan (PMP): 1) Draft PMP 2) Final PMP 3) Updates as necessary	Draft PMP within 60 calendar days from contract award, Final PMP within 14 calendar days of receipt of AF comments on the draft and update as necessary throughout the POP. The AF will determine when whole document PMP updates are warranted	AF approval of PMP. The PMP should be maintained with accuracy and completeness based on the current technical approach for each site, management structure, etc.
N/A	Integrated Master Schedule (IMS)/Milestone Payment Schedule (MPS)	Draft IMS/MPS within 60 calendar days from contract award, Final IMS/MPS within 14 calendar days of receipt of AF comments on the draft, and updates monthly throughout the POP	AF approval of IMS/MPS.
N/A	Basewide Quality Program Plans (QPP)	Draft Basewide QPP within 60 calendar days from contract award and update as necessary throughout the POP	AF and regulatory approval of Basewide QPP.
N/A	Land Use Control Implementation Plan (LUCIP)	One (1) year	AF and regulatory approval of LUCIP.
N/A	1,4-Dioxane Step 1	Two (2) years	AF and regulatory approval of Tech Memo/Report
N/A	1,4-Dioxane Step 2	Three (3) years	AF and regulatory approval of Tech Memo/Report
N/A	1,4-Dioxane Step 3	Three (3) years	AF and regulatory approval of Tech Memo/Report

Site	Performance Objective	Performance Period*	Performance Standard
All Open Sites (IRP, MMRP, PFAS, etc.)	Community Involvement Plan (CIP) and updates are required prior to the RI phase, after the DD/ROD is signed, and every five (5) years thereafter for each Installation and associated Geographically Separate Units (GSUs), per Enclosure 4.	Draft CIP or Update within 180 calendar days from Sub-CLIN award; Draft Final CIP or Update within 14 calendar days of receipt of AF comments on the draft; Final CIP or Update within 14 calendar days of approval by the AF.	AF and regulatory approval of CIP.
Fairchild AFB			
DP064	Record of Decision	Three (3) years	AF and regulatory approval of ROD/DD (i.e., Air Force and regulatory signatures on Final ROD/DD).
FT004	Removal of unused treatment system	One (1) year	AF and regulatory approval of System Abandonment Completion Report.
LF001	LTM in accordance with the approved ROD/DD	Within one (1) year from exercise of each Sub-CLIN	AF and regulatory approval of LTM documentation (e.g., Land Use Control Inspection Reports).
LF002	RA-O in accordance with the approved ROD/DD	Through the duration of OP 8	AF and regulatory approval of RA-O documentation (e.g., Annual Groundwater Monitoring Reports, Monthly Operations and Maintenance [O&M] Reports, etc.). AF approval of Performance Model Evaluation Report during RA-O.
LF002	Restart Remediation System	One (1) year	AF and regulatory approval documenting completion of all actions in a System Start up Report.
OW058	Record of Decision	Three (3) years	AF and regulatory approval of ROD/DD (i.e., Air Force and regulatory signatures on Final ROD/DD).

Site	Performance Objective	Performance Period*	Performance Standard
SD037	RA-O in accordance with the approved ROD/DD	Nine (9) years	AF and regulatory approval of RA-O documentation (e.g., Annual Groundwater Monitoring Reports, Monthly Operations and Maintenance [O&M] Reports, etc.). AF approval of Performance Model Evaluation Report during RA-O.
SD037	Alternate Objectives: 1) Advanced Site Characterization (Supplemental Site Investigation (SSI), Revised Conceptual Site Model (CSM), and Recommended Monitoring Program Update) 2) Remedy Evaluation and Recommendation (including results of any pilot study) 3) Decision Document Amendment	Nine (9) years	AF and regulatory approval of SSI Report, revised CSM and Base-wide Monitoring Plan. AF approval of the remedy evaluation and recommended proposed remedial strategy including successful demonstration of the existing or alternate remedy (e.g., through pilot or field test) showing decreasing trends in COCs. AF and regulatory approval of ESD or ROD Amendment (i.e., Air Force and regulatory signatures on Final ESD or ROD Amendment).
SS009	Achieve Supplemental Investigation/Corrective Measures Study Achieve Corrective Action Plan (CAP)	Five (5) years	AF and regulatory approval of CMS and CAP (i.e., Air Force and regulatory signatures on Final CMS and CAP).
SS009	LTM in accordance with the approved CAP	Through the duration of OP 8	AF and regulatory approval of LTM documentation (e.g., Land Use Control Inspection Reports).

Site	Performance Objective	Performance Period*	Performance Standard
SS039	Achieve Advanced Site Characterization including Supplemental Site Investigation, Revised 3-D Conceptual Site Model, and Updated Groundwater Monitoring Program (I)RA-O in accordance with the interim ROD/DD	Through the duration of OP 8	AF and regulatory approval of RA-O documentation (e.g., Annual Groundwater Monitoring Reports, Monthly Operations and Maintenance [O&M] Reports, etc.). AF approval of Performance Model Evaluation Report during RA-O.
ST006	Removal of unused treatment system	One (1) year	AF and regulatory approval of System Abandonment Completion Report.
TU500	RA-O in accordance with the approved CMS/CAP	Through the duration of OP 8	AF and regulatory approval of RA-O documentation (e.g., Annual Groundwater Monitoring Reports, Monthly Operations and Maintenance [O&M] Reports, etc.). AF approval of Performance Model Evaluation Report during RA-O.
TU502	Remedy in Place (RIP) Upon achievement of RIP, continue RA-O with optimization in accordance with the CMS/CAP throughout the duration of the POP	Three (3) years Through the duration of OP 8	AF and regulatory approval of RIP (e.g., Construction Completion Report and first RA-O Report demonstrating remedy is operating properly and successfully). AF approval of Performance Model Evaluation Report during RA-O. AF and regulatory approval of RA-O documentation (e.g., Annual Groundwater Monitoring Reports, Monthly O&M Reports, etc.).

Site	Performance Objective	Performance Period*	Performance Standard
TU506	RA-O in accordance with the approved CAP	Through the duration of OP 8	AF and regulatory approval of RA-O documentation (e.g., Annual Groundwater Monitoring Reports, Monthly Operations and Maintenance [O&M] Reports, etc.). AF approval of Performance Model Evaluation Report during RA-O.
WP003	ROD Amendment IRA-O until ROD Amendment is achieved RA-O in accordance with the ROD/DD Amendment throughout the duration of the POP	Three (3) years Through the duration of OP 8	AF and regulatory approval of ROD/DD (i.e., Air Force and regulatory signatures on Final ROD/DD). AF and regulatory approval of RA-O documentation (e.g., Annual Groundwater Monitoring Reports, Monthly O&M Reports, etc.). AF approval of Performance Model Evaluation Report during RA-O.
WP003	Removal of unused treatment system	One (1) year	AF and regulatory approval of System Abandonment Completion Report.

*The Performance Period is from the date of award of the first performance Sub-CLIN.

1.3.2 Additional Scope Discussion and Limits

In addition to the requirements identified in Table 1, the Contractor shall be responsible for:

- Operations and Maintenance (O&M) of all remediation equipment to include all wells belonging to the FAFB ERP and well abandonment with AF and regulatory approval (if required) when the well is no longer necessary.
- Establishing a quality control/quality assurance process to ensure documents are of an acceptable quality and do not contain typos, formatting issues, contradictory information in tables and text, etc.
- Contaminants for which there are promulgated federal, state, or local standards.
- AFCEC may determine during the POP that clean-up needs to be accomplished at a particular site where PFAS is present if there is a promulgated State Maximum

Contaminant Level (MCL) that is approved for use by the Department of Defense (DoD) as an Applicable or Relevant and Appropriate Requirement (ARAR) standard. These determinations may result in additional sites or additional work related to existing sites being added to the contract via modification.

- 1,4-Dioxane investigations shall be conducted as described in “Interim Air Force Guidance on Sampling and Response Actions for 1,4-Dioxane at Operational and [Base Realignment and Closure] BRAC Installations,” dated 24 May 2013. The Contractor shall present results in one Tech Memo/Report per installation documenting the analytical methods and maps depicting sampling locations within the trichloroethene (TCE) plume and sample analysis results.

Manage and dispose of investigation-derived waste (IDW) media associated with PFAS in accordance with the AF Guidance Memorandum “Interim Guidance on Destruction or Disposal of Materials Containing Per- and Polyfluoroalkyl Substances in the United States” dated 11 July 2023, AF Guidance Memorandum “Guidance on Incineration of Materials Containing Per- and Polyfluoroalkyl Substances” dated 14 July 2023, and Section 4.14.2 of this document.

The Contractor shall also comply with federal, state, local, and base requirements for any task involving the transportation of hazardous wastes and/or contaminated materials to off-site treatment, storage and/or disposal facilities. This includes 40 Code of Federal Regulations (CFR) Parts 260 and 263, 49 CFR Parts 172, 173, 174, 178, and 179, and all other applicable local, state, and federal transportation regulations.

- The Contractor shall test IDW for PFAS using EPA test method 1633 as required for waste acceptance. Washington waste disposal facilities are rejecting all waste without PFAS sampling, therefore all IDW must be analyzed for PFAS. If waste contains detectable levels of PFAS, it must go to a Subtitle C landfill (closest is in Oregon). If waste does not have detectable levels of PFAS it can go to the local landfill.
- For wastewater treatment sites that may be retrofitted for PFAS during the ORC POP by a non-ORC contractor, ongoing O&M activities – such as filter changeouts and the collection of influent, mid, and effluent samples for evaluation – may be added to the ORC contract via modification.
- Ensuring that remedial actions do not negatively impact the distribution of any other contaminants and/or emerging contaminants (e.g., PFAS, 1,4-dioxane).
- Basewide monitoring well network inventory, inspection, affixing monitoring well ID tags, and repair Annual Report (to include basewide maps).
- An Annual Basewide LUC report including the Voluntary Cleanup Program (VCP) sites.
- Preparing for (create and mailout invitations, support poster sessions) and conducting RAB meetings; performing community outreach activities; and preparing CIPs or Updates as described in Sections 4.6.1, 4.6.2, and Enclosure 4.

- Participation in Town Hall meeting presentations and providing posters when necessary.
- Generating a Basewide Well and LUC Boundaries map and updating annually.
- Providing maps of proposed affected areas as required for all dig permits.
- For off-base sampling locations, preparation of necessary Access Agreement, Easements, etc., on AF behalf, and/or coordination/scheduling of field activities, or providing results to homeowners.

The Contractor shall NOT be responsible for:

- Reasonably unanticipated contaminants at sites identified in Table 1 (e.g., previously undetected mercury within a TCE plume); however, Contractors would be responsible for reasonably anticipated contaminants (e.g., vinyl chloride in a TCE plume).
- Remediation or treatment of contaminants for which there are no promulgated federal, state, or local standards or AF agreements at time of contract award unless included via modification.
- Official regulatory changes occurring after contract award, as documented in Administrative Code, laws, and regulations, e.g., decrease in residential Soil Cleanup Target Levels, Groundwater Cleanup Target Levels, etc.
- Sites not identified in Table 1.
- Remediation of sites with unexploded ordnance (UXO), Discarded Military Munitions (DMMs), munitions constituents (MCs) present in high enough concentrations to pose an explosive hazard, and chemical warfare material (CWM).

2.0 APPLICABLE DOCUMENTS

The Contractor shall identify and comply with all applicable , federal, state, and local statutes, rules, policies, manuals and any other guidance; Department of Defense (DoD) and AF instructions, manuals, handbooks, regulations, guidance, and policy letters (including AF policy and guidance for IRP); Executive Orders (EOs), American Society for Testing and Materials (ASTM), American Petroleum Institute (API) Codes, National Association of Corrosions Engineers (NACE), National Fire Protection Association (NFPA), Steel Structures and Painting Counsel (SSPC), National Electrical Code (NEC), Uniform Fire Code (UFC), and International Building Code (IBC) including all changes and amendments in effect on the date of issuance of this contract, without limitation. It is the Contractor's responsibility to identify and comply with all applicable requirements. In addition, the Contractor shall refer to the current versions of the DoD Policy and Guidelines for Acquisitions Involving Environmental Sampling or Testing and The United States AF Construction Management Implementation Guide.

The Contractor shall identify and comply with all applicable documents for the installation under this ORC, including RODs, ROD Amendments, ESDs, RCRA Permits and subsequent modifications, Risk Evaluation Corrective Action Program (RECAP) documents, the Endangered Species Act, other Decision Documents, Deeds, waste management guidance, and conveyance notices.

3.0 GOVERNMENT FURNISHED INFORMATION AND PROPERTY

Government Furnished Information is contained in the Administrative Record (<https://ar.afcec-cloud.af.mil/>) or listed in Enclosure 2. The documentation provided represents the most recent and appropriate documentation available for the installation and sites identified in this PWS. Electronic format is not guaranteed.

The Contractor shall properly account for and manage all new and existing GFP procured and utilized at the installation as-is where-is in accordance with the Federal Acquisition Regulation (FAR). Lists of current GFP are provided in Enclosure 3. All Real Property installed during the contract shall be turned over to the Government consistent with procedures identified in Section 8.3.2.

The Contractor is responsible for providing all other supplies and equipment not already installed, and not listed in Enclosure 3, that are required to achieve the POs of this contract. All AF-owned property, including real property used for remediation purposes, must be maintained by the Contractor in accordance with applicable maintenance requirements and usability for the intended purpose. The Contractor is responsible for disposal of unneeded, unusable, or obsolete GFP as required, and transfer of remaining GFP to the Government at the end of the contract POP. Prior to disposal of excess or unserviceable equipment listed in Enclosure 3, the Contractor shall coordinate activities with the CO for disposition instructions.

4.0 MANAGEMENT, PLANNING, AND REPORTING REQUIREMENTS

The Contractor shall implement a full range of environmental remediation activities as required to meet objectives of this contract and in accordance with all applicable or relevant and appropriate federal, state, and local laws and regulations; DoD policies; and Installation-specific orders, agreements, or rules. The Contractor shall supply all labor, equipment, and materials necessary to accomplish the work through the entire POP of the contract. The Contractor shall perform management and planning functions, including performance measurement and fund status reporting.

The PMP, IMS, and MPS documents shall be fully integrated and consistent. Consistency shall be maintained throughout the POP by fully implementing programmatic change control processes compliant with EC 5.2.1 (Execution of Change Control Boards) and PMI guidance. It is the Contractor's responsibility to clearly demonstrate an applied understanding and compliance with ORC requirements, application of guidance/requirements, and consistency between the PMP, IMS, and MPS. The Contractor shall create a single file for each of the IMS and MPS files and deliver them as separate files as required.

4.1 Project Management Plan

The Contractor shall develop and maintain a detailed PMP. The PMP shall specify the project's resources and tasks corresponding to the Sub-CLINs for this contract as required for the planning, execution, control, and completion of the stated POs. At a minimum, the PMP shall include the following sections: technical approach for achieving the POs in accordance with the PWS, management approach including sub-contractor management, organization and integration of the project team, schedule management, project controls, transitional activities, risk management, quality management, health and safety management, procurement management, security management, and communications plans. The Contractor is responsible for complying with the "Optimized Remediation Contract (ORC) Program Management Plan (PMP) Guidance" latest version, as well as standard industry practice. Clarification on PMP content and the level of detail required to address the ORC program shall be provided by the COR.

The PMP shall demonstrate a comprehensive decomposition of each work package/PO deliverable and exhibit a clear and concise correlation between the PWS, IMS, and MPS. The Contractor is responsible for complying with the guidance for the Development of Contract Line Item Number Structures, Integrated Master Schedules, and Milestone Payment Schedules (CLIN, IMS, and MPS Guidance) per the latest version of the "Optimized Remediation Contract (ORC) Program Management Plan (PMP) Guidance."

The first draft of the PMP shall be submitted in accordance with Table 1. The Draft PMP and subsequent revisions shall be subject to AF review and approval. The Final PMP shall be due within fourteen (14) calendar days of receipt of AF comments on the Draft versions. The Contractor shall maintain the PMP throughout the duration of the contract utilizing dated page changes and track change deletions and insertions (electronic copies) as practicable. Whole document PMP updates during the life of the ORC may be necessary based on the accumulation of small incremental changes or significant changes (e.g., contract requirements, technical approaches, risk and issue management, or key personnel). The Contractor shall prepare two whole document updates during the POP of the ORC. The AF will determine when PMP updates are warranted.

4.2 Schedule and Planning Requirements – Integrated Master Schedule

The Contractor shall prepare and submit an Integrated Master Schedule (IMS) in hardcopy and in electronic format (Microsoft Project, Adobe Acrobat portable document file (.pdf)). The Baseline IMS will be finalized during development of the PMP, and the Contractor shall update monthly.

The following are minimum AF requirements for the IMS:

- Presents a realistic sequence and timing of all activities and documents necessary to demonstrate achievement of the PO within the PP. The IMS shall demonstrate full compliance with the PWS, including achieving POs within the required PP.
- Utilizes a realistic calendar (i.e., work week of five eight-hour days, no submittals on Federal holidays, etc.), appropriate logic ties, clearly defined constraints, and identifies key points where risk mitigation/contingency actions may need to be taken.

- Includes the following columns in the exact order as shown below:
 - Installation Name: Identify Enterprise Environmental, Safety, and Occupational Health Management Information System (EESOH-MIS) Installation Name per Table 1. The Installation name must be included in every line of every Sub-CLIN.
 - Site Number: Identify EESOH-MIS Site ID per Table 1 and Site Alias, if applicable. The EESOH-MIS Site ID must be included on every line of the IMS where applicable.
 - CLIN/Sub-CLIN: Identify CLIN and/or Sub-CLIN per Section B of the contract. The CLIN or Sub-CLIN must be included on every line of the IMS, as appropriate.

Note: Sub-CLINs for compliance activities (routine regulatory requirements to comply with binding agreements) are denoted as #####CX and Sub-CLINs for performance activities (remedial advancement or progress towards the PO) are denoted as #####AX. For example, for POs of RA-O with Optimization, the Performance Goal “A” Sub-CLINs are specifically for reporting progress in achieving the performance goal identified in the performance model (separate reports for each year). This requires a separate report identifying the most recent result for the performance indicator(s), usually a COC concentration, and how that compares with the projected value of the performance indicator in the performance model. The “C” Sub-CLINs are specifically for operating the remedy and reporting all required results, such as COC concentrations, geochemical, groundwater elevations, etc.

- Task Description: Include detailed description of all activities (e.g., meetings, permitting, site access, work plans, mobilization, field work, documents, reviews, coordination with stakeholders, etc.) associated with achievement of the PO, and a clear indication of regulatory CERCLA/State Program phase completions (e.g., RIP Achieved, RC Achieved, etc.) and PO achievement.
 - Activities should not be grouped together; every activity must have a separate entry. For example, the IMS must show separate activities for sample collection, sample analysis, data validation, ERPIMS upload, injections (mobilization, substrate injection, demobilization), and well installation (mobilization, drilling/well completion, demobilization).
- Start and Finish Dates: Document Start date and Finish date for each required activity and document, including appropriate durations and Government and Regulatory review periods in accordance with Section 6.2 of the PWS.
 - Include an obligation date, notice to proceed date, or projected award date as the first activity for each Sub-CLIN.
 - Include a clearly identified final field work (e.g., FINAL FIELD ACTIVITY) Start date and Finish Date for each site (i.e., indicate when

the final set of field activities such as injections, groundwater sampling, or others will be complete).

- Milestone Payment Amount: Include negotiated amount consistent with the approved MPS ensuring the sum of all milestone payments equals the value of the CLIN/Sub-CLIN per Section B of the contract.
- Percent Complete: Record completion status of all activities and documents as approved by the COR.
- Predecessor and Successor: Define relationships and constraints associated with activities and documents.

The Contractor shall prepare and maintain the IMS in accordance with the PMP Guidance (latest version). The Contractor shall maintain and submit an IMS monthly in electronic format in accordance with the requirements above and include updates to progress and approved changes (e.g., Government or regulatory review periods, technical approaches, milestone payment updates, or contract requirements). The IMSs shall be submitted electronically to the Contractor's ORC document repository and in accordance with instructions from the COR. The Contractor shall prepare and maintain the IMS in accordance with the PMP Guidance (latest version).

4.3 Milestone Payment Schedule

The Contractor shall prepare and submit an IMS, from which they will extract the information required to generate an MPS and will submit each as two separate files. NOTE: The MPS is not part of the proposal. Award of the contract does not equate to final acceptance of the IMS or of the MPS. The IMS and MPS, including payment milestones and percentages, will be discussed and agreed upon among the Government and Contractor during the review of the initial PMP/IMS/MPS and approved by the COR.

The following are minimum AF requirements for the MPS:

- Presents appropriate milestone payments considered integral and necessary to the achievement of the POs.
- Ties interim and final milestone payments to performance models as described in Section 8.1.3.1 (also see Sections 1.2.6 and 1.2.7.2).
- Includes a reasonable number of milestone payments per CLIN/Sub-CLIN based on the scope and anticipated duration to achieve CLIN/Sub-CLIN objective and/or PO.
- Aligns with the CLINs/Sub-CLINs in Section B of the award document and includes the following columns:
 - Installation Name: Identify EESOH-MIS Installation Name per Table 1.
 - EESOH-MIS Site ID: Identify EESOH-MIS Site ID per Table 1 and Site Alias, if applicable.
 - CLIN/Sub-CLIN: Identify CLIN and/or Sub-CLIN per Section B of the contract.

Note Sub-CLINs for compliance activities (routine regulatory requirements to comply with binding agreements) are denoted as #####CX and Sub-CLINs for performance activities (remedial advancement or progress towards the PO) are denoted as #####AX. For example, for POs of RA-O with Optimization, the Performance Goal “A” Sub-CLINs are specifically for reporting progress in achieving the performance goal identified in the performance model (separate reports for each year). This requires a separate report identifying the most recent result for the performance indicator(s), usually a COC concentration, and how that compares with the projected value of the performance indicator in the performance model. The “C” Sub-CLINs are specifically for operating the remedy and reporting all required results, such as COC concentrations, geochemical, groundwater elevations, etc.

- Milestone Payment Identification Number: Include unique number assigned to each milestone payment for tracking purposes.
- Milestone Payment Description: Include detailed description of definable and measurable step considered integral and necessary to the achievement of the CLIN/Sub-CLIN objective and/or PO.
- Milestone Payment Amount: Include negotiated amount ensuring the sum of all milestone payments equals the value of the CLIN/Sub-CLIN per Section B of the contract.
- Milestone Payment Percentage: Include percentage of the milestone payment in relation to the total CLIN/Sub-CLIN value. The final payment milestone(s) within a CLIN/Sub-CLIN demonstrating achievement of the CLIN/Sub-CLIN objective must be a minimum of 20% of the total CLIN/Sub-CLIN value. This may include both the AF approved and regulator approved versions. Milestones should not be front-loaded but instead be commensurate with the work completed.
- Completion Date: Document completion date for each milestone payment consistent with the Finish date presented in the IMS.
- Percent Complete: Identify completion status (0% or 100%) of all milestone payments as approved by the COR.
- Invoice Number: Clearly indicate the invoice number associated with the milestone payment as approved by the COR for the purposes of tracking payment. This information can be completed as invoices are prepared.
- Excludes unacceptable milestone payments representing a “progress” payment or a monthly payment for level of effort expended including:
 - Preparation and/or submittal of documents
 - Site mobilization/demobilization (unless exempted by CO)
 - Accomplishment of field activities including the following:

- Substrate/chemical injection
- Injection letter work plans
- Injection summary memoranda
- Field documentation tech memos
- Semi-annual cap inspection tech memos
- Quarterly and monthly LUC/LTM inspection reports
- Quarterly discharge reports
- Construction bond
- Draft reports
- Well construction logs
- Payments of Less Than 2% of Sub-CLIN cost
- Submittal of a monthly status
- Management and overhead costs (e.g., program/project management, monthly reporting, etc.)
- Allocation of PMP, Basewide Quality Program Plan (QPP), or other Basewide costs to specific sites
- Multiple draft versions of a document before AF/Regulatory approval

Refer to the ORC PMP Guidance, Section 4.4, for more detailed information on common errors in preparation of the MPS.

The Contractor shall maintain and submit an MPS monthly, in electronic format, in accordance with the requirements above and include updates to progress (e.g., Percent Complete, Invoice Number) (see Section 4.4 Cost and Status Reporting). The MPS shall be submitted electronically to the Contractor's ORC document repository and in accordance with instructions from the COR. The Contractor shall prepare and maintain the MPS in accordance with the CLIN, IMS, and MPS Guidance.

Milestone payments within a CLIN/Sub-CLIN may be revised in response to changes in the approach for achievement of the CLIN/Sub-CLIN objective without a contract modification so long as the changes do not impact the total value or objective of the CLIN/Sub-CLIN. All changes to the MPS, with the exception of tracking invoicing of completed milestone payments, must be approved by the COR.

Completion of milestones shall demonstrate payment is appropriate and warranted. COR approval of the documentation supporting the completion of the milestone is required for payment. In general, milestones are considered complete upon approval by AF (and regulators where required). Where regulatory approval or acceptance is required for this documentation, AF approval will occur following regulatory approval of the documentation. Approval occurs

upon final signature of documents requiring signature by the AF and/or regulators. The COR will take into consideration the appropriate approval of necessary documentation by regulators consistent with the applicable regulatory drivers of this PWS. The Contractor may propose a revision of the milestones to reflect their PMP and provide for interim milestones. Interim milestones will only be accepted if they represent significant progress toward milestone completion, and completion of these interim steps can be measured and demonstrated. Payments will be tied to the successful completion of major milestones, or an interim milestone plan approved by the Government, through the COR. To that end, all proposed interim milestones should be associated with easily demonstrated metrics tied to performance measurements (e.g., Government approval of a draft final report, Regulatory approval of a final document such as semi-annual and annual groundwater monitoring reports, Remedial Investigation reports, or Records of Decision). All milestones must have a defined means for demonstrating completion in order to facilitate certification.

Milestones must represent tangible progress toward achieving the PO. In general, progress payments are disallowed. Progress payments include payment for interim steps needed to achieve the PO. As an example, milestones for conducting monthly landfill inspections would represent progress payments. Acceptable milestones would be a semi-annual or annual LTM Report of the results of the landfill inspections.

For milestones where regulatory approval is required and cannot be obtained, the AF will evaluate the Contractor's supporting documents to determine if they are legally and technically acceptable to warrant payment for achieving that milestone.

The Contractor is limited to one invoice submitted to the AF per month. The invoice must itemize the milestone payments for each CLIN/Sub-CLIN associated with the invoice. The Contractor will not receive payment until milestones are achieved in accordance with the MPS. The AF will not approve partial payments.

Note that AF approval of the first version of a document that will be submitted for regulatory review is a valid milestone. AF and regulatory approval of the final version of that document is also an acceptable milestone.

4.4 Cost and Status Reporting

The Contractor shall prepare and submit a monthly Contractor's Progress, Status, and Management Report (CPSMR). The CPSMR shall be used to review and evaluate the overall progress of the project, along with any existing or potential problem areas. The report shall be prepared and submitted in an electronic format to the Contractor's ORC document repository and/or in accordance with the CPSMR Template. The CPSMR shall also be used to indicate whether efforts for each site are on target for meeting the PO. The Contractor shall submit an updated IMS each month with the CPSMR.

4.5 ORC Document Repository

The Contractor shall maintain a document repository for all ORC documents. The repository is intended to be a single access point repository for all ORC documentation. It shall be accessible

to stakeholders during the life of the ORC. The Contractor shall provide notifications to AFCEC, COR, and Installation POC(s) at the time data is included in the repository.

The Contractor shall create and maintain a Master Document List (MDL) that includes all documents, whether the document is a deliverable or not, prepared during the course of this contract. The Contractor shall maintain the project documents for the duration of this contract and delivered to the AF no later than 90 calendar days prior to POP expiration.

4.6 Meeting and Conference Requirements

4.6.1 Meeting/Teleconference Support

The Contractor shall participate in post-award meetings, Project Management Review (PMR) meetings, and teleconferences with the AF as necessary to achieve the POs in this PWS. The Contractor shall coordinate meetings, provide logistical support (e.g., facilities, audio/visual), create and present materials, and lead technical discussions.

The Contractor shall also attend and/or support meetings and teleconferences to discuss technical or regulatory issues, project progress, and status with the AF and regulatory agency representatives. Specifically, the Contractor shall host an internal kick-off meeting with the AF within fifteen (15) calendar days from contract award. In keeping with the AF's commitment to the regulators, the Contractor shall host a kick-off meeting with the AF and regulators within thirty (30) calendar days from contract award. At a minimum, the following topics will be discussed at the regulatory kick-off meeting: project schedules for field work and deliverables; achieve a mutual understanding of expected review times; identify standards, criteria, and guidance to be used during site characterization and remediation; identify potential points of compliance; identify regulatory processes and other applicable state agency programs (i.e., Water Protection, Department of Health, Air Pollution, etc.); identify site constraints and dependencies (i.e., site access, right of entry, security, ongoing site activities, topography, slope stability, etc.); and determine potential community interests.

The Contractor shall also attend and provide both technical and logistical support for Restoration Advisory Board (RAB) meetings (if needed), Tier 1/Tier II partnering meetings and teleconferences. Tier 1 meetings occur monthly, and Tier II meetings occur eight (8) times a year. Bi-weekly teleconferences shall also be required to discuss in detail progress and any technical or management issues. Also, other periodic meetings/teleconferences shall be required, as necessary. Currently, regulatory meetings occur on a monthly basis for Fairchild AFB. However, the frequency of meetings may change based on the status of the ERP. The AF will be present for all technical and public meetings with the regulatory agencies; however, the Contractor shall coordinate the meetings, provide logistical support (e.g., facilities, audio/visual), create and present materials, and lead technical discussions. The Contractor shall clearly identify themselves as "Contractors" in all situations involving stakeholders. The Contractor shall prepare and submit for AF review and concurrence any presentation materials and agendas for meetings no less than 5 working days prior to the event. The Contractor shall prepare minutes for all meetings attended within 14 calendar days following the event. Travel to/from the Installation and to other continental United States (CONUS) locations for such purposes as

meeting attendance, briefings, and/or presentations may be required in support of this remedial action. These activities are considered incidental to the effort required and shall not be included for separate milestone payments.

The Contractor shall not contact any regulatory agency without prior notification and approval by the Installation POC(s).

4.6.2 Public Meetings and Hearings

The Contractor shall support all community involvement requirements to meet CERCLA, RCRA, and other regulatory requirements including public meetings, public notices, RAB meetings, Technical Working Groups, Community Advisory Group meetings, public comment periods, and responsiveness summary preparation.

Currently, the Fairchild AFB RAB meets on an ad-hoc basis (typically semi-annually). If the RAB is not currently active, the Contractor shall reassess community interest every 24 months per AFI 32-7020 requirements. The frequency of meetings may change based on the status of the ERP. In coordination with AFCEC and the Installation POC(s), the Contractor shall attend teleconferences as necessary with the assigned Public Affairs Officer (PAO) to ensure the PAO is fully aware of all ongoing activities, public outreach status, compliance with applicable regulations, and possible issues that might impact the AF and its public image. The Contractor shall coordinate with the Installation POC(s) before any contact with the PAO.

Examples of types of Public Affairs requirements include the presentation of technical information and logistical support (e.g., advertising, audio-visual, handouts, report(s), recordings, verbatim transcripts, poster boards, slides, synopses, etc.) for events and/or meetings in support of the Government's position. All reports and other information generated under this contract shall become the property of the Government, and distribution to any other source by the Contractor is prohibited unless authorized by the COR.

The Contractor shall research, coordinate, and provide responses for short-notice internal and external requests for information, such as congressional inquiries and media requests, as needed by the PAO or other applicable action officers. These inquiries require the Contractor to provide the AF factual and responsive information within 24 hours of request.

4.6.2.1 Community Involvement Plan (CIP) Update

The Contractor shall prepare a CIP or Update the existing CIP, in accordance with Table 1, to support the installation's community involvement program (see Enclosure 4). The CIP or Update shall address how the Air Force will conduct public outreach about cleanup activities and how community members can engage and participate in decision making throughout the cleanup process. One CIP or Update is prepared for each installation. A consolidated CIP or Update is prepared for the parent installation and any applicable Geographically Separate Units (GSU).

The Contractor is required to prepare a CIP or update the existing CIP at each installation. CIPs shall be prepared as early as possible in the CERCLA process, specifically prior to the RI phase. CIP updates are completed after the DD/ROD is signed and every five (5) years thereafter. CIP

updates also are required for Removal Actions with planning periods greater than six (6) months and removal activities lasting more than four (4) months.

4.7 Spatial Data (Map) Requirements

The Contractor shall NOT establish new Geographic Information Systems (GIS).

In furtherance of the environmental construction or restoration effort, the Contractor shall provide geospatial data and map(s) of Installation features (historical, existing, or planned) altered or constructed as required to achieve the POs of this contract.

The Contractor shall provide data to update the GIS and/or computer-aided design and drafting (CADD) files as required to achieve the POs of this contract. Source data and product data remain the property of the United States Government.

The Contractor shall also ensure that GIS data is submitted in a file geodatabase that meets the current AF adaptation of Spatial Data Standards for Facilities, Infrastructure, and Environment (SDSFIE) within the AF GeoBase program. The Contractor shall consult with each Installation POC and/or Installation GIO office to ensure CADD and GIS data is compatible with each Installation's requirements.

All products associated with this contract that provide a map representation of the location of Installation features (historical, existing, or planned), including Installation maps, site plans, area development plans, walls-out as-built depictions, or other related overhead (plan) views of an Installation (partial or entire) must adhere to the following requirements. (NOTE: This requirement does not currently involve walls-in facility floor plans or interior renderings.)

All maps and associated data must comply with the latest version of SDSFIE available from the SDSFIE Web site: <http://www.sdsfieonline.org/> or contact the AFCEC GIO at AFCEC.GIO.Workflow@us.af.mil or (210) 925-4620. These data will be organized using the current version of the standard approved by the Headquarters Air Force GeoBase Office as the functional lead for Installation mapping and visualization. The SDSFIE will determine file and feature class identification and definition, attribution, and valid domain values. When any geospatial information collected as a result of the contract includes information identified in the Common Installation Picture or recognized Mission Data Set (MDS), the Contractor will deliver data consistent with the established requirements for the data and will ensure functionality with the receiving system. Information must be collected at no less than 1:1200 scale. Spatial data will meet or exceed National Map Accuracy Standards at those scales. Metadata will be provided and will use Federal Geographic Data Committee (FGDC) Content Standards for Digital Geospatial Metadata (CSDGM) for organization.

As a requirement of this contract, the Contractor shall provide to the Government all shape files, file geodatabases, map exchange files (MXDs), and Geospatial data accumulated as a result of investigation recorded on compact discs (CDs) (FedEx for delivery on next business day) and also electronically. Geospatial data must be delivered in a geo-referenced GIS format (feature-based file structures with one-to-one cardinality between spatial records and attribute records) which would include Environmental Systems Research Institute's (ESRI) shapefile and

geodatabase formats. All attribute data as specifically outlined in the contract, must be included either in the GIS data file or as a separate table with an SDSFIE key variable that may be used to relationally join the separate table with the GIS data file. All geospatial data must be delivered in the North American Datum 1983 (NAD83) projection, State Plane Coordinate System, using feet or metric coordinate units. For all locations within the Restricted Area, Universal Transverse Mercator (UTM) coordinates must also be provided. Further guidance on mapping units, coordinate systems, and projections is available from the Installation GIO.

Mapping- or Survey-Grade Global Positioning Systems (GPS) or comparable traditional survey methods will be used to collect geospatial data. The use of mapping- or survey-grade GPS will depend on the precision requirements of the product data. These requirements will be specified later in this PWS for all contract activities where geospatial data are involved. In the case of contracts involving utility construction, location and attribute data will be obtained at the time of excavation. Further information about precision requirements should be obtained from the Installation Execution Support (GeoBase) Office.

Source data and product data remain the property of the United States Government. The Contractor shall be required to explain and demonstrate the company's process for protecting all geospatial data including, but not limited to, geometry, attributes, metadata, topologies, and relational database schemas and operations used in association with this PWS. The Contractor shall be required to sign a non-disclosure agreement attesting to the same before source data are released. Further information about security and non-disclosure requirements should be obtained from the Installation GIO. Some installation map data, sources and/or products may be considered by the government to be "sensitive, but unclassified". The intent of this clause is to prevent intentional or unintentional dissemination of "sensitive, but unclassified" information, to include unauthorized access to the source and product data by any entity wishing to do harm to the Air Force or United States Government while the data resides on the Contractor's computer network. The Contractor is not authorized to release this information to any third party without the explicit consent of the AFCEC GIO (AFCEC/CPAB) or its involved Installation. All source information must be returned to the Government POC or destroyed upon completion of this project. Documentation of information destruction shall be provided to the Installation POC(s). Special requirements for handling classified map data, if applicable, will be addressed elsewhere in this PWS.

The Contractor is required to follow Department of Homeland Security, Management Directive (MD) 11042.1 regarding Safeguarding Sensitive but Unclassified (For Official Use Only) information dated 5 January 2005.

4.8 Information Security

4.8.1 Computer and Network Access Requirements

Contractor personnel working on this contract must complete the required security investigation to obtain the required security clearance. This must be accomplished before operating government furnished computer workstations or systems that have access to Air Force e-mail systems or computer systems that access classified information. The contractor shall comply

with the DoDM 5200.02, Procedures for the DoD Personnel Security Program and AFMAN 33-152, User Responsibilities and Guidance for Information Systems, requirements.

4.8.2 Cybersecurity Reporting

All information created, stored, or transmitted under this contract is the property of the Government. The Contractor will remove all government information from the Contractor's computers in accordance with Air Force and DoD policy and provide certification of removal to the CO.

Contractor agrees to require, in writing to the CO, that all subcontracting work performed will ensure the subcontractor is equally bound to adhere to all cybersecurity requirements listed below.

Contractor agrees to require, in writing, that all subcontractors provide the subcontract compliance metrics/evidence of compliance for all subcontract work awarded. Contractor agrees to consolidate all subcontract metrics and contract compliance evidence as part of their overall metrics and contract compliance reporting to the government COR.

Contractor agrees to ensure all products/services provided: Are designed, implemented, and maintained in accordance with the statutes, guidance, and regulatory compliance requirements listed below. Contractor agrees to thoroughly review each of the requirements listed below for targeted applicability to the product/service provided to the government. Contractor agrees to provide, in writing to the CO, a catalog showing each applicable section of the regulations listed below; what design/implementation criteria will be used to meet each individual requirement, along with implementation checklists and maintenance tasks that will be used to ensure compliance is met and retained for all of the following:

- Department of Defense Federal Acquisition Regulation (DFAR) 252.204-7012
- Unified Facilities Criteria (UFC) 4-101-06
- Department of Defense Directive (DoDD) 8140.01 Cyberspace Workforce Management
- Department of Defense Directive (DoDD) 3020.40 Mission Assurance (MA)
- Department of Defense Regulation (DoD) 5200.08-R Physical Security Program
- National Institute of Standards and Technology (NIST) Special Publication 800-53 (latest version), Security and Privacy Controls for Information Systems and Organizations
- National Institute of Standards and Technology (NIST) Special Publication 800-82 (latest version), Guide to Industrial Control Systems Security
- AF Systems Security Instruction (AFSSI) 7700 Emission Security
- Defense Information Systems Agency (DISA) Security Technical Implementation Guides (STIGs)
- Defense Information Systems Agency (DISA) Security Requirements Guides (SRGs)

Contractor agrees to provide, in writing to the CO, an explanation for each section of regulatory guidance listed above where a targeted section could apply under a certain set of circumstances but does not apply under the targeted product/service being delivered. The intent of this contractual obligation is to minimize the chances of a situation where the government awards a contract based on contractor acceptance of responsibility where the contractor incorrectly feels certain aspects of regulatory compliance did not apply to their product/service – thus ultimately providing a service/product that does not meet the original intent of the government.

4.9 Notification Requirements

The Contractor shall notify the COR, with courtesy copies to AFCEC and Installation POC(s), of critical issues that may affect the contract performance and/or human health, safety, and the environment. Verbal notification shall be made immediately, followed by written notification to the CO with courtesy copies to AFCEC and Installation POC(s) within five (5) working days.

The types of issues that require notification include, but are not limited to, health risks, spills, Notices of Violation (NOVs) (received or anticipated), changes in critical personnel, and finding unanticipated UXO, DMMs, MCs present in high enough concentrations to pose an explosive hazard, or CWM. Contractor shall follow the 3Rs principle of Recognize, Retreat, and Report if Munitions and Explosives of Concern (MEC) are encountered or suspected to have been encountered.

If unanticipated UXO is discovered during field activities, the Contractor shall immediately stop work, contact base security, report the discovery to the COR, AFCEC, and Installation POC(s), and implement the appropriate safety precautions. If an item is suspected to be a chemical munition (liquid filled) the contractor shall call base security who will contact Base EOD to assess the item. Field activities shall not continue until clearance is received from the CO.

If the Contractor anticipates working beyond the PP to achieve a final milestone due to unanticipated UXO, the Contractor shall submit a PP extension request to the CO at least 60 calendar days prior to the expiration date of the Sub-CLIN.

4.10 Permits

The Contractor shall develop, coordinate, apply, comply with, and/or modify all federal, state, local, and other applicable environmental permits, access agreements, easements, licenses, and certificates required to achieve the POs of this contract as detailed in Sections 4.10.1 and 4.10.2. The AF has signature authority of all easement agreements, modifications and/or renewals of new or existing permits, licenses, and certificates required under this contract. The Contractor shall maintain a library of these documents at the Contractor's site office as well as the corporate facility handling this contract. The Contractor shall comply with all applicable permit conditions.

4.10.1 Environmental Permits

Pursuant to CERCLA (42 U.S.C. 9621(e)), no federal, state, or local permits shall be required for onsite removal or remedial actions. The Contractor must consult with the AF prior to obtaining environmental permits for all on-site and off-site CERCLA activities. For non-CERCLA

restoration sites, the Contractor shall assist the AF to comply with all applicable permit conditions including permit modification requirements and payment of permit fees. If the Contractor has any questions whether a particular permit may or may not be required, the Contractor shall consult with the AF prior to obtaining the permit. The Contractor shall be responsible for reviewing and responding to site-specific underground utility locating systems request tickets, or other dig permit requests, requiring the identification of subsurface appurtenances and utilities associated with the remediation systems included in this contract. If the Contractor obtains environmental permits, it is responsible for implementing and paying for them. Utility location ticket requests will be sent to the Contractor, and the Contractor will be required to review, respond, and address all location requirements in accordance with state law and regulations. The Contractor shall maintain all records pertaining to location requests.

4.10.2 Rights of Access to Non-AF Real Property

The Contractor shall prepare documents using AF-provided templates for the AF to maintain or modify existing rights of access, or to acquire new rights of access, to non-AF land which the Contractor needs to satisfy the POs of this contract. On the AF's behalf, the designated Installation official will negotiate and sign the documents to obtain or modify the necessary rights of access with technical assistance from the Contractor. Based on the stated right of access needs of the Contractor, the AF will decide which type of right of access (e.g., access agreement, right of entry, license, easement, lease, or fee acquisition) will be obtained. Technical assistance expected or that may be requested by the AF from the Contractor for rights of access include description of the amount of real property on which access is being sought, provision of property surveys, title searches, and title insurance (necessary only for easements, leases for greater than 30 years, or fee acquisitions), environmental site due diligence, appraisals of fair market value, amount of expected intrusion on the property or property disturbance, cost estimates of restoring property to its original condition after access is no longer needed, and potential technical witness testimony in the event the AF must pursue involuntary condemnation through the U.S. Department of Justice in state or federal court. Payment of associated expenses includes costs associated with providing the aforementioned technical assistance, fees for recordation of real property documents associated with acquiring the right(s) of access, costs for payment of or restoring property damage resulting from Contractor's activities on the property on which the right(s) of access were acquired, costs for obtaining "dig safe" or "utility clearance" approvals from appropriate utility and governmental entities, and costs for notifying or communicating with affected property owners regarding rights of access.

4.11 Photo Documentation

The Contractor shall prepare digital photographic documentation, as required, to achieve the POs of this contract. The Contractor shall limit photographic documentation of site(s) to building(s) under investigation, field activities, and sample locations. Photographs containing AF personnel, mission-critical assets, or that could reveal troop movements are not permitted. Photography of any kind shall be coordinated through the COR and Installation POC.

4.12 Remote and/or Austere Sites

NOT APPLICABLE

4.13 Site Access

The Contractor shall obtain and monitor assigned security badges, Defense Biometric Identification System (DBIDS), and passes used by all applicable personnel for the duration of this contract. All security badges, DBIDS, and passes shall be returned to the COR upon expiration of the badge/DBIDS/pass, upon completion of the project, or when possession of the badge/DBIDS/pass is no longer necessary (e.g., upon removal of Contractor personnel from specific projects).

Additional access or security requirements/limitations that may impact scheduling are provided below. Advance coordination for site access is required as follows:

- There is a “Historical district” on the flight-line areas, but notification is not required for access.
- Special flight-line access will be needed for WP003 and FT004. This will require a Restricted Area Badge (preferred for all contractors as it allows for gate access, and they can serve as escorts to other sub-contractors) or entry with the AF RPM. An Entry Authorization Letter can be obtained through the 92nd OSS and requires one-month advance notice. Authorization is valid for one year.
- Hanger 1001 (TU500) requires an appointment set through phone.
- An escort is required for access to sites within the airfield or the airfield’s “red line” and requires one week’s advance notice (contractor personnel with a Restricted Area Badge would eliminate this issue).
- WP036 requires a scheduled appointment, typically weeks in advance, and an escort at all times.
- LF002 requires a one-time key.

4.14 Worksite Activities and Coordination

4.14.1 Coordination of Activities

The Contractor shall coordinate worksite activities with all applicable personnel to ensure the protection of human health and the environment; the prevention of damage to property, utilities, materials, supplies, and equipment; and the avoidance of work interruptions. The Contractor shall perform emergency response to situations arising from project activities. The Contractor shall perform emergency repairs to facilities, systems, improvements, or utilities damaged in the course of executing the contract requirements. The Contractor shall comply with all local, state, federal, and military laws and guidance covering security activities. The Contractor shall comply with Occupational Safety and Health Administration (OSHA) safety and health regulations and local safety office requirements. The Contractor is required to provide the CO copies of any OSHA report(s) submitted during the duration of the contract.

4.14.2 Radiological Waste, Hazardous Material, and Hazardous Waste Permitting and Reporting

The Contractor shall handle all radiological waste, hazardous materials, and hazardous waste in accordance with applicable federal, state, local, and installation requirements. The Contractor shall provide all radiological waste, hazardous materials use, and hazardous waste disposal documentation to AFCEC, COR, and Installation POC(s), and shall register with the Hazardous Materials Pharmacy program (if available) at the installation to ensure appropriate and efficient tracking of the Contractor's hazardous material purchases, inventories, use, and releases such as required by the Emergency Planning and Community Right-to-Know Act (EPCRA), EOs, or any Installation reporting requirements.

The Contractor shall also comply with federal, state, local, and installation requirements for any task involving the transportation of radiological waste, hazardous wastes, and contaminated materials to off-site treatment, storage, and/or disposal facilities. This includes 40 Code of Federal Regulations (CFR) Parts 260 and 263, 49 CFR Parts 172, 173, 174, 178, and 179, and all other applicable federal, state, and local transportation regulations. The Contractor is responsible for all disposal costs of hazardous wastes.

The Contractor shall perform all work in a manner that minimizes the pollution of air, water, or land and develop contingency measures for cleanup of any spills that may occur during the performance of this Contract. The Contractor is responsible for performing IDW characterization, management, and disposal in support of the environmental restoration project in this contract. Waste management activities including identification, hazardous waste determination, characterization, segregation and storage, labeling and marking, preparation of transportation documents, and record keeping shall be in accordance with EPA and Department of Transportation (DOT) regulations, state hazardous waste regulations, if applicable, and the installation RCRA permit, if applicable. All IDW generated by the DERP is subject to the Off-Site Rule (40 CFR 300.440). Wastes may be placed in facilities compliant with RCRA or other applicable federal or state requirements. The Contractor is responsible for disposal costs of all IDW.

All waste media from areas with identified PFAS contamination shall be segregated, stored, and disposed of in accordance with the guidance provided in Section 1.3.

The Contractor shall write and implement waste management plans for government review and approval before initiating on-site restoration work. The plans shall document the process for making a hazardous waste determination for IDW in accordance with 40 CFR 262.11 and procedures for managing the waste and documenting disposal. For work involving generation and disposal of hazardous waste, the Contractor shall coordinate activities with the installation hazardous waste manager and perform waste management that complies with all generator requirements in 40 CFR Part 262. These requirements include, but are not limited to, making hazardous waste determinations, determining generator category, obtaining USEPA ID numbers, notification of hazardous waste activity, use of the manifest system, complying with pre-transportation requirements, and maintaining records in accordance with 40 CFR 262.40 and 40 CFR 262.44. For installations with existing hazardous waste identification numbers, coordinate

waste with installation environmental staff. Note that the installation is the waste generator and oversees and approves waste management activities. The installation has signature authority as the generator on hazardous waste manifests prepared by the Contractor; however, Contractors may be required to sign waste characterization profiles, bills of lading for non-hazardous waste, and other DOT shipping papers.

The Contractor is required to receive a Certificate of Disposal/Destruction/or Placement for all hazardous wastes, CERCLA remediation wastes, asbestos, polychlorinated biphenyls (PCB), etc. from the ultimate disposal facility. The certificate must correlate to each shipment of waste to the facility. The Contractor shall submit the certificates to the CO for placement in the project/site file.

After IDW disposal is complete at the site, an IDW report addendum shall be prepared to describe the IDW activities at each site and be included as an addendum to one of the final reports.

4.14.2.1 Regulatory Requirements

All activities and IDW documents required by this scope of work shall comply with and reflect the following regulations and appropriate guidance publications, at a minimum:

- DOT, Hazardous Material Regulations, 49 CFR Subtitle B, Chapter I, Subchapters A, B, and C.
- USEPA, Hazardous Waste Regulations, 40 CFR Chapter I, Subchapter I.
- USEPA Regulations, 40 CFR Chapter I, Subchapter J – Superfund, Emergency Planning, and Community Right-To-Know Programs.
- USEPA Regulations, 40 CFR Chapter I, Subchapter J, Part 300 – National Oil and Hazardous Substances Pollution Contingency Plan (NCP).
- CERCLA, 42 USC 9601-9675.
- RCRA 42 USC 6901 et seq.
- Other applicable federal, state, and local solid waste requirements.

5.0 CHEMISTRY REQUIREMENTS

The Contractor shall be responsible for the quality of all required chemistry services performed. The Contractor shall ensure that all chemistry-related tasks are conducted in accordance with the project-specific Work Plan (WP). The Contractor shall identify a Program Chemist as key personnel in the project WP. The Program Chemist will act as a POC on all chemistry-related issues and shall be responsible for ensuring that all Data Quality Objectives (DQOs) are met.

5.1 Quality Assurance

The Contractor shall develop project-specific DQOs to ensure data of adequate quality are collected to support project decisions. DQOs shall be developed in consensus with the restoration project team and in accordance with the Uniform Federal Policy for Quality

Assurance Project Plans (UFP-QAPP) and USEPA QA/G4, “Guidance on Systematic Planning Using the Data Quality Objective Process” (most recent version) and documented in the project WP. The Contractor shall ensure that all requirements specified in the project WP are met. If not met, the Contractor may be required to re-accomplish sampling at the Contractor’s expense.

All laboratory services shall be conducted in accordance with the approved project WP. Samples shall not be submitted for analysis until the WP is approved.

The Contractor shall administer an AFCEC-approved performance evaluation sample program, verify and validate data, and perform corrective actions in accordance with the project WP. See attached AFCEC guidance document, Ensuring Chemistry Data Quality – AFCEC Performance Evaluation Program. Data validation shall be conducted on requirements presented in the WP, and performed by an independent, qualified, and experienced data validator in accordance with DoD General Data Validation Guidelines and any applicable Modules. One hundred percent of the data shall be validated. The level of data validation shall be project specific, a minimum of Stage 2B, documented in the project-specific WP, and approved by the COR. The data validation standard operating procedure shall be included in the WP. Significant deviations from project requirements discovered during data validation shall be communicated with the project chemist and COR as part of the data validation process.

A data validation report shall be prepared and shall sufficiently document the data validation procedure and provide a clear understanding of the representativeness of the data. The results of the data validation shall be summarized in the associated technical report with supporting data validation reports included in an appendix. A data usability assessment of the validated data shall be performed. The results of the data usability assessment shall be included in the technical report, and shall identify the limitations of the data, and the effect qualified results have on the decisions being made for the project.

5.2 Laboratory Selection

The Contractor shall select a laboratory with analytical capabilities sufficient for the methods specified in the WP and adequate throughput capacity to handle the project’s analytical workload during all field activities. During analysis and reporting, the Contractor shall ensure that the selected laboratory is accredited under the DoD Environmental Laboratory Accreditation Program (ELAP) and meets all state and federal requirements, including state certification where appropriate.

The Contractor may establish an on-site laboratory at the project site if determined necessary by the Contractor. However, on-site test laboratories shall also be accredited under the DoD ELAP and meet all state and federal requirements, including state certification where appropriate.

5.3 Analytical Data Management

The Contractor shall ensure that all hard copy and electronic data deliverables supplied by the laboratory are complete and adequate to support the quality and usability of the data. Raw data packages shall be submitted to AFCEC upon request. Data packages shall meet federal and state standards and include all information required to re-create the analysis, including correspondence

with the laboratory regarding Quality Assurance and Quality Control (QA/QC) exceedances and documentation of corrective actions.

5.4 Record Keeping

The Contractor shall create and maintain in one location written (in bound, numbered logbook) and electronic records sufficient to recreate each sampling, analytical, testing, and monitoring event, and shall make these records available to the Government upon request. The Contractor shall maintain records of, and derived from, all activities outlined in the appropriate portion of the Quality Program Plan (QPP) supporting the generation of these sampling and analysis records. The Contractor shall also retain written calculations using information obtained from sampling, analysis monitoring, and testing activities, to include all raw data. All information shall be provided to the Government upon request.

All field documentation shall be recorded in bound, numbered logbooks. Field logbooks shall have numbered pages and shall include a complete record of all field activities. If multiple field logbooks are required, each shall be numbered and specifically identified to indicate dates and sites where used. Field documentation shall be recorded at the time of fieldwork, i.e., details may not be added after the fact. All information required to fully recreate sampling, investigation, and remediation events shall be documented in the field logbook. Use of field forms may augment but not replace the detail required in the field logbook. The field logbooks are a critical part of the official project record; the Contractor shall include procedures for maintenance, review, tracking, etc., of the field logbook in the programmatic UFP-QAPP.

5.5 PFAS Sampling and Analysis

If PFAS sampling is required, samples shall be analyzed in accordance with DoD and AF policy. In addition, the Contractor shall follow any applicable current State or Federal guidance for PFAS sampling.

6.0 PLANS AND REPORTS

6.1 Quality Program Plans

The QPP shall include the WP, the Health and Safety Plan (HSP) (as required by 29 CFR 1910.120), and the Construction Quality Plan (CQP) if required.

6.1.1 Work Plans

Prepare WPs to comply with DoD, AF, USEPA (epa.gov/quality), state, and local regulations and guidance. Basewide and site-specific WPs that require sampling and analysis shall be prepared in accordance with the UFP-QAPP, using the optimized UFP-QAPP worksheets. The optimized UFP-QAPP worksheets shall constitute the entire WP when sampling and analysis is required. WPs shall be specified as separate payment milestones under the site-specific Sub-CLIN(s) as appropriate.

6.1.2 Health and Safety Plan

The Contractor shall prepare an HSP to comply with AF, OSHA, USEPA, federal/state/local health and safety regulations and guidance, including EM 385-1-1. In accordance with EM 385-

1-1, the HSP will consist of a Site Safety and Health Plan (SSHP) and Accident Prevention Plan (APP). Utilize to the fullest extent possible any existing related HSP, tailored specifically to the current effort. The Contractor shall maintain written certification that the approved HSP has been reviewed with all personnel that work at the project site prior to their mobilization. The Contractor and all subcontractors are required to comply with the approved HSP (including SSHP and APP). The Government can shut down operations due to non-compliance without cost to the Government until safety issues are resolved.

6.1.3 Construction Quality Plan

The Contractor shall provide a CQP to comply with AF, OSHA, USEPA, federal, state, and local quality regulations, if needed.

6.2 Technical Plans and Reports

The Contractor shall provide reports and various other deliverables in accordance with the most appropriate industry standard, or where applicable, any federal or state guidelines.

Technical plans and reports are required to demonstrate that POs and milestones are being met and that payment is appropriate.

Most documents must be submitted for initial AF review followed by submittal to one or more regulatory agencies. The Contractor shall ascertain the number of copies required for delivery to all relevant parties. Regulatory Agency review times will be based on the agency reviewing the document, complexity of the deliverable, and workload of the technical review team, including regulatory partners. The AF is unable to commit to review times for another agency. The Contractor shall be responsible for coordination of document review schedule with all stakeholders. However, historical regulatory review times have averaged 45 to 60 calendar days for the WDOE and 30 to 60 calendar days for the EPA. Please be advised that workload for those averages may not mirror workload under an ORC accelerated environment. Therefore, Contractors should review available information and form their own independent conclusions as to the time necessary, as well as risks and appropriate mitigation and contingency measures, to achieve the PO and PP with their approach. Legally binding documents such as reports, correspondence, No Further Action (NFA) documents, regulatory closure documents, RODs, or other decision documents shall be signed by the AF and not the Contractor.

The Contractor shall submit all plans, reports, and other documents in Internal Draft, Draft, Draft Final, and Final versions, as appropriate for that specific document. Not all documents will require submittal of all versions. The Contractor shall provide multiple versions of the following documents:

- Installation RPM: 3 hard copies and 1 CD/DVD of all draft documents; 3 hard copies and 1 CD/DVD of all Draft Final and Final documents. Six hard copies of Final LUC reports.
- AFCEC Program Manager: 1 CD/DVD of all documents and native files at the end of the contract.
- COR: 1 CD/DVD of all documents and native files at the end of the contract.

- State Regulator: 1 hard copy of documents for VCP sites.
- EPA: 1 hard copy and 1CD/DVD of all Draft Final and Final documents.

The following are the estimated review times. Complex documents, Permit mods, and Decision Documents may require additional time.

Reviewer	Document Review (for each version)	Response To Comments Review
AF Review	30 calendar days	21 calendar days
AF and Legal* Review	60 calendar days	
Coordination/Signature – Installation	120 calendar days	
Coordination/Signature – CZ	90 calendar days	
* Legal review required per AFI 32-7020 for: PA/SIs that result in Site Closeout, Engineering Evaluations/Cost Analysis (EE/CA), Removal Action Memoranda, FS, PP, ROD and ROD modifications, Five-Year Reviews, Remedial Action Completion Reports (RACRs), Site Closeout Reports, NPL deletion requests. See AFI 32-7020 for additional information.		

The Contractor shall upload all documents to Contractor's ORC document repository. The documents required for this contract shall be proposed by the Contractor and will be included in the Contractor's IMS.

7.0 SITE WORK

The Contractor shall perform site preparation, site characterization and field investigation, conservation, demolition, and site restoration as required to achieve the POs of this contract.

7.1 Conservation

Activities shall be planned and implemented in a manner that protects existing site utilities, structures, surface features, service operations, monitoring and other types of wells, and the general site environment. This includes the protection of prehistoric and/or historic sites identified in the Installation Integrated Cultural Resources Management Plan (ICRMP); endangered/threatened wildlife species and their potential habitats; exemplary natural areas as defined in the base Integrated Natural Resources Management Plan (INRMP); and trees, shrubs, and other vegetation not in the affected zone from dust damage, soil compaction, and physical contact with machines and equipment. Work activities shall be coordinated with AFCEC, COR, and Installation POC(s) (Cultural Resources manager, Natural Resources manager, and Installation Operating Support POCs) to ensure compliance with these requirements. If appropriate, the Contractor shall conserve uncontaminated topsoil by removal, storage, or redistribution. All reasonable measures shall be taken to minimize and suppress fugitive emissions of dust, vapors, and other site materials during site work. All fill materials shall be non-contaminated with the proper documentation to demonstrate as such. The Contractor shall conduct all operations and activities with the intent of reducing the amount of pollution generated. Specific areas to be focused on are generation of solid waste, use of hazardous materials, use of ozone depleting chemicals, generation of hazardous waste, and use of energy

and water. During site work the Contractor shall plan, construct, operate, maintain, optimize, and decommission systems necessary to control storm water run-on and run-off, and transport surface water drainage to a treatment plant, discharge location, or any other appropriate destination.

Maps of the proposed area are required for all dig permits.

7.2 Site Characterization and Field Investigation

The Contractor shall perform field investigation and sampling/analysis that characterizes environmental conditions, in accordance with approved DQOs, as required to achieve the POs of the site. The Contractor shall identify specific site characterization activities proposed to achieve the POs.

7.3 Site Preparation

The Contractor shall perform site work as necessary to prepare sites for field activities. Security and access controls shall be implemented to prevent unauthorized entry to sites and to protect wildlife from site exposure. The Contractor shall survey existing utilities to determine adequacy and need for modifications to support site activities. The Contractor shall obtain appropriate approvals and shall construct connections or new systems for electrical power, water, sewer, gas distribution, telephone, and other utilities, as required, to achieve the POs of this contract. Additionally, the provision and cost of utility metering devices associated with implementation of existing and proposed remedies, including installation of individual meters for necessary utilities, is the responsibility of the Contractor. The Contractor shall meter all utilities consumption on a monthly basis. The Contractor shall be responsible for the associated cost of internet at site LF002.

7.4 Demolition

Any demolition activities shall be ancillary to other requirements. The Contractor shall demolish facilities, systems, and other improvements as required in this contract in accordance with applicable federal, state, and local laws and regulations. The Contractor shall conduct demolition efforts in conjunction with such activities as new environmental remedial system construction and site clearing if required to achieve the POs of this contract. The Contractor shall perform surveys as part of demolition efforts and is responsible for providing GIS information to Installation Civil Engineering.

- Removal of unused treatment systems at sites FT004, ST006, and WP003.

7.5 Site Restoration

The Contractor shall decontaminate equipment and facilities, decommission facilities as necessary, and fully restore the site(s) as close as possible to pre-construction conditions prior to demobilizing from the site(s). The Contractor shall remove any temporary facilities and implement erosion control measures such as seeding, mulch, sodding, and erosion control fabrics; restore roads, structures, and utilities; and plant trees, shrubbery, grasses, and other

vegetation. The Contractor shall document and report on activities and train Government personnel to perform required maintenance, as requested.

8.0 ENVIRONMENTAL REQUIREMENTS

The Contractor shall perform a full range of activities to achieve the POs of this contract. Requirements may include, but are not limited to, completion of conceptual design(s), construction, implementation, demolition, and emergency response as related to environmental engineering and construction tasks.

The Contractor shall execute environmental restoration projects in accordance with approved DQOs and applicable federal, state, and local laws and regulations. The Contractor shall evaluate, complete, and modify designs as necessary, and plan, optimize, install, construct, test, and decommission any site as required to achieve the POs of this contract. The Contractor shall document all activities as stated herein.

The Contractor may change the site-specific approach for attaining POs, as needed based on approval of the PM/COR, due to site conditions, regulatory changes, etc. All changes to the site-specific PO attainment approach shall be maintained current in the PMP, IMS, and MPS.

The Contractor shall perform support such as designing, planning, programming, scoping, studying, investigating, evaluating, optimizing, and consulting on environmental engineering and construction efforts. The Contractor shall also provide training to Government and other Contractor personnel regarding the O&M of equipment, systems, and facilities during equipment shakedown periods. The Contractor shall perform O&M of equipment, systems, and facilities prior to approval by the Government.

The Contractor shall implement Environmental Management System (EMS) principles in accordance with Contractor requirements of AFI 32-7001 (*Environmental Management*), to include Green and Sustainable Remediation (GSR) techniques, to the extent practicable while ensuring protection of human health and the environment. EMS and GSR are defined in Enclosure 1, Acronyms and Definitions. An EMS follows the “Plan-Do-Check-Act” cycle and considers the environmental impact of investigative and remedial activities during the remedy selection process as well as operation and maintenance of the remediation activity. The Contractor shall incorporate an EMS approach into all environmental restoration projects, evaluating activities and selecting a remedy, product, and/or service that minimizes the environmental impact from the remedy, yet provides the maximum environmental benefit to the cleanup over the entire life of the remedial project. The Contractor shall mitigate, minimize, or otherwise manage the potential environmental impacts from all remediation activities. Contractors working on AF Installations must complete an initial EMS awareness-level training and integrate EMS training with other required Contractor orientation and training.

8.1 Environmental Restoration Process Application

The Contractor shall perform all activities necessary to meet all ORC requirements. Environmental Restoration requirements include the full range of investigation, cleanup, optimization, and LTM activities. The Contractor shall develop and update a CSM and an exit

strategy (as described in Sections 8.1.1 and 8.1.2). The Contractor shall also provide logical approaches to improve remedy protectiveness, effectiveness, and cost efficiency and to facilitate progress towards completion of the POs. The goals are to assess and optimize remedy performance and monitoring, to demonstrate remedy progress in accordance with approved performance models, and to take the site to its best long-term use or to closure.

This contract involves a performance-based approach, where the contracted work is performed with a focus on results. Results are achieved by 1) The achievement of the PO in the PP in accordance with the Performance standard per Table 1, or 2) The achievement of interim milestones that demonstrate value-added progress towards the achievement of the PO. This ORC enables the Contractor to select actions best suited to the site requirements, ensures that best management practices and best available technologies are employed, and focuses on continual improvement by applying an EMS approach. The Contractor's proposed approach shall be commensurate with site conditions, site status, and requirements to achieve the PO within the PP.

8.1.1 Conceptual Site Model Guidance

For all sites, the Contractor shall prepare or update site CSMs following DQOs. The CSM is a comprehensive written and graphical description of all available information about site conditions that could influence remedy design, selection, or performance. Thus, the CSM forms the basis for defining Remedial Action Objectives (RAOs) and for developing and implementing an exit strategy. A CSM incorporates several elements, including the following:

- Three-dimensional representation of:
 - Nature and extent of contaminant (including source types and affected media)
 - Site geology
 - Site hydrogeology
 - Biological and geochemical conditions
 - Monitoring points
- Contaminant fate and transport in the environment;
- Risks, receptors, and potential receptors (under current and reasonably expected future exposure scenarios);
- Past remedial actions and locations of remedial components and monitoring points
- Historical, current, and expected future land uses; and
- Other factors relevant to the understanding of contamination at the site.⁹

⁹ ITRC. (2004). *Remediation Process Optimization: Identifying Opportunities for Enhanced and More Efficient Site Remediation*.

The Contractor shall develop initial or updated CSMs for all sites listed in Table 1 of this PWS and work described in Section 1.3.2. An appropriately detailed CSM is required beginning with the remedial investigation phase for all restoration program sites and must be maintained until the end of the project life.

The Contractor shall update the CSM as new data and site knowledge are acquired. This is crucial for assessing and optimizing remedy performance and performance monitoring programs.¹⁰ New data may be obtained upon completion of remedial investigation, supplemental investigation, pilot studies, bioremediation investigations, and routine monitoring of remedy performance. Revisions to the CSM will be included in investigation and monitoring reports, as necessary. For more information, see USEPA Groundwater Road Map (OSWER Directive No. 9283.1-34, 2011) and Environmental Cleanup Best Management Practices: Effective Use of the Project Life Cycle Conceptual Site Model (EPA 542-F-11-011, 2011), ITRC guidance (ITRC, 2004 and 2006), and ASTM International (formerly known as American Society for Testing and Materials) standard designations E1689 (2014) and D5979 (2014).

8.1.2 Exit Strategy

The Contractor shall develop a stand-alone exit strategy for all Table 1 sites and work described in Section 1.3.2 where a remedy is planned or in place. Initial exit strategy development is required at the point of remedy selection for all Table 1 sites and work described in Section 1.3.2 and must be maintained until the end of the project life. For sites where a remedy is already in place, include a new or updated exit strategy along with work planning documents. If the exit strategy changes, the revised document must be resubmitted. An exit strategy for a site is the detailed plan for achieving the RAOs that have been selected as the end points. Stated another way, the RAOs are the overall goals that must be met for the site to either achieve RC or be approved for SC or planned land use. An exit strategy represents a formalized process for taking the site from its current state to its best long-term use or to closure (independent of duration). The strategy represents a plan to actively manage the site and make decisions at various points that will best tailor remedial and monitoring efforts to achieve the RAOs in the most efficient and effective manner. The strategy is best developed with consideration of stakeholder and regulatory agency concerns, resource constraints, and technical realities; it also includes well-defined means to measure and track progress. An exit strategy is dynamic and must be updated as new data and site knowledge are acquired. The exit strategy would need to be modified or revised if the plan for achieving the RAOs is failing. Such failure may be identified when interim milestones are not achieved, even after corrective action. Contingent actions identified in the exit strategy decision logic would then be implemented.

A well-developed exit strategy contains six elements:

- Decision document for the RA goals
- Summary of the CSM, including a description of the future site land use

¹⁰ ITRC. (2006). *Exit Strategy—Seeing the Forest Beyond the Trees*.

- Decision logic, flow chart, or defined sequence of remedial activities and contingency triggers
- Clearly established process to evaluate performance relative to decision parameter
- Provisions for periodic reevaluation of the project goals and RA decisions (e.g., contingency planning), and
- Means to verify cleanup following cessation of active remediation.

Because it is difficult to optimize any element of a remedial decision if the overall objectives (remediation end points) and site-specific technical constraints are not well understood, any optimization effort should begin with an evaluation of the exit strategy, which incorporates the previously listed six elements.¹¹ For more information, see ITRC guidance (ITRC, 2004 and 2006).

8.1.3 Performance and Optimization

8.1.3.1 Performance Models

The Contractor shall develop performance models for all sites listed in Table 1 of this PWS and work described in Section 1.3.2 that are not currently in LTM status. Work planning documents shall contain the performance model. Final performance models shall be submitted as part of the Work Plan required under PWS Section 6.1.1. Performance models shall describe how site conditions are expected to change over time, using appropriate performance indicators, from current state through PO achievement. The Contractor shall add all new data to the performance model and provide Performance Model Evaluation Reports, which demonstrate whether the remedial response is progressing and performing consistently with the performance model.

Performance model and site management approach shall incorporate the following:

- Develop and document the approach to determine remedial progress relative to the defined performance indicators, associated decision criteria, and objectives consistent with the performance model. The documented approach is expected to facilitate decisions about optimization as well as provide a quantifiable understanding of how the response is progressing, list contingency options, and demonstrate when the objective has been reached. An individual site may have more than one performance model (e.g., different parts of the site that are addressed by separate remedies and represented by different sets of monitoring wells). Contingencies must be developed for performance that does not achieve interim milestones. These contingencies must be identified in the exit strategy. The Contractor must inform AF of any contingency being implemented and receive AF approval before implementation.
- Demonstrate an understanding of the site-specific CSM as it relates to the operation of existing systems, distribution of contaminants, and remedy effectiveness and degradation rates (see details on the definition of CSM in Section 8.1.1). Update the CSM using

¹¹ ITRC. (2004). *Remediation Process Optimization: Identifying Opportunities for Enhanced and More Efficient Site Remediation*.

DQOs as needed based on performance and monitoring data throughout the PP and implement remedy contingencies as warranted by the evolving CSM. Submit updated CSMs subsequent to receipt of new information.

- Develop an exit strategy that identifies and implements opportunities to improve remedy protectiveness, effectiveness, and cost efficiency, and to facilitate progress toward the end goal of the exit strategy, including innovative technologies. The goal is to accelerate contaminant reduction, thereby minimizing future AF liability and cost to the greatest degree feasible. Update the exit strategy as dictated by site progress throughout the PP. Submit updated remediation strategies subsequent to receipt of new information.
- Develop baselines and performance models for all contaminants, including degradation products (i.e., vinyl chloride), that are regulated, that describe the historic and expected course of the remedial progress (i.e., how conditions are expected to change over time as demonstrated by appropriate performance indicators) from the current baseline state through PO achievement.
- Define the baseline state for each COC. The baseline state is determined by using select monitoring wells that are representative of the site and with sufficient data to develop statistics-based historic concentration trends for site COCs. A scientific approach that uses a line of best-fit (e.g., first-order decay rate) is appropriate for estimating the baseline attenuation rate. The baseline attenuation rate, in turn, can be used to extrapolate a baseline concentration to the end of the PP. Supporting information for the baseline concentrations shall include the rationale for the well selection and the time period used to develop the trends, justification for the selected line of best-fit, actual values used to define the trend, and extension of the line of best-fit to predict values for future years independent of future remedy implementation plans. For additional detail on development of baselines, refer to the “Optimized Remediation Contract (ORC) Program Management Plan (PMP) Guidance,” Version 1, Section 2.
- Using the baseline as a starting point (above), develop a scientifically-based remedial performance model for each COC. The performance model shall be representative of the contaminant extent being addressed and include performance indicators, decision criteria, and annual and final goals achievable within the PP. The Air Force will carefully scrutinize selected performance indicators to ensure that they demonstrate achievement of response objectives and not merely progress. The Performance Model shall also be used to maintain or return performance of a remedy as described by the model. The Performance Model shall indicate performance milestones that will be used to determine if the remedy is achieving the projected change in performance indicator. Goals should be consistent with the performance model used to optimize remedial efficiency, quantify how the response is progressing, and demonstrate when the annual and final goals have been achieved. The performance model shall show projected changes to the site performance indicator(s) based on an assumed rate of change (e.g., an estimated biodegradation rate constant). Subsequent changes to the performance model will only be permitted at the discretion of the AF.

Performance Models will identify at least three ranges, subject to AF approval:

- Ideal-to-acceptable performance
- Process-improvement-and-corrective-action range requiring modifications to the remedy to return to acceptable performance, and
- Process-failure-and-contingency action range that requires implementation of an acceptable option to the current remedy.
- The Contractor shall specify the number of consecutive data points that would trigger corrective action.
- Refer to the latest ORC PMP Guidance for additional information on the creation and use of performance models.

8.1.3.2 Optimization Benefits Reporting

NOT APPLICABLE

8.1.3.3 Optimization Summary and Forecasting

NOT APPLICABLE

8.2 Transition of Work

Activities will transition to this contract upon completion of the current Contractor's field support and/or final deliverable on sites noted in the tables below. The Contractor shall ramp-up management of this contract to ensure seamless operations of existing systems and no lapses in service.

Table 2: Transition of Work Table

Contract Number	Agency / Contractor / POP End	Final Expected Endpoint
FA8903-24-C-0039	772 ESS/PKS / BAY WEST / September 26, 2026	LF002, SS009, TU500, TU506: RA-O TU502: Annual Monitoring DP064, OW058, SD037: Draft ROD SS039, WP003: IRA-O FT004, LF001, SS018, SR939, ST006: RC DP012: ESD and LTM SS009: RA-O

Contract Number	Agency / Contractor / POP End	Final Expected Endpoint
		DP013: OES and LTM

Table 3: Sampling Transition Table

Site ID	Contract (POP End)	Final RA-O/ LTM Event under Existing Contract	Expected Date of Last Sampling Event under Existing Contract	Existing Contract Final Reports/Outcome	Next Expected Sampling Event under ORC
DP012	9/26/2026	LTM (every five years), LUC inspection	No sampling	2025 LUC Inspection Report_Final	March 2028
DP013	9/26/2026	LTM (every five years), LUC inspection	No sampling	2025 LUC Inspection Report_Final	March 2028
LF001	9/26/2026	LTM (every five years), LUC inspection	No sampling	2025 LUC Inspection Report_Final	March 2028
LF002	9/26/2026	QTR Monitoring, Monthly O&M, Annual Air Sampling	August 2026	2026 QTR Report (Q3)_Draft	October 2026
OW058	9/26/2026	N/A	N/A	Proposed Plan_Final	September 2028
SS009	9/26/2026	LTM	April 2026	2026 Annual Monitoring Report_Final	April 2027
SS039	9/26/2026	Semi-annual GW Sampling	April 2026	2026 Semi-Annual Report_Draft	October/November 2026
TU500	9/26/2026	Semi-annual	April 2026	2026 Semi-Annual Report_Draft	October/November 2026
TU502	9/26/2026	LUC inspection, annual GW sampling	None	None	October 2027

Site ID	Contract (POP End)	Final RA-O/LTM Event under Existing Contract	Expected Date of Last Sampling Event under Existing Contract	Existing Contract Final Reports/Outcome	Next Expected Sampling Event under ORC
TU506	9/26/2026	Semi-annual	April 2026	2026 Semi-Annual Report_Draft	October/November 2026
WP003	9/26/2026	Semi-annual Monitoring	June 2026	2026 QTR Report (Q2) Draft	October/November 2026

8.3 Environmental Construction

The Contractor shall perform construction; restoration; and demolition of utilities, real property systems, and infrastructure in support of environmental restoration requirements as required to achieve the POs of this contract. Construction and demolition activities shall be in conformance with applicable AF and other federal, state, and local standards and regulations to include Installation-specific regulations. The Contractor shall erect or install support buildings, equipment enclosures, and storage facilities for construction materials and contaminated material awaiting disposal as permitted by the Installation.

8.3.1 Design

A conceptual design (typically 10–30% design) for environmental projects may be provided to the Contractor for completion of the design and then construction. This work may be provided in phases. The Contractor is accountable for all aspects of the final design under federal, state, and applicable local laws. All completed designs shall be signed and sealed in accordance with all applicable requirements. The Contractor shall complete project working drawings and the various plans and schedules, including a construction schedule, and obtain submittal approvals and permits. Working drawings and specifications shall comply with codes, laws, and the request for proposal requirements. The working drawings shall be submitted for AF review.

The Contractor shall assist with coordinating regulatory reviews and respond to regulatory comments, shall ensure technical adequacy of the final design, and shall provide quality control of all phases of the contract.

8.3.2 Inspection

Upon completion of the final construction, the Contractor shall conduct a pre-final walk-through inspection and publish the pre-final inspection findings in a pre-final inspection report.

The Contractor shall conduct a final inspection and publish the findings in a final inspection report. The inspection shall concentrate on the items identified at the pre-final inspection and recorded in the pre-final report. The final inspection report shall (1) certify that all items of the design have been implemented and that the construction is complete; (2) include a record of “signed and sealed” as-built drawings and specifications verifying that all development standards have been met. At the final inspection, the Contractor shall present a completed DD Form 1354,

Transfer and Acceptance of Real Property to the Base Civil Engineer (BCE) or other appropriate organization for signature and approval.

8.3.3 Delivery and Warranty

The Contractor shall complete all inspection and commissioning requirements prior to final inspection. The warranty shall be issued in accordance with FAR 52.246-21. Extended warranties offered by the Contractor and its subcontractors or suppliers may be accepted at the Government's discretion. The Contractor shall review installed equipment and prepare a repository of equipment/systems with information such as scheduled maintenance, compatibility with existing systems, vendor sources, and warranty expiration dates for all systems installed at sites that will not achieve site closure by the end of the POP. The Contractor shall also provide system O&M manuals and parts lists to the Government.

8.4 Environmental Resources Program Information Management System

The Contractor shall comply with the Environmental Resources Program Information Management System (ERPIMS) data requirements for all field-derived data/information supported by ERPIMS data structure including, but not limited to, sampling data, remediation system identification data, remediation technology performance data, relevant QA/QC data, lithology, groundwater, monitoring well location, well construction, well maintenance, and/or abandonment information. After receipt of the contract, the Contractor shall submit an ERPIMS Data Submission Schedule within 30 calendar days of award to establish the projected framework for ERPIMS data submissions. The Contractor shall record and enter field and laboratory data and submit this data as specified in the latest ERPIMS Data Loading Handbook (DLH) using the latest version of the ERPIMS software utility (ERPTools). ERPIMS data submissions are required within 90 calendar days of the conclusion of each sampling event unless a written waiver or extension is obtained from the CO in coordination with AFCEC Environmental Restoration Branch Chief. The AFCEC website (address provided under separate cover) offers the latest DLH, ERPTools client software, ERPIMS policy, ERPIMS Help Desk contact info, data submission requirements, ERPTools training schedules, and more. Data submissions shall be error-free, pass all validation checks, and fully comply with the ERPIMS DLH. The Contractor shall ensure that any required corrections are accomplished within both the contract POP and before funds expiration. The preferred procedure is for laboratories to use ERPTools to input/submit chemistry data for initial validation, import, and submission by the Prime Contractor. ERPTools training is available to prime and laboratory Contractors. All ORC milestones that include analytical sampling shall include successful ERPIMS loading of all relevant ERPIMS data elements into the production database as a minimum acceptance criterion.

8.5 Innovative and Proven Technologies

The Contractor shall, to the extent reasonably practical, plan, design, construct, operate, monitor, and decommission innovative environmental remediation, monitoring, and other technologies as required to achieve the POs of this contract. The AF seeks technologies and methodologies that are innovative, sustainable, cost-effective, and will lead to accelerated closure of environmental sites.

8.6 Operations and Maintenance

The Contractor shall perform RA-O/O&M requirements following DQOs in accordance with Section 5.1. The Contractor shall be responsible for the operation, maintenance, repair, replacement, installation of new wells, monitoring, optimization, and evaluation of in-place and proposed environmental systems and well network throughout their active life. This shall include all materials required to replace any exhaustible process materials required to operate and maintain the individual processes specified in the system O&M manuals and equipment manufacturer specifications. The Contractor shall provide system O&M manuals and parts list to the Government within 90 calendar days of system installation or modification. The Contractor shall provide an O&M manual within 180 calendar days for systems that do not have an O&M manual, or the existing manual is deficient. The Contractor shall be responsible for training maintenance personnel in system operations. The Contractor shall ensure that the operation of the environmental system is optimal and effective at achieving system goals.

The Contractor shall review installed equipment and prepare databases of equipment/systems with information such as scheduled maintenance, compatibility with existing systems, vendor sources, and warranty expiration dates for all systems installed at sites that will not achieve SC by the end of the POP.

The Contractor shall be responsible for the following associated with the Basewide groundwater monitoring program at Fairchild AFB:

- Complete a comprehensive monitoring well inventory, including resurveying horizontal and vertical location, and update monitoring well network; for wells selected to include in the network, re-develop monitoring wells that have not been in use for three years.
- Complete a comprehensive monitoring well condition assessment on an annual basis. Remedy any deficiencies (i.e., paint casings, reset bollards).
- Recommend network optimization. Sampling may be required prior to well decommissioning/abandonment.

8.7 Ordnance Removal and Support

Small Arms Ammunition Range Removal and Support

The Contractor may be required to remove, render inert, destroy, recycle, and dispose of small arms ammunition to achieve the POs of this contract. The Contractor shall perform associated investigative work if required to achieve the POs in this contract. Coordination with the Installation's EOD office may be required prior to any specific response to small arms ammunition. However, the Contractor shall be responsible for and perform investigations and plan response actions to remove, transport, and dispose of small arms ammunition.

8.8 Radiological and Hazardous Waste Removal and Support

The Contractor shall destroy, recycle, and dispose of hazardous and radiological wastes and materials and provide all hazardous materials use and hazardous and radiological waste disposal documentation to AFCEC, COR, and Installation POC(s) or designated alternate. An AF

representative will sign all hazardous and radiological material/waste manifests. The Contractor shall perform associated investigative work as required.

8.9 Study Effort Incidental to Remedy or Corrective Action

The Contractor may engage in supplemental study work in pursuit of a remedy or corrective action. This may include but is not limited to (1) performing bench-scale and pilot-scale studies of remediation technology, and (2) drafting new decision documents (e.g., ROD Amendment, ESD, RCRA Permit modification).

8.10 Five-Year Review Support

In accordance with AF policy, the Contractor shall support Five-Year Reviews (e.g., supplying documents to independent reviewers, attending site inspections, and participating in meetings/interviews) of all remedial actions, including non-CERCLA cleanup actions using the USEPA guidance document “Comprehensive Five-Year Review Guidance,” OSWER No 9355.7-03B-P, June 2001. The Contractor shall also be responsible for implementing findings, recommendations, and/or remedying deficiencies documented in a Five-Year Review which have been identified in the GFI, for any site identified in Table 1 and work described in Section 1.3.2.

9.0 PERFORMANCE STANDARDS AND SURVEILLANCE ACTIVITIES

The AF will utilize the Quality Assurance Activities to define the procedures and guidelines to evaluate the technical and quality performance of the Contractor in accordance with this PWS. The Quality Assurance Activities ensure that the work, to include that of subcontractors and suppliers, complies with the regulatory and contractual requirements, and documents that all the various activities required to achieve completion of CLINs/Sub-CLINs and that contract requirements not associated directly with a CLIN/Sub-CLIN are being accomplished, tracked, and surveilled.

The Contractor is fully responsible for executing the work under this contract and supervising/directing the work of subcontractors. Surveillance of Contractor performance and compliance shall be completed in accordance with the PWS. The Government’s contractual relationship and oversight responsibilities are only with the Contractor.

Figure 1. Performance Standards and Ratings Definitions

Performance Standard	Exceptional	Very Good	Satisfactory	Marginal	Unsatisfactory
Basic Definition	Contractor exceeds the performance requirements for the milestone, deliverable, or standard, with no substantive input from AFCEC.	Contractor exceeds the performance requirements for the milestone, deliverable, or standard, with minimal input from AFCEC.	Contractor meets the performance requirements for the milestone, deliverable, or standard, with moderate input from AFCEC.	Contractor meets the performance requirements for the milestone, deliverable, or standard, with significant input from AFCEC.	Contractor does not meet the performance requirements for the milestone, deliverable, or standard.
<i>Performance Category 1: Quality of Deliverable</i>					
Quality	Draft and Draft Final deliverables are of excellent quality, approved as submitted, or with no substantive comments limited to grammar, spelling, or terminology.	Draft deliverables are of high quality and comments are mostly minor. Final deliverables are approved after one round of AFCEC comments on the Draft Final through acceptance of response to comments table and back check of Final report against original comments. No further revisions are required.	Draft deliverables are of acceptable quality with only a few numbers of comments identifying major weaknesses. Final deliverables are approved after two rounds of AFCEC comments on Draft Final. No further revisions are required.	Draft deliverables are of poor quality with a significant number of comments identifying major weaknesses or deficiencies. Final deliverables require more than two rounds of AFCEC comments on Draft Final before being approved. (e.g., changes are required to the Final document due to inadequate incorporation of comments).	Draft deliverables are of very poor quality and are rejected for re-submittal without comment. Final deliverables did not comply with contract requirements, or one or more document versions required more than three rounds of AFCEC comments before being approved.
<i>Performance Category 2: Quality of Service</i>					
Quality	AFCEC review finds that	AFCEC review of	AFCEC review of work	AFCEC review of	AFCEC review of work

Performance Standard	Exceptional	Very Good	Satisfactory	Marginal	Unsatisfactory
	the data collected and/or the work performed exceeds the requirement of the PWS. No deficiencies noted.	work does not identify any deficiencies that compromise the quality of the data collected or work performed.	identifies deficiencies that do not compromise the quality of the data collected or work performed and can be corrected.	work identifies deficiencies that compromise the quality of the data collected or work performed but was corrected.	identifies deficiencies that compromise the quality of the data collected or work performed and cannot be corrected.
Performance Category 3: Schedule					
Schedule	Contractor achieves milestone more than 60 days ahead of schedule (unless the COR waives this requirement), per criteria established in the PWS.	Contractor achieves milestone less than 60 days but more than 30 days ahead of schedule (unless the COR waives this requirement), per criteria established in the PWS.	Contractor achieves milestone according to the schedule (unless the COR waives this requirement), per criteria established in the PWS.	Contractor achieves milestone no more than 90 days behind schedule (unless the COR waives this requirement), per criteria established in the PWS.	Contractor achieves milestone more than 90 days behind schedule or does not achieve the milestone (unless the COR waives this requirement), per criteria established in the PWS.
Performance Category 4: Safety					
Safety	No significant safety deficiencies are reported during QA inspection of fieldwork. No lost time accidents or injuries are recorded during the fieldwork.	No more than one serious safety deficiency is reported during QA inspection of fieldwork. If any serious safety deficiency is noted during the project, appropriate investigation, corrective action, implementation, and	No more than two serious safety deficiencies are reported during QA inspection of fieldwork. If any serious safety deficiency is noted during the project, appropriate investigation, corrective action, implementation, and written verification of the corrective action are provided to AFCEC.	No more than three serious safety deficiencies are reported during QA inspection of fieldwork. If any serious safety deficiency is noted during the project, appropriate investigation, corrective action,	More than three serious safety deficiencies are reported during QA inspection of field activities, or a serious safety deficiency is reported but not properly investigated and corrected, or two or more lost time accidents or injuries is recorded during the fieldwork.

Performance Standard	Exceptional	Very Good	Satisfactory	Marginal	Unsatisfactory
		written verification of the corrective action are provided to AFCEC. No lost time accidents or injuries are recorded during the fieldwork.	No lost time accidents or injuries are recorded during the fieldwork.	implementation, and written verification of the corrective action are provided to AFCEC. No more than one lost time accident or injury is recorded during the fieldwork.	
Performance Category 5: Management of Key Personnel and Resources					
Management of Key Personnel and Resources	All key personnel proposed by the Contractor were assigned to the project or key personnel were substituted by equally or more highly qualified individuals. Zero instances of resource management issues creating a negative impact to the activity.	All key personnel proposed by the Contractor were assigned to the project or key personnel were substituted by equally or more highly qualified individuals. No more than one instance of resource management issues creating a negative impact to the activity.	All key personnel proposed by the Contractor were assigned to the project or key personnel were substituted by equally or more highly qualified individuals. No more than two instances of resource management issues creating a negative impact to the activity.	All key personnel proposed by the Contractor were assigned to the project or key personnel were substituted by equally or less qualified individuals. No more than three instances of resource management issues creating a negative impact to the activity.	All key personnel proposed by the Contractor were assigned to the project or key personnel were substituted by less qualified individuals. More than three instances of resource management issues creating a negative impact to the activity.
Performance Category 6: Stakeholder Concurrence					
Stakeholder Concurrence	Contractor obtains concurrence on deliverables from all project stakeholders including state and local regulatory agencies. This concurrence is obtained independently with no involvement and	Contractor obtains concurrence on deliverables from all project stakeholders including state and local regulatory agencies. This concurrence is	Contractor obtains concurrence on deliverables from all project stakeholders including state and local regulatory agencies. This concurrence is obtained with moderate	Contractor obtains concurrence on deliverables from all project stakeholders including state and local regulatory agencies. This concurrence is	Contractor does not obtain concurrence on deliverables from all project stakeholders including state and local regulatory agencies.

Performance Standard	Exceptional	Very Good	Satisfactory	Marginal	Unsatisfactory
	coordination required by AFCEC.	obtained independently with limited involvement and coordination required by AFCEC.	involvement and coordination required by AFCEC.	obtained with significant involvement and coordination required by AFCEC.	

Figure 2. Service Summary

Performance Objective	PWS Para. Reference	Threshold	Surveillance Method
Project Management Plan (PMP): 1) Draft PMP 2) Final PMP 3) Updates as necessary	Para. 1.3.1; 4.1	Satisfactory Ref. Figure 1, Performance Categories 1, 2, & 5 Draft within 60 calendar days from contract award, Final within 14 calendar days of receipt of AF comments on the draft	100% Inspection Ref. Figure 3 “Technical Plans and Report Quality”
Integrated Master Schedule (IMS)/Milestone Payment Schedule (MPS)	Para. 1.3.1; 4.2; 4.3	Satisfactory Ref. Figure 1, Performance Categories 1, 2, & 5 Draft within 60 calendar days from contract award, Final within 14 calendar days of receipt of AF comments on the draft	100% Inspection of initial IMS/MPS Periodic Inspection of Updates (MPS review only when changes are required, IMS review monthly) Ref. Figure 3 “IMS and MPS”

Performance Objective	PWS Para. Reference	Threshold	Surveillance Method
Basewide Quality Program Plans (QPP) for each Installation	Para. 1.3.1; 6.1; 6.1.1; 6.1.2; 6.1.3	Satisfactory Ref. Figure 1, Performance Categories 1, 2, & 5 Draft within 60 calendar days from contract award and update as necessary throughout the POP	100% Inspection Ref. Figure 3 “Technical Plans and Report Quality”
Community Involvement Plan (CIP) for all open sites at each Installation	Para. 1.3.1; 4.6.2.1	Satisfactory Ref. Figure 1, Performance Categories 1, 2, & 5	100% Inspection Ref. Figure 3 “Technical Plans and Report Quality”
Restoration Advisory Board Support	Para 1.3.1; 4.6.2	Satisfactory Ref. Figure 1, Performance Categories 1, 2, & 5	100% Inspection Ref. Figure 3 “Communications” and “Status Reports, Meeting Minutes, and Presentations”
LTM in accordance with the approved ROD/DD (Multiple Sites)	Para 1.2.6; 1.2.7.2.1; 1.3.1; 1.3.2	Satisfactory Ref. Figure 1, Performance Categories 1-5	Periodic Inspection Semi-annually and Annually of LTM activities 100% Inspection of milestone reports Ref. Figure 3 All surveillance activities apply

Performance Objective	PWS Para. Reference	Threshold	Surveillance Method
RA-O in accordance with the approved ROD/DD (Multiple Sites)	Para 1.2.6; 1.2.7.2.1; 1.3.1; 1.3.2	Satisfactory Ref. Figure 1, Performance Categories 1-5	Periodic Inspection (Weekly) of RA-O activities 100% Inspection of milestone reports Ref. Figure 3 All surveillance activities apply
Record of Decision and/or Corrective Measure Study/Corrective Action Plan (Multiple Sites)	Para 1.2; 1.2.6; 1.3.1; 2.0; 6.2; 8.9	Satisfactory Ref. Figure 1, Performance Categories 1-5	Periodic Inspection 100% Inspection of milestone reports Ref. Figure 3 All surveillance activities apply
Record of Decision – Amendment (Multiple Sites)	Para 1.2; 1.2.6; 1.2.7.3; 1.3.1; 2.0; 6.2; 8.9	Satisfactory Ref. Figure 1, Performance Categories 1-5	Periodic Inspection 100% Inspection of milestone reports Ref. Figure 3 All surveillance activities apply
Remedy in Place	Para 1.3.1	Satisfactory Ref. Figure 1, Performance Categories 1-5	Periodic Inspection 100% Inspection of milestone reports Ref. Figure 3 All surveillance activities apply

Performance Objective	PWS Para. Reference	Threshold	Surveillance Method
Alternate Objectives	Para 1.2.7; 1.3.1	Satisfactory Ref. Figure 1, Performance Categories 1-5	Periodic Inspection 100% Inspection of milestone reports Ref. Figure 3 All surveillance activities apply
Removal of Unused Treatment System	Para 1.3.1	Satisfactory Ref. Figure 1, Performance Categories 1-5	Periodic Inspection 100% Inspection of milestone reports Ref. Figure 3 All surveillance activities apply
Restart Remediation System	Para 1.3.1	Satisfactory Ref. Figure 1, Performance Categories 1-5	Periodic Inspection 100% Inspection of milestone reports Ref. Figure 3 All surveillance activities apply

Figure 3. Surveillance Activities Table

Surveillance Activities	Performance Measure	Monitoring Method	Documentation
Communications	- Ability to team with project stakeholders. - Timely notification of potential issues and problems.	Periodic Inspections/ Customer Feedback/ Contractor's Progress,	AFCEC approval

Surveillance Activities	Performance Measure	Monitoring Method	Documentation
		Status, and Management Reports/ Status Meetings	
Technical Plans and Report Quality	- AFCEC approval. (Revisions not required due to unacceptable quality.) - Regulatory approval of technical document.	100% Inspection	COR completed PARs, emails, and letters and regulator emails and letters
Field Work Completion	- Installation or removal of equipment, systems, and wells in accordance with regulatory requirements. - Performance of sampling in accordance with approved QAPP/Work Plan. - Restoration of site surface to original or agreed-upon conditions.	Periodic Inspections/ Customer Feedback	COR completed PARs, emails, and letters with RPM concurrence
Laboratory Analysis and Data Review	- AFCEC approval of laboratory data package. - AFCEC approval of data validation report. - Environmental Resources Program Information Management System (ERPIMS) data submissions that are error-free, pass all validation checks, are submitted within 90 days of sample collection, and fully comply with the ERPIMS Data Loading Handbook.	Periodic Inspections	COR completed PARs, emails, and letters, and customer surveys
Status Reports, Meeting Minutes, and Presentations	Adequate detail/accuracy upon first submittal. (Revisions not required due to unacceptable quality.)	Periodic Inspections/ Customer Feedback	AFCEC approval
IMS and MPS	- Adherence to IMS/MPS guidance. - Maintenance of IMS/MPS to accurately reflect completed activities and realistic schedule of planned activities. - Monthly submission of IMS updates per PWS requirements	Periodic Inspections/ Customer Feedback	AFCEC approval
O&M	O&M of equipment, systems, and wells in accordance with regulatory requirements, manufacturer instructions, and O&M manuals.	Periodic Inspections/ Customer Feedback	COR completed PARs, emails, and letters with RPM concurrence

10.0 SERVICE CONTRACT REPORTING (SCR) REQUIREMENTS

IAW 10 United States Code (U.S.C.) 2330a, the DoD is required "to establish a data collection system to provide management information with regard to each purchase of services by a military department or Defense Agency for services." For DoD, this includes contract actions in specific service acquisition portfolio groups, to include logistics management services, equipment related services, knowledge-based services, and electronics and communications services that exceed \$3M annually.

11.0 CONTRACTOR LABOR HOURS

The Contractor shall report ALL Contractor labor hours (including subcontractor labor hours) required for performance of services provided under this task order via SAM. Contractor is required to completely fill in all required data fields at <http://www.sam.gov>.

Reporting inputs will be for the labor executed during the period of performance for each Government fiscal year (FY), which runs 1 October through 30 September. The reporting period for contractors in SAM generally is open from mid-October to mid-December for reporting against the prior government fiscal year. SAM will only enable reporting for entities with contracts that meet the SCR thresholds. Contractors may direct questions to the SAM help desk.

12.0 USES AND SAFEGUARDING OF INFORMATION

Information from the secure web site is considered proprietary in nature when the task order number and Contractor identity are associated with the direct labor hours and direct labor dollars. At no time will any data be released to the public with the Contractor name and task order number associated with the data.

13.0 POINTS OF CONTACT

POCs will be specified upon contract award.