

Scope of Work

M/V John A.B Dillard Jr Main Engine Maintenance for Two ACERT C-32 Caterpillar Marine Engines

1. Tasks and Deliverables

- a. Complete the following on both Port and Starboard CAT ACERT C032 Marine Engines with a certified Caterpillar marine technician/mechanic. All replacement parts, fluids, etc. shall be manufacturer recommended or marine grade equivalent.
 - i. Replace extended life coolant (ELC) with ELC-Advanced. Drain and Flush system with potable water.
 - ii. Contractor will be responsible for disposal of all materials used for work according to Federal, State, and local regulations.
 - iii. Remove and replace cooling system temperature regulators.
 - iv. Check, clean, and calibrate engine speed/timing sensors.
 - v. Clean, test, inspect, and reseal heat exchanger.
 - vi. Clean, test, and inspect oil cooler.
 - vii. Replace auxiliary water pump and all necessary parts related with new
 - viii. Replace all soft fuel lines with new.
- b. Provide a condition found report for all failed conditions, parts, seals, etc. discovered while performing, but not directly associated with, the work described above.
- c. Provide a certified Caterpillar marine technician/mechanic for a sea trial to observe/valid performance of work completed. Remedy unsatisfactory performance, if observed.

2. Period of Performance – 30 days

3. Work shall be performed between the hours of 6AM and 4PM, Monday through Friday, excluding federal holidays.
4. Perform work at the vessel's berth at 2100 Bridgeway Sausalito, CA 94965.
5. Prior to the start of work, coordinate with the Contracting Officer's Representative (COR) on an Activity Hazard Analysis for working the vessel before, during, and after work. At a minimum, this will cover proper Lock-out tag-out procedures. A pre work safety meeting will be held each day with contractor and COR govt surveillance team.
6. All work will be performed under government surveillance determined by COR
7. Itemize parts, labor, etc. into the submitted quote.
8. Payment to be processed after successful sea trial with no observed leaks, overheating, or other unsatisfactory performance associated with work performed.