

Statement of Work

For

Replace Lights ARCENT, 1947

Project: VLSB 26-0075

10 Feb 2026

Scope of Work:

This Statement of Work (SOW) is for the LED upgrade of all the office troffer lights at ARCENT B1947 on Shaw AFB for FY26. The contractor shall provide all personnel, equipment, supplies, facilities, transportation, tools, materials, supervision, and other items and non-personal services necessary for the replacement/upgrade of the existing lights to LEDs at the following facility:

B1947 ARCENT

The contractors work shall be done in accordance with the International Building Code (IBC), National Electric Code (NEC), National Electrical Safety Code (NESC), National Fire Protection Association (NFPA), ASHRAE 90.1, and Unified Facilities Criteria (UFC), and latest editions. In addition, all work shall adhere to the Shaw AFB design standards (2018).

The contractor's responsibilities shall include the following:

1. Demolition and disposal of the existing fluorescent lighting fixtures (1'x4', 2'x4', 2'x2'). To include hangers and lamps back to the existing circuit and conduit.
2. Installation of new LED troffers (1'x4', 2'x4', 2'x2').
3. Commissioning of the systems to ensure functionality.
4. Submittals and O&M manuals.

The contractor shall perform all work with minimal impact on the daily operations of base personnel and the surrounding work environment. The Contractor shall coordinate with the contract inspector to arrange for access to the work areas and provide a 2-week minimum notice.

B1947 – Lighting Replacement

Demolition

- Demo and dispose of the existing fluorescent 1x4, 2x4, and 2x2 troffer fixtures, to include lamps, ballasts, and hangers. See **Attachments 01** and **02** for fixture locations and types. Types labeled A1-A5, A9, and P1-P3 are the troffers to be demo'd.

- The demarcation point for the demo is back to the existing conduit and circuit (they are to remain). The fixtures, lamps, and hangers are to be demo'd.

LED Lighting Install

The LED install shall be compliant with *UFC 3-530-01 – Interior and Exterior Lighting Systems (Attachment 03)* and *ASHRAE 90.1 (Attachment 04)*. The main areas to be replaced are office spaces and therefore shall have an average illuminance of 30 fc (foot-candles) per UFC. Per the UFC, the LEDs shall also have a CRI of 80+ and a CCT of 3500K. All lights shall work in range of 100-277V. All lights shall have ability to be dimmed between 30% and 70% of full lighting power.

The contractor shall provide shop drawings that includes the average illuminance calculations.

The contractor shall update and reseal the following drawings.

V2-E-600,V2-E-601,V2-E-602,V2-E-603,V2-E-604 CAD files to be provided after award.

The contractor shall also submit an updated light panel list.

All LED fixtures shall be used as static lighting, with dimming capability. Toggle switches shall remain for on/off functionality. This project shall not utilize the dimming capability of the fixtures.

In areas where lift is needed, the contractor shall work around any government furniture, avoiding damages.

- Install the new type A1 LED 1'x4' troffer fixtures for both floors.
 - 2 emergency backup fixtures. Requires emergency battery backups. Locations indicated on Attachment 01.
- Install the new type A2 LED 1'x4' troffer fixtures for both floors.
 - 31 fixtures.
 - 9 of the fixtures are on emergency backup and require an emergency battery backup. Locations indicated on Attachment 01.
- Install the new type A3 LED 2'x4' troffer fixtures for both floors.
 - 95 fixtures.
 - 1 fixture is on emergency backup and requires an emergency battery backup. Location indicated on Attachment 01.
- Install the new type A4 LED 2'x4' troffer fixtures for both floors.
 - 9 fixtures.
 - 2 of the fixtures are on emergency backup and require an emergency battery backup. Locations indicated on Attachment 01.
- Install the new type A5 LED 2'x2' troffer fixtures for both floors.

- 81 fixtures.
 - 2 of the fixtures are on emergency backup and require an emergency battery backup. Locations indicated on Attachment 01.
- Install the new type A9 2'x4' troffer fixtures for both floors.
 - 18 fixtures.
 - 3 of the fixtures are on emergency backup and require an emergency battery backup. Locations indicated on Attachment 01.
- Install the new type B1 LED fixtures with 2'x2' prismatic lens fixtures for both floors.
 - 281 fixtures.
 - 18 of the fixtures are on emergency backup and require an emergency battery backup. Locations indicated on Attachment 01.
- Install the new type P1 2'x4' parabolic troffer fixtures for both floors.
 - 284 fixtures.
 - 10 of the fixtures are on emergency backup and require an emergency battery backup. Locations indicated on Attachment 01.
- Install the new type P2 2'x4' parabolic troffer fixtures for both floors.
 - 658 fixtures.
 - 7 of the fixtures are on emergency backup and require an emergency battery backup. Locations indicated on Attachment 01.
- Install the new type P3 2'x2' parabolic troffer fixtures for both floors.
 - 621 fixtures.
 - 127 of the fixtures are on emergency backup and require an emergency battery backup. Locations indicated on Attachment 01.
- After all fixture installs are complete, connect them to the existing circuit and conduit, using electrical whips from the fixtures.
- Test for functionality.
- Provide O&M manuals for the lights.

Assumptions & Attachements

- A scaffolding/scissor lift will be required for two areas with fixtures at 28' high.
- The 1947 facility will provide bathroom access for the crew.
- CE will provide a laydown yard after the contract is awarded.
- No PE sealed drawings required.
- Attachments:
 - Attachment 01 – B1947 ARCENT Lighting Plans
 - Attachment 02 – B1947 ARCENT Luminaire Schedules
 - Attachment 03 – UFC 3-530-01-2023
 - Attachment 04 – ASHRAE 90.1-2022

Schedule

- Site access: Contractor will need an escort with security clearance.
- 27 weeks to complete the lighting replacement.

GENERAL DESIGN AND CONSTRUCTION NOTES:

Any references to State Government, Federal Government, or Industry standards or specifications made herein shall form a part of this specification to the extent referenced thereto and all materials and workmanship under this contract shall comply with or exceed these standards and references. All referenced standards shall be the latest edition.

The Contractor shall supply manufacture's cut sheets with the submittal where the component is identified.

Where specific part numbers or manufactures are referenced, it shall be understood that the contractor may use an approved equal.

All manufactured equipment and products shall be new materials in good condition and installed as per manufacturer's latest printed instructions, unless specified otherwise herein.

The Contractor is responsible for protection of existing facilities equipment from damage during installation and testing operations.

Contractor shall take into account the special treatment of hazardous waste, as well as the environmental implications related to building demolition management (i.e. fluorescent lighting tubes, t-stats, etc.). Every effort shall be made to recycle eligible materials, and those not suitable, shall be disposed of off base in accordance with all (SCDHEC) South Carolina Department of Health and Environmental Control regulations.

If any submittal doesn't, in the opinion of the Contracting Officer, meet or exceed the requirements contained within this SOW, in the Shaw AFB Design Standards or in any referenced design guidance or nationally recognized code then it shall be considered to be unacceptable and returned to the Contractor for correction and resubmission. The Contracting Officer has the option, in lieu of disapproval, to provide acceptance of a submittal with required corrections identified if it is determined the submittal is substantially complete and correct.

Ensure that any demolition, utility cut and capping, and debris removal service performed at Shaw AFB, South Carolina is completed in such a manner that will restore a neat and professional appearance of base areas.

The facility/area shall be cleaned in its entirety, including exterior areas, before being returned the government.

WARRANTY:

Contractor shall furnish a minimum one year warranty against defects in material and workmanship starting on the beneficial occupancy date.

GENERAL INFORMATION:

The contractor shall provide all management, tools, supplies, equipment, labor, and applicable licenses and permits necessary to complete the requirements within. All work shall be done in strict accordance with this Statement of Work and subject to the terms and conditions of the contract and in accordance with (UFC) Unified Facilities Criteria, Unified Facilities Guide Specifications (UFGS), the International Building Code (IBC), International plumbing code (IPC), South Carolina Department of Health and Environmental Control (SCDHEC), National Electrical Code (NEC), National Electrical Safety Code (NESC), National Fire Protection Association (NFPA), EPA 402-K-01-001 (2008), South Carolina Department of Transportation (SCDOT), South Carolina Department of Health and Environmental Control (SCDHEC) Shaw Air Force Base Design and Construction Standards, Change 2, 21 Aug 2018 and all other applicable codes.

Contractor is responsible for verifying all dimensions, quantities and square footages. All dimensions, quantities and square footages included are approximations. Construction and demolition shall be in strict accordance with the Shaw Air Force Base Design and Construction Standards. The information provided in this Statement of Work (SOW), the provided drawings, and the requirements of the Shaw Air Force Base Design and Construction Standards shall be determined to be the minimum standards required in this project.

The contractor shall video all areas in which work shall occur prior to starting work to include interior and exterior of the project site. UFC's take precedence over all standards, codes and Shaw AFB Design Standards and requirements that pertain to the work within this SOW.

During construction, the contractor shall take care not to damage existing structures, etc. that will not be replaced as part of this contract. Contractor shall be responsible for the

temporary support of all devices as required to perform work. Any demolition work that needs to be accomplished to complete the contract is the responsibility of the contractor. All material shall be installed per manufacturers' recommendations. All items listed in the SOW are to be supplied and installed by the contractor unless otherwise noted.

A pre-construction meeting will be held at Shaw AFB to include the Contractor and Government representatives. The Government shall set up this meeting, to be held on Shaw AFB, with the Contractor and Government representatives, to discuss all remodel requirements, as well as any other construction issues the Contractor may have. All finishes shall be presented to the project inspector as **one** submittal for selection and approval prior to installation. All material that could be discontinued shall be on-site, i.e. carpet and tile prior to starting project so there will be no difference in color.

All Contractors shall be responsible for submitting a completed DD1354 (AUG 2013 edition, PDF file) with each progress payment request (beginning at 50% construction completion). This form shall be marked "Draft" until the Contractor has reached approximately 90% completion, or when it has been determined that funding will not be adjusted due to modifications. The Contractor shall have a reviewed and accepted DD1354 submitted to the Government Inspector two (2) weeks prior to the scheduled final inspection date (i.e. Placed In Service Date). This reviewed and accepted DD1354 shall be marked "Interim" until the final inspection occurs.

PERMITS:

The contractor shall pay for and obtain any required permits. The contractor shall act in accordance with this Statement of Work, SCDHEC, Federal, and Shaw AFB guidelines.

WORKING CONDITIONS:

The Contractor shall take all precautions to insure that his operations are conducted in a manner as to minimally interfere with the normal operations of the base and the safety and convenience of the base personnel. The contractor shall coordinate utility outages with the Civil Engineering Squadron (CE) service call and the user.

ASBESTOS/LEAD BASED PAINT:

N/A - Building B1947 was built in 2010

DEBRIS HAULING AND DISPOSAL:

Contractor shall use an approved hauling route to prevent interference with base operations. In order to prevent problems with traffic, noise, wear and tear on roads, or other problems having the potential to adversely affect health, safety, or the environment, the government reserves the right to regulate routes, intervals, delivery points, and times for hauling.

All debris hauled by the contractor shall be enclosed to prevent leaking, spilling, or blowing. The Contractor shall ensure all debris or dirt is promptly removed from any transportation route if such debris is spilled, blown, or leaked from hauling equipment and vehicles. The contractor shall remove all dirt and mud caused by tracks of hauling equipment within one hour of notification by the Government. All demolition debris collected by the contractor shall be housed dumpsters and covered at all times and disposed of in an authorized landfill or transfer station. No disposal or burning is allowed on base. The contractor shall provide the government inspector with an electronic copy of each dump receipt on the following work day by 0800 with the daily report.

DAILY REPORTS:

The contractor shall provide the government with an electronic copy of each dump receipt along with the daily report by 0800 the following work day. All daily reports will be submitted in RAKEN format and shall include pictures of work performed for each day.

END OF STATEMENT OF WORK