

Supply Items

U.S. Army Corps of Engineers (USACE)

Material Procurement Package –

1. Purpose

The contractor shall furnish, package, label, and deliver the materials listed in Section 2 to the Saylorville Lake Visitor Center, **8250 NW Horseshoe Rd, Ankeny, Iowa 50023**. All materials must meet the specifications provided, be new and unused, and comply with applicable industry standards, including AWWA, ASTM, and manufacturer requirements.

2. Bill of Materials (BOM) – Required Items

The contractor shall supply the following items in the exact quantities listed. Substitutions are **not permitted** without prior written approval from the Contracting Officer (KO).

2.1 Structural Connectors & Hardware

- **32** – SUL210Z Skewed Single Joist Hanger
- **32** – SUR210Z Skewed Single Joist Hanger
- **240** – LUS210Z Single Joist Hanger
- **24** – HUCQ412Z-SDSG Concealed Flange Face-Mount Hanger (must include all required SDS screws)
- **80** – Titen HD 5/8" x 6" Anchors
- **40** – 5/8" Galvanized Flat Washers
- **8** – GJH1125P 1-1/2" Galvanized Joist Hanger Nail – 5 lb boxes

2.2 Lumber – Treated Southern Yellow Pine (SYP)

All treated lumber must be:

- **#1 or #2 grade SYP as specified**
- **Ground-contact rated**
- **Pressure-treated per AWWA UC4A or higher**

Required quantities:

- **120** – 2" x 12" x 16' #1 SYP Treated – Ground Contact
- **11** – 2" x 12" x 20' #1 SYP Treated – Ground Contact
- **400** – 2" x 6" x 16' #2 SYP Treated – Ground Contact
- **32** – 2" x 8" x 20' #2 SYP Treated – Ground Contact

- **800** – 2"x2" x 4' Baluster #1 SYP Treated- Ground Contact
- **25** – 4"x4" x 10' #1 SYP Treated-Ground Contact

2.3 Glu-Lam Beams – Treated

Beams must be:

- **3-1/2" x 11-7/8"**
- **Treated for exterior exposure**
- **Rated for structural load-bearing applications**

Quantities:

- **8** – 32' x 3-1/2" x 11-7/8" R/L Treated Glu-Lam Beam
- **3** – 20' x 3-1/2" x 11-7/8" R/L Treated Glu-Lam Beam

2.4 Fasteners & Specialty Screws

- **8** – BTX9318 9" x 3-1/8" Bronze Star Screws – Bulk 23.8 lb containers

2.5 Protective Tape

- **16** – 4" x 50' Super Seal Joist Tape (Protecto-Wrap)
- **56** – 2" x 50' Super Seal Joist Tape (Protecto-Wrap)

3. Material Standards & Compliance

All supplied materials must meet the following standards:

- **Simpson Strong-Tie** components must be genuine, manufacturer-certified products.
- **Treated lumber** must comply with:
 - AWWPA Standards (UC4A minimum for ground contact)
 - ASTM D1990 (structural lumber evaluation)
 - Grade stamps from an accredited agency (SPIB, WCLIB, etc.)
- **Glu-lam beams** must meet:
 - ANSI A190.1
 - APA/EWS certification
 - Exterior-rated adhesive requirements
- **Fasteners and anchors** must meet:
 - ICC-ES approvals where applicable
 - ASTM A153 or equivalent for galvanization

4. Packaging, Marking, and Labeling

Contractor shall ensure:

- All items are packaged to prevent damage during transport.
- Lumber is banded securely and protected from moisture.
- Hardware is boxed and labeled with manufacturer, model number, and quantity.
- Pallets are clearly marked with:
 - Contract number
 - Item description
 - Quantity
 - Delivery location

5. Delivery Requirements

- Delivery FOB Destination: **Within 14 days of contract award**
- Delivery destination: **8250 NW Horseshoe Rd, Ankeny, Iowa 50023.**
- Deliveries must occur **Monday–Friday, 7:00am –3:00pm**, excluding federal holidays.
- Contractor must coordinate delivery at least **48 hours in advance** with the **POC:** (Jake Kidman 515-710-9744).
- A delivery ticket must accompany each shipment and include:
 - Contract number
 - Itemized list of materials
 - Quantities delivered
 - Manufacturer information

Partial shipments require prior approval.

6. Inspection and Acceptance

USACE will inspect materials upon delivery for:

- Correct quantities
- Compliance with specifications
- Damage or defects
- Proper documentation

Materials failing inspection will be rejected and must be replaced at no cost to the Government.

7. Warranty

All materials shall carry the standard manufacturer warranty. Defective materials discovered during installation or within the warranty period must be replaced by the contractor at no additional cost.

8. Contractor Responsibilities

- Provide all materials listed in Section 2.

- Ensure compliance with all specifications and standards.
- Coordinate delivery with the POC
- Replace any damaged or non-compliant materials.
- Maintain communication with the KO and COR throughout the procurement process.
- INVOICES SHALL BE SENT TO THE FOLLOWING POINT OF CONTACT: Phillip Rustad at phillip.d.rustad@usace.army.mil
- Please ensure that your invoice reflects the company name(s) and physical address listed on your SAM registration.

CLIN	Description	Qty	Unit	Unit Price	Total
0001	SUL210Z Skewed Single Joist Hanger	32	EA	___	___
0002	SUR210Z Skewed Single Joist Hanger	32	EA	___	___
0003	2"x12"x16' #1 SYP Treated – Ground Contact	120	EA	___	___
0004	2"x12"x20' #1 SYP Treated – Ground Contact	11	EA	___	___
0005	LUS210Z Single Joist Hanger	240	EA	___	___
0006	32'x3-1/2"x11-7/8" R/L Treated Glu-Lam Beam	8	EA	___	___
0007	20'x3-1/2"x11-7/8" R/L Treated Glu-Lam Beam	3	EA	___	___
0008	Titen HD 5/8" x 6" Anchors	80	EA	___	___
0009	5/8" Galvanized Flat Washer	40	EA	___	___
0010	HUCQ412Z-SDSG Concealed Flange FM Hanger (with SDS screws)	24	EA	___	___
0011	GJH1125P 1-1/2" Galvanized Joist Hanger Nails – 5 lb box	8	BX	___	___
0012	2"x6"x16' #2 SYP Treated – Ground Contact	400	EA	___	___
0013	BTX9318 9"x3-1/8" Bronze Star Screw – 23.8 lb container	8	CT	___	___
0014	2"x8"x20' #2 SYP Treated – Ground Contact	32	EA	___	___
0015	4"x50' Super Seal Joist Tape (Protecto-Wrap)	16	RL	___	___
0016	2"x50' Super Seal Joist Tape (Protecto-Wrap)	56	RL	___	___
0017	2"x2" x 4' Baluster #1 SYP Treated- Ground Contact	800	EA	___	___
0018	4"x4" x 10' #1 SYP Treated-Ground Contact	25	EA	___	___

Total Contract Value: \$_____