

USS MIGUEL KEITH
ESB-5

N32205-XX-X-XXXX, -XXXX, -XXXX

ESB-5 FIRE FIGHTING SMART SUPPORT PWS

1.0 ABSTRACT

1.1 Test and demonstrate the ship's fire detection and fixed fire fighting systems for the SMART/INSURV Inspection.

2.0 REFERENCES/ENCLOSURES

2.1 References:

- 2.1.1 Code of Federal Regulations, 46 CFR, Chapter 1, part 76.27 (latest revision)
- 2.1.2 NAVSEA Drawing No. 8496378 Fire Control and Safety Plan (available onboard)
- 2.1.3 Tech Manual S9543-AA-MMC-010, High Pressure Carbon Dioxide Marine Fire Suppression System (available onboard)
- 2.1.4 Tech Manual S9555-FL-MMC-010, Aqueous Film Forming Foam (AFFF) Fire Fighting Equipment System (available onboard)
- 2.1.5 Tech Manual TG511-AD-MMC-010, Addressable Fire Detection System, Installation, Operation and Maintenance Manual (available onboard)
- 2.1.6 TEST MEMO 80833, CO2 SYSTEMS - HIGH/LOW PRESSURE
- 2.1.7 TEST MEMO 80812, SMOKE, FIRE AND GAS DETECTORS
- 2.1.8 TEST MEMO 80841, FOAM SPRINKLING SYSTEM
- 2.1.9 TEST MEMO 80846, FIRE EXTINGUISHING SYSTEM, GALLEY

2.2 Enclosures:

2.2.1 None.

3.0 ITEM LOCATION/DESCRIPTION

3.1 Location/Quantity:

3.1.1 Various, as per reference 2.1.2.

3.2 Description/Manufacturer's Data:

- a. CO2 Systems
Mfr: Kidde-Belleville, Division of Kidde, Inc.
- b. Fire Detection System
Mfr: Herbert S. Hiller Corp.
- c. Fire Protection System, AFFF
Mfr: VARIOUS

4.0 GOVERNMENT FURNISHED EQUIPMENT/MATERIAL/SERVICES

4.1 Material: None.

USS MIGUEL KEITH
ESB-5

N32205-XX-X-XXXX, -XXXX, -XXXX

ESB-5 FIRE FIGHTING SMART SUPPORT PWS

5.0 NOTES

- 5.1 Testing evolutions shall be coordinated with and through the Port Engineer, Chief Engineer, Chief Mate, and the SMART Inspectors.
- 5.2 Period of Performance: 06 to 11 April 2026
- 5.3 Location: an available 7th Fleet port of call, determined upon contract award

6.0 QUALITY ASSURANCE REQUIREMENTS

- 6.1 All work shall be to the satisfaction of the Port Engineer , Chief Engineer, Chief Mate and the Smart Inspectors.

7.0 STATEMENT OF WORK REQUIRED

- 7.1 The contractor shall provide the services of a USCG/ABS approved firm specializing in the repair and re-certification of fixed and portable CO2, AFFF, galley, and dry chemical fire extinguishing systems and equipment onboard ship. Said firm shall attend the ship and test and demonstrate the fire detection and fixed fire fighting systems in reference 2.1.2, using references 2.1.3 thru 2.1.9 for guidance.
- 7.2 Contractor to preform inspection and test of the heat and smoke sensor devices in accordance with ref 2.1.1 to the satisfaction of the SMART inspectors using ref 2.1.5 and 2.1.7 for guidance.
- 7.3 Conduct an operational simulation test of all fire detection and fire fighting systems in the presence of the Chief Engineer, Port Engineer, and SMART inspectors in accordance with references 2.1.6 through 2.1.9. Contractor to provide all test equipment and materials to complete all test and inspections specified in references 2.1.6 through 2.1.9. Demonstrate proper operation of all remote releases, ventilation shutdowns, time delays, and alarms. Contractor to arrange for shipping of all test equipment to and from port location.
 - 7.3.1 Provide two (2) each new 60 second Time delays to the Ship.
- 7.4 Once all testing and inspections are complete the contractor shall reconnect all systems making sure all bottles are filled and systems are ready for service.
- 7.5 All dirt and debris resulting from this work item shall be removed daily and all areas left clean and in good order.
- 7.6 Manufacturer's Representative: None.

USS MIGUEL KEITH
ESB-5

N32205-XX-X-XXXX, -XXXX, -XXXX

ESB-5 FIRE FIGHTING SMART SUPPORT PWS

7.7 Preparation of Drawings: None.

8.0 GENERAL REQUIREMENTS: None Additional.