

STATEMENT OF WORK

1.0 Specifications

1.1 Baltimore VA Maryland Health Care System, VA Medical Center 3rd Floor
Greenspace/Atrium Artificial Plants: Contractors shall provide and install all new artificial plants, trees and flowers to complete the installation.

1.1.1 Note: Field Measurements need to be obtained prior to product being ordered.

1.2 Scope of Work: The following specifications apply to artificial plants, trees and flowers on the Baltimore Hospital 3rd floor Greenspace/Atrium at Baltimore VA Maryland Health Care System, VA Medical Center:

1.2.1 Zone A: Patient Window Garden Beds: Artificial plants are 26 inch in overall height, which is the distance from the very bottom of the weighted base to the top of the foliage. This will feature UltraLeaf-IFR a proprietary, commercial grade, inherently fire-retardant foliage designed to meet ASTM-E84 and /or NFPA-701 fire-safety standards for indoor use.

1.2.1.01 78ft Length x 8ft Width Elements:

Qty (26) 21" Artificial Blue with Purple Hydrangea Bush.

Qty (26) 26" Artificial Lavender Bush.

Qty (26) 17" Artificial Orange Wildflower Bush.

Qty (26) 14.5" Artificial Pink Verbena Cluster Bush.

Qty (52) 18" Grass Bush.

1.2.2 Zone B: 3 Raised Garden Beds: Artificial Plants 43 inch in overall height, which is the distance from the very bottom of the weighted base to the top of the foliage. This will feature UltraLeaf-IFR a proprietary, commercial grade, inherently fire- retardant foliage designed to meet ASTM-E84 and /or NFPA-701 fire-safety standards for indoor use.

1.2.2.01 8ft Length x 3ft Width Elements:

Qty (3) 43" Artificial Schefflera Ball Tree.

Qty (18) 17" Artificial Orange Wildflower Bush.

Qty (24) 12.5 Artificial Grape Hyacinth Plant.

Qty (36) 10"x10" Artificial Grass Mat.

Qty (15) 36" Artificial Hanging Fuchsia Bougainvillea Bush.

1.2.3 Zone C: Middle Garden Bed: Artificial Plants 56" in overall height, which is the distance from the very bottom of the weighted base to the top of the foliage. This will feature UltraLeaf-IFR a proprietary, commercial grade, inherently fire- retardant foliage designed to meet ASTM-E84 and /or NFPA-701 fire-safety standards for indoor use.

1.2.3.01 78ft Length x 8ft Width Elements:

Qty (36) 56" Artificial Foxtail Onion Grass.

Qty (32) 32" Artificial Tree Fern Plant.

Qty (48) 30" Green/Yellow Onion Grass Bush.

- 1.2.4 Zone D: Middle Garden Bed by Walkway: Artificial Plants 26" in overall height, which is the distance from the very bottom of the weighted base to the top of the foliage. This will feature UltraLeaf-IFR a proprietary, commercial grade, inherently fire- retardant foliage designed to meet ASTM-E84 and /or NFPA-701 fire-safety standards for indoor use.

1.2.4.01 78ft Length x 6ft Width Elements:

Qty (25) 21" Artificial Blue with Purple Hydrangea Bush.

Qty (30) 26" Artificial Lavender Bush.

Qty (25) 17" Artificial Orange Wildflower Bush.

Qty (30) 14.5" Artificial Pink Verbena Cluster.

Qty (25) 24" Artificial Magnolia Leaf Bush with Red Tips.

- 1.2.4 Zone E: Far End Garden Bed Near Black Fence: Artificial Plants 56" in overall height, which is the distance from the very bottom of the weighted base to the top of the foliage. This will feature UltraLeaf-IFR a proprietary, commercial grade, inherently fire- retardant foliage designed to meet ASTM-E84 and /or NFPA-701 fire-safety standards for indoor use.

1.2.4.01 78ft Length x 10ft Width Elements:

Qty (22) 56" Artificial Foxtail Onion Grass.

Qty (12) 3' Artificial Dracaena Reflexa Tree.

Qty (24) 45" Artificial Onion Grass Bush.

Qty (18) 40" Artificial Selloum Philodendron.

Qty (24) 32" Artificial Tree Fern Plant.

Qty (32) 26" Artificial Lavender Bush.

2.0 Photography

2.1 Photos for approval shall be provided by the contractor.

3.0 Onsite Assembly

3.1 Contractor will deliver all necessary materials to complete the Greenspace/Atrium project as specified.

4.0 BT 3rd Floor Greenspace/Atrium Plan:

Contractor personnel shall return VA Contractor ID badges to designated VA personnel before leaving the Medical Center.

- Drawings – If any departure from the contract drawings are deemed necessary by the Contractor, the details of such departure and the reasons therefore shall be submitted to the Contracting Officer for approval as soon as practical.
- Verification of Dimensions – The Contractor shall verify the dimensions of the rooms and shall advise the Contracting Officer of any discrepancy before performing any work.
- Smoking Policy. VAMC is a non-smoking facility. Smoking is not permitted.
- Infection Control. The Contractor shall abide by the procedures specified by the VA Infection Control Nurse in the Infection Control Risk Assessment (ICRA) for this project to prevent infection risks.