

DESIGN-BUILD



eProject# 1807261

Demolish Vacant BEQ Building 132H

Naval Station Great Lakes, IL

SUBMITTED BY:

Naval Facilities Engineering Systems Command
NAVFAC Mid-Atlantic, PWD Great Lakes, IL

PREPARED BY:

Project/Design Manager: Erica Schmidt

APPROVED BY:

For Commander, NAVFAC Midlant
Date: ~~03/04/2025~~ 02/27/2026 Addendum 01

1.0 Table of Contents (RFP Parts 2-6)

1. PART 2 – GENERAL REQUIREMENTS

- 01 14 00 WORK RESTRICTIONS
- 01 20 00 PRICE AND PAYMENT PROCEDURES
- 01 30 00 ADMINISTRATIVE REQUIREMENTS
- 01 31 23.13 20 ELECTRONIC CONSTRUCTION AND FACILITY SUPPORT CONTRACT MANAGEMENT SYSTEM
- 01 32 17.00 20 COST-LOADED NETWORK ANALYSIS SCHEDULES (NAS)
- 01 33 00 SUBMITTAL PROCEDURES
- 01 35 26 GOVERNMENTAL SAFETY REQUIREMENTS
- 01 45 00.05 20 DESIGN AND CONSTRUCTION QUALITY CONTROL
- 01 50 00 TEMPORARY CONSTRUCTION FACILITIES AND CONTROLS
- 01 57 19 TEMPORARY ENVIRONMENTAL CONTROLS
- 01 74 19 CONSTRUCTION WASTE MANAGEMENT AND DISPOSAL
- 01 78 00 CLOSEOUT SUBMITTALS

2. PART 3 – PROJECT PROGRAM

- CHAPTER 1. PROJECT DESCRIPTION
- CHAPTER 2. PROJECT OBJECTIVES **REV-ADDENDUM 01**
- CHAPTER 3. SITE ANALYSIS/ENVIRONMENTAL CONSIDERATIONS
- CHAPTER 4. BUILDING REQUIREMENTS
- CHAPTER 5. NOT USED
- CHAPTER 6. ENGINEERING SYSTEMS REQUIREMENTS

3. PART 4 – PERFORMANCE TECHNICAL SPECIFICATIONS

- F20 COMPLETE BUILDING DEMOLITION
- G10 SITE PREPARATION
- G20 SITE IMPROVEMENTS
- Z10 GENERAL PERFORMANCE TECHNICAL SPECIFICATION

4. PART 5 – PRESCRIPTIVE SPECIFICATIONS

- SECTION 02 41 00 DEMOLITION

5. PART 6 – ATTACHMENTS

General

- 01_ Permits Record of Decision (PROD)
- 02_ Base Access Forms: DON Local Population ID Card/Base Access Pass Registration & 2023 Statement of Purpose

Architectural Drawings

- 03_ A2.1 Level 1 Floor Plan (Partial)
- 04_ A2.2 Level 2 Floor Plan (Partial)
- 05_ A2.3 Level 3 Floor Plan (Partial)
- 06_ A2.4 Level 4 Floor Plan

07_A2.6_Level 1 Floor Plan (Partial)
08_A2.7_Level 2 Floor Plan (Partial)
09_A2.8_Level 3 Floor Plan (Partial)

Environmental

10_Contractor Guidance Manual - Construction Storm Water Management 24 JAN 2023
10a_Refrigerant Compliance Plan Naval Station Great Lakes (January 2025)

Utility Maps

11_Communication Ducts
12_Electrical Manholes and Ducts
13_Electric Feeder H52
14_UEM Fiber
15_Sanitary Sewer
16_Abandoned Steam
17_Street Lights
18_Potable Water

Templates

19_Asbestos Hazard Abatement Plan
20_Lead, Cadmium, Chromium Compliance Plan

1.0a Order of Precedence

In the event of conflict or inconsistency between any of the below described portions of the conformed contract, precedence must be given in the following order (descending order of precedence):

- (1) Standard Form 1442, Price Schedule, and Davis Bacon Wage Rates.
- (2) Part 1 - Contract Clauses.
- (3) Part 2 - General Requirements.
- (4) Part 3 - Project Program Requirements.
- (5) Part 6 - Attachments (excluding Concept Drawings).
- (6) Part 5 - Prescriptive Specifications exclusive of performance specifications.
- (7) Part 4 - Performance Specifications exclusive of prescriptive specifications.
- (8) Part 6 - Attachments (Concept Drawings).

PART TWO - GENERAL REQUIREMENTS

SECTION 01 14 00

WORK RESTRICTIONS
11/22, CHG 3: 08/24

PART 1 GENERAL

1.1 SUBMITTALS

Government approval is required for submittals with a "G" classification. Submittals not having a "G" classification are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

List of Contact Personnel

SD-07 Certificates

1.2 CONTRACTOR ACCESS AND USE OF PREMISES

1.2.1 Activity Regulations

Ensure that Contractor personnel employed on the Activity become familiar with and obey Activity regulations including safety, fire, traffic and security regulations. Keep within the limits of the work and avenues of ingress and egress. Wear appropriate personal protective equipment (PPE) in designated areas. Do not enter any restricted areas unless required to do so and until cleared for such entry. Ensure all Contractor equipment, include delivery vehicles, are clearly identified with their company name.

1.2.1.1 Subcontractors and Personnel Contacts

Provide a list of contact personnel of the Contractor and subcontractors including addresses and telephone numbers for use in the event of an emergency. As changes occur and additional information becomes available, correct and change the information contained in previous lists.

1.2.1.2 Installation Access

Obtain access to Navy installations through participation in the Defense Biometrics Identification System (DBIDS). Requirements for Contractor employee registration, and transition for employees currently under Navy Commercial Access Control System (NCACS), are available at <https://www.cnic.navy.mil/Operations-and-Management/Base-Support/DBIDS/>. No fees are associated with obtaining a DBIDS credential.

1.2.1.2.1 Registration for DBIDS

Registration for DBIDS is available at <https://www.cnic.navy.mil/Operations-and-Management/Base-Support/DBIDS/>. Procedure includes:

- a. Provide completed SECNAV FORM 5512/1 to the designated Trusted Agent. This form is available for download at <https://www.cnic.navy.mil/Operations-and-Management/Base-Support/DBIDS/>.

- b. Upon successful completion of the background check, the Government will complete the DBIDS enrollment process, which includes Contractor employee photo, fingerprints, base restriction and several other assessments.
- c. Upon successful completion of the enrollment process, the Contractor employee will be issued a DBIDS credential, and will be allowed to proceed to worksite.

1.2.1.2.2 DBIDS Eligibility Requirements

Throughout the length of the contract, the Contractor employee must continue to meet background screen standards. Periodic background screenings are conducted to verify continued DBIDS participation and installation access privileges. DBIDS access privileges will be immediately suspended or revoked if at any time a Contractor employee becomes ineligible.

An adjudication process may be initiated when a background screen failure results in disqualification from participation in the DBIDS, and Contractor employee does not agree with the reason for disqualification. The Government is the final authority.

1.2.1.2.3 DBIDS Notification Requirements

- a. Immediately report instances of lost or stolen badges to the Contracting Officer.
- b. Immediately collect DBIDS credentials and notify the Contracting Officer in writing under the following circumstances:
 - (1) An employee has departed the company without having properly returned or surrendered their DBIDS credentials.
 - (2) There is a reasonable basis to conclude that an employee, or former employee, might pose a risk, compromise, or threat to the safety or security of the Installation or anyone therein.

1.2.1.3 No Smoking Policy

Smoking is prohibited within and outside of all buildings on installation, except in designated smoking areas. This applies to existing buildings, buildings under construction and buildings under renovation. Discarding tobacco materials other than into designated tobacco receptacles is considered littering and is subject to fines. The Contracting Officer will identify designated smoking areas.

1.2.2 Working Hours

Regular working hours will consist of an 8-1/2 hour period, between 6:30 a.m. and 4:00 p.m., Monday through Friday, excluding Government holidays.

1.2.3 Work Outside Regular Hours

Work outside regular working hours requires Contracting Officer approval. Make application 15-calendar days prior to such work to allow arrangements to be made by the Government for inspecting the work in progress, giving the specific dates, hours, location, type of work to be performed, contract number and project title. Based on the justification provided, the

Contracting Officer may approve work outside regular hours. During periods of darkness, the different parts of the work must be lighted in a manner approved by the Contracting Officer. Make utility cutovers after normal working hours or on Saturdays, Sundays, and Government holidays unless directed otherwise.

1.2.4 Exclusionary Period

No work, exterior to the facility, may be performed during the period of 01 NOV to 01 APR, without prior written approval of the Contracting Officer. This period has not been considered in computing the time allowed for the performance of this contract.

1.2.5 Occupied Buildings

The Contractor will be working around existing, occupied buildings.

The existing buildings and their contents must be kept secure at all times. Provide temporary closures as required to maintain security as directed by the Contracting Officer.

Use water sprinkling, temporary enclosures, and/or other suitable methods to limit the amount of dust and dirt rising and scattering in the air.

1.2.6 Utility Cutovers and Interruptions

- a. Make utility cutovers and interruptions after normal working hours or on Saturdays, Sundays, and Government holidays. Conform to procedures required in paragraph WORK OUTSIDE REGULAR HOURS.
- b. Ensure that new utility lines are complete, except for the connection, before interrupting existing service.
- c. Interruption to water, sanitary sewer, storm sewer, telephone service, electric service, air conditioning, heating, fire alarm, and compressed air are considered utility cutovers pursuant to the paragraph WORK OUTSIDE REGULAR HOURS.
- d. Operation of Station Utilities: The Contractor must not operate nor disturb the setting of control devices in the station utilities system, including water, sewer, electrical, and steam services. The Government will operate the control devices as required for normal conduct of the work. The Contractor must notify the Contracting Officer giving reasonable advance notice when such operation is required.
- e. Connection to Existing Sanitary Sewer Line: Provide positive verification that the existing line conveys sanitary sewer; verify line is not incorrectly connected to a storm drain.

PART 2 PRODUCTS

Not used.

PART 3 EXECUTION

Not used.

-- End of Section --

SECTION 01 20 00

PRICE AND PAYMENT PROCEDURES

11/20, CHG 4: 08/24

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

U.S. ARMY CORPS OF ENGINEERS (USACE)

EP 1110-1-8

(2021) Engineering and Design --
Construction Equipment Ownership and
Operating Expense Schedule

1.2 SUBMITTALS

Government approval is required for submittals with a "G" classification. Submittals not having a "G" classification are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Schedule of Prices; G

1.3 SCHEDULE OF PRICES

1.3.1 Data Required

Within 15-calendar days of notice of award, prepare and deliver to the Contracting Officer's Representative (COR) a Schedule of Prices (construction Contract) as directed. Schedule of Prices must have cost summarized and totals provided for each construction category. Provide a detailed breakdown of the Contract price, giving quantities for each of the various kinds of work, unit prices, and extended prices. Indirect activities (e.g., meetings, presentations, submittals, surveys, haul road or storage yard maintenance, dust control, security) will not be cost loaded. Evenly distribute the costs across the associated construction activities. Contractor overhead and profit including salaries for field office personnel, if applicable, must be proportionately spread over all pay items and not included as individual pay items.

1.3.2 Payment Schedule Instructions

Payments will not be made until the Schedule of Prices has been submitted to and accepted by the COR (Construction Manager (CM)). For design phase progress payment(s), the Schedule of Prices from the Cost Loaded CPM must include detailed design activities and general (summarized) approach for the construction phase(s) of the project. The Schedule of Prices must be fully developed with detailed construction line items as design progresses. The complete design and construction Schedule of Prices must be submitted and accepted prior to starting construction work.

For Fast-Track or Critical Path Submittals of construction projects, the Schedule of Prices must include detailed design and construction line items for each fast-tracked/ critical path phase(s), submitted to and accepted by the Contracting Officer during the Post Award Kickoff Meetings and confirmed prior to starting construction work in that phase. Additionally, the Schedule of Prices must be separated as follows:

a. Primary Facilities Cost Breakdown:

Defined as work on the primary facilities out to the 5 foot line. Work out to the 5 foot line includes construction encompassed within a theoretical line 5 foot from the face of exterior walls and includes attendant construction, such as pad mounted HVAC cooling equipment, cooling towers, and transformers placed beyond the 5 foot line.

b. Supporting Facilities Cost Breakdown:

Defined as site work, including incidental work, outside the 5 foot line.

1.4 CONTRACT MODIFICATIONS

In conjunction with the Contract Clause DFARS 252.236-7000 Modification Proposals-Price Breakdown, and where actual ownership and operating costs of construction equipment cannot be determined from Contractor accounting records, base equipment use rates upon the applicable provisions of the EP 1110-1-8.

1.5 CONTRACTOR'S INVOICE AND CONTRACT PERFORMANCE STATEMENT

1.5.1 Content of Invoice

Requests for payment will be processed in accordance with the Contract Clause FAR 52.232-27 Prompt Payment for Construction Contracts and FAR 52.232-5 Payments Under Fixed-Price Construction Contracts. Invoices not completed in accordance with contract requirements will be returned to the Contractor for correction of the deficiencies. Include the documents listed below in the requests for payment.

- a. The Contractor's invoice, on NAVFAC Form 7300/30 furnished by the Government, showing in summary form, the basis for arriving at the amount of the invoice. Form 7300/30 must include certification by Quality Control (QC) Manager as required by the Contract.
- b. The Estimate for Voucher/ Contract Performance Statement on NAVFAC Form 4330/54 furnished by the Government. Use NAVFAC Form 4330, unless otherwise directed by the Contracting Officer, on NAVFAC Contracts when a Monthly Estimate for Voucher is required.
- c. Contractor's Monthly Estimate for Voucher and Contractors Certification (NAVFAC Form 4330) with Subcontractor and supplier payment certification. Other documents, including but not limited to, that need to be received prior to processing payment include the following submittals as required. These items are still required monthly even when a pay voucher is not submitted.
- d. Monthly Work-hour report.
- e. Updated Construction Progress Schedule and tabular reports required by

the contract.

- f. Contractor Safety Self Evaluation Checklist.
- g. Updated submittal register.
- h. Solid Waste Disposal Report.
- i. Certified payrolls.
- j. Updated testing logs.
- k. Other supporting documents as requested.

1.5.2 Submission of Invoices

Monthly invoices and supporting forms for work performed through the anniversary award date of the Contract must be submitted to the Contracting Officer within 5 calendar days of the date of invoice. For example, if Contract award date is the 7th of the month, the date of each monthly invoice must be the 7th and the invoice must be submitted by the 12th of the month.

1.6 PAYMENTS TO THE CONTRACTOR

Payments will be made on submission of itemized requests by the Contractor which comply with the requirements of this section, and will be subject to reduction for overpayments or increase for underpayments made on previous payments to the Contractor.

1.6.1 Obligation of Government Payments

The obligation of the Government to make payments required under the provisions of this Contract will, at the discretion of the Contracting Officer, be subject to reductions and suspensions permitted under the FAR and agency regulations including the following in accordance with FAR 32.103 Progress Payments Under Construction Contracts:

- a. Reasonable deductions due to defects in material or workmanship;
- b. Claims which the Government may have against the Contractor under or in connection with this Contract;
- c. Unless otherwise adjusted, repayment to the Government upon demand for overpayments made to the Contractor; and
- d. Failure to maintain accurate "as-built" or record drawings in accordance with FAR 52.236.21.

1.6.2 Payment for Onsite and Offsite Materials

Progress payments may be made to the Contractor for materials delivered on the site, for materials stored off construction sites, or materials that are in transit to the construction sites under the following conditions:

- a. FAR 52.232-5(b) Payments Under Fixed Price Construction Contracts.
- b. Materials delivered on the site, but not installed, and off-site materials to be considered for progress payment must be major high

cost, long lead, special order, or specialty items, not susceptible to deterioration or physical damage in storage or in transit to the construction site. Examples of materials acceptable for payment consideration include, but are not limited to, structural steel, non-magnetic steel, non-magnetic aggregate, equipment, machinery, large pipe and fittings, precast/prestressed concrete products, plastic lumber (e.g., fender piles/curbs), and high-voltage electrical cable. Materials not acceptable for payment include consumable materials such as nails, fasteners, conduits, gypsum board, glass, insulation, and wall coverings.

- c. Provide the Contracting Officer with documentation (e.g., Purchase Orders or Material Contracts) to justify payment for materials in advance of installation. When appropriate, include the Defense Priorities and Allocations System (DFAS) ratings (e.g., DX or DO) on purchase orders or material contracts to ensure timely delivery.
- d. Materials to be considered for progress payment prior to installation must be specifically and separately identified in the Contractor's estimates of work submitted for the Contracting Officer's approval in accordance with Schedule of Prices requirement of this Contract. Requests for progress payment consideration for such items must be supported by documents establishing their value (e.g., paid invoices) and that the title requirements of the clause at FAR 52.232-5 Payments Under Fixed-Price Construction Contracts have been met.
- e. Ensure materials are adequately insured and protected from theft and exposure. Provide insurance documentation (e.g., Builder's Risk Insurance) which covers the overall value of the materials to be paid in advance of installation.
- f. Provide a written consent from the surety company with each payment request for offsite materials.
- g. Materials to be considered for progress payments prior to installation must be stored either in Hawaii, Guam, Puerto Rico, or the Continental United States. Other locations are subject to written approval by the Contracting Officer.
- h. Materials in transit to the job site or storage site are not acceptable for payment.

PART 2 PRODUCTS

Not used.

PART 3 EXECUTION

Not used.

-- End of Section --

SECTION 01 30 00

ADMINISTRATIVE REQUIREMENTS

11/20, CHG 4: 08/24

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

U.S. ARMY CORPS OF ENGINEERS (USACE)

EM 385-1-1

(2024) Safety -- Safety and Occupational
Health (SOH) Requirements

1.2 SUBMITTALS

Government approval is required for submittals with a "G" classification. Submittals not having a "G" classification are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

View Location Map

Progress and Completion Pictures

Design Submittal Packaging

Performance Assessment Plan (PAP)

1.3 VIEW LOCATION MAP

Submit, prior to or with the first digital photograph submittals, a sketch or drawing indicating the required photographic locations. Update as required if the locations are moved.

1.4 PROGRESS AND COMPLETION PICTURES

Photographically document site conditions prior to start of construction operations. Provide monthly, and within one month of the completion of work, digital photographs, 1600x1200x24 bit true color minimum resolution in JPEG file format showing the sequence and progress of work. Take a minimum of 20 digital photographs each week throughout the entire project from a minimum of ten different viewpoints selected by the Contractor unless otherwise directed by the Contracting Officer. Submit with the monthly invoice two sets of digital photographs, each set on a separate compact disc (CD) or data versatile disc (DVD), cumulative of all photos to date. Indicate photographs demonstrating environmental procedures. Provide photographs for each month in a separate monthly directory and name each file to indicate its location on the view location sketch. Also provide the view location sketch on the CD or DVD as a digital file. Include a date designator in file names. Photographs provided are for unrestricted use by the Government.

1.5 MINIMUM INSURANCE REQUIREMENTS

Provide the minimum insurance coverage required by FAR 28.307-2 Liability, during the entire period of performance under this contract. Provide other insurance coverage as required by State law.

1.6 SUPERVISION

The Government reserves the right to remove and replace the Superintendent, Quality Control Manager, and/or the Site Safety Health Officer (SSHO) if their performance is deemed unsatisfactory by the Contracting Officer/Contracting Officer's Representative.

1.6.1 Superintendent Qualifications

Provide project superintendent with a minimum of 10 years experience in construction with at least 5 of those years as a superintendent on projects similar in size and complexity. The individual must be familiar with the requirements of EM 385-1-1 and have experience in the areas of hazard identification and safety compliance. The individual must be capable of interpreting a critical path schedule and construction drawings. The qualification requirements for the alternate superintendent are the same as for the project superintendent. The Contracting Officer may request proof of the superintendent's qualifications at any point in the project if the performance of the superintendent is in question.

1.6.2 Minimum Communication Requirements

Have at least one qualified superintendent, or competent alternate, capable of reading, writing, and conversing fluently in the English language, on the job-site at all times during the performance of Contract work. In addition, if a Quality Control (QC) representative is required on the Contract, then that individual must also have fluent English communication skills.

1.6.3 Duties

The project superintendent is primarily responsible for managing subcontractors and coordinating day-to-day production and schedule adherence on the project. The superintendent is required to attend Red Zone meetings, partnering meetings, and quality control meetings. The superintendent or qualified alternative must be on-site at all times during the performance of this contract until the work is completed and accepted.

1.6.4 Non-Compliance Actions

The Project Superintendent is subject to removal by the Contracting Officer for non-compliance with requirements specified in the contract and for failure to manage the project to ensure timely completion. Furthermore, the Contracting Officer may issue an order stopping all or part of the work until satisfactory corrective action has been taken. No part of the time lost due to such stop orders is acceptable as the subject of claim for extension of time for excess costs or damages by the Contractor.

1.7 PRECONSTRUCTION MEETING

Upon completion of design and design acceptance by the government, prior to

commencing any work at the site, coordinate with the Contracting Officer a time and place to meet for the Preconstruction Meeting. The purpose of this meeting is to discuss and develop a mutual understanding of the administrative requirements of the Contract including but not limited to: daily reporting, invoicing, value engineering, safety, base-access, outage requests, hot work permits, schedule requirements, quality control, schedule of prices or earned value report, shop drawings, submittals, cybersecurity, prosecution of the work, government acceptance, final inspections and contract close-out. Contractor must present and discuss their basic approach to scheduling the construction work and any required phasing.

1.7.1 Attendees

Contractor attendees must include the Project Manager, Superintendent, Site Safety and Health Officer (SSHO), Quality Control Manager and major subcontractors.

1.8 POST AWARD KICKOFF (PAK) MEETING

Immediately after award, coordinate with the Contracting Officer a time and place for the PAK Meeting. The PAK meeting must be held within 35 calendar days after contract award and prior to commencing work. If mutually agreed upon by the Contractor and the Government, the PAK Meeting may be held concurrently with the Design Presentation/Design Development Meeting or Concept Design Workshop (CDW) whichever is required.

1.8.1 PAK Meeting Outcomes

- a. Integrate the Contractor and all client representatives into the project team.
- b. Achieve consensus from the project team on any issues and concerns with the Contractor's technical proposal and the User's functional requirements. Confirm the design is within the project budget.
- c. Review the administrative requirements of the contract that are critical during the design phase.
- d. Establish clear lines of communication and points of contact for Government and Contractor team members.
- e. Obtain an acceptable conceptual design including floor and site plans, signed by the client, Contractor and other key team members.
- f. Review the project design schedule and design package requirement, design submittal packaging, and preliminary construction schedule in accordance with Section 01 32 17.00 20 COST-LOADED NETWORK ANALYSIS SCHEDULES (NAS). Discuss design milestones and events that will be included in the Quality Control Communication Plan.
- g. Establish clear expectations and schedules for facility turnover, providing DD Form 1354 asset management records, eOMSI submittals, Guiding Principle Validation, Third Party Certification (if applicable), and training of Government maintenance personnel.
- h. Establish procedure for design packages reviews, Contractor's resolution to comments, and Government's role in review of packages.

1.8.2 PAK Meeting Contractor Attendees

The following Contractor personnel must attend the PAK meeting; Project Manager, Project Scheduler, Lead Designer-of-Record (DOR), Design Staff responsible for each architectural/engineering discipline when facility design is discussed, Superintendent, QC Manager, and the DQC Manager. Optional attendees include: Principal, Assistant Project Manager, major subcontractors and specialized supplemental QC personnel.

1.9 FACILITY TURNOVER PLANNING MEETINGS (Red Zone Meetings)

Meet with the Government to identify strategies to ensure the project is carried to expeditious closure and turnover to the Client. Start planning the turnover process at the Pre-Construction Conference meeting with a discussion of the Red Zone process and convene at regularly scheduled NAVFAC Red Zone Meetings beginning at approximately 75 percent of project completion. Include the following in the facility Turnover effort:

1.9.1 Red Zone Checklist

- a. Contracting Officer's Technical Representative (COTR) will provide the Contractor a copy of the Red Zone Checklist template.
- b. Prior to 75 percent completion, modify the Red Zone Checklist template by adding or deleting critical activities applicable to the project and assign planned completion dates for each activity. Submit the modified Red Zone Checklist to the Contracting Officer. The Contracting Officer may request additional activities be added to the Red Zone Checklist at any time as necessary.

1.9.2 Meetings

- a. Conduct regular Red Zone Meetings beginning at approximately 75 percent project completion, or three to six months prior to Beneficial Occupancy Date (BOD), whichever comes first.
- b. The Contracting Officer will establish the frequency of the meetings, which is expected to increase as the project completion draws nearer. At the beginning, Red Zone meetings may be every two weeks then increase to weekly towards the final month of the project.
- c. Using the Red Zone Checklist as a Plan of Action and Milestones (POAM) and basis for discussion, review upcoming critical activities and strategies to ensure work is completed on time.
- d. During the Red Zone Meetings discuss with the COTR any upcoming activities that require Government involvement.
- e. Maintain the Red Zone Checklist by documenting the actual completion dates as work is completed and update the Red Zone Checklist with revised planned completion dates as necessary to match progress. Distribute copies of the current Red Zone Checklist to attendees at each Red Zone Meeting.

1.10 PARTNERING

To most effectively accomplish this Contract, the Contractor and Government must form a cohesive partnership with the common goal of drawing on the

strength of each organization in an effort to achieve a successful project without safety mishaps, conforming to the Contract, within budget and on schedule. The partnering team must consist of personnel from both the Government and Contractor including project level and corporate level leadership positions. Key Personnel from the supported command, end user, NAVFAC, PWD, FEAD, Contractor, key subcontractors and the Designer of Record are required to participate in the Partnering process.

1.10.1 Team-Led (Informal) Partnering

- a. The Contracting Officer will coordinate the initial Team-Led (Informal) Partnering Session with key personnel of the project team, including Contractor and Government personnel. The Partnering Session will be co-led by the Government Construction Manager and Contractor's Project Manager.
- b. The Initial Team-led Partnering session may be held concurrently with the [Post-Award Kickoff](#) meeting. Partnering sessions will be held at a location mutually agreed to by the Contracting Officer and the Contractor, typically at a conference room on-base or at the Contractor's temporary trailer.
- c. The Initial Team-Led Partnering Session will be conducted and facilitated using electronic media (a video and accompanying forms) provided by Contracting Officer.
- d. The Partners will determine the frequency of the follow-on sessions.
- e. Participants will bear their own costs for meals, lodging and transportation associated with Partnering.

1.11 [PERFORMANCE ASSESSMENT PLAN \(PAP\)](#)

The [Performance Assessment Plan \(PAP\)](#) will be used to document design innovation and budget management, provide performance feedback to the Contractor, and as a basis for interim and final evaluations in the Contractor Performance Appraisal Reporting System (CPARS) on-line database.

It is the intent of the Government to establish the PAP based on tangible, measurable indicators of outstanding contractor performance, and on commitments made in the Contractor's proposal. The initial PAP may be found on the NAVFAC Design-Build Request for Proposal Website in RFP PART 6 Attachments. Review and finalize the initial PAP during the Partnering Session. During the initial Partnering Session, the Government, the Contractor, the Designer-of-Record, and the Client will establish the PAP. Following the establishment of the PAP, the Contractor will present it, with his input, for update and discussion at projects meetings which discuss project performance. Submit an updated PAP on a monthly basis with the invoice for that period as a minimum.

1.12 MOBILIZATION

Contractor shall mobilize to the jobsite within 30 calendar days of final building design approval. Mobilize is defined as having equipment AND having a physical presence of at least one person from the contractor's team on the jobsite.

PART 2 PRODUCTS

Not used.

PART 3 EXECUTION

Not used.

-- End of Section --

SECTION 01 31 23.13 20

ELECTRONIC CONSTRUCTION AND FACILITY SUPPORT CONTRACT MANAGEMENT SYSTEM (eCMS)
08/23, CHG 1: 02/24

PART 1 GENERAL

1.1 CONTRACT ADMINISTRATION

Utilize the Naval Facilities Engineering Systems Command's (NAVFAC's) Electronic Construction and Facility Support Contract Management System (eCMS) for the transfer, sharing, and management of electronic technical submittals and documents. The web-based eCMS is the designated means of transferring technical documents between the Contractor and the Government. Paper media or email submission, including originals or copies, of the documents are not permitted unless identified within the contract.

All government contracting specialist/officer, legal, and command communications will remain the same.

1.2 USER PRIVILEGES

The Contractor's key staff may be provided access to eCMS. Contact the COR for eCMS account access. Project roles and system roles will be established to control each user's menu, application, and software privileges, including the ability to create, edit, or delete objects. Additional project roles may be assigned for workflow. The COR makes the final decision on roles for the project. User's ability to view, edit documents may be lowered at the discretion of the COR.

Only one eCMS user account is required regardless of the number of user's projects. Notify the COR within seven calendar days if a contractor user is no longer associated with company or project so they can remove them from any open record and inactivate them from the project.

1.2.1 eCMS Subcontractor Users

If the contractor's user is a subcontractor, the subcontractor must be registered under the name of their company and email. For example it is common for contractors to contract Quality Control Managers. The QC Manager's account should be under their company's name and email reducing the number of eCMS accounts required.

For Design Build, the contractor's Designer of Record Architectural Engineer will be given a single account. Only one account per AE is required. The role of the AE is determined by the project role assigned by the COR. The contractor is to request their AE staff be placed into the AE-KTR-DOR project role.

1.2.2 Users with Multiple Roles

Users may have multiple roles associated with their account within eCMS. Roles are used in workflow. When a user is added to the project, they will be assigned the default role when the user was created. Contact the COR to change or add roles to the user for the project.

1.2.3 Loss of Privilege

Users may lose privilege to access eCMS at the discretion of the Contracting Officer. The eCMS is a collaborative system that allows flexibility of use and does not restrict all inappropriate user actions. User activities are logged into eCMS in visible and background data collection. Users found to use eCMS in an inappropriate action may have their eCMS access revoked. Examples include, but not limited to, fraudulent representations, sharing user accounts with others, and changing approved records without the consent of the COR. Depending on the severity of the infraction, the users can lose eCMS access for a period of time, permanently for the project, or lose eCMS access for any project. The contractor may appeal the suspension in writing to the contracting officer within 14 calendar days of notice. The appeal must identify the infraction, supporting information, and steps to ensure the infraction will not happen in the future.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" classification. Submittals not having a "G" classification are for Contractor Quality Control approval. Submit the following in accordance with 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

List of Contractor's Personnel; G

For Division 1 government approved Pre-Construction submittals, combine into a single Pre-Construction Submittal Package. Annotated with SD Type of SD-01. Pre-Construction submittal package approval date will be used as a KPI.

1.4 SYSTEM REQUIREMENTS AND CONNECTIVITY

1.4.1 General

NAVFAC eCMS requires a web-browser (platform-neutral) and Internet connection. For best results, recommend using browser in InPrivate/Incognito mode; Internet speeds greater than 40mbps when uploading files, computers with high RAM and Solid State Drives, "White List" eCMS website, Zip or Split files for better uploading. Non-NAVFAC Users are not to use VPN when using eCMS per NAVFAC IT.

The use of eCMS is required by the Contractor and all associated costs and time necessary to utilize eCMS will be borne by the Contractor with no allowance for time extensions and at no additional cost to the government.

1.4.2 Contractor Personnel List

Within 20 calendar days of contract award, provide to the Contracting Officer a [list of Contractor's personnel](#) who will have the responsibility for the transfer, sharing and management of electronic [design](#), submittals, RFIs, daily reports, and other files and will require access to the eCMS. Project personnel roles which must be filled as applicable in the eCMS, include, at a minimum, the Contractor's Project Manager (KTR-PM), [Designer of Record](#) (AE-KTR-DOR), Superintendent (KTSUPT), Quality Control (QC) Manager (KTR-QC), Principal (KTR-PRIN), and Site Safety and Health Officer (KTR-SSHO). Notify the COR immediately of any personnel changes to the

project. The Contracting Officer reserves the right to perform a security check on all potential users.

Internal design deliberations under a D-B contract are managed outside of eCMS. Besides the D-B DOR Representative, D-B design team members are neither required nor encouraged to create user accounts in eCMS. Users are highly recommended to take eCMS live or online training prior to use. See <https://www.navfac.navy.mil/Business-Lines/Design-and-Construction/About-Us/Design-and-Construction-Documents/Electronic-Construction-Management-System-eCMS/> for eCMS useful information

Provide the following information:

Company Name

Name (First, Last)

Email Address

Project Role (CQM, SSHO, Superintendent, CM, PM, Principal)

Existing or New eCMS User

1.5 SECURITY CLASSIFICATION

In accordance with Department of Navy guidance, all military construction contract data are unclassified, unless specified otherwise by a properly designated Original Classification Authority (OCA) and in accordance with an established Security Classification Guide (SCG). Refer to the project's OCA when questions arise about the proper classification of information.

In conformance with the Freedom of Information Act (FOIA), DoD INSTRUCTION 5200.48 CONTROLLED UNCLASSIFIED INFORMATION (CUI), and DoD requirements, any unclassified project documentation uploaded into the eCMS must be designated either "U - UNCLASSIFIED" (U) or "CUI - CONTROLLED UNCLASSIFIED INFORMATION" (CUI). NAVFAC eCMS must only be used for the transaction of unclassified information associated with construction projects. Controlled Unclassified Identification (CUI) documents may be loaded into eCMS with the appropriate markings.

1.5.1 Markings on CUI Documents

Contractor's proprietary information, or documents determined by the originator in accordance with CUI guidance, should be marked CUI. Proprietary information not marked CUI can be released under the Freedom of Information Act (FOIA). Apply the appropriate markings before any document is uploaded into eCMS. Markings are not required on Unclassified U documents.

1.6 eCMS UTILIZATION

Establish, maintain, and update data and documentation in the eCMS throughout the duration of the contract. Utilize eCMS to transfer all submittals, RFIs, daily reports, and other files required by contract to be forwarded to the government.

Full eCMS use is required. All Submittals/Information to use eCMS Modules including, but not limited to, RFIs, Daily Reports, Meeting Minutes, Communications, Issues, Punch Lists, Checklists, and Flysheets, unless

otherwise directed by the COR or Contracting Officer.

1.6.1 Restricted Information

Personally Identifiable Information (PII) transmittal such as credit card, driver's license, passport, social security, and payroll number are not permitted in eCMS. Name, address, and email are permitted. Pre-negotiation information such as cost estimates that require formal negotiations are not allowed. For example, proposed changes over the SAP level of \$250k require formal negotiations. Cost estimates for LEAN, ULTRA LEAN, and Design Changes under the SAP level are at the discretion of the COR's or Contract Specialist/Officer's direction. The eCMS must only be used for the transaction of unclassified information associated with construction projects. Controlled Unclassified Identification (CUI) documents may be loaded into eCMS with the appropriate markings. Uploading of files directly into the Documents folder is not allowed. All documents must be uploaded using an eCMS module.

1.6.2 Naming Convention for Files

Titles of files uploaded are to be descriptive of the purpose and content of the file. For example RFI_ROOF_Leak.doc or for submittals, SUB_LIGHT_FIXTURE.pdf. Titles of file to be uploaded must only contain uppercase letters, lowercase letters, numbers, hyphens (-), underscores (_) and periods (.). Use of any other characters is not allowed and may create an error. When practicable, adding the record number to the title is desired. For example RFI_XYZ12345_ROOF_Leak.doc. Uploading files with the same title will create a new revision in eCMS. Original revision is Rev 0, the first revision is Rev 1. Uploaded files are to use the default file location regardless of the module used unless directed by the COR.

Table 1 also identifies which eCMS application is to be used in the transmittal of data (these are subject to change based on the latest software configuration).

Table 1 - Project Documentation Types

SUBJECT/NAME	REMARKS	eCMS APPLICATION
As-Built Drawings	Locations of sensitive areas must be labeled as either "Controlled Area" or "Restricted Area" and may be shown on unclassified documents with the approval from Site Security Manager	Submittals
Building Information Modeling (BIM)	Locations of sensitive areas must be labeled as either "Controlled Area" or "Restricted Area" and may be shown on unclassified documents with the approval from Site Security Manager	Submittals
Construction Permits	Refer to rules of the issuing activity, state or jurisdiction	Submittals

SUBJECT/NAME	REMARKS	eCMS APPLICATION
Construction Schedules (Activities and Milestones)		Submittals
Construction Schedules		Submittals
Construction Schedules (3-Week Look ahead)	Import the schedule file into the scheduling application, and select "Approve" to establish a new schedule baseline	Meeting Minutes
DD 1354 Transfer of Real Property	When applicable, required for final billing.	Submittals
Daily Production Reports	Provide weather conditions, crew size, man-hours, equipment, and materials information	Daily Report
Daily Quality Control (QC) Reports	Provide QC Phase, Definable Features of Work Identify visitors	Daily Report
Designs and Specifications	Locations of sensitive areas must be labeled as either "Controlled Area" or "Restricted Area" and may be shown on unclassified documents with the approval from Site Security Manager	Submittals
Environmental Notice of Violation (NOV), Corrective Action Plan	Refer to rules of the issuing activity, state or jurisdiction	Submittals
Environmental Protection Plan (EPP)		Submittals
Invoice (Supporting Documentation)	Applies to supporting documentation only. Invoices are submitted in Wide-Area Workflow (WAWF)	Submittals
Jobsite Documentation, Bulletin Board, Labor Laws, SDS	Redact any PII information when loaded into eCMS	Submittals
Meeting Minutes		Meeting Minutes

SUBJECT/NAME	REMARKS	eCMS APPLICATION
Modification Documents	Provide final modification documents for the project. Upload into Modifications RFPs folder	Communications
Operations & Maintenance Support Information (OMSI/eOMSI), Facility Data Worksheet	1. Locations of sensitive areas must be labeled as either "Controlled Area" or "Restricted Area" and may be shown on unclassified documents with the approval from Site Security Manager 2. Design reviews will be performed in existing "Dr Checks"	Submittals
Photographs	Subject to base/installation restrictions	Submittals
QCM Initial Phase Checklists		Meeting Minutes or Checklists
QCM Preparatory Phase Checklists		Meeting Minutes or Checklists
Quality Control Plans		Submittals
QC Certifications		Submittals
QC Punch List		Punch Lists
Red-Zone Checklist		Punch List or Checklists
Rework Items List		Punch Lists
Request for Information (RFI) Post-Award		RFIs
Safety Plan		Submittals
Safety - Activity Hazard Analyses (AHA)		Submittals
Safety - Mishap Reports		Daily Report

SUBJECT/NAME	REMARKS	eCMS APPLICATION
Shop Drawings	Locations of sensitive areas must be labeled as either "Controlled Area" or "Restricted Area" and may be shown on unclassified documents with the approval from Site Security Manager	Submittals
Storm Water Pollution Prevention (Notice of Intent - Notice of Termination)	Refer to rules of the issuing activity, state or jurisdiction	Submittals
Submittals and Submittal Register		Submittals
Testing Plans, Logs, and Reports		Submittals
Training/Reference Materials		Submittals
Training Records (Personnel)	Redact any PII information if storing in eCMS	Submittals
Utility Outage/Tie-In Request/Approval		Submittals
Warranties/BOD Letter		Submittals
Quality Assurance Reports		Checklists (Government initiated)
Non-Compliance Notices		Non-Compliance Notices (Government initiated)
Other Government-prepared documents		GOV ONLY
Letters to government contracting, claims, REAs, and other contracting officer communications	eCMS is not the primary tool to use in contracting officer communications. eCMS can only store documents or letters after the submission to the contracting officer is made.	Communications

SUBJECT/NAME	REMARKS	eCMS APPLICATION
All Othere Documents	Refer to FOIA guidelines and contact the FOIA official to determine whether exemptions exist	As applicable

1.6.3 RFIs Module

Create contractor RFIs using eCMS RFIs module. The contractor must confirm the numbering convention with the COR if different than eCMS default.

If the government (GOV) Response has "No" Cost or Schedule Impact, this reply is given with the expressed understanding that it does not constitute a basis for any change in the amount or time of subject contract. Information provided in this response does not authorize work not currently included in the contract. If GOV Response is "Yes" or "Potentially" then this response may require a change to the contract. If the contractor disagrees with either the government's No Cost determination or No Schedule impact determination, or both, the contractor has 14 calendar days to notify the COR and Contracting Officer in writing.

1.6.4 Submittals Module

Create contractor submittals using eCMS Submittals module. The contractor must confirm the numbering convention with the COR if different than eCMS default.

1.6.5 Submittal Packages Module

Create submittal packages using the eCMS Submittal Packages module in lieu of or in addition to Related Objects. Submittal Packages track completion of the packaged submittals and is used in NAVFAC HQ's KPIs.

1.6.6 Communications Module

Create communications using the eCMS Communications module. The Communications module is used to create or document communications that are not a part of other eCMS modules. Use of Communications module will memorialize information into an eCMS record file. The following are Types of Communications:

Email

Memo to File

Face to Face

Telephone

Web Collaboration

Photos

Other Documents

Other

Unless directed by the COR, upload documents or files that do not have a corresponding eCMS module. Choose "Photos" Type for Photos and "Other Documents" for all other documents.

1.6.7 Issues Module

Create or respond to issues using the eCMS Issues module. Respond to CPARS issues using the Issues module.

1.6.8 Meeting Minutes Module

Create or respond to Meeting Minutes using the eCMS Meetings module.

Document required contractual meetings. Dates of meetings are used in NAVFAC KPIs. Minimum meetings in eCMS include the following:

- Post Award Kickoff (PAK)

- Pre-construction (Pre Con)

- Initial and Preparatory Three Phases of Control

- Quality Control (QC)

1.6.9 Potential Change Items Module

Not used.

1.6.10 Daily Report Module

Create Daily Reports using the eCMS Daily Report Module. The contractor must confirm the numbering convention with the COR if different than eCMS default.

1.6.11 Punchlists Testing Logs (Legacy)

Punchlist Testing Logs is a legacy program that is being replaced by the Punch Lists Module. This module is to be used for reference of past projects. Use the Punch Lists Module for all future work.

1.6.12 Punch Lists Module

The eCMS Punch Lists module is useful more than just for Punchlists. The module includes the capability of batch editing, create items from Optical Character Recognition (OCR) plans, assign tasks and track completion of individual items.

Create the following using the Punch Lists module:

- Rework Items List

- DFOW List

- Punch-Out Inspection

Pre-Final Punchlist Inspection

Final Punchlist Inspection

Testing Logs

1.6.13 FWD UltraLean COAR RFP Module

Not Used.

1.6.14 Non-Compliance Notices (NCN) Module

Respond to Non-Compliance Notices listed in the Non-Compliance Notices module.

1.6.15 Checklists

Use Checklist listed in the contractor's eCMS menu and as directed by the COR. Checklists capture data and is used in dashboards and KPIs.

1.6.15.1 Partnering Team Health Survey Checklist

Contractor must use the eCMS checklist to document the partnering team health survey. Partnering Team Health Survey is in accordance with the Partnering Specification of this contract.

1.6.16 Flysheets

Use Flysheets listed in the contractor's eCMS menu, if available, and as directed by the COR. Flysheets allow the contractor to print out information from other systems and upload into eCMS. The eCMS will use OCR to capture the information as data. Flysheets capture data and used in dashboards and KPIs.

1.6.17 eCMS Outage

In the case where eCMS is unavailable for 8 hours or more, paper or email may be used in the interim to maintain project schedule.

Once the system is operational, all final records are required to be recreated using the appropriate module. Subject/title of the record to include the type of record i.e., RFI/Submittal/Daily Report/Communication/Other, the identification number(s), and the statement "Processed Outside of eCMS". Example, "RFI 001 Processed Outside of eCMS".

1.6.18 User Account Activity

NAVFAC eCMS captures user data and activities that are directly related to the user's account. The user agrees through the use of eCMS, their account activities will be captured and can be displayed on eCMS printed reports.

1.7 QUALITY ASSURANCE

Requested Government response dates on Submittals must be in accordance with the terms and conditions of the Contract unless previously agreed by the COR. Requesting response dates earlier than the required review and response time, without concurrence by the Government COR, may be cause for rejection.

Incomplete submittals will be rejected without further review and must be resubmitted. Required Government response dates for resubmittals must reflect the date of resubmittal, not the original submittal date.

All submittals and associated attachments must be transmitted to the Government via the COR. Transmittals are no longer required when using eCMS since approval status is tracked on the submittal. Transmittal forms can be attached to submittals if approved by the COR. Submittals requiring government approval are "Transmitted For" "Approval". Submittals requiring contractor approved submittals, including those designated for Contractor Quality Control approval or Information Only, are "*Transmitted For" "Information Only" in the Submittal Module. Provide and sign the QC certification or approving statement on the attachment per submittal specification section. When Submittal Packages are required, use eCMS Submittal Packages after creating individual submittals. Importing Submittals from the Submittal Register is optional. Contact the COR for the data conversion requirements.

PART 2 PRODUCTS

Not Used.

PART 3 EXECUTION

Not Used.

-- End of Section --

SECTION 01 32 17.00 20

COST-LOADED NETWORK ANALYSIS SCHEDULES (NAS)

11/23, CHG 1: 08/24

PART 1 GENERAL

1.1 DEFINITIONS

The cost-loaded Network Analysis Schedule (NAS) is a tool to manage the project, both for Contractor and Government activities. The NAS is also used to report progress, evaluate time extensions, and provide the basis for progress payments.

For consistency, when scheduling software terminology is used in this section, the terms in Primavera's scheduling programs are used.

1.2 SCHEDULE REQUIREMENTS PRIOR TO THE START OF WORK

1.2.1 Preliminary Scheduling Meeting

Before preparation of the Project Baseline Schedule, and prior to the start of work, meet with the Contracting Officer to discuss the proposed schedule and the requirements of this section. Propose projected data dates for monthly update schedules for the project and incorporate each monthly update submittal into submittal register. Discuss required forms, terminology, and submittal requirements of this section and other requirements related to schedule management for this contract. Use the NAVFAC-provided Preliminary Scheduling Meeting Guideline in the completion of the intended mutual understanding.

1.2.2 Project Baseline Schedule

1.2.2.1 Baseline NAS

Submit the **Baseline NAS** at the Post-Award Kickoff (PAK) Meeting or within 30 calendar days after contract award whichever occurs first. The Baseline schedule must include detailed design activities and a general approach to construction, including summary activities for required phasing and definable areas. Summary Construction activities must not exceed duration of 60 calendar days, unless approved otherwise by Contracting Officer. Data date must be set to contract award date and no progress recorded for any activity.

Only bonds and the required Preliminary Scheduling Meeting may be recorded as complete prior to acceptance of the Baseline NAS. The acceptance of a Baseline NAS is a condition precedent to:

- a. The Contractor submitting the first design submittal.
- b. Processing Contractor's invoices(s) other than that for the bonds.

1.2.2.2 Post-Award Kickoff (PAK) Meeting and Baseline NAS

Present the Draft Baseline NAS at the PAK Meeting. Be prepared to discuss the schedule logic emphasizing how the schedule satisfies the design package requirements and incorporates the required government review periods for each design submittal.

1.2.2.3 Construction Baseline

Submit the detailed Construction Baseline NAS prior to the pre-final design submittal. The pre-final design submittal will not be reviewed until a Construction Baseline NAS is submitted.

The acceptance of the Construction Baseline NAS is a condition precedent to:

- a. The contractor starting demolition work or construction stage(s) of the contract.
- b. Processing Contractor's invoices for demolition or construction activities.
- c. Review of any construction phase schedule updates.

Submittal of the Construction Baseline NAS must be the Contractor's certification that the submitted schedule meets the requirements of the Contract Documents, and represents the Contractor's plan on how the work will be accomplished. Provide all items listed in paragraph REQUIRED TABULAR REPORTS AND NATIVE P6 XER FILES with baseline NAS submittal.

1.3 WEEKLY LOOK AHEAD SCHEDULE

1.3.1 Weekly CQC Coordination and Production Meeting

Submit the first look ahead schedule 30 days after contract award and continue to submit weekly until contract completion.

Transmit the Weekly Look Ahead Schedule Submittal to the Contracting Officer on the first day of the current week that the look ahead schedule covers and at least one working day prior to Quality Control meetings or as agreed to by Contracting Officer. Contractor is required to provide all attendees at meetings that require discussion of the schedule.

1.3.2 Weekly Look Ahead Schedule Requirements

Prepare and issue a Three-Week Look Ahead schedule to provide a more detailed day-to-day plan of upcoming work identified on the Project Network Analysis Schedule. Requirements include:

- a. For each Look Ahead schedule activity, identify parent NAS activity number(s). The parent NAS activity is the activity in the NAS that would incorporate the Look Ahead schedule activity requirement and scope of work.
- b. Update schedule each week to show the planned work for the current and following three-week period. Also include previous week, as-built work, showing actual start and finish dates.
- c. Include upcoming outages, closures, preparatory meetings, and initial meetings, testing and inspections.
- d. Clearly identify longest path activities on the Weekly Look Ahead Schedule. Include a key or legend that distinguishes longest path activities. Include all Longest Path activity NAS start/finish dates exceeded and occurring during this period.

- e. Identify responsibility for each activity.
- f. The detail work plans are to be bar chart type schedules, derived from but maintained separately from the Project NAS on an electronic spreadsheet program and printed on 11 by 17 inch sheets as directed by the Contracting Officer.
- g. Activities must not exceed 5 working days in duration and have sufficient level of detail to assign crews, tools and equipment required to complete the work.
- h. Lookahead activities are not limited to only onsite work. Include but not limited to submittal, offsite fabrication, and procurement activities if needed to ensure longest path is maintained. Include design activities and coordination when part of scope.
- i. Upload Lookahead to eCMS as a submittal by the date and time required by contracting officer.

1.4 MONTHLY NETWORK ANALYSIS

Submittal of Monthly NAS is the Contractor's certification that the submitted schedule meets the requirements of the Contract Documents and represents the Contractor's plan on how the work will be accomplished. Provide all items listed in paragraph REQUIRED TABULAR REPORTS AND NATIVE P6 XER FILES with the monthly NAS submittal.

1.4.1 Monthly Network Analysis Updates

- a. Regardless of whether an invoice is being submitted monthly, or no progress in the schedule occurred, an updated schedule (or with new data date) must be submitted monthly to the Government. The Monthly NAS update must be submitted within 10 calendar days of the data date.
- b. Regardless of whether a baseline or other schedule is submitted and accepted, an updated schedule must be submitted monthly to the Government. Monthly updates submitted before the baseline being accepted will be considered as (interim and for information only) submittal.
- c. Provide all items listed in paragraph REQUIRED TABULAR REPORTS AND NATIVE P6 XER FILES, with each monthly NAS update submittal.
- d. Meet with Government representative(s) at monthly intervals to review and agree on the information presented in the updated project schedule. The submission of an accepted, updated schedule to the Government is a condition precedent to the processing of the Contractor's invoice.
- e. Activity progress must incorporate as-built events as they occurred and correspond to records including but not limited to submittals and daily production and quality control reports.
- f. Software Settings: Handle schedule calculations and Out-of-Sequence progress (if applicable) through Retained Logic, not Progress Override. Show all activity durations and float values in days. Show activity progress using Remaining Duration. Set default activity type to "Task Dependent".

- g. Update schedule must reflect current Contract Completion Date and contract value in accordance with all conformed contract modifications issued prior to data date of NAS update.

1.4.2 As-Built Schedule

As a condition precedent to the release of retention and making final payment, submit an "As-Built Schedule," as the last schedule update showing all activities at 100 percent completion. This schedule must reflect the exact manner in which the project was actually constructed.

1.5 CORRESPONDENCE AND TEST REPORTS

Reference Schedule activity IDs that are being addressed in each correspondence (e.g., letters, Requests for Information (RFIs), e-mails, meeting minute items, Production and QC Daily Reports, material delivery tickets, photographs) and test report (e.g., concrete, soil compaction, weld, pressure).

1.6 ADDITIONAL SCHEDULING REQUIREMENTS

Other specification sections may include additional scheduling requirements, including systems to be inspected, tested and commissioned, and submittal procedures. Those schedule requirements must be incorporated into the NAS schedule.

1.7 SUBMITTALS

Government approval/acceptance is required for submittals with a "G" classification. Submittals not having a "G" classification are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Baseline NAS; G

Construction Baseline NAS; G

Designated Project Scheduler; G

SD-07 Certificates

Weekly Look Ahead Schedule

Monthly Network Analysis Updates; G

SD-11 Closeout Submittals

As-Built Schedule; G

1.8 SOFTWARE

Prepare and maintain project schedules using Primavera P6 software in a version compatible with Government's current version. Importing data into P6 using data conversion techniques or third party software is cause for rejection of the submitted schedule. Schedules with Performing Organizational Breakdown Structure (POBS) data is cause for rejection.

1.9 DESIGNATED PROJECT SCHEDULER

Within 30 calendar days of contract award, submit to the Contracting Officer for approval an individual who will serve as the Designated Project Scheduler. Include a copy of the candidate's resume with qualifications. The Contracting Officer may remove the Designated Project Scheduler, and require replacement, if the scheduler does not effectively fulfill their duties in accordance with the contract requirements. Payment request will not be processed without an approved Designated Project Scheduler.

1.9.1 Qualifications

The Designated Project Scheduler must have prepared and maintained at least three previous construction schedules, of similar size and complexity to this contract, using Primavera P6.

1.9.2 Duties

Duties of the Designated Project Scheduler include to be actively involved and be responsible for the following::

- a. Prepare Baseline NAS.
- b. Prepare monthly schedule updates.
- c. Prepare tabular reports.
- d. Prepare Time Impact Analysis (TIA) as necessary.
- e. Provide certification that NAS and TIA submittals conform to the contract requirements.

1.10 NETWORK SYSTEM FORMAT

Prepare the schedule in accordance with the following Primavera P6 settings and parameters. Deviation from these settings and parameters, without prior consent of the Contracting Officer, is cause for rejection of schedule submission.

1.10.1 Schedule Activity Properties and Level of Detail

1.10.1.1 Activity Identification and Organization

- a. Identify **design and** construction activities planned for the project and other activities that could impact project completion if delayed in the NAS.
- b. Each activity must have a unique name.
- c. Identify administrative type activity/milestones, including all pre-construction submittal and permit requirements prior to demolition or construction stage.
- d. Include times for procurement, Contractor quality control and construction, acceptance testing and training in the schedule.
- e. Include the Government approval time required for the submittals that require Government Approval prior to construction.

- f. Create separate activities for each Phase, Area, Floor Level and Location the activity is occurring.
- g. Do not use construction category activity to represent non-work type reference (e.g., Serial Letter, Request for Information) in NAS. Place Non-work reference within the P6 activity details notebook.

Activity categories included in the schedule are specified below.

1.10.1.2 Activity Logic

- a. With the exception of the Contract Award and Contract Completion Date (CCD) milestone activities, activity must not be open-ended; each activity must have at least one predecessor and at least one successor.
- b. Activities must not have open start or open finish (dangling) logic.
- c. Do not use lead or lag logic without Contracting Officer prior approval.
- d. Minimize redundant logic ties.
- e. Once an activity exists on the schedule it must not be deleted or renamed to change the scope of the activity and must not be removed from the schedule logic without approval from the Contracting Officer.
 - (1) While an activity cannot be deleted, where said activity is no longer applicable to the schedule, but must remain within the logic stream for historical record, change the activity original and remaining duration to zero and clearly label "(NO LONGER REQUIRED)" after the activity name. Actual finish date for activity that falls behind the data date. Redistribute accordingly any remaining budget associated with that activity, to other remaining appropriate activity.
 - (2) Document any such change in the activities' "Notebook," including a date and explanation for the change.
 - (3) The ID number for a "NO LONGER REQUIRED" activity must not be re-used for another activity.

1.10.1.3 Longest Path Activity Baseline Limitation

For P6 settings, critical activities are defined as being on the Longest Path. Longest Path (Critical) Activities must not make up more than 30 percent of all activity within the Construction Baseline Schedule.

1.10.1.4 Assigned Calendars

All NAS activity must be assigned calendars that reflect required and anticipated non-work days.

1.10.1.5 Activity Categories

1.10.1.5.1 Design Activities

Design activities must include design decision points and design submittal packages, including critical path submittals for Fast Tracked Phases. Review times for design development packages must be included in the

schedule. Refer to Section 01 33 10.05 20 DESIGN SUBMITTAL PROCEDURES, for specific requirements.

1.10.1.5.2 Pre-construction Activities

Examples of pre-construction activities include, but are not limited to, bond approval, permits, pre-construction submittals and approvals. Include pre-construction activities that are required to be completed prior to the Contractor starting the demolition or construction stage of work.

1.10.1.5.3 Procurement Activities

Examples of procurement activities include, but are not limited to: Material/equipment submittal preparation, submittal and approval of material/equipment; material/equipment fabrication and delivery, and material/equipment on-site. As a minimum, separate procurement activities must be provided for critical items, long lead items, items requiring Government approval and material/equipment procurement for which payment will be requested in advance of installation. Show each delivery with relationship tie to the Construction Activity specifically for the delivery.

1.10.1.5.4 Government Activities

Government and other agency activities that could impact progress must be clearly identified. Government activities include, but are not limited to; Government approved submittal reviews, Government conducted inspections/tests, environmental permit approvals by State regulators, utility outages, Design Start, Construction Start (including Design/Construction Start for each Fast-Track Phase, and delivery of Government Furnished Material/Equipment.

1.10.1.5.5 Construction Quality Management (CQM) Activities

The Preparatory and Initial Phase meetings for each Definable Feature of Work identified in the Contractor's Quality Control Plan must be included in the Three-Week Look Ahead Schedule. Preparatory and Initial phase meetings are not required in the NAS, but can be represented by a start milestone linked to successor parent Construction Activity. The Follow-up Phase must be represented by the Construction Activities themselves in the NAS.

1.10.1.5.6 Construction Activities

On-site construction activities that are the responsibility of the Contractor or Contractor's subcontractors must not have a duration in excess of 20 working days without prior approval by the Contracting Officer. Contractor activities must be driven by calendars that reflect Saturdays, Sundays and all Federal Holidays as non-work days, unless otherwise defined in this contract. Federal Holidays are as defined in 5 USC 6103.

1.10.1.5.7 Turnover and Closeout Activities

Include activities or milestones for items on the NAVFAC Red Zone Checklist/POAM that are applicable to this project. As a minimum, include required Contractor testing, required Government acceptance inspections on equipment, Pre-Final Inspection, Punch List Completion, Final Inspection and Acceptance. Add an unconstrained start milestone for the initial NAVFAC Red Zone - Facility Turnover Planning Meeting at approximately 75

percent construction contract completion or six months prior to Contract Completion Date (CCD), whichever is sooner. Include a separate NAVFAC Red Zone - Facility Turnover Planning Meeting Milestone for each phase if the contract requires construction to be completed in phases.

1.10.1.6 Contract Milestones and Constraints

1.10.1.6.1 Project Start Date Milestones

Include as the first activity on the schedule a start milestone titled, "Contract Award", which must have a Mandatory Start constraint equal to the Contract Award Date.

1.10.1.6.1.1 Design Phase Completion Milestone

Include an unconstrained finish milestone on the schedule titled, "Design Phase Completion". Design Phase Completion is defined as the point in time when all design requirements are complete and approved. Duration for Government review and approval must be included as predecessor activities to Design Phase Completion.

1.10.1.6.1.2 Post-Award Kickoff (PAK) meeting Milestone

Include an unconstrained finish milestone on the schedule titled, "Post-Award Kickoff Meeting". The Post Award Kickoff Meeting may be a single day, or it may range over several days. The intent is to cover all PAK topics, including Partnering and Concept Design Workshop (if required) in one continuous session.

1.10.1.6.2 Preconstruction Submittals Finish Milestone

Include an unconstrained finish milestone on the schedule titled, "Preconstruction Submittals". This milestone is complete when all required preconstruction submittals have been reviewed and approved by the Government.

1.10.1.6.3 Contractor Mobilization Finish Milestone

Include an unconstrained finish milestone on the schedule titled, "Contractor Mobilization".

1.10.1.6.4 NAVFAC Red Zone - Facility Turnover Planning Meeting Milestones

See paragraph TURNOVER AND CLOSEOUT ACTIVITIES above.

1.10.1.6.5 Substantial Completion Milestone

Include an unconstrained finish milestone on the schedule titled "Substantial Completion." Substantial Completion is defined as the point in time the Government would consider the project ready for beneficial occupancy wherein by mutual agreement of the Government and Contractor, Government use of the facility is allowed while construction access continues in order to complete remaining items (e.g., punch list and other close out submittals). Include a separate Substantial Completion Milestone for each phase if the contract requires construction to be completed in phases.

1.10.1.6.6 DD-1354 Finish Milestone

Add unconstrained finish milestone, titled "DD-1354" and scheduled 30 calendar days prior to Substantial Completion, whenever a Form DD-1354 is required in accordance with Section 01 20 00 PRICE AND PAYMENT PROCEDURES. Include a separate DD-1354 Finish Milestone for each phase if the contract requires construction to be completed in phases.

1.10.1.6.7 Projected Completion Milestone

Include an unconstrained finish milestone on the schedule titled "Projected Completion." Projected Completion is defined as the point in time all contract requirements are complete and verified by the Government with a successful Final Inspection in accordance with Section 01 45 00 QUALITY CONTROL. This milestone must have the Contract Completion Date (CCD) milestone as its only successor.

1.10.1.6.8 Contract Completion Date (CCD) Milestone

Last schedule entry must be an unconstrained finish milestone titled "Contract Completion (CCD: DD-MM-YY)." DD-MM-YYYY is the current contract completion date at data date, day-month-year corresponding to P6 Must Finish By Date. NAS milestone updates of Project Completion finish date for longest path must reflect calculated float as positive or negative based on CCD. Calculation of schedule updates must be such that if the finish of the "Projected Completion" milestone falls after the contract completion date, then negative float is calculated on the longest path. If the finish of the "Projected Completion" milestone falls before the contract completion date, the float calculation must reflect positive float on the longest path.

1.10.1.6.9 Additional Milestones

Provide up to 5 additional milestones as required by Contracting Officer.

1.10.1.7 Work Breakdown Structure & Activity Code

At a minimum, establish a Work Breakdown Structure (WBS) and provide activity codes identified as follows:

1.10.1.7.1 Work Breakdown Structure (WBS)

Group all activities and milestones within appropriate WBS elements/levels including, at a minimum, the following:

a. Project Milestones:

- (1) Management Milestones
- (2) Project Administrative Meetings
- (3) Permits
- (4) Design Phase
- (5) Submittals and Reviews

b. Pre-Construction Phase:

- (1) Submittals and Reviews
- (2) Procurement
- (3) Mobilization
- c. Construction Phase: Create multiple elements/levels in accordance with project specific definable features of work including in WBS descending order as follows:
 - (1) General Area
 - (a) Type of Work Item
 - 1. Location
- d. Project Closeout: Include activity items such as, but not limited to, Punchlist, Demobilization, O&M, As-built Drawings, Training, and As-built NAS.
- e. Modifications: Create Conformed and Non-Conformed elements/levels under Modification WBS. Create multiple elements/levels as the project progresses identified by issue and Fragnet placed in Conformed for modifications issued prior data date, or Non-Conformed for issues not modified to contract prior data date.
- f. Removed Activity: Activity is "removed" by remaining within logic sequence, eliminating duration and adding "(NO LONGER REQUIRED)" after Activity Name in Activity Table.

1.10.1.7.2 Responsibility Code

Use "RESP" for Activity Code Name. All activities in the project schedule must be identified with the resource for completing the task. Activities must not belong to more than one responsible party.

1.10.1.7.3 Activity Category Code

Use "CAT" for Activity Code Name for the following Project Level activity codes:

- a. Assign "PROC" value to Procurement type activity
- b. Assign "PRE-CON" value to Pre-construction activity
- c. Assign "CONS" value to Construction type activity
- d. Assign "TEST" value to dedicated testing type activities
- e. Assign "CX" value to dedicated Commissioning type activities
- f. Assign "CLOS" value to dedicated Close Out type activity
- g. Assign "OTHR" to other activity not otherwise designated
- h. Assign "DSGN" value to Design type activity

1.10.1.8 Adverse Weather Lost Work Days

Assign the Weather Calendar to any activity that could be impacted by adverse weather. The Contracting Officer will issue a modification in accordance with the contract clauses, giving the Contractor a time only extension for the difference of days between the anticipated and actual adverse weather delay if the number of actual adverse weather delay days exceeds the number of days anticipated for the month in which the delay occurs and the adverse weather delayed activities are on the longest path to contract completion in the period when delay occurred. A lost workday due to weather conditions is defined as a day in which the Contractor cannot work at least 50 percent of the day on the impacted activity. Impacts resulting from adverse weather must be documented in Narrative Report for the month that it occurred.

Make changes to P6 project calendars to reflect as-built conditions where work occurred where originally anticipated as non-work days, and where work did not occur (lost work day).

1.10.1.9 Cost Loading

The Project Network Analysis Schedule (NAS) must be cost-loaded and will provide the basis for progress payments. Earned Value Reports must be derived from and correspond to cost loaded NAS. Use the Critical Path Method (CPM) and the Precedence Diagram Method (PDM) to satisfy time and cost applications.

Sum of all costs assigned to activities must equal the current contract value as of the data date of the baseline or update schedule. Activity cost loading must be without front-end loading. Provide additional documentation if requested by the Contracting Officer.

1.10.1.9.1 Cost Loading Activities

- a. Cost load construction activities. Define construction activities as on-site work activities that can be traced directly to the construction, alteration, demolition, repair of a project facility, infrastructure, or sitework.
- b. Assign costs for materials which payment will be requested in advance of installation, including their quantities, to their respective procurement activities that were approved by the Contracting Officer. Assign labor costs, including their quantities, for material and equipment paid for after installation to their respective construction activities.
- c. Costs for mobilization will not be paid as individual pay items with the exception of batch plant set-up, mobilization of dredging equipment or other similar labor-intensive situations. If payment for mobilization costs are approved, assign costs for demobilization activities. The value of demobilization activities must not be less than 40 percent of the total costs for mobilization/demobilization activities. If not approved as a separate line item, evenly disperse over construction activities the costs for mobilization and demobilization.
- d. The value of commissioning, testing, and closeout WBS section may not be less than 10 percent of the total costs for procurement and construction activities.

- e. ALL activities assigned Government responsibility will have Zero Cost. No contractor cost should be assigned to an activity designated as a Government responsibility.
- f. Do not include field overhead positions as individual cost loaded activities. Evenly disperse indirect costs (e.g., meetings, presentations, submittals, surveys, haul road or storage yard maintenance, dust control, security) and profit to construction activities assigned to the Construction Phase WBS level.

1.10.1.9.2 Partial Payment

Breakdown unit of measure and cost must be defined within P6 Activity Detail Expenses for partial payment of any cost loaded activity. Lump sum cost loaded activity will not be partially paid.

1.10.2 Schedule Software Settings and Restrictions

- a. Activity Constraints: Date/time constraint(s), other than those required by the contract, are not allowed unless accepted by the Contracting Officer. Identify any constraints proposed and provide an explanation for the purpose of the constraint in the Narrative Report as described in paragraph REQUIRED TABULAR REPORTS.
- b. Default Progress Data Disallowed: Actual Start is date work begins on activity with intent to pursue work to substantial completion. Actual Finish is date work is substantially complete to point where successor activity can begin. Actual dates on the CPM schedule must correspond with activity dates reported on the Contractor Quality Control and Production Reports.
- c. At a minimum, include the following settings and parameters in P6 Schedule preparation:
 - (1) General: Define or establish Calendars and Activity Codes at the "Project" level, not the "Global" level.
 - (2) Admin Drop-Down Menu, Admin Preferences, Time Periods Tab:
 - (a) Set time periods for P6 to 8.0 Hours/Day, 40.0 Hours/Week, 172.0 Hours/Month and 2000.0 Hours/Year.
 - (b) Use assigned calendar to specify the number of work hours for each time period: Must be checked.
 - (3) Admin Drop-Down Menu, Admin Preferences, Earned Value Tab:
 - (a) Technique for computing performance percent complete: Use "Activity percent Complete"
 - (b) Technique for computing Estimate to Complete: Use "PF = 1".
 - (c) Earned Value Calculation: Use "Budgeted values with current dates".
 - (4) Project Level, Dates Tab:
 - (a) Set "Must Finish By" date to "Contract Completion Date", and

set "Must Finish By" time to 05:00pm.

(5) Project Level, Defaults Tab:

- (a) Duration Type: Set to "Fixed Duration & Units".
- (b) Percent Complete Type: Set to "Physical".
- (c) Activity Type: Set to "Task Dependent".
- (d) Calendar: Set to "Standard 5 Day Workweek". Calendar must reflect Saturday, Sunday and all Federal holidays as non-work days. Alternative calendars may be used with Contracting Officer approval.

(6) Project Level, Calculations Tab:

- (a) Default Price/Unit for activities without resource or role Price/Units: Set to "\$1/h".
- (b) Activity percent complete based on activity steps: Must be Checked.
- (c) Link Budget and At Completion for not started activities: Must be Checked.
- (d) Reset Remaining Duration and Units to Original: Must be Selected.
- (e) Subtract Actual from At Completion: Must be Selected.
- (f) Recalculate Actual units and Cost when duration percent complete changes: Must be Checked.
- (g) Update units when costs change on resource assignments: Must be Unchecked.
- (h) Link Actual to Date and Actual This Period Units and Cost: Must be Checked.

(7) Project Level, Settings Tab:

- (a) Define Critical Activities: Check "Longest Path".

(8) Work Breakdown Structure Level, Earned Value Tab:

- (a) Technique for Computing Performance Percent Complete: "Activity percent complete" is selected.
- (b) Technique for Computing Estimate to Complete (ETC): "PF = 1" is selected.

1.10.3 Required Tabular Reports and Native P6 XER Files

Include the following reports with the Baseline, Monthly Update and any other required schedule submittals:

- a. Time Scaled Logic Schedule

- b. Provide formatted 11 by 17-inch Time-scaled Logic Schedule in color and landscape-oriented with each schedule submittal. Clearly show activities on the longest path setting Gantt chart longest path activity bars to red. Group activities by WBS and sort by finish date in ascending order. Include the following information in column form for each activity and include accompanying Gantt chart:

- (1) Activity ID
- (2) Activity Name
- (3) Original Duration
- (4) Remaining duration
- (5) Physical Percent Complete
- (6) Start Date
- (7) Finish Date
- (8) Total Float
- (9) Project-level Calendar

- c. Previous Monthly Update Comparison Time Scaled Logic Schedule (Submit with all Monthly Update Schedule Submittals.)

- d. Provide formatted 11 by 17-inch Time-scaled Logic Schedule in color and landscape-oriented with each monthly update schedule submittal. Clearly show activities on the current month longest path setting Gantt chart longest path activities bars to red. Show previous month activities as yellow bars and previous month milestones in yellow within Gantt chart. Sort by finish date in ascending order. Filter activities for longest path. Maintain and assign the accepted previous month update or the accepted baseline schedule for the first update submittal as the baseline and primary baseline in P6 before printing the schedule. Include the following information in column form for each activity and include accompanying Gantt chart:

- (1) Activity ID
- (2) Activity Name
- (3) Original Duration
- (4) Current Month Remaining Duration
- (5) Current Month Start Date
- (6) Previous Month Update Start Date (BL Project Start)
- (7) Start Date Delta between Current Month and Previous Month
(Variance - BL Project Start Date)
- (8) Current Month Finish Date
- (9) Previous Month Finish Date (BL Project Finish)

(10) Finish Date Delta between Current Month and Previous Month
(Variance - BL Project Start Date)

(11) Current Month Total Float

- e. P6 native XER file: Include the back-up native .xer program file compatible with the current Government version of Primavera P6. Each native schedule file must have a unique file name to include project name and data date using (yyyy-mm-dd) convention. Each native schedule must have a unique Project ID and Project Name.
- f. Log Report: P6 Scheduling/Leveling Report.
- g. Narrative Report: Identify and justify:

(1) Provide Project Summary Data in format below:

- (a) Data Date _____
- (b) Award Date: _____
- (c) Original Project Duration: _____ days post Award Date
- (d) Current Project Duration: _____ days post Award Date
- (e) Time percent elapsed: _____ percent at data date
- (f) Original CCD: _____
- (g) Current CCD: _____ (thru MOD _____)
- (h) Anticipated CCD: _____ (____ calendar days early/late)
- (i) Original Contract Value: \$_____
- (j) Current Contract Value: \$_____
- (k) Invoiced Amount: \$_____ (____ percent)
- (l) Cost Growth: _____ percent
- (m) Schedule Growth: _____ percent
- (n) There are a total of _____ activities, _____ activities complete (____ percent), _____ activities in progress (____ percent), _____ activities not started (____ percent). Of the in progress and not started activities; _____ (____ percent) are on the longest path. The longest path has duration of _____ calendar days from data-date to anticipated project completion.

(2) Progress made in each area of the project;

(3) Longest Path;

(4) Date/time constraint(s), other than those required by the contract

(5) Listing of all changes made between the previous schedule and current updated schedule include: added or deleted activities,

original and remaining durations for activities that have not started, logic (sequence constraint lag/lead), milestones, planned sequence of operations, longest path, calendars or calendar assignments, and cost loading;

- (6) Any decrease in previously reported activity Earned Amount;
 - (7) Pending items and status thereof, including permits, changes orders, and time extensions;
 - (8) Status of Contract Completion Date and interim milestones;
 - (9) Status of Projected Completion Milestone and account of difference in calendar days between previous update Projected Completion Milestone
 - (10) Current and anticipated delays listing Activity Names and IDs for impacted activities (describe cause of delay and corrective actions(s) and mitigation measures to minimize);
 - (11) Description of current and potential future schedule problem areas.
 - (12) Identification of any weather and restricted lost time as compared to anticipated weather for the month and anticipated restricted days for which the update is submitted. Impacts resulting from adverse weather must be documented in tabular form showing the calendar month (or billing period) with the days on which construction activity incurred Lost Work Days due to adverse weather. In narrative form, describe the adverse weather cause such as precipitation measurement, temperature, wind or other influencing factors, and why work was impacted. Describe the construction activity(s) that was (were) scheduled, impacted.
- h. Each entry in the narrative report must cite the respective Activity ID and Activity Name, the date and reason for the change, and description of the change.
 - i. Earned Value Report: Derive from and correspond to P6 cost loaded schedule. List all activities having a budget amount cost loaded. Compile total earnings on the project from notice to proceed to current progress payment request. Show current budget, previous physical percent complete, to-date physical percent complete, previous earned value, to-date earned value, cost this period and cost to complete on the report for each activity.
 - j. Schedule Variance Control (SVC) Diagram: With each schedule submission, provide a SVC diagram showing 1) A Cash Flow Curve indicating planned project cost based on each of projected early and projected late activity finish dates and 2) one curve for Earned Value to-date. Revise Cash Flow Curves when the contract is modified, or as directed by the Contracting Officer Include a legend on report clearly indication 3 curves: early finish, late finish, and earned-value to date.
 - k. Use the following settings in Activity Usage Profile Options:
 - (1) In the Data section, under Display, the radio box for Cost must be selected.

- (2) In the Data section, under Filter for Bars/Graphs, the checkbox for Total must be checked.
- (3) In the Show Bars/Curves section:
 - (a) Under the By Date column, the checkboxes for Baseline, Actual and Remaining Late must be checked. The checkboxes for Budgeted and Remaining Early must be unchecked.
 - (b) Under the Cumulative column, the checkboxes for Baseline, Actual and Remaining Late must be checked. The checkboxes for Budgeted and Remaining Early must be unchecked.
 - (c) Set the color for Baseline to green.
 - (d) Set the color for Actual to blue.
 - (e) Set the color for Remaining Late to red.
- (4) In the Show Earned Value Curves section, the checkboxes for Planned Value Cost, Earned Value Cost and Estimate at Completion must be unchecked.
- l. Logic Diagram showing timescale from data date to 60 days after data date with filter for longest path. Leave Group By selection blank and sort by finish date in ascending order.
- m. Baseline or Monthly Update Checklist as applicable completed and certified by Qualified Scheduler. Baseline Project Schedule and Monthly Update Schedule Checklists can be found on the Whole Building Design Guide website at <https://www.wbdg.org/ffc/dod/unified-facilities-guide-specifications-ufgs/ufgs-01-32-17-00-20>
- n. Screen shot PDF of Primavera P6 Time Periods Settings referenced in paragraph SCHEDULE SOFTWARE SETTINGS AND RESTRICTIONS, list item c.(2): ADMIN DROP-DOWN MENU, ADMIN PREFERENCES, TIME PERIODS TAB
- o. Screen shot PDF of Primavera P6 Earned Value Settings referenced in paragraph SCHEDULE SOFTWARE SETTINGS AND RESTRICTIONS, list item c.(3): ADMIN DROP-DOWN MENU, ADMIN PREFERENCES, EARNED VALUE TAB

1.11 CONTRACT MODIFICATION

1.11.1 Time Impact Analysis (TIA)

Submit a Time Impact Analysis with each cost and time proposal for a proposed change. TIA must illustrate the influence of each change or delay on the Contract Completion Date or milestones. No time extensions will be granted nor delay damages paid unless a delay occurs which consumes all available Project Float, impacts the longest path, and extends the Projected Completion beyond the Contract Completion Date.

- a. Each TIA must be in both narrative and schedule form. The narrative must:
 - (1) . Define the scope and conditions of the change;

- (2) . Provide start and finish dates of impact;
 - (3) . Successor(s) and predecessor(s) activities to impact period;
 - (4) . Responsible party;
 - (5) . Describe how the impact originated;
 - (6) . How it impacts the schedule's longest path.
- b. The schedule submission must consist of three native XER files:
- (1) Fragnet used to define the scope of the changed condition
 - (2) Most recent accepted schedule update as of the time of the impact start date. Update this schedule to show all activity progress as of the time of the impact start date. The impact start date is identified as the time when an existing activity is impeded for either starting or finishing.
 - (3) The impacted schedule that has the Fragnet inserted in the updated schedule and the schedule "run" so that the new completion date is determined.
- c. For claimed as-built project delay, the inserted Fragnet TIA method must be modified to account for as-built events known to occur after the data date of schedule update used. Updated schedules for periods following the impact start date will be used to evaluate how the project progressed (as-built) through the finish of impact. Impact to longest path must be determined for each following update period.
- d. All TIAs must include any mitigation, and must determine the apportionment of the overall delay assignable to each individual delay. Apportionment must provide identification of delay type and classification of delay by compensable and non-compensable events. The associated narrative must clearly describe analysis methodology used, and the findings in a chronological listing beginning with the earliest delay event.
- (1) Identify and classify types of delay defined as follows:
 - (a) Force majeure delay (e.g., weather delay): Any delay event caused by something or someone other than the Government or the Contractor, or the risk of which has not been assigned solely to the Government or the Contractor. If the force majeure delay is on the longest path, in absence of other types of concurrent delays, the Contractor is granted an extension of contract time, classified as a non-compensable event.
 - (b) A Contractor-delay: Any delay event caused by the Contractor, or the risk of which has been assigned solely to the Contractor. If the contractor-delay is on the longest path, in absence of other types of concurrent delays, Contractor is not granted extension of contract time, and classified as a non-compensable event. Where absent other types of delays, and having impact to project completion, Contractor must provide to Contracting Officer a Corrective Action Plan identifying plan to mitigate delay.

- (c) A Government-delay: Any delay event caused by the Government, or the risk of which has been assigned solely to the Government. If the Government-delay is on the longest path, in absence of other types of concurrent delays, the Contractor is granted an extension of contract time, and classified as a compensable event.
 - (2) Functional concurrency must be used to analyze concurrent delays, where: separate delay issues delay project completion, do not necessarily occur at same time, rather occur within same monthly schedule update period at minimum, or within same as-built period under review. If a combination of functionally concurrent delay types occurs, it is considered Concurrent Delay, which is defined in the following combinations:
 - (a) Government-delay concurrent with contractor-delay: excusable time extension, classified non-compensable event.
 - (b) Government-delay concurrent with force majeure delay: excusable time extension, classified non-compensable event.
 - (c) Contractor-delay concurrent with force majeure delay: excusable time extension, classified non-compensable event.
 - (3) Pacing delay reacting to another delay (parent delay) equally or more critical than paced activity must be identified prior to pacing. Contracting Officer will notify Contractor prior to pacing. Contractor must notify Contracting Officer prior to pacing. Notification must include identification of parent delay issue, estimated parent delay time period, paced activity(s) identity, and pacing reason(s). Pacing Concurrency is defined as follows:
 - (a) Government-delay concurrent with contractor-pacing: excusable time extension, classified compensable event.
 - (b) Contractor-delay concurrent with Government-pacing: inexcusable time extension, classified non-compensable event
- e. Submit electronic file containing the narrative and the source schedule files used in the time impact analysis.

1.12 PROJECT FLOAT

Project Float is the length of time between the Contractor's Projected Completion Milestone and the Contract Completion Date. Project Float available in the schedule will not be for the exclusive use of either the Government or the Contractor.

The use of Resource Leveling is prohibited. Techniques used for the purpose of artificially adjusting activity durations to consume float and influence longest path are prohibited.

PART 2 PRODUCTS

Not used.

PART 3 EXECUTION

Not used.

-- End of Section --

SECTION 01 33 00

SUBMITTAL PROCEDURES

08/18, CHG 4: 02/21

PART 1 GENERAL

1.1 DEFINITIONS

1.1.1 Submittal Descriptions (SD)

Submittal requirements are specified in the technical sections. Examples and descriptions of submittals identified by the Submittal Description (SD) numbers and titles follow:

SD-01 Preconstruction Submittals

Submittals that are required prior to or commencing with the start of work on site.

Preconstruction Submittals include schedules and a tabular list of locations, features, and other pertinent information regarding products, materials, equipment, or components to be used in the work.

Certificates Of Insurance

Surety Bonds

List Of Proposed Subcontractors

List Of Proposed Products

Baseline Network Analysis Schedule (NAS)

Submittal Register

Schedule Of Prices Or Earned Value Report

Accident Prevention Plan

Work Plan

Quality Control (QC) plan

Environmental Protection Plan

SD-05 Design Data

Design calculations, mix designs, analyses or other data pertaining to a part of work.

SD-06 Test Reports

Report signed by authorized official of testing laboratory that a material, product or system identical to the material, product or system to be provided has been tested in accord with specified requirements. Unless specified in another section, testing must have been within three years of date of contract award for the project.

Report that includes findings of a test required to be performed on an actual portion of the work or prototype prepared for the project before shipment to job site.

Report that includes finding of a test made at the job site or on sample taken from the job site, on portion of work during or after installation.

Investigation reports

Daily logs and checklists

Final acceptance test and operational test procedure

SD-07 Certificates

Statements printed on the manufacturer's letterhead and signed by responsible officials of manufacturer of product, system or material attesting that the product, system, or material meets specification requirements. Must be dated after award of project contract and clearly name the project.

Document required of Contractor, or of a manufacturer, supplier, installer or Subcontractor through Contractor. The document purpose is to further promote the orderly progression of a portion of the work by documenting procedures, acceptability of methods, or personnel qualifications.

Confined space entry permits

Text of posted operating instructions

SD-11 Closeout Submittals

Documentation to record compliance with technical or administrative requirements or to establish an administrative mechanism.

Special requirements necessary to properly close out a construction contract. For example, Record Drawings and as-built drawings. Also, submittal requirements necessary to properly close out a major phase of construction on a multi-phase contract.

1.1.2 Approving Authority

Office or designated person authorized to approve the submittal.

1.1.3 Work

As used in this section, on-site and off-site construction required by contract documents, including labor necessary to produce submittals, construction, materials, products, equipment, and systems incorporated or to be incorporated in such construction. In exception, excludes work to produce SD-01 submittals.

1.2 SUBMITTALS

Government approval is required for submittals with a "G" classification.
Submittals not having a "G" classification are for Contractor Quality

Control approval. Submit the following in accordance with Section 01 33 00
SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Submittal Register; G

1.3 SUBMITTAL CLASSIFICATION

1.3.1 Government Approved (G)

Within the terms of the Contract Clause SPECIFICATIONS AND DRAWINGS FOR CONSTRUCTION, submittals are considered to be "shop drawings."

1.3.2 For Information Only

Submittals not requiring Government approval will be for information only. Within the terms of the Contract Clause SPECIFICATIONS AND DRAWINGS FOR CONSTRUCTION, they are not considered to be "shop drawings."

1.4 FORWARDING SUBMITTALS REQUIRING GOVERNMENT APPROVAL

As soon as practicable after award of contract, and before procurement or fabrication, forward to the Contracting Officer's Representative/Construction Manager submittals required in the technical sections of this specification, including shop drawings, product data and samples. In addition, forward a copy of the submittals to the Contracting Officer.

1.4.1 O&M Data

Submit data specified for a given item within 30 calendar days after the item is delivered to the contract site.

In the event the Contractor fails to deliver O&M data within the time limits specified, the Contracting Officer may withhold from progress payments 50 percent of the price of the items to which such O&M data apply.

1.5 PREPARATION

1.5.1 Transmittal Form

Transmit each submittal, except sample installations and sample panels to the office of the approving authority using the transmittal form prescribed by the Contracting Officer. Include all information prescribed by the transmittal form and required in paragraph IDENTIFYING SUBMITTALS. Use the submittal transmittal forms to record actions regarding samples.

1.5.2 Identifying Submittals

The Contractor's Quality Control Manager must prepare, review and stamp submittals, including those provided by a subcontractor, before submittal to the Government.

Identify submittals, except sample installations and sample panels, with the following information permanently adhered to or noted on each separate component of each submittal and noted on transmittal form. Mark each copy of each submittal identically, with the following:

- a. Project title and location
- b. Construction contract number
- c. Dates of the drawings and revisions
- d. Name, address, and telephone number of Subcontractor, supplier, manufacturer, and any other Subcontractor associated with the submittal.
- e. Section number of the specification by which submittal is required
- f. Submittal description (SD) number of each component of submittal
- g. For a resubmission, add alphabetic suffix on submittal description, for example, submittal 18 would become 18A, to indicate resubmission
- h. Product identification and location in project.

1.5.3 Submittal Format

1.5.3.1 Format of SD-01 Preconstruction Submittals

When the submittal includes a document that is to be used in the project, or is to become part of the project record, other than as a submittal, do not apply the Contractor's approval stamp to the document itself, but to a separate sheet accompanying the document.

Provide data in the unit of measure used in the contract documents.

1.5.3.2 Format for SD-02 Shop Drawings

Provide shop drawings not less than 8 1/2 by 11 inches nor more than 30 by 42 inches, except for full-size patterns or templates. Prepare drawings to accurate size, with scale indicated, unless another form is required.

Ensure drawings are suitable for reproduction and of a quality to produce clear, distinct lines and letters, with dark lines on a white background.

- a. Include the nameplate data, size, and capacity on drawings. Also include applicable federal, military, industry, and technical society publication references.
- b. Dimension drawings, except diagrams and schematic drawings. Prepare drawings demonstrating interface with other trades to scale. Use the same unit of measure for shop drawings as indicated on the contract drawings. Identify materials and products for work shown.

Submit an electronic copy of drawings in PDF format and native electronic format.

1.5.3.2.1 Drawing Identification

Include on each drawing the drawing title, number, date, and revision numbers and dates, in addition to information required in paragraph IDENTIFYING SUBMITTALS.

Number drawings in a logical sequence. Each drawing is to bear the number of the submittal in a uniform location next to the title block. Place the Government contract number in the margin, immediately below the title block, for each drawing.

Reserve a blank space, no smaller than two (2) inches on the right-hand side of each sheet for the Government disposition stamp.

1.5.3.3 Format of SD-03 Product Data

Present product data submittals for each section. Include a table of contents, listing the page and catalog item numbers for product data.

Indicate, by prominent notation, each product that is being submitted; indicate the specification section number and paragraph number to which it pertains.

1.5.3.3.1 Product Information

Supplement product data with material prepared for the project to satisfy the submittal requirements where product data does not exist. Identify this material as developed specifically for the project, with information and format as required for submission of SD-07 Certificates.

Provide product data in units used in the Contract documents. Where product data are included in preprinted catalogs with another unit, submit the dimensions in contract document units, on a separate sheet.

1.5.3.3.2 Standards

Where equipment or materials are specified to conform to industry or technical-society reference standards of such organizations as the American National Standards Institute (ANSI), ASTM International (ASTM), National Electrical Manufacturer's Association (NEMA), Underwriters Laboratories (UL), or Association of Edison Illuminating Companies (AEIC), submit proof of such compliance. The label or listing by the specified organization will be acceptable evidence of compliance. In lieu of the label or listing, submit a certificate from an independent testing organization, competent to perform testing, and approved by the Contracting Officer. State on the certificate that the item has been tested in accordance with the specified organization's test methods and that the item complies with the specified organization's reference standard.

1.5.3.3.3 Data Submission

Collect required data submittals for each specific material, product, unit of work, or system into a single submittal that is marked for choices, options, and portions applicable to the submittal. Mark each copy of the product data identically. Partial submittals will not be accepted for expedition of the construction effort.

Submit the manufacturer's instructions before installation.

1.5.3.4 Format of SD-04 Samples

1.5.3.4.1 Sample Characteristics

Furnish samples in the following sizes, unless otherwise specified or unless the manufacturer has prepackaged samples of approximately the same size as specified:

- a. Sample of Equipment or Device: Full size.

- b. Sample of Materials Less Than 2 by 3 inches: Built up to 8 1/2 by 11 inches.
- c. Sample of Materials Exceeding 8 1/2 by 11 inches: Cut down to 8 1/2 by 11 inches and adequate to indicate color, texture, and material variations.
- d. Sample of Linear Devices or Materials: 10 inch length or length to be supplied, if less than 10 inches. Examples of linear devices or materials are conduit and handrails.
- e. Sample Volume of Nonsolid Materials: Pint. Examples of nonsolid materials are sand and paint.
- f. Color Selection Samples: 2 by 4 inches. Where samples are specified for selection of color, finish, pattern, or texture, submit the full set of available choices for the material or product specified. Sizes and quantities of samples are to represent their respective standard unit.
- g. Sample Panel: 4 by 4 feet.
- h. Sample Installation: 100 square feet.

1.5.3.4.2 Sample Incorporation

Reusable Samples: Incorporate returned samples into work only if so specified or indicated. Incorporated samples are to be in undamaged condition at the time of use.

Recording of Sample Installation: Note and preserve the notation of any area constituting a sample installation, but remove the notation at the final clean-up of the project.

1.5.3.4.3 Comparison Sample

Samples Showing Range of Variation: Where variations in color, finish, pattern, or texture are unavoidable due to nature of the materials, submit sets of samples of not less than three units showing extremes and middle of range. Mark each unit to describe its relation to the range of the variation.

When color, texture, or pattern is specified by naming a particular manufacturer and style, include one sample of that manufacturer and style, for comparison.

1.5.3.5 Format of SD-05 Design Data

Provide design data and certificates on 8 1/2 by 11 inch paper.

1.5.3.6 Format of SD-06 Test Reports

By prominent notation, indicate each report in the submittal. Indicate the specification number and paragraph number to which each report pertains.

1.5.3.7 Format of SD-07 Certificates

Provide design data and certificates on 8 1/2 by 11 inch paper.

1.5.3.8 Format of SD-08 Manufacturer's Instructions

Present manufacturer's instructions submittals for each section. Include the manufacturer's name, trade name, place of manufacture, and catalog model or number on product data. Also include applicable federal, military, industry, and technical-society publication references. If supplemental information is needed to clarify the manufacturer's data, submit it as specified for SD-07 Certificates.

Submit the manufacturer's instructions before installation.

1.5.3.8.1 Standards

Where equipment or materials are specified to conform to industry or technical-society reference standards of such organizations as the American National Standards Institute (ANSI), ASTM International (ASTM), National Electrical Manufacturer's Association (NEMA), Underwriters Laboratories (UL), or Association of Edison Illuminating Companies (AEIC), submit proof of such compliance. The label or listing by the specified organization will be acceptable evidence of compliance. In lieu of the label or listing, submit a certificate from an independent testing organization, competent to perform testing, and approved by the Contracting Officer. State on the certificate that the item has been tested in accordance with the specified organization's test methods and that the item complies with the specified organization's reference standard.

1.5.3.9 Format of SD-09 Manufacturer's Field Reports

By prominent notation, indicate each report in the submittal. Indicate the specification number and paragraph number to which each report pertains.

1.5.3.10 Format of SD-11 Closeout Submittals

When the submittal includes a document that is to be used in the project or is to become part of the project record, other than as a submittal, do not apply the Contractor's approval stamp to the document itself, but to a separate sheet accompanying the document.

Provide data in the unit of measure used in the contract documents.

1.5.4 Source Drawings for Shop Drawings

1.5.4.1 Source Drawings

The entire set of source drawing files (DWG) will not be provided to the Contractor. Request the specific Drawing Number for the preparation of shop drawings. Only those drawings requested to prepare shop drawings will be provided. These drawings are provided only after award.

1.5.4.2 Terms and Conditions

Data contained on these electronic files must not be used for any purpose other than as a convenience in the preparation of construction data for the referenced project. Any other use or reuse is at the sole risk of the Contractor and without liability or legal exposure to the Government. The Contractor must make no claim, and waives to the fullest extent permitted by law any claim or cause of action of any nature against the Government, its agents, or its subconsultants that may arise out of or in connection with the use of these electronic files. The Contractor must, to the

fullest extent permitted by law, indemnify and hold the Government harmless against all damages, liabilities, or costs, including reasonable attorney's fees and defense costs, arising out of or resulting from the use of these electronic files.

These electronic source drawing files are not construction documents. Differences may exist between the source drawing files and the corresponding construction documents. The Government makes no representation regarding the accuracy or completeness of the electronic source drawing files, nor does it make representation to the compatibility of these files with the Contractor hardware or software. The Contractor is responsible for determining if any conflict exists. In the event that a conflict arises between the signed and sealed construction documents prepared by the Government and the furnished source drawing files, the signed and sealed construction documents govern. Use of these source drawing files does not relieve the Contractor of the duty to fully comply with the contract documents, including and without limitation the need to check, confirm and coordinate the work of all contractors for the project. If the Contractor uses, duplicates or modifies these electronic source drawing files for use in producing construction data related to this contract, remove all previous indication of ownership (seals, logos, signatures, initials and dates).

1.5.5 Electronic File Format

Provide submittals in electronic format, with the exception of material samples required for SD-04 Samples items. In addition to the electronic submittal, provide three hard copies of the submittals. Compile the submittal file as a single, complete document, to include the Transmittal Form described within, and also separately attach the native files which were used to create PDF. The attached files should include the original digital files used to create the submittal. Name the electronic submittal file specifically according to its contents, and coordinate the file naming convention with the Contracting Officer. Electronic files must be of sufficient quality that all information is legible. Use PDF as the electronic format, unless otherwise specified or directed by the Contracting Officer. Generate PDF files from original documents with bookmarks so that the text included in the PDF file is searchable and can be copied. If documents are scanned, optical character resolution (OCR) routines are required. Index and bookmark files exceeding 30 pages to allow efficient navigation of the file. When required, the electronic file must include a valid electronic signature or a scan of a signature.

E-mail electronic submittal documents smaller than 10MB to an e-mail address as directed by the Contracting Officer. Provide electronic documents over 10 MB on an optical disc or through an electronic file sharing system such as the DOD SAFE Web Application located at the following website: <https://safe.apps.mil/>.

1.6 QUANTITY OF SUBMITTALS

1.6.1 Number of SD-01 Preconstruction Submittal Copies

Unless otherwise specified, submit administrative documents electronically.

1.6.2 Number of SD-04 Samples

a. Submit one sample of each required item.

- b. Submit one sample panel or provide one sample installation where directed. Include components listed in the technical section or as directed.
- c. Submit one sample installation, where directed.
- d. Submit one sample of nonsolid materials.

1.7 INFORMATION ONLY SUBMITTALS

Submittals without a "G" designation must be certified by the QC manager and submitted to the Contracting Officer for information-only. Provide information-only submittals to the Contracting Officer a minimum of 14 calendar days prior to the Preparatory Meeting for the associated Definable Feature of Work (DFOW). Approval of the Contracting Officer is not required on information only submittals. The Contracting Officer will mark "receipt acknowledged" on submittals for information and will return only the transmittal cover sheet to the Contractor. Normally, submittals for information only will not be returned. However, the Government reserves the right to return unsatisfactory submittals and require the Contractor to resubmit any item found not to comply with the contract. This does not relieve the Contractor from the obligation to furnish material conforming to the plans and specifications; will not prevent the Contracting Officer from requiring removal and replacement of nonconforming material incorporated in the work; and does not relieve the Contractor of the requirement to furnish samples for testing by the Government laboratory or for check testing by the Government in those instances where the technical specifications so prescribe.

1.8 PROJECT SUBMITTAL REGISTER

A sample Project Submittal Register showing items of equipment and materials for when submittals are required by the specifications is provided as "Attachment A - Submittal Register."

1.8.1 Submittal Management

Prepare and maintain a submittal register, as the work progresses. Do not change data that is output in columns (c), (d), (e), and (f) as delivered by Government; retain data that is output in columns (a), (g), (h), and (i) as approved. As an attachment, provide a submittal register showing items of equipment and materials for which submittals are required by the specifications. This list may not be all-inclusive and additional submittals may be required.

Column (c): Lists specification section in which submittal is required.

Column (d): Lists each submittal description (SD Number. and type, e.g., SD-02 Shop Drawings) required in each specification section.

Column (e): Lists one principal paragraph in each specification section where a material or product is specified. This listing is only to facilitate locating submitted requirements. Do not consider entries in column (e) as limiting the project requirements.

Column (f): Lists the approving authority for each submittal.

Thereafter, the Contractor is to track all submittals by maintaining a complete list, including completion of all data columns and all dates on which submittals are received by and returned by the Government.

1.8.2 Preconstruction Use of Submittal Register

Submit the submittal register. Include the QC plan and the project schedule. Verify that all submittals required for the project are listed and add missing submittals. Coordinate and complete the following fields on the register submitted with the QC plan and the project schedule:

Column (a) Activity Number: Activity number from the project schedule.

Column (g) Contractor Submit Date: Scheduled date for the approving authority to receive submittals.

Column (h) Contractor Approval Date: Date that Contractor needs approval of submittal.

Column (i) Contractor Material: Date that Contractor needs material delivered to Contractor control.

1.8.3 Contractor Use of Submittal Register

Update the following fields with each submittal throughout the contract.

Column (b) Transmittal Number: List of consecutive, Contractor-assigned numbers.

Column (j) Action Code (k): Date of action used to record Contractor's review when forwarding submittals to QC.

Column (l) Date submittal transmitted.

Column (q) Date approval was received.

1.8.4 Approving Authority Use of Submittal Register

Update the following fields:

Column (b) Transmittal Number: List of consecutive, Contractor-assigned numbers.

Column (l) Date submittal was received.

Column (m) through (p) Dates of review actions.

Column (q) Date of return to Contractor.

1.8.5 Action Codes

1.8.5.1 Government Review Action Codes

"A" - "Approved as submitted"

"AN" - "Approved as noted"

"RR" - "Disapproved as submitted"; "Completed"

"NR" - "Not Reviewed"

"RA" - "Receipt Acknowledged"

1.8.6 Delivery of Copies

Submit an updated electronic copy of the submittal register to the Contracting Officer with each invoice request. Provide an updated Submittal Register monthly regardless of whether an invoice is submitted.

1.9 VARIATIONS

Variations from contract requirements require Contracting Officer approval pursuant to contract Clause FAR 52.236-21 Specifications and Drawings for Construction, and will be considered where advantageous to the Government.

1.9.1 Considering Variations

Discussion of variations with the Contracting Officer before submission of a variation submittal will help ensure that functional and quality requirements are met and minimize rejections and resubmittals. For variations that include design changes or some material or product substitutions, the Government may require an evaluation and analysis by a licensed professional engineer hired by the contractor.

Specifically point out variations from contract requirements in a variation submittal. Failure to point out variations may cause the Government to require rejection and removal of such work at no additional cost to the Government.

1.9.2 Warranting that Variations are Compatible

When delivering a variation for approval, the Contractor warrants that this contract has been reviewed to establish that the variation, if incorporated, will be compatible with other elements of work.

1.9.3 Review Schedule Extension

In addition to the normal submittal review period, a period of 14 working days will be allowed for the Government to consider submittals with variations.

1.10 SCHEDULING

Schedule and submit concurrently product data and shop drawings covering component items forming a system or items that are interrelated. Submit pertinent certifications at the same time. No delay damages or time extensions will be allowed for time lost in late submittals. .

- a. Coordinate scheduling, sequencing, preparing, and processing of submittals with performance of work so that work will not be delayed by submittal processing. The Contractor is responsible for additional time required for Government reviews resulting from required resubmittals. The review period for each resubmittal is the same as for the initial submittal.
- b. Submittals required by the contract documents are listed on the

submittal register. If a submittal is listed in the submittal register but does not pertain to the contract work, the Contractor is to include the submittal in the register and annotate it "N/A" with a brief explanation. Approval by the Contracting Officer does not relieve the Contractor of supplying submittals required by the contract documents but that have been omitted from the register or marked "N/A."

- c. Resubmit the submittal register and annotate it monthly with actual submission and approval dates. When all items on the register have been fully approved, no further resubmittal is required.

Contracting Officer review will be completed within 15-working days after the date of submission.

- d. Except as specified otherwise, allow a review period, beginning with receipt by the approving authority, that includes at least 15 working days for submittals for QC manager approval and 20 working days for submittals where the Contracting Officer is the approving authority. The period of review for submittals with Contracting Officer approval begins when the Government receives the submittal from the QC organization.
- e. For submittals requiring review by a Government fire protection engineer, allow a review period, beginning when the Government receives the submittal from the QC organization, of 20 working days for return of the submittal to the Contractor.

1.10.1 Reviewing, Certifying, and Approving Authority

The QC Manager is responsible for reviewing all submittals and certifying that they are in compliance with contract requirements. The approving authority on submittals is the QC Manager unless otherwise specified. At each "Submittal" paragraph in individual specification sections, a notation "G" following a submittal item indicates that the Contracting Officer is the approving authority for that submittal item. Provide an additional copy of the submittal to the Government Approving authority

1.10.2 Constraints

Conform to provisions of this section, unless explicitly stated otherwise for submittals listed or specified in this contract.

Submit complete submittals for each definable feature of the work. At the same time, submit components of definable features that are interrelated as a system.

When acceptability of a submittal is dependent on conditions, items, or materials included in separate subsequent submittals, the submittal will be returned without review.

Approval of a separate material, product, or component does not imply approval of the assembly in which the item functions.

1.10.3 QC Organization Responsibilities

- a. Review submittals for conformance with project design concepts and compliance with contract documents.
- b. Process submittals based on the approving authority indicated in the

submittal register.

- (1) When the QC manager is the approving authority, take appropriate action on the submittal from the possible actions defined in paragraph APPROVED SUBMITTALS.
- (2) When the Contracting Officer is the approving authority or when variation has been proposed, forward the submittal to the Government, along with a certifying statement, or return the submittal marked "not reviewed" or "revise and resubmit" as appropriate. The QC organization's review of the submittal determines the appropriate action.

- c. Ensure that material is clearly legible.
- d. Stamp each sheet of each submittal with a QC certifying statement or an approving statement, except that data submitted in a bound volume or on one sheet printed on two sides may be stamped on the front of the first sheet only.

- (1) When the approving authority is the Contracting Officer, the QC organization will certify submittals forwarded to the Contracting Officer with the following certifying statement:

"I hereby certify that the (equipment) (material) (article) shown and marked in this submittal is that proposed to be incorporated with Contract Number is in compliance with the contract drawings and specification, can be installed in the allocated spaces, and is submitted for Government approval.

Certified by Submittal Reviewer _____, Date _____
(Signature when applicable)

Certified by QC Manager _____, Date _____"
(Signature)

- (2) When approving authority is the QC manager, the QC manager will use the following approval statement when returning submittals to the Contractor as "Approved" or "Approved as Noted."

"I hereby certify that the (material) (equipment) (article) shown and marked in this submittal and proposed to be incorporated with Contract Number is in compliance with the contract drawings and specification, can be installed in the allocated spaces, and is approved for use.

Certified by Submittal Reviewer _____, Date _____
(Signature when applicable)

Approved by QC Manager _____, Date _____"
(Signature)

- e. Sign the certifying statement or approval statement. The QC organization member designated in the approved QC plan is the person signing certifying statements. The use of original ink for signatures is required. Stamped signatures are not acceptable.
- f. Update the submittal register as submittal actions occur, and maintain the submittal register at the project site until final acceptance of all work by the Contracting Officer.

- g. Retain a copy of approved submittals and approved samples at the project site.

1.11 GOVERNMENT APPROVING AUTHORITY

When the approving authority is the Contracting Officer, the Government will:

- a. Note the date on which the submittal was received from the QC manager.
- b. Review submittals for approval within the scheduling period specified and only for conformance with project design concepts and compliance with contract documents.
- c. Identify returned submittals with one of the actions defined in paragraph REVIEW NOTATIONS and with comments and markings appropriate for the action indicated.

Upon completion of review of submittals requiring Government approval, stamp and date submittals and return to the Contractor. One copy of the submittal will be retained by the Contracting Officer's Representative.

1.11.1 Review Notations

Submittals will be returned to the Contractor with the following notations:

- a. Submittals marked "approved" or "accepted" indicate no exception is taken to the material that is subject to review.
- b. Submittals marked "approved as noted" or "approved, except as noted, resubmittal not required," indicates no exception is taken to the material that is subject to review except where corrections are noted. The work must be furnished as corrected provided that the Contractor takes no exception to the corrections.
- c. Submittals marked "not approved," "disapproved," or "revise and resubmit" indicate incomplete submittal or noncompliance with the contract requirements or design concept. Resubmit with appropriate changes. Do not proceed with work for this item until the resubmittal is approved.
- d. Submittals marked "not reviewed" indicate that the submittal has been previously reviewed and approved, is not required, does not have evidence of being reviewed and approved by Contractor, or is not complete. A submittal marked "not reviewed" will be returned with an explanation of the reason it is not reviewed. Resubmit submittals returned for lack of review by Contractor or for being incomplete, with appropriate action, coordination, or change.
- e. Submittals marked "receipt acknowledged" indicate that submittals have been received by the Government. This applies only to "information-only submittals" as previously defined.

1.12 DISAPPROVED SUBMITTALS

Make corrections required by the Contracting Officer. If the Contractor considers any correction or notation on the returned submittals to constitute a change to the contract drawings or specifications, give notice

to the Contracting Officer as required under the FAR clause titled CHANGES. The Contractor is responsible for the dimensions and design of connection details and the construction of work. Failure to point out variations may cause the Government to require rejection and removal of such work at the Contractor's expense.

If changes are necessary to submittals, make such revisions and resubmit in accordance with the procedures above. No item of work requiring a submittal change is to be accomplished until the changed submittals are approved.

1.13 APPROVED SUBMITTALS

The Contracting Officer's approval of submittals is not to be construed as a complete check, and indicates only that

Approval or acceptance by the Government for a submittal does not relieve the Contractor of the responsibility for meeting the contract requirements or for any error that may exist, because under the Quality Control (QC) requirements of this contract, the Contractor is responsible for ensuring information contained within each submittal accurately conforms with the requirements of the contract documents.

After submittals have been approved or accepted by the Contracting Officer, no resubmittal for the purpose of substituting materials or equipment will be considered unless accompanied by an explanation of why a substitution is necessary.

1.14 APPROVED SAMPLES

Approval of a sample is only for the characteristics or use named in such approval and is not to be construed to change or modify any contract requirements. Before submitting samples, provide assurance that the materials or equipment will be available in quantities required in the project. No change or substitution will be permitted after a sample has been approved.

Match the approved samples for materials and equipment incorporated in the work. If requested, approved samples, including those that may be damaged in testing, will be returned to the Contractor, at its expense, upon completion of the contract. Unapproved samples will also be returned to the Contractor at its expense, if so requested.

Failure of any materials to pass the specified tests will be sufficient cause for refusal to consider, under this contract, any further samples of the same brand or make as that material. The Government reserves the right to disapprove any material or equipment that has previously proved unsatisfactory in service.

Samples of various materials or equipment delivered on the site or in place may be taken by the Contracting Officer for testing. Samples failing to meet contract requirements will automatically void previous approvals. Replace such materials or equipment to meet contract requirements.

PART 2 PRODUCTS

Not Used

PART 3 EXECUTION

Not Used

-- End of Section --

SECTION 01 35 26

GOVERNMENTAL SAFETY REQUIREMENTS
05/24

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN SOCIETY OF SAFETY PROFESSIONALS (ASSP)

ANSI/ASSP A10.34 (2021) Protection of the Public on or
Adjacent to Construction Sites

ANSI/ASSP A10.44 (2020) Control of Energy Sources
(Lockout/Tagout) for Construction and
Demolition Operations

ASTM INTERNATIONAL (ASTM)

ASTM F855 (2020) Standard Specifications for
Temporary Protective Grounds to Be Used on
De-energized Electric Power Lines and
Equipment

INSTITUTE OF ELECTRICAL AND ELECTRONICS ENGINEERS (IEEE)

IEEE 1048 (2016) Guide for Protective Grounding of
Power Lines

IEEE C2 (2023) National Electrical Safety Code

INTERNATIONAL SAFETY EQUIPMENT ASSOCIATION (ISEA)

ANSI/ISEA Z89.1 (2014; R 2019) American National Standard
for Industrial Head Protection

NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION (NEMA)

NEMA Z535.2 (2011; R 2017) Environmental and Facility
Safety Signs

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 51B (2024) Standard for Fire Prevention During
Welding, Cutting, and Other Hot Work

NFPA 70 (2023; ERTA 7 2023; TIA 23-15) National
Electrical Code

NFPA 70E (2024) Standard for Electrical Safety in
the Workplace

NFPA 241 (2022) Standard for Safeguarding

Construction, Alteration, and Demolition
Operations

U.S. ARMY CORPS OF ENGINEERS (USACE)

EM 385-1-1 (2024) Safety -- Safety and Health
Requirements Manual

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

10 CFR 20 Standards for Protection Against Radiation

29 CFR 1910 Occupational Safety and Health Standards

29 CFR 1915 Confined and Enclosed Spaces and Other
Dangerous Atmospheres in Shipyard
Employment

29 CFR 1926 Safety and Health Regulations for
Construction

49 CFR 173 Shippers - General Requirements for
Shipments and Packagings

CPL 2.100 (1995) Application of the Permit-Required
Confined Spaces (PRCS) Standards, 29 CFR
1910.146

1.2 DEFINITIONS

The following definitions are for the convenience of the reader. If there is a referenced document in the text of this specification section, that is the document that should define terms for that paragraph. If further clarification is needed, contact the Contracting Officer.

1.2.1 Site Safety and Health Officer (SSHO)

A Contractor Employee that is responsible for overseeing and ensuring implementation of the prime Contractor's Safety and Occupational Health (SOH) program according to the Contract, EM 385-1-1, applicable federal, state, and local requirements.

1.2.1.1 Level One SSHO

A designated employee with full-time SOH responsibility that meets and follows the requirements of EM 385-1-1.

1.2.1.2 Level Two SSHO

A designated employee with Level Two SSHO responsibility that meets and follows the requirements of EM 385-1-1. Level Two SSHOs cannot be assigned to projects that have a residual Risk Assessment Code (RAC) of high or extremely high.

1.2.1.3 Level Three SSHO

A designated Qualified Person or Competent Person with SOH responsibility that meets and follows the requirements of EM 385-1-1. Level 3 SSHOs cannot be assigned to projects that have a residual RAC of high or

extremely high.

1.2.1.4 Alternate SSHO

An employee that meets the definition of the contract-required level SSHO, but is not the primary SSHO.

1.2.2 Competent Person (CP)

The CP is a person designated in writing, who, through training, knowledge and experience, is capable of identifying, evaluating, and addressing existing and predictable hazards in the working environment or working conditions that are unsanitary, hazardous, or dangerous to personnel, and who has authorization to take prompt corrective measures to eliminate them.

1.2.3 Qualified Person (QP)

The QP is a person designated in writing, who, by possession of a recognized degree, certificate, or professional standing, or extensive knowledge, training, and experience, has successfully demonstrated their ability to solve or resolve problems related to the subject matter, the work, or the project.

1.3 SUBMITTALS

Government Acceptance or Approval does not remove responsibility from the Contractors for their actions or liability.

Government approval is required for submittals with a "G" classification. Submittals not having a "G" classification are for Contractor Quality Control approval. Submit the following in accordance with Sections 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Accident Prevention Plan (APP); G
SD-06 Test Reports

Accident Reports; G

LHE Inspection Reports

Monthly Exposure Reports; G

SD-07 Certificates

Crane Operators/Riggers

Activity Hazard Analysis (AHA); G

Certificate of Compliance

Contractor Safety Self-Evaluation Checklist

Hot Work Permit

License Certificates

Portable Gauge Operations Planning Worksheet; G

Radiography Operation Planning Work Sheet; G

Standard Lift Plan; G

1.4 PUBLIC HEALTH EMERGENCIES

In the event of a declared public health emergency, follow safety precautions as required by the Occupational Safety and Health Administration (OSHA) www.osha.gov, the Centers for Disease Control and Prevention (CDC) www.cdc.gov, and as required by federal, state and local requirements.

1.5 MONTHLY EXPOSURE REPORTS

Provide a Monthly Exposure Report by the fifth of each month. This report is a compilation of employee-hours worked each month for all site workers, both Prime and subcontractor. Failure to submit the report may result in retention of up to 10 percent of the progress payment.

1.6 CONTRACTOR SAFETY SELF-EVALUATION CHECKLIST

Contracting Officer will provide a "Contractor Safety Self-Evaluation checklist" to the Contractor at the preconstruction conference. Complete the checklist monthly and submit with each request for payment voucher. This submission is required monthly even when a payment voucher is not requested. An acceptable score of 90 or greater is required. Failure to submit the completed safety self-evaluation checklist or achieve a score of at least 90 may result in retention of up to 10 percent of the voucher. The Contractor Safety Self-Evaluation checklist can be found on the Whole Building Design Guide website at www.wbdg.org/ffc/dod/unified-facilities-guide-specifications-ufgs/ufgs-01-35-26

1.7 REGULATORY REQUIREMENTS

In addition to the detailed requirements included in the provisions of this Contract, comply with the most recent edition of USACE EM 385-1-1, and the following federal, state, and local laws, ordinances, criteria, rules and regulations at the date of the Solicitation for this Contract. Submit matters of interpretation of standards to the appropriate administrative agency for resolution before starting work. Where the requirements of this specification, applicable laws, criteria, ordinances, regulations, and referenced documents vary, the most stringent requirements govern.

1.7.1 Subcontractor Safety Requirements

For this Contract, neither Contractor nor any subcontractor may enter into Contract with any subcontractor that fails to meet the following requirements. The term subcontractor in this and the following paragraphs means any entity holding a Contract with the Contractor or with a subcontractor at any tier.

1.7.1.1 Experience Modification Rate (EMR)

Subcontractors on this Contract must have an effective EMR less than or equal to 1.10, as computed by the National Council on Compensation Insurance (NCCI) or if not available, as computed by the state agency's rating bureau in the state where the subcontractor is registered, when entering into a subcontract agreement with the Prime Contractor or a

subcontractor at any tier. The Prime Contractor may submit a written request for additional consideration to the Contracting Officer where the specified acceptable EMR range cannot be achieved. Relaxation of the EMR range will only be considered for approval on a case-by-case basis for special conditions and must not be anticipated as tacit approval. Contractor's Site Safety and Health Officer (SSHO) must collect and maintain the certified EMR ratings for all subcontractors on the project and make them available to the Government at the Government's request.

1.7.1.2 OSHA Days Away from Work, Restricted Duty, or Job Transfer (DART) Rate

Subcontractors on this Contract must have a DART rate, calculated from the most recent, complete calendar year, less than or equal to 3.4 when entering into a subcontract agreement with the Prime Contractor or a subcontractor at any tier. The OSHA Dart Rate is calculated using the following formula:

$$(N/EH) \times 200,000$$

Where:

N = number of injuries and illnesses with days away, restricted work, or job transfer

EH = total hours worked by all employees during most recent, complete calendar year

200,000 = base for 100 full-time equivalent workers (working 40-hours per week, 50 weeks per year)

The Prime Contractor may submit a written request for additional consideration to the Contracting Officer where the specified acceptable OSHA Dart rate range cannot be achieved for a particular subcontractor. Relaxation of the OSHA DART rate range will only be considered for approval on a case-by-case basis for special conditions and must not be anticipated as tacit approval. Contractor's Site Safety and Health Officer (SSHO) must collect and maintain self-certified OSHA DART rates for all subcontractors on the project and make them available to the Government at the Government's request.

1.8 SITE QUALIFICATIONS, DUTIES, AND MEETINGS

1.8.1 Site Safety and Health Officer (SSHO)

1.8.1.1 Qualifications of SSHO

All SSHOs must be Level One SSHOs and shall meet the training and experience requirements identified in the EM 385-1-1 and this Contract.

1.8.1.2 Duties of SSHO

All SSHOs will carry out the roles and responsibilities as identified in this Contract and the EM 385-1-1. All SSHOs will be designated on an ENG Form 6282, provided by the Contracting Officer. Superintendent, QC Manager, and SSHO are subject to dismissal if their required duties are not being effectively carried out. If either the Superintendent, QC Manager, or SSHO are dismissed, project work will be stopped and will not be allowed to resume until a suitable replacement is approved and the above duties are

again being effectively carried out.

1.8.1.3 Safety Meetings

Conduct safety meetings to review past activities, plan for new or changed operations, review pertinent aspects of appropriate AHA (by trade), establish safe working procedures for anticipated hazards, and provide pertinent Safety and Occupational Health (SOH) training and motivation. Conduct meetings at least once a month for all supervisors at the project location. The SSHO, supervisors, or foremen must conduct meetings at least once a week for the trade workers. Document meeting minutes to include the date, persons in attendance, subjects discussed, and names of individual(s) who conducted the meeting. Maintain documentation on-site and furnish copies to the Contracting Officer on request. Notify the Contracting Officer of all scheduled meetings 7 calendar days in advance.

1.8.2 Roles and Responsibilities of Prime Contractor and SSHO

The Prime Contractor and SSHO must ensure that the requirements of all applicable OSHA and EM 385-1-1 are met for the project. The Prime Contractor must ensure an SSHO or an equally qualified Alternate SSHO(s) is at the worksite at all times to implement and administer the Contractor's safety program and Government accepted Accident Prevention Plan. If the required SSHO has to temporarily (that is, up to 24 hours / 1 day) leave the site of work due to unforeseen or emergency situations, a Level One, Two, or Three SSHO may be used in the interim and must be on the site of work at all times when work is being performed.

If the SSHO must be off-site for a period longer than 24 hours / 1 day, a qualified alternate that meets the contract requirements must be onsite.

a. Prime contractor must ensure all SSHOs will:

- (1) Are designated on an ENG Form 6282.
- (2) Meet minimum training and experience requirements identified in EM 385-1-1.
- (3) Execute roles and responsibilities identified in EM 385-1-1.

1.8.3 Additional Requirements

The Level One SSHO may also serve as the Superintendent.

1.8.4 Competent Person for Confined Space Entry

Provide a CP for Confined Space Entry who meets the requirements of EM 385-1-1 and herein. The CP for Confined Space Entry must supervise the entry into each confined space in accordance with EM 385-1-1.

1.8.5 Preconstruction Conference

- a. Contractor representatives who have a responsibility or significant role in accident prevention on the project must attend the preconstruction conference. This includes the project superintendent, Site Safety and Occupational Health Officer, quality control manager, or any other assigned safety and health professionals who participated in the development of the APP (including the Activity Hazard Analyses (AHAs) and special plans, program and procedures associated with it).

- b. Discuss the details of the submitted APP to include incorporated plans, programs, procedures and a listing of anticipated AHAs that will be developed and implemented during the performance of the Contract. This list of proposed AHAs will be reviewed and an agreement will be reached between the Contractor and the Contracting Officer as to which phases will require an analysis. In addition, establish a schedule for the preparation, submittal, and Government review of AHAs to preclude project delays. The creation of the APP and Schedule will be created after being given Notice to Proceed.
- c. Deficiencies in the submitted APP, identified during the Contracting Officer's review, must be corrected, and the APP re-submitted for review prior to the start of construction. Work is not permitted to begin until an APP is established that is acceptable to the Contracting Officer.

1.9 ACCIDENT PREVENTION PLAN (APP)

1.9.1 Accident Prevention Plan (APP)

Provide a site-specific Accident Prevention Plan (APP), including Activity Hazard Analyses (AHA), in accordance with EM 385-1-1, ENG Form 6293, for the design team to follow during site visits and investigations. For subsequent visits, update the plan if there are changes in the personnel who will be attending, or the tasks to be performed. Submit the APP for review and acceptance by the Government at least 15 calendar days prior to the start of the design field work after being given Notice to Proceed. Field work must not begin until the design APP is accepted by the Contracting Officer. Prior to the start of construction incorporate the Design APP into the Construction APP so that one site specific APP exists for the project and submit to the Contracting Officer for acceptance.

If the design scope includes borings or other subsurface investigations, include in the APP the type of field investigation and verification techniques, such as visual, local utility locating service scanning and third party subcontractor scanning, potholing, or hand digging within two feet of a known utility that will be required. Mark underground utilities before starting any ground-disturbing actions. Notify the Contracting Officer 15 days prior to the start of soil borings or sub-surface investigations.

1.9.2 Accident Prevention Plan (APP)

A competent person must prepare the written site-specific APP. Prepare the APP in accordance with the format and requirements of EM 385-1-1, ENG Form 6293, and herein. The APP must be job-specific and address any unusual or unique aspects of the project or activity for which it is written. The APP must interface with the Contractor's overall safety and occupational health program referenced in the APP in the applicable APP element, and made site-specific. Describe the methods to evaluate past safety performance of potential subcontractors in the selection process. Also, describe innovative methods used to ensure and monitor safe work practices of subcontractors. The Government considers the Prime Contractor to be the "controlling employer" for all worksite safety and health of the subcontractors. Contractors are responsible for informing their subcontractors of the safety provisions under the terms of the Contract and the penalties for noncompliance, coordinating the work to prevent one craft from interfering with or creating hazardous working conditions for other

crafts, and inspecting subcontractor operations to ensure that accident prevention responsibilities are being carried out. The APP must be signed in accordance with the APP and ENG Form 6293 Accident Prevention Plan Worksheet. The SSHO must provide and maintain the APP and a log of signatures by each subcontractor foreman, attesting that they have read and understand the APP, and make the APP and log available on-site to the Contracting Officer. If English is not the foreman's primary language, the Prime Contractor must provide an interpreter.

Submit the APP to the Contracting Officer 15 calendar days prior to the date of the preconstruction conference for acceptance. Work cannot proceed without an accepted APP. Once reviewed and accepted by the Contracting Officer, the APP and attachments will be enforced as part of the Contract. Disregarding the provisions of this Contract or the accepted APP is cause for stopping of work, at the discretion of the Contracting Officer, until the matter has been rectified. Continuously review and amend the APP, as necessary, throughout the life of the Contract. Changes to the accepted APP must be made with the knowledge and concurrence of the Contracting Officer, project superintendent, SSHO and Quality Control Manager. Incorporate unusual or high-hazard activities not identified in the original APP as they are discovered. Should any severe hazard exposure (i.e., imminent danger) become evident, stop work in the area, secure the area, and develop a plan to remove the exposure and control the hazard. Notify the Contracting Officer within 24 hours of discovery. Eliminate and remove the hazard. In the interim, take all necessary action to restore and maintain safe working conditions in order to safeguard onsite personnel, visitors, the public (as defined by ANSI/ASSP A10.34), and the environment.

1.9.3 Names and Qualifications

Provide plans in accordance with the requirements outlined in EM 385-1-1, including the following:

- a. Names and qualifications (resumes including education, training, experience and certifications) of site safety and health personnel designated to perform work on this project to include the designated Site Safety and Health Officer and other competent and qualified personnel to be used. Specify the duties of each position.
- b. As a minimum, designate and submit qualifications of Competent Persons (CP) for each of the following major areas: excavation; scaffolding; fall protection; hazardous energy; confined space; health hazard recognition, evaluation and control of chemical, physical and biological agents; and personal protective equipment and clothing to include selection, use and maintenance. Designate and submit qualifications for additional CPs as applicable to the work performed under this Contract.

1.9.4 Plans

Provide plans in the APP in accordance with the requirements outlined in EM 385-1-1, including the following:

1.9.4.1 Lead, Cadmium, and Chromium Compliance Plan

Identify the safety and health aspects of work involving lead, cadmium and chromium, and prepare in accordance with Section 02 83 00 LEAD REMEDIATION (DOR to edit).

1.9.4.2 Asbestos Hazard Abatement Plan

Identify the safety and health aspects of asbestos work, and prepare in accordance with Section 02 82 00 ASBESTOS REMEDIATION (DOR to edit).

1.9.4.3 Polychlorinated Biphenyls (PCB) Plan

Identify the safety and health aspects of Polychlorinated Biphenyls work, and prepare in accordance with Sections 02 84 33 REMOVAL AND DISPOSAL OF POLYCHLORINATED BIPHENYLS (PCBs) (DOR to edit) and 02 61 23 REMOVAL AND DISPOSAL OF PCB CONTAMINATED SOILS (DOR to edit).

1.9.4.4 Site Demolition Plan

Identify the safety and health aspects, and prepare in accordance with Section 02 41 00 DEMOLITION, EM 385-1-1, and referenced sources. Include engineering survey as applicable.

1.10 ACTIVITY HAZARD ANALYSIS (AHA)

Before beginning each activity, task or Definable Feature of Work (DFOW) involving a type of work presenting hazards not experienced in previous project operations, or where a new work crew or subcontractor is to perform the work, the Contractor(s) performing that work activity must prepare an AHA. AHAs must be developed by the Prime Contractor, subcontractor, or supplier performing the work, and provided for Prime Contractor review and approval before submitting to the Contracting Officer. AHAs must be signed by the SSHO, Superintendent, QC Manager and the subcontractor Foreman performing the work. Format the AHA in accordance with EM 385-1-1 or as directed by the Contracting Officer. Submit the AHA for review at least 15 working days prior to the start of each activity task, or DFOW. The Government reserves the right to require the Contractor to revise and resubmit the AHA if it fails to effectively identify the work sequences, specific anticipated hazards, site conditions, equipment, materials, personnel and the control measures to be implemented.

AHAs must identify competent persons required for phases involving high risk activities, including confined entry, crane and rigging, excavations, trenching, electrical work, fall protection, and scaffolding.

1.10.1 AHA Management

Review the AHA list periodically (at least monthly) at the Contractor supervisory safety meeting, and update as necessary when procedures, scheduling, or hazards change. Use the AHA during daily inspections by the SSHO to ensure the implementation and effectiveness of the required safety and health controls for that work activity.

1.10.2 AHA Signature Log

Each employee performing work as part of an activity, task or DFOW must review the AHA for that work and sign a signature log specifically maintained for that AHA prior to starting work on that activity. The SSHO must maintain a signature log on site for every AHA. Provide employees whose primary language is other than English, with an interpreter to ensure a clear understanding of the AHA and its contents.

1.11 SITE SAFETY REFERENCE MATERIALS

Maintain safety-related references applicable to the project, including those listed in paragraph REFERENCES. Maintain applicable equipment manufacturer's manuals.

1.12 EMERGENCY MEDICAL TREATMENT

Contractors must arrange for their own emergency medical treatment in accordance with EM 385-1-1. The Government has no responsibility to provide emergency medical treatment.

1.13 NOTIFICATIONS AND REPORTS

1.13.1 Accident Notification

Notify the Contracting Officer in accordance with the EM 385-1-1 Accident Reporting Timeline.

Table Accident Reporting Required Timeline		
Accident Type	Notify KO or COR	Complete Final Accident Report on ENG 3394 and provide to KO or COR
Fatality, in-patient hospitalization, amputation, eye loss, or property damage over \$600,000.	Immediately, no later than (NLT) 8 Hours	Within 7 Days
All other accidents and near misses	Immediately, no later than (NLT) 24 Hours	Within 7 Days

Within notification include Contractor name; Contract title; type of Contract; name of activity, installation or location where accident occurred; date and time of accident; names of personnel injured; extent of property damage, if any; extent of injury, if known, and brief description of accident (for example, type of construction equipment used and PPE used). Preserve the conditions and evidence on the accident site until the Government investigation team arrives on-site and Government investigation is conducted. Assist and cooperate fully with the Government's investigation(s) of any accident or near miss.

1.13.2 Accident Reports

- a. Conduct an accident investigation for recordable injuries and illnesses, property damage, and near misses as defined in EM 385-1-1, to establish the root cause(s) of the accident. Complete the applicable NAVFAC Contractor Incident Reporting System (CIRS), and electronically submit via the NAVFAC Enterprise Safety Applications Management System (ESAMS). Complete and submit an accident investigation report in ESAMS within 7 days for accidents as defined by EM 385-1-1. Complete the investigation report within 30 days. Accidents must include a written report submitted as an attachment in ESAMS using the following outline:

- (1) Summary description to include:
 - (a) process
 - (b) findings
 - (c) outcomes
- (2) Root Cause
- (3) Direct Factors
- (4) Indirect and Contributing Factors
- (5) Corrective Actions
- (6) Recommendations

All accidents are reportable, regardless of whether or not it is recordable.

- b. Near Misses: For Navy Projects, complete the applicable documentation in NAVFAC Contractor Incident Reporting System (CIRS), and electronically submit via the NAVFAC Enterprise Safety Applications Management System (ESAMS). Near miss reports are considered positive and proactive Contractor safety management actions.
- c. Conduct an accident investigation for any load handling equipment accident (including rigging accidents) to establish the root cause(s) of the accident. Complete the Load Handling Equipment (LHE) Accident Report (Crane and Rigging Accident Report) form and provide the report to the Contracting Officer within 30 calendar days of the accident. Do not proceed with crane operations until cause is determined and corrective actions have been implemented to the satisfaction of the Contracting Officer. The Contracting Officer will provide a blank copy of the accident report form.

1.13.3 LHE Inspection Reports

Submit LHE inspection reports required in accordance with EM 385-1-1 and as specified herein with Daily Reports of Inspections.

1.13.4 Certificate of Compliance and Pre-lift Plan/Checklist for LHE and Rigging

Provide a Certificate of Compliance for LHE entering an activity under this Contract and in accordance with EM 385-1-1. Post certifications on the crane.

Develop a Standard Lift Plan (SLP) in accordance with EM 385-1-1 and using Standard Pre-Lift Crane Plan/Checklist for each lift planned. Submit SLP to the Contracting Officer for approval within 15 calendar days in advance of planned lift.

1.14 HOT WORK PERMIT

1.14.1 Permit and Personnel Requirements

Submit and obtain a written permit prior to performing "Hot Work" (i.e., welding or cutting) or operating other flame-producing/spark producing devices, from the Fire Division. A permit is required from the Explosives Safety Office for work in and around where explosives are processed, stored, or handled. Contractors are required to meet all criteria before a permit is issued. Provide at least two 20 pound 4A:20 BC rated extinguishers for normal "Hot Work". The extinguishers must be current inspection tagged, and contain an approved safety pin and tamper resistant seal. It is also mandatory to have a designated FIRE WATCH for any "Hot Work" done at this activity. The Fire Watch must be trained in accordance with NFPA 51B and remain on-site for a minimum of 1 hour after completion of the task or as specified on the hot work permit.

When starting work in the facility, require personnel to familiarize themselves with the location of the nearest fire alarm boxes and place in memory the emergency Fire Division phone number. Report any fire, no matter how small, to the responsible Fire Division immediately.

1.14.2 Work Around Flammable Materials

Obtain permit approval from a NFPA Certified Marine Chemist, or Certified Industrial Hygienist for "Hot Work" within or around flammable materials (such as fuel systems or welding/cutting on fuel pipes) or confined spaces (such as sewer wet wells, manholes, or vaults) that have the potential for flammable or explosive atmospheres.

Whenever these materials, except beryllium and chromium (VI), are encountered in indoor operations, local mechanical exhaust ventilation systems that are sufficient to reduce and maintain personal exposures to within acceptable limits must be used and maintained in accordance with manufacturer's instruction and supplemented by exceptions noted in EM 385-1-1.

1.15 RADIATION SAFETY REQUIREMENTS

Submit License Certificates, employee training records, and Leak Test Reports for radiation materials and equipment to the Contracting Officer and Radiation Safety Office (RSO), and Contracting Oversight Technician (COT) for all specialized and licensed material and equipment proposed for use on the construction project (excludes portable machine sources of ionizing radiation including moisture density and X-Ray Fluorescence (XRF)). Maintain on-site records whenever licensed radiological materials or ionizing equipment are on Government property.

Protect workers from radiation exposure in accordance with 10 CFR 20, ensuring any personnel exposures are maintained As Low As Reasonably Achievable.

1.15.1 Radiography Operation Planning Work Sheet

Submit a Gamma and X-Ray Radiography Operation Planning Work Sheet to Contracting Officer 14 days prior to commencement of operations involving radioactive materials or radiation generating devices. For portable machine sources of ionizing radiation, including moisture density and XRF, use and submit the Portable Gauge Operations Planning Worksheet instead.

The Contracting Officer and COT will review the submitted worksheet and provide questions and comments.

Contractors must use primary dosimeters process by a National Voluntary Laboratory Accreditation Program (NVLAP) accredited laboratory.

1.15.2 Site Access and Security

Coordinate site access and security requirements with the Contracting Officer and COT for all radiological materials and equipment containing ionizing radiation that are proposed for use on a government facility. For gamma radiography materials and equipment, a Government escort is required for any travels on the Installation. The Navy COT or Government authorized representative will meet the Contractor at a designated location outside the Installation, ensure safety of the materials being transported, and will escort the Contractor for gamma sources onto the Installation, to the job site, and off the Installation. For portable machine sources of ionizing radiation, including moisture density and XRF, the Navy COT or Government authorized representative will meet the Contractor at the job site.

Provide a copy of all calibration records, and utilization records to the COT for radiological operations performed on the site.

1.15.3 Loss or Release and Unplanned Personnel Exposure

Loss or release of radioactive materials, and unplanned personnel exposures must be reported immediately to the Contracting Officer, RSO, and Base Security Department Emergency Number.

1.15.4 Site Demarcation and Barricade

Properly demark and barricade an area surrounding radiological operations to preclude personnel entrance, in accordance with EM 385-1-1, Nuclear Regulatory Commission, and Applicable State regulations and license requirements, and in accordance with requirements established in the accepted Radiography Operation Planning Work Sheet.

Do not close or obstruct streets, walks, and other facilities occupied and used by the Government without written permission from the Contracting Officer.

1.15.5 Security of Material and Equipment

Properly secure the radiological material and ionizing radiation equipment at all times, including keeping the devices in a properly marked and locked container, and secondarily locking the container to a secure point in the Contractor's vehicle or other approved storage location during transportation and while not in use. While in use, maintain a continuous visual observation on the radiological material and ionizing radiation equipment. In instances where radiography is scheduled near or adjacent to buildings or areas having limited access or one-way doors, make no assumptions as to building occupancy. Where necessary, the Contracting Officer will direct the Contractor to conduct an actual building entry, search, and alert. Where removal of personnel from such a building cannot be accomplished and it is otherwise safe to proceed with the radiography, position a fully instructed employee inside the building or area to prevent exiting while external radiographic operations are in process.

1.15.6 Transportation of Material

Comply with 49 CFR 173 for Transportation of Regulated Amounts of Radioactive Material. Notify Local Fire authorities and the site Radiation Safety Officer (RSO) of any Radioactive Material use.

1.15.7 Schedule for Exposure or Unshielding

Actual exposure of the radiographic film or unshielding the source must not be initiated until after 5 p.m. on weekdays.

1.15.8 Transmitter Requirements

Adhere to the base policy concerning the use of transmitters, such as radios and cell phones. Obey Emissions control (EMCON) restrictions.

1.16 CONFINED SPACE ENTRY REQUIREMENTS

Confined space entry must comply with EM 385-1-1, 29 CFR 1926, 29 CFR 1910, and Directive CPL 2.100. Any potential for a hazard in the confined space requires a permit system to be used.

1.16.1 Rescue Procedures and Coordination with Local Emergency Responders

Develop and implement an on-site rescue and recovery plan and procedures. The rescue plan must not rely on local emergency responders for rescue from a confined space.

1.17 SEVERE STORM PLAN

In the event of a severe storm warning, the Contractor must comply with the applicable Storm Plan and:

- a. Secure outside equipment and materials and place materials that could be damaged in protected areas.
- b. Check surrounding area, including roof, for loose material, equipment, debris, and other objects that could be blown away or against existing facilities.
- c. Ensure that temporary erosion controls are adequate.

PART 2 PRODUCTS

2.1 CONFINED SPACE SIGNAGE

Provide permanent signs integral to or securely attached to access covers for new permit-required confined spaces. Signs for confined spaces must comply with NEMA Z535.2. Provide signs with wording: "DANGER--PERMIT-REQUIRED CONFINED SPACE, DO NOT ENTER" in bold letters a minimum of one inch in height and constructed to be clearly legible with all paint removed. The signal word "DANGER" must be red and readable from 5 feet.

PART 3 EXECUTION

3.1 CONSTRUCTION AND OTHER WORK

Comply with EM 385-1-1, NFPA 70, NFPA 70E, NFPA 241, the APP, the AHA,

Federal and State OSHA regulations, and other related submittals and activity fire and safety regulations. The most stringent standard prevails.

PPE is governed in all areas by the nature of the work the employee is performing. Use personal hearing protection at all times in designated noise hazardous areas or when performing noise hazardous tasks. Safety glasses must be worn or carried/available on each person. Mandatory PPE includes:

- a. Head Protection that meets ANSI/ISEA Z89.1
- b. Long Pants
- c. Appropriate Safety Footwear
- d. Appropriate Class Reflective Vests

3.1.1.1 Worksite Communication

Employees working alone in a remote location or away from other workers must be provided an effective means of emergency communications (i.e., cellular phone, two-way radios, land-line telephones or other acceptable means). The selected communication must be readily available (easily within the immediate reach) of the employee and must be tested prior to the start of work to verify that it effectively operates in the area/environment. Develop an employee check-in/check-out communication procedure to ensure employee safety.

3.1.1.2 Hazardous Material Use

Each hazardous material must receive approval from the Contracting Office or their designated representative prior to being brought onto the job site or prior to any other use in connection with this Contract. Allow a minimum of 10 working days for processing of the request for use of a hazardous material.

3.1.1.3 Hazardous Material Exclusions

Notwithstanding any other hazardous material used in this Contract, radioactive materials or instruments capable of producing ionizing/non-ionizing radiation (with the exception of radioactive material and devices used in accordance with EM 385-1-1 such as nuclear density meters for compaction testing and laboratory equipment with radioactive sources) as well as materials which contain asbestos, mercury or polychlorinated biphenyls, di-isocyanates, lead-based paint, and hexavalent chromium, are prohibited. The Contracting Officer, upon written request by the Contractor, may consider exceptions to the use of any of the above excluded materials. Low mercury lamps used within fluorescent lighting fixtures are allowed as an exception without further Contracting Officer approval. Notify the Radiation Safety Officer (RSO) prior to excepted items of radioactive material and devices being brought on base.

3.1.1.4 Unforeseen Hazardous Material

Contract documents identify materials such as PCB, lead paint, and friable and non-friable asbestos and other OSHA regulated chemicals (i.e., 29 CFR Part 1910.1000). If material(s) that may be hazardous to human health upon disturbance are encountered during demolition, repair, renovation, or construction operations. Stop that portion of work and notify the

Contracting Officer immediately. Within 14 calendar days the Government will determine if the material is hazardous. If material is not hazardous or poses no danger, the Government will direct the Contractor to proceed without change. If material is hazardous and handling of the material is necessary to accomplish the work, the Government will issue a modification.

3.2 UTILITY OUTAGE REQUIREMENTS

Apply for utility outages at least 10 business days in advance. At a minimum, the written request must include the location of the outage, utilities being affected, duration of outage, any necessary sketches, and a description of the means to fulfill energy isolation requirements in accordance with EM 385-1-1. In accordance with EM 385-1-1, where outages involve Government or Utility personnel, coordinate with the Government on all activities involving the control of hazardous energy.

These activities include, but are not limited to, a review of Hazardous Energy Control Program (HECP) and HEC procedures, as well as applicable Activity Hazard Analyses (AHAs). In accordance with EM 385-1-1 and NFPA 70E, work on energized electrical circuits must not be performed without prior Government authorization. Government permission is considered through the permit process and submission of a detailed AHA. Energized work permits are considered only when de-energizing introduces additional or increased hazard or when de-energizing is infeasible.

3.3 OUTAGE COORDINATION MEETING

After the utility outage request is approved and prior to beginning work on the utility system requiring shut-down, conduct a pre-outage coordination meeting in accordance with EM 385-1-1. This meeting must include the Prime Contractor, the Prime and subcontractors performing the work, the Contracting Officer, and the Public Utilities representative. All parties must fully coordinate HEC activities with one another. During the coordination meeting, all parties must discuss and coordinate on the scope of work, HEC procedures (specifically, the lock-out/tag-out procedures for worker and utility protection), the AHA, assurance of trade personnel qualifications, identification of competent persons, and compliance with HECP training in accordance with EM 385-1-1. Clarify when personal protective equipment is required during switching operations, inspection, and verification.

3.4 CONTROL OF HAZARDOUS ENERGY (LOCKOUT/TAGOUT)

Provide and operate a Hazardous Energy Control Program (HECP) in accordance with EM 385-1-1, 29 CFR 1910, 29 CFR 1915, ANSI/ASSP A10.44, NFPA 70E.

3.4.1 Safety Preparatory Inspection Coordination Meeting with the Government or Utility

For electrical distribution equipment that is to be operated by Government or Utility personnel, the Prime Contractor and the subcontractor performing the work must attend the safety preparatory inspection coordination meeting, which will also be attended by the Contracting Officer's Representative, and required by EM 385-1-1. The meeting will occur immediately preceding the start of work and following the completion of the outage coordination meeting. Both the safety preparatory inspection coordination meeting and the outage coordination meeting must occur prior to conducting the outage and commencing with lockout/tagout procedures.

3.4.2 Lockout/Tagout Isolation

Where the Government or Utility performs equipment isolation and lockout/tagout, the Contractor must place their own locks and tags on each energy-isolating device and proceed in accordance with the HECF. Before any work begins, both the Contractor and the Government or Utility must perform energy isolation verification testing while wearing required PPE detailed in the Contractor's AHA and required by EM 385-1-1. Install personal protective grounds, with tags, to eliminate the potential for induced voltage in accordance with EM 385-1-1.

3.4.3 Lockout/Tagout Removal

Upon completion of work, conduct lockout/tagout removal procedure in accordance with the HECF. In accordance with EM 385-1-1, each lock and tag must be removed from each energy isolating device by the authorized individual or systems operator who applied the device. Provide formal notification to the Government (by completing the Government form if provided by Contracting Officer's Representative), confirming that steps of de-energization and lockout/tagout removal procedure have been conducted and certified through inspection and verification. Government or Utility locks and tags used to support the Contractor's work will not be removed until the authorized Government employee receives the formal notification.

3.5 FALL PROTECTION PROGRAM

Establish a fall protection program, for the protection of all employees exposed to fall hazards. Within the program include company policy, identify roles and responsibilities, education and training requirements, fall hazard identification, prevention and control measures, inspection, storage, care and maintenance of fall protection equipment and rescue and evacuation procedures in accordance with EM 385-1-1.

3.5.1 Fall Protection Equipment and Systems

Enforce use of personal fall protection equipment and systems designated (to include fall arrest, restraint, and positioning) for each specific work activity in the Site Specific Fall Protection and Prevention Plan and AHA at all times when an employee is exposed to a fall hazard. Protect employees from fall hazards as specified in EM 385-1-1.

Provide personal fall protection equipment, systems, subsystems, and components that comply with EM 385-1-1 and 29 CFR 1926.

3.5.1.1 Additional Personal Fall Protection Measures

In addition to the required fall protection systems, other protective measures such as safety skiffs, personal floatation devices, and life rings, are required when working above or next to water in accordance with EM 385-1-1. Personal fall protection systems and equipment are required when working from an articulating or extendible boom, swing stages, or suspended platform. In addition, personal fall protection systems are required when operating other equipment such as scissor lifts. The need for tying-off in such equipment is to prevent ejection of the employee from the equipment during raising, lowering, travel, or while performing work.

3.5.1.2 Personal Fall Protection Equipment

Only a full-body harness with a shock-absorbing lanyard or self-retracting

lanyard is an acceptable personal fall arrest body support device. The use of body belts is not acceptable. Harnesses must have a fall arrest attachment affixed to the body support (usually a Dorsal D-ring) and specifically designated for attachment to the rest of the system. Snap hooks and carabineers must be self-closing and self-locking, capable of being opened only by at least two consecutive deliberate actions and have a minimum gate strength of 3,600 lbs in all directions. Use webbing, straps, and ropes made of synthetic fiber. The maximum free fall distance when using fall arrest equipment must not exceed 6 feet, unless the proper energy absorbing lanyard is used. Always take into consideration the total fall distance and any swinging of the worker (pendulum-like motion), that can occur during a fall, when attaching a person to a fall arrest system. Equip all full body harnesses with Suspension Trauma Preventers such as stirrups, relief steps, or similar in order to provide short-term relief from the effects of orthostatic intolerance in accordance with EM 385-1-1.

3.6 ELECTRICAL

Perform electrical work in accordance with EM 385-1-1.

3.6.1 Electrical Work

As described in EM 385-1-1, electrical work is to be conducted in a de-energized state unless there is no alternative method for accomplishing the work. In those cases obtain an energized work permit from the Contracting Officer. The energized work permit application must be accompanied by the AHA and a summary of why the equipment/circuit needs to be worked energized. Underground electrical spaces must be certified safe for entry before entering to conduct work. Cables that will be cut must be positively identified and de-energized prior to performing each cut. Attach temporary grounds in accordance with ASTM F855 and IEEE 1048. Perform all high voltage cable cutting remotely using hydraulic cutting tool. When racking in or live switching of circuit breakers, no additional person other than the switch operator is allowed in the space during the actual operation. Plan so that work near energized parts is minimized to the fullest extent possible. Use of electrical outages clear of any energized electrical sources is the preferred method.

When working in energized substations, only qualified electrical workers are permitted to enter. When work requires work near energized circuits as defined by NFPA 70, high voltage personnel must use personal protective equipment that includes, as a minimum, electrical hard hat, safety footwear, insulating gloves and electrical arc flash protection for personnel as required by NFPA 70E. Insulating blankets, hearing protection, and switching suits may also be required, depending on the specific job and as delineated in the Contractor's AHA. Ensure that each employee is familiar with and complies with these procedures and 29 CFR 1910.

3.6.2 Qualifications

Electrical work must be performed by QP with verifiable credentials who are familiar with applicable code requirements. Verifiable credentials consist of State, National and Local Certifications or Licenses that a Master or Journeyman Electrician may hold, depending on work being performed, and must be identified in the appropriate AHA. Journeyman/Apprentice ratio must be in accordance with State, Local requirements applicable to where work is being performed.

3.6.3 Arc Flash

Conduct a hazard analysis/arc flash hazard analysis whenever work on or near energized parts greater than 50 volts is necessary, in accordance with NFPA 70E.

All personnel entering the identified arc flash protection boundary must be QPs and properly trained in NFPA 70E requirements and procedures. Unless permitted by NFPA 70E, no Unqualified Person is permitted to approach nearer than the Limited Approach Boundary of energized conductors and circuit parts. Training must be administered by an electrically qualified source and documented.

3.6.4 Grounding

Ground electrical circuits, equipment and enclosures in accordance with NFPA 70 and IEEE C2 to provide a permanent, continuous and effective path to ground unless otherwise noted by EM 385-1-1.

3.6.5 Testing

Temporary electrical distribution systems and devices must be inspected, tested and found acceptable for Ground-Fault Circuit Interrupter (GFCI) protection, polarity, ground continuity, and ground resistance before initial use, before use after modification and at least monthly. Monthly inspections and tests must be maintained for each temporary electrical distribution system, and signed by the electrical CP or QP.

-- End of Section --

SECTION 01 45 00

QUALITY CONTROL
08/23, CHG 1: 05/24

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by the basic designation only.

ASTM INTERNATIONAL (ASTM)

ASTM C1077	(2024) Standard Practice for Agencies Testing Concrete and Concrete Aggregates for Use in Construction and Criteria for Testing Agency Evaluation
ASTM D3666	(2016) Standard Specification for Minimum Requirements for Agencies Testing and Inspecting Road and Paving Materials
ASTM D3740	(2019) Minimum Requirements for Agencies Engaged in the Testing and/or Inspection of Soil and Rock as Used in Engineering Design and Construction
ASTM E329	(2023) Standard Specification for Agencies Engaged in Construction Inspection, Testing, or Special Inspection
ASTM E543	(2021) Standard Specification for Agencies Performing Non-Destructive Testing

U.S. ARMY CORPS OF ENGINEERS (USACE)

EM 385-1-1	(2024) Safety -- Safety and Health Requirements Manual
ER 1110-3-12	(2021) Military Engineering and Design Quality Management

1.2 PAYMENT

Separate payment will not be made for providing and maintaining an effective Quality Control program. Include all associated costs in the applicable Pricing Schedule item.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" classification. Submittals not having a "G" classification are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES.

SD-01 Preconstruction Submittals

Contractor Quality Control (CQC) Plan; G

Additional Requirements For Design Quality Control (DQC) Plan; G

SD-05 Design Data

Design Quality Control

Discipline-Specific Checklists

Design Quality Control Documentation (DQCD)

SD-06 Test Reports

Verification Statement

1.4 GENERAL REQUIREMENTS

Establish and maintain an effective quality control (QC) system that complies with FAR 52.246-12 Inspection of Construction. QC is comprised of plans, procedures, and organization necessary to produce an end product that complies with the Contract requirements. The QC system covers all design and construction operations, both onsite and offsite, and must be keyed to the proposed design and construction sequence. The Quality Control Manager, Superintendent, Site Safety and Health Officer (SSHO), and all on-site supervisors are responsible for the quality of work and are subject to removal by the Contracting Officer for non-compliance with the quality requirements specified in the Contract. The Quality Control Manager must maintain a physical presence at the work site at all times and is the primary individual responsible for all quality control.

1.5 QUALITY CONTROL (QC) PROGRAM REQUIREMENTS

Establish and maintain a QC program as described in this section. The QC program consists of a QC Organization, QC Plan, QC Plan Meeting(s), a Coordination and Mutual Understanding Meeting, QC meetings, three phases of control, submittal review and approval, testing, completion inspections, QC certifications, and documentation necessary to provide materials, equipment, workmanship, fabrication, construction and operations that comply with the requirements of this Contract. The QC program must cover on-site and off-site work and be keyed to the work sequence. No construction work or testing may be performed unless the QC Manager is on the work site. The QC Manager must report to an officer of the firm and not be subordinate to the Project Superintendent or the Project Manager. The QC Manager, Project Superintendent and Project Manager must work together effectively. Although the QC Manager is the primary individual responsible for quality control, all individuals will be held responsible for the quality of work on the job.

1.5.1 Meetings

1.5.1.1 Quality Control Plan Meeting

Prior to submission of the QC Plan, the Contractor may request a meeting with the Contracting Officer to discuss the QC Plan requirements of this Contract.

The purpose of this meeting is to develop a mutual understanding of the QC

Plan requirements prior to plan development and submission and to agree on the Contractor's list of Definable Feature of Work (DFOW).

1.5.1.1.2 Coordination and Mutual Understanding Meeting

After the **Post Award Kickoff Meeting**, before start of **design or construction**, and prior to acceptance by the Government of the CQC Plan, meet with the Contracting Officer and discuss the Contractor's quality control system. During the meeting, a mutual understanding of the system details must be developed, including the forms for recording the CQC operations, **design activities**, control activities, testing, administration of the system for both onsite and offsite work, and the interrelationship of Contractor's Management and control with the Government's Quality Assurance. Minutes of the meeting will be prepared by the QC Manager and signed by the Contractor, **the Architect/Engineer (A/E)**, and the Government. Provide a copy of the signed minutes to all attendees. At a minimum the Coordination and Mutual Understanding Meeting must be repeated when a new QC Manager is appointed. There can be other occasions when subsequent **meetings** will be called by either party to reconfirm mutual understandings or address deficiencies in the CQC system or procedures which can require corrective action by the Contractor.

1.5.1.2.1 Purpose

The purpose of this meeting is to develop a mutual understanding of the QC details, including documentation, administration for on-site and off-site work, design intent, environmental requirements and procedures, coordination of activities to be performed, and the coordination of the Contractor's management, production, and QC personnel. At the meeting, the Contractor must explain in detail how three phases of control will be implemented for each DFOW, as well as how each DFOW will be affected by each management plan or requirement as listed below:

- a. Waste Management Plan.
- b. Procedures for noise and acoustics management.
- c. Environmental Protection Plan.
- d. Environmental regulatory requirements.

1.5.1.2.2 Coordination of Activities

Coordinate activities included in various sections to assure efficient and orderly installation of each component. Coordinate operations included under different sections that are dependent on each other for proper installation and operation.

1.5.1.2.3 Attendees

As a minimum, the Contractor's personnel required to attend include an officer of the firm, the Project Manager, Project Superintendent, QC Manager, Alternate QC Manager, Environmental Manager, and subcontractor representatives. Each subcontractor who will be assigned QC responsibilities must have a principal of the firm at the meeting.

1.5.1.3 Quality Control (QC) Meetings

After the start of construction, conduct weekly QC meetings led by the QC

Manager at the work site with the Project Superintendent, and the other personnel as necessary. The QC Manager is to prepare the minutes of the meeting and provide a copy to the Contracting Officer within 2 working days after the meeting. The Contracting Officer may attend these meetings. As a minimum, accomplish the following at each meeting:

- a. Review the minutes of the previous meeting.
- b. Review the schedule and the status of work and deficiencies/rework. Review the most current approved schedule (in accordance with schedule specification) and the status of work and deficiencies/rework.
- c. Review the status of submittals and Request For Information (RFIs).
- d. Review the work to be accomplished in the next 3 weeks as defined by the schedule section paragraph WEEKLY LOOK AHEAD in Section 01 32 17.00 20 COST-LOADED NETWORK ANALYSIS SCHEDULES (NAS) and all documentation required for that work.
- e. Review Testing Plan and Log including status of tests performed since last QC Meeting.
- f. Resolve QC and production problems. Discuss status of pending change orders.
- g. Address items that may require revising the QC Plan.
- h. Review Accident Prevention Plan (APP) and effectiveness of the safety program.
- i. Review environmental requirements and procedures.
- j. Review Environmental Management Plan.
- k. Review Waste Management Plan.
- l. Review the status of training completion.

1.5.2 Contractor Quality Control (CQC) Plan

Submit no later than 30 days after Contract Award, the CQC Plan proposed to implement the requirements FAR 52.246-12 Inspection of Construction. Design and Construction will be permitted to begin only after acceptance of the CQC Plan and other Contract requirements Design work is not permitted to start prior to approval of a Design Quality Control Plan.

1.5.2.1 Content of Contractor Quality Control (CQC) Plan

Provide a CQC Plan, prior to start of construction that includes a table of contents, with major sections identified, pages numbered sequentially, and that documents the proposed methods and responsibilities for accomplishing quality control during the construction of the project. The CQC Plan must at a minimum include the following sections:

- a. A description of the quality control organization and acknowledgment that the CQC staff will implement the three phase control system for all aspects of the work specified.
- b. An organizational chart showing the quality control organization with

individual names and job titles and lines of authority up to an executive of the company at the home office.

- c. NAMES AND QUALIFICATIONS: Names and qualifications, in resume format, (including position titles and durations for qualifying experiences) for each person in the QC organization. Include the Construction Quality Management (CQM) for Contractors course certifications for the QC personnel as required by the paragraph CONSTRUCTION QUALITY MANAGEMENT TRAINING.
- d. DUTIES, RESPONSIBILITY AND AUTHORITY OF QC PERSONNEL: Duties, responsibilities, and authorities of each person in the QC organization.
- e. OUTSIDE ORGANIZATIONS: A listing of outside organizations, such as architectural and consulting engineering firms, that will be employed by the Contractor and a description of the services these firms will provide.
- f. APPOINTMENT LETTERS: Letters signed by an officer of the firm appointing the QC Manager and Alternate QC Manager, *Design Quality Control Manager*, and stating that they are responsible for implementing and managing the QC program as described in this Contract. Include in this letter the responsibility of the QC Manager and Alternate QC Manager to implement and manage the three phases of control, and their authority to stop work that is not in compliance with the Contract. Letters of direction are to be issued by the QC Manager to outline duties, authorities, and responsibilities. Include copies of the letters in the QC Plan.
- g. SUBMITTAL PROCEDURES AND INITIAL SUBMITTAL REGISTER: Procedures for reviewing, approving, scheduling, and managing submittals, including those of subcontractors, *designers of record, consultants, architect-engineers (AE)*, offsite fabricators, suppliers, and purchasing agents. Provide the name(s) of the person(s) in the QC organization authorized to review and certify submittals prior to approval. Provide the initial submittal of the Submittal Register as specified in Section 01 33 00 SUBMITTAL PROCEDURES.
- h. TESTING LABORATORY INFORMATION: Testing laboratory information required by the paragraph ACCREDITATION REQUIREMENTS, as applicable.
- i. TESTING PLAN AND LOG: A Testing Plan and Log that includes the tests required, associated feature of work required, referenced by the specification paragraph number requiring the test, the frequency, and the person responsible for each test.
- j. Procedures to complete *design and* construction deficiencies from identification through acceptable corrective action. Establish verification procedures that identified deficiencies have been corrected. This phase is performed prior to beginning work on each definable feature of work, after all required plans, documents, materials are approved, and after copies are at the work site.
- k. Reporting procedures, including proposed reporting formats.
- l. Procedures for submitting and reviewing design changes/variations prior to submission to the Contracting Officer.
- m. LIST OF DEFINABLE FEATURES: A Definable Feature of Work (DFOW) is a

task that is separate and distinct from other tasks and has control requirements and work crews unique to that task. A DFOW is identified by different trades or disciplines, or it is work by the same trade in a different environment. A DFOW is by definition any item or activity on the construction schedule, and the schedule specification provides direction regarding how the DFOWs are to be structured. Include in the list of DFOWs for all activities on the Construction Schedule. Provide separate DFOWs in the Network Analysis Schedule for each design development stage and submittal package. Although each section of the specifications can generally be considered as a definable feature of work, there are frequently more than one definable features under a particular section. Identify the specification section number and schedule activity ID for each DFOW listed. The DFOW list will be reviewed in coordination with the construction schedule and agreed upon during the Coordination of Mutual Understanding Meeting.

- n. PROCEDURES FOR PERFORMING AND TRACKING THE THREE PHASES OF CONTROL: Identify procedures used to ensure the three phases of control to manage the quality on this project. For each Definable Feature of Work (DFOW), a Preparatory and Initial phase checklist will be filled out during the Preparatory and Initial phase meetings. Conduct the Preparatory and Initial Phases and meetings with a view towards obtaining quality construction by planning ahead and identifying potential problems for each DFOW.

1.5.2.2 Additional Requirements for Design Quality Control (DQC) Plan

The following additional requirements apply to the DQC Plan:

- a. Submit and maintain a DQC Plan as an effective quality control program which assures that all services required by this Contract are performed and provided in a manner that meets professional architectural and engineering quality standards. As a minimum, all documents must be technically reviewed by competent, independent reviewers identified in the DQC Plan. The same element that produced the product may not perform the Design Quality Control Review. Correct errors and deficiencies in the design documents prior to submitting them to the Government.
- b. Include the design schedule in the master project schedule, showing the sequence of events involved in carrying out the project design tasks within the specific Contract period. Schedule must include sufficient detail to identify all major design tasks, including those that control the flow of work. Include review and correction periods associated with each item. Schedule must be a forward planning as well as a project monitoring tool. The schedule reflects calendar days and not dates for each activity. If the schedule is changed, submit a revised schedule reflecting the change within 7 calendar days.
- c. Include in the DQC Plan the discipline-specific checklists to be used during the design and quality control of each submittal. Submit at each design phase as part of the project documentation these completed discipline-specific checklists. ER 1110-3-12 provides some useful information in developing checklists.
- d. Implement the DQC Plan by a Design Quality Control Manager who has the responsibility of being cognizant of and assuring that all documents on the project have been coordinated and who coordinates work with and reports to the Contracting Officer via the QC Manager. Notify the

Contracting Officer, in writing, of the name of the individual and the name of an alternate person assigned to the position.

- e. Provide Quality Control Documentation procedures such as QC review sets and QC comments to demonstrate that cross checking of all engineering discipline's design drawings and specifications has taken place. The QC review documentation must exhibit a checking process of the design documents for completeness, accuracy, and constructability.
- f. Names of the individuals, including their respective firm names, who will be serving as the Designer of Record (DOR) in their respective design discipline.
- g. Submit a formal Communication Plan that indicates the frequency of design meetings and what information is covered in those meetings, key design decision points tied to the Network Analysis Schedule and how the DOR plans to include the Government in those decisions, peer review procedures, interdisciplinary coordination, design review procedures, and comment resolution.

The Communication Plan must emphasize key decisions and possible problems the Contractor and Government may encounter during the design phase of the project. Provide a plan to discuss design alternatives and design coordination with the stakeholders at the key decision points as they arise on the project. Identify individual stakeholders and suggested communication methods that will be employed to expedite and facilitate each anticipated critical decision. Communication methods may include: Concept Design Workshop, over-the-shoulder review meetings, presentation at client's office, lifecycle cost analysis presentation, technical phone conversation, and formal review meeting. The design portion of the Communication Plan must be written by the DQC Manager and confirmed during the Post Award Kick-off Partnering. Update the Communication Plan at every Partnering meeting.

- h. A statement of Life Safety and Fire Protection Features Inspections and Testing must be prepared by the Fire Protection DOR. Examples of life safety and fire protection features include, but are not limited to, water distribution systems including fire pumps and fire hydrants, fire resistive assemblies such as fire rated walls/partitions, through-penetration firestop systems, spray-applied fireproofing of structural components, fire alarm and detection systems, fire suppression and standpipe systems, means of egress components, emergency and exit lighting fixtures. The plan must include a listing of the individuals, approved agencies or firms that will be retained for conducting the required inspections and tests accompanied by a description of individual inspector's experience, and a copy of all required certifications. Additional copies of this plan must be submitted to the NAVFAC Fire Protection Engineer and the Installation Fire Chief. This plan must include the following:
 - (1) Comprehensive list of systems, components or features to be inspected and tested.
 - (2) Description of performance verification testing activities for each system or component.
 - (3) Procedures and schedules for functional performance tests of all systems requiring functional testing.

- i. Procedures for ensuring the design documents are submitted in accordance with FC 1-300-09N, Navy and Marine Corps Design Procedures and other procedures to ensure disciplines have been properly coordinated to eliminate conflicts.

1.5.3 Acceptance of the Quality Control (QC) and Design Quality Control (DQC) Plan

The Contracting Officer's acceptance of the Contractor QC Plan and Design Quality Control Plan is required prior to the start of design and construction. The Contracting Officer reserves the right to require changes in the QC and DQC Plan and operations as necessary, including removal or addition of personnel, to ensure the specified quality of work. The Contracting Officer reserves the right to interview any member of the QC and DQC organization at any time to verify the submitted qualifications. All QC and DQC organization personnel are subject to acceptance by the Contracting Officer. The Contracting Officer may require the removal of any individual for non-compliance with quality requirements specified in the Contract.

1.5.4 Preliminary Construction Work Authorized Prior to Acceptance

The only construction work that is authorized to proceed prior to the acceptance of the QC Plan is mobilization of storage and office trailers, temporary utilities, and surveying with specific prior approval of the Contracting Officer.

1.5.5 Notification of Changes

Notify the Contracting Officer, in writing, of any proposed changes in the QC Plan or changes to the QC organization personnel. Proposed changes are subject to acceptance by the Contracting Officer.

1.6 QUALITY CONTROL (QC) ORGANIZATION

1.6.1 Quality Control (QC) Manager

1.6.1.1 Duties

Provide a QC Manager at the work site to implement and manage the QC program.

The only duties and responsibilities of the QC Manager are to manage and implement the QC program on this Contract. The QC Manager must attend the partnering meetings, QC Plan Meetings, Coordination and Mutual Understanding Meeting, conduct the QC meetings, perform the three phases of control, perform submittal review and approval, ensure testing is performed and provide QC certifications and documentation required in this Contract. The QC Manager is responsible for managing and coordinating the three phases of control and documentation performed by testing laboratory personnel and any other inspection and testing personnel required by this Contract. The QC Manager is the manager of all QC activities.

1.6.1.2 Qualifications

The QC Manager must be an individual with a minimum of 10 years combined experience in the following positions: Project Superintendent, QC Manager, Project Manager, Project Engineer or Construction Manager on similar size and type construction Contracts which included the major trades that are part of this Contract. The individual must have at least 5 years experience as a QC Manager. The individual must be familiar with the

requirements of EM 385-1-1 and have experience in the areas of hazard identification, safety compliance, and sustainability.

The QC Manager and all members of the QC organization must be capable of reading, writing, and conversing fluently in the English language.

1.6.1.3 Construction Quality Management Training

In addition to the above experience and education requirements, the QC Manager and all members of the QC team must have completed the CQM for Contractors course. If the QC Manager does not have a current certification, obtain the CQM for Contractors course certification within 90 days of award. This course is periodically offered by the Naval Facilities Engineering Systems Command and the Army Corps of Engineers. Contact the Contracting Officer for information on the next scheduled class.

The Construction Quality Management Training certificate expires after 5 years. If the QC Manager's certificate has expired, retake the course to remain current.

1.6.2 Organizational Changes

Maintain the QC staff with personnel as required by the specification section at all times. When it is necessary to make changes to the QC staff, revise the CQC Plan to reflect the changes and submit the changes to the Contracting Officer for acceptance.

1.6.3 Design Quality Control (DQC) Manager

The DQC Manager must be a member of the QC organization, must coordinate actions with the QC Manager, and must not be subordinate to the Project Superintendent or the Project Manager.

1.6.3.1 Qualifications

- a. A minimum of 5 years experience as a design Architect or Engineer on similar size and type designs / or design-build Contracts. Provide education, experience, and management capabilities on similar size and type Contracts.
- b. Be a registered professional engineer or architect with an active registration. Provide proof of registration as part of the resume submittal package.
- c. Complete the US Army Corps of Engineers (USACE) course entitled "Construction Quality Management (CQM) for Contractors."

1.6.3.2 Responsibilities

- a. Be responsible for the design integrity, professional design standards, and all design services required.
- b. Be a member of the DOR firm but may not be the DOR or the person stamping and approving final construction drawings or approving submittals.
- c. Be responsible for development of the design portion of the QC Plan, incorporation and maintenance of the approved Design Schedule, and the preparation of DQC Reports and minutes of all design meetings.

- d. Participate in the Post Award Kick-Off, all design planning meetings, design presentations, partnering, and QC meetings.
- e. Implement the DQC Plan and must remain on staff involved with the project until completion of the project.
- f. Be cognizant of and assure that all design documents on the project have been developed in accordance with the Contract.
- g. Provide Design Quality Control Documentation (DQCD) which indicates design coordination of the engineering disciplines. Submit DQCD with the pre-final and final design submittals as required in Section 01 33 00 SUBMITTAL PROCEDURES.
- h. Develop the submittal register. Coordinate with each DOR to determine what items need to be submitted, and who needs to approve.
- i. Provide QC certification for design compliance.
- j. Certify and sign statement on each invoice that all work to be paid to the DOR under the invoice has been completed in accordance with the Contract requirements.
- k. Prepare weekly DQC Reports that document the work the design team accomplished that week.

1.6.4 Alternate Quality Control (QC) Manager Duties and Qualifications

Designate an alternate for the QC Manager at the work site to serve in the event of the designated QC Manager's absence. The period of absence may not exceed 2 weeks at one time, and not more than 30 workdays during a calendar year. The qualification requirements for the Alternate QC Manager must be the same as for the QC Manager.

1.6.5 Designer of Record (DOR) Qualifications

The DOR must be a registered design professional, retained by the Prime Contractor, responsible for the overall design and review of submittal documents prepared by others. The DOR is registered or licensed to practice their respective design profession as defined by the statutory requirements of the professional registration laws in the state in which the design professional works. The DOR cannot serve as the DQC Manager.

1.7 SUBMITTAL AND DELIVERABLES REVIEW AND APPROVAL

Procedures for submission, review and approval of submittals are described in Section 01 33 00 SUBMITTAL PROCEDURES. Procedures must include field verification of relevant dimensions and component characteristics by the QC organization prior to submittal being sent to the Contracting Officer. The CQC organization is responsible for certifying that all submittals and deliverables are in compliance with the Contract.

1.8 THREE PHASES OF CONTROL

CQC enables the Contractor to ensure that the construction, including that of subcontractors and suppliers, complies with the requirements of the Contract. At least three phases of control must be conducted by the QC Manager to adequately cover both on-site and off-site work for each

definable feature of the construction work as follows:

1.8.1 Preparatory Phase

Document the results of the preparatory phase actions by separate minutes prepared by the QC Manager and attach to the daily CQC report. Instruct applicable workers as to the acceptable level of workmanship required to meet Contract specifications.

Notify the Contracting Officer at least 2 business days in advance of each preparatory phase meeting. The meeting will be conducted by the QC Manager and attended by the Project Superintendent, and the foreman responsible for the DFO. When the DFO will be accomplished by a subcontractor, that subcontractor's foreman must attend the preparatory phase meeting. This phase is performed prior to beginning work on each definable feature of work, after all required plans/documents/materials are approved/accepted, and after copies are at the work site. Perform the following prior to beginning work on each DFO:

- a. Review each paragraph of the applicable specification sections, reference codes, and standards. Make available during the preparatory inspection a copy of those sections of referenced codes and standards applicable to that portion of the work to be accomplished in the field. Maintain and make available in the field for use by Government personnel until final acceptance of the work.
- b. Review the Contract drawings.
- c. Verify that field measurements are as indicated on construction or shop drawings or both before confirming product orders, to minimize waste due to excessive materials.
- d. Verify that appropriate shop drawings and submittals for materials and equipment have been submitted and approved. Verify receipt of approved factory test results, when required.
- e. Review the testing plan and ensure that provisions have been made to provide the required QC testing.
- f. Examine the work area to ensure that the required preliminary work has been completed and complies with the Contract and ensure any deficiencies/rework items in the preliminary work have been corrected and confirmed by the Contracting Officer.
- g. Review coordination of product/material delivery to designated prepared areas to execute the work.
- h. Examine the required materials, equipment and sample work to ensure that they are on hand and conform to the approved shop drawings and submitted data and are properly stored.
- i. Check to assure that all materials and equipment have been tested, submitted, and approved.
- j. Discuss specific controls to be used, construction methods, construction tolerances, workmanship standards, and the approach that will be used to provide quality construction by planning ahead and identifying potential problems for each DFO. Ensure any portion of the plan requiring separate Contracting Officer acceptance has been

approved.

- k. Review the APP and appropriate Activity Hazard Analysis (AHA) to ensure that applicable safety requirements are met, and that required Safety Data Sheets (SDS) are submitted.

1.8.2 Initial Phase

Notify the Contracting Officer at least 2 business days in advance of each initial phase. When construction crews are ready to start work on a DFOW, conduct the initial phase with the Project Superintendent, and the foreman responsible for that DFOW. Observe the initial segment of the DFOW to ensure that the work complies with Contract requirements. Document the results of the initial phase in the daily CQC Report and in the Initial Phase Checklist. Repeat the initial phase for each new crew to work on-site when acceptable levels of specified quality are not being met. Indicate the exact location of initial phase for definable feature of work for future reference and comparison with follow-up phases. Perform the following for each DFOW:

- a. Check work to ensure that it is in full compliance with Contract requirements. Review minutes of the preparatory meeting.
- b. Verify adequacy of controls to ensure full Contract compliance. Verify required control inspection and testing comply with the Contract.
- c. Establish level of workmanship and verify that it meets the minimum acceptable workmanship standards. Compare with required sample panels as appropriate.
- d. Resolve any workmanship issues.
- e. Ensure that testing is performed by the approved laboratory.
- f. Check work procedures for compliance with the APP and the appropriate AHA to ensure that applicable safety requirements are met.
- g. Review project specific work plans (i.e., HAZMAT Abatement, Stormwater Management) to ensure all preparatory work items have been completed and documented.

1.8.3 Follow-Up Phase

Perform the following for on-going DFOW daily, or more frequently as necessary, until the completion of each DFOW. The Final Follow-Up for any DFOW will clearly note in the daily report the DFOW is completed, and all deficiencies/rework items have been completed in accordance with the paragraph DEFICIENCY/REWORK ITEMS LIST. Each DFOW that has completed the Initial Phase and has not completed the Final Follow-up must be included on each daily report. If no work was performed on that DFOW for the period of that daily report, it must be so noted. Document all Follow-Up activities for DFOWs in the daily CQC Report:

- a. Ensure the work including control testing complies with Contract requirements until completion of that particular work feature. Record checks in the CQC documentation.
- b. Maintain the quality of workmanship required.

- c. Ensure that testing is performed by the approved laboratory.
- d. Ensure that deficiencies/rework items are being corrected. Conduct final follow-up checks and correct all deficiencies prior to the start of additional features of work which may be affected by the deficient work.
- e. Do not build upon nor conceal non-conforming work.
- f. Assure manufacturers' representatives have performed necessary inspections if required and perform safety inspections.

1.8.4 Additional Preparatory and Initial Phases

Conduct additional preparatory and initial phases on the same DFOW if the quality of on-going work is unacceptable, if there are changes in the applicable QC organization, if there are changes in the on-site production supervision or work crew, if work on a DFOW has not started within 45 days of the initial preparatory meeting or has resumed after 45 days of inactivity, or if other problems develop.

1.8.5 Notification of Three Phases of Control for Off-Site Work

Notify the Contracting Officer at least 2 weeks prior to the start of the preparatory and initial phases.

1.8.6 Deficiency/Rework Items List

The QC Manager must maintain a list of work that does not comply with the Contract, identifying what items need to be corrected, the activity ID number associated with the item, the date the item was originally discovered, the date the item will be corrected by, and the date the item was corrected.

The QC Manager reviews the list at each weekly QC Meeting:

- a. There is no requirement to report a deficiency/rework item that is corrected the same day it is discovered.
- b. No successor task may be advanced beyond the preparatory phase meeting until all deficiencies/rework items have been cleared by the QC Manager and concurred with by the Contracting Officer. This must be confirmed as part of the Preparatory Phase activities.
- c. Attach a copy of the "Deficiency/Rework Items List" to the last daily CQC Report of each month.
- d. The Contractor is responsible for including those items identified by the Contracting Officer.
- e. All deficiencies/rework items must be confirmed as corrected by the QC Manager, and concurred by the Contracting Officer, prior to commencement of any completion inspections per paragraph COMPLETION INSPECTIONS unless specifically exempted by the Contracting Officer.
- f. Non-Compliance with these requirements is grounds for removal in accordance with paragraph ACCEPTANCE OF THE QUALITY CONTROL (QC) and DESIGN QUALITY CONTROL (DQC) PLAN.

- g. All delays, concurrent or related to failure to manage, monitor, control, and correct deficiencies/rework items are entirely the responsibility of the Contractor and can not be made the subject, or any component of any request for additional time or compensation.

1.9 TESTING

Perform specified or required tests to verify that control measures are adequate to provide a product which conforms to Contract requirements. Upon request, furnish to the Government duplicate samples of test specimens for possible testing by the Government. Testing includes operation and acceptance tests when specified. Procure the services of an U.S. Army Corps of Engineers approved testing laboratory or establish an approved testing laboratory at the project site or within 50 miles. Perform the following activities and record and provide the following data:

- a. Verify that testing procedures comply with Contract requirements.
- b. Verify that facilities and testing equipment are available and comply with testing standards.
- c. Check test instrument calibration data against certified standards.
- d. Verify that recording forms and test identification control number system, including all test documentation requirements, have been prepared.
- e. Record results of all tests taken, both passing and failing on the CQC report for the date taken. Specification paragraph reference, location where tests were taken, and the sequential control number identifying the test. If approved by the Contracting Officer, actual test reports are submitted later with a reference to the test number and date taken. Provide an information copy of tests performed by an offsite or commercial test facility directly to the Contracting Officer. Failure to submit timely test reports as stated results in nonpayment for related work performed and disapproval of the test facility for this Contract.

1.9.1 Accreditation Requirements

Construction materials testing laboratories must be accredited by a laboratory accreditation authority and must submit a copy of the Certificate of Accreditation and Scope of Accreditation. The laboratory's scope of accreditation must include the appropriate ASTM standards (ASTM E329, ASTM C1077, ASTM D3666, ASTM D3740, ASTM E543) listed in the technical sections of the specifications. Laboratories engaged in Hazardous Materials Testing must meet the requirements of OSHA and EPA. The policy applies to the specific laboratory performing the actual testing, not just the Corporate Office.

1.9.2 Laboratory Accreditation Authorities

Laboratory Accreditation Authorities include the National Voluntary Laboratory Accreditation Program (NVLAP) administered by the National Institute of Standards and Technology at <https://www.nist.gov/nvlap>, the American Association of State Highway and Transportation Officials (AASHTO) Accreditation Program at <http://www.aashtoresource.org/aap/overview>, International Accreditation Services, Inc. (IAS) at <https://www.iasonline.org/>, U.S. Army Corps of Engineers Materials Testing Center (MTC) at <https://www.erd.usace.army.mil/Media/Fact-Sheets/>

[Fact-Sheet-Article-View/Article/476661/materials-testing-center/](#), the American Association for Laboratory Accreditation (A2LA) program at <https://a2la.org/>, the Washington Association of Building Officials (WABO) at <https://www.wabo.org/> (Approval authority for WABO is limited to projects within Washington State), and the Washington Area Council of Engineering Laboratories (WACEL) at <https://www.wacel.org/lab-accreditation-and-inspection-agency-audit-programs/laboratory-accreditation-program/> (Approval authority by WACEL is limited to projects within Facilities Engineering Command (FEC) Washington geographical area).

1.9.3 Capability Check

The Contracting Officer retains the right to check laboratory equipment in the proposed laboratory and the laboratory technician's testing procedures, techniques, and other items pertinent to testing, for compliance with the standards set forth in this Contract. Laboratories utilized for testing soils, concrete, asphalt, and steel must meet criteria detailed in [ASTM D3740](#) and [ASTM E329](#).

1.9.4 Test Results

Cite applicable Contract requirements, tests or analytical procedures used. Provide actual results and include a statement that the item tested or analyzed conforms or fails to conform to specified requirements. If the item fails to conform, notify the Contracting Officer immediately. Conspicuously stamp the cover sheet for each report in large red letters "CONFORMS" or "DOES NOT CONFORM" to the specification requirements, whichever is applicable. Test results must be signed by a testing laboratory representative authorized to sign certified test reports. Furnish the signed reports, certifications, and other documentation to the Contracting Officer via the QC Manager. [Furnish a summary report of field tests at the end of each month, in accordance with paragraph DOCUMENTATION AND INFORMATION FOR THE CONTRACTING OFFICER.](#)

1.9.5 Test Reports and Monthly Summary Report of Tests

[Furnish the signed reports, certifications, and a summary report of field tests at the end of each month to the Contracting Officer. Attach a copy of the summary report to the last daily CQC Report of each month.](#)

1.10 COMPLETION INSPECTIONS

1.10.1 Punch-Out Inspection

Near the completion of all work or any increment thereof, established by a completion time stated in the Contract Clause entitled "Commencement, Prosecution, and Completion of Work," or stated elsewhere in the specifications, the QC Manager must conduct an inspection of the work and develop a "punch list" of items which do not conform to the approved drawings, specifications, and Contract. Include in the punch list any remaining items on the "Deficiency/Rework Items List", that were not corrected prior to the Punch-Out Inspection as approved by the Contracting Officer in accordance with the paragraph DEFICIENCY/REWORK ITEMS LIST. Include within the punch list the estimated date by which the deficiencies will be corrected. Provide a copy of the punch list to the Contracting Officer.

The QC Manager, or staff, must make follow-on inspections to ascertain that

all deficiencies have been corrected. All punch list items must be confirmed as corrected by the QC Manager and concurred by the Contracting Officer. Once this is accomplished, notify the Government that the facility is ready for the Government "Pre-Final Inspection".

1.10.2 Pre-Final Inspection

The Government and QC Manager will perform this inspection to verify that the facility is complete and ready to be occupied. A Government "Pre-Final Punch List" will be documented by the QC Manager as a result of this inspection. The QC Manager will ensure that all items on this list are corrected and concurred by the Contracting Officer prior to notifying the Government that a "Final" inspection with the Client can be scheduled. All items noted on the "Pre-Final" inspection must be corrected and concurred by the Contracting Officer in a timely manner and be accomplished before the Contract completion date for the work, or any increment thereof, if the project is divided into increments by separate completion dates unless exceptions are directed by the Contracting Officer.

1.10.3 Final Acceptance Inspection

Notify the Contracting Officer at least 14 calendar days prior to the date a final acceptance inspection can be held. State within the notice that all items previously identified on the pre-final punch list will be corrected and acceptable, along with any other unfinished Contract work, by the date of the final acceptance inspection. The Contractor must be represented by the QC Manager, the Project Superintendent, and others deemed necessary. Attendees for the Government will include the Contracting Officer, other Government QA personnel, and personnel representing the Client. Failure of the Contractor to have all Contract work acceptably complete for this inspection will be cause for the Contracting Officer to bill the Contractor for the Government's additional inspection cost in accordance with the Contract Clause entitled "Inspection of Construction."

1.11 QUALITY CONTROL (QC) CERTIFICATIONS

1.11.1 Contractor Quality Control (CQC) Report Certification

Contain the following statement within the CQC Report: "On behalf of the Contractor, I certify that this report is complete and correct and equipment and material used, and work performed during this reporting period is in compliance with the Contract drawings and specifications to the best of my knowledge, except as noted in this report."

1.11.2 Completion Certification

Upon completion of work under this Contract, the QC Manager must furnish a certificate to the Contracting Officer attesting that "the work has been completed, inspected, tested and is in compliance with the Contract." Provide a copy of this final QC Certification for completion to the preparer of the Operation & Maintenance (O&M) documentation.

1.11.3 Invoice Certification

Furnish a certificate to the Contracting Officer with each payment request, signed by the QC Manager, attesting that as-built drawings are current, coordinated and attesting that the work for which payment is requested, including stored material, complies with Contract requirements.

1.12 DOCUMENTATION AND INFORMATION FOR THE CONTRACTING OFFICER

1.12.1 Construction Documentation

Reports are required for each day that work is performed and must be attached to the Contractor Quality Control Report prepared for the same day. Maintain current and complete records of on-site and off-site QC program operations and activities. Reports are required for each day work is performed. Account for each calendar day throughout the life of the Contract.

The Project Superintendent and the QC Manager must prepare and sign the Contractor Production and CQC Reports, respectively. Every space on the forms must be filled in. Use N/A if nothing can be reported in one of the spaces. The reporting of work must be identified by terminology consistent with the construction schedule. In the "Remarks" sections of the reports, enter pertinent information including directions received, problems encountered during construction, work progress and delays, conflicts or errors in the drawings or specifications, field changes, safety hazards encountered, instructions given and corrective actions taken, delays encountered, a record of visitors to the work site, quality control problem areas, deviations from the QC Plan, construction deficiencies encountered, and meetings held. For each entry in the report(s), identify the Schedule Activity No. that is associated with the entered remark.

1.12.2 Quality Control Activities

CQC and Contractor Production reports will be prepared daily to maintain current records providing factual evidence that required quality control activities and tests have been performed. Include in these records the work of subcontractors and suppliers on an acceptable form that includes, as a minimum, the following information:

- a. The name and area of responsibility of the Contractors and any subcontractors.
- b. Operating plant/equipment with hours worked, idle, or down for repair.
- c. Work performed each day, giving location, description, and by whom. When a Network Analysis Schedule (NAS) is used, identify each item of work performed each day by NAS activity number.
- d. Control phase activities performed. Preparatory, and Initial phase Checklists associated with the DFOW referenced to the construction schedule. Follow-up phase activities identified to the DFOW. If testing activities are associated with the Follow-up phase activities for a specific DFOW note this and include those reports.
- e. Test and control activities performed with results and references to specifications and drawings requirements. Identify the control phase (Preparatory, Initial, Follow-up). List of deficiencies noted, along with corrective action in accordance with the paragraph DEFICIENCY/REWORK ITEMS LIST.
- f. Quantity of materials received at the site with statement as to acceptability, storage, and reference to specifications and drawings requirements.
- g. Submittals and deliverables reviewed, with Contract reference, by whom,

and action taken.

- h. Offsite surveillance activities, including actions taken.
- i. Job safety evaluations stating what was checked, results, and instructions or corrective actions.
- j. Instructions given/received and conflicts in plans and specifications.
- k. Provide documentation of design quality control activities. For independent design reviews, provide, as a minimum, identification of the Design Quality Control Review team and their review comments, responses and the record of resolution of the comments.

1.12.3 Verification Statement

Indicate a description of trades working on the project; the number of personnel working; weather conditions encountered; and any delays encountered. Cover both conforming and deficient features and include a statement that equipment and materials incorporated in the work and workmanship comply with the Contract.

Furnish the original and one copy of these records in report form to the Government by 10:00 AM the next working day after the date covered by the report. As a minimum, prepare and submit one report for every 7 days of no work and on the last day of a no work period. All calendar days need to be accounted for throughout the life of the Contract. The first report following a day of no work will be for that day only. Reports need to be signed and dated by the QC Manager. Include copies of test reports and copies of reports prepared by all subordinate quality control personnel within the QC Manager Report.

1.12.4 Quality Control Validation

Establish and maintain the following in an electronic folder. Divide folder into a series of tabbed sections as shown below. Ensure folder is updated at each required progress meeting.

- a. CQC Meeting minutes in accordance with paragraph QUALITY CONTROL (QC) MEETINGS.
- b. All completed Preparatory and Initial Phase Checklists, arranged by specification section, further sorted by DFOV referenced to the construction schedule. Submit each individual Phase Checklist the day the phase event occurs as part of the CQC daily report.
- c. All milestone inspections, arranged by Activity Number referenced to the construction schedule.
- d. An up-to-date copy of the Testing Plan and Log with supporting field test reports, arranged by specification section referenced to the DFOV to which individual reports results are associated. Individual field test reports will be submitted within 2 working days after the test is performed in accordance with the paragraph QUALITY CONTROL ACTIVITIES.
- e. Copies of all Contract modifications, arranged in numerical order. Also include documentation that modified work was accomplished.

- f. An up-to-date copy of the paragraph DEFICIENCY/REWORK ITEMS LIST.
- g. Upon commencement of Completion Inspections of the entire project or any defined portion, maintain up-to-date copies of all punch lists issued by the QC staff to the Contractor and subcontractors and all punch lists issued by the Government in accordance with the paragraph COMPLETION INSPECTIONS.

1.12.5 Testing Plan and Log

As tests are performed, the QC Manager will record on the "Testing Plan and Log" the date the test was performed and the date the test results were forwarded to the Contracting Officer. Attach a copy of the updated "Testing Plan and Log" to the last daily CQC Report of each month. Provide a copy of the final "Testing Plan and Log" to the preparer of the Operation & Maintenance (O&M) documentation.

1.12.6 As-Built Drawings

The QC Manager must ensure the as-built drawings, required by Section 01 78 00 CLOSEOUT SUBMITTALS are kept current on a daily basis and marked to show deviations which have been made from the Contract drawings. The as-built drawings document commences with the QC Manager ensuring all amendments, or changes to the Contract prior to Contract award are accurately noted in the initial document set creating the accurate baseline of the Contract prior to any work starting. Ensure each deviation has been identified with the appropriate modifying documentation (e.g., PC No., Modification No., Request for Information No.). The QC Manager must initial each revision. Upon completion of work, the QC Manager will furnish a certificate attesting to the accuracy of the as-built drawings prior to submission to the Contracting Officer.

1.13 NOTIFICATION ON NON-COMPLIANCE

The Contracting Officer will notify the Contractor of any detected non-compliance with the Contract. Take immediate corrective action after receipt of such notice. Such notice, when delivered to the Contractor at the work site, is deemed sufficient for the purpose of notification. If the Contractor fails or refuses to comply promptly, the Contracting Officer may issue an order stopping all or part of the work until satisfactory corrective action has been taken. No part of the time lost due to such stop orders will be made the subject of a claim for extension of time for excess costs or damages by the Contractor.

1.14 DELIVERY, STORAGE, AND HANDLING

Designate receiving/storage areas for incoming material to be delivered according to installation schedule and to be placed convenient to work area in order to minimize waste due to excessive materials handling and misapplication. Store and handle materials in a manner as to prevent loss from weather and other damage. Keep materials, products, and accessories covered and off the ground, and store in a dry, secure area. Prevent contact with material that may cause corrosion, discoloration, or staining. Protect all materials and installations from damage by the activities of other trades.

PART 2 PRODUCTS

Not Used

PART 3 EXECUTION

Not Used

-- End of Section --

SECTION 01 50 00

TEMPORARY CONSTRUCTION FACILITIES AND CONTROLS

11/20, CHG 3: 08/24

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN WATER WORKS ASSOCIATION (AWWA)

AWWA C511 (2017; R 2021) Reduced-Pressure Principle
Backflow Prevention Assembly

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 70 (2023) National Electrical Code

NFPA 241 (2022) Standard for Safeguarding
Construction, Alteration, and Demolition
Operations

U.S. ARMY CORPS OF ENGINEERS (USACE)

EM 385-1-1 (2024) Safety -- Safety and Occupational
Health (SOH) Requirements

U.S. FEDERAL HIGHWAY ADMINISTRATION (FHWA)

MUTCD (2009; Rev 2012) Manual on Uniform Traffic
Control Devices

1.2 SUBMITTALS

Government approval is required for submittals with a "G" classification. Submittals not having a "G" classification are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Construction Site Plan; G

Traffic Control Plan; G

Haul Road Plan; G

Contractor Computer Cybersecurity Compliance Statements; G

Contractor Temporary Network Cybersecurity Compliance Statements; G

SD-06 Test Reports

Backflow Preventer Tests

SD-07 Certificates

Backflow Tester Certification

Backflow Preventers Certificate of Full Approval

1.3 CONSTRUCTION SITE PLAN

Prior to the start of work, submit for Government approval a site plan showing the locations and dimensions of temporary facilities (including layouts and details, equipment and material storage area (onsite and offsite), and access and haul routes, avenues of ingress/egress to the fenced area and details of the fence installation. Identify any areas which may have to be graveled to prevent the tracking of mud. Indicate if the use of a supplemental or other staging area is desired. Show locations of safety and construction fences, site trailers, construction entrances, trash dumpsters, temporary sanitary facilities, and worker parking areas.

1.4 BACKFLOW PREVENTERS CERTIFICATE

1.4.1 Backflow Tester Certificate

Prior to testing, submit to the Contracting Officer certification issued by the State or local regulatory agency attesting that the backflow tester has successfully completed a certification course sponsored by the regulatory agency. Tester must not be affiliated with a company participating in other phases of this Contract.

1.4.2 Backflow Prevention Training Certificate

Submit a certificate recognized by the State or local authority that states the Contractor has completed at least 10 hours of training in backflow preventer installations. The certificate must be current.

1.5 DOD CONDITION OF READINESS (COR)

DOD will set the Condition of Readiness (COR) based on the weather forecast for sustained winds 50 knots (58 mph) or greater. Contact the Contracting Officer for the current COR setting.

Monitor weather conditions a minimum of twice a day and take appropriate actions according to the approved Emergency Plan in the accepted Accident Prevention Plan, EM 385-1-1 Emergency Plan requirements and the instructions below.

Unless otherwise directed by the Contracting Officer, comply with:

- a. Condition FOUR (Sustained winds of 58 mph or greater expected within 72 hours): Normal daily jobsite cleanup and good housekeeping practices. Collect and store in piles or containers scrap lumber, waste material, and rubbish for removal and disposal at the close of each work day. Maintain the construction site including storage areas, free of accumulation of debris. Stack form lumber in neat piles less than 3.3 feet high. Remove all debris, trash, or objects that could become missile hazards. Review requirements pertaining to "Condition THREE" and continue action as necessary to attain "Condition FOUR" readiness. Contact Contracting Officer for weather and COR updates and completion of required actions.

- b. Condition THREE (Sustained winds of 58 mph or greater expected within 48 hours): Maintain "Condition FOUR" requirements and commence securing operations necessary for "Condition ONE" which cannot be completed within 18 hours. Cease all routine activities which might interfere with securing operations. Commence securing and stow all gear and portable equipment. Make preparations for securing buildings. Reinforce or remove formwork and scaffolding. Secure machinery, tools, equipment, materials, or remove from the jobsite. Expend every effort to clear all missile hazards and loose equipment from general base areas. Contact Contracting Officer for weather and COR updates and completion of required actions. Review requirements pertaining to "Condition TWO" and continue action as necessary to attain "Condition THREE" readiness.
- c. Condition TWO (Sustained winds of 58 mph or greater expected within 24 hours): Secure the jobsite, and leave Government premises.
- d. Condition ONE. (Sustained winds of 58 mph or greater expected within 12 hours): Contractor access to the jobsite and Government premises is prohibited.

PART 2 PRODUCTS

2.1 TEMPORARY SIGNAGE

2.1.1 Bulletin Board

Prior to the commencement of work activities, provide a clear weatherproof covered bulletin board not less than 36 by 48 inches in size for displaying the Equal Employment Opportunity poster, a copy of the wage decision contained in the Contract, Wage Rate Information poster, Safety and Health Information as required by EM 385-1-1 and other information approved by the Contracting Officer. Coordinate requirements herein with 01 35 26 GOVERNMENTAL SAFETY REQUIREMENTS. Locate the bulletin board at the project site in a conspicuous place easily accessible to all employees, and in location as approved by the Contracting Officer.

2.1.2 Project Identification Signs

The requirements for the signs, their content, and location are as indicated. Erect signs within 15 days after receipt of the notice to proceed. Correct the data required by the safety sign daily, with light colored metallic or non-metallic numerals.

2.1.3 Warning Signs

Post temporary signs, tags, and labels to give workers and the public adequate warning and caution of construction hazards according to the EM 385-1-1. Attach signs to the perimeter fencing every 150 feet warning the public of the presence of construction hazards. Signs must require unauthorized persons to keep out of the construction site. Correct the data required by safety signs daily. Post signs at all points of entry designating the construction site as a hard hat area.

2.2 TEMPORARY TRAFFIC CONTROL

2.2.1 Haul Roads

Construct access and haul roads necessary for proper prosecution of the work under this Contract in accordance with EM 385-1-1. Construct with suitable grades and widths; avoid sharp curves, blind corners, and dangerous cross traffic. Submit haul road plan for approval. Provide necessary lighting, signs, barricades, and distinctive markings for the safe movement of traffic. The method of dust control, although optional, must be adequate to ensure safe operation at all times. Location, grade, width, and alignment of construction and haul roads are subject to approval by the Contracting Officer's Representative. Lighting must be adequate to assure full and clear visibility for full width of haul road and work areas during any night work operations.

2.2.2 Barricades

Erect and maintain temporary barricades to limit public access to hazardous areas. Barricades are required whenever safe public access to paved areas such as roads, parking areas or sidewalks is prevented by construction activities or as otherwise necessary to ensure the safety of both pedestrian and vehicular traffic. Securely place barricades clearly visible with adequate illumination to provide sufficient visual warning of the hazard during both day and night.

2.3 FENCING

Provide fencing along the construction site and at all open excavations and tunnels to control access by unauthorized personnel. Safety fencing must be highly visible to be seen by pedestrians and vehicular traffic. All fencing must meet the requirements of EM 385-1-1. Remove the fence upon completion and acceptance of the work.

2.3.1 Polyethylene Mesh Safety Fencing

Temporary safety fencing must be a high visibility orange colored, high density polyethylene grid, a minimum of 48 inches high and maximum mesh size of 2 inches. Fencing must extend from the grade to a minimum of 48 inches above the grade and be tightly secured to T-posts spaced as necessary to maintain a rigid and taut fence. Fencing must remain rigid and taut with a minimum of 200 pounds of force exerted on it from any direction with less than 4 inches of deflection.

2.3.2 Chain Link Panel Fencing

Temporary panel fencing must be galvanized steel chain link panels 6 feet high. Multiple fencing panels may be linked together at the bases to form long spans as needed. Each panel base must be weighted down using sand bags or other suitable materials in order for the fencing to withstand anticipated winds while remaining upright. Fencing must remain rigid and taut with a minimum of 200 pounds of force exerted on it from any direction with less than 4 inches of deflection.

2.3.3 Post-Driven Chain Link Fencing

Temporary post-driven fencing must be galvanized chain link fencing 6 feet high supported by an tightly secured to galvanized steel posts driven below grade. Fence posts must be located on minimum 10 foot centers. Posts may

be set in various surfaces such as sand, soil, asphalt or concrete as necessary. Chain link fencing must remain rigid and taut with a minimum of 200 pounds of force exerted on it from any direction with less than 4 inches of deflection. Completely remove fencing and posts at the completion of construction and restore surfaces disturbed or damaged to its original condition. Locate and identify underground utilities prior to setting fence posts. Equip fence with a lockable gate. Gate must remain locked when construction personnel are not present.

2.4 TEMPORARY WIRING

Provide temporary wiring in accordance with EM 385-1-1, NFPA 241 and NFPA 70. Include monthly inspection and testing of all equipment and apparatus.

2.5 BACKFLOW PREVENTERS

Certificate of Full Approval from FCCCHR List, University of Southern California, attesting that the design, size and make of each backflow preventer has satisfactorily passed the complete sequence of performance testing and evaluation for the respective level of approval. Certificate of Provisional Approval is not acceptable.

Reduced pressure principle type conforming to the applicable requirements AWWA C511. Furnish backflow preventers complete with flanged connections rated for 150-pound pressure; valve bodies made of ductile iron; mounted gate valve and strainer; internal components constructed of 304 stainless steel.

PART 3 EXECUTION

3.1 EMPLOYEE PARKING

Construction Contract employees must park privately owned vehicles in an area designated by the Contracting Officer. Employee parking must not interfere with existing and established parking requirements of the Government installation.

3.2 AVAILABILITY AND USE OF UTILITY SERVICES AT NAVAL STATION GREAT LAKES

3.2.1 Temporary Utilities

Provide temporary utilities required for construction. Materials may be new or used, must be adequate for the required usage, not create unsafe conditions, and not violate applicable codes and standards.

3.2.2 Payment for Utility Services

- a. The Government will make all reasonably required utilities available from existing outlets and supplies, as specified in the Contract. Unless otherwise provided in the Contract, the amount of each utility service consumed will be charged to or paid at current prevailing rates. Rates are adjusted every October 1st and are good for one year.
- b. The point at which the Government will deliver such utilities or services and the quantity available must be coordinated with the Contracting Officer. Contractor shall pay all costs incurred in connecting, converting, and transferring the utilities to the work, including providing backflow-preventing devices on connections to domestic water lines; providing water and electric meters; and

providing transformers. Maintain utility services to existing facilities surrounding the site at all times. .

c. The Contractor may provide their own utilities.

3.2.3 Meters and Temporary Connections

Provide and maintain necessary temporary connections, distribution lines, and meters required to measure the amount of each utility used for the purpose of determining charges. Notify the Contracting Officer, in writing, 30 days before final electrical connection is desired so that a utilities contract can be established. The Government shall review and approve the temporary power plan prior to installation and final connection. Submit outage request for final temporary power and water connections 15 calendar days in advance. The Government will make the final electrical connection after inspection and approval of the Contractor's temporary wiring installation. Do not make the final electrical connection.

3.2.4 Advance Deposit

A Private Party General Terms and Conditions for will need to be completed prior to utilities being provided. The Contracting Officer can provide a blank copy of the GTC. An advance deposit for utilities consisting of an estimated month's usage or a minimum of \$500.00 will be required.

3.2.5 Final Meter Reading

Before completion of the work and final acceptance of the work by the Government, notify the Contracting Officer, in writing, 15 calendar days before termination is desired, include the appropriate outage request. The Government will take a final meter reading and disconnect service. Then the Contractor shall remove all the temporary distribution lines, meter, meter bases, and associated appurtenances. Contractor shall pay all costs incurred to return Government facilities and property to pre connection levels, repairing all damage that may have resulted from temporary utility connection or removal. Contractor shall pay all outstanding utility bills before final acceptance of the work by the Government.

3.2.6 Water

Make connections to existing facilities to provide water for construction purposes. All connections to the potable water system require the installation and certification of backflow-preventing devices.

3.2.7 Sanitation

Provide and maintain within the construction area minimum field-type sanitary facilities in accordance with EM 385-1-1 Section 02. Locate the facilities behind the construction fence or out of the public view. Clean units and empty wastes at least once a week or more frequently by removal of waste to a commercial facility. Penalties or fines associated with improper disposal will be the responsibility of the Contractor. Maintain these conveniences at all times. Include provisions for pest control and elimination of odors. Government toilet facilities will not be available to Contractor's personnel.

3.2.8 Telephone

Make arrangements with local telephone company, NMCI and other pertinent

base communications departments and pay all costs associated.

3.2.9 Fire Protection

Provide temporary fire protection equipment for the protection of personnel and property during construction. Remove debris and flammable materials weekly to minimize potential hazards.

3.3 TRAFFIC PROVISIONS

3.3.1 Maintenance of Traffic

- a. Conduct operations in a manner that will not close a thoroughfare or interfere with traffic on railways or highways except with written permission of the Contracting Officer at least 15 calendar days prior to the proposed modification date, and provide a [Traffic Control Plan](#) for Government approval detailing the proposed controls to traffic movement for approval. The plan must be in accordance with State and local regulations and the [MUTCD](#), Part VI. Contractor may move oversized and slow-moving vehicles to the worksite provided requirements of the highway authority have been met.
- b. Conduct work so as to minimize obstruction of traffic, and maintain traffic on at least half of the roadway width at all times. Obtain approval from the Contracting Officer prior to starting any activity that will obstruct traffic.
- c. Provide, erect, and maintain, at Contractor's expense, lights, barriers, signals, passageways, detours, Life Safety Signage, overhead protection, and other items that may be required by the authority having jurisdiction.
- d. Provide cones, signs, barricades, lights, or other traffic control devices and personnel required to control traffic. Do not use foil-backed material for temporary pavement marking because of its potential to conduct electricity during accidents involving downed power lines.

3.3.2 Protection of Traffic

Maintain and protect traffic on all affected roads during the construction period except as otherwise specifically directed by the Contracting Officer. Measures for the protection and diversion of traffic, including the provision of watchmen and flagmen, erection of barricades, placing of lights around and in front of equipment the work, and the erection and maintenance of adequate warning, danger, and direction signs, will be as required by the State and local authorities having jurisdiction. Provide self-illuminated (lighted) barricades during hours of darkness. All personnel working in roadways will wear brightly-colored vests or other high visibility apparel in accordance with [EM 385-1-1](#). Protect the traveling public from damage to person and property. Minimize the interference with public traffic on roads selected for hauling material to and from the site. Investigate the adequacy of existing roads and their allowable load limit. Contractor is responsible for the repair of damage to roads caused by construction operations.

3.3.3 Rush Hour Restrictions

Do not interfere with the peak traffic flows preceding and during normal

operations without notification to and approval by the Contracting Officer.

3.3.4 Dust Control

Dust control methods and procedures must be approved by the Contracting Officer. Coordinate dust control methods with 01 57 19 TEMPORARY ENVIRONMENTAL CONTROLS.

3.4 REDUCED PRESSURE BACKFLOW PREVENTERS

Provide an approved reduced pressure backflow prevention assembly at each location where the Contractor taps into the Government potable water supply.

Perform backflow preventer tests using test equipment, procedures, and certification forms conforming to those outlined in the latest edition of the Manual of Cross-Connection Control published by the FCCCHR Manual. Test and tag each reduced pressure backflow preventer upon initial installation (prior to continued water use) and quarterly thereafter. Tag must contain the following information: make, model, serial number, dates of tests, results, maintenance performed, and signature of tester. Record test results on certification forms conforming to requirements cited earlier in this paragraph.

3.5 CONTRACTOR'S TEMPORARY FACILITIES

Contractor is responsible for security of their property. Provide adequate outside security lighting at the temporary facilities. Trailers must be anchored to resist high winds and meet applicable state or local standards for anchoring mobile trailers. Coordinate anchoring with EM 385-1-1. The Contract Clause entitled "FAR 52.236-10, Operations and Storage Areas" and the following apply:

3.5.1 Administrative Field Offices

Provide and maintain administrative field office facilities within the construction area at the designated site. Government office and warehouse facilities will not be available to the Contractor's personnel.

In the event a new building is constructed for the temporary project field office, it must be a minimum 12 feet in width, 16 feet in length and have a minimum of 7 feet headroom. Equip the building with approved electrical wiring, at least one double convenience outlet and the required switches and fuses to provide 110-120 volt power. Provide a work table with stool, desk with chair, two additional chairs, and one legal size file cabinet that can be locked. The building must be waterproof, supplied with a heater, have a minimum of two doors, electric lights, a telephone, a battery-operated smoke detector alarm, a sufficient number of adjustable windows for adequate light and ventilation, and a supply of approved drinking water. Provide approved sanitary facilities. Screen the windows and doors and provide the doors with deadbolt type locking devices or a padlock and heavy-duty hasp bolted to the door. Door hinge pins must be non-removable. Arrange the windows to open and to be securely fastened from the inside. Protect glass panels in windows by bars or heavy mesh screens to prevent easy access. In warm weather, provide air conditioning capable of maintaining the office at 50 percent relative humidity and a room temperature 20 degrees F below the outside temperature when the outside temperature is 95 degrees F. Unless otherwise directed by the Contracting Officer, remove the building from the site upon completion and

acceptance of the work.

3.5.2 Storage Area

Construct a temporary 6 foot high chain link fence around trailers and materials. Include plastic strip inserts, colored brown, so that visibility through the fence is obstructed. Fence posts may be driven, in lieu of concrete bases, where soil conditions permit. Do not place or store trailers, materials, or equipment outside the fenced area unless such trailers, materials, or equipment are assigned a separate and distinct storage area by the Contracting Officer away from the vicinity of the construction site but within the installation boundaries. Trailers, equipment, or materials must not be open to public view with the exception of those items which are in support of ongoing work on the current day. Do not stockpile materials outside the fence in preparation for the next day's work. Park mobile equipment, such as tractors, wheeled lifting equipment, cranes, trucks, and like equipment within the fenced area at the end of each work day.

Keep fencing in a state of good repair and proper alignment. If the Contractor elects to traverse grassed or unpaved areas which are not established roadways with construction equipment or other vehicles, cover the grassed or unpaved areas with a layer of gravel as necessary to prevent rutting and the tracking of mud onto paved or established roadways; gravel gradation must be at the Contractor's discretion. Mow and maintain grass located within the boundaries of the construction site for the duration of the project. Grass and vegetation along fences, structures, under trailers, and in areas not accessible to mowers must be edged or trimmed neatly.

3.5.3 Supplemental Storage Area

Upon request, and pending availability, the Contracting Officer will designate another or supplemental area for the use and storage of trailers, equipment, and materials. This area may not be in close proximity of the construction site but will be within the installation boundaries. Maintain the area in a clean and orderly fashion and secured if needed to protect supplies and equipment. Utilities will not be provided to this area by the Government.

3.5.4 Appearance of Trailers

- a. Trailers must be roadworthy and comply with all appropriate state and local vehicle requirements. Trailers which are rusted, have peeling paint or are otherwise in need of repair will not be allowed on Installation property. Trailers must present a clean and neat exterior appearance and be in a state of good repair.
- b. Maintain the temporary facilities. Failure to do so will be sufficient reason to require their removal at the Contractor's expense.

3.5.5 Safety Systems

Protect the integrity of all installed safety systems or personnel safety devices. Obtain prior approval from the Contracting Officer if entrance into systems serving safety devices is required. If it is temporarily necessary to remove or disable personnel safety devices in order to accomplish Contract requirements, provide alternative means of protection prior to removing or disabling any permanently installed safety devices or

equipment and obtain approval from the Contracting Officer.

3.5.6 Weather Protection of Temporary Facilities and Stored Materials

Take necessary precautions to ensure that roof openings and other critical openings in the building are monitored carefully. Take immediate actions required to seal off such openings when rain or other detrimental weather is imminent, and at the end of each workday. Ensure that the openings are completely sealed off to protect materials and equipment in the building from damage.

3.5.6.1 Building and Site Storm Protection

When a warning of gale force winds is issued, take precautions to minimize danger to persons, and protect the work and nearby Government property. Precautions must include, but are not limited to, closing openings; removing loose materials, tools and equipment from exposed locations; and removing or securing scaffolding and other temporary work. Close openings in the work when storms of lesser intensity pose a threat to the work or any nearby Government property.

3.6 PLANT COMMUNICATIONS

Whenever the individual elements of the plant are located so that operation by normal voice between these elements is not satisfactory, install a satisfactory means of communication, such as telephone or other suitable devices and make available for use by Government personnel.

3.7 TEMPORARY PROJECT SAFETY FENCING

As soon as practicable, but not later than 15 days after the date established for commencement of work, furnish and erect temporary project safety fencing at the work site. Maintain the safety fencing during the life of the Contract and, upon completion and acceptance of the work, remove from the work site.

3.8 CLEANUP

Remove construction debris, waste materials, packaging material and the like from the work site daily. Any dirt or mud which is tracked onto paved or surfaced roadways must be cleaned away. Store all salvageable materials resulting from demolition activities within the fenced area described above or at the supplemental storage area. Neatly stack stored materials not in trailers, whether new or salvaged.

3.9 RESTORATION OF STORAGE AREA

Upon completion of the project remove the bulletin board, signs, barricades, haul roads, and all other temporary products from the site. After removal of trailers, materials, and equipment from within the fenced area, remove the fence. Restore areas used during the performance of the Contract to the original or better condition. Remove gravel used to traverse grassed areas and restore the area to its original condition, including top soil and seeding as necessary.

-- End of Section --

SECTION 01 57 19

TEMPORARY ENVIRONMENTAL CONTROLS

08/22

PART 1 GENERAL

This document is intended to summarize environmental requirements for contract work specific to Naval Station Great Lakes (NSGL). Where differences with regulatory requirements or recognized advisory standards occur, the more stringent shall apply.

NSGL, including Contractor project work site(s) are subject to Federal, State, and local regulatory, and/or Navy policy inspection to verify compliance with environmental regulations. The Contractor shall cooperate fully with NSGL Environmental Division, and all regulatory representatives which may visit their job site and shall provide immediate notification to the Navy Contracting Officer of such regulatory visits. The Contractor shall complete, maintain, and make available to the Contracting Officer, and NSGL designated or regulatory agency representative(s) all documentation relating to environmental compliance as requested. Herein - local regulations refer to Lake County Illinois requirements.

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASSOCIATION OF ILLINOIS SOIL AND WATER CONSERVATION DISTRICTS
(AISWCD)

IUM (2020) Illinois Urban Manual

ILLINOIS ENVIRONMENTAL PROTECTION AGENCY (IEPA)

35 IAC 900-901 Title 35 of Illinois Administrative Code,
Subtitle H: Noise, Chapter I: Pollution
Control Board

U.S. DEPARTMENT OF THE NAVY (DON)

OPNAV M-5090.1 (2014) Environmental Readiness Manual

U.S. ENVIRONMENTAL PROTECTION AGENCY (EPA)

EPA SW-846 (Third Edition; Update IV) Test Methods
for Evaluating Solid Waste:
Physical/Chemical Methods

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

29 CFR 1910.1053 Respirable Crystalline Silica

29 CFR 1910.1200 Hazard Communication

29 CFR 1926.1153 Respirable Crystalline Silica

40 CFR 50	National Primary and Secondary Ambient Air Quality Standards
40 CFR 60	Standards of Performance for New Stationary Sources
40 CFR 63	National Emission Standards for Hazardous Air Pollutants for Source Categories
40 CFR 64	Compliance Assurance Monitoring
40 CFR 82	Protection of Stratospheric Ozone
40 CFR 112	Oil Pollution Prevention
40 CFR 122.26	Storm Water Discharges (Applicable to State NPDES Programs, see section 123.25)
40 CFR 241	Guidelines for Disposal of Solid Waste
40 CFR 243	Guidelines for the Storage and Collection of Residential, Commercial, and Institutional Solid Waste
40 CFR 258	Subtitle D Landfill Requirements
40 CFR 260	Hazardous Waste Management System: General
40 CFR 261	Identification and Listing of Hazardous Waste
40 CFR 261.7	Residues of Hazardous Waste in Empty Containers
40 CFR 262	Standards Applicable to Generators of Hazardous Waste
40 CFR 262.11	Hazardous Waste Determination and Recordkeeping
40 CFR 263	Standards Applicable to Transporters of Hazardous Waste
40 CFR 264	Standards for Owners and Operators of Hazardous Waste Treatment, Storage, and Disposal Facilities
40 CFR 265	Interim Status Standards for Owners and Operators of Hazardous Waste Treatment, Storage, and Disposal Facilities
40 CFR 266	Standards for the Management of Specific Hazardous Wastes and Specific Types of Hazardous Waste Management Facilities
40 CFR 268	Land Disposal Restrictions
40 CFR 273	Standards for Universal Waste Management

40 CFR 273.2	Standards for Universal Waste Management - Batteries
40 CFR 273.4	Standards for Universal Waste Management - Mercury Containing Equipment
40 CFR 273.5	Standards for Universal Waste Management - Lamps
40 CFR 273.6	Applicability - Aerosol Cans
40 CFR 279	Standards for the Management of Used Oil
40 CFR 300	National Oil and Hazardous Substances Pollution Contingency Plan
40 CFR 355	Emergency Planning and Notification
40 CFR 403	General Pretreatment Regulations for Existing and New Sources of Pollution
40 CFR 745	Lead-Based Paint Poisoning Prevention in Certain Residential Structures
40 CFR 761	Polychlorinated Biphenyls (PCBs) Manufacturing, Processing, Distribution in Commerce, and Use Prohibitions
49 CFR 171	General Information, Regulations, and Definitions
49 CFR 172	Hazardous Materials Table, Special Provisions, Hazardous Materials Communications, Emergency Response Information, and Training Requirements
49 CFR 173	Shippers - General Requirements for Shipments and Packagings
49 CFR 178	Specifications for Packagings

1.2 DEFINITIONS

1.2.1 Chemical Wastes

Includes salts, acids, alkalines, herbicides, pesticides, and organic chemicals.

1.2.2 Class I and II Ozone Depleting Substance (ODS)

Class I ODS is defined in Section 602(a) of The Clean Air Act. A list of Class I ODS can be found on the EPA website at the following weblink.
<https://www.epa.gov/ozone-layer-protection/ozone-depleting-substances>.

Class II ODS is defined in Section 602(s) of The Clean Air Act. A list of Class II ODS can be found on the EPA website at the following weblink.
<https://www.epa.gov/ozone-layer-protection/ozone-depleting-substances>.

1.2.3 Contractor Generated Hazardous Waste

Contractor generated hazardous waste is materials that, if abandoned or disposed of, may meet the definition of a hazardous waste. These waste streams would typically consist of material brought on site by the Contractor to execute work, but are not fully consumed during the course of construction. Examples include, but are not limited to, excess paint thinners (i.e., methyl ethyl ketone, toluene), waste thinners, excess paints, excess solvents, waste solvents, excess pesticides, and contaminated pesticide equipment rinse water.

1.2.4 Electronics Waste

Electronics waste is discarded electronic devices intended for salvage, recycling, or disposal.

1.2.5 Environmental Pollution and Damage

Environmental pollution and damage is the presence of chemical, physical, or biological elements or agents which adversely affect human health or welfare; unfavorably alter ecological balances of importance to human life; affect other species of importance to humankind; or degrade the environment aesthetically, culturally or historically.

1.2.6 Environmental Protection

Environmental protection is the prevention/control of pollution and habitat disruption that may occur to the environment during construction. The control of environmental pollution and damage requires consideration of land, water, and air; biological and cultural resources; and includes management of visual aesthetics; noise; solid, chemical, gaseous, and liquid waste; radiant energy and radioactive material as well as other pollutants.

1.2.7 Fill Soil

Soil brought on to NSGL must be initially sampled to confirm compliance with IEPA Tiered Approach to Corrective Action Objectives (TACO) Tier 1 residential property use scenario for the ingestion, inhalation and migration to groundwater exposure pathways criteria (35 IAC Part 742). If documentation is available from the borrow site vendor, the data can be submitted for a sufficiency review by PWD-Environmental Division (PWD-EV DIV). If the borrow site vendor does not have analytical data that documents the condition of the soils, Contractor shall collect representative samples from the proposed borrow area. All fill soils data provided by the site owner or Contractor must be certified by an Illinois Licensed Professional Engineer using IEPA Form LCP-663 as uncontaminated soil in accordance with the IEPA Act 415 ILCS 5/22.51 (f)(2)(B).

Regardless of source site use, the Contractor shall analyze samples for all Target Analyte List and Target Compound List constituents using U.S. Environmental Protection Agency SW846 methods with detection limits appropriate for comparison to the IEPA Tier 1 TACO residential criteria. All Laboratory Analysis for Fill Soils must be performed by an IEPA/NELAP laboratory. Chain of Custody must document soil sample location, preferably by address. Sample frequency shall be, at a minimum, one (1) sample per 500 tons soil. No soils shall be brought into NSGL until PWD-EV DIV has been provided documentation of and accepted the analytical data results.

1.2.8 Hazardous Debris

As defined in paragraph SOLID WASTE, debris that contains listed hazardous waste (either on the debris surface, or in its interstices, such as pore structure) in accordance with 40 CFR 261. Hazardous debris also includes debris that exhibits a characteristic of hazardous waste in accordance with 40 CFR 261.

1.2.9 Hazardous Materials

Hazardous material is any material that: Is defined in 49 CFR 171, listed in 49 CFR 172, regulated as a hazardous material in accordance with 49 CFR 173; or requires a Safety Data Sheet (SDS) in accordance with 29 CFR 1910.1200; or during end use, treatment, handling, packaging, storage, transportation, or disposal meets or has components that meet or have potential to meet the definition of a hazardous waste as defined by 40 CFR 261 Subparts A, B, C, or D. Designation of a material by this definition, when separately regulated or controlled by other sections or directives, does not eliminate the need for adherence to that hazard-specific guidance which takes precedence over this section for "control" purposes. Such material includes but is not limited to: ammunition, weapons, explosive actuated devices, propellants, pyrotechnics, chemical and biological warfare materials, medical and pharmaceutical supplies, medical waste and infectious materials, bulk fuels, radioactive materials, and other materials such as asbestos, mercury, and polychlorinated biphenyls (PCBs). Nonetheless, the exposure may occur incidental to manufacture, storage, use and demilitarization of these items.

1.2.10 Hazardous Waste

Hazardous Waste is any material that meets the definition of a solid waste and exhibits a hazardous characteristic (ignitability, corrosivity, reactivity, or toxicity) as specified in 40 CFR 261, Subpart C, or contains a listed hazardous waste as identified in 40 CFR 261, Subpart D, or is designated as a hazardous waste by the Illinois State Hazardous Control Authority or IEPA.

1.2.11 Land Application

Land Application means spreading or spraying discharge water at a rate that allows the water to percolate into the soil. No sheeting action, soil erosion, discharge into storm sewers, discharge into defined drainage areas, or discharge into the "waters of the United States" must occur. Comply with federal, state, and local laws and regulations.

1.2.12 Municipal Separate Storm Sewer System (MS4) Permit

MS4 permits are those held by municipalities or installations to obtain NPDES permit coverage for their stormwater discharges.

1.2.13 National Pollutant Discharge Elimination System (NPDES)

The NPDES permit program controls water pollution by regulating point sources that discharge pollutants into waters of the United States.

1.2.14 Oily Waste

Oily waste are those materials that are, or were, mixed with Petroleum,

Oils, and Lubricants (POLs) and have become separated from that POLs. Oily wastes also means materials, including wastewaters, centrifuge solids, filter residues or sludges, bottom sediments, tank bottoms, and sorbents which have come into contact with and have been contaminated by, POLs and may be appropriately tested and discarded in a manner which is in compliance with Illinois state and local requirements. The most stringent requirement shall apply.

This definition includes materials such as oily rags, "kitty litter" sorbent clay and organic sorbent material. These materials may be land filled provided that: It is not prohibited in other state regulations or local ordinances; it is the result of minor leaks or spills resulting from normal process operations; and free-flowing oil has been removed to the practicable extent possible. Large quantities of this material, generated as a result of a major spill or in lieu of proper maintenance of the processing equipment, are a solid waste. As a solid waste, perform a hazardous waste determination prior to disposal. As this can be an expensive process, it is recommended that this type of waste be minimized through good housekeeping practices and employee education.

1.2.15 Regulated Waste

Regulated waste are solid wastes that have specific additional federal, state, or local controls for handling, storage, or disposal.

1.2.16 Sediment

Sediment is soil and other debris that have eroded and have been transported by runoff water or wind.

1.2.17 Solid Waste

Solid waste is a solid, liquid, semi-solid or contained gaseous waste. A solid waste can be a hazardous waste, non-hazardous waste, or non-Resource Conservation and Recovery Act (RCRA) regulated waste. Garbage, refuse, debris, sludge, or other discharged material, including materials resulting from domestic, industrial, commercial, or agricultural operations are considered examples of solid waste.

1.2.17.1 Debris

Debris is non-hazardous solid material generated during the construction, demolition, or renovation of a structure that exceeds 2.5-inch particle size that is: a manufactured object; plant or animal matter; or natural geologic material (for example, cobbles and boulders), broken or removed concrete, masonry, and rock asphalt paving; ceramics; roofing paper and shingles. Inert materials may not be reinforced with or contain ferrous wire, rods, accessories and weldments. A mixture of debris and other material such as soil or sludge is also subject to regulation as debris if the mixture is comprised primarily of debris by volume, based on visual inspection.

1.2.17.2 Clean Construction and Demolition Debris (CCDD)

As defined by the Illinois Environmental Protection Agency, CCDD is uncontaminated broken concrete without protruding metal bars, bricks, rock, stone, or reclaimed asphalt pavement generated from construction or demolition activities. When uncontaminated soil is mixed with any of these materials, the uncontaminated soil is considered CCDD.

1.2.17.3 Green Waste

Green waste is the vegetative matter from landscaping, land clearing and grubbing, including, but not limited to, grass, bushes, scrubs, small trees and saplings, tree stumps and plant roots. Marketable trees, grasses and plants that are indicated to remain, be re-located, or be re-used are not included.

1.2.17.4 Non-Hazardous Waste

Non-hazardous waste is waste that is excluded from, or does not meet, hazardous waste criteria in accordance with 40 CFR 261.

1.2.17.5 Recyclables

Recyclables are materials, equipment and assemblies such as doors, windows, door and window frames, plumbing fixtures, glazing and mirrors that are recovered and sold as recyclable. It also includes commercial-grade refrigeration equipment with Freon removed, household appliances where the basic material content is metal, clean polyethylene terephthalate bottles, cooking oil, used fuel oil, textiles, high-grade paper products and corrugated cardboard, stackable pallets in good condition, clean crating material, and clean rubber/vehicle tires. Metal meeting the definition of lead contaminated or lead based paint contaminated may not be included as recyclable if sold to a scrap metal company. Paint cans that meet the definition of empty containers in accordance with 40 CFR 261.7 may be included as recyclable if sold to a scrap metal company.

1.2.17.6 Surplus Soil

Surplus soil is existing soil that is in excess of what is required for this work, including aggregates intended, but not used, for on-site mixing of concrete, mortars, and paving. Contaminated soil meeting the definition of hazardous material or hazardous waste is not included and must be managed in accordance with paragraph HAZARDOUS MATERIAL MANAGEMENT.

1.2.17.7 Project Spoils

All demolition debris (including residuals from construction), excess soil, and other by-products resulting from demolition or construction shall be removed from NSGL within 30-days of project completion. Soil shall be verified free of contaminants (per Section 1.2.7 above) and shall require prior approval by PWD-EV DIV before its use at alternate site(s) on Naval Station Great Lakes.

1.2.17.8 Scrap Metal

This includes scrap and excess ferrous and non-ferrous metals such as reinforcing steel, structural shapes, pipe, and wire that are recovered or collected and disposed of as scrap. Scrap metal meeting the definition of hazardous material or hazardous waste is not included.

1.2.17.9 Wood

Wood is dimension and non-dimension lumber, plywood, chipboard, hardboard. Treated or painted wood that meets the definition of lead contaminated or lead based contaminated paint is not included. Treated wood includes, but is not limited to, lumber, utility poles, crossties, and other wood

products with chemical treatment.

1.2.17.10 Paint Containers

Metal, plastic and other containers that are empty of paints, surface-containing materials, solvents, thinners and adhesives. If permitted by regulation and product label, a thin dry film (not to exceed one-inch) may remain within the container.

1.2.18 Surface Discharge

Surface discharge means discharge of water into drainage ditches, storm sewers, or creeks meeting the definition of "waters of the United States". Surface discharges from construction sites are discrete, identifiable sources and require a permit from the governing agency. Comply with federal, state, and local laws and regulations.

The term "Surface Discharge" implies that the water is discharged with possible sheeting action and subsequent soil erosion may occur. Waters that are surface discharged may terminate in drainage ditches, storm sewers, creeks, or "waters of the United States" and would require a permit to discharge water from the governing agency. All projects with land disturbances greater than or equal to one acre in total area must have a National Pollution Discharge Elimination System (NPDES) Construction Site Activity Storm Water Permit to discharge surface water from a construction site, issued by the Illinois Environmental Protection Agency. All projects with discharge of dredged or fill material to waters of the United States must have a Section 401 Water Quality Permit issued by the Illinois Environmental Protection Agency.

1.2.19 Wastewater

Wastewater is the used water and solids that flow through a sanitary sewer to a treatment plant.

1.2.19.1 Stormwater

Stormwater is any precipitation in an urban or suburban area that does not evaporate or soak into the ground, but instead collects and flows into storm drains, rivers, and streams.

1.2.20 Waters of the United States

Waters of the United States means Federally jurisdictional waters, including wetlands, that are subject to regulation under Section 404 of the Clean Water Act or navigable waters, as defined under the Rivers and Harbors Act.

1.2.21 Wetlands

Wetlands are those areas that are inundated or saturated by surface or groundwater at a frequency and duration sufficient to support, and that under normal circumstances do support, a prevalence of vegetation typically adapted for life in saturated soil conditions.

1.2.22 Universal Waste

The universal waste regulations streamline collection requirements for certain hazardous wastes (unbroken) in the following categories: batteries,

pesticides, mercury-containing equipment (for example, thermostats), and lamps (for example, fluorescent bulbs). The rule is designed to reduce hazardous waste in the municipal solid waste (MSW) stream by making it easier for universal waste handlers to collect these items and send them for recycling or proper disposal. These regulations can be found at [40 CFR 273](#).

1.2.23 Waste Hazardous Material (WHM)

Any waste material which because of its quantity, concentration, physical, chemical or other defined characteristics may pose a substantial hazard to human health or the environment and which has been so designated. Used oil not containing any hazardous waste, as discussed above, falls under this definition.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" classification. Submittals not having a "G" classification are for Contractor Quality Control approval. Submit the following in accordance with Section [01 33 00](#) SUBMITTAL PROCEDURESS:

SD-01 Preconstruction Submittals

Preconstruction Survey; G

Regulatory Notifications; G

Environmental Manager Qualifications; G

Environmental Protection Plan; G

Dirt and Dust Control Plan; G

Stormwater Pollution Prevention Plan (SWPPP); G

Stormwater Notice of Intent (for NPDES coverage under the general permit for construction activities); G

Spill Prevention Control And Countermeasure (SPCC) Plan; G

Erosion And Sediment Control Plan; G

SD-06 Test Reports

Monthly Solid Waste Disposal Report; G

Laboratory Analysis For Fill Soils

Laboratory Analysis For Waste Disposal

Laboratory Analysis For Excavated Soils

SD-07 Certificates

ECATTS Certificate Of Completion; G

Employee Training Records; G

Erosion and Sediment Control Inspector Qualifications

SD-11 Closeout Submittals

Assembled Employee Training Records; G

Solid Waste Management Permit; G

Waste Determination Documentation; G

Hazardous Waste/Debris Management; G

Disposal Documentation for Hazardous and Regulated Waste; G

Contractor Hazardous Material Inventory Log; G

1.4 ENVIRONMENTAL PROTECTION REQUIREMENTS

Provide and maintain, during the life of the contract, environmental protection as defined. Plan for and provide environmental protective measures to control pollution that develops during construction practice. Plan for and provide environmental protective measures required to correct conditions that develop during the construction of permanent or temporary environmental features associated with the project. Protect the environmental resources within the project boundaries and those affected outside the limits of permanent work during the entire duration of this Contract. Comply with federal, state, local, and Navy, to include OPNAV M-5090.1, regulations and policy pertaining to the environment, including water, air, solid waste, hazardous waste and substances, oily substances, and noise pollution.

Tests and procedures assessing whether construction operations comply with Applicable Environmental Laws may be required. Analytical work must be performed by qualified laboratories; and where required by law, the laboratories must be certified.

1.4.1 Training in Environmental Compliance Assessment Training and Tracking System (ECATTS)

1.4.1.1 Personnel Requirements

The Environmental Manager is responsible for environmental compliance on projects. The Environmental Manager, must complete applicable ECATTS training modules, as determined by PWD-EV Division prior to starting respective portions of on-site work under this Contract. If personnel changes occur for any of these positions after starting work, replacement personnel must complete applicable ECATTS training within 14 calendar days of assignment to the project.

1.4.1.2 Certification

Submit an ECATTS certificate of completion for personnel who have completed the required ECATTS training. This training is web-based and can be accessed from any computer with Internet access using the following instructions.

Register for NAVFAC Environmental Compliance Assessment, Training, and Tracking System, by logging on to <https://environmentaltraining.ecatts.com/>. Obtain the password for registration from the Contracting Officer.

1.4.1.3 Refresher Training

This training has been structured to allow contractor personnel to receive credit under this contract and to carry forward credit to future contracts. Ensure the Environmental Manager review their training plans for new modules or updated training requirements prior to beginning work. Some training modules are tailored for specific Illinois state regulatory requirements; therefore, Contractors working in multiple states will be required to retake modules tailored to the state where the contract work is being performed.

ECATTS is available for use by all contractor and subcontractor personnel associated with this project.

1.4.2 Conformance with the Environmental Management System

Perform work under this contract consistent with the policy and objectives identified in the installation's Environmental Management System (EMS). Perform work in a manner that conforms to objectives and targets of the environmental programs and operational controls identified by the EMS. Support Government personnel when environmental compliance and EMS audits are conducted by escorting auditors at the Project site, answering questions, and providing proof of records being maintained. Provide monitoring and measurement information as necessary to address environmental performance relative to environmental, energy, and transportation management goals. In the event an EMS nonconformance or environmental noncompliance associated with the contracted services, tasks, or actions occurs, take corrective and preventative actions. In addition, employees must be aware of their roles and responsibilities under the installation EMS and of how these EMS roles and responsibilities affect work performed under the contract.

Coordinate with the installation's EMS coordinator to identify training needs associated with environmental aspects and the EMS, and arrange training or take other action to meet these needs. Provide training documentation to the Contracting Officer. The Installation Environmental Office will retain associated environmental compliance records. Make EMS Awareness training completion certificates available to Government auditors during EMS audits and include the certificates in the Employee Training Records. See paragraph EMPLOYEE TRAINING RECORDS.

1.5 QUALITY ASSURANCE

1.5.1 Preconstruction Survey and Protection of Features

This paragraph supplements the Contract Clause PROTECTION OF EXISTING VEGETATION, STRUCTURES, EQUIPMENT, UTILITIES, AND IMPROVEMENTS. Prior to start of any onsite construction activities, perform a [Preconstruction Survey](#) of the project site with the Contracting Officer, and take photographs showing existing environmental conditions in and adjacent to the site. Submit a report for the record. Include in the report a plan describing the features requiring protection under the provisions of the Contract Clauses, which are not specifically identified on the drawings as environmental features requiring protection along with the condition of trees, shrubs and grassed areas immediately adjacent to the site of work and adjacent to the Contractor's assigned storage area and access route(s), as applicable. The Contractor and the Contracting Officer will sign this survey report upon mutual agreement regarding its accuracy and

completeness. Protect those environmental features included in the survey report and any indicated on the drawings, regardless of interference that their preservation may cause to the work under the Contract.

Pre-approval is required prior to photographing on Naval Station Great Lakes.

1.5.2 Regulatory Notifications

The contractor is responsible for providing all regulatory notification requirements in accordance with federal, state and local regulations. In cases where the Government shall provide public notification (such as stormwater permitting), coordinate with the Contracting Officer. Submit draft copies of regulatory notifications to the Contracting Officer at least 45 days prior to commencement of work activities. Regulatory notification review time may vary depending on the work scope and requirement. Typically, regulatory notifications must be provided for the following (this listing is not all-inclusive): demolition, renovation, NPDES defined site work, construction, removal or use of a permitted air emissions source, and remediation of controlled substances (asbestos, hazardous waste, lead paint). The contractor is required to obtain concurrence from the Contracting Officer and PWD-EV Division prior to submitting permits and other approval requests to regulatory agencies.

1.5.3 Environmental Brief

Attend an environmental brief to be included in the preconstruction meeting. Provide the following information: types, quantities, and use of hazardous materials that will be brought onto the installation; and types and quantities of wastes/wastewater that may be generated during the Contract. Discuss the results of the Preconstruction Survey at this time.

Prior to initiating any work on site, meet with the Contracting Officer and PWD-EV Division to discuss the proposed Environmental Protection Plan (EPP) or equipment local requirement. Develop a mutual understanding relative to the details of environmental protection, including measures for protecting natural and cultural resources, required reports, required permits, permit requirements (such as mitigation measures), and other measures to be taken.

1.5.4 Environmental Manager

Appoint in writing an Environmental Manager for the project site. The Environmental Manager is directly responsible for coordinating contractor compliance with federal, state, local, and installation requirements. The Environmental Manager must ensure compliance with Hazardous Waste Program requirements (including hazardous waste handling, storage, manifesting, and disposal); implement the EPP; ensure environmental permits are obtained, maintained, and closed out; ensure compliance with Stormwater Program requirements; ensure compliance with Hazardous Materials (storage, handling, and reporting) requirements; and coordinate any remediation of regulated substances (lead, asbestos, PCB transformers). This can be a collateral position; however, the person in this position must be trained to adequately accomplish the following duties: ensure waste segregation and storage compatibility requirements are met; inspect and manage Satellite Accumulation areas; ensure only authorized personnel add wastes to containers; ensure Contractor personnel are trained in 40 CFR requirements in accordance with their position requirements; coordinate removal of waste containers; and maintain the Environmental Records binder and required documentation, including environmental permits compliance and close-out. Submit Environmental Manager Qualifications to the Contracting Officer.

1.5.5 Employee Training Records

Prepare and maintain [Employee Training Records](#) throughout the term of the contract meeting applicable 40 CFR requirements. Provide Employee Training Records in the Environmental Records Binder. Submit these [Assembled Employee Training Records](#) to the Contracting Officer at the conclusion of the project, unless otherwise directed.

Train personnel to meet [IEPA and EPA](#) requirements. Conduct environmental protection/pollution control meetings for personnel prior to commencing construction activities. Conduct additional meetings for new personnel and when site conditions change. Include in the training and meeting agenda: methods of detecting and avoiding pollution; familiarization with statutory and contractual pollution standards; installation and care of devices, vegetative covers, and instruments required for monitoring purposes to ensure adequate and continuous environmental protection/pollution control; anticipated hazardous or toxic chemicals or wastes, and other regulated contaminants; recognition and protection of archaeological sites, artifacts, waters of the United States, and endangered species and their habitat that are known to be in the area. Provide copy of the [Erosion and Sediment Control Inspector Qualifications](#) [upon request](#).

1.5.6 Non-Compliance Notifications

The Contracting Officer will notify the Contractor in writing of any observed noncompliance with federal, state or local environmental laws or regulations, permits, and other elements of the Contractor's EPP. After receipt of such notice, inform the Contracting Officer of the proposed corrective action and take such action when approved by the Contracting Officer. The Contracting Officer may issue an order stopping all or part of the work until satisfactory corrective action has been taken. FAR 52.242-14 Suspension of Work provides that a suspension, delay, or interruption of work due to the fault or negligence of the Contractor allows for no adjustments to the contract for time extensions or equitable adjustments. In addition to a suspension of work, the Contracting Officer may use additional authorities under the contract or law.

1.6 ENVIRONMENTAL PROTECTION PLAN

The purpose of the EPP is to present an overview of known or potential environmental issues that must be considered and addressed during construction. Incorporate construction related objectives and targets from the installation's EMS into the EPP. Include in the EPP measures for protecting natural and cultural resources, required reports, and other measures to be taken. [Prior to initiating any work on site, meet with the Contracting Officer or Contracting Officer Representative to discuss the EPP and develop a mutual understanding relative to the details for environmental protection including measures for protecting natural resources, required reports, and other measures to be taken. Submit the EPP within 30 days after contract award. Submit the draft EPP within 30 days after contract award for review and approval by PWD-EV DIV. Commencement of work will not begin until the EPP has been approved.](#) Revise the EPP throughout the project to include any reporting requirements, changes in site conditions, or contract modifications that change the project scope of work in a way that could have an environmental impact. No requirement in this section will relieve the Contractor of any applicable federal, state, and local environmental protection laws and regulations. During Construction, identify, implement, and submit for approval any additional

requirements to be included in the EPP. Maintain the current version onsite.

The EPP includes, but is not limited to, the following elements:

1.6.1 General Overview and Purpose

1.6.1.1 Descriptions

A brief description of each specific plan required by environmental permit or elsewhere in this Contract such as stormwater pollution prevention plan; spill control plan; solid waste management plan; wastewater management plan; air pollution control plan; contaminant prevention plan; a historical, archaeological, cultural resources, biological resources and wetlands plan; Hazardous, Toxic and Radioactive Waste (HTRW) Plan; and Non-Hazardous solid waste disposal plan, as applicable for the project.

1.6.1.2 Duties

The duties and level of authority assigned to the person(s) on the job site who oversee environmental compliance, such as who is responsible for adherence to the EPP, who is responsible for spill cleanup and training personnel on spill response procedures, who is responsible for manifesting hazardous waste to be removed from the site (if applicable), and who is responsible for training the Contractor's environmental protection personnel.

1.6.1.3 Procedures

A copy of any standard or project-specific operating procedures that will be used to effectively manage and protect the environment on the project site.

1.6.1.4 Communications

Communication and training procedures that will be used to convey environmental management requirements to Contractor employees and subcontractors.

1.6.1.5 Contact Information

Emergency contact information with the individual's name, job title, office phone number, cell phone number, and e-mail address.

1.6.2 General Site Information

1.6.2.1 Drawings

Drawings showing locations of proposed temporary excavations or embankments for haul roads, stream crossings, jurisdictional wetlands, material storage areas, structures, sanitary facilities, storm drains and conveyances, and stockpiles of excess soil.

1.6.2.2 Work Area

Work area plan showing the proposed activity in each portion of the area and identify the areas of limited use or nonuse. Include measures for marking the limits of use areas, including methods for protection of features to be preserved within authorized work areas and methods to

control runoff and to contain materials on site, and a traffic control plan.

Show where any fuels, hazardous substances, solvents, or lubricants will be stored. Provide a spill plan to address any releases of those materials.

1.6.2.3 Documentation

A letter signed by an officer of the firm appointing the Environmental Manager and stating that person is responsible for managing and implementing the Environmental Program as described in this contract. Include in this letter the Environmental Manager's authority to direct the removal and replacement of non-conforming work.

1.6.3 Management of Natural Resources

- a. Land resources
- b. Tree and other vegetation protection
- c. Replacement of damaged landscape features
- d. Temporary construction
- e. Stream crossings
- f. Fish and wildlife resources
- g. Wetlands, floodplains, and environmentally sensitive habitat(s)
- h. Waters and Tributary waters of the U.S.
- i. Illinois Coastal Zone

1.6.4 Protection of Historical and Archaeological Resources

- a. Objectives
- b. Methods

1.6.5 Stormwater Management and Control

Stormwater management and control applies to any project that disturbs soil and /or vegetation, where work is being completed or staged near a storm sewer, or that is discharging water. Follow guidance from the Installation Environmental Office for Stormwater Management.

- a. Ground cover
- b. Erodible soils
- c. Temporary measures
 - (1) Structural Practices
 - (2) Temporary and permanent stabilization
 - (3) Control of runoff
 - (4) Vegetation and Mulch

- d. Effective selection, implementation and maintenance of Best Management Practices (BMPs).
- e. Stormwater Pollution Prevention Plan (SWPPP).

The EPP must include a Stormwater Pollution Prevention Plan (SWPPP). The Government will review the EPP, including the Stormwater Pollution Prevention Plan. Upon government approval, the contractor will then will submit the Notice of Intent (NOI) to the Illinois Environmental Protection Agency after the plan has been approved. No construction will take place before the submission of the NOI; approval of the NPDES permit requires 30 calendar days after the submission of the NOI. The Contractor may NOT begin earthmoving activities until 30 calendar days after the submission of the NOI. Approval of the Contractor's plan by the Government will not relieve the Contractor of his responsibility for control of pollutants and other environmental protection measures. Address all comments to the SWPPP generated by the Illinois Environmental Protection Agency within seven calendar days of receipt of comments. Certify, in writing, that all recommended changes have been made to the SWPPP, and must submit certification to the Contracting Officer's Representative (COR). Post, in a visible location accessible for public viewing, the IEPA response letter, to be provided by the Government, and ILR10 at the project site.

- a. A Stormwater Pollution Prevention Plan which identifies the type and location of the erosion and sediment controls to be provided. The plan must meet the requirements of the Illinois NPDES Permit No. ILR10 (included at the end of this section). The management practices, controls, and other provisions contained in the plan must be as protective as the requirements in the Illinois Urban Manual, IUM. The contents of the plan must address all items listed in Part IV of the permit, including but not limited to:
 - (1) Site description, controls, maintenance, inspections, and non-stormwater discharges.
 - (2) A map of the final site conditions.
 - (3) A site construction plan that includes the locations and dimensions of land disturbing activities, locations of soil stockpiles, locations and dimensions of erosion control measures, and a schedule with the start and finish dates of each land disturbing activity, including the installation of erosion control measures. Provisions and a schedule for maintenance of the erosion control measures during construction must also be included in the plan.
 - (4) Name and qualifications of the person(s) responsible for inspecting the site in accordance with the requirements given in ILR10.
 - (5) A copy of the blank inspection checklist that will be used during ILR10 site inspections.
 - (6) The plan must contain the certification statement contained in Part IV(F) of the NPDES Permit No. ILR10.

1.6.6 Protection of the Environment from Waste Derived from Contractor Operations

Control and disposal of solid and sanitary waste.

Control and disposal of hazardous waste.

Management controls, transportation and disposal requirements for RCRA, TSCA, Universal, Special and other regulated sub-categories of solid waste.

This item consist of the management procedures for hazardous waste to be generated. The elements of those procedures will coincide with the Installation Hazardous Waste Management Plan when within an installation. The Contracting Officer will provide a copy of the Installation Hazardous Waste Management Plan as applicable.

As a minimum, include the following information, as appropriate to the waste stream(s):

- a. Projected quantities of waste/debris to be generated. Estimated volumes by waste stream. Specifically identify RCRA, TSCA, Universal, Special and other regulated waste streams.
- b. Procedures to ensure a written waste determination is made for appropriate wastes that are to be generated
- c. Sampling/analysis plan, including laboratory method(s) that will be used for waste determinations and copies of relevant laboratory certifications
- d. Methods and proposed locations for hazardous waste accumulation/storage (that is, in tanks and/or containers)
- e. Management procedures for storage, labeling, transportation, and disposal of waste (on-site treatment of waste is prohibited unless specifically approved)
- f. Management procedures and regulatory documentation ensuring disposal of hazardous waste complies with Federal and State Land Disposal Restrictions (40 CFR 268)
- g. Management procedures for recyclable hazardous materials such as lead-acid batteries, used oil, and similar
- h. Used oil management procedures in accordance with 40 CFR 279 .
- i. Pollution prevention/hazardous waste minimization procedures
- j. Proposed disposal and/or recycling facilities, include one copy of a State and local solid waste management permit or license showing such agency's approval of the disposal facility. Contractor is required to use hazardous waste disposal facilities approved by the PWD-EV Division. Waste may not be transported off Government property until authorized by the Hazardous Waste Program Manager, the Installation Environmental Program Director, or another qualified Environmental Department staff member.
- k. Proposed means of waste transportation, including transporter's licenses and certifications relevant to regulated waste streams.

Proposed waste transporter and destination landfill EPA Identification Numbers, so these organizations can be evaluated by the Hazardous Waste Program Manager as acceptable service providers.

- l. Procedures to be employed to ensure required employee training records are maintained.
- m. It is the contractor's responsibility to remove or dispose of any hazardous or nonhazardous material brought on site. Any RCRA hazardous waste must be disposed of under the contractor's EPA ID Number.
- n. Proposed waste profile sheets for any/all waste streams to be disposed of must be provided to Environmental Hazardous Waste Program Manager to review for accuracy, and signature on behalf of the Generator (if this is determined to be the Navy's generated waste).

If Section 01 74 19.05 20 is included in the contract, submit the Plan required by that section as part of the EPP.

1.6.7 Prevention of Releases to the Environment

Procedures, such as an SPCC plan, to prevent unintended releases to the environment, to include but not limited to: air emissions, fugitive dust, and discharge to waterways.

Notifications in the event of a release to the environment

1.6.8 Regulatory Notification and Permits

List what notifications and permit applications must be made. Some permits require up to 180 days to obtain or involve 30 days (or more) advance regulator notice and authorization before site work can begin. Demonstrate that those permits have been obtained (or have been drafted for Navy review) including copies of applicable environmental permits. The EPP will not be approved until the permits have been obtained.

MANDATORY REQUIREMENT: Obtain concurrence from the Contracting Officer prior to submitting permits and other approval requests to regulatory agencies.

1.6.9 Clean Air Act Compliance

1.6.9.1 Haul Route

Submit truck and material haul routes along with a [Dirt and Dust Control Plan](#) for controlling dirt, debris, and dust on Installation roadways. As a minimum, identify in the plan the subcontractor and equipment for cleaning along the haul route and measures to reduce dirt, dust, and debris from roadways.

1.6.9.2 Pollution Generating Equipment

Identify air pollution generating equipment or processes that may require federal, state, or local permits under the Clean Air Act. Examples of such equipment includes but is not limited to: boiler(s), water heater(s), and emergency generator(s). Determine requirements based on any current installation permits and the impacts of the project. Provide a list, including specifications, of all fixed or mobile equipment, machinery or operations that could generate air emissions during the project to the

Installation Environmental Office (Air Program Manager). Examples of specifications include the fuel type and BTU rating of boilers, the fuel type and BTU rating of water heaters, the fuel type and horsepower rating of generators. These specifications will be used to determine the applicability of Air Permit requirements e.g. Construction Permit, Notification of Insignificant Activities. Consult with PWD-EV DIV (Air Program Manager) to ensure required permits are obtained prior to installing and operating applicable equipment/processes. Contractor is responsible for drafting the required permit application(s) and/or Notifications of Insignificant Activities. Ensure required permits are obtained prior to installing and operating applicable equipment/processes.

1.6.9.3 Stationary Internal Combustion Engines

Identify portable and stationary internal combustion engines that will be supplied, used or serviced. Comply with 40 CFR 60 Subpart IIII, 40 CFR 60 Subpart JJJJ, 40 CFR 63 Subpart ZZZZ, and local regulations as applicable. At minimum, include the make, model, serial number, manufacture date, size (engine brake horsepower), and EPA emission certification status of each engine. Maintain applicable records and log hours of operation and fuel use. Logs must include reasons for operation and delineate between maintenance/testing, emergency, and non-emergency operation.

1.6.9.4 Refrigerants

Contractors must comply with the Naval Station Great Lakes Refrigerant Compliance Plan (issued Jan 2025), follow steps outlined in the NAVFAC Mid-Lant process # ML-B-15.2.2 Refrigeration Compliance Management, and use the "CAA 40-82F" forms described in both of the aforementioned documents to report activity to the Contracting Officer, PWD FMD, and PWD EV. Submit completed forms to Eric Hunter in requirements and PWD EV department.

Identify management practices to ensure that heating, ventilation, and air conditioning (HVAC) work involving refrigerants complies with 40 CFR 82 requirements. Technicians working on, removing or maintaining refrigeration systems or air conditioning equipment must have current Section 608 Technician Certification. Technicians must be certified, maintain copies of certification on site, use certified equipment and log work that requires the addition or removal of refrigerant. Any refrigerant reclaimed is the property of the Government, coordinate with the PWD-EV Division to determine the appropriate turn in location. Any recovered R22 materials must be returned to PWD Shops. Removing these materials off-site is prohibited. An "Appliance" or "Chiller" form must be completed and returned to PWD-EV DIV for any "old" refrigeration or air conditioning equipment scheduled for disposal. These solid wastes may have specific additional Federal, state, or local controls for handling, storage, or disposal.

New and converted HVAC&R equipment shall include refrigerant isolation valves and service apertures to facilitate recovery and recycling procedures.

1.6.9.5 Air Pollution-engineering Processes

Identify planned air pollution-generating processes and management control measures (including, but not limited to, spray painting, abrasive blasting, demolition, material handling, fugitive dust, and fugitive emissions). Log hours of operations and track quantities of materials used.

1.6.9.6 Compliant Materials

Provide the Government a list of SDSs for all hazardous materials proposed for use on site. Materials must be compliant with all Clean Air Act regulations for emissions including solvent and volatile organic compound contents, and applicable National Emission Standards for Hazardous Air Pollutants requirements. The Government may alter or limit use of specific materials as needed to meet installation permit requirements for emissions.

1.7 LICENSES AND PERMITS

Obtain licenses and permits required for the construction of the project and in accordance with FAR 52.236-7 Permits and Responsibilities. Notify the Government of all equipment that may require permits or special approvals that the Contractor plans to use on site. This paragraph supplements the Contractor's responsibility under FAR 52.236-7 Permits and Responsibilities.

The Contactor, including their representative(s), is prohibited from initiating contact with federal, state, or local agencies on behalf of NSGL without prior written consent from the Contracting Officer. This requirement shall apply to all correspondence, permits, spills, or environmental emergency incidents occurring on NSGL.

Copies of all environmental related permits or other regulatory authorizations shall be submitted to the PWD-EV DIV via Contracting Officer for approval prior to submission to the applicable regulatory agencies. Permits or other regulatory authorizations shall be received by the Contractor, with copy provided to the Contracting Officer, prior to start of field work. Example of permits or regulatory authorizations (this list is not all inclusive) include: Storm Water Permits, U.S. Army Corps of Engineers Permits, and Temporary Tank Authorization. The Contractor is responsible for conforming to all permit requirements, performing all quality control inspections of the work in progress, and to submit notifications and certifications to the applicable regulatory agency via the Contracting Officer.

NOTE: No permits or regulatory approvals will be prepared and/or obtained by the Navy or Contracting Officer.

Where required by State regulations, inspections and certifications will be provided through the services of a Professional Engineer (PE), registered where the work is being performed, i.e. State of Illinois. Where a PE is not required, the individual must be otherwise qualified by other current State licensure, specific training and prior experience (minimum 5 years). As part of the Employee Training Records submittal, provide a sub item containing the name, appropriate professional registration or license number, address, and telephone number of the professionals or other qualified persons who will be performing the inspections and certifications for each permit.

1.8 ENVIRONMENTAL RECORDS BINDER

Maintain on-site a separate three-ring Environmental Records Binder and submit at the completion of the project. Make separate parts within the binder that correspond to each submittal listed under paragraph CLOSEOUT SUBMITTALS in this section.

1.9 SOLID WASTE MANAGEMENT PERMIT

Provide the Contracting Officer with written notification of the quantity of anticipated solid waste or debris that is anticipated or estimated to be generated by construction. Include in the report the locations where various types of waste will be disposed or recycled. Include letters of acceptance from the receiving location or as applicable; submit one copy of the receiving location state and local Solid Waste Management Permit or license showing such agency's approval of the disposal plan before transporting wastes off Government property.

1.9.1 Monthly Solid Waste Disposal Report

Monthly, submit a solid waste disposal report to the Contracting Officer. For each waste, the report will state the classification (using the definitions provided in this section), amount, location, and name of the business receiving the solid waste.

1.10 FACILITY HAZARDOUS WASTE GENERATOR STATUS

Naval Station Great Lakes is designated as a Large Quantity Generator. Meet the regulatory requirements of this generator designation for any work conducted within the boundaries of this Installation. Comply with provisions of federal, state, and local regulatory requirements applicable to this generator status regarding training and storage, handling, and disposal of construction derived wastes.

PART 2 PRODUCTS

2.1 PRODUCTS AND BUILDING MATERIALS

The Contractor shall ensure all new and/or replacement products, building materials and components of construction are free of recognized hazardous contents. Prohibited contents include (this list is not all inclusive): asbestos-containing materials; lead and chromium containing paints and surface coating materials; mercury; polychlorinated biphenyls (PCBs); and Per- and Polyfluoroalkyl substances (PFAS). Only low NOX burners for boilers and water heaters shall be installed. Upon request from the Navy, Contractor shall provide Safety Data Sheets or other testing data demonstrating that the materials of construction do not contain any recognized hazardous content.

Products shall comply with FAR 23.1 and FAR 23.7. To the maximum extent practicable, purchase sustainable products and services identified or recommended by the Environmental Protection Agency.

For guidance on which PFAS substances are prohibited, please refer to the "Addition of Certain PFAS to the TRI by the National Defense Authorization Act" at <https://www.epa.gov/toxics-release-inventory-tri-program/list-pfas-added-tri-ndaa>

Exemption to this restriction may be requested in writing from the Contracting Officer if an acceptable substitute is unavailable or mandated by military specifications.

The Contractor shall strive to incorporate sustainable acquisition for the supply of products and services. Guidance can be found at these sites: <https://www.gsa.gov/governmentwide-initiatives/climate-action-and->

sustainability/buy-green-products-services-and-vehicles
and
<https://www.epa.gov/greenerproducts/introduction-ecolabels-and-standards-greener-products>

PART 3 EXECUTION

3.1 PROTECTION OF NATURAL RESOURCES

Minimize interference with, disturbance to, and damage to fish, wildlife, and plants, including their habitats. Prior to the commencement of activities, consult with PWD-EV Division as applicable, regarding rare species or sensitive habitats that need to be protected. The protection of rare, threatened, and endangered animal and plant species identified, including their habitats, is the Contractor's responsibility.

Preserve the natural resources within the project boundaries and outside the limits of permanent work. Restore to an equivalent or improved condition upon completion of work that is consistent with the requirements of the PWD-EV Division or as otherwise specified. Confine construction activities to within the limits of the work indicated or specified. If the work is within the Lake Michigan watershed, wetlands, streams, or contributing waterways thereof, conform to the national permitting requirements of the Clean Water Act.

Avoid impacts to migratory birds during nesting season (approximately April to September). The Migratory Bird Treaty Act prohibits the take of protected migratory bird species without prior authorization. Ensure project area does not contain active bird nests prior to work starting.

3.1.1 Flow Ways

Do not alter water flows or otherwise significantly disturb the native habitat adjacent to the project and critical to the survival of fish and wildlife located on or within proximity to the project site.

3.1.2 Vegetation

Except in areas to be cleared, do not remove, cut, deface, injure, or destroy existing trees or shrubs without the Contracting Officer's permission. Do not fasten or attach ropes, cables, or guys to existing nearby trees for anchorages unless authorized by the Contracting Officer. Where such use of attached ropes, cables, or guys is authorized, the Contractor is responsible for any resultant damage.

Protect existing trees that are to remain to ensure they are not injured, bruised, defaced, or otherwise damaged by project operations. By approved methods, remove trees with 30 percent or more of their root systems damaged or destroyed. Remove trees and other landscape features scarred or damaged by equipment operations.

Undamaged replacement plantings are required for removed trees and damaged landscaping. Contractor is required to submit a proposed landscape plan for approval by the Contracting Officer and PWD-EV DIV that identifies replacement plantings with common name, scientific name, quantity of each, and proposed planting sites. Proposed landscape plan must comply with the Integrated Natural Resources Management Plan. Replacement plantings shall be appropriate for planting location and obtained from nursery stock with 35-mile distance from NSGL.

For lawn and grass seeding, permanent seed mix shall be applied, unless otherwise specified by the Contract. Seed mix must be free of noxious weeds. Seed shall be applied at a time best suited for germination of the species selected. Seeded areas shall achieve 95-percent coverage and weed free at the end of the establishment-period. Sodded areas shall achieve 100% coverage and be weed free. Pollinator-friendly native grass and wildlife seed mixes should be used to the extent practicable in appropriate areas.

Contractor is responsible for maintenance of all replacement vegetation which includes watering, weeding, trimming, edging, and necessary preservation and maintenance care for a minimum of two-years from date of planting acceptance by the Navy. Additionally, plantings must be guaranteed against loss, disease, pests, or otherwise degradation for this time period. Vegetation failing to flourish or otherwise survive shall be replaced in kind at the Contractor's expense.

3.1.3 Streams

Stream crossings must allow movement of materials or equipment without violating water pollution control standards of the federal, state, and local governments. Construction of stream crossing structures must be in compliance with all required permits including, but not limited to, Clean Water Act Section 404, and Section 401 Water Quality.

The Contracting Officer's approval and appropriate permits are required before any equipment will be permitted to ford (i.e. enter or cross) streams or creeks. In areas where frequent crossings are required, install temporary culverts or bridges. Obtain Contracting Officer's approval prior to installation. Remove temporary culverts, bridges, and related structures upon completion of work, and restore the impacted area to a condition equal to or better than its original condition.

3.2 STORMWATER

Do not discharge stormwater from construction sites to the sanitary sewer. If the water is noted or suspected of being contaminated, it may only be released to the storm drain system if the discharge is specifically permitted. Obtain authorization in advance from the Installation Environmental Office for any release of contaminated water.

3.2.1 Construction General Permit

If one or more acres (0.4 or more hectares) of total land area are to be disturbed, a Construction General Permit is required to be submitted to the Illinois EPA. The measurement of total land area to be disturbed includes all project lay down areas. Under the terms and conditions of the permit, install, inspect, maintain BMPs, prepare stormwater erosion and sediment control inspection reports, and submit SWPPP inspection reports. Maintain construction operations and management in compliance with the terms and conditions of the general permit for stormwater discharges from construction activities.

3.2.1.1 Stormwater Pollution Prevention Plan

Submit a project-specific Stormwater Pollution Prevention Plan (SWPPP) to the Contracting Officer for approval, within 30 days of Contract Award and prior to the commencement of work. The SWPPP must meet the requirements of

40 CFR 122.26 and the Illinois EPA General Permit for stormwater discharges from construction sites.

Include the following:

- a. Comply with terms of the Illinois EPA general permit for stormwater discharges from construction activities. Prepare SWPPP in accordance with Illinois EPA requirements. Use EPA guide Developing your Stormwater Pollution Prevention Plan located at <https://www.epa.gov/npdes/developing-stormwater-pollution-prevention-plan-swppp> to prepare the SWPPP.
- b. Select applicable BMPs from EPA Fact Sheets located at <https://www.epa.gov/npdes/national-menu-best-management-practices-bmps-stormwater#constr> or in accordance with applicable state or local requirements.
- c. Include a completed copy of the Notice of Intent, BMP Inspection Report Template, and Stormwater Notice of Termination, except for the effective date.
- d. Comply with additional local requirements.

3.2.1.2 Stormwater Notice of Intent for Construction Activities

Any construction activity that results in total land disturbance of 1 acre or more must prepare and submit the Notice of Intent for NPDES coverage under the general permit for construction activities. Before submitting to the EPA, it must first be sent to the Contracting Officer for review and approval.

Submit the approved NOI and appropriate permit fees using the EPA Gateway Portal. For further guidance, go to https://usepa.servicenowservices.com/oeca_icis. No land disturbing activities may commence without permit coverage. Maintain an approved copy of the SWPPP at the onsite construction office, and continually update as regulations require, reflecting current site conditions.

Comply with additional state and local requirements.

3.2.1.3 Inspection Reports

Submit "Inspection Reports" to the Contracting Officer in accordance with Illinois EPA Construction General Permit.

3.2.1.4 Stormwater Pollution Prevention Plan Compliance Notebook

Create and maintain a three ring binder of documents that demonstrate compliance with the Construction General Permit. Include a copy of the permit Notice of Intent, proof of permit fee payment, SWPPP and SWPPP update amendments, inspection reports and related corrective action records, copies of correspondence with the EPA, and a copy of the permit Notice of Termination in the binder. At project completion, the notebook becomes property of the Government. Provide the compliance notebook to the Contracting Officer.

3.2.1.5 Stormwater Notice of Termination for Construction Activities

Submit a Notice of Termination to the Contracting Officer for approval once

construction is complete and final stabilization has been achieved on all portions of the site for which the permittee is responsible. Once approved, submit the Notice of Termination to the appropriate state or federal agency. Prepare [as-built topographic survey](#) information required by the permitting agency for certification of the stormwater management system, and provide to the Contracting Officer.

3.2.2 Erosion and Sediment Control [Plan and Measures](#)

[Submit an Erosion and Sediment Control Plan to the Contracting Officer. Preserve vegetation to the maximum extent practicable. Measures shall be in accordance with state and local laws and regulations. The management practices, controls, and other provisions contained in the plan shall minimally meet the protective requirements in the Illinois Urban Manual, IUM.](#)

[The Contractor's best management practices must also be in accordance with the State of Illinois National Pollutant Discharge Elimination System \(NPDES\) Storm Water Pollution Prevention requirements. Any temporary measures must be removed after the area has been stabilized.](#)

Erosion control inspection reports may be compiled as part of a stormwater pollution prevention plan inspection reports.

3.2.2.1 Erosion Control

Prevent erosion by [appropriate methods including but not limited to: mulching, Compost Blankets, Geotextiles, and temporary slope drains.](#) Stabilize slopes by sodding, seeding, or such combination of these methods necessary for effective erosion control. Use of hay bales is prohibited.

Provide seeding in accordance with Section [VEGETATION](#).

3.2.2.2 Sediment Control Practices

Implement sediment control practices to divert flows from exposed soils, temporarily store flows, or otherwise limit runoff and the discharge of pollutants from exposed areas of the site. Implement sediment control practices prior to soil disturbance and prior to creating areas with concentrated flow, during the construction process to minimize erosion and sediment laden runoff. Include the following devices: silt fence, temporary diversion dikes, [and storm drain inlet protection.](#) Location and details of installation and construction are indicated on the drawings.

3.2.3 Work Area Limits

Mark the areas that need not be disturbed under this Contract prior to commencing construction activities. Mark or fence isolated areas within the general work area that are not to be disturbed. Protect monuments and markers before construction operations commence. Where construction operations are to be conducted during darkness, all markers must be visible in the dark. Personnel must be knowledgeable of the purpose for marking and protecting particular objects.

3.2.4 Contractor Facilities and Work Areas

Place field offices, staging areas, stockpile storage, and temporary buildings in areas designated on the drawings or as directed by the [PWD-EV Division Stormwater Manager via the](#) Contracting Officer. Move or relocate the Contractor facilities only when approved by the Government. Provide

erosion and sediment controls for onsite borrow and spoil areas to prevent sediment from entering nearby waters. Control temporary excavation and embankments for plant or work areas to protect adjacent areas.

3.2.5 Municipal Separate Storm Sewer System (MS4) Management

Comply with the Installation's MS4 permit requirements. [Comply with local requirements.](#)

3.3 SURFACE AND GROUNDWATER

3.3.1 Cofferdams, Diversions, and Dewatering

Do not discharge excavation ground water to the sanitary sewer, storm drains, [Skokie Creek](#), or to surface waters of [Lake Michigan including Pettibone Creek and its tributaries](#) without prior specific authorization in writing from the [PWD-EV Division](#). Discharge of hazardous substances will not be permitted under any circumstances. Use sediment control BMPs, [such as coir logs or other methods acceptable to PWD-EV Division](#), to prevent construction site runoff from directly entering any storm drain or surface waters. [Contractor shall provide erosion protection of the surrounding soils.](#) Lay down areas shall be pre-approved. Lay-down areas shall not be located near environmentally sensitive areas such as floor drains, storm drains and building air intakes.

[The Contractor's diversions and dewatering operations must comply with the state of Illinois water quality standards and anti-degradation provisions, Section 404 of the Clean Water Act, and the Section 401 Water Quality Certification for this project.](#)

3.3.1.1 Dewatering Plan

[If dewatering will be conducted, submit a Dewatering Plan to the Contracting Officer. Groundwater from construction activities will require collection and temporary storage, allowing time for sampling, analysis, and approval from PWD-EV DIV to discharge to the sanitary sewer or for any treatment requirements. After proper analysis of encountered groundwater, and upon approval by PWD-EV DIV, it can be discharged to the sanitary sewer. To obtain approval from PWD-EV DIV, the groundwater should be analyzed for analytes and compounds listed in the Northshore Water Reclamation District \(NSWRD\) Ordinance titled "Northshore Water Reclamation District, An Ordinance Relating to Sewers and Sewer Systems" dated June 26, 2023 \(the most recent version is to be used when available\), and meet the limits set forth in Section 5.02 of this ordinance.](#)

[In addition, NSWRD set forth the following discharge limits for NSGL:](#)

pH	5-10.5 Standard Units (S.U.)
Sulfide	0.5 mg/l
Mercury	0.38 ppb

[NOTE: Above limits shall be met, irrespective of the limits set forth in the NSWRD Ordinance cited above.](#)

[Provide PWD-EV DIV \(Wastewater Manager\) with information on infiltrated groundwater management, temporary storage capacity, locations, and any filtration and/or treatment actions planned prior to work start.](#)

[If construction dewatering is noted or suspected of being contaminated, it may only be released to the storm drain system if the discharge is](#)

specifically permitted. Obtain authorization for any contaminated groundwater release in advance from PWD-EV DIV and the federal or state authority, as applicable.

Contractor shall submit to the Contracting Officer site specific details, to include drawings, maps, and/or aerial photos of procedures that will be applied if project will impact waters of the U.S. or environmentally sensitive areas (i.e. wetland, collection or retention basins, etc.).

3.3.2 Waters of the United States

Do not enter, disturb, destroy, or allow discharge of contaminants into waters of the United States. The protection of waters of the United States shown on the drawings in accordance with paragraph LICENSES AND PERMITS is the Contractor's responsibility. Authorization to enter specific waters of the United States identified does not relieve the Contractor from any obligation to protect other waters of the United States within, adjacent to, or in the vicinity of the construction site and associated boundaries.

3.3.3 Stream Crossings

Comply with the State of Illinois water quality standards and anti-degradation provisions, Section 404 of the Clean Water Act, and the Section 401 Water Quality Certification for construction of stream crossing for this project.

3.4 PROTECTION OF CULTURAL RESOURCES

3.4.1 Archaeological Resources

Carefully protect in-place archaeological resources within the work area and be responsible for their preservation during the life of the Contract. If, during excavation or other construction activities, any previously unidentified or unanticipated historical, archaeological, and cultural resources are encountered, activities that may damage or alter such resources will be suspended. Resources covered by this paragraph include, but are not limited to: any human skeletal remains or burials; artifacts; shell, midden, bone, charcoal, or other deposits; rock or coral alignments, pavings, walls, or other constructed features; and any indication of agricultural or other human activities. Upon such an encounter, immediately notify the Contracting Officer and PWD-EV Division Cultural Resources Manager so that the appropriate authorities may be notified and a determination made as to their significance and what, if any, special disposition of the finds should be made. Cease all activities that may result in impact to or the destruction of these resources until directed by the Contracting Officer to resume work. Secure the area and prevent employees or other persons from trespassing on, removing, or otherwise disturbing such resources. The Government retains ownership and control over archaeological resources.

3.4.2 Historical Resources

Existing historical resources within the work area are shown on the drawings upon request when information is available. Protect these resources and be responsible for their preservation during the life of the Contract.

3.5 AIR RESOURCES

Equipment operation, activities, or processes will be in accordance with

40 CFR 64, 40 CFR 82, and state air emission and performance laws and standards.

3.5.1 Preconstruction Air Permits

Notify the Air Program Manager, through the Contracting Officer, at least 6 months prior to bringing equipment, assembled or unassembled, onto the Installation, so that air permits can be secured. Necessary permitting time must be considered in regard to construction activities. Clean Air Act (CAA) permits must be obtained prior to bringing equipment, assembled or unassembled, onto the Installation.

3.5.2 Oil or Dual-fuel Boilers and Furnaces

Provide product data and details for new, replacement, or relocated fuel fired boilers, heaters, or furnaces to the PWD-EV Division Air Program Manager and PWD-FMD through the Contracting Officer. Data to be reported include: equipment purpose (water heater, building heat, process), manufacturer, model number, serial number, fuel type (oil type, gas type) size (MMBTU heat input), and manufacturers' published emission rates for air pollutants. Provide in accordance with paragraph PRECONSTRUCTION AIR PERMITS.

3.5.3 Burning

Burning is prohibited on the Government premises.

3.5.4 Class I and II ODS Prohibition

Class I and II ODS are Government property and must be returned to the Government for appropriate management. Contractors are prohibited from selling or otherwise transferring any Class I and Class II ODS outside the Navy without written consent. Contract specifications and contractual actions shall not include the transfer of Class I and Class II ODS to Contractors. The Contractor, as directed in writing by the Contracting Officer shall deposit excess Class I and Class II ODS into the Navy portion of the DoD ODS-Reserve. Class I and Class II ODS on site include R12 and R22 respectively. All shipments of ODS off-site shall comply with the provisions of 40 CFR Part 173.301 'General Provisions for Shipments of Compressed Gases in Cylinders.' Refrigerant recovered and recycled may be stored and used locally in order to service existing Class I and Class II ODS Air Conditioning and Refrigeration (AC&R) equipment as part of the contracted work, or turn into the NSGL PWD AC Shop for re-use, coordinated via the Contracting Officer. Any recovered R22 materials must be returned to NSGL PWD Shops and removing these materials off site is prohibited. Class I and II ODS will not be used in the performance of this contract, nor be provided as part of the equipment unless required by government/military specification. This prohibition will be considered to prevail over any other provision, specification, drawing, or referenced documents. Regulations related to the protection of stratosphere ozone may be found in 40 CFR 82.

All released, recovered/reclaimed, recycled or deposits made to the DoD ODS-Reserve shall be reported to NSGL PWD-EV DIV (Air Program Manager) and PWD-FMD. Minimum report requirements include - name and type of ODS; amount (reported in pounds); date; and HVAC&R units involved. For any "old" refrigeration and/or air conditioning equipment scheduled for disposal, an "Appliance" or "Chiller" form must be completed and returned to EV.

Disposal of appliances with a refrigerant charge in excess of five (5) must be tracked. See the NSGL PWD-EV DIV Air Program Manager for the appropriate forms. The form must be completed and returned to NSGL PWD-EV DIV (Air Program Manager) and PWD-FMD.

3.5.4.1 Labels

As required per 48 CFR 52.223-11, 23.804(a)(1) and FAR 52.223-11, the Contractor shall label products that contain or are manufactured with ozone-depleting substances in the manner and to the extent required by 42 U.S.C. 7671 and 40 CFR part 82 subpart E as follows: "Warning: Contains (or manufactured with, if applicable) *insert the name of substances*, a substance(s) which harm(s) public health and environment by destroying ozone in the upper atmosphere.

As required per 48 CFR 52.223-12, 23.804(a)(2) and FAR 52.223-12, the Contractor shall comply with the applicable requirements of Sections 608 and 609 of the Clean Air Act (42 U.S.C.7671g and 7 671h). Unless otherwise specified in the contract, the Contractor shall reduce the use, release, or emissions of high global warming potential hydrofluorocarbons under this contract by:

- a) Transitioning over time to the use of another acceptable alternative in lieu of high global warming potential hydrofluorocarbons in a particular end use for which EPA's SNAP program has identified other acceptable alternatives that have lower global warming potential;
- b) Preventing and repairing refrigerant leaks through service and maintenance during contract performance;
- c) Implementing recovery, recycling, and responsible disposal programs that avoid release or emissions during equipment service and as the equipment reaches the end of its useful life; and
- d) Using reclaimed hydrofluorocarbons, where feasible.

The Contractor shall refer to EPA's SNAP program (available at <http://www.epa.gov/snap>) to identify alternatives. The SNAP list of alternatives is found at 40 CFR part 82 subpart G with supplemental tables available at <http://www.epa.gov/snap>

For equipment and appliances that normally each contain 50 or more pounds of hydrofluorocarbons or refrigerant blends containing hydrofluorocarbons and any equipment that will be maintained, serviced, repaired, or disposed under this contract the Contractor shall:

- a) Track on an annual basis, between October 1 and September 30, the amount in pounds of hydrofluorocarbons or refrigerant blends containing hydrofluorocarbons contained in the equipment and appliances delivered to the Government under this contract by
 - 1) Type of hydrofluorocarbon (e.g., HFC-134 a, HFC-125, R-410 A, R-404 A, etc.);
 - 2) Contract number; and
 - 3) Equipment/appliance
- b) Report that information to the Contracting Officer annually by November 30 of each year during contract performance and at the end of contract performance.

3.5.5 Venting of Refrigerant

Accidental venting of a refrigerant is a release and must be reported immediately to the Contracting Officer, NSGL PWD-EV DIV Air Program Manager, and PWD-FMD. Intentional venting of refrigerants (including most Non-ODS substitute refrigerants) is prohibited per 40 CFR 82.

3.5.6 EPA Certification Requirements

Heating and air conditioning technicians must be certified through an EPA-approved program. Maintain copies of certifications at the employees' places of business; technicians must carry certification wallet cards, as provided by environmental law.

The Contractor shall use EPA-approved refrigerant recovery equipment for all commercial off-the-shelf equipment. For equipment designed and used solely by the military (military-unique systems), recovery equipment shall be designed to the extent practical, to achieve performance comparable to the EPA equipment requirement. EPA-approved refrigerant recovery equipment shall be calibrated with proper calibration gas prior to each use. Calibration gas must be within the specified shelf-life as recommended in the SDS.

3.5.7 Dust Control

Keep dust down at all times, including during nonworking periods. Sprinkle or treat, with dust suppressants, the soil at the site, haul roads, and other areas disturbed by operations. Dry power brooming will not be permitted. Instead, use vacuuming, wet mopping, wet sweeping, or wet power brooming. Air blowing will be permitted only for cleaning nonparticulate debris such as steel reinforcing bars. Only wet cutting will be permitted for cutting concrete blocks, concrete, and bituminous concrete. Do not unnecessarily shake bags of cement, concrete mortar, or plaster. Since these products contain Crystalline Silica, comply with the applicable OSHA standard, 29 CFR 1910.1053 or 29 CFR 1926.1153 for controlling exposure to Crystalline Silica Dust. Release of fugitive dust is cause for project shutdown by PWD-EV Division.

3.5.7.1 Particulates

Dust particles, aerosols and gaseous by-products from construction activities, and processing and preparation of materials (such as from asphaltic batch plants) must be controlled at all times, including weekends, holidays, and hours when work is not in progress. Maintain excavations, stockpiles, haul roads, permanent and temporary access roads, plant sites, spoil areas, borrow areas, and other work areas within or outside the project boundaries free from particulates that would exceed 40 CFR 50, state, and local air pollution standards or that would cause a hazard or a nuisance. Sprinkling, chemical treatment of an approved type, baghouse, scrubbers, electrostatic precipitators, or other methods will be permitted to control particulates in the work area. Sprinkling, to be efficient, must be repeated to keep the disturbed area damp. Provide sufficient, competent equipment available to accomplish these tasks. Perform particulate control as the work proceeds and whenever a particulate nuisance or hazard occurs. Comply with state and local visibility regulations.

3.5.7.2 Abrasive Blasting

Blasting operations cannot be performed without prior approval of the PWD-EV Division Air Program Manager. The use of silica sand is prohibited in sandblasting.

Provide tarpaulin drop cloths and windscreens to enclose abrasive blasting operations to confine and collect dust, abrasive agent, paint chips, and

other debris. Perform work involving removal of hazardous material in accordance with 29 CFR 1910.

Submit analytical results of the debris generated from abrasive blasting operations per paragraph LABORATORY ANALYSIS. Hazardous waste generated from blasting operations will be managed in accordance with paragraph HAZARDOUS WASTE/DEBRIS MANAGEMENT and with the PWV-EV Division Hazardous Waste Manager approval. Disposal of non-hazardous abrasive blasting debris will be in accordance with paragraph SOLID WASTE MANAGEMENT.

3.5.8 Odors

Control odors from construction activities. The odors must be in compliance with state regulations and local ordinances and may not constitute a health hazard.

3.6 WASTE MINIMIZATION

Minimize the use of hazardous materials and the generation of waste. Include procedures for pollution prevention/ hazardous waste minimization in the Hazardous Waste Management Section of the EPP. Obtain a copy of the installation's Pollution Prevention/Hazardous Waste Minimization Plan for reference material when preparing this part of the EPP. If no written plan exists, obtain information by contacting the Contracting Officer. Describe the anticipated types, estimated quantities, use/application, and alternative options of the of the hazardous materials to be used in the performance of the contracted work.

3.6.1 Salvage, Reuse and Recycle

Identify anticipated materials and waste for salvage, reuse, and recycling. Describe actions to promote material reuse, resale or recycling. To the extent practicable, all scrap metal must be sent for reuse or recycling and will not be disposed of in a landfill.

Include the name, physical address, and telephone number of the hauler, if transported by a franchised solid waste hauler. Include the destination and, unless exempted, provide a copy of the state or local permit (cover) or license for recycling.

3.6.2 Nonhazardous Solid Waste Diversion Report

Maintain an inventory of nonhazardous solid waste diversion and disposal of construction and demolition debris. Submit a report to the Contracting Officer on the first working day after each fiscal year quarter, starting the first quarter that nonhazardous solid waste has been generated. Include the following in the report:

Construction and Demolition (C&D) Debris Disposed	_____ cubic yards or tons, as appropriate
C&D Debris Recycled	_____ cubic yards or tons,
C&D Debris Composted	_____ cubic yards or tons, as appropriate
Total C&D Debris Generated	_____ cubic yards or tons, as appropriate

Construction and Demolition (C&D) Debris Disposed	_____ cubic yards or tons, as appropriate
Waste Sent to Waste-To-Energy Incineration Plant (This amount should not be included in the recycled amount)	_____ cubic yards or tons, as appropriate

3.7 WASTE MANAGEMENT AND DISPOSAL

3.7.1 Waste Determination Documentation

All potentially hazardous solid waste streams that are not subject to a specific exclusion or exemption from the hazardous waste regulations (e.g., scrap metal, domestic sewage) or subject to special rules, (lead-acid batteries and precious metals) must be characterized in accordance with the requirements of 40 CFR 262.11 or corresponding applicable state or local regulations. Base waste determination on user knowledge of the processes and materials used, and analytical data when necessary. Consult with the Installation environmental staff for guidance on specific requirements. Attach support documentation to the Waste Determination form. As a minimum, provide a Waste Determination form for the following waste (this listing is not exhaustive): oil- and latex -based painting and caulking products, solvents, adhesives, aerosols, petroleum products, and containers of the original materials.

3.7.1.1 Sampling and Analysis of Waste

3.7.1.1.1 Waste Sampling

Sample waste in accordance with EPA SW-846 and EPA 530/F-93/004. Clearly mark each sampled drum or container with the Contractor's identification number, and cross reference to the chemical analysis performed.

3.7.1.1.2 Laboratory Analysis for Waste Disposal

Follow the analytical procedure and methods in accordance with the 40 CFR 261. Provide analytical results and reports performed to the Contracting Officer. Coordinate all activities with PWD-EV Division Hazardous Waste Manager. Contractor must provide copy of analytical results to Contracting Officer and PWD-EV DIV within 3 calendar days from receipt.

3.7.1.1.3 Analysis Type

Identify hazardous waste by analyzing for the following characteristics: ignitability, corrosivity, reactivity, toxicity based on TCLP results, PCBs, and cyanide. The analyte list could vary based on generator knowledge of the waste stream and concurrence from PWD-EV Division.

3.7.2 Solid Waste Management

3.7.2.1 Control and Management of Solid Wastes

Pick up solid wastes, and place in covered containers that are regularly emptied. Do not prepare or cook food on the project site. Prevent contamination of the site or other areas when handling and disposing of wastes. At project completion, leave the areas clean for acceptance by the

Contracting Officer. Employ segregation measures so that no hazardous or toxic waste will become co-mingled with non-hazardous solid waste. Transport solid waste off Government property and dispose of it **off-site at an approved landfill** in compliance with **40 CFR 260**, state, and local requirements for solid waste disposal. A Subtitle D RCRA permitted landfill is the minimum acceptable offsite solid waste disposal option. Verify that the selected transporters and disposal facilities have the necessary permits and licenses to operate. Solid waste disposal offsite must comply with most stringent local, state, and federal requirements, including **40 CFR 241**, **40 CFR 243**, and **40 CFR 258**.

Equip dumpsters with a secure cover and keep covers closed at all times, except when being loaded with trash and debris. For large demolitions, large dumpsters without lids are acceptable but should not have debris higher than the sides before emptying. Empty dumpsters at least once per week, or as needed to keep the site free of debris and trash. Locate dumpsters behind the construction fence or out of the public view. If necessary, provide 55-gallon trash containers to collect debris in the construction site area. Locate trash containers behind the construction fence or out of the public view. Empty trash containers at least once a day, or as needed to keep the site free of trash..

Manage hazardous material used in construction, including but not limited to, aerosol cans, waste paint, cleaning solvents, contaminated brushes, and used rags, in accordance with **49 CFR 173**.

3.7.3 Control and Management of Hazardous Waste

Do not dispose of hazardous waste on Government property. Do not discharge any waste to a sanitary sewer, storm drain, or to surface waters or conduct waste treatment or disposal on Government property without written approval of the Contracting Officer and **PWD-EV Division** Hazardous Waste Manager.

3.7.3.1 Hazardous Waste/Debris Management

Identify construction activities that will generate hazardous waste or debris. Provide a documented waste determination for resultant waste streams. Identify, label, handle, store, and dispose of hazardous waste or debris in accordance with federal, state, and local regulations, including **40 CFR 261**, **40 CFR 262**, **40 CFR 263**, **40 CFR 264**, **40 CFR 265**, **40 CFR 266**, and **40 CFR 268**.

Manage hazardous waste in accordance with the approved Hazardous Waste Management Section of the EPP. Store hazardous wastes in approved containers in accordance with **49 CFR 173** and **49 CFR 178**. Hazardous waste generated within the confines of Government facilities is identified as being generated by the Government. Prior to removal of any hazardous waste from Government property, hazardous waste manifests must be signed by personnel from the **PWD-EV Division**. Do not bring hazardous waste onto Government property. Provide the Contracting Officer with a copy of waste determination documentation for any solid waste streams that have any potential to be hazardous waste or contain any chemical constituents listed in **40 CFR 372-SUBPART D**. **Refer to Section 3.13 for hazardous or regulated waste spill procedures.**

3.7.3.2 Waste Storage/Satellite Accumulation/90 Day Storage Areas

Accumulate hazardous waste at satellite accumulation points and in compliance with **40 CFR 262** and applicable state or local regulations. **If**

the work requires the temporary collection/storage of regulated or hazardous wastes, the Contractor must establish a Satellite Accumulation Area (SAA) or a 90 Day Storage Area at the point of generation. Submit a request in writing to the Contracting Officer and provide the following information (Attach Site Plan to the Request):

Contract Number	_____
Contractor	_____
Haz/Waste or Regulated Waste POC	_____
Phone Number	_____
Type of Waste	_____
Source of Waste	_____
Emergency POC	_____
Phone Number	_____
Location of the Site	_____

Attach a Waste Determination form for the expected waste streams. Allow 10 working days for processing this request. Additional compliance requirements (e.g., training and contingency planning) that may be required are the responsibility of the Contractor. Barricade the designated area where waste is being stored and post a sign identifying as follows:

"DANGER - UNAUTHORIZED PERSONNEL KEEP OUT"

NOTE: All SAA requests must be approved by PWD-EV Division, to ensure compliance with SAA regulations as outlined in 40 CFR 262 and 40 CFR 265.

Once waste accumulation begins, and continuing until all hazardous / regulated / universal waste is removed from base, the Contractor must conduct and submit a weekly SAA inspection form to PWD-EV Division.

3.7.3.3 Hazardous Waste Disposal

3.7.3.3.1 Responsibilities for Contractor's Disposal

Provide hazardous waste manifest to the PWD-EV Division Hazardous Waste Manager for review, approval, and signature prior to shipping waste off Government property. No hazardous, toxic, or universal waste; or hazardous material shall be disposed or abandoned on government property. Unless otherwise noted in this contract, the government is not responsible for disposal of any Contractor-generated waste material.

The disposal of incidental materials used to accomplish the work (this list is not all inclusive) including: aerosol cans, waste paint, cleaning solvents, contaminated brushes, rags, clothing, etc. are the responsibility of the Contractor.

The Contractor is not authorized to discharge any materials to sanitary sewer, storm drain, or water way or conduct waste treatment or disposal on government property without written approval of the Contracting Officer.

3.7.3.3.1.1 Services

Provide service necessary for the final treatment or disposal of the hazardous material or waste in accordance with 40 CFR 260 - 40 CFR 279, local, and state, laws and regulations, and the terms and conditions of the Contract within 60 days after the materials have been generated. These services include necessary personnel, labor, transportation, packaging, detailed analysis (if required for disposal or transportation, include manifesting or complete waste profile sheets, equipment, and compile documentation).

3.7.3.3.1.2 Samples

Obtain a representative sample of the material generated for each job done to provide waste stream determination.

3.7.3.3.1.3 Analysis

Analyze each sample taken and provide analytical results to the Contracting Officer. See paragraph WASTE DETERMINATION DOCUMENTATION.

3.7.3.3.1.4 Labeling

During waste accumulation label all containers in accordance with 40 CFR 262. Prior to offering a waste for off-site transport, determine the Department of Transportation's (DOT's) proper shipping names for waste in accordance with 49 CFR 172 (each container requiring disposal) and demonstrate to the Contracting Officer how this determination is developed and supported by the sampling and analysis requirements contained herein. Label all containers of hazardous waste with the words "Hazardous Waste" or other words to describe the contents of the container in accordance with 40 CFR 262 and applicable state or local regulations.

3.7.3.3.2 Contractor Storage and Disposal Requirements

Hazardous waste generated must be disposed of in accordance with the following conditions to meet installation requirements acceptable for staging and disposal:

- a. Drums must be compatible with waste contents and drums must meet DOT requirements for 49 CFR 173 for transportation of materials.
- b. Band drums to wooden pallets.
- c. No more than three 55 gallon drums or two 85 gallon over packs are to be banded to a pallet.
- d. Band using 1-1/4 inch minimum band on upper third of drum.
- e. Material labels must be located in middle of drum, filled out to indicate actual volume of material, name of material manufacturer, other vendor information as available.
- f. Leave 3 to 5 inches of empty space above volume of material. This space is called 'outage'.
- g. Conduct and submit weekly Satellite Accumulation Area (SAA) inspections to PWD-EV DIV to ensure compliance with 40 CFR 262 and 40 CFR 265.

3.7.3.4 Universal Waste Management

Manage the following categories of universal waste in accordance with federal, state, and local requirements and installation instructions:

- a. Batteries as described in 40 CFR 273.2
- b. Lamps as described in 40 CFR 273.5
- c. Mercury-containing equipment as described in 40 CFR 273.4
- d. Aerosol cans as described in 40 CFR 273.6
- e. Installation specific

Mercury is prohibited in the construction of this facility, unless specified otherwise, and with the exception of mercury vapor lamps and fluorescent lamps. Dumping of mercury-containing materials and devices such as mercury vapor lamps, fluorescent lamps, and mercury switches, in rubbish containers is prohibited. Remove without breaking, pack to prevent breakage, and transport out of the activity in an unbroken condition for disposal as directed.

NOTE: All debris resulting from cleanup of broken mercury-containing devices, lamps, fluorescent bulbs, etc. shall be managed as hazardous waste for disposal.

3.7.3.5 Electronics End-of-Life Management

Recycle or dispose of electronics waste, including, but not limited to, used electronic devices such computers, monitors, hard-copy devices, televisions, mobile devices, in accordance with 40 CFR 260-262, state, and local requirements, and installation instructions.

3.7.3.6 Disposal Documentation for Hazardous and Regulated Waste

Profile, manifest, pack, ship and dispose of hazardous or toxic waste and universal waste that is generated as a result of construction in accordance with the generating facility's generator status under the Resource Conservation and Recovery Act (RCRA) or equivalent State regulation. The government reserves the right to approve or disapprove all Contractor Disposal Facilities based on compliance issues.

- a. Contractor must provide copy of analytical results to PWD-EV DIV within 3 calendar days from receipt.
- b. Contractor must provide Name, Address and EPA ID numbers of proposed waste TDSF (treatment & disposal facilities) to PWD-EV DIV for approval.
- c. Contractor will prepare draft waste profile and draft disposal manifest to PWD-EV DIV for approval prior to waste removal from base.
- d. Contact the Contracting Officer for the facility RCRA identification number (Generator EPA ID number) that is to be used on each manifest.
- e. Advance coordination (at least 48 hours) with the PWD-EV DIV (Hazardous Waste Program Manager) at (847) 688-6915 is required for hazardous and other regulated wastes.

NOTE: Only a designated PWD-EV Division representative may sign manifests on behalf of the Naval Station Great Lakes.

Submit a copy of the applicable EPA and or state permit(s), manifest(s), or license(s) for transportation, treatment, storage, and disposal of hazardous and regulated waste by permitted facilities. Hazardous regulated or universal waste manifests must be reviewed, signed, and approved by the Contracting Officer before the Contractor may ship waste off of Naval Station Great Lakes property. To obtain specific disposal instructions, the contractor must coordinate with the PWD-EV Division via the Contracting Officer.

Per the Naval Station Great Lakes Commanding Officer, manifesting approvals of hazardous and regulated waste for disposal, will be performed by PWD-EV Division. This is required for tracking purposes to maintain regulatory compliance with Federal and State Environmental Protection Agency regulations.

Manifesting arrangements shall be scheduled at least 48 hours in advance, excluding emergencies. Normal service hours are from 7 to 11:30 a.m. and 12:00 to 3:30 p.m. Monday through Friday. After business hours, weekend and holiday manifesting can be requested in writing 72-hours prior to shipment. The Government reserves the right to refuse all after hour, weekend, and holiday manifesting at the Government's convenience. The Contractor shall be responsible for preparing all manifests and waste shipment records for each load of waste to be transported off NSGL and completing all appropriate Land Disposal Notifications. The Contractor shall contact PWD-EV DIV (Hazardous Waste Manager) at (847)688-6915 for review and signature of all manifests. Generator copies of all manifests. Contractor shall provide a draft manifest to the PWD-EV DIV (Hazardous Waste Manager) before disposal process begins, to ensure the information presented on the manifest meets PWD-EV DIV and EPA requirements. Generator copies of all manifests from disposal facilities, as well as Certificates of Disposal/Recycling, shall be returned to the PWD-EV DIV within thirty (30) days of shipment off Naval Station Great Lakes. Failure to provide these documents is a violation of the Hazardous Waste standard, therefore results to future manifest denial from PWD-EV Division.

Items required prior to manifests and waste shipment records being signed:

- a. Prime Contractor
 - (1) Laboratory Reports on Waste Streams
 - (2) Draft Waste Profile Sheets
 - (3) Proposed designation of TSDF, its EPA ID number and address.
 - (4) Draft Waste Manifest
- b. Transporter
 - (1) Name, address, phone number, and P.O.C.
 - (2) Transporter's EPA ID number
 - (3) Copies of transporter permits, and hauler I.D. number
 - (4) Proof of Insurance

3.7.4 Releases/Spills of Oil and Hazardous Substances

3.7.4.1 Response and Notifications

Exercise due diligence to prevent, contain, and respond to spills of hazardous material, hazardous substances, hazardous waste, sewage, regulated gas, petroleum, lubrication oil, and other substances regulated

in accordance with 40 CFR 300. Maintain spill cleanup equipment and materials at the work site. In the event of a spill, take prompt, effective action to stop, contain, curtail, or otherwise limit the amount, duration, and severity of the spill/release. In the event of any releases of oil and hazardous substances, chemicals, or gases or other environmental-related emergency that exceeds the Contractor's capability, immediately (within 15 minutes) notify the Naval Station Great Lakes Emergency Dispatch Center and Contracting Officer. The government will respond and take prompt action when:

a. The Contractor has not promptly begun spill cleanup procedures within one hour of spill discovery/occurrence; or

b. If in the Government's judgment, the Contractor's actions are insufficient to abate life threatening conditions and/or impose an environmental threat, or otherwise threatens any body of water or environmentally sensitive areas.

3.7.4.1.1 On-site Spills or Releases

All spills or releases of petroleum products (including cooking oil and animal grease), hazardous substances, regulated waste, regulated gases or sewage occurring on Navy property shall be reported immediately (within 15-minutes) to:

Region Emergency Dispatch Center (757) 443-3623/3624
(HAZMAT, Fire, Police, Ambulance) 911

Contracting Officer (As identified during kick-off meeting)

Public Works Duty Officer (847) 204-3630
(After normal business hours)

Public Works Department EV-DIV (847) 688-5395 x270
Or (630) 715-8765

The Navy will take prompt response action as deemed necessary to contain and otherwise resolve spills or releases with potential impact to environmentally sensitive areas occurring on NSGL including storm sewers; tributary waters of Lake Michigan; creeks/streams; wetlands; critical habitats; and protected or susceptible habitats.

If the government responds or provides assets to any spill or release incident, the Contractor shall reimburse the government for all costs/expenses related to - cleanup, remediation, sample analysis, material, equipment, clothing, and labor.

3.7.4.1.2 Off-site spills or releases

All spills or releases occurring off site involving government property are the responsibility of the Contractor for reporting to federal, state and local agencies, and will also be reported to:

Contracting Officer (As identified during kick-off meeting)

Public Works Duty Officer (847) 204-3630
(After normal business hours)

Public Works Department EV-DIV (847) 688-5395 x270
Or (630) 715-8765

3.7.4.2 Reporting of Spills or Releases

The Navy's designated PWD-EV Division representative is solely responsible for reporting spill or release incidents occurring on Naval Station Great Lakes to Federal, State, and local agencies.

The Contractor is solely responsible for reporting of incidents that occur off of the Naval Station Great Lakes installation (i.e. off government property) as required by 40 CFR 355, State, local regulations and Navy Instructions.

3.7.4.3 Clean Up

Spill response shall be in accordance with 40 CFR 300, and applicable state and NSGL requirements. Contain and clean up spills without cost to the Government. Provide copies of written notification(s) and documentation that a verbal notification was made within five working days.

3.7.5 Mercury Materials

Immediately report to the Environmental Office and the Contracting Officer instances of breakage or mercury spillage. Clean mercury spill area to the satisfaction of the Contracting Officer and the PWD-EV Division.

Do not recycle a mercury spill cleanup; manage it as a hazardous waste for disposal.

3.7.6 Wastewater

3.7.6.1 Disposal of Wastewater

Disposal of wastewater must be as specified below.

3.7.6.1.1 Treatment

Do not allow wastewater from construction activities, such as onsite material processing, concrete curing, foundation and concrete clean-up, water used in concrete trucks, and forms to enter water ways or to be discharged prior to being treated to remove pollutants. Dispose of the construction- related waste water off-Government property in accordance with 40 CFR 403, state, regional, and local laws and regulations. The proposed type of treatment system shall be approved by the PWD-EV Division and its location must be coordinated and approved with the Contracting Officer.

3.7.6.1.2 Land Application

Water generated from the flushing of lines after disinfection. Disinfection cannot undergo land application and can be discharged into the sanitary sewer with prior approval and notification to the Wastewater Media Operator.

3.8 HAZARDOUS MATERIAL MANAGEMENT

Include hazardous material control procedures in the Safety Plan, in accordance with Section 01 35 26 GOVERNMENTAL SAFETY REQUIREMENTS. Address procedures and proper handling of hazardous materials, including the

appropriate transportation requirements. Do not bring hazardous material onto Government property that does not directly relate to requirements for the performance of this contract. Submit an SDS and estimated quantities to be used for each hazardous material to the Contracting Officer prior to bringing the material on the installation. Typical materials requiring SDS and quantity reporting include, but are not limited to, oil and latex based painting and caulking products, solvents, adhesives, aerosol, and petroleum products. Use hazardous materials in a manner that minimizes the amount of hazardous waste generated. Containers of hazardous materials must have National Fire Protection Association labels or their equivalent. Certify that hazardous materials removed from the site are hazardous materials and do not meet the definition of hazardous waste, in accordance with 40 CFR 261 and Illinois requirements. Incidental materials used to support the contract are the responsibility of the Contractor for disposal.

Under no circumstances is the Contractor permitted to discharge any materials or waste to the sanitary sewer or storm drain system(s), creeks, waterways or tributary waters of Lake Michigan, or dispose on Naval Station Great Lakes.

3.8.1 Contractor Hazardous Material Inventory Log

Submit the "Contractor Hazardous Material Inventory Log" (found at: <https://www.wbdg.org/ffc/dod/unified-facilities-guide-specifications-ufgs/forms-graphics-tables>), which provides information required by (EPCRA Sections 312 and 313) along with corresponding SDS, to the Contracting Officer at the start and at the end of construction (30 days from final acceptance), and update no later than January 31 of each calendar year during the life of the contract. Keep copies of the SDSs for hazardous materials onsite. At the end of the project, provide the Contracting Officer with copies of the SDSs, and the maximum quantity of each material that was present at the site at any one time, the dates the material was present, the amount of each material that was used during the project, and how the material was used.

The Contracting Officer may request documentation for any spills or releases, environmental reports, or off-site transfers.

3.9 PREVIOUSLY USED EQUIPMENT

Clean previously used construction equipment prior to bringing it onto the project site. Equipment must be free from soil residuals, egg deposits from plant pests, noxious weeds, and plant seeds. Consult with the U.S. Department of Agriculture jurisdictional office for additional cleaning requirements.

3.10 CONTROL AND MANAGEMENT OF ASBESTOS-CONTAINING MATERIAL (ACM)

Manage and dispose of asbestos- containing waste in accordance with all applicable federal, state, and local requirements. Refer to Section 02 82 00 ASBESTOS REMEDIATION. Manifest asbestos-containing waste and provide the manifest to the Contracting Officer and the PWD-EV Division Hazardous Waste Manager. Notifications to the regulatory authorities and the PWD-EV Division Installation Air Program Manager are required before starting any asbestos work.

Upon discovery of known or suspected Asbestos-Containing Material (ACM) not identified in contract documents, the Contractor shall immediately stop all work that may generate further damage to the material, and notify the

Contracting Officer for guidance.

3.11 CONTROL AND MANAGEMENT OF LEAD-BASED PAINT (LBP)

Manage and dispose of lead-contaminated waste in accordance with 40 CFR 745 and Section 02 83 00 LEAD REMEDIATION. Manifest any lead-contaminated waste and provide the manifest to the Contracting Officer.

3.12 CONTROL AND MANAGEMENT OF POLYCHLORINATED BIPHENYLS (PCBs)

Manage and dispose of PCB-contaminated waste in accordance with 40 CFR 761 and Section 02 84 33 REMOVAL AND DISPOSAL OF POLYCHLORINATED BIPHENYLS (PCBs).

3.13 CONTROL AND MANAGEMENT OF LIGHTING BALLAST AND LAMPS CONTAINING PCBs

Manage and dispose of contaminated waste in accordance with 40 CFR 761.

3.14 PETROLEUM, OIL, LUBRICANT (POL) STORAGE AND FUELING

POL products include flammable or combustible liquids, such as gasoline, diesel, lubricating oil, used engine oil, hydraulic oil, mineral oil, and cooking oil. Store POL products and fuel equipment and motor vehicles in a manner that affords the maximum protection against spills into the environment. Manage and store POL products in accordance with EPA 40 CFR 112, and other federal, state, regional, and local laws and regulations. Use secondary containments, dikes, curbs, and other barriers, to prevent POL products from spilling and entering the ground, storm or sewer drains, stormwater ditches or canals, or navigable waters of the United States. Describe in the EPP (see paragraph ENVIRONMENTAL PROTECTION PLAN) how POL tanks and containers must be stored, managed, and inspected and what protections must be provided. Storage of fuel on the project site must be in accordance with EPA, state, and local laws and regulations and paragraph OIL STORAGE INCLUDING FUEL TANKS.

3.14.1 Used Oil Management

Manage used oil generated on site in accordance with 40 CFR 279. Determine if any used oil generated while onsite exhibits a characteristic of hazardous waste. Used oil containing 1,000 parts per million of solvents is considered a hazardous waste and disposed of at the Contractor's expense. Used oil mixed with a hazardous waste is also considered a hazardous waste. Dispose in accordance with paragraph HAZARDOUS WASTE DISPOSAL.

3.14.2 Oil Storage Including Fuel Tanks

Provide secondary containment and overfill protection for oil storage tanks. A berm used to provide secondary containment must be of sufficient size and strength to contain the contents of the tanks plus 5 inches freeboard for precipitation. Construct the berm to be impervious to oil for 72 hours that no discharge will permeate, drain, infiltrate, or otherwise escape before cleanup occurs. Use drip pans during oil transfer operations; adequate absorbent material must be onsite to clean up any spills and prevent releases to the environment. Cover tanks and drip pans during inclement weather. Provide procedures and equipment to prevent overfilling of tanks. If tanks and containers with an aggregate aboveground capacity greater than 1320 gallons will be used onsite (only containers with a capacity of 55 gallons or greater are counted), provide

and implement a [Spill Prevention Control and Countermeasure \(SPCC\) plan](#) meeting the requirements of [40 CFR 112](#). Do not bring underground storage tanks to the installation for Contractor use during a project. Submit the SPCC plan to the Contracting Officer for approval.

Monitor and remove any rainwater that accumulates in open containment dikes or berms. Inspect the accumulated rainwater prior to draining from a containment dike to the environment, to determine there is no oil sheen present.

3.15 INADVERTENT DISCOVERY OF PETROLEUM-CONTAMINATED SOIL OR HAZARDOUS WASTES

If petroleum-contaminated soil, or suspected hazardous waste is found during construction that was not identified in the Contract documents, immediately notify the Contracting Officer. Do not disturb this material until authorized by the Contracting Officer.

3.16 CHLORDANE

Evaluate excess soils and concrete foundation debris generated during the demolition of housing units or other wooden structures for the presence of chlordane or other pesticides prior to reuse or final disposal.

3.17 SOUND INTRUSION

Make the maximum use of low-noise emission products, as certified by the EPA. Blasting or use of explosives are not permitted. [The Contractor is prohibited from producing or otherwise emitting noise between the weekday hours of 7 p.m. and 7 a.m. or 8 p.m. and 9 a.m. on weekends or holidays such that the emitted sound creates a disturbance extending beyond the NSGL property line.](#)

[Where technically feasible activities shall be conducted in such a manner that maximum sound levels will not create a public nuisance, or otherwise violate local ordinance. Mitigate noise from powered equipment or other noise producing sources and activities with sound barriers, muffling devices, lower settings on power equipment and shortened work cycle.](#)

[During the initial kick-off meeting, Contractor shall identify noise sources expected to produce or otherwise create nuisance noise extending beyond the project site. Examples include \(this list is not all inclusive\): pile-drivers and rock crushers.](#)

[Keep construction activities under surveillance and control to minimize environment damage by noise. Comply with the provisions of the State of Illinois rules given in \[35 IAC 900-901\]\(#\).](#)

3.18 SOIL MANAGEMENT

[Contractor must comply with the most recent version of the Naval Station Great Lakes Soils Management Plan \(revised December 2023\). Excavated soil may only be reused as backfill at the location from which it was excavated. Soils may not be abandoned in place, removed from the project site, or stockpiled elsewhere on the installation for later use.](#)

[Contractor shall provide the PWD-EV Division with a proposed sampling plan for review and approval prior to excavation, to include timing, frequency, and sampling method, as well as proposed testing organization. A](#)

representative sample of soil is to be collected and must undergo Laboratory Analysis for Excavated Soils 2 different determinations:

- a. In accordance with 35 Illinois Administrative Code (IAC) Part 742, TACO screen analytical parameters of regulated compounds is to be compared with the IEPA TACO default exposure threshold limits. Guidance on IL TACO can be found here:
<https://www2.illinois.gov/epa/topics/cleanup-programs/taco/fact-sheets/Pages/introduction.aspx>
- b. A Profile/Waste Characterization, a.k.a. RCRA Analysis, is performed if the soil material is characterized as a regulated waste, i.e. if the regulated parameters are identified in the soil materials at concentrations greater than the IEPA TACO default exposure thresholds. A Profile/Waste Characterization determines how the soil performs in a landfill environment (hazardous versus non-hazardous determination). Based on this data, a 'Waste Profile' is considered complete to support the disposal and manifest requirements.

State and Federal guidance for PFAS is currently under development. Until a standard is developed, PFAS sampling will be required on a location-specific basis, based on historical site use.

Contractor shall provide all sampling analytical results to the PWD-EV Division within 3 business days of receipt from testing organization. For all soils requiring landfill disposal, Contractor is responsible for coordinating with the landfill facility to ensure analytical samples and subsequent soil will be accepted for disposal. Provide confirmation of acceptance from the landfill facility to the PWD-EV Division prior to excavation.

3.19 POST CONSTRUCTION CLEANUP

Clean up areas used for construction in accordance with Contract Clause: "Cleaning Up". Unless otherwise instructed in writing by the Contracting Officer, remove traces of temporary construction facilities such as haul roads, work area, structures, foundations of temporary structures, stockpiles of excess or waste materials, and other vestiges of construction prior to final acceptance of the work. Grade parking area and similar temporarily used areas to conform with surrounding contours.

-- End of Section --

SECTION 01 74 19

CONSTRUCTION WASTE MANAGEMENT AND DISPOSAL

02/19, CHG 3: 11/21

PART 1 GENERAL

1.1 DEFINITIONS

1.1.1 Co-mingle

The practice of placing unrelated materials together in a single container, usually for benefits of convenience and speed.

1.1.2 Construction Waste

Waste generated by construction activities, such as scrap materials, damaged or spoiled materials, temporary and expendable construction materials, and other waste generated by the workforce during construction activities.

1.1.3 Demolition Debris/Waste

Waste generated from demolition activities, including minor incidental demolition waste materials generated as a result of Intentional dismantling of all or portions of a building, to include clearing of building contents that have been destroyed or damaged.

1.1.4 Disposal

Depositing waste in a solid waste disposal facility, usually a managed landfill or incinerator, regulated in the US under the Resource Conservation and Recovery Act (RCRA).

1.1.5 Diversion

The practice of diverting waste from disposal in a landfill or incinerator, by means of eliminating or minimizing waste, or reuse of materials.

1.1.6 Final Construction Waste Diversion Report

A written assertion by a material recovery facility operator identifying constituent materials diverted from disposal, usually including summary tabulations of materials, weight in short-ton.

1.1.7 Recycling

The series of activities, including collection, separation, and processing, by which products or other materials are diverted from the solid waste stream for use in the form of raw materials in the manufacture of new products sold or distributed in commerce, or the reuse of such materials as substitutes for goods made of virgin materials, other than fuel.

1.1.8 Reuse

The use of a product or materials again for the same purpose, in its original form or with little enhancement or change.

1.1.9 Salvage

Usable, salable items derived from buildings undergoing demolition or deconstruction, parts from vehicles, machinery, other equipment, or other components.

1.1.10 Source Separation

The practice of administering and implementing a management strategy to identify and segregate unrelated waste at the first opportunity.

1.2 CONSTRUCTION WASTE (INCLUDES DEMOLITION DEBRIS/WASTE)

Divert a minimum of 60 percent by weight of the project construction waste and demolition debris/waste from the landfill or incinerator. Follow applicable industry standards in the management of waste. Apply sound environmental principles in the management of waste. (1) Practice efficient waste management when sizing, cutting, and installing products and materials and (2) use all reasonable means to divert construction waste and demolition debris/waste from landfills and incinerators and to facilitate the recycling or reuse of excess construction materials.

1.3 CONSTRUCTION WASTE MANAGEMENT

Implement a Construction Waste Management Program for the project. Take a pro-active, responsible role in the management of construction construction waste, recycling process, disposal of demolition debris/waste, and require all subcontractors, vendors, and suppliers to participate in the Construction Waste Management Program. Establish a process for clear tracking, and documentation of construction waste and demolition debris/waste.

1.3.1 Implementation of Construction Waste Management Program

Develop and document how the Construction Waste Management Program will be implemented in a Construction Waste Management Plan. Submit a Construction Waste Management Plan to the Contracting Officer for approval. Construction waste and demolition debris/waste materials include un-used construction materials not incorporated in the final work, as well as demolition debris/waste materials from demolition activities or deconstruction activities. In the management of waste, consider the availability of viable markets, the condition of materials, the ability to provide material in suitable condition and in a quantity acceptable to available markets, and time constraints imposed by internal project completion mandates.

1.3.2 Oversight

The Environmental Manager, as specified in Section 01 57 19 TEMPORARY ENVIRONMENTAL CONTROLS, is responsible for overseeing and documenting results from executing the Construction Waste Management Plan for the project.

1.3.3 Special Programs

Implement special programs involving rebates or similar incentives related to recycling of construction waste and demolition debris/waste materials. Retain revenue or savings from salvaged or recycling, unless otherwise directed. Ensure firms and facilities used for recycling, reuse, and

disposal are permitted for the intended use to the extent required by federal, state, and local regulations.

1.3.4 Special Instructions

Provide on-site instruction of appropriate separation, handling, recycling, salvage, reuse, and return methods to be used by all parties at the appropriate stages of the projects. Designation of single source separating or commingling will be clearly marked on the containers.

1.3.5 Waste Streams

Delineate waste streams and characterization, including estimated material types and quantities of waste, in the Construction Waste Management Plan. Manage all waste streams associated with the project. Typical waste streams are listed below. Include additional waste streams not listed:

- a. Land Clearing Debris
- b. Asphalt
- c. Masonry and CMU
- d. Concrete
- e. Metals (Includes, but is not limited to, banding, stud trim, ductwork, piping, rebar, roofing, other trim, steel, iron, galvanized, stainless steel, aluminum, copper, zinc, bronze.)
- f. Wood (nails and staples allowed)
- g. Glass
- h. Paper
- i. Plastics (PET, HDPE, PVC, LDPE, PP, PS, Other)
- j. Gypsum
- k. Non-hazardous paint and paint cans
- l. Carpet
- m. Ceiling Tiles
- n. Insulation
- o. Beverage Containers

1.4 SUBMITTALS

Government approval is required for submittals with a "G" classification. Submittals not having a "G" classification are for Contractor Quality Control approval. Submit the following in accordance with Sections 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Construction Waste Management Plan; G

SD-11 Closeout Submittals

Final Construction Waste Diversion Report; S

1.5 MEETINGS

Conduct Construction Waste Management meetings. After award of the Contract and prior to commencement of work, schedule and conduct a meeting with the Contracting Officer to discuss the proposed Construction Waste Management Plan and to develop a mutual understanding relative to the management of the Construction Waste Management Program and how waste diversion requirements will be met.

The requirements of this meeting may be fulfilled during the coordination and mutual Understanding meeting outlined in Section 01 45 00 QUALITY CONTROL. At a minimum, discuss and document waste management goals at following meetings:

- a. Pre-demolition meeting.
- b. Regular site meetings.
- c. Work safety meeting (if applicable).

1.6 CONSTRUCTION WASTE MANAGEMENT PLAN

Submit Construction Waste Management Plan within 15 calendar days after notice to proceed. Revise and resubmit Construction Waste Management Plan as necessary, in order for construction to begin.. Submit Construction Waste Management Plan not less than 60 calendar days before scheduled final site or building design approval. Revise and resubmit Construction Waste Management Plan until it receives final approval from the Contracting Officer, in order for construction to begin. Execute demolition or deconstruction activities in accordance with Section 02 41 00 DEMOLITION. Manage demolition debris/waste or deconstruction materials in accordance with the approved construction waste management plan.

An approved Construction Waste Management Plan will not relieve the Contractor of responsibility for compliance with applicable environmental regulations or meeting project cumulative waste diversion requirement. Ensure all subcontractors receive a copy of the approved Construction Waste Management Plan. The plan demonstrates how to meet the project waste diversion requirement. Also, include the following in the plan:

- a. Identify the names of individuals responsible for waste management and waste management tracking, along with roles and responsibilities on the project.
- b. Actions that will be taken to reduce solid waste generation, including coordination with subcontractors to ensure awareness and participation.
- c. Description of the regular meetings to be held to address waste management.
- d. Description of the specific approaches to be used in recycling/reuse of the various materials generated, including the areas on site and equipment to be used for processing, sorting, and temporary storage of materials.

- e. Name of landfill and incinerator to be used.
- f. Identification of local and regional re-use programs, including non-profit organizations such as schools, local housing agencies, and organization that accept used materials such as material exchange networks and resale stores. Include the name, location, phone number for each re-use facility identified, and provide a copy of the permit or license for each facility.
- g. List of specific materials, by type and quantity, that will be salvaged for resale, salvaged and reused on the current project, salvaged and stored for reuse on a future project, or recycled. Identify the recycling facilities by name, address, and phone number.
- h. Identification of materials that cannot be recycled or reused with an explanation or justification, to be approved by the Contracting Officer.
- i. Description of the means by which materials identified in item (g) above will be protected from contamination.
- j. Description of the means of transportation of the recyclable materials (whether materials will be site-separated and self-hauled to designated centers, or whether mixed materials will be collected by a waste hauler and removed from the site).
- k. Copy of training plan for subcontractors and other services to prevent contamination by co-mingling materials identified for diversion and waste materials.

Distribute copies of the waste management plan to each subcontractor, [Environmental Manager](#), and the Contracting Officer.

1.7 RECORDS (DOCUMENTATION)

1.7.1 General

Maintain records to document the types and quantities of waste generated and diverted through re-use, recycling and sale to third parties; through disposal to a landfill or incinerator facility. Provide explanations for materials not recycled, reused or sold. Collect and retain manifests, weight tickets, sales receipts, and invoices specifically identifying diverted project waste materials or disposed materials.

1.7.2 Accumulated

Maintain a running record of materials generated and diverted from landfill disposal, including accumulated diversion rates for the project. Make records available to the Contracting Officer during construction or incidental demolition activities. Provide a copy of the diversion records to the Contracting Officer upon completion of the construction, incidental demolitions or minor deconstruction activities.

1.8 FINAL CONSTRUCTION WASTE DIVERSION REPORT

A Final Construction Waste Diversion Report is required at the end of the project. Provide [Final Construction Waste Diversion Report](#) 60 days prior to the Beneficial Occupancy Date (BOD).

1.9 COLLECTION

Collect, store, protect, and handle reusable and recyclable materials at the site in a manner which prevents contamination, and provides protection from the elements to preserve their usefulness and monetary value. Provide receptacles and storage areas designated specifically for recyclable and reusable materials and label them clearly and appropriately to prevent contamination from other waste materials. Keep receptacles or storage areas neat and clean.

Train subcontractors and other service providers to either separate waste streams or use the co-mingling method as described in the Construction Waste Management Plan. Handle hazardous waste and hazardous materials in accordance with applicable regulations and coordinate with Section 01 57 19 TEMPORARY ENVIRONMENTAL CONTROLS. Separate materials by one of the following methods described herein:

1.9.1 Source Separation Method

Separate waste products and materials that are recyclable from trash and sort as described below into appropriately marked separate containers and then transport to the respective recycling facility for further processing. Deliver materials in accordance with recycling or reuse facility requirements (e.g., free of dirt, adhesives, solvents, petroleum contamination, and other substances deleterious to the recycling process). Separate materials into the category types as defined in the Construction Waste Management Plan.

1.9.2 Other Methods

Other methods proposed by the Contractor may be used when approved by the Contracting Officer.

1.10 DISPOSAL

Control accumulation of waste materials and trash. Recycle or dispose of collected materials off-site at intervals approved by the Contracting Officer and in compliance with waste management procedures as described in the waste management plan. Except as otherwise specified in other sections of the specifications, dispose of in accordance with the following:

1.10.1 Reuse

Give first consideration to reusing construction and demolition materials as a disposition strategy. Recover for reuse materials, products, and components as described in the approved Construction Waste Management Plan. Coordinate with the Contracting Officer to identify onsite reuse opportunities or material sales or donation available through Government resale or donation programs. Sale of recovered materials is not allowed on the Installation. Consider the use of surplus industrial supply broker services, who match entities with reusable or repurpose industrial materials with entities with need of such materials.

1.10.2 Recycle

Recycle non-hazardous construction and demolition/debris materials that are not suitable for reuse. Track rejection of contaminated recyclable materials by the recycling facility. Rejected recyclables materials will not be counted as a percentage of diversion calculation. Recycle all

fluorescent lamps, HID lamps, mercury (Hg) -containing thermostats and ampoules, and PCBs-containing ballasts and electrical components as directed by the Contracting Officer. Do not crush lamps on site as this creates a hazardous waste stream with additional handling requirements.

1.10.3 Waste

Dispose by landfill or incineration only those waste materials with no practical use, economic benefit, or recycling opportunity.

PART 2 PRODUCTS

Not used.

PART 3 EXECUTION

Not used. -- End of Section --

SECTION 01 78 00

CLOSEOUT SUBMITTALS

05/19, CHG 1: 08/21

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

U.S. DEPARTMENT OF DEFENSE (DOD)

FC 1-300-09N

(2024) Navy and Marine Corps Design

1.2 DEFINITIONS

Note: Replace the term "construction" with "demolition" to accurately represent the scope of work. Documentation must include a detailed record of all demolition activities and final site conditions.

1.2.1 Record Drawings

The record drawings are the final compilation of actual conditions reflected in the as-built drawings.

1.3 SOURCE DRAWING FILES

Request the full set of electronic drawings, in the source format, for Record Drawing preparation, after award and at least 30 days prior to required use.

1.3.1 Terms and Conditions

Data contained on these electronic files must not be used for any purpose other than as a convenience in the preparation of construction drawings and data for the referenced project. Any other use or reuse is at the sole risk of the Contractor and without liability or legal exposure to the Government. The Contractor must make no claim and waives to the fullest extent permitted by law, any claim or cause of action of any nature against the Government, its agents or sub consultants that may arise out of or in connection with the use of these electronic files. The Contractor must, to the fullest extent permitted by law, indemnify and hold the Government harmless against all damages, liabilities or costs, including reasonable attorney's fees and defense costs, arising out of or resulting from the use of these electronic files.

These electronic CAD drawing files are not construction documents. Differences may exist between the CAD files and the corresponding construction documents. The Government makes no representation regarding the accuracy or completeness of the electronic CAD files, nor does it make representation to the compatibility of these files with the Contractor hardware or software. In the event that a conflict arises between the signed and sealed construction documents prepared by the Government and the furnished Source drawing files, the signed and sealed construction documents govern. The Contractor is responsible for determining if any

conflict exists. Use of these Source Drawing files does not relieve the Contractor of duty to fully comply with the contract documents, including and without limitation, the need to check, confirm and coordinate the work of all contractors for the project. If the Contractor uses, duplicates or modifies these electronic source drawing files for use in producing construction drawings and data related to this contract, remove all previous indicia of ownership (seals, logos, signatures, initials and dates).

1.4 SUBMITTALS

Government approval is required for submittals with a "G" classification. Submittals not having a "G" classification are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-11 Closeout Submittals

Post-Demolition Record Drawings; G,

PART 3 EXECUTION

2.1 RECORD DRAWINGS

Prepare and provide Record Drawings and Source Documents in accordance with FC 1-300-09N including, but not limited to:

Site Plan Post-Demolition: Reflect the site after demolition, including finished grades, utility terminations, and conditions of adjacent structures.

Utility Abandonment Details: Show capped lines, removed utilities, or relocated services.

Final Grading and Drainage Plan: Document how the site was restored and graded for proper drainage.

Transmit electronically unless directed otherwise.

2.2 CLEANUP

KTR must remove all demolition debris, waste, and hazardous materials from the site, leaving it clean, level, and safe for future use. Disposal must comply with federal, state, and local regulations. Dust control measures must be implemented, and adjacent areas kept free of debris. Recycle, salvage, and return construction and demolition waste from project in accordance with Section 01 57 19 TEMPORARY ENVIRONMENTAL CONTROLS, and 01 74 19 CONSTRUCTION WASTE MANAGEMENT AND DISPOSAL. Final site acceptance will require inspection for compliance with these requirements.

-- End of Section --

PART THREE - PROJECT PROGRAM

Project Program

Demolish Vacant BEQ Building 132H

FY-25

**NAVSTA Great Lakes
Great Lakes, IL**

Date 03/04/2025

TABLE OF CONTENTS

COVER PAGE.....	166
TABLE OF CONTENTS.....	167
1.PROJECT DESCRIPTION.....	168
2.PROJECT OBJECTIVES.....	169
2.1. Applicable Codes and Standards	
2.2. Facility Function	
2.3. Project Specific Priorities	
2.4. Special Design Challenges	
3.SITE ANALYSIS/EV CONSIDERATIONS.....	171
3.1 Existing Site Conditions	
3.2 Site Development Requirements	
4.BUILDING REQUIREMENTS.....	172
5. NOT USED	
6.ENGINEERING SYSTEMS REQUIREMENTS.....	173
F20 Selective Building Demolition	
G10 Site Preparations	
G20 Site Improvements	

Part 3 contains the project description, functional and performance requirements, scope items, and expected quality levels that exceed Part 4. Part 4 identifies design criteria, verification requirements, and performance and quality requirements of products.

1.0 PROJECT DESCRIPTION

The contractor must furnish all necessary supervision, technical personnel, labor, materials, machinery, tools, equipment, and services required to completely demolish and remove Building 132H, a vacant 4-story student barrack located at 3110 2nd Street, Great Lakes, IL. The building, constructed in 1999, has a total area of 96,117 square feet.

The demolition work includes, but is not limited to:

1. Preparation and Mobilization
 - Hazardous Material survey
 - Secure site with appropriate fencing, signage, and safety measures to ensure the protection of personnel and adjacent properties
2. Demolition
 - Safely and systematically demolish the entire structure, including foundations, utilities and all related components.
 - Ensure dust control, noise mitigation, and adherence to environmental regulations.
3. Debris Removal
 - Remove and dispose of all debris, materials, and waste generated from the demolition in accordance with local, state, and federal regulations
 - Restore the site to a clean, level condition, suitable for future use
 - Building footprint is to be backfilled, compacted, graded, and seeded.

2.0 PROJECT OBJECTIVES

2.1 Applicable Codes and Standards

In addition to the codes and standards listed in Part 4, the design and construction must be in accordance with the latest revision/edition of the following referenced codes and standards. The term "Latest Revision/Edition" is defined as the version as of the project award date.

-All planning and design requirements must be in accordance with the Unified Facilities Criteria (UFC) Program. UFC documents are available on the Whole Building Design Guide website (<https://www.wbdg.org/ffc/dod/unified-facilities-criteria-ufc>).

-Other NAVFAC Technical Publications <http://www.wbdg.org/ffc/navy-navfac>

- Unified Facilities Guide Specifications (UFGS)
<http://www.wbdg.org/ffc/dod/unified-facilities-guide-specifications-ufgs>

- NAVFAC Regional Specifications <http://www.wbdg.org/ffc/navy-navfac/regional-specifications>
- U.S. Army Corps of Engineers (USACE) Safety and Health Requirements Manual, EM 385-1-1, 15 MARCH 2024
https://www.publications.usace.army.mil/Portals/76/Publications/EngineerManuals/EM_385-1-1.pdf

2.2 Facility Function

The building, which was previously used as student barracks, is now vacant and deteriorating from lack of maintenance.

2.3 Project Specific Priorities

Design submittals must be prepared in accordance with FC 1-300-09N, *Navy and Marine Corps Design Procedures* and clearly illustrate the project scope.

Note: A Designer of Record (DOR) is required in a limited capacity to prepare the demolition drawings, edit/tailor all applicable specification sections, and provide technical support during construction. Two (2) design package submittals are required: a 100% Pre-Final package and a Final/Issued for Construction (IFC) package. All comments from the Pre-Final review must be fully addressed in the Final/IFC submission. Pre-Final specifications must be redlined, while the Final/IFC specifications must be fully edited, with all brackets and redlines removed. The Final/IFC package must have "Issued for Construction" clearly marked in red across the cover sheet and in the revision block, with all previous iterations removed. The Final submission must be stamped and sealed by the Designer of Record (DOR), with the Satisfactory to (Sat-to) date filled in.

Design review comments will be managed through ProjNet (DrChecks) – web-based design review and collaboration tool (projnet.org).

2.3.1 Sustainable Design and Construction

Formal sustainable reporting is not required for this project. However, it's strongly encouraged to incorporate sustainable practices and solutions to the fullest extent possible.

2.3.2 Storm Water Management - Low Impact Development (LID)

Communicate the debris containment plan/method to NAVFAC Environmental. This plan should fully contain all debris, visible dust, and water produced. Protect all nearby storm drains. Surround the project area with silt fence. Use best management practices to manage any temporary soil/waste piles. Locate these piles and staging areas downhill of storm drains, preferably on a flat surface. A Notice of Intent (NOI) will be required if more than one (1) acre will be disturbed.

Grade final elevation in order to limit/mitigate overland flow from overwhelming a single storm drain, ensuring even distribution amongst surrounding infrastructure. Provide red lines to include utilities/structures abandoned in place, or not previously identified on drawings.

2.4 Special Design Challenges

The demolition of B132H will require addressing several design challenges.

The project must include the identification and removal of any hazardous materials, including asbestos or lead-based paint, in compliance with current environmental regulations. Note: Include HAZMAT survey **and cost itemization for hazardous material removal** in the base bid;
~~Removal will be awarded separately (do not include in base bid).~~ If hazardous materials are detected, the contractor must develop and submit an abatement plan to the Government for review and approval before proceeding with any work. Refer to Part 3, Section F2020 for additional information.

Structural integrity and proximity to occupied buildings must be considered to minimize impact on surrounding areas.

The plan should ensure safe location and disconnection of utilities. The active communications manhole C156 must be protected during demolition and remain accessible afterward, with necessary adjustments or raising as needed.

KTR must account for potential unanticipated site conditions and ensure all work adheres to current safety standards.

3.0 SITE ANALYSIS/ENVIRONMENTAL CONSIDERATIONS

Obtain digging permit prior to start of demolition.

The Contractor must obtain a digging permit prior to demolition and is responsible for locating all existing utilities by contacting J.U.L.I.E. at (800) 892-0123, hiring an independent third-party utility locate (including steam), and performing a Ground Penetrating Radar (GPR) survey within the demolition limits. Utilities must be marked, and the Contractor must submit the GPR report and locate documentation to the Government for review before any below-grade demolition. Any asbestos-containing materials must be abated in accordance with federal, state, and local regulations, and all subsurface elements, including foundations, utilities, vaults, and piping, must be demolished and removed from the site.

KTR must protect all utilities to remain and repair or replace any damage at their own expense.

Contractor must provide temporary erosion control measures in accordance with the NAVSTA Great Lakes PWD, Environmental Operations "Construction Storm Water Management" (Contractor Guidance Manual) included in Part 6, *Attachments*. Erosion control protections are required during construction (silt fence in areas where sediment could migrate downhill). Nearby manholes and storm drains must be protected during construction and temporary Best Management Practices (BMP) must be removed when the project is complete.

Lay-down areas must be pre-approved by NAVFAC. Lay-down areas must be placed in locations away from environmentally sensitive areas, e.g. storm drains.

Discharging wastewater generated by cement/concrete processing activities to storm drains, on the ground or to Waters of the State, is prohibited. All processing wastewater must be disposed of off-site, to an approved/licensed disposal facility.

3.1 Existing Site Conditions

Before beginning any demolition work, survey the site and examine the drawings and specifications to determine the extent of the work.

The KTR must provide passageways around the area of demolition to ensure safe passage of persons in the area.

No part of the building may be left in an unsafe condition. If any danger is imminent, the KTR must rope off/barricade, around the area.

Should adjacent facilities, property, streets, or sidewalks be damaged in any matter, the Contractor must repair promptly at no cost to the Government.

3.2 Site Development Requirements

Restore the site to a clean, level condition, suitable for future use as specified by the project requirements.

Building footprint/site is to be backfilled, compacted, graded, and seeded to match adjacent and surrounding contours, ensuring positive drainage and uniformity with the existing landscape.

4.0 BUILDING REQUIREMENTS

Any salvageable items of value left after the owner has removed what he/she wants in the building will then become the property of the contractor. There is a significant amount of leftover barrack-style (hotel-like) furniture that was left behind when the building was abandoned. There is also debris inside the building due to its ongoing deterioration. Demolition cost must include the disposal of this material.

The following must be salvaged and brought to NSGL PWD: the fire alarm system panel, alarm radio transmitter, alarm radio transmitter antenna booster power supply. The Knox box and all fire extinguishers must be taken to Building 106. Care shall be taken while removing and handling fire protection equipment. Coordinate details with the contracting officer at the pre-construction meeting.

6.0 ENGINEERING SYSTEM REQUIREMENTS

6. ENGINEERING SYSTEMS REQUIREMENTS

F20 SELECTIVE BUILDING DEMOLITION

GENERAL SYSTEMS REQUIREMENTS

Perform all off-site work necessary to meet the requirements of the project, local codes, reference standards, technical specifications and performance criteria.

Identify and obtain permits to comply with federal, state, and local regulatory requirements associated with this work. Complete the Permits Record of Decision (PROD) form with the first design submittal package. Determine correct permit fees and pay said fees. Forward copies of permits, permit applications, and the completed PROD form to the Government's Civil Reviewer. Perform work in accordance with the approved permits.

Contractor must file all State of Illinois Demolition/Renovation/Asbestos Project Notification Forms and revisions to the appropriate agencies; IEPA, IDPH, Cook County, or the City of Chicago, dependent on location and work to be done. KTR must provide proof of acceptance and payment of any applicable fees. KTR must abide by the 10-working day waiting period before commencement of work, if applicable.

Coordinate and obtain approval from the Contracting Officer for proposed haul route(s), work site access point(s), utility connections, employee parking location(s) and material laydown and storage area(s).

F2010 BUILDING ELEMENTS DEMOLITION

This project includes the complete demolition and removal of Building No. 132H, a 96,117 square foot masonry bearing wall structure.

The building is a typical 4-story barracks structure, approximately 40-50 feet tall (assuming each floor is approximately 10-12 feet in height).

F2010 1.1 GENERAL DEMOLITION

The building and its foundations must be demolished completely, including all below-grade elements.

Proceed with demolition in a systematic manner from the top of the structure to the ground. Complete demolition work above each floor before disturbing any of the supporting members on the lower levels.

Demolish concrete and masonry in small sections.

F2010 1.2 UTILITIES

Physically verify the locations of all existing utilities. Utilities and Energy Management (UEM) requirements are as follows:

- Remove all secondary electric cables remaining from the transformer to the building. All electric/communications ducts must be cut, capped, and sealed a minimum of 18" below finished grade.
- Protect the Gate 3 transformer (located to the Northwest) during demo.
- Protect the street light circuit running from the Gate 3 transformer, feeding the street lights along 2nd St.
- Remove street light 20909 and cable back to light 20908.
- Refeed the parking lot lights to the South of 132H from B130H. There is a temporary electrical feed to the AMI equipment in B132H (which will be removed by the Government). Leave equipment in place as long as possible. Notify Al Ghys (alan.j.ghys.civ@us.navy.mil; 847-688-2121 x122) when equipment needs to be removed by NAVFAC.
- The communications ducts connected to B132H itself are to be cut/capped and sealed a minimum of 18" below finished grade (See Attachment 11).
- Communications manhole C156 (inside of B132H) is to remain and shall be protected during demo. Multiple fiber circuits run through this manhole and cannot be damaged. Manhole must remain accessible after demolition; Provide necessary adjustments or raising, as needed.
- 8" sanitary service to building needs to be plugged in MH 09A (located to South). The plug shall be installed and visible in the manhole. Navy can assist with limiting flow in the manhole while the Contractor performs their work. This assistance shall be requested via a utility outage request. Remove all manholes upstream of 09A to include at a minimum 09B, 09C & 09D. Utilities must be disconnected first, prior to any building demolition.
- Retain and protect Communications Vault C156 within mechanical room 122 during building 132H demolition. Retain and protect all ductbanks, conduits, and cables running between Communications Manhole C158, Vault C156 and Manhole C157. After demolition of the building is complete, replace vault C156 cover with hinged vault access doors suitable for outdoor applications and adjust elevation of vault doors to new finished grade.

Note: Power to B132H has already been disconnected, and all associated primary cables and transformers were removed during a previous demolition project (Buildings 128H and 129H).

Refer to Part 5, Section 02 41 00, *DEMOLITION*, 1.3.4 Utility Service, for additional information.

F2010 1.3 DUST CONTROL/CONSTRUCTION EMISSIONS

Prevent the spread of dust and debris to avoid the creation of a nuisance or hazard in the surrounding area. During this project, no person shall cause or allow dust or particles to become visible beyond the project boundary.

Contractor must write a Fugitive Dust Control Plan for construction activities (e.g. building demolition, filling-in of excavation, grading). The Fugitive Dust Control Plan is subject to review and approval by NSGL Environmental Division.

Fugitive Dust Control Plan must include discussion and reference to plans to control surface water releases of any water or chemical used to control fugitive dust.

F2010 1.4 TRAFFIC CONTROL

KTR must conduct demolition operations and the removal of debris to ensure minimum interference with roads, streets, walks, and other adjacent occupied or used facilities.

F2010 1.5 WEATHER PROTECTION

Protect the work in progress at the end of each workday, as required.

F2010 1.6 BURNING & BLASTING

Burning on-site will not be permitted.

Blasting will not be permitted on the project site.

F201001 SUBSTRUCTURE & SUPERSTRUCTURE

Remove structural framing members and lower to ground by means of suitable method(s). Columns, beams, and other structural members which are being dismembered must not be under any stress other than their own weight during removal and must be chained or lashed in place to prevent any uncontrolled swinging or dropping. Large structural members must not be thrown or dropped but must be carefully lowered from the building.

Locate demolition equipment throughout the structure and remove materials so as to not impose excessive loads to supporting walls, floors, or framing.

Demolish foundations and footings entirely.

F201002 EXTERIOR CLOSURE

Demolish concrete and masonry in small sections.

F2020 HAZARDOUS COMPONENT ABATEMENT

A hazardous material survey report is not available to support this project.

Prior to starting work, the Contractor must hire a first tier subcontractor to conduct a Hazardous Material Survey of the project site and prepare a report. Refer to UFC 3-810-01N, *Navy and Marine Corps Environmental Engineering for Facility Construction*, for restrictions and for additional requirements and criteria. Facility areas and components affected by the project must be inspected for asbestos-containing materials, lead-based paint, paint containing lead, cadmium and chromium, and any other hazardous materials. The inspection must be performed by an EPA-Accredited Asbestos Inspector and EPA-Accredited Lead Inspector or Lead Risk Assessor. The inspectors must be appropriately licensed in the State of project site location. Follow 40 CFR 763 Subpart E, Asbestos Hazard Emergency Response Act (AHERA) requirements for inspection of friable and non-friable asbestos containing materials. Send samples to a third party accredited laboratory. Laboratories performing analysis for asbestos must be NIST/NVLAP accredited and rated proficient in the NIST/NVLAP sponsored quality assurance program for asbestos identification. Laboratories performing analysis for lead must be NLLAP accredited and

rated proficient in the NIOSH/EPA Environmental Lead Proficiency Analytical Testing Program (ELPAT). Retest all roofing tars, sealants, caulking, and resilient floor covering materials (including vinyl and asphalt floor tiles, sheet vinyl flooring, and flooring mastics and adhesives) with PLM results of 1% or less. Retesting using Transmission Electron Microscopy (TEM). The Contractor must submit the report to the Government for review and approval prior to starting work. Any historical surveys provided by the Government are for reference purposes only. Hazardous component abatement will be contingent on the results of the survey.

If any unforeseen or suspect hazardous materials are encountered during demolition or construction, it must be brought to the Government's attention for action. The Contractor must immediately notify the Government of potential schedule impacts from the discovered materials.

The DOR must edit UFGS 02 82 00, *Asbestos Remediation* and submit for Government review and approval. Perform asbestos work in accordance with the approved Asbestos Hazard Abatement Plan as described in UFGS 02 82 00. The Designer of Record must use the attached Asbestos Hazard Abatement Plan template attached in Part 6, *Attachments*, and submit for Government review and approval. The Designer of Record must be an EPA-accredited Asbestos Project Designer and be appropriately licensed in the State of Illinois. The approved abatement plan must be monitored by the PQP in accordance with the requirements of the approved edited specification. Abatement work must not begin until both the edited specification and abatement plan are approved by the Government.

F2020 1.1 PAINT RELATED WORK – LEAD, CADMIUM, AND CHROMIUM

The DOR must edit UFGS 02 83 00, *Lead Remediation* and submit for Government review and approval. Perform work involving the removal of lead-based paint or paint containing lead, cadmium and/or chromium in accordance with the approved Lead, Cadmium and Chromium Compliance Plan described in UFGS 02 83 00. The Designer of Record shall use the attached Lead, Cadmium and Chromium Compliance Plan template attached in Part 6, *Attachments*, and submit for Government review and approval. The Designer of Record must be an EPA-accredited Licensed Lead Abatement Contractor or Supervisor and be appropriately licensed in the State of Illinois. The Lead, Cadmium and Chromium Compliance Plan shall be prepared in accordance with the requirements of the approved edited specification. Submit the plan for Government review and approval. Work shall not begin until both the specification and Lead, Cadmium and Chromium Compliance Plan are reviewed and approved by the Government.

F2020 1.2 PRIVATE QUALIFIED PERSON (PQP)

Private Qualified Person (PQP)

The Contractor is required to hire a PQP to ensure compliance with the approved work plans and perform independent inspections, testing and verification of the hazardous

components work including: asbestos, lead containing paint, mercury & LLR components, PCBs, ODS.

Asbestos

Remove and dispose of asbestos-containing materials and debris. Assume all fire doors are positive for ACM. For bidding purposes assume 100-doors for removal/disposal.

Mercury & LLR Components

Remove all: fluorescent light tubes, thermostats and switches, smoke detectors, exit signs as mercury vapor containing or LLR components.

PCB's

Remove all: light ballasts, transformers, capacitors, without markings regarding PCB content (e.g. "NO PCB", "NON PCB") as PCB containing.

Ozone Depleting Substances (ODS)

Remove the following equipment which contains ODS: air conditioning equipment, fire suppression system cylinders and canisters. Contractors must comply with the Naval Station Great Lakes Refrigerant Compliance Plan (issued Jan 2025), follow steps outlined in the NAVFAC Mid-Lant process # ML-B-15.2.2 Refrigeration Compliance Management, and use the "CAA 40-82F" forms described in both of the aforementioned documents to report activity to the Contracting Officer, PWD FMD, and PWD EV.

1. If during ODC/ Freon removal a release occurs, Contractor is required to inform the Contracting Officer, PWD FMD, and PWD EV of the incident date and estimated quantity released using Form CAA 40-82F-1
2. The government shall retain full ownership of all recovered Class I & II ODSs, which shall be returned to the Navy. Contractor shall notify the Contracting Officer to arrange transfer of recovered ODSs to the appropriate NSGL PWD Department.

Disposal

All waste materials will become the property of the Contractor and must be transported, disposed of or recycled in accordance with all state and federal regulations.

--End of Section--

6. ENGINEERING SYSTEMS REQUIREMENTS

G10 SITE PREPARATION

SYSTEM DESCRIPTION

The site preparation activities consist of site clearing, demolition, salvage, relocation, earthwork, and hazardous waste remediation to ready the site for other work associated with the project.

GENERAL SYSTEM REQUIREMENTS

Perform a topographic survey of the project site and include in the demolition drawings.

KTR must install 6'-0" high galvanized cyclone construction fence with brown color screening around demolition site. KTR storage must be within demolition site.

Lay-down areas must be pre-approved and not be located near environmentally sensitive areas such as storm drains, floor drains, and building air intakes.

G1010 SITE CLEARING

Burning will not be allowed.

All grubbing and clearing residue, demolished material, rubbish and debris generated by this project must be hauled off-site and off-station by the Contractor.

The U.S. Fish and Wildlife Service (USFWS) lists the northern long-eared bat as federally endangered and has proposed to list the tricolored bat as federally endangered under the Endangered Species Act. These bats species utilize trees for roosting and have also been observed roosting in human-made structures, such as buildings, barns, and bridges. Since the project is located within 1,000 feet of suitable habitat, individual trees and the building are considered potential summer habitat. Consultation with USFWS is required prior to demolition. Once project design is underway and it has been decided which surrounding trees are being saved and which are planned for removal, information/plans must be submitted to the NSGL Environmental Division to initiate consultation process. Work cannot proceed without USFWS concurrence on the species effect determination. Assume 30-day review time for scheduling purposes.

G101002 TREE REMOVAL/G101003 STUMP REMOVAL

Remove and dispose of trees as required, ensuring only trees specified for removal are affected. Efforts must be made to preserve as many trees as possible.

Note: Most trees will need to be removed; however, some may remain, primarily on the East side of the building near the berm/2nd Street and a few on the North side near the sidewalk. Contractor must submit a proposed design, which can be further reviewed with the environmental team.

Trees designated for removal must be cut and the stumps ground or removed to a depth of

at least 18" below the ground surface. Removal areas must be restored to natural grade upon completion of the tree removal. See Part 4, Sections G101002 & G101003. Refer to Part 2, Section 01 57 19, *Temporary Environmental Controls* for additional information.

G101006 DEBRIS DISPOSAL

Dispose of debris off-site in compliance with local environmental regulations.

Waste materials will become the property of the Contractor; transport, dispose of or recycle waste materials in accordance with Part 2 Section 01 57 19, *Temporary Environmental Controls*.

G102001 BUILDING MASS DEMOLITION

Demolish the existing building entirely. Refer to Section F2020, "Hazardous Component Abatement" for requirements regarding removal of hazardous materials and components.

G102003 UNDERGROUND SITE DEMOLITION

Refer to Part 3, Section F2010, 1.2 *Utilities*.

G102003 1.1 UNDERGROUND STORAGE TANKS

The project site does not require underground storage tank removal.

G102007 SITE CLEANUP

Waste materials will become the property of the Contractor; transport, dispose of or recycle waste materials in accordance with Part 2 Section 01 57 19, *Temporary Environmental Controls*.

G102007 1.1 SPILLS

In the event of a spill, notify the KO immediately. Take immediate containment actions to minimize effects.

G1030 SITE EARTHWORK

Building footprint is to be backfilled, compacted, graded and seeded. Provide all fill necessary to bring the existing grades under the demolished building to be level with the adjacent present grades. Provide grading so the site will drain well.

Backfill IAW NSGL Soil Management Plan, UFC 3-201-01 *Civil Engineering* and UFC 3-220-04FA *Backfill for Subsurface Structures*.

G1040 HAZARDOUS WASTE REMEDIATION & DUST SUPPRESSION

Use water sprinkling, temporary enclosures, and/or other suitable methods, as necessary, to limit the amount of dust and dirt rising and scattering in the air. Comply with the governing

Clean Air regulations. Do not use water where it may create hazardous or objectionable conditions such as pollution, ice, or flooding.

G1040 1.1 CONTAMINATED SOIL AND GROUNDWATER

The project site does not require contaminated soil or groundwater work.

--End of Section--

6. ENGINEERING SYSTEMS REQUIREMENTS

G20 SITE IMPROVEMENTS

Upon completion of all demolition work, the Contractor must repair streets, sidewalks, or other features scheduled to remain, that have been damaged due to this demolition, to a condition equal to or better than their pre-existing conditions. Materials used for repair must be of like kind and of the thickness, width, length, etc. as the original.

G2050 LANDSCAPING

The site of the former building must be landscaped as a lawn.

Guarantee landscaping for a period of one year.

Provide landscaping restoration IAW UFC 3-201-2 *Landscape Architecture*, with Change 1.

G205001 FINE GRADING AND SOIL PREPARATION

Provide 4" of topsoil for lawn areas and fine grade.

G205002 EROSION CONTROL MEASURES

Prevent erosion from occurring by providing erosion control measures as required by city, state and federal requirements.

G205004 SEEDING SPRIGGING AND SODDING

Seed building footprint area, as indicated. Restore existing turf areas disturbed by Contractor operations that are to remain as turf areas. Restore by means of seeding and provide same guarantee and maintenance as for new landscape areas.

--End of Section--

PART FOUR - PERFORMANCE TECHNICAL SPECIFICATIONS

Note: This project is a demolition project. Wherever the term “construction” is mentioned in this Part, it should be understood as “demolition,” and all specifications related to construction activities shall apply to demolition activities, as appropriate.

F20 COMPLETE BUILDING DEMOLITION

G10 SITE PREPARATION

G20 SITE IMPROVEMENTS

Z10 GENERAL PERFORMANCE TECHNICAL SPECIFICATION

SECTION F20

SELECTIVE BUILDING DEMOLITION 09/22

F20 GENERAL

RFP Part 3 including the Engineering System Requirements (ESR) provide project specific requirements. The RFP Part 4, Performance Technical Sections (PTS) provide generalized technical requirements that apply to multiple facility types and include more requirements than are applicable to any one project. Therefore, only the RFP Part 4 requirements that apply to the project and further define the RFP Part 3 project specific requirements are required.

F20 1.1 DESIGN GUIDANCE

Provide the design and installation in accordance with the following references. This Performance Technical Specification (PTS) adds clarification to the fundamental requirements contained in the following Government Standards. The general requirements of this PTS section are located in PTS Section Z10, *General Performance Technical Specification*.

Industry standards, codes, and government standards that are referenced in the section text that are not found in the [Unified Master Reference List \(UMRL\)](#) in the [Federal Facility Criteria \(FFC\)](#) at the [Whole Building Design Guide \(WBDG\)](#) website, are listed below for basic designation identification. Comply with the required and advisory portions of the current edition of the standard at the time of contract award.

F20 1.1.1 Industry Standards

Refer to UMRL for reference designation identification.

F20 1.1.2 Government Standards

UNIFIED FACILITIES CRITERIA (UFC)

UFC 1-200-01	DoD Building Code (General Building Requirements) (A reference in this PTS section to UFC 1-200-01 requires compliance with the Tri-Service Core UFCs that are listed therein, which includes the following significant UFC(s): UFC 1-200-02, High Performance and Sustainable Building Requirements UFC 3-201-01, Civil Engineering UFC 3-101-01, Architecture)
UFC 3-810-01N	Navy and Marine Corps Environmental Engineering for Facility Construction

UNIFIED FACILITIES GUIDE SPECIFICATIONS (UFGS)

UFGS 01 57 19	Temporary Environmental Controls
UFGS 02 82 00	Asbestos Remediation
UFGS 02 83 00	Lead Remediation
UFGS 02 84 16	Handling of Lighting Ballasts and Lamps Containing PCBs and Mercury
UFGS 02 84 33	Removal and Disposal of Polychlorinated Biphenyls (PCBs)
UFGS 02 85 00	Mold Remediation
UFGS 31 21 13	Radon Mitigation

U.S. ARMY CORPS of ENGINEERS (USACE)

EM 385 -1-1	Safety -- Safety and Health Requirements or latest edition including changes
-------------	--

F20 1.2 QUALITY ASSURANCE

Materials and assemblies installed in the work must be inspected and found to be in compliance with industry standards prior to acceptance of the work. Items found not to be in compliance must be removed, or corrective measures taken, to assure compliance with the referenced standard. Disposal of materials must be as specified and performed in a manner to protect workers and existing structures to remain.

F20 1.3 PERFORMANCE VERIFICATION AND ACCEPTANCE CRITERIA

Compliance with the requirements will be determined by a review of the design and construction submittals and by field inspection. See Part 2 Section 01 33 00, *Submittal Procedures*, for additional requirements.

F20 1.4 DESIGN SUBMITTALS

Provide design submittals in accordance with Z10, *General Performance Technical Specifications*, Part 2 Section 01 33 00 *Submittal Procedures*, Facilities Criteria (FC) 1-300-09N, *Navy and Marine Corps Design Procedures*, and UFC 3-810-01N, *Navy and Marine Corps Environmental Engineering for Facility Construction*.

F20 1.5 CONSTRUCTION SUBMITTALS

Submit construction submittals in accordance with PTS Section Z10,

General Performance Technical Specifications. In addition to the Z10 requirements and if applicable to this project, the Designer of Record (DOR) must obtain governing body approval for the construction submittals contained in the following UFGS sections and USACE Safety Manual as a minimum:

UFGS 01 57 19, *Temporary Environmental Controls*

UFGS 02 82 00, *Asbestos Remediation*

UFGS 02 83 00, *Lead Remediation*

UFGS 02 84 16, *Handling of Lighting Ballasts and Lamps Containing PCBs and Mercury*

UFGS 02 84 33, *Removal and Disposal of Polychlorinated Biphenyls (PCBs)*

UFGS 02 85 00, *Mold Remediation*

UFGS 31 21 13, *Radon Mitigation*

EM 385-1-1, *Safety and Health Requirements*, latest edition including changes

a. Engineering Safety Survey

b. Demolition Plan/ Deconstruction Plan

F2010 BUILDING ELEMENTS DEMOLITION

All demolition materials and appurtenances must be properly disposed of in accordance with all applicable regulations. Maximize the use of deconstruction and recycling services. Before demolition can commence, any hazardous materials must be abated in accordance with the requirements of the ESR and other parts of the RFP. Provide a Demolition Plan/ Deconstruction Plan that is based on a Registered Engineers Survey in accordance with EM 385-1-1 and has been approved by the DOR. Obtain approval from the Contracting Officer for the proposed demolition plan and work/outage schedule prior to demolition activities.

F2010 1.1 GENERAL DEMOLITION

The work includes demolition, salvage of identified items and materials and removal of resulting rubbish and debris. Remove rubbish and debris from Government property daily, unless otherwise directed. Materials that cannot be removed daily must be stored in areas specified in the approved Demolition Plan as described in Part 2 Section 01 57 19.

F2010 1.2 UTILITIES

Remove existing utilities and terminate in a manner conforming to the nationally recognized code covering the specific utility. Disturbance to utilities cannot cause a failure to utilities to remain operational, unless a planned outage is approved by the FEAD/ROICC and coordinated with on-site personnel.

F2010 1.3 DUST CONTROL

Perform dust control activities in accordance with approved Dirt and Dust Control Plan as described in Part 2 Section 01 57 19 and ESR F20.

F2010 1.4 TRAFFIC CONTROL

Where pedestrian, vehicle, aircraft safety is endangered, use traffic barricades.

F2010 1.5 WEATHER PROTECTION

For portions of the building to remain, protect building interior, materials, and equipment from weather at all times.

F2010 1.6 BURNING

Perform burning operations in accordance with ESR Section F20.

F201001 SUBSTRUCTURE & SUPERSTRUCTURE

Perform substructure or superstructure demolition work in accordance with ESR Section F20.

F201002 EXTERIOR CLOSURE

Perform exterior closure demolition work in accordance with ESR Section F20.

F2020 HAZARDOUS COMPONENTS ABATEMENT

F2020 1.1 PRIVATE QUALIFIED PERSON (PQP)

The PQP must perform independent inspections, testing and verification of the hazardous components work as indicated in ESR Section F20 and the approved work plans as described in Part 2 Section 01 57 19. The PQP must be appropriately licensed in the state in which the work will be performed.

F2020 1.2 FURNISHINGS

The government must remove all uncontaminated furnishings and equipment from the work area prior to the start of the work.

F2020 1.3 OZONE DEPLETING SUBSTANCES (ODS)

Perform ozone depleting substances (ODS) related work as indicated in the RFP and in accordance with Section 01 57 19.

F2020 1.4 DISPOSAL

All waste materials will become the property of the Contractor and must be transported, disposed of and recycled in accordance with the approved disposal plan as described in Part 2 Section 01 57 19.

-- End of Section --

SECTION G10

SITE PREPARATION 09/22

G10 GENERAL

RFP Part 3 including the Engineering System Requirements (ESR) provide project specific requirements. The RFP Part 4, Performance Technical Sections (PTS) provide generalized technical requirements that apply to multiple facility types and include more requirements than are applicable to any one project. Therefore, only the RFP Part 4 requirements that apply to the project and further define the RFP Part 3 project specific requirements are required.

G10 1.1 DESIGN GUIDANCE

Provide the design and installation in accordance with the following references. This Performance Technical Specification (PTS) adds clarification to the fundamental requirements contained in the following Government Standards. The general requirements of this PTS section are located in PTS Section Z10, *General Performance Technical Specification*.

Industry standards, codes, and Government standards referenced in the section text that are not found in the [Unified Master Reference List \(UMRL\)](#) in the [Federal Facility Criteria \(FFC\)](#) at the [Whole Building Design Guide \(WBDG\)](#) website, are listed below for basic designation identification. Comply with the required and advisory portions of the current edition of the referenced standard at the time of contract award.

G10 1.1.1 Industry Standards and Codes

AMERICAN NATIONAL STANDARDS INSTITUTE (ANSI)

Refer to UMRL for reference designation identification.

G10 1.1.2 Government Standards

CORPS OF ENGINEERS (COE)

COE EM 385-1-1	Safety and Health Requirements Manual
----------------	---------------------------------------

UNIFIED FACILITIES CRITERIA (UFC)

UFC 1-200-01	DoD Building Code (General Building Requirements) (A reference in this PTS section to UFC 1-200-01 requires compliance with the Tri-Service Core UFCs that are listed therein, which includes the following significant UFC(s): UFC 1-200-02, High Performance and
--------------	---

Sustainable Building Requirements
UFC 3-201-01, Civil Engineering
UFC 3-220-01, Geotechnical
Engineering)

UFC 3-810-01N Navy and Marine Corps Environmental
Engineering for Facility
Construction

UNIFIED FACILITIES GUIDE SPECIFICATIONS (UFGS)

UFGS 31 00 00 Earthwork

UFGS 01 57 19 Temporary Environmental Controls

UFGS 02 61 13 Excavation and Handling of
Contaminated Material

UFGS 02 61 23 Removal and Disposal of PCB
Contaminated Soils

UFGS 02 65 00 Underground Storage Tank Removal

G10 1.2 PERFORMANCE VERIFICATION AND ACCEPTABLE TESTING

Compliance with the requirements will be determined by a review of the design and construction submittals and by field inspection. See Part 2 Section 01 33 00, *Submittal Procedures*, for additional requirements. Verify earthwork performance via testing detailed in the paragraph, "Field Quality Control", in UFGS Section 31 00 00, Earthwork.

G10 1.3 DESIGN SUBMITTALS

Submit design submittals in accordance with Part 2 Section 01 33 00, *Submittal Procedures*, FC 1-300-09N, *Navy and Marine Corps Design Procedures*, UFC 3-201-01, *Civil Engineering*, and UFC 3-220-01, *Geotechnical Engineering*.

In addition, UFGS sections listed below or in the body of the PTS text are to be used by the Designer of Record (DOR) as a part of the design submittal. If the UFGS products or systems are applicable to the project, the DOR is required to edit these referenced UFGS sections and submit them as a part of the design submittal specification. Edit the specification sections in accordance with the limitations stated in PTS section Z10, *General Performance Technical Specifications*:

UFGS 31 00 00, *Earthwork*.

G10 1.4 CONSTRUCTION SUBMITTALS

Submit construction submittals in accordance with PTS Section Z10, *General Performance Technical Specifications*. In addition to the Z10 requirements, the Designer of Record (DOR) is required to approve the following construction submittals as a minimum:

Submittals in Part 2 UFGS Section 01 57 19, *Temporary Environmental*

Controls.

Submittals in UFGS Section 02 61 13, *Excavation and Handling of Contaminated Material*

Submittals in UFGS Section 31 00 00, *Earthwork.*

Submittals in UFGS Section 02 61 23, *Removal and Disposal of PCB Contaminated Soils.*

Submittals in UFGS Section 02 65 00, *Underground Storage Tank Removal.*

Waste Management Plan in accordance with Part 2 UFGS Section 01 74 19, *Construction Waste Management and Disposal.*

G10 1.5 GEOTECHNICAL REPORT

G10 1.5.1 Subsurface Soils Information

Provided subsurface soil information is included for the Contractor's information only, and is not guaranteed to fully represent all subsurface conditions. The data included in this RFP is intended for proposal preparation and preliminary design only. Perform, at the Contractor's expense, such subsurface exploration, investigation, testing, and analysis for the design and construction of the site improvements.

G10 1.5.2 Contractor-provided Geotechnical Engineer

The Contractor-provided Geotechnical Engineer is required to be experienced with soil conditions in the region where the project site is located. The Geotechnical Engineer is required to evaluate the RFP data, obtain and evaluate additional data to support the design and construction, and prepare a Geotechnical Report.

Coordinate work by the Contractor-provided Geotechnical Engineer at the project location with the Contracting Officer so as not to interfere with normal base operations. A minimum of two weeks prior to the Foundation Work Design submittal, provide the Contractor's Geotechnical Report (a searchable Adobe Acrobat PDF version on CD and two printed copies) for review and record keeping purposes. The report will become the property of the Government. Provide the geotechnical reports generated during construction, such as pile driving results and analysis, to the Contracting Officer. In addition, provide a searchable Adobe Acrobat PDF version and two printed copies for record keeping purposes.

G10 1.5.3 Contractor-Provided Geotechnical Report

Submit a written Geotechnical report based upon Government-provided subsurface investigation data and additional field and laboratory testing accomplished at the discretion of the Contractor's Geotechnical Engineer. Include in the Geotechnical Report all requirements listed in UFC 3-220-01, *Geotechnical*

Engineering, paragraph entitled "Section 1803 Geotechnical Investigations"; in addition, include the following:

a. The project site description, vicinity map and site map indicating the location of borings and any other sampling locations. Provide 24 hour groundwater observations for at least 20 percent of the borings, minimum one boring. Provide notes explaining any abbreviations or symbols used and describing any special site preparation requirements.

b. Results of field and laboratory testing, whether Government or Contractor-provided. Address existing subsurface conditions, selection and design of the foundation and floor slab, underground construction including utility installation and other site specific requirements (such as soil stabilization and slope stability).

c. Engineering analysis, discussion and recommendations Addressing:

1) Settlement analysis - Limit settlement in accordance with UFC 3-220-01 *Geotechnical Engineering* and EM 1110-1-1904 "Settlement Analysis".

2) Bearing Capacity analysis.

3) Foundation selection (shallow, deep, special) and construction considerations; dimensions, and installation procedures.

4) Site preparation (earthwork procedures and equipment, compaction requirements, building slab preparation, soil sensitivity to weather and equipment, groundwater influence on construction, mitigation of expansive soils or liquefaction potential, and dewatering requirements).

5) Sheet piling and shoring considerations.

6) Pavement design calculations with parameters defined, actual or assumed, and recommended thicknesses and materials.

7) Infiltration rate.

8) Haul routes and stockpile locations for earthwork.

9) Calculations to support conclusions and recommendations.

10) Present recommendations on a structure-by-structure basis.

A registered Geotechnical Engineer is required to sign the Geotechnical Report.

Accompany the submitted report with a cover letter identifying any report recommendations proposed to be adopted into the design which are interpreted by the Contractor as a changed condition to the Geotechnical or Pavement related requirements of the RFP.

G10 1.5.4 Geotechnical Site Data required in Design Drawings

The Contractor's final design drawings must include the Government-provided subsurface data presented in the RFP, as well as additional borings and laboratory test result data performed by the Contractor. The data provided is required to include:

a. Logs of Borings and related summary of laboratory test results and groundwater observations. Provide 24 hour groundwater observations for at least 20 percent of the borings, minimum one boring. Provide notes explaining any abbreviations or symbols used and describing any special site preparation requirements.

b. Indicate the locations of borings on the drawings. Revise the design drawings to reference the Contractor's Geotechnical Report as being a basis for design.

G1010 SITE CLEARING

G1010 1.1 GENERAL

N/A

G1010 1.2 BURNING

Burning will not be allowed.

G101001 CLEARING

G101001 1.1 CLEARING

Clear trees, shrubs, brush and vegetation for construction of the project. Clearing includes the felling, trimming, and cutting of trees into sections and the satisfactory disposal of the trees and other vegetation designated for removal, including downed timber, snags, brush, and rubbish occurring within the areas to be cleared.

G101001 1.2 PRESERVATION

Preserve and protect trees, shrubs and vegetation not directly impacted by the construction in accordance with Part 2 Section 01 57 19, *Temporary Environmental Controls*, and PTS Section G101002 Tree Removal.

G101002 TREE REMOVAL

Remove and dispose of trees to a depth of at least 18 inches (450 mm) below ground surface. Fill depressions with satisfactory material and compact. Mound fill 2 inches (50 mm) above adjacent surface to allow for settling when not part of a subbase.

G101003 STUMP REMOVAL

Remove stumps to a depth of at least 18 inches (450 mm) below ground surface. Fill depressions with satisfactory material and compact. Mound fill 2 inches (50 mm) above adjacent surface to allow for settling when not part of a

subbase.

G101004 GRUBBING

Within the clearing limits, remove and dispose of logs, shrubs, brush, matted roots, roots larger than 2 inches (50 mm) in diameter, and other debris to a depth of at least 18 inches (450 mm) below ground surface. Fill depressions made by grubbing with satisfactory material and compact to make the new surface conform to the adjacent surface of the ground.

G101005 SELECTIVE THINNING

G101005 1.1 TREE THINNING

Trim trees to remain of dead branches 1-1/2 inches (38 mm) or more in diameter. Cut limbs and branches in accordance with ANSI A300.

G101006 DEBRIS DISPOSAL

Prevent spillage on pavements, streets, or adjacent areas. Dispose of surplus and unsuitable material off of Government property.

G1020 SITE DEMOLITION & RELOCATIONS

G1020 1.1 GENERAL

Demolition work includes the demolition, removal and legal disposal of existing construction debris to accommodate the new construction. Take precautions to prevent damages to existing utilities, construction and materials not scheduled for demolition, repair or replacement; repair damages to the construction and materials to the satisfaction of the Contracting Officer and at no additional cost to the Government.

G1020 1.2 AUTHORIZATION

Do not begin demolition until the Demolition Plan has been approved by, and authorization is received from, the Contracting Officer.

G1020 1.3 TITLE TO MATERIALS

Whenever possible, salvage or recycle features demolished in lieu of disposing of as waste in a landfill. Existing features to be demolished which are not salvageable or reused become the property of the Contractor, and must be removed from the project site. The Government will not be responsible for the condition, loss of, or damage to, such property after contract award. Materials and equipment cannot be viewed by prospective purchasers or sold on the site.

G1020 1.4 REUSE OF MATERIALS AND EQUIPMENT

Remove and store materials and equipment to be reused or relocated to prevent damage, and reinstall as the work progresses.

G1020 1.5 SALVAGED MATERIALS AND EQUIPMENT

Deliver salvaged materials and equipment that are to be removed by the

Contractor and that are to remain the property of the Government to a storage site on the installation, in accordance with instructions of the Contracting Officer.

G102001 BUILDING MASS DEMOLITION

Refer to Section F20, *Selective Building Demolition*, for additional information.

G102002 ABOVEGROUND SITE DEMOLITION

G102002 1.1 DUST AND DEBRIS CONTROL

Prevent the spread of dust and debris to occupied portions of a building or on pavements and avoid the creation of a nuisance or hazard in the surrounding area. Do not use water for dust control if it results in hazardous or objectionable conditions such as, but not limited to, ice, flooding, or pollution.

G102002 1.2 PROTECTION

G102002 1.2.1 Traffic Control

Where pedestrian and driver safety is endangered in the area of removal work, provide traffic control in accordance with FHWA Manual on Uniform Traffic Control Devices (MUTCD).

G102002 1.2.2 Foreign Object Damage (FOD)

Not used.

G102002 1.2.3 Existing Work

Protect existing work that is to remain in place, be reused, or remain the property of the Government. At no additional expense to the Government, repair items that are damaged during performance of the work to original condition, or replace with new. Do not overload pavements to remain.

G102002 1.3 PAVING AND SLABS

Remove concrete and asphaltic concrete paving and slabs as required for construction of project. Remove the existing aggregate base in areas to receive new pavement to the depth of the proposed pavement section below new finish grade. Remove the existing aggregate base in areas not to receive new pavement to a depth of 8 inches (200 mm) below existing adjacent grade and break remaining pavement (if any) to allow drainage. Provide neat sawcuts at limits of pavement removal; protect sawcuts so that new pavement butts against the existing without feathering.

G102003 UNDERGROUND SITE DEMOLITION

G102003 1.1 UTILITY TERMINATION

Terminate utilities in accordance with state and local rules and

regulations; the nationally recognized code; and the requirements of the utility provider covering the specific utility; UFC 3-201-01, *Civil Engineering*; and approved by the Contracting Officer.

G102003 1.2 PROTECTION OF EXISTING UTILITIES

Protect existing utilities to remain. Where removal of existing utilities and pavement is required, provide approved barricades, temporary covering of exposed areas, and temporary services or connections. Repair damage to existing utilities to remain at no additional expense to the Government.

G102004 BUILDING RELOCATION

Refer to Section F20, *Selective Building Demolition*, for additional information.

G102005 UTILITY RELOCATION

Repair relocated items that are damaged or replace damaged items with new undamaged items at no additional expense to the Government.

G102006 FENCING RELOCATION

Remove and replace post foundations. Repair relocated items that are damaged or replace damaged items with new undamaged items at no additional expense to the Government.

G102007 SITE CLEANUP

Remove rubbish and debris from the installation daily; do not allow accumulations inside or outside the building(s) or on pavements. Store materials that cannot be removed daily in areas specified by the Contracting Officer.

G102007 1.1 SPILLS

In the event of a spill or release of hazardous substances, pollutant, contaminant or oil, notify the Contracting Officer immediately. Take immediate containment actions to minimize the effect of any spill or leak in accordance with the ESR and the approved spill work plan as described in Part 2 Section 01 57 19, *Temporary Environmental Controls*. Perform clean up at no additional expense to the Government.

G1030 SITE EARTHWORK

G1030 1.1 GENERAL

This section includes the design and construction requirements for earthwork and grading related to construction of the roadways, parking, paved areas and other related sitework. Refer to Section A10, *Foundations*, for earthwork related to construction of structures, including building, footings, foundations, retaining walls, slabs, tanks, and utility appurtenances.

The Designer of Record is required to utilize UFGS Section 31 00 00,

Earthwork, for the project specification, and to submit the edited specification section as a part of the design submittal for the project.

G103001 GRADING

Provide site grading in accordance with the requirements of UFC 3-201-01, *Civil Engineering*.

G103001 1.1 ELEVATIONS

Establish finish floor elevations in accordance with UFC 1-200-01, *DoD Building Code (General Building Requirements)*, and UFC 3-101-01, *Architecture*.

G103001 1.2 SITE GRADING

Grade the site such that associated storm water runoff does not adversely affect surrounding sites. Preserve natural topographic features to minimize the impact on the existing drainage patterns at and adjacent to the site.

G103001 1.3 FINISHED SURFACES

Provide finish grading with drainage towards new and existing drainage features and with no resulting low spots that hold water or that direct runoff towards new or existing facilities or site amenities.

G103001 1.4 RODENT AND VEGETATION CONTROL

Prevent and eliminate standing water.

G103004 FILL & BORROW

G103004 1.1 SOURCES

Where sufficient topsoil and satisfactory materials are not available on the project site, provide suitable borrow materials.

G103004 1.2 REQUIREMENTS FOR OFF SITE SOIL

Test off-site soil in accordance with UFGS Section 31 00 00, *Earthwork*, section titled "Requirements for Off Site Soil".

G103004 1.3 UNSATISFACTORY SOIL MATERIALS

Remove uncontaminated unsatisfactory soil materials from the site. Unsatisfactory materials are materials which do not comply with the requirements for satisfactory materials. Unsatisfactory materials also include man-made fills, trash, refuse, backfills from previous construction or material classified as satisfactory which contains root and other organic matter, frozen material, and stones larger than 3 inches. The Contracting Officer shall be notified of any contaminated materials.

G103004 1.4 TOPSOIL

Refer to Section G2050, "Landscaping". Remove unsatisfactory, existing topsoil from the site in accordance with the Project Program.

G103005 COMPACTION

Provide compaction in accordance with UFGS Section 31 00 00, *Earthwork*, and the recommendations of the Contractor's Geotechnical Engineer, whichever is greater.

G103006 SOIL STABILIZATION

Provide soil stabilization designed to function as required by site conditions in accordance with the State Highway specifications and standards in the state where the project is located. Apply and install geosynthetics in accordance with the manufacturer's written instructions.

G103007 SLOPE STABILIZATION

Provide slope stabilization methods in accordance with the State Highway specifications and standards in the state where the project is located. Design and install manufactured products, gabions, geogrids, rock anchors in accordance with the manufacturer's written instructions.

G103008 SOIL TREATMENT

G103008 1.1 TERMITE CONTROL

Refer to Section A1010 1.2, "Termite Control".

G103009 SHORING

Provide sheeting, shoring, bracing, cribbing and underpinning in accordance with the Army Corps of Engineer's Safety and Health Requirements Manual (COE EM 385-1-1), UFC 3-220-01, *Geotechnical Engineering*, UFC 3-301-01, *Structural Engineering*, and other Federal, State and local codes and requirements.

Provide protection of existing structures.

G103010 TEMPORARY DEWATERING

The design of the temporary dewatering system is required to account for soil conditions, rainfall, fluctuations in the groundwater elevations and the potential settlement impact on adjacent facilities due to dewatering. Provide dewatering in accordance with UFGS Section 31 00 00, *Earthwork*. While the excavation is open, maintain the water level continuously, at least 1.0 foot (0.30 m) below the working level.

French drains, sumps, ditches or trenches are not allowed within 3 feet (0.9 m) of the foundation of any structure without written approval of the Government's Civil/Geotechnical Reviewer.

G103011 TEMPORARY EROSION & SEDIMENT CONTROL

G103011 1.1 TEMPORARY EROSION & SEDIMENT CONTROL

Develop and implement temporary erosion and sediment control measures and other Best Management Practices (BMPs) prior to or in conjunction with commencement of earthwork in accordance with the state Erosion and Sediment Control Laws and Regulations. Remove non-permanent erosion control measures after vegetation is fully established.

G103011 1.2 MAINTENANCE

Maintain temporary erosion control measures in accordance with state Erosion and Sediment Control Laws and Regulations throughout the project until areas are fully stabilized.

G1040 HAZARDOUS WASTE REMEDIATION & DUST SUPPRESSION

Perform work in accordance with Part 2 Section 01 57 19, *Temporary Environmental Controls*.

G1040 1.1 DISPOSAL

Manage, transport and dispose of waste materials in accordance with Part 2 Section 01 57 19, *Temporary Environmental Controls*.

-- End of Section --

SECTION G20

SITE IMPROVEMENTS 09/22

G20 GENERAL

RFP Part 3 including the Engineering System Requirements (ESR) provide project specific requirements. The RFP Part 4, Performance Technical Sections (PTS) provide generalized technical requirements that apply to multiple facility types and include more requirements than are applicable to any one project. Therefore, only the RFP Part 4 requirements that apply to the project and further define the RFP Part 3 project specific requirements are required.

G20 1.1 DESIGN GUIDANCE

Provide the design and installation in accordance with the following references. This Performance Technical Specification (PTS) adds clarification to the fundamental requirements contained in the following Government Standards. The general requirements of this PTS section are located in PTS Section Z10, *General Performance Technical Specification*.

Industry standards, codes, and Government standards referenced in the section text that are not found in the [Unified Master Reference List \(UMRL\)](#) in the [Federal Facility Criteria \(FFC\)](#) at the [Whole Building Design Guide \(WBDG\)](#) website, are listed below for basic designation identification. Comply with the required and advisory portions of the current edition of the referenced standard at the time of Contract award.

G20 1.1.1 Industry Standards and Codes

AMERICAN NATIONAL STANDARDS INSTITUTE (ANSI)

AMERICAN SOD PRODUCERS ASSOCIATION (ASPA)

U.S CONSUMER PRODUCT SAFETY COMMISSION, PUBLICATION NO. 325

Refer to UMRL for reference designation identification.

G20 1.1.2 Government Standards

U.S. GENERAL SERVICES ADMINISTRATION (GSA)

FS RR-F-191	Fencing and Wire and Post Metal (and Gates, Chain-link Fence Fabric, and Accessories)
-------------	---

FACILITIES CRITERIA (UFC)

UFC 1-200-01	DoD Building Code (General Building Requirements) (A reference in this PTS section to UFC 1-200-01 requires compliance with the Tri-
--------------	---

	Service Core UFCs that are listed therein, which includes the following significant UFC(s): UFC 1-200-02, High Performance and Sustainable Building Requirements UFC 3-201-01, Civil Engineering UFC 3-201-02, Landscape Architecture UFC 3-210-01, Low Impact Development UFC 3-220-01, Geotechnical Engineering
UFC 3-250-01	Pavement Design for Roads and Parking Areas
UFC 3-270-01	Asphalt Maintenance and Repair
UFC 3-270-02	Asphalt Crack Repair
UFC 3-270-03	Concrete Crack and Partial Depth Spall Repair
UFC 3-270-04	Concrete Repair
UFC 4-022-02	Selection and Application of Vehicle Barriers
UFC 4-022-03	Security Fences and Gates

G20 1.2 QUALITY ASSURANCE

Not required.

G20 1.3 PERFORMANCE VERIFICATION AND ACCEPTANCE TESTING

Compliance with the requirements will be determined by a review of the design and construction submittals and by field inspection. See Part 2 Section 01 33 00 *Submittal Procedures*, for additional requirements.

Verify satisfactory performance via Performance Verification, as detailed in this section of the RFP. Verify satisfactory performance also via testing as detailed in the paragraph, Field Quality Control, in UFGS Specification Sections utilized.

G20 1.3.1 Subgrade Preparation Performance Verification

Perform subgrade preparation in accordance with PTS Section G10. If required by the Designer of Record, perform proof rolling. Perform proof rolling in the presence of the Contracting Officer. Rutting or pumping of material is required to be undercut and replaced with satisfactory soil materials as defined in Section G10, *Site Preparation*.

G20 1.3.2 Base Course Performance Verification

G20 1.3.2.1 Aggregate Base Course

- a. Sampling: ASTM D75/D75M.
- b. Gradation: ASTM C136.
- c. Thickness: Confirm in-place compacted thickness. Acceptable tolerances are plus or minus 0.5 inches (13 mm). One test for every 500 square yards (418 square meters); minimum 2 tests.
- d. Density: ASTM D1556 or ASTM D6938. One field test for every 1000 square yards (836 square meters); minimum 2 tests. ASTM D1557, Method A, B or C; one laboratory test for the project.
- e. Visual: Provide smooth surface with no ruts.

G20 1.3.2.2 Other Types of Base Courses

For other types of base courses, provide field testing in accordance with the SHS.

G2050 LANDSCAPING

Landscape area is defined as permeable areas within the project boundaries not covered by buildings, roads, parking lots, sidewalks, and other non-permeable areas. Provide landscape improvements to all site areas disturbed by construction.

G205001 FINE GRADING AND SOIL PREPARATION

See Section G10, *Site Preparation*. Provide 4 inches (102 mm) of topsoil with appropriate soil amendments, as recommended by a current soil composition test, for areas to be planted with turf grass.

G205002 EROSION CONTROL MEASURES

See Section G10, *Site Preparation*.

G205004 SEEDING, SPRIGGING, AND SODDING

Hydroseed areas that are to be seeded and are larger than 1,000 square feet (92.90 square meters). Select hydroseed mix composition that is appropriate for surrounding land use and compatible and consistent with local application rates, seed availability and established practice in the project area. If project dates are unknown, specify required planting dates or alternative species for different seasons. Apply seed at a time best suited for germination of the selected species. Seeded areas are required to achieve a 95-percent coverage of the selected species and be weed free at the end of the Establishment Period.

-- End of Section --

SECTION Z10

GENERAL PERFORMANCE TECHNICAL SPECIFICATION 06/23

Z10 GENERAL

RFP Part 3 including the Engineering System Requirements (ESR) provide project specific requirements. The RFP Part 4, Performance Technical Sections (PTS) provide generalized technical requirements that apply to multiple facility types and include more requirements than are applicable to any one project. Therefore, only the RFP Part 4 requirements that apply to the project and further define the RFP Part 3 project specific requirements are required.

Z10 1.1 NARRATIVE

All Performance Technical Specification (PTS) sections must be used in conjunction with all parts of the Design Build (D/B) Request for Proposal (RFP) to determine the full requirements of this solicitation. This PTS section provides general requirements for the other PTS sections of this RFP and is used in conjunction with the other PTS sections.

Refer to Part 2 TOC 1.0a for the "Order of Precedence" of the RFP Parts. Requirements listed in the Project Program take precedence over the PTS sections requirements; therefore, requirements identified in the Project Program eliminate options related to that requirement in the PTS sections.

Z10 1.2 DESIGN GUIDANCE

Provide work in compliance with the following design standards and codes, as a minimum. Government standards listed in this RFP take precedence over industry standards.

The PTS Sections reference published standards, the titles of which can be found in the *Unified Master Reference List (UMRL)* on the Whole Building Design Guide at the [Unified Facilities Guide Specification \(UFGS\) Website](#) . The publications referenced form a part of this specification to the extent referenced. The publications are referred to in the section text by the basic designation only. Industry standards, codes, and Government standards referenced in the section text, and not found in the UMRL, are listed at the beginning of the PTS sections.

The advisory provisions of all referenced codes, standards, and specifications must be mandatory; substitute words such as "must", or "required" for words such as "should", "may", or "recommended," wherever they appear. The results of these wording substitutions incorporate these code and standard statements as requirements. Reference to the "authority having jurisdiction" for variance from criteria must be interpreted to mean the "Chief Engineer, NAVFAC" and for contractual obligations on this project must be interpreted to mean the "Contracting Officer". Comply with the required and advisory portions of the current edition of the standard at the time of contract

award.

The following list of codes and standards is not comprehensive and is augmented by other codes and standards referenced and cross-referenced in the RFP.

Z10 1.2.1 INDUSTRY CODES

INTERNATIONAL BUILDING CODE (IBC) as modified by UFC 1-200-01. UFC 1-200-01 applies the IBC to the project and references other commercial standards and UFC criteria that become part of the contract.

Z10 1.2.2 INDUSTRY REQUIREMENTS

WHOLE BUILDING DESIGN GUIDE (WBDG)

WHOLE BUILDING DESIGN GUIDE, Ensure Occupant Safety and Health (Systems Safety Engineering) at <https://www.wbdg.org/design-objectives/secure-safe/occupant-safety-health>

Z10 1.2.3 GOVERNMENT STANDARDS

Z10 1.2.3.1 UNIFIED FACILITIES CRITERIA (UFC)

UFC 1-200-01	DoD Building Code (UFC 1-200-01 is a hub document that provides general building requirements and references other critical UFCs. A reference to UFC 1-200-01 requires compliance with the Tri-Service Core UFCs listed therein.)
UFC 1-200-02	High Performance and Sustainable Building Requirements
FC 1-300-09N	Navy and Marine Corps Design Procedures

Z10 1.2.3.2 FEDERAL STANDARDS

Architectural Barriers Act Standards with DEPSECDEF Memorandum 31 Oct 2008, "Access for People with Disabilities"

Occupational Safety and Health Administration (OSHA)

Z10 1.3 MATERIALS AND EQUIPMENT REQUIREMENTS IDENTIFICATION

N/A

Z10 1.4 COMMISSIONING

N/A

Z10 1.5 PERFORMANCE VERIFICATION AND ACCEPTANCE TESTS

N/A

Z10 1.6 SUBMITTALS

Refer to Part 2, Section 01 33 00, *Submittal Procedures*.

Z10 1.6.1 DESIGN SUBMITTALS

Submit design submittals in accordance with FC 1-300-09N, *Navy and Marine Corps Design Procedures*, and other discipline-specific guidelines listed in the applicable PTS sections.

The Designer of Record (DOR) must edit the UFGS sections for the project and submit the edited specification as a part of the design submittal. The DOR must edit the UFGS as follows:

- (1) Prepare UFGS Specifications as part of the project specification,
- (2) Delete only portions of the UFGS specification that are not applicable to the project,
- (3) Edit only the bracketed choices that are within the UFGS specification text,
- (4) Edit blank bracketed options to include requirements that exercise prudence and adherence to acceptable industry standards,
- (5) Comply with the directions, directives, and requirements of all UFGS Criteria Notes. The UFGS Criteria Notes are typically bordered on the top and bottom by a line of asterisks to highlight their location.
- (6) If proprietary information is provided or required to streamline the construction submittal process, include proprietary information in the edited UFGS sections and added to the end of each UFGS section. Confirm that the proprietary products, materials, and systems listed in the specifications are in compliance with the requirements of the RFP.

Z10 1.6.2 CONSTRUCTION SUBMITTALS

Submit for approval to the Designer of Record (DOR), construction submittals, product data, manufacturer's information, shop drawings, and test reports on all materials and systems installed in the project, unless the DOR designates submittal for QC approval. Refer to each PTS section for further construction submittal requirements relating to the work identified in that particular PTS section. Some PTS sections reference UFGS sections that will require more construction submittals for DOR approval than is stated above.

--End of Section--

Z10 1.6 SUBMITTALS

Refer to Part 2, Section 01 33 00, *Submittal Procedures*.

Z10 1.6.1 DESIGN SUBMITTALS

Submit design submittals in accordance with FC 1-300-09N, *Navy and Marine Corps Design Procedures*, and other discipline-specific guidelines listed in the applicable PTS sections.

The Designer of Record (DOR) must edit the UFGS sections for the project and submit the edited specification as a part of the design submittal. The DOR must edit the UFGS as follows:

- (1) Prepare UFGS Specifications as part of the project specification,
- (2) Delete only portions of the UFGS specification that are not applicable to the project,
- (3) Edit only the bracketed choices that are within the UFGS specification text,
- (4) Edit blank bracketed options to include requirements that exercise prudence and adherence to acceptable industry standards,
- (5) Comply with the directions, directives, and requirements of all UFGS Criteria Notes. The UFGS Criteria Notes are typically bordered on the top and bottom by a line of asterisks to highlight their location.
- (6) If proprietary information is provided or required to streamline the construction submittal process, include proprietary information in the edited UFGS sections and added to the end of each UFGS section. Confirm that the proprietary products, materials, and systems listed in the specifications are in compliance with the requirements of the RFP.

Z10 1.6.2 CONSTRUCTION SUBMITTALS

Submit for approval to the Designer of Record (DOR), construction submittals, product data, manufacturer's information, shop drawings, and test reports on all materials and systems installed in the project, unless the DOR designates submittal for QC approval. Refer to each PTS section for further construction submittal requirements relating to the work identified in that particular PTS section. Some PTS sections reference UFGS sections that will require more construction submittals for DOR approval than is stated above.

--End of Section--

PART FIVE - PRESCRIPTIVE SPECIFICATIONS

UFGS SECTION 02 41 00 DEMOLITION

SECTION 02 41 00

DEMOLITION

08/22

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AIR-CONDITIONING, HEATING AND REFRIGERATION INSTITUTE (AHRI)

AHRI Guideline K (2009) Guideline for Containers for Recovered Non-Flammable Fluorocarbon Refrigerants

AMERICAN SOCIETY OF SAFETY PROFESSIONALS (ASSP)

ASSP A10.6 (2006) Safety & Health Program Requirements for Demolition Operations - American National Standard for Construction and Demolition Operations

U.S. ARMY CORPS OF ENGINEERS (USACE)

EM 385-1-1 (2024) Safety -- Safety and Occupational Health (SOH) Requirements

U.S. DEFENSE LOGISTICS AGENCY (DLA)

DLA 4145.25 (Jun 2000; Reaffirmed Oct 2010) Storage and Handling of Liquefied and Gaseous Compressed Gases and Their Full and Empty Cylinders;
<https://www.dla.mil/Portals/104/Documents/DispositionServices/ddsr/docs/cylinderjointpub.pdf>

U.S. DEPARTMENT OF DEFENSE (DOD)

DOD 4000.25-1-M (2006) MILSTRIP - Military Standard Requisitioning and Issue Procedures

MIL-STD-129 (2014; Rev R; Change 1 2018; Change 2 2019; Change 3 2023) Military Marking for Shipment and Storage

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

40 CFR 61 National Emission Standards for Hazardous Air Pollutants

40 CFR 82 Protection of Stratospheric Ozone

49 CFR 173.301 Shipment of Compressed Gases in Cylinders

and Spherical Pressure Vessels

1.2 PROJECT DESCRIPTION

1.2.1 Definitions

1.2.1.1 Demolition

Demolition is the process of tearing apart and removing any feature of a facility together with any related handling and disposal operations.

1.2.1.2 Deconstruction

Deconstruction is the process of taking apart a facility with the primary goal of preserving the value of all useful building materials.

1.2.1.3 Demolition Plan

Demolition Plan is the planned steps and processes for managing demolition activities and identifying the required sequencing activities and disposal mechanisms.

1.2.1.4 Deconstruction Plan

Deconstruction Plan is the planned steps and processes for dismantling all or portions of a structure or assembly, to include managing sequencing activities, storage, re-installation activities, salvage and disposal mechanisms.

1.2.2 Demolition Plan

Prepare a [Demolition Plan](#) and submit proposed salvage, demolition, and removal procedures for approval before work is started. Include in the plan procedures for careful removal and disposition of materials specified to be salvaged, coordination with other work in progress, a disconnection schedule of utility services, a detailed description of methods and equipment to be used for each operation and of the sequence of operations. [Identify components and materials to be salvaged for reuse or recycling with reference to paragraph Existing Facilities to be Removed. Append tracking forms for all removed materials indicating type, quantities, condition, destination, and end use.](#) Coordinate with Waste Management Plan in accordance with Section 01 74 19 CONSTRUCTION WASTE MANAGEMENT AND DISPOSAL. Provide procedures for safe conduct of the work in accordance with [EM 385-1-1](#). Plan must be approved by Contracting Officer prior to work beginning.

1.2.3 General Requirements

Do not begin demolition until authorization is received from the Contracting Officer. [The work of this section is to be performed in a manner that maximizes the value derived from the salvage and recycling of materials.](#) Remove rubbish and debris from the project site; do not allow accumulations inside or outside the building. The work includes demolition, salvage of identified items and materials, and removal of resulting rubbish and debris. Remove rubbish and debris from Government property daily, unless otherwise directed. Store materials that cannot be removed daily in areas specified by the Contracting Officer. In the interest of occupational safety and health, perform the work in accordance with [EM 385-1-1](#), Section 23, Demolition, and other applicable Sections.

1.3 ITEMS TO REMAIN IN PLACE

Comply with FAR 52.236-9 to protect existing vegetation, structures, equipment, utilities, and improvements. Coordinate the work of this section with all other work indicated. Construct and maintain shoring, bracing, and supports as required. Ensure that structural elements are not overloaded. Increase structural supports or add new supports as may be required as a result of any cutting, removal, deconstruction, or demolition work performed under this contract. Do not overload pavements to remain. Provide new supports and reinforcement for existing construction weakened by demolition, deconstruction, or removal work. Repairs, reinforcement, or structural replacement require approval by the Contracting Officer prior to performing such work.

1.3.1 Existing Construction Limits and Protection

Do not disturb existing construction beyond the extent indicated or necessary for installation of new construction. Provide temporary shoring and bracing for support of building components to prevent settlement or other movement. Provide protective measures to control accumulation and migration of dust and dirt in all work areas. Remove snow, dust, dirt, and debris from work areas daily.

1.3.2 Weather Protection

For portions of the building to remain, protect building interior and materials and equipment from the weather at all times. Where removal of existing roofing is necessary to accomplish work, have materials and workmen ready to provide adequate and temporary covering of exposed areas.

1.3.3 Trees

Protect trees within the project site which might be damaged during demolition, and which are indicated to be left in place, by a 6 foot high fence. Erect and secure fence a minimum of 5 feet from the trunk of individual trees or follow the outer perimeter of branches or clumps of trees. Replace any tree designated to remain that is damaged during the work under this contract with like-kind or as approved by the Contracting Officer.

1.3.4 Utility Service

Maintain existing utilities indicated to stay in service and protect against damage during demolition operations. Prior to start of work, utilities serving each area of alteration or removal will be shut off by the Government/utility provider upon written request and disconnected and sealed by the Contractor.

Steam - Cut and cap abandoned steam/condensate into the buildings.

Gas - Coordinate with North Shore Gas for demolition/abandonment of gas lines near the facilities.

Water/wastewater - Contractor remove the existing lines all the way back to the mains to be left in service. Fire hydrants are to remain.

Electric - Coordinate system disconnection outage with UEM.

Storm - Roof drains to be removed, manhole covers to be raised, etc.

Telephone - Disconnect and remove all phone wires specific to the building from the AT&T network. Any wiring that passes through to other buildings or locations must be protected and maintained to prevent service disruptions.

Communications/Fiber Optic service - Remove fiber optic cabling to the maximum extent possible without causing damage to adjacent cables. At a minimum, retract fiber cabling to the nearest manhole, neatly coil, and properly label for future identification.

1.3.5 Facilities

Protect electrical and mechanical services and utilities. Where removal of existing utilities and pavement is specified or indicated, provide approved barricades, temporary covering of exposed areas, and temporary services or connections for electrical and mechanical utilities. Floors, roofs, walls, columns, pilasters, and other structural components that are designed and constructed to stand without lateral support or shoring, and are determined to be in stable condition, must remain standing without additional bracing, shoring, or lateral support until demolished or deconstructed, unless directed otherwise by the Contracting Officer. Ensure that no elements determined to be unstable are left unsupported and place and secure bracing, shoring, or lateral supports as may be required as a result of any cutting, removal, deconstruction, or demolition work performed under this contract.

1.4 BURNING

The use of burning at the project site for the disposal of refuse and debris will not be permitted. Where burning is permitted, adhere to federal, state, and local regulations.

1.5 AVAILABILITY OF WORK AREAS

Areas in which the work is to be accomplished will be available at contract award.

1.6 SUBMITTALS

Government approval is required for submittals with a "G" classification. Submittals not having a "G" classification are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Demolition Plan; G

Existing Conditions

SD-07 Certificates

Notification; G

SD-11 Closeout Submittals

Receipts

1.7 QUALITY ASSURANCE

Submit timely [notification](#) of demolition projects to Federal, State, regional, and local authorities in accordance with [40 CFR 61](#), Subpart M. Notify the State's environmental protection agency and the Contracting Officer in writing 10 working days prior to the commencement of work in accordance with [40 CFR 61](#), Subpart M. Comply with federal, state, and local hauling and disposal regulations. In addition to the requirements of the "Contract Clauses," conform to the safety requirements contained in [ASSP A10.6](#). Comply with the Environmental Protection Agency requirements specified. Use of explosives will not be permitted.

1.7.1 Dust and Debris Control

Prevent the spread of dust and debris and avoid the creation of a nuisance or hazard in the surrounding area. Do not use water if it results in hazardous or objectionable conditions such as, but not limited to, ice, flooding, or pollution.

The contractor must develop a Fugitive Dust Control Plan that outlines procedures, equipment, and actions to meet the performance standards at the compliance point. If the contractor's methods, equipment, or actions fail to meet these standards during demolition activities, the contractor must cease dust-producing operations.

No person must allow or cause the emission of airborne fugitive particulate matter from demolition activities that is visible to an observer looking upward beyond the project site boundary. The project boundary is defined by the temporary chain link fence surrounding the site. Demolition activities include, but are not limited to, building removal, pavement or subgrade removal, grading, excavation, material handling, storage, paving, landscaping, cleaning, and sweeping.

The Fugitive Dust Control Plan is subject to review by the NSGL Environmental Division and must include provisions for controlling surface water releases from any water or chemicals used in dust suppression.

1.8 PROTECTION

1.8.1 Traffic Control Signs

a. Where pedestrian and driver safety is endangered in the area of removal work, use traffic barricades with flashing lights. Notify the Contracting Officer prior to beginning such work.

1.8.2 Protection of Personnel

Before, during and after the demolition work continuously evaluate the condition of the structure being demolished and take immediate action to protect all personnel working in and around the project site. No area, section, or component of floors, roofs, walls, columns, pilasters, or other structural element will be allowed to be left standing without sufficient bracing, shoring, or lateral support to prevent collapse or failure while workmen remove debris or perform other work in the immediate area.

1.9 RELOCATIONS

Perform the removal and reinstallation of relocated items as indicated with

workmen skilled in the trades involved. Repair or replace items to be relocated which are damaged by the Contractor with new undamaged items as approved by the Contracting Officer.

1.10 EXISTING CONDITIONS

Before beginning any demolition work, survey the site and examine the drawings and specifications to determine the extent of the work. Record existing conditions in the presence of the Contracting Officer or the Contracting Officer's Representative showing the condition of structures and other facilities adjacent to areas of alteration or removal. Photographs or electronic images with a minimum resolution of 3072 x 2304 pixels, capable of a print resolution of 300 dpi, will be acceptable as a record of existing conditions. Include in the record the elevation of the top of foundation walls, finish floor elevations, possible conflicting electrical conduits, plumbing lines, alarms systems, the location and extent of existing cracks and other damage and description of surface conditions that exist prior to starting work. It is the Contractor's responsibility to verify and document all required outages which will be required during the course of work, and to note these outages on the record document. Submit survey results to the Contracting Officer or the Contracting Officer's Representative.

PART 2 PRODUCTS

2.1 FILL MATERIAL

- a. Comply with excavating, backfilling, and compacting procedures for soils used as backfill material to fill basements, voids, depressions or excavations resulting from demolition of structures. [Provide fill material consisting of waste products from demolition until all waste appropriate for this purpose is consumed.](#)

PART 3 EXECUTION

3.1 EXISTING FACILITIES TO BE REMOVED

Inspect and evaluate existing structures onsite for reuse. Disassemble existing construction scheduled to be removed for reuse. Dismantled and removed materials are to be separated, set aside, and prepared as specified, and stored or delivered to a collection point for reuse, remanufacture, recycling, or other disposal, as specified. Designate materials for reuse onsite whenever possible.

3.1.1 Structures

- a. Demolish structures in a systematic manner from the top of the structure to the ground. Complete demolition work above each tier or floor before the supporting members on the lower level are disturbed. Demolish concrete and masonry walls in small sections. Remove structural framing members and lower to ground by means of derricks, platforms hoists, or other suitable methods as approved by the Contracting Officer.
- b. Locate demolition and deconstruction equipment throughout the structure and remove materials so as to not impose excessive loads to supporting walls, floors, or framing.

3.1.2 Utilities and Related Equipment

3.1.2.1 General Requirements

Do not interrupt existing utilities serving occupied or used facilities, except when authorized in writing by the Contracting Officer. Do not interrupt existing utilities serving facilities occupied and used by the Government except when approved in writing and then only after temporary utility services have been approved and provided. Do not begin demolition or deconstruction work until all utility disconnections have been made. Shut off and cap utilities for future use, as indicated.

3.1.2.2 Disconnecting Existing Utilities

Remove existing utilities , as indicated and terminate in a manner conforming to the nationally recognized code covering the specific utility and approved by the Contracting Officer. When utility lines are encountered but are not indicated on the drawings, notify the Contracting Officer prior to further work in that area. Remove meters and related equipment and deliver to a location in accordance with instructions of the Contracting Officer.

3.1.3 Fire Alarm Panels and Transmitters

Retain fire alarm panels and transmitters and provide to the KO.

3.1.4 Air Conditioning Equipment

Remove air conditioning, refrigeration, and other equipment containing refrigerants without releasing chlorofluorocarbon refrigerants to the atmosphere in accordance with the Clean Air Act Amendment of 1990.

3.1.5 Items With Unique/Regulated Disposal Requirements

Remove and dispose of items with unique or regulated disposal requirements in the manner dictated by law or in the most environmentally responsible manner.

3.2 CONCURRENT EARTH-MOVING OPERATIONS

Do not begin excavation, filling, and other earth-moving operations until all demolition in the area has been completed and debris removed. Fill holes, open basements and other hazardous openings.

3.3 DISPOSITION OF MATERIAL

3.3.1 Title to Materials

Except for salvaged items specified in related Sections, and for materials or equipment scheduled for salvage, all materials and equipment removed and not reused or salvaged, become the property of the Contractor and must be removed from Government property. Materials approved for storage by the Contracting Officer must be removed before completion of the contract. Title to materials resulting from demolition and deconstruction, and materials and equipment to be removed, is vested in the Contractor upon approval by the Contracting Officer. The Government will not be responsible for the condition or loss of, or damage to, such property after contract award. Showing for sale or selling materials and equipment on site is prohibited.

3.3.2 Reuse of Materials and Equipment

Remove and store materials and equipment listed in the Demolition Plan to be reused or relocated to prevent damage, and reinstall as the work progresses. Coordinate the re-use of materials and equipment with the re-use requirements in accordance with Section 01 74 19 CONSTRUCTION WASTE MANAGEMENT AND DISPOSAL. Capture re-use of materials in the diversion calculations for the project.

3.3.3 Salvaged Materials and Equipment

Remove materials and equipment that are listed in the Demolition Plan to be removed by the Contractor and that are to remain the property of the Government, and deliver to a storage site.

- a. Salvage items and materials, as directed.
- b. Store all materials salvaged for the Contractor as approved by the Contracting Officer and remove from Government property before completion of the contract. Coordinate the salvaged materials with tracking requirements in accordance with Section 01 74 19 CONSTRUCTION WASTE MANAGEMENT AND DISPOSAL. Capture salvaged materials in the diversion calculations for the project.
- c. Remove salvaged items to remain the property of the Government in a manner to prevent damage, and packed or crated to protect the items from damage while in storage or during shipment. Items damaged during removal or storage must be repaired or replaced to match existing items. Properly identify the contents of containers.

3.3.4 Disposal of Ozone Depleting Substance (ODS)

Class I and Class II ODS are defined in Section, 602(a) and (b), of The Clean Air Act. Prevent discharge of Class I and Class II ODS to the atmosphere. Place recovered ODS in cylinders meeting AHRI Guideline K suitable for the type ODS (filled to no more than 80 percent capacity) and provide appropriate labeling. Remove recovered ODS from Government property and dispose of in accordance with 40 CFR 82. Dispose products, equipment and appliances containing ODS in a sealed, self-contained system (e.g. residential refrigerators and window air conditioners) in accordance with 40 CFR 82. Submit Receipts or bills of lading, as specified. Submit a shipping receipt or bill of lading for all containers of ozone depleting substance (ODS) shipped to the Defense Depot, Richmond, Virginia.

3.3.4.1 Special Instructions

No more than one type of ODS is permitted in each container. Apply a warning/hazardous label to the containers in accordance with Department of Transportation regulations. Provide a tag with the following information on all cylinders including but not limited to fire extinguishers, spheres, or canisters containing an ODS:

- a. Activity name and unit identification code
- b. Activity point of contact and phone number
- c. Type of ODS and pounds of ODS contained

d. Date of shipment

e. National stock number (for information, call (804) 279-4525).

3.3.5 Transportation Guidance

Ship all ODS containers in accordance with MIL-STD-129, DLA 4145.25 (also referenced one of the following: Army Regulation 700-68, Naval Supply Instruction 4440.128C, Marine Corps Order 10330.2C, and Air Force Regulation 67-12), 49 CFR 173.301, and DOD 4000.25-1-M.

3.4 CLEANUP

Remove debris and rubbish from project site and similar excavations. Remove and transport the debris in a manner that prevents spillage on streets or adjacent areas. Apply local regulations regarding hauling and disposal.

3.5 DISPOSAL OF REMOVED MATERIALS

3.5.1 Regulation of Removed Materials

Dispose of debris, rubbish, scrap, and other nonsalvageable materials resulting from removal operations with all applicable federal, state and local regulations as contractually specified in the Waste Management Plan. Storage of removed materials on the project site is prohibited.

3.5.2 Burning on Government Property

Burning of materials removed from demolished and deconstructed structures will not be permitted on Government property.

3.5.3 Removal to Spoil Areas on Government Property

Transport noncombustible materials removed from demolition and deconstruction structures to designated spoil areas on Government property.

3.5.4 Removal from Government Property

Transport waste materials removed from demolished and deconstructed structures, except waste soil, from Government property for legal disposal. Dispose of waste soil per Section 01 57 19 TEMPORARY ENVIRONMENTAL CONTROLS.

3.6 REUSE OF SALVAGED ITEMS

Recondition salvaged materials and equipment designated for reuse before installation. Replace items damaged during removal and salvage operations or restore them as necessary to usable condition.

-- End of Section --