



ROOFING PROJECTS

Roofing Systems

Current Conditions

- Past Life Expectancy \ Storm Related Issues
- Requires constant maintenance and related repair
- Deteriorated roofing systems lead to :
 - Increased decking and substrate damage
 - Damaged interior finishes and equipment
 - Potential safety related issues
 - Inherent mold growth and other indoor air quality issues.

Roofing Projects

Goals

- Replace Damaged and Failing Roof Systems
- New Technology
- Provide a safe environment that protects occupants as well contents.
- Uniformity throughout the United States
- Staff and Inmate Training

Roofing Systems

Training

- Projects to utilize inmate labor, where appropriate.
- Inmate work crews would be screened by BOP to ensure compatibility with this program.
- Staff Supervision will be provided at all times.
- Contractor will be required to train facility staff as well as inmate work crews to:
 - Properly identify problem areas.
 - Remove and properly handle construction debris.
 - Preparing the existing deck and substrate to receive new systems.
 - Installation of new systems and required flashing.
 - Proper maintenance procedures to maintain longevity of the new system
- Provide a knowledgeable experienced "Factory" certified work force.

Roofing Systems

Project Implementation

- 31 Roofing projects will be funded and issued for bid proposal over the next 4 fiscal years.
- These projects are estimated at a total cost of approximately \$61.2 m.
- Projects will be issued for bid by groups, based on type of work required and geographic locations.
- Projects to utilize inmate labor, where appropriate.
- Fiscal Responsibility to ensure "Best Value" to the Government.

Projects

South Central Region
FCI Bastrop



Projects

South Central Region FCI Bastrop

- FCI Bastrop was constructed in 1979 consists of 393,348 s.f. under roof and occupies 175 acres.
- Existing TPO on Housing Units (4) and asphalt built-up roofs over other areas are past life cycle.
- Housing Units – approx. 40,000 s.f.
 - Remove existing TPO roof system and repair damaged Decking.
 - Install new TPO roof system with insulation, parapet coping/cap and roof drain bodies
- Remaining Roof Area – approx. 58,000 s.f.
 - Thoroughly clean the existing asphalt built-up roof
 - Overlay new TPO roof system over existing
 - Install new drain bodies, parapet coping and caps

Projects

South Central Region
FMC Carswell



Projects

South Central Region FMC Carswell

- FMC Carswell was constructed in 1995, comprised of 20 buildings with 171,185 s.f. under roof.
- Existing roofing systems of various types installed and are past life cycle and beyond repair.
- Roof leaks have caused some damage to sections of the metal decking and associated supports.
- Deck types vary from concrete (approx. 63,000 s.f.) to metal (approx. 40,000 s.f.)
- Leaks have caused damage to interior finishes and suspected mold is present.
- New Work will consist of
 - Remove all damaged roof system (approx. 103,000 s.f.) and repair all damaged decking/supports
 - Install new TPO roof system to include insulation, roof drain bodies, parapet coping/cap and flashing.
 - Perform complete mold remediation in affected areas.
 - Repair damaged interior finishes.

Projects

South Central Region
MDC Houston



Projects

South Central Region MDC Houston

- MDC Houston was constructed in 1998 and consist of 300,000 s.f. and 11 floors.
- Existing asphalt built-up roof is past life cycle and despite regular maintenance continues to deteriorate.
- Evaluate existing roof area (approx. 30,000 s.f.) and repair damaged areas.
- Install new TPO roof system overlay with new drain bodies, parapet coping/cap and flashing.
- Possible difficulties:
 - Working in congested street conditions.
 - Roof areas on multiple floors and locations.
 - Handling of material and construction debris.

Projects

South Central Region
FTC Oklahoma City



Projects

Western Region FTC Oklahoma City

- FTC Oklahoma City was constructed in 1995, consists of 5 buildings with approximately 585,000
- The main FTC building consists of 5 floors and approximately 100,000 s.f. of roof area. This area has a modified bitumen roof system that has exceeded its life cycle and multiple areas are leaking, causing roof deck and interior finish damage.
- Remove existing roof system and repair damaged decking and supports.
- Install new TPO roof with insulation, drain bodies, parapet coping/cap and flashing.
- Possible difficulties:
 - Working in close vicinity to an active airport operation
 - Handling of material and construction debris.

Projects

South Central Region
FCI Three Rivers



Projects

South Central Region FCI Three Rivers

- FCI Three Rivers was constructed in 1990 and occupies approximately 300 acres.
- Existing roofs are approx. 110,000 s.f. and constructed of standing seam metal with skylights.
- Metal roofs are leaking throughout and have caused damaged to existing wood structure and decking.
- Replace all roofs with new standing seam metal roofing system to include new decking and insulation.
- Remove skylights and reframe the openings to allow proper tie-in to existing slopes.
- No suspected environmental issues are expected.

Projects

Southeast Region

FCC Yazoo City – FCI 1



Projects

Southeast Region FCC Yazoo – FCI 1

- FCC Yazoo was constructed in 1997, consists of 4 facilities and occupies approx. 1000 acres.
- FCI 1 has approximately 43,500 s.f. of asphalt built-up roofing that is past life cycle.
- Areas affected – Special Housing Unit, GP Housing Unit (1), Administrative, Medical, Recreation Buildings
- Remove existing roofing system and repair damaged metal decking
- Install new TPO roofing system with insulation, roof drain bodies, parapet coping/cap and flashing.

Projects

Southeast Region

FDC Miami



Projects

Southeast Region FDC Miami

- FDC Miami was constructed in 1999 consists of 550,965 s.f. and 13 floor levels
- Existing 44,000 s.f. asphalt built-up roof located on the 4th and 13th floor levels are is past life cycle and leaking.
- Remove existing roof system and repair metal decking and supports.
- Install new TPO roof system with new insulation drain bodies, parapet coping/cap and flashing.
- Possible difficulties:
 - Working in congested street conditions.
 - Roof areas on multiple floors and locations.
 - Handling of material and construction debris.

Projects

Northeast Region
FMC Devens



Projects

Northeast Region FMC Devens

- FMC Devens was originally constructed in 1960 and converted to BOP Facility in 1998
- Consists of 22 buildings and situated on approximately 222 acres
- Existing asphalt built-up roof approximately 120,000 s.f. is severely deteriorated and past life cycle.
- Remove existing roof system and repair existing metal roof deck and supports
- Install new TPO roof system with new insulation drain bodies, parapet coping/cap and flashing.
- No asbestos or environmental concerns are expected.

Projects

Northeast Region
FCI Lewisburg



Projects

Northeast Region FCI Lewisburg

- FCI Lewisburg was constructed in 1932, consists 1,158,514 s.f. and situated on 950 acres.
- Existing asphalt built-up roof on the UNICOR Factory (approximately 105,000) s.f. is severely deteriorated and past life cycle.
- Remove existing roof system and repair existing metal roof deck and supports
- Install new TPO roof system with new insulation drain bodies, parapet coping/cap and flashing.
- No asbestos or environmental concerns are expected.
- Historical Preservation Concerns.

Projects

Northeast Region
FCI Fort Dix



Projects

Northeast Region FCI Fort Dix

- FCI DIX was constructed in 1992 consists of 1,228,428 s.f. and occupies 210 acres.
- Existing roofing system is EPDM with gravel ballast and is past life cycle.
- Remove existing roof system (approx. 225,000 s.f.) and repair existing metal roof deck and supports
- Install new TPO roof system with new insulation drain bodies, parapet coping/cap and flashing.
- New gutters, scuppers and downspout.
- Mold Remediation Expected
- Repair/Replace damaged interior ceilings and finished.
- Minor brick repair and tuck pointing.

Projects

Mid-Atlantic Region
FCI Memphis



Projects

Mid-Atlantic Region FCI Memphis

- FCI Memphis was constructed in 1977, consists 24 buildings totaling 304,000 s.f. and occupies 111 acres
- Existing roof is a mixture of TPO and EPDM roofing systems and are severely deteriorated.
- Remove existing roof systems (approx. 245,000 s.f.) and repair existing metal roof deck and supports
- Install new TPO roof system with new insulation, drain bodies, parapet coping/cap and flashing.

Projects

Mid-Atlantic Region
USP Lee



Projects

Mid-Atlantic Region USP Lee

- USP Lee was constructed in 2001, consists of 675,647 s.f. and occupies 265 acres.
- Existing EPDM roofing systems are past life cycle and severely deteriorated.
- Remove existing roof systems (approx. 128,000 s.f.) and repair existing metal roof deck and supports
- Install new TPO roof system with new insulation, drain bodies, parapet coping/cap and flashing.
- Repair existing lightning protection system to eliminate on-going ground fault issues.

Projects

North Central Region
FCI Waseca



Projects

North Central Region FCI Waseca

- FCI Waseca was originally an Agricultural College for the University of Minnesota and converted to a BOP Facility in 1996.
- Consists of 675,647 s.f. and occupies 265 acres.
- Existing gravel ballast EPDM roofing systems are past life cycle and severely deteriorated.
- Concrete decking is present however roofs have significant ponding throughout.
- Remove existing roof systems on Special Housing Unit, Medical, Food Service and Recreation Buildings (approx. 250,000 s.f.).
- Install new TPO roof system with new insulation, drain bodies, parapet coping/cap and flashing.