



STATEMENT OF WORK

**REMOVE UNDERGROUND STORAGE
TANK TK 101 AT LF E10**

PROJECT No: GHLN 26-7127

Prepared By:
90 CES/CEM
Missile Engineering
F.E. Warren Air Force Base, Wyoming

Carla J. Mlinar
Project Manager

February 17, 2026

TABLE OF CONTENTS

OVERVIEW	3
SCOPE OF WORK.....	3
SECURITY REQUIREMENTS	4
PRINCIPLE FEATURES OF WORK PER CSI DIVISION.....	8
CSI 01 – General Requirements	8
CSI 02 – Existing Conditions	13
CSI 02 65 00 – Underground Storage Tank Removal	14
CSI 26 00 00 – Electrical.....	14
CSI 28 00 00 – Electrical Safety and Security	14
CSI 03 – Concrete.....	15
CSI 23 11 - Facility Fuel Piping.....	15
CSI 31 23 00 – Earthwork – Excavation and Fill.....	16
CSI 31 38 00 – Proof Rolling	17
CSI 33 56 10 – Utilities – Factory Fabricated Fuel Storage Tanks	17
ATTACHMENT 1	19
ATTACHMENT 2	20
Chart 6FtDW – 4Kgal.pdf_safe – Calibration Chart	20
APPENDIX 1 – REFERENCES	21
***NOTE: Any Specifications and/or Regulations must be in accordance with the most current).....	21

Statement of Work
Remove Underground Storage Tank TK101 at LF E10
Project No: GHLN 26-7127
February 17, 2026

OVERVIEW

1. This project includes the removal and disposal of an existing 4,000-gallon (diameter of 8') double-wall fiberglass underground diesel fuel storage tank, spill bucket, and associated components at the E10 Launch Facility (LF).
 - a. The existing tank will not be replaced.
 - i. None of the units mentioned above are to be replaced after removal.
 - b. Unit's spill bucket, Veeder-Root tube (and power-off), fill tube, vent, and any other associated components will need to be removed.
 - c. Removal and disposal of any sludge remaining in the UST and the UST's spill bucket.
 - d. Lines from the UST to the LSB will be capped no further than one foot (1') from the LSB exterior wall.
 - e. Fill void area left from the UST removed.
2. The Period of Performance (PoP) for this project shall be **90 calendar days**.
3. The work shall be performed at LF E-10 located in Laramie County Wyoming. The LF is under the control of F.E. Warren Air Force Base, Wyoming. These specifications describe the requirements for the work under this contract. The distances from F.E. Warren AFB is indicated below.

SITE	COUNTY	STATE	DISTANCE (MILES)
E-10	Laramie	WY	53

SCOPE OF WORK

1. The Contractor shall provide all labor, materials, equipment, and transportation necessary for the removal and disposal of an existing 4,000-gallon double-wall underground diesel fuel storage tank, the UST's spill bucket, Veeder-Root tubing (and power-off), fill tube, vent, drop tube, and associated components to include filling the void after the UST has been removed as specified in this *Statement of Work* in strict compliance with the specifications, applicable drawings, attachments, and the *Terms and Conditions* of the Contract as well as all applicable and current building codes, standards, and practices in the industry.
2. The Contractor is responsible for supplying and installing a turnkey, fully functional, tested, and operational product meeting the performance requirements outlined by these specifications. The Contractor will provide any special permits or licenses that may be required, obtain adequate insurance, and coordinate all inspections required by applicable laws and regulations, except as otherwise specified herein.
3. The Contractor will provide adequate supervision to ensure the project proceeds smoothly, efficiently, and follows direction outlined in this SOW.
4. The Contractor will keep a copy of the most current *Statement of Work* and drawings on the jobsite.
5. Accomplish all work in accordance with the Contract specifications.
6. The Project Coordinator shall be the Contracting Officer (CO) from the 90 Contracting Squadron, and the Project Manager shall be the 90 Civil Engineer Squadron/Missile Engineering Flight (90 CES/CEM).

7. In the case of the winter season that has direct impact to perform the work outlined in this SOW, the Contractor shall notify the Government they can no longer perform work. 90 CES/CEM will validate that the weather no longer allows work to be performed within the specifications.
 - a. If the reason for stopping work is due to weather impacted material supplies, the Contractor shall provide a letter to support the winter suspension.
 - b. The project will be placed into suspension, and the remaining number of PoP days will be documented.
 - c. When weather conditions become favorable for work, the CO will begin coordinating with the contractor to establish a timeline for their return to work.

When the suspension is lifted, a new completion date will be established based on the remaining PoP days.

SECURITY REQUIREMENTS

1. The Contractor and their personnel, including employees and any subcontractors, shall comply with pertinent Air Force security regulations while working on the project. Special security clearances such as Confidential, Secret, etc., are not required of the Contractor or Contractor representatives for the performance of this project.
2. **Real-ID Compliance Identification:** IAW DodM 5200.08V2_DAFMAN31-101V3_DAFGM 2024-01, Installation Perimeter Access Control.
 - a. Base access will require Real ID-Compliant identification for base access.
 - b. Failure of the vendor to ensure personnel have Real ID-compliant identification will result in denial of base access.
 - c. Levels of Security: Individuals performing work under this contract shall comply with applicable program security requirements. Contractors will support the following levels of security: Unclassified and Unclassified But Sensitive.
3. **Base Access:** The Contractor shall request access onto F.E. Warren AFB through the CO or authorized representative a minimum of three (3) working days prior to needed entry.
 - a. One form of ID, as a legible photocopy or electronically scanned valid driver's license, state photo ID card, or official state/federal photo ID card shall be submitted for each employee requiring base access.
4. **Missile Field Access:** Access to LF is controlled by the U.S. Air Force. All Contractor shall submit the following for each employee to include prime, subcontractor, and deliver/testing services employees.
 - a. One form of ID, as a legible photocopy or electronically scanned valid driver's license, state photo ID card, or official state/federal photo ID card.
5. **Site Entry:**
 - a. To gain entry onto site, Contractor personnel shall be
 - i. Identified by Escort Official.
 - ii. Submit to physical and electronic search of person and materials.
 - iii. Physically escorted on-site by an authorized Escort Official and remain under constant escort surveillance while on site.
 - b. Upon arrival, the Escort Official will identify all Contractor personnel and verify identifications.
6. **Vehicles/Equipment:**
 - a. Contractor vehicles and equipment will be allowed to park inside the security fence to support the work under this contract and shall be searched by Security personnel prior to entry.
 - i. The Contractor shall obtain approval from 90 CES/CEM prior to leaving vehicles and equipment parked overnight.
 - Overnight parking inside the security fence at the LFs will not be allowed.
 - ii. Contractor vehicles and equipment shall be placed so as not to interfere with gates, emergency escape routes, antenna, and other above ground structures.

- b. The access road from the main road to site is controlled by the U.S. Air Force. The area adjacent to the access road is private, federal, state, or county property.
 - i. The Contractor shall obtain approval from 90 CES/CEM prior to parking vehicles and equipment on the access road.
 - Vehicles parked on the access road shall be clear of the perimeter fence or gate by a minimum of twenty-five feet (25’).

7. Contraband:

- a. The Contractor shall ensure contraband items are not brought onto site by Contractor personnel. The following items are considered contraband on LF sites.
 - i. Privately owned firearms to include rifles, shotguns, handguns, air/pellet guns, and sling shots.
 - ii. Privately owned ammunition or unauthorized ammunition.
 - iii. Knives less than four inches in length are permitted.
 - iv. Explosives, except for official use or storage.
 - v. Illegal drugs or controlled substances.
- b. Cellular phones are permitted in certain areas; however, the use of photographic capabilities is never permitted. The Escort Official and/or Security personnel will identify areas where cellular phones are/are not permitted and will confiscate improperly used cellular phones.

8. Anti-Terrorism:

- a. Notifications: If the Contractor (contract employees/subcontractors) identify any suspicious activity, they shall contact the Base Defense Operations Center (BDOC) at 307-773-3501 (on-base)/Missile Security Control (MSC) at 307-773-2701 (off-base) and notify the CO and 90 CES/CEM that they contacted the BDOC and/or MSC.
- b. Training: Contractor employees that require routine physical access to a Federally-controlled facility or military installation shall complete Level I antiterrorism awareness training within thirty (30) calendar days of requiring access and annually thereafter and send a copy of their employees’ training certificate(s) to the CO. Training is located at Joint Knowledge Online (JKO) website: <https://jkodirect.jten.mil/Atlas2/page/login/Login.jsf>

- 9. F.E. Warren AFB Communications:** The majority of work will be at areas where commercial phone service is not available. The following phone numbers are provided for assistance in conducting on-base telephone communications.

OFFICE	NUMBER
Emergency	911
Base Operator	(307) 773-1110
Visitor Control Center (VCC)	(307) 773-3694
Contracting Office	(307) 773-3535
Fire Department Tech Services	(307) 773-5528
Civil Engineer Squadron (CES)	(307) 773-3600
CES Missile Engineering	(307) 773-2438
CES Customer Service	(307) 773-3175
CES Environmental	(307) 773-2594
Missile Wing Safety	(307) 773-1842
Bioenvironmental Engineering	(307) 773-3088

- 10. Interrupted Site Access:** If existing access to the site is to be temporarily blocked, temporary access shall be properly provided by the Contractor. The Contractor shall notify the CO twenty-one (21) calendar days prior to any interruption of access to the site. The date, site(s) affected, length of time, and alternate entry method shall be submitted on a *Site Interruption Plan* for approval.

- 11. Vacating The Work Area:** During exercises, natural disaster, and national emergencies or for security reasons, the Contractor may be required to vacate a work area.

12. Staging/Storing: Materials and equipment not stored at Contractor's facilities shall be stored on approved Air Force property or approved adjacent private or public properties.

a. Staging/Storing on Air Force Property:

- i. The Contractor shall obtain approval from 90 CES/CEM prior to storing on Air Force property. Unkempt, insecure, or unsightly storage shall not be allowed.
 - There is limited facility storage space at the LFs and shall only be allowed on a case-by-case basis.
 - There is no facility storage space at the LFs.
- ii. A storage plan may be required if storage containers are to be left on or near the site, for security considerations.

b. Staging/Storing on Adjacent Properties:

- i. Contractors not storing on Air Force property shall store on adjacent private or public properties within the Limit of Potential Ground Disturbance as shown in Attachment 1.
- ii. The Contractor shall obtain written consent of the landowner or leaseholder.

13. Adjacent, Private, &/or Public Property/Landowners/Leaseholders: Contractor shall obtain written agreements and lien releases with adjacent private and public landowners and leaseholders when operations require use of these properties for storage or access to Air Force property. Landowner Agreements will allow the use of property by Contractor, and the lien releases shall release the Air Force from any damage to private property because of Contractor operations. Where leaseholders are present on the property, the signatures of both landowners and leaseholders are required. Copies of agreements and lien releases shall be supplied to the CO prior to the start of work on each site. The Contractor will not be allowed to start work on a site until agreements are in place.

14. Operational Security (OPSEC): The Contractor shall adhere to the following minimum requirements in support of this requirement:

- a. All contractors, subcontractors, their employees, associates, and consultants who have access to critical information and indicators shall comply with the Air Force-sponsored Operations Security (OPSEC) program.
- b. OPSEC is an information-related capability that preserves friendly essential secrecy by using a process to identify, control, and protect critical information and indicators. If critical information and indicators are disclosed, it could allow adversaries or potential adversaries to identify and exploit friendly vulnerabilities leading to increased risk to mission failure or the loss of life. The desired effect of OPSEC is to influence the adversary's behavior and actions by reducing the adversary's ability to collect and exploit critical information and indicators about friendly activities.
- c. Responsibilities:
 - i. The Contractor shall ensure employees receive OPSEC education that includes an overview of the OPSEC process; the definition of OPSEC; its purpose; what is critical information; the individual's role in protecting critical information; and the general adversary threat to the AF's critical information. Additionally, OPSEC education shall include updated threat information, changes to critical information and indicators, new procedures and/or OPSEC measures implemented, altered, or deleted by the organization.
 - ii. DoD Contractors with OPSEC requirements or those who have access to critical information and indicators shall complete initial and annually-recurring refresher training. Accomplishment of initial OPSEC training shall not exceed ninety (90) calendar days from initial assignment to a contract with OPSEC requirements. Access to mission-critical information will not be allowed until OPSEC education has been completed and documented.
 - iii. OPSEC education is a continuous requirement. The host unit OPSEC coordinator shall track OPSEC training status to include the personnel working on the contract, when each

individual has received the required initial OPSEC training, and when refresher training is due and/or completed.

- iv. The Contractor's personnel shall not discuss government operations in public or over unprotected or unencrypted communications. Controlled unclassified information (CUI) may only be transmitted as directed in this SOW.
- v. The Contractor shall not post to company websites, publications, newsletters, or any other media any images, data, or any other information that reveals sensitive government operations, personnel, equipment, and/or classified or controlled unclassified information. When in doubt, the company press release related to this contract should be coordinated through the COR or CO, as applicable.
- vi. Prior to seeking approval through F.E. Warren AFB Public Affairs, any information to be released outside of official U.S. Government channels, via any media to include electronic communication, shall be approved through an OPSEC review. All personnel shall promptly report OPSEC-related incidents, issues, and concerns to the host-unit OPSEC coordinator.
- vii. The Contractor shall restrict access to those individuals with a valid need-to-know who are actually providing services under the contract. Further dissemination to other contractors, subcontractors, or any other government agencies and private individuals or organizations is prohibited unless authorized in writing.
- viii. Because observation of events, operations, physical changes, etc. may reveal National Security Information, specific restrictions are needed to preclude unintentional release of this information to unauthorized parties. Unauthorized disclosure and transfer of National Security Information is punishable under 18 USC§793. Therefore, the Contract Personnel shall not disclose to unauthorized third parties, post to unofficial sites to include Social Networking sites any images, data/information, or observed events that reveal sensitive government operations, personnel, and equipment, including but not limited to
 - Tactics, techniques, and procedures, production, work schedules, any visible or concealed modifications, upgrades, additions to vessels, aircraft, or weapons or equipment; increases, change, or decrease in work/deployment frequency or government personnel, vehicles, vessel, and/or aircraft movements; specialized equipment orders, deliveries, shipments, etc. Unauthorized disclosures and attempts to solicit this type of information by unauthorized third parties or others not affiliated with this contract shall be reported to the COR or CO, as applicable.
 - Government issued badges, identification shall be removed and/or concealed from plain sight when off base and shall not be left in vehicles or unprotected areas. Badges and passes may not be duplicated, copied, or loaned to others. Lost or stolen identification badges, vehicle passes, etc., will be immediately reported to the COR, CO, and/or installation Security Office.

15. Controlled Unclassified Information (CUI):

- a. Contractors shall follow CUI safeguarding and dissemination controls in accordance with Part 2002 of Title 32 CFR DoDI 5200.48, Controlled Unclassified Information; and DoDI 5200.48_DAFI 16-1403, Controlled Unclassified Information.
 - i. Unlike classified information, an individual or organization generally does not need to demonstrate a need-to-know to access CUI, unless required by a law, regulation, or government-wide policy, but shall have a lawful government purpose for such access.
- b. Marking Requirements: Contractors shall follow CUI marking requirements in accordance with DoDI 5200.48 and DoDI 5200.48_DAFI 16-1403.
- c. Dissemination: Contractors shall follow CUI dissemination requirements in accordance with DoDI 5200.48 and DoDI 5200.48_DAFI 16-1403.

- d. Storage: Contractors shall follow CUI storage requirements in accordance with DoDI 5200.48 and DoDI 5200.48_DAFI 16-1403.
 - i. During work hours, steps shall be taken to minimize the risk of access by unauthorized personnel, such as not reading, discussing, or leaving CUI information unattended where unauthorized personnel are present.
 - ii. After working hours, CUI information will be stored in unlocked containers, desks, or cabinets if the government or government-contract building provides security for continuous monitoring access. If the building security is not provided, the information shall be stored in locked desks, file cabinets, bookcases, locked rooms, or similarly secured areas.
- e. Transmission: Contractors shall follow CUI transmission requirements in accordance with DoDI 5200.48 and DoDI 5200.48_DAFI 16-1403.
 - i. DoD SAFE shall be the primary method of submitting information and documentation.
- f. Disposition: Contractors shall follow CUI disposition requirements in accordance with DoDI 5200.48 and DoDI 5200.48_DAFI 16-1403.
 - i. Record and non-record copies of CUI documents will be disposed of in accordance with Chapter 33 of title 44, U.S.C. and the DoD Components' records management directives. When destroying CUI, including in an electronic form, agencies shall do so in a manner making it unreadable, indecipherable, and irrecoverable. If the law, regulation, or government-wide policy specifies a method of destruction, agencies shall use the method prescribed.
 - ii. Record and non-record copies of CUI documents may be destroyed by means approved for destroying classified information or by any other means making it unreadable, indecipherable, and irrecoverable the original information such as those identified in NIST SP 800-88 and in accordance with Section 2002.14 of Title 32, CFR.
- g. Disclosure: Contractors shall follow CUI disclosure requirements in accordance with DoDI 5200.48 and DoDI 5200.48_DAFI 16-1403.
 - i. Contractors shall follow CUI disclosure requirements in in accordance with DoDI 5200.48 and DoDI 5200.48_DAFI 16-1403.

PRINCIPLE FEATURES OF WORK PER CSI DIVISION

NOTE: Refer to this *Statement of Work*, drawings, and attachments for complete details of work. This scope is a general overview of intended work.

CSI 01 – General Requirements

1. **Project Scheduling:** The Contractor shall submit project schedule to the CO within fifteen (15) working days after award of the Contract.
 - a. The Contractor shall coordinate all work with the CO and 90 CES/CEM to verify that work can be performed as scheduled before traveling to the work site.
 - i. Provide a minimum of ten (10) working days' notice, in writing, before beginning work.
 - ii. Provide a means for contact after normal working hours for notification of emergency changes to the schedule.
 - iii. If work is not coordinated as stated, Air Force personnel may not be available, work may not be permitted, and the Government shall not incur any additional cost as a result.
 - b. Working hours will be between the hours of 7:30 a.m. (start processing on site) and 4:00 p.m. (terminated work off site) excluding Saturdays, Sundays, and Federal Holidays. An Escort Official (i.e. 90 CES/CEM Inspector or other) will be provided during these work hours. Processing onto and off site may require approximately thirty (30) minutes each and shall not be considered a delay time.
 - i. Recognized Federal Holidays include:
 - New Year's Day (January 1).
 - Birthday of Martin Luther King, Jr. (third Monday in January).

- Washington's Birthday (third Monday in February).
 - Memorial Day (last Monday in May).
 - Juneteenth National Independence Day (June 19).
 - Independence Day (July 4).
 - Labor Day (first Monday in September).
 - Columbus Day (second Monday in October).
 - Veterans Day (November 11).
 - Thanksgiving Day (fourth Thursday in November).
 - Christmas Day (December 25).
- c. AF Form 3064 *Contract Progress Schedule* and AF Form 3065 *Contract Progress Report* shall be submitted monthly, as required.
- 2. Submittals:** Prior to starting any work and in accordance with AF Form 66 *Schedule of Material Submittals* (aka "Submittal Register"), submit documentation (e.g., EAL information, plans, agreements, specifications, SDS, etc.) on AF Form 3000 *Material Approval Submittal* to the CO via DoD SAFE in accordance with the requirements of these specifications.
- a. Submittals shall be provided as one (1) searchable electronic copy via DoD SAFE. Submittals shall be marked with the appropriate classification.
 - b. Each Contractor-supplied item shall be submitted for approval and approved by the CO prior to installation. In no case shall materials be incorporated into the work unless prior written approval is obtained from the CO.
 - c. Include outlines, dimensional, assembly and subassembly drawings, parts list and other data required to completely describe each item to be used.
 - d. When more than one model, series or design is illustrated on any one submittal sheet, the item of intended use shall be highlighted and clearly marked with an arrow or asterisk to eliminate confusion as to the product to be approved. Any materials and/or methods not in strict conformance with the requirements of this contract shall also be submitted for review and approval.
 - e. All submittal information shall be provided by the Contractor, not less than fifteen (15) working days prior to any site work or by the date determined by the CO at the pre-construction meeting. A signed and dated copy of the submittal shall be returned to the Contractor after approval or disapproval.
- 3. Shop Drawings:** Shop drawings shall be submitted for all items or components to be fabricated or assembled and requiring detail drawings more than, or to complement, the general drawings and details included in the plans.
- a. The plans shall be supplemented by shop drawings as necessary to adequately control the work. Shop drawings may consist of drawings, diagrams, Safety Data Sheets (SDS), illustrations, schedules, calculations, or other data prepared by the Contractor, subcontractor, manufacturer, supplier, or distributor which illustrate specific portions of the work to be fabricated or installed in accordance with the plan details and specifications.
 - b. Any work done prior to approval of shop drawings shall be done at the Contractor's own risk.
- 4. Product Data:** Manufacturer's product data for all commercial products, components, devices, or distinct units shall be submitted by the Contractor for review prior to installation in the work.
- a. Product data includes catalog sheets, brochures, SDS, diagrams, schematics, schedules, performance starts, illustrations and any other standard descriptive data.
 - b. All product data submitted shall be clearly marked to identify pertinent materials, products, or models to be incorporated in the work.
 - i. All dimensions, clearances, tolerances, performance characteristics, specifications, wiring diagrams, and other such pieces of information shall be clearly marked or highlighted.
- 5. Certificates of Compliance:** A Manufacturer's certificate of compliance for all materials to be incorporated in the work shall be submitted to the CO prior to execution of the work.

- a. Certificates shall certify compliance with project specifications, applicable reference standards or specifications, and test data requirements as required.
 - b. Certificates shall further contain the name, title and signature of the individual certifying the product, and the name and address of the corporation or business supplying the product and certificate.
- 6. Test Results:** The Contractor shall complete testing in accordance with all project specifications, applicable local/state/federal rules or regulations, and industry standards or manufacturers' recommendations and submit results to the CO.
- 7. Quality Control:** The Contractor shall provide and maintain an effective quality control program.
 - a. The Contractor shall comply with applicable references, standards, specifications, and manufacturers' recommendations, listed in Appendix 1.
 - i. The Contractor shall request clarification from the CO if the manufacturers' instructions conflict with contract documents before proceeding.
- 8. Utility Services:** The Contractor shall provide all utilities, to include but not limited to portable generators, water (drinking and construction), and phone services for Contractor personnel, as needed.
 - a. When working at the LFs, limited utilities are available.
 - i. At the LFs, portable latrines are stationed and will be available for use by Contractor personnel.
 - b. The Contractor shall provide site facilities for lunch and break areas, as needed.
- 9. Equipment:** Provide all equipment necessary to accomplish the contract work. Non-standard/non-hand-held equipment must be listed on the *Schedule of Material Submittal Form*.
 - a. Power equipment shall be equipped with safety, noise limiting, and fume control devices. The equipment shall be in a safe and efficient operating condition.
 - b. Only experienced operators shall be permitted to operate the equipment.
 - c. Plug-in power tools are preferred as wireless power tools are only permitted in certain areas.
 - d. Cameras are permitted in certain areas if approved by 90 CES/CEM.
- 10. Excavation:** No excavation, regardless of depth, will begin without first obtaining an approved AF Form 103 *Base Civil Engineering Work Clearance Request* (aka "Dig Permit"). The Contractor shall submit Dig Permit request(s) to 90 CES Customer Service (307-773-3175) in Building 322 thirty (30) calendar days prior to the planned excavation date. Permits shall be renewed by the Contractor every fourteen (14) calendar days.
 - a. The Contractor shall provide the following to the Customer Service when planning an excavation:
 - i. A drawing showing the area to be excavated.
 - 90 CES/CEM can provide an electronic site map to the Contractor for markup.
 - ii. The purpose of the excavation.
 - iii. Name, phone number, and organization of the Contractor's point of contact.
 - b. The Contractor shall review the permit, keep signed copy on site and shall be responsible for maintaining utility markings during excavation.
 - c. The Contractor shall notify 90 CES/CEM prior to any excavation.
 - i. If ground water or landfill debris is encountered, the Contractor shall suspend excavation and notify 90 CES/CEM.
 - d. Exploratory excavation by hand or vacuum is required within five (5) feet of either side of marked underground utilities.
 - i. Hand digging or vacuum excavation is required when crossing underground utilities.
 - ii. If excavation is required parallel and within five (5) feet of an existing utility, exploratory excavation shall be performed by hand or vacuum until the location of the utilities is physically confirmed.
 - iii. After the location of the utility is physically confirmed, excavation may be performed by machine.
 - e. Exploratory potholes in roadway areas shall be restored using a flowable fill mixture.

- i. In other areas, native backfill material shall be used. The surface condition shall be restored to the pre-existing state.
 - f. Items encountered and damaged within five (5) feet on either side of a marked line or around a marked items shall be repaired by the Contractor.
 - i. Items encountered and damaged outside of five (5) feet on either side of a marked line or around a marked point shall be repaired by the Air Force.
 - ii. In either case, the Contractor shall notify 90 CES/CEM immediately if any damage occurs.
- 11. Burning/Welding:** The Contractor shall obtain an AF Form 592 *Hot Work Permit* (aka “*Burn Permit*”), at least three (3) working days prior to work.
- a. Coordinate with the onsite Escort Official or contact 90 CES/CEM at (307) 773-2438 for requirements, initiation, and completion of permit.
 - b. Contractor shall have the completed permit control number prior to any burning/welding operations.
- 12. Environmental Compliance:** The Contractor is responsible for complying with the State’s or States’ environmental quality regulations, and the Environmental Protection Agency (EPA) Region 7 or 8 Office in Denver for any National Pollutant Discharge Elimination System (NPDES) Construction General Permits.
- a. If a permit is not required by the affected State or Federal agency with jurisdiction on federal sites, the Contractor shall provide written documentation referencing reason for waiver.
- 13. Green Procurement Program (GPP):** In performance of this contract, contractors shall use EPA designated recycled content products, Information Technology (IT) Energy Star products/appliances, Federal Energy Management Program (FEMP) Designated Energy Efficient Low Stand By Power products/appliances, U.S. Department of Agriculture (USDA) Bio based/Bio preferred products, Environmentally preferable products, Electronic Product Environmental Assessment Tool (EPEAT) registered products, Water Sense or other water efficient products, non- or Low Ozone depleting substances under the Significant New Alternatives Policy (SNAP), non or Low toxic or hazardous constituents (e.g. non-VOC paint) and any other environmentally sustainable product/method, to the greatest extent possible.
- 14. Hazardous Materials:** The Contractor shall coordinate all hazardous materials (HAZMAT), to include each compound or chemical intended to be utilized on the site, with 90 CES Environmental (307-773-2594) for review and approval prior to delivery and use on the site.
- a. Hazardous material is defined in Federal Standard, FED/STD-313F (Tables I and II). The definition of materials presenting a health hazard or physical hazard is found in 29 CFR 1910.
 - b. The HAZMAT approval documentation shall be maintained on the site and all workers shall familiarize themselves with their contents.
 - c. The Contractor shall be responsible for establishing a system, which tracks the procurement, delivery to site, installation, and disposal of all hazardous materials including proper disposal documents.
 - d. The Contractor shall be held responsible for proper cleanup and disposal of any hazardous or toxic materials spilled while completing the work in this contract. All cleanups shall be accomplished in accordance with applicable local, state, and federal regulations at no cost to the Government.
 - e. No ozone depleting substances shall be used while completing the work in this contract.
 - i. This includes the exterior/interior of adjacent buildings and parking lot/access road.
- 15. Safety:** The Contractor is solely responsible for all safety on the project including, but not limited to traffic control, trenching, confined space entry, equipment and materials storage, and compliance by all employees with Base Regulations.
- a. Particular care shall be exercised in connection with the operation of vehicles and other equipment on the site.
 - b. Project safety shall be coordinated with the Air Force prior to commencing service.

- c. The Contractor shall notify the CO of all modifications to the Safety Plan.
- d. Contractor shall comply with the rules, regulations, standards, and requirements of the Department of Defense (DoD) AFI 32-7002, *Environmental Compliance and Pollution Prevention*, Section 1.3 for Statutes and Regulations (<http://www.e-publishing.af.mil>), EPA 40 CFR Subchapter I, Part 260-268 and FED-STD-313C, Tables I and II and 20 CFR 1910, the Occupational Safety and Health Administration (OSHA www.osha.gov), and other applicable local, state, and federal requirements regarding disturbing or removing hazardous materials.
- e. The federal government is not exempt from compliance with environmental and labor regulations.
- f. The Contractor shall notify the CO and 90 CES/CEM of any emergency situation(s).
- g. The Contractor shall educate each employee to ensure clear understanding of the following:
 - i. A review of hazards inherent in the work environment and the precautions required to reduce the hazard.
 - ii. The Contractor shall always maintain a complete first aid kit.
 - Location of first aid and other emergency facilities shall be identified.
 - iii. Detailed description of what to do in case of injury, fire, or identification of a safety hazard.
 - iv. Review of daily cleanup procedures, including location and review of company safety rules (either posted or handout).
 - v. The Contractor shall provide all personal protective equipment (PPE) including, but not limited to, ear plugs, goggles, face shields, gloves, safety shoes, and hard-hats. Complete instructions on where and how to use all PPE shall be given by the Contractor.
 - vi. All personnel shall wear PPE when required by the Contractor or by 90 CES/CEM.
 - vii. Hospitals near various sites are noted below for emergency purposes.

Cheyenne Regional Medical Center	Regional West Medical Center	Sterling Regional Medical Center
214 23 rd St Cheyenne, WY 82001 307-634-2273	4021 Avenue B Scottsbluff, NE 69361 308-635-3711	615 Fairhurst St Sterling, CO 80751 970-522-0122

16. Site Conditions: Daily, or more often as necessary, clean all work areas of debris as well as Contractor tools, equipment, and other materials.

- a. This includes the exterior/interior of adjacent buildings and parking lot/access road.
- b. The work site shall be returned to a like condition in which it was found prior to start of work or in better condition than commencement of work to the satisfaction of the CO and 90 CES/CEM.
- c. Damage to Air Force property caused by Contractor vehicles, operations, equipment, or personnel shall be repaired at the Contractor's expense with no additional cost to the Government. Skilled craftsmen in the trade shall repair such damage to the satisfaction of the CO and 90 CES/CEM.
 - i. Any suspected damage to Air Force property shall be documented and submitted to CO with a detailed description of the type and location of damage within seventy-two (72) hours of damage.

17. Request for Information (RFI): The Contractor shall submit RFIs to the CO via a *Request for Information* form prior to any work proceeding.

- a. The RFI shall include whether the information or solution requested will be an increase, decrease, or no change in contract cost.
- b. Any work done prior to approval of the RFI shall be done at the Contractor's own risk.

18. Modifications: Any change in site conditions or work encountered outside the scope of this contract shall be presented to the CO.

- a. A contract modification will be issued by the CO *prior* to any work proceeding.
- 19. Red Line Drawings:** The Contractor shall submit post-construction (aka “red-lined”) drawings to the CO prior to project close out.
 - a. Drawings shall include all changes, revisions, discrepancies, or clarifications encountered during construction.
 - b. Drawings shall be complete, showing all dimensions, geometry, locations, connections, and operations of elements.
 - i. The Contractor shall submit the corresponding digital files from electronic drafting software (e.g., AutoCAD or Autodesk), as required.
 - c. Drawings shall be marked with the appropriate classification.
- 20. Warranties:** Thirty (30) calendar days prior to final acceptance of each delivery order, the Contractor shall obtain and submit written warranties for each equipment, product, good, or service supplied under this contract.
 - a. This project has no work or items in need of warranties.

CSI 02 – Existing Conditions

- 1. The Contractor shall perform an inspection encompassing the existing conditions of the tank, the spill bucket, and any of the associated components performed during this contract.
 - a. The Contractor shall verify all quantities, dimensions, and existing site conditions necessary for completion of the project.
 - b. Existing Tank
 - i. The existing 4000-gallon tank is empty of fuel (refer to **CSI 02 65 00** this SOW and project’s Drawings for further information).
 - 1. Residual sludge in the tank will need to be removed and disposed of in accordance with local, state, and federal requirements (refer to **CSI 02 65 00** and **CSI 33 56 10** this SOW).
 - ii. Remove the vent for the existing UST.
 - iii. Remove the emergency alarm system.
 - c. Removal of Existing Tank
 - i. Remove the existing 4000 gallon UST in accordance with local, state, and federal requirements to include this SOW, refer to **CSI 02 65 00**, **CSI 26 00 00**, **CSI 28 00 00**, **CSI 03**, **CSI 23 11**, **CSI 31 23 00**, **CSI 31 38 00**, and **CSI 33 65 10**.
 - d. Existing Slab Under Tank
 - i. The existing tank has a slab under it.
 - ii. The slab is to remain undisturbed.
 - e. Lines from UST to LSB
 - i. Lines.
 - 1. The existing supply lines from the UST to the LSB will be cut and capped no further than one foot (1’) from the LSB exterior wall.
 - 2. The existing return lines and the containment pipes are two inches (2”) and three inches (3”), respectively are to be cut and capped no further no further than one foot (1’) from the LSB exterior wall.
 - 3. After cut and cap lines are completed, remaining lines from cut to the UST are to be removed and disposed of in accordance with **CSI 02 65 00**, **CSI 26 00 00**, **CSI 28 00 00**, **CSI 23 11**, and **CSI 33 65 10**.
 - f. Existing Spill Bucket
 - i. Remove existing spill bucket and the surface slab surrounding concrete mount.
 - 1. The removed spill bucket is not to be disposed of nor stored on Air Force Property.

- ii. Remove existing wires in the conduits in accordance with current NEMA requirements, NEC requirements, local, state, and federal regulations. These wires supply power and signal routing to the existing tank monitors.
 - 1. Existing wires are ¾" – 1" conduits running out to the tank.
 - 2. The removed wiring and conduits are not to be disposed of or stored on Air Force Property.
 - iii. The integral fill tube has an adapter under the spill bucket that transitions from the three inches (3") fill tube to the four inches (4") fill tube inside the spill bucket.
 - 1. The Contractor will take all necessary precautions to ensure not to contaminate any of the surrounding ground by debris falling when removal of tubing and other components of the spill bucket.
 - 2. The removed integral tubing and adapter are not to be disposed of nor stored on Air Force Property.
 - iv. All removed items are to be disposed of in accordance with current local, state, and federal requirements.
 - g. Existing Veeder-Root
 - i. Existing Veeder-Root receptacle in the Launch Support Building will be disabled.
 - h. Existing Slope and Erosion
 - i. UST void area is to be filled with clean fill material and compacted (refer to **CSI 31 23 00** this SOW and project's Drawings for further information).

CSI 02 65 00 – Underground Storage Tank Removal

- 1. Specification covers requirements for removal and disposal of underground, nonhardened tanks, and piping used to store petroleum products, waste oil or hazardous wastes in accordance with current local, state, and federal Regulations.
- 2. The Contractor shall maintain communication with the 90 CES/CEI Environmental Program Manager, and the 90 CES/CEM Inspector(s) throughout the duration of the project.
 - a. Notifications
 - i. The Contractor is responsible to submit all pre-notifications and post-notifications in accordance with current local, state, and federal requirements prior to commencement of work to remove & dispose of existing tank.
 - These notifications shall also be submitted to both the 90 CES/CEI Fuel Storage Tank Program Manager and to the 90 CES/CEM Chief Construction Chief.
 - b. Removal & Disposal
 - i. The Contractor must coordinate with each required authority for removal & disposal of any remaining contents within the tank and comply with current local, state, and federal standards for testing, assessing, and reporting requirements.
 - ii. Removal of the existing tank must comply with current local, state, and federal requirements.

CSI 26 00 00 – Electrical

- 1. Specification covers requirements for electrical operations.
- 2. The Contractor shall conform to current requirements for power systems in accordance with current National Fire Protection Association (NFPA) 70, National Electrical Code (NEC), and International Electrical Code (ICC) including any local, state, and federal regulations affected by electrical operations.

CSI 28 00 00 – Electrical Safety and Security

- 1. Specification covers requirements for electrical safety and security when conducting work with/around/by electrical operations.
- 2. Existing spill bucket.

- a. Existing wires in the conduits supply power and signal routing to the existing tank monitors. This system consists of conduits and the spill bucket. Each are to be appropriately disposed of after removal complying with local, state, and federal regulations.
 - i. Current conditions.
 - 1. There is a 3-way connection in the existing conduit.
 - 2. Wires are #18 AWG stranded Belden 300 V shield.
 - ii. The AC power to the Veeder-Root is to be disconnected.
- b. Existing conduits are approximately, four (4) different runs of thirty feet (30') wire span over 120 feet.
 - 1. Two (2) wires are for the tank level monitor.
 - 2. Two (2) wires are connected to the interstitial monitor to the spill bucket.
 - ii. There is a six foot (6') loop for each wire at the panel and at the sensor.
- c. In the Mechanical Room, the interstitial liquid sensor is hooked up to the Veeder-Root panel located. Power is to be disconnected.

CSI 03 – Concrete

- 1. Specification covers requirements for removal and disposal of existing spill bucket, surface slab, and associated components in accordance with current local, state, and federal regulations.
- 2. The Contractor shall maintain communication with the 90 CES/CEI Environmental Program Manager, and the 90 CES/CEM Inspector(s) throughout the duration of the project.
 - a. Notifications
 - i. The Contractor is responsible to submit all pre-notifications and post-notifications in accordance with current local, state, and federal requirements prior to commencement of work to remove & dispose of existing tank. These notifications shall also be submitted to both the 90 CES/CEI Fuel Storage Tank Program Manager and to the 90 CES/CEM Chief Construction Chief.
 - b. Removal & Disposal
 - i. Existing Spill Bucket & Remaining sludge in Tank.
 - The Contractor must coordinate with each required authority for removal & disposal of any remaining contents within the spill bucket and any components in accordance with current Federal and State standards for testing, assessing, and reporting requirements.
 - ii. Concrete
 - Remove and dispose of concrete in compliance with current local, state, and federal requirements.
 - iii. Tank
 - Remove existing tank in compliance with current local, state, and federal requirements.
 - iv. Any items listed under **CSI 03** removed becomes the property of the Contractor and is not allowed to be stored on any Air Force property.

CSI 23 11 - Facility Fuel Piping

- 1. Specification covers requirements for furnishing all equipment, materials, labor, tools, and techniques for equipment associated with the installation of a spill bucket.
- 2. Existing Spill bucket is an existing five-gallon (5), double walled OPW.
 - Top edge is approximately three inches (3") above grade elevation (refer to project's Drawings).
- 3. Any items listed removed under **CSI 03** and **CSI 23 11** becomes the property of the Contractor and is not allowed to be stored on any Air Force property.
- 4. Dispose of piping in accordance with local, state, and federal requirements.

CSI 31 23 00 – Earthwork – Excavation and Fill

1. Specification covers requirements for furnishing all equipment, materials, labor, tools, and techniques for earthwork conducted pre/during/post construction.
2. Material
 - a. Remove unsuitable material from the Site in accordance with the Specifications.
 - b. Stockpile suitable material in accordance with the Specifications is to be used as fill for this contract.
 - i. Ensure the stockpile remains free of foreign material and vegetation.
 - c. Materials that are incompatible shall be removed from the Site.
 - i. The Contractor shall be responsible for all material removed from the Site and shall make all necessary arrangements for the proper disposal of the material, including the payment of any applicable fees or permits.
 - d. Materials that are compatible with the specified new materials shall be stored on the Site in an area approved for short term stockpiling during the removal process.
 - i. The stored materials shall be clean and free of excessive fines, organics, frozen, or any other deleterious material in accordance with this contract.
 - ii. Unused stored materials shall be removed promptly from the Site before completion of the construction activities.
 - iii. The Contractor shall be responsible for all material removed from the Site and shall make all necessary arrangements for the proper disposal of the material, including the payment of any applicable fees or permits.
3. Excavation
 - a. Excavate material in accordance with Specifications and drawings.
 - b. Remove unsuitable material from the Site in accordance with the Specifications of this contract.
 - c. Stockpile suitable material in accordance with the Specifications of this contract.
 - i. Ensure the stockpile remains free of foreign materials and vegetation.
 - d. The wasting of suitable backfill material, removed as part of the Site Excavation, shall not be permitted where conditions exist for this material's reuse in the construction activities at the Site.
 - e. The contractor shall be responsible for supplying equivalent imported fill material to offset any wasted suitable fill.
 - i. Unit line items for excavation shall be based on in-place volume.
4. Excavate to neat lines as required to perform the work.
 - a. The Contractor shall provide and install shoring in accordance with local, state, and federal requirements to include applicable requirements of Occupational Safety and Health Administration (OSHA) Standards specifically OSHA Subpart 1910 for General Industry and OSHA Subpart 1926 for Construction.
5. During construction, perform excavation and fill in a manner and sequence that will always provide proper drainage.
6. Fill
 - a. Fill material shall be in accordance with the Specifications and Drawings.
 - b. Suitable excavated materials may be used as fill material in all locations.
 - c. Imported or existing filling material shall be well graded granular material free of excessive fines, silts, clays, organics, frozen, or other deleterious materials like Wyoming Department of Transportation Type L or W Gradation.

Sieve Size	Percent Passing
1 – ½	100
1	90-100
½	60-85
No. 4	35-65
No. 8	25-53
No. 30	10-30
No. 200	3-15

- d. Place and mechanically compact fill material in six inch (6”) maximum lifts unless otherwise noted in the Specifications.
 - i. The compaction densities and compaction effort evaluations shall be in accordance with **CSI 31 38 00** unless otherwise noted in the Specifications.
- e. Use a sheep’s foot or other mechanical means to reach the best compactive efforts.
 - i. Exposed course shall be free of surface water (wet conditions resulting from rainfall).

CSI 31 38 00 – Proof Rolling

1. Specification provides a method for visual evaluation of testing procedures for compaction efforts of in-place soils, soil-aggregate, and base aggregates – Proof Rolling.
2. Procedure
 - a. A water truck or construction of material haul vehicle (end dump) shall be loaded to the maximum capacity or legal Gross Vehicle Weight (GVW).
 - i. Tire pressure shall be the maximum rated pressure for the tire/vehicle.
 - ii. The vehicle shall be driven at 2 to 4 miles/hour over the entire compacted surface to be tested.
 - b. Maximum deflection under the test vehicle tire is limited to half inch (1/2”).
 - i. Excessive deflection or pumping of the supporting solid shall indicate test failure.
 - c. Moisture-content of the tested soils shall be maintained at optimum based on visual verification of soils during placement or testing in accordance with the Specifications.
 - i. Proof roll pattern shall allow only one roll over an area to be tested with sufficient time and space to allow for field measurement and recording of deflections.
 - d. Failed areas of layer of soil shall be corrected by additional compaction or mechanical methods to include plowing, disking, and mixing previously removed materials to the area.

CSI 33 56 10 – Utilities – Factory Fabricated Fuel Storage Tanks

1. Specification covers systems using factory-fabricated storage tanks with capacities less than or equal to 200,000L (50,000 gallons).
2. The Contractor shall maintain communication with the 90 CES/CEI Environmental Program Manager, and the 90 CES/CEM Inspector(s) throughout the duration of the project.
3. The Contractor shall follow all compliance requirements in accordance with local, state, and federal requirements.
 - a. Pre-notifications and post-notifications
 - i. The Contractor is responsible to submit all pre-notifications and post-notifications in accordance with current local, state, and federal agencies prior to commencement of work to remove & dispose of existing tank.
 - ii. These notifications shall also be submitted to both the 90 CES/CEI Fuel Storage Tank Program Manager and to the 90 CES/CEM Chief Construction Chief.
 - b. Disposal
 - i. The Contractor must coordinate with each required authority for removal & disposal of any remaining contents within the tank and comply with current local,

- state, and federal regulatory standards for testing, assessing, and reporting requirements.
- ii. Removal of the existing UST must comply with current local, state, and federal requirements.
- c. Reporting
 - i. Reporting requirements must comply with the current local, state, and federal requirements, assessing, and reporting.
 - ii. The Contractor is to maintain a copy or have immediate access to provide documentation per review of all reports at the work site if requested by the 90 CES/CEI Fuel Storage Tank Program Manager or the 90 CES/CEM Chief Construction Chief i.e. soil sampling, disposal, and/or compaction.
 - iii. The Contractor is responsible to supply a copy of any documentation, specifically Sections ***CSI 02 65 00***, ***CSI 03***, and ***CSI 33 56 10*** in this SOW, submitted to local, state, or federal agencies to demonstrate compliance shall provide a copy(ies) to both the 90 CES/CEI Fuel Storage Tank Program Manager and to the 90 CES/CEM Chief Construction Chief.

END OF STATEMENT OF WORK

ATTACHMENT 1

LF Limit of Potential Ground Disturbance (approx. 210 ft from LF Boundary with Easement)



ATTACHMENT 2

Chart 6FtDW – 4Kgal.pdf_safe – Calibration Chart

APPENDIX 1 – REFERENCES

*****NOTE: Any Specifications and/or Regulations must be in accordance with the most current)**

1) References

- a) Title 40 CFR Environmental Protection Agency (EPA), Subchapter I, Part 260-268
- b) Title 29 CFR 1910 OSHA,
- c) Federal Standard, FED-STD-313C, Tables I and II
- d) Federal Acquisition Regulation (FAR) 52.237-2: *Protection of Government Buildings, Equipment, and Vegetation*

2) WEBSITES:

- Acceptable Document-Submittals
DoD SAFE: www.safe.app.mil
- Anti-Terrorism
<https://jkodirect.jten.mil/Atlas2/page/login/Login.jsf>
- Occupational Safety and health Administration (OSHA)
www.osha.gov
- Department of Defense
<http://www.e-publishing.af.mil>

3) USAF Submittal Forms (AF...)

- a) Form 103 *Base Civil Engineering Work-Clearance Request* aka “Dig Permit”
- b) Form 592 *Hot Work Permit* aka “Burn Permit”
- c) Form 66 *Schedule of Material Submittal Form*
- d) Form 3000 *Material Approval Submittal*
- e) Form 3064 *Contract Progress Schedule*
- f) Form 3065 *Contract Progress Report*

4) References:

a. CSI 02 65 00 – Underground Storage Tank Removal

- i. Publications listed below form a part of this specification to the extent referenced and for basic designation only.
- ii. American National Standards Institute (ANSI)
 - ANSI/UL/ULC 1316: 2018 Underwriters Laboratories (UL) Standard for Fiber Reinforced Underground Tanks for Flammable and Combustible Liquids
- iii. American Petroleum Institute (API)
 - API PUBL 1628 - A Guide to the Assessment and Remediation of Underground Petroleum Releases
 - API RP 1604 - Closure of Underground Petroleum Storage Tanks
- iv. ASTM International (ASTM)
 - ASTM D 4397 - Standard Specification for Polyethylene Sheeting for Construction, Industrial, and Agricultural Application
- v. National Fire Protection Association (NFPA)
 - NFPA 30 – Flammable and Combustible Liquids Code
 - NFPA 31 – Standard for the Installation of Oil-Buring Equipment.
- vi. U.S. Army Corps of Engineering (USACE)
 - EM 385-1-1 - Safety—Safety and Health Requirements
- vii. U.S. Environmental Protection Agency (EPA)

- EPA 530/F-93/004 - Test Methods for Evaluating Solid Waste (Vol IA, IB, IC, and II) (SW-846)
 - API EPA 600/4-79/020 - Methods for Chemical Analysis of Water and Wastes
- viii. U.S. National Archives and Records Administrations (NARA)
 - 29 CFR 1910 Occupational and Safety and Health Standards
 - 40 CFR 280 Technical Standards and Corrective Action Requirements for Owners and Operations of Underground Storage Tanks (US)
- b. CSI 26 00 00 – Electrical**
 - i. Publications listed below form a part of this specification to the extent referenced and for basic designation only.
 - ii. American National Standards Institute (ANSI)
 - ANSI S3.2 – Method for Measuring the Intelligibility of Speech Over
 - iii. National Fire Protection Association (NFPA)
 - NFPA 70 – National Electrical Code
- c. CSI 28 00 00 – Electrical Safety and Security**
 - i. Publications listed below form a part of this specification to the extent referenced and for basic designation only.
 - ii. U.S. National Archives and Records Administrations (NARA)
 - 29 CFR 1910 Occupational and Safety and Health Standards (OSHA)
 - iii. National Fire Protection Association (NFPA)
 - NFPA 70 – National Electrical Code (NEA)
- d. CSI 03 – Concrete**
 - i. Publications listed below form a part of this specification to the extent referenced and for basic designation only.
 - ii. U.S. Army Corps of Engineering (USACE)
 - EM 385-1-1 - Safety—Safety and Health Requirements
 - iii. U.S. Environmental Protection Agency (EPA)
 - EPA 530/F-93/004 - Test Methods for Evaluating Solid Waste (Vol IA, IB, IC, and II) (SW-846)
 - API EPA 600/4-79/020 - Methods for Chemical Analysis of Water and Wastes
 - iv. U.S. National Archives and Records Administrations (NARA)
 - 29 CFR 1910 Occupational and Safety and Health Standards
 - 40 CFR 280 Technical Standards and Corrective Action Requirements for Owners and Operations of Underground Storage Tanks (US)
- e. CSI 23 11 – Facility Fuel Piping**
 - i. Publications listed below form a part of this specification to the extent referenced and for basic designation only.
 - ii. American National Standards Institute (ANSI)
 - ANSI S3.2 – Method for Measuring the Intelligibility of Speech Over
 - iii. National Fire Protection Association (NFPA)
 - NFPA 70 – National Electrical Code
- f. CSI 31 23 00 – Earthwork – Excavation and Fill**
 - i. Publications listed below form a part of this specification to the extent referenced and for basic designation only.
 - ii. Army Core of Engineers (USACE)
 - EM 385-1-1 – Safety—Safety and Health Requirements
 - iii. Environmental Protection Agency
 - EPA 600/4-79/020 – Methods for Chemical Analysis of Water and Wastes

- EPA SW-846.3-3 – Test Methods for Evaluating Solid Waste: Physical/Chemical Methods
 - <https://www.epa.gov/ust/underground-storage-tanks-usts-laws-and-regulations>
- ix. Department of Environmental Quality, State of Wyoming, Tank Program
- g. CSI 33 56 10 – Utilities – Factory Fabrication Fuel Storage Tanks**
 - i. Publications listed below form a part of this specification to the extent referenced and for basic designation only.
 - ii. U.S. National Archives and Records Administrations (NARA)
 - 29 CFR 1910 Occupational and Safety and Health Standards
 - iii. Department of Environmental Quality, State of Wyoming, Tank Program