

CHILLER SCHEDULE AIR COOLED

SYMBOL	DESCRIPTION	CAPACITY KW (TON)	REFRIGERANT	EVAPORATOR DATA				CONDENSER DATA			COMP. ELECT. DATA		TOTAL ELECT. DATA						EER	OPER. WT. Kg	REMARKS
				L/S	EWI (C)	LWI (C)	MAX PD	NO. OF FANS	EAT (C)	FAN RLA (EACH)	QTY	TOTAL KW	MCA	MOP	V	ø	Hz				
	ROTARY AIR COOLED	385	HCFC-22	16.7	12.78	7.22	38.7	10	32.2	5.1	2	119.6	535	700	200	3	60	10.4	4400	---	

PUMP SCHEDULE

TAG NO.	SERVICE	TYPE	(KPA)	MOTOR		RPM	REMARKS
				H.P.	VOLTAGE/ø		
	HWS&R	BASE MOUNTED CENTRIFUGAL	5.8	299	5 208/3	3500	① VFD
	CHWS&R	BASE MOUNTED CENTRIFUGAL	16.7	299	15 208/3	1750	① VFD

① PROVIDE WITH NON-OVERLOADING MOTOR SELECTION AND SUCTION DIFFUSER WITH STRAINER.

HOT WATER DUCT HEATING COIL SCHEDULE

TAG	SERVICE	L/S SA	KW	AIR TEMP (°C)		WATER FLOW L/S	LENGTH x HEIGHT	MAX. WPD (KPA)	MAX. APD (PA)
				EAT	LAT				
	AH-7	1490	20.0	12.7	23.8	0.43	560x508	0.34	75

NOTES:

1. BASED ON 82.1 EWT, 71.0 LWT. PROVIDE WITH FLANGE MOUNTINGS,
SAME SIDE CONNECTIONS AND DRAINABLE HEADER.

DUCTLESS SPLIT SYSTEM HEAT PUMP SCHEDULE

MARK	COOLING CAPACITY KW			HEATING CAPACITY KW	TOTAL SUPPLY AIR L/S	INDOOR FAN MOTOR FLA	VOLTS	M.C.A.	PHASE	OUTDOOR UNIT M.C.A.	VOLTS	PHASE
	TOTAL	SENS.	COIL EAT °C Δ/°C WB									
DSS-1	3.6	3.6	25.1/16.6	1.5	188	0.5	120	17	1	12	208	1

NOTES:

1. COOLING CAPACITIES BASED ON ENTERING AIR TEMPERATURES LISTED AND 33.8°C, OUTSIDE AIR TEMPERATURE.
2. PROVIDE SINGLE POINT CONNECTION WITH INTEGRAL DISCONNECT FOR INDOOR UNIT AND AUXILIARY ELECTRIC HEAT.
3. PROVIDE WITH INTEGRAL CONDENSATE PUMP.

AIR CONTROL SCHEDULE

SYSTEM	AIR SEPARATOR			EXPANSION TANK					RELIEF PRESS. (kPa)	FILL PRESS. (kPa)
	L/S	MAX. P.D. KPa	LINE SIZE	LITERS CAPACITY	LITERS ACCEP. CAPACITY	APPROX. DIAMETER	APPROX. HEIGHT			
CHILLED WATER	16.7	15	125	84	45	305	1148		420	210
HOT WATER	5.8	10	75	25.3	129	406	1807		420	210

ELECTRIC UNIT HEATER SCHEDULE

UNIT NO.	WATTS	VOLTS	PHASE	No. OF STEPS	NOMINAL L/S	REMARKS
	500	120	1	1	85	① ②

① PROVIDE WITH INTEGRAL TAMPER RESISTANT THERMOSTAT, INTEGRAL DISCONNECT, AND BLOWER.

② PROVIDE WITH SURFACE MOUNTING KIT AND "DEAD FRONT" ELECTRICAL CONSTRUCTION.

4-PIPE CONSTANT VOLUME AIR HANDLING UNIT SCHEDULE

TAG NO.	FAN					COIL DATA								REMARKS
	L/S SA	L/S OA	H.P.	ESP (PA)	VOLTAGE/ø	TYPE	EDB °C	EWB °C	LAT °C	WATER L/S	WATER P.D. KPA	KW SEN	KW TOT	
	1490	680	3	250	208/3	6 ROW CHW	28.7	22.3	12.5	2.3	27.0	28.1	52.7	---
						2 ROW HW	8.6	---	29.4	0.81	67.5	---	37.5	---
	694	220	3/4	188	115/1	6 ROW CHW	27.3	21.0	12.6	0.85	9.78	10.9	19.6	---
						2 ROW HW	5.6	---	36.21	0.31	44.0	---	14.5	---

HOT WATER UNIT HEATER SCHEDULE

UNIT NO.	APPROX. L/S	MIN. CAPACITY (KW)	L/S	EWT (°C)	EAT (°C)	MAX. PD (KPA)	MAX. HP	VOLTS	PHASE	REMARKS
	385	8	0.18	82	13	0.48	1/20	115	1	

DUCT CONSTRUCTION AND LEAK DETECTION SCHEDULE

MARK	DUCT PRESSURE CLASS (Pa)				DUCT SEAL CLASS	DUCT LEAK CLASS L/S PER 100 SM	DUCT TEST PRESSURE PA	DUCT TEST TYPE	REMARKS
	SUPPLY DUCT	RETURN DUCT	EXHAUST DUCT	OUTSIDE AIR DUCT					
AHU-1 THRU 6	1000	250	N/A	250	B	121.93	1000	①	
AHU-7 & 8	250	250	N/A	250	C	121.93	N/A	②	
VW'S	250	250	N/A	N/A	C	121.93	N/A	②	
EF'S/SF'S	N/A	N/A	250	N/A	C	121.93	N/A	②	
ERU'S	250	250	N/A	250	C	121.93	N/A	②	

- ① PROVIDE DALT TESTING. ③ RECTANGULAR = 1.18
ROUND = 0.66
② VISUAL TESTING. ④ RECTANGULAR = 4.73
ROUND = 2.37

ROOM AIR CONDITIONER SCHEDULE

MARK	FAN DATA			COOLING DATA		ELEC. DATA INDOOR UNIT		REMARKS
	HIGH/LOW AIR L/S	OUTSIDE AIR L/S	MOTOR KW	TOTAL KW	SENSIBLE KW	MCA/MOCP	VOLTS/ø	
	153 / 118	33	1.1	3.29	2.32	6.4 / 15	265/1	① ②

- ① COOLING CAPACITY BASED ON EAT = 75° F. DB/63° F. WB AND 95° F. AMBIENT AIR TEMPERATURE.
② PROVIDE MANUFACTURER'S STANDARD WALL SLEEVE, DRAIN KIT, AND POWER CORD.

HOT WATER RESET SCHEDULE

OUTSIDE TEMPERATURE (°C)	HOT WATER TEMPERATURE (°C)
ABOVE 10°	60°
BETWEEN 3° AND 10°	71°
BELOW 3°	82°

SPACE DESIGN NOISE CONDITIONS

SPACE	NOISE, (RC MARK II LEVEL)
RESIDENTIAL (MODULE) AREA	RC 25 TO 35
ADMINISTRATION SPACES	RC 35 TO 45
CIRCULATION SPACES	RC 35 TO 45
PUBLIC TOILETS	RC 35 TO 45
TRAINING, TV, AND MTG. ROOMS	RC 25 TO 35
TELEPHONE EQUIPMENT ROOMS	RC 35 TO 45
JANITOR CLOSETS	RC 35 TO 45
LINEN STORAGE ROOMS	RC 35 TO 45
LAUNDRY FACILITIES	RC 35 TO 45
MECHANICAL ROOMS	N/A
ELECTRICAL ROOMS	N/A
AIR HANDLER ROOMS	N/A

THE NOISE LEVEL DESIGN SHALL FOLLOW THE PROCEDURES AND
RECOMMENDATIONS PRESCRIBED IN THE CHAPTER "SOUND AND
VIBRATION CONTROL" IN THE LATEST EDITION OF THE ASHRAE
APPLICATION HANDBOOK, AS PART OF THE ASHRAE HANDBOOKS SERIES.

CONTROL VALVE SCHEDULE

EQUIPMENT SERVED	COOLING VALVE	HEATING VALVE	HEATING VALVE	TYPE
AHU-1	X		1.83	3-WAY
AHU-1		X	0.71	3-WAY
AHU-2	X		1.89	3-WAY
AHU-2		X	0.72	3-WAY
AHU-3	X		2.21	3-WAY
AHU-3		X	0.82	3-WAY
AHU-4	X		2.12	3-WAY
AHU-4		X	0.82	3-WAY
AHU-5	X		2.12	3-WAY
AHU-5		X	0.83	2-WAY
AHU-6	X		2.21	3-WAY
AHU-6		X	0.83	2-WAY
AHU-7	X		2.3	3-WAY
AHU-7		X	0.81	2-WAY
AHU-8	X		0.85	3-WAY
AHU-8		X	0.31	2-WAY
VW-1		X	0.03	2-WAY
HWC-1		X	0.43	2-WAY

NOTE: ALL VALVES TO BE MODULATING WITH A
MAXIMUM PRESSURE DROP OF 35 KPA.



1318

APPROVED

ACTIVITY - SCHEDULE NO.

DATE: JUNE 28, 2004

APPROVED

FOR THE PROJECT MANAGER

DATE: 28 JULY 2002

BY: M.J.H.

BY: J.D.

BY: D.F./E.L.

BY: G.W.D.

BY: J.M.

BY: J.M.

BY: J.M.

BY: J.M.

BY: J.M.

BY: J.M.

BY: J.M.

BY: J.M.

BY: J.M.

BY: J.M.

BY: J.M.

BY: J.M.

BY: J.M.

BY: J.M.

BY: J.M.

BY: J.M.

BY: J.M.

BY: J.M.

BY: J.M.

BY: J.M.

BY: J.M.

BY: J.M.

BY: J.M.

BY: J.M.

BY: J.M.

BY: J.M.

BY: J.M.

BY: J.M.

BY: J.M.

BY: J.M.

BY: J.M.

BY: J.M.

BY: J.M.

BY: J.M.

BY: J.M.

BY: J.M.

BY: J.M.

BY: J.M.