

PERFORMANCE WORK STATEMENT (PWS)

BUREAU OF ENGRAVING AND PRINTING

DISTRICT CURRENCY FACILITY (DCF)

WASTEWATER PRETREATMENT PLANT OPERATION AND MAINTENANCE SERVICES

1.0 Background

The Bureau of Engraving & Printing's (BEP) Facility is a component of the United States Department of the Treasury that designs, engraves, and prints U.S. currency banknotes and other U.S. security products. U.S. currency banknote manufacturing occurs at BEP's District of Columbia Facility (DCF) located in Washington, DC. BEP's primary customer is the Federal Reserve Board (FRB). As part of the manufacturing process various industrial wastewater streams are generated as well as storm water streams. These waste streams must be either pretreated through the BEP Wastewater Pretreatment Plant (WWPP) in order to comply with environmental regulations that allow for their discharge into the sanitary sewer or must be otherwise managed in compliance with applicable regulations.

1.1 Objective

The Bureau of Engraving & Printing's (BEP) Facility located in Washington, DC contains an Industrial Wastewater Pretreatment Plant (WWPP). BEP's objective is to procure contractor services to manage, operate, maintain supplies and perform maintenance and provide technical support for the Wastewater and Storm Water Programs. The WWPP requires services to support the BEP on a 24/7 basis. The WWPP currently consists of four (4) systems: (1) Wiping Solution Wastewater Pretreatment Plant (WSWPP), (2) Plating Wastewater Pretreatment Plant (PWPP), (3) Grease Trap Wastewater Pretreatment Plant (GTWPP), and (4) Wiping Solution Recycling Plant (WSRP). The WWPP includes an on-site lab and a materials storage area. Refer to Attachments 2, 3, 4, 5, and 6 for descriptions of the five (5) systems as well as Attachment 9 and 10 for listings of the equipment that are part of the WSWPP and PWPP, respectively. The GTWPP may be removed during the course of this contract. In addition to these systems, additional systems are currently being researched that will be included in the scope of this requirement. These processes will be limited to elementary neutralization and/or oil and water separation.

1.2 References

REGULATION/ PUBLICATION	ORGANIZATION/ FEDERAL/STATE/LOCAL AGENCY	WEBSITE/ LOCATION
Federal, State, Local and Organizational Regulations/ Publications/ Codes		
All applicable regulations as prescribed under 29 CFR 1910.	Occupational Safety and Health Standards (OSHA), Department of Labor	http://www.osha.gov/
Applicable Standards and codes, including the National Electric Code (NEC) codes.	National Fire Protection Agency (NFPA)	http://www.nfpa.org/
Applicable standards related to safety and health and ANSI/ASQC Q91-1987 Quality Systems Model for Quality Assurance in Design/Development, Production, Installation, and Servicing.	American National Standards Institute (ANSI)	http://www.ansi.org/
All applicable Washington D.C. regulations related to air, solid waste and water quality.	District of Columbia, Office of Documents and Administrative Issuance.	http://ddoe.dc.gov/service/regulations-and-legislative-affairs

All applicable regulations, including but not limited to; • 40 CFR 110 Discharge of Oil • 40 CFR 112 Oil Pollution Prevention • 40 CFR 122 and 123 • 40 CFR 136 • 40 CFR 141 through 143 • 40 CFR 260 through 268 • 40 CFR 273 Standards for Universal Waste Management • 40 CFR 279 Standards for the Management of Used Oil • 40 CFR 300 and 302 Releases to the Environment • 40 CFR 370 Hazardous Chemical Reporting: Community Right-to-Know • 40 CFR 372 Toxic Chemical Release Reporting: Community Right-to-Know • 40 CFR 403 General Pretreatment Regulations for Existing and New Sources of Pollution • 40 CFR 433.15 Pretreatment Standards for Existing Sources • NPDES Multi-Sector General Permit for Storm Water Discharges Associated With Industrial Activities • NPDES General Permit for Discharges from	United States Environmental Protection Agency (EPA)	http://www.epa.gov/
---	--	--

Construction Activities		
• 49 CFR 171-180	United States Department of Transportation (DOT)	http://www.dot.gov/
BEP's Wastewater Discharge Permit	DC Water (DCWASA)	Attachment 1
BEP Regulations/ Publications/ Codes		
BEP's WWPP Wiping Solution Wastewater Pretreatment Plant (WSWPP) Process Description	BEP	Attachment 2
BEP's WWPP Chemical Treatment Process Plating Wastewater Pretreatment Plant (PWPP) Process Description	BEP	Attachment 3
BEP's WWPP Chemical Treatment Process Grease Trap Wastewater Pretreatment Plant (GTWPP) Process Description	BEP	Attachment 4
BEP's WWPP Chemical Treatment Process Wiping Solution Recycling Plant (WSRP) Process Description	BEP	Attachment 5
BEP Environment, Health, and Safety Requirement for Construction and Services	BEP	Attachment 8
Wage Determination	DOL	Attachment 11
BEP Environment, Health, and Safety Policy 75B-01	BEP	Provided to the successful contractor after award.
BEP's Quality Management System Manual	BEP	Provided to the successful contractor after award
BEP's Environmental Management System Manual 75B-00	BEP	Provided to the successful contractor after award
BEP Operational Control – Management of Hazardous Waste 75D-03.0-04	BEP	Provided to the successful contractor after award
BEP's SPCC Plan	BEP	Provided to the successful contractor after award
BEP's Emergency Action & Fire Prevention Plan 75D-04.0-01	BEP	Provided to the successful contractor after award
Escort Procedure: BEP Security Manual 71-00, Chapter 13	BEP	Provided to the successful contractor after award

The Contractor shall comply with and perform all Services associated with the contract in accordance with any and all applicable Regulations/ Publications/ Codes. The Contractor is solely responsible for ensuring it is complying with and performing in accordance with any such amendments, supplements to such Regulations/ Publications/ Codes as well as any and all superseding documents issued or enacted during the life of the contract. The following is a listing of applicable Regulations/ Publications/ Codes governing the management, operation, supply, maintenance, and engineering of the BEP Plant. This list is not all inclusive.

The Contractor shall notify in writing the Contracting Officer (hereinafter “CO”) and Contracting Officer Representative (hereinafter “COR”) of any change to an applicable Regulation/ Publication/ Codes and any impact it may have on the contract price. Before implementing any change that will result in a decrease or no change in the contract price, the Contractor shall submit to the CO a proposal no later than fifteen (15) calendar days following receipt of the notification of the change by the Contractor. The Contractor shall implement those changes that result in a decrease or no change in the contract price as directed by the CO. Before implementing any change that will result in an increase in the contract price, the Contractor shall submit to the CO a proposal no later than fifteen (15) calendar days following receipt of the notification of the change by the Contractor. The Government and the Contractor shall then negotiate the change into the contract under the terms and provisions of the contract.

1.3 Acronyms and Definitions

The terms set forth below shall have the following meanings throughout this document:

1.3.1 "BEP" or "Bureau" means the Bureau of Engraving and Printing, U.S. Department of the Treasury.

1.3.2 "Contractor personnel" means all Contractor employees, including subcontractor employees, or any other person(s) acting for or on behalf of the Contractor to perform the Services as specified herein.

1.3.3 "Chemical Process" means a process by which a chemical is manufactured or a process that is inherently chemical in nature such as manufacturing processes that require the physical management of chemical usages in the process and require associated quality control techniques to maintain the process. Examples of chemical processes would be substrate-coating operations, painting operations, pharmaceutical operations, water treatment operations, etc. Specifically excluded from this definition is the process of the use of chemicals in boiler treatment or the process of the use of chemicals in cooling tower treatment or chiller facilities.

1.3.4 "Double shift" means two (2) times the normal time period of the contractor's single shift. If the Contractor's normal shift is 12 hours, a double shift is 24 hours consecutively. If the Contractor's normal shift is 8 hours, a double shift is 16 hours consecutively.

1.3.5 “Equipment” means items or components purchased to support the plant that as a whole, that are expected to have a life span of >3 years. Examples would include motors; pumps; pH and ORP control systems – including controller and cables; lab spectrometer; jar testing apparatus, lab scales, moisture analyzer, etc.

1.3.6 “Environmental Management System or EMS” means the environmental system that the BEP employs to minimize the environmental risk of all actions and programs undertaken by the BEP. Through this system, BEP is committed to continually improving products and processes, protecting the environment through prevention of pollution, and investing in employees, facilities and equipment to enable that improvement and provide a safe workplace.

1.3.7 "Facilities and/or Facility" means BEP's District of Columbia facility (hereinafter “DCF”), including the Plant, and any changes or improvements thereto, located at 301 14th Street, S.W., Washington, DC 20228-0001.

1.3.8 “Immediate or Immediately” means within fifteen (15) minutes, unless otherwise specified.

1.3.9 “Janitorial Supplies” means any and all supplies that may be used by personnel to keep the Plant and the personnel clean. Examples of janitorial supplies include, but are not limited to: paper towels, toilet paper, any bathroom supplies, hand soaps, sanitizers, mops, mop buckets, brooms, dust pans, and components, any floor mats sent for periodic cleaning service, trash bags, etc.

1.3.10 "Key Personnel" means Contractor personnel or positions who/which are vital to the performance of the Contract and are required to be filled by the Contractor with at least one individual, subject to the requirements herein. Those roles that are considered Key are the Program Manager, Plant Manager, Assistant Plant Manager, Maintenance Manager, Laboratory Technician, Maintenance Technician, Office Automation Assistant, Supervisor and Operator.

1.3.11 "Materials" means the consumables (e.g. chemicals [lab reagents, support, and process]), supplies (e.g. spare and repair parts and components) and other necessary materials (e.g. equipment, lubricants and containers) used to perform these services.

1.3.12 "Maintenance” includes work to repair and maintain as well as installation of process improvements. This includes work undertaken to prevent damage to equipment, a system or component thereof that otherwise would be more costly to completely overhaul or replace, to maintain Plant equipment and systems in a specified condition, or to restore equipment, systems or components to initial or usable condition by overcoming the effects of breakdowns, wear and tear, damage or deterioration, or work to correct an inoperable, broken, damaged, or worn system or component to a condition such that it operates in the manner in which it was intended or is restored to its "as built" condition and may consist of refurbishing and replacing systems or components as necessary in order to ensure reliable, long-term and safe and efficient operation of the Plant. However, work performed under Maintenance shall be classified as follows: **1.3.12.1**

“Preventive/Predictive Maintenance” Preventive/Predictive maintenance is maintenance that is routinely scheduled and performed prior to the failure of equipment.

1.3.12.2 "Non-Routine Maintenance" Non-routine maintenance is unscheduled maintenance performed to correct items, which do not adversely affect production or jeopardize compliance with Regulations/ Publications/ Codes, specifically the

Discharge Permit or constitute immediate danger to people, property or the environment, but if left unrepaired would result in failure of equipment, systems and/or other issues.

1.3.12.3 "Emergency Maintenance" Emergency maintenance is unscheduled maintenance performed to correct failures, which constitute an immediate danger to people, property, the environment or impact production or jeopardize compliance with Regulations/ Publications/ Codes, specifically the Discharge Permit.

1.3.13 “Maximo” A BEP provided enterprise asset management application software through which asset lifecycle maintenance is performed. All materials, supplies and spare parts are managed through the storeroom function and all maintenance activities including PMs, calibrations, monitoring and measuring activities are managed through the service request and work order system. Although Maximo is a BEP wide application, the Plant will utilize a separate subset of the system that is not visible to the rest of BEP on a generalized basis.

1.3.14 "Monitoring and Testing" Monitoring and Testing is performed to provide reasonable assurance that Plant equipment is functioning as designed and that the equipment functions properly under both normal and emergency conditions so that adequate treatment is provided to meet Regulations/ Publications requirements.

1.3.15 "Normal Operating Hours" means twenty four (24) hours a day, seven (7) days a week, including all Federal Holidays and BEP’s Year End Shutdown (Y.E.S.) Period. The BEP’s Y.E.S period typically occurs between December 25th and January 1st of each year. The COR will notify the Contractor of any change to the schedule.

1.3.16 “Oxidation-Reduction Potential or ORP” means tendency of a chemical species to acquire electrons and thereby be reduced. ORP is expressed in millivolts or mV.

1.3.17 “Permit” means BEP’s Wastewater Discharge permit and future revisions. Refer to Attachment 1 of this document for a copy of the current Permit.

1.3.18 “Personal Protective Equipment or PPE” means any type of device, material or equipment that is used to protect an individual from environmental or occupational harm that may be present due to conditions of normal operation or abnormal operation. Examples of these include but are not limited to: safety shoes, safety glasses, gloves, hearing protection, hard hats, protective suits, lotions or creams, etc.

1.3.19 “Prime Contractor” means the Contractor that the BEP has awarded a contract, for which this PWS serves to describe services that are to be provided to the BEP.

1.3.20 “pH” means the negative log of the hydrogen ion concentration of an aqueous material expressed in Standard Units or S.U.

1.3.21 “Plant” means BEP's Industrial Wastewater Pretreatment Plant located at the BEP Washington, DC Facility and any changes, replacement or improvements thereto. The Plant currently consists of four (4) systems: (1) Wiping Solution Wastewater Pretreatment Plant (hereinafter “WSWPP”), (2) Plating Wastewater Pretreatment Plant (hereinafter “PWPP”), (3) Grease Trap Wastewater Pretreatment Plant (hereinafter “GTWPP”), (4) Wiping Solution Recycling Plant (hereinafter “WSRP”).

In addition, the Plant includes an on-site lab and Materials storage area.

1.3.22 “Plant shutdown or Plant stoppage” occurs when the Plant is out of operation due to a mechanical, electrical or operational failure, lack of treatment chemicals, or inadequate volume in the treatment tanks. Plant shutdown or Plant stoppage does not occur when the plant is intentionally shut off by the Government because the BEP is not in operation or resulting from a planned shutdown/ stoppage that does not affect BEP operations.

1.3.23 “Performance Work Statement or PWS” means this document and all attachments listed herein that describe the services and deliverables required to be provided under the associated awarded contract and options if exercised.

1.3.24 “Quality Management System or QMS” means the quality system that the BEP employs. Everything BEP does supports producing secure, high-quality banknotes that meet customer requirements. BEP is committed to continually improving products and processes and investing in BEP employees and equipment to enable that improvement.

1.3.25 “Regulations/ Publications/ Codes” means any and all applicable Federal, State, Local and Organizational laws, regulations, codes, ordinances and conditions (i.e. public and occupational health, safety, and environmental protection, pretreatment regulations, etc.) as well as any and all BEP policies, procedures, guidelines and requirements that govern the management, maintenance and operation of the Plant. A listing of applicable Regulations/ Publications/ Codes is provided in Section 1.2 of this document.

1.3.26 “Repair or Repairs” means emergency repairs and minor repairs that are performed (1) in the event that any component or part, including equipment of the Plant should fail or not perform in accordance with Regulations/ Publications and/or equipment specifications, (2) by knowledgeable, trained, certified and experienced personnel utilizing proper equipment and tools and (3) to provide reliable, long-term and safe and efficient operation of the Plant. Repairs are classified as follows:

1.3.26.1 “Emergency Repairs”: Emergency repairs are required to correct failures which constitute an immediate danger to workers, property, and impact production or jeopardize the Plant’s compliance with Regulations/ Publications, specifically the Permit. The Contractor shall assess the situation, immediately (within 15 minutes of becoming aware of the issue) notify the COR or designee and provide a plan of action, and once approved, proceed with completing such repairs in a safe and expeditious manner.

1.3.26.2 “Repairs”: Repairs are required to correct failures which do not adversely affect production or constitute immediate danger to workers, property, and impact production or jeopardize the Plant’s compliance with Regulations/ Publications, specifically the Permit. The Contractor shall assess the situation, notify the COR or designee and provide a plan of action within twenty-four (24) hours of being alerted or becoming aware of failure or situation, and once approved, proceed with completing the repair in a safe and expeditious manner.

1.3.27 “Safety Stock” material stored in sufficient quantity to last for a desired duration, that is stored for extended periods of time, however periodically changed out, to ensure continuity of operations, material quality, and container integrity in the event that the material(s) cannot be received due to unforeseen circumstances such as inclement weather or other circumstance. They are not part of the standard usage materials quantity inventory, however must be managed separately. **1.3.28 “SCADA”** Supervisory Control and Data Acquisition software and associated hardware. This is also referred to as Human-Machine Interface software or HMI. This is the equipment control software used for operational control in most of the Plant systems.

1.3.29 "Services" means the Contractor providing throughout the performance of the contract any and all labor and resources such as, but not limited to; Management, Operations, Technical Support, Maintenance, Sampling and Testing, Monitoring, Measuring, Repairs, Process improvements, Emergency Repairs, Transportation as well as any Tools and Equipment and Materials furnished by or utilized by the Contractor in the performance of this effort for the safe, clean, orderly, efficient and successful operation, management and maintenance during Normal Operating Hours the BEP Plant.

1.3.30 “Supplies” means consumables or sub-components of equipment that are expected to have a life of <3 years. Examples include parts to rebuild a pump, I/O boards for PLC systems, individual parts of a mixer i.e. gear box, shaft, impeller, pH probes with associate mounting components, ORP probes with associate mounting components, laboratory reagents, bottles, etc.

1.3.31 “Tools and Equipment” means the tools and equipment furnished by the Contractor to perform the Services. For example, the Contractor is to identify and provide its personnel with the necessary respiratory and Personnel Protective Equipment (hereinafter “PPE”) as required by OSHA regulations. The Contractor is responsible for identifying the Tools and Equipment needed to perform these Services.

1.3.32 “Variance” means when an item (spare part, material, chemical, etc.) is used in a way that is different from the original intended use. An example would be using Bentonite to absorb liquid in a sludge box that has free liquids. The original intended use of Bentonite is only in the WSWPP treatment process between T-1 and T-3, where it is fed into the waste stream to begin the treatment process. Any other use would be a variance.

2.0 SCOPE

The Contractor shall perform any and all Services necessary for the safe, neat, clean, orderly, efficient and successful management, operation, maintenance, and technical support during Normal Operating Hours of the BEP’s Industrial Wastewater Pretreatment Plant (hereinafter “Plant”) which includes small ancillary treatment systems, existing and installed, during the performance of this contract located in Washington, DC in addition to assigned Storm water activities.

The Government’s objectives are to obtain Services of exceptional value that afford it the opportunity to continuously improve, reduce costs and develop effective and efficient means to manage, operate, and maintain the Plant. Therefore, the Contractor shall implement the necessary controls, plans, processes, etc. to ensure such value. The contractor shall ensure that prudent engineering and operating practices are utilized at all times; with prudent engineering and operating practices meaning the practices, methods, and acts that at a particular time, in the exercise of reasonable judgment in light of the facts known or that should have been known at the time a decision was made, would be expected to accomplish the desired result in a manner consistent with law, regulation, reliability, safety, environmental protection, and the written recommendations of the equipment manufacturers. The Government will continue to implement improvements to the Plant throughout the duration of this effort and future efforts; thus it is expected that the Contractor is able to continuously tailor their controls, plans, processes, etc. to the needs of the BEP. The Contractor is expected to perform in accordance with the contract and performance requirements contained herein and in the attachments. The separation of the Contractor’s responsibility and BEP’s responsibility is the point at which a given utility (electricity, air, water, wastewater, and IT supplies) is provided to the equipment in the Plant. Once the utility is attached to the Plant equipment, the remainder of the responsibility belongs to the Contractor and is as such, then governed by the requirements prescribed herein. The end of the responsibility is either at the discharge point or the point at which there is a valve past the last piece of equipment in the WWPP.

2.1 Contract Line Item Number (CLIN) Structure, Definitions, and Notes:

The Contract Line Items (CLINs) are defined. The Government reserves the right to consolidate the CLIN or issue separate CLIN for each.

2.1.1 CLIN 0001: Firm Fixed Price (FFP) hourly rate - Phase-in and Training Service Labor –Program Manager.

Description: This CLIN will provide for all the Program Manager labor associated with Phase-in for the Plant (**Ref. Sections 5.2., 5.12.1**).

2.1.2 CLIN 0002: Firm Fixed Price (FFP) hourly rate - Phase-in and Training Service Labor –Plant Manager.

Description: This CLIN will provide for all the Plant Manager labor associated with Phase-in for the Plant (**Ref. Sections 5.2., 5.12.1**).

2.1.3 CLIN 0003: Firm Fixed Price (FFP) hourly rate - Phase-in and Training Service Labor – Assistant Plant Manager.

Description: This CLIN will provide for all the Assistant Plant Manager labor associated with Phase-in for the Plant (**Ref. Sections 5.2., 5.12.1**).

2.1.4 CLIN 0004: Firm Fixed Price (FFP) hourly rate - Phase-in and Training Service Labor – Maintenance Manager.

Description: This CLIN will provide for all the Maintenance Manager labor associated with Phase-in for the Plant (**Ref. Sections 5.2., 5.12.1**).

2.1.5 CLIN 0005: Firm Fixed Price (FFP) hourly rate - Phase-in and Training Service Labor – Supervisor.

Description: This CLIN will provide for all the Supervisor labor associated with Phase-in for the Plant (**Ref. Sections 5.2., 5.12.1**).

2.1.6 CLIN 0006: Firm Fixed Price (FFP) hourly rate - Phase-in and Training Service Labor – Operator.

Description: This CLIN will provide for all the Operator labor associated with Phase-in for the Plant (**Ref. Sections 5.2., 5.12.1**).

2.1.7 CLIN 0007: Firm Fixed Price (FFP) hourly rate - Phase-in and Training Service Labor – Laborer.

Description: This CLIN will provide for all the Laborer labor associated with Phase- in for the Plant (**Ref. Sections 5.2., 5.12.1**).

2.1.8 CLIN 0008: Firm Fixed Price (FFP) hourly rate - Phase-in and Training Service Labor – Laboratory Technician.

Description: This CLIN will provide for all the Laboratory Technician labor associated with Phase-in for the Plant (**Ref. Sections 5.2., 5.12.1**).

2.1.9 CLIN 0009: Firm Fixed Price (FFP) hourly rate - Phase-in and Training Service Labor – Office Automation Assistant.

Description: This CLIN will provide for all the Office Assistant labor associated with Phase-in for the Plant (**Ref. Sections 5.2., 5.12.1**).

2.1.10 CLIN 0010: Firm Fixed Price (FFP) hourly rate - Phase-in and Training Service Labor – Maintenance Technician.

Description: This CLIN will provide for all the Maintenance Technician labor associated with Phase-in for the Plant (**Ref. Sections 5.2., 5.12.1**).

2.1.11 CLIN 0011: Firm Fixed Price (FFP) hourly rate – Service Labor – Program Manager.

Description: This CLIN will provide for all the labor of the Program Manager to perform the services as contain herein this PWS.

2.1.12 CLIN 0012 (and subsequent options if exercised): Firm Fixed Price (FFP) hourly rate – Service Labor – Plant Manager.

Description: This CLIN will provide for all the labor of the Plant Manager to perform the services as contained herein this PWS.

2.1.13 CLIN 0013 (and subsequent options if exercised): Firm Fixed Price (FFP) hourly rate – Service Labor – Assistant Plant Manager

Description: This CLIN will provide for all the labor of the Assistant Plant Manager to perform the services as contained herein this PWS.

2.1.14 CLIN 0014 (and subsequent options if exercised): Firm Fixed Price (FFP) hourly rate – Service Labor – Maintenance Manager

Description: This CLIN will provide for all the labor of the Maintenance Manager to perform the services as contained herein this PWS.

2.1.15 CLIN 0015 (and subsequent options if exercised): Firm Fixed Price (FFP) hourly rate – Service Labor – Supervisor Operator

Description: This CLIN will provide for all the labor of the Supervisor to perform the services as contained herein this PWS.

2.1.16 CLIN 0016 (and subsequent options if exercised): Firm Fixed Price (FFP) hourly rate – Service Labor – Operator

Description: This CLIN will provide for all the labor of the Operator to perform the services as contained herein this PWS.

2.1.17 CLIN 0017 (and subsequent options if exercised): Firm Fixed Price (FFP) hourly rate – Service Labor – Laborer

Description: This CLIN will provide for all of the labor of the Laborer to perform the services as contained herein this PWS.

2.1.18 CLIN 0018 (and subsequent options if exercised): Firm Fixed Price (FFP) hourly rate – Service Labor – Laboratory Technician

Description: This CLIN will provide for all of the labor of the Laboratory Technician to perform the services as contained herein this PWS.

2.1.19 CLIN 0019 (and subsequent options if exercised): Firm Fixed Price (FFP) hourly rate – Service Labor – Office Automation Assistant

Description: This CLIN will provide for all of the labor of the Office Automation Assistant to perform the services as contained herein this PWS.

2.1.20 CLIN 0020 (and subsequent options if exercised): Firm Fixed Price (FFP) hourly rate – Service Labor – Maintenance Technician

Description: This CLIN will provide for all of the labor of the Maintenance Technician to perform the services as contained herein this PWS

2.1.21 CLIN 0021 (and subsequent options if exercised): Cost Reimbursable NTE – Service: Ancillary and Materials.

Description: This CLIN includes the ancillary services performed by outside sub- contractors. Ancillary Services include the following, but not limited to outside laboratory analysis, laboratory DI water unit servicing, soft water systems servicing, process control equipment and scale calibrations, confined space meter calibrations and service, laboratory equipment calibrations and servicing, and corrosion monitoring for sulfuric acid storage tank and piping. This CLIN also provides for all supplies (**Ref. Section 1.3.30**) for the systems (WSWPP, PWPP, GTWPP, WSRP). This includes lubricants, plant deodorizers, and laboratory supplies and chemicals, pH, ORP and conductivity probes, pump parts, etc. This provides for all equipment replacement (**Ref. Section 1.3.5**) for the systems (WSWPP, PWPP, GTWPP, WSRP). (**Ref. Sections 3.3., 3.27., 3.28., 3.32., 3.36.**)

2.1.22 CLIN 0022 (and subsequent options if exercised): Cost Reimbursable NTE – Service: Process Chemicals.

Description: This CLIN provides for all process and treatment chemicals used to recycle the used wiping solution, make-up new wiping solution, treat the non-recycled wiping solution, and treat the plating wastewater. A listing of materials and their annual usage estimates are provided in Attachment 22. (**Ref. Section 3.3.3.**)

2.1.23 CLIN 0023 (and subsequent options if exercised): FFP, Cost Reimbursable NTE - Service - Process Improvements Engineering and Materials.

Description: This CLIN provides for the engineering labor to develop process improvements. The Contractor may suggest Process Improvements and submit a quotation, or the government can request the Contractor to provide a quotation for a Process Improvement. These would be in terms of a Task Order (TO) or a Delivery Order (DO). If the Process Improvement is decided to go forward with, a requisition would be written to cover the cost for the engineering labor here under this CLIN. It is anticipated that only 1 or 2 Process Improvement projects would be undertaken in a year. **(Ref. Sections 3.25., 3.30., 3.34.).**

2.1.24 CLIN 0024 (and subsequent options if exercised): FFP, Cost Reimbursable NTE – Service - Emergency Repair.

Description: This CLIN provides for emergency repair services for the systems (WSWPP, PWPP, GTWPP, WSRP). This CLIN provides for emergency technician service where the prime Contractor does not have the equipment to perform emergency repairs, an example might be welding on a stainless steel tank to fix a leak, another example would be if something happened to the SCADA software and IT could not fix the problem. This CLIN does not include services that the Contractor is required to provide as otherwise noted in the PWS, however, or does not have the personnel or personnel with the required skills to perform the work **(Ref. Section 1.3.31).**

2.1.25 CLIN Notes:

2.1.25.1 All Service Labor CLINs in Section 2.1 include Management, Operations, Maintenance and Process Improvement Engineering. Examples of the labor requirements included would be operating the process systems, labor for managing and obtaining parts and supplies, and equipment, identifying new spare parts requirements for the equipment, setting up and maintaining Maximo for the Plant, cleaning all equipment in the plants, calibrating probes, changing malfunctioning probes, performing all maintenance on all of the plant equipment, recording data, collecting samples for operational control

and performing operational control testing, system compatibility testing, collecting compliance samples, sending compliance samples to the lab, and preparing deliverables. The scope of the Service Labor CLINs also include labor to install process improvements associated with the equipment where the improvements fall clearly in line with the required capabilities of the personnel, such as installing system equivalent pumps, tanks and control equipment as well as decontaminating and removing obsolete equipment as applicable. If the Contractor determines that they do not have the skills to install these types of process improvements, they may obtain the service from a subcontractor at the expense of the prime Contractor, but will not be reimbursed by the Government for this action additionally, since this function is already included by the Service Labor CLINs for which the Contractor is already being reimbursed.

2.1.25.2 For each Service Labor CLIN the hourly rate is firm fixed price.

2.1.25.3 Invoicing under Service Labor CLINs in Section 2: Each invoice will require supporting documentation as to the number of personnel filling each role and the number of hours each person filling the role worked individually on site. No labor performed off site or under the contractor as support on site will be additionally reimbursed because the work is already considered to be reimbursed under the established Service Labor CLINs that include any potential support for the individual role(s). The individual totals must equal the total hours invoiced for the month for the respective CLIN. The supporting documentation must be for the period that the invoice covers.

2.1.25.4 For Equipment and Supply CLINs, individual item receipts demonstrating receipt by the Contractor must be received by the COR within 60 days of receipt by the Contractor, if applicable. The only exception to this requirement is for items that require installation that are part of a project. Once installed, the exception no longer applies. The COR will then submit the information to BEP Receiving to obtain BEP system receipt(s). Once obtained, the Contractor may only then submit the invoice for reimbursement under the respective CLIN.

3.0 Contractor Responsibilities:

The Contractor shall be responsible for, but not limited to:

3.1 General: Managing, operating, and maintaining the Plant in a neat, clean, orderly, efficient and professional fashion during Normal Operating Hours, to include furnishing required service labor, supplies and equipment in performance of this contract.

3.1.1 Fines and Penalties: The Contractor shall assume full responsibility and liability for compliance with all applicable regulations pertaining to the health and safety of personnel, security, and environmental management within the Contractor's control during the execution of work, and shall hold the BEP harmless for any action on its part or that of its employees or subcontractors including but not limited to illness, injury, death or fines. If the Contractor fails to operate the Plant in compliance with the BEP Discharge Permit or any applicable regulation and any fines or penalties are assessed against the BEP, the Contractor shall reimburse the BEP the amount of these fines and penalties and the cost of any legal defense against them.

3.1.1.1 Plant Shutdown: The Contractor shall fully recognize that the services covered by this contract are vital to BEP's mission; that continuation of the services shall be maintained at the utmost proficiency without interruption since the operation, management and maintenance of the Plant is vital to the BEP's mission. If the Contractor fails to maintain the Plant in 100% operational status and/or in compliance with the Regulations/Publications/Codes, except when such conditions are beyond the control of the Contractor (e.g. acts of God, civil unrest, labor disputes, military events) or when directed by the BEP, resulting in shutdowns/stoppages and/or fines or penalties being levied against the BEP, the BEP will assess damages and pass that amount onto the Contractor for reimbursement.

3.1.2 House Keeping: This includes keeping waste to a minimum as well as keeping the Plant work area free of all foreign materials. Control cabinets are not to be used for storage and all maintenance items (tools, excess parts, used parts, waste materials, etc.) are to be placed in their proper location at the end of the operations or maintenance event.

3.1.3 Odor Control: The Contractor shall ensure that no malodorous odors escape from the plant. There are processes internal to the plant, which periodically generates malodorous odors. These odors must be controlled inside of the plant before they exit the plant by the use of odor control agents.

3.1.4 Roll – up Doors: Outside of extenuating circumstance, all roll-up doors must be kept closed unless transferring materials or equipment. The doors must be closed within 15 minutes of using the door, unless the doors are being used by the Office of Security. If a separate government contractor is causing the doors to be opened periodically, it is still the responsibility of the Plant Contractor to ensure that the doors are opened and closed as prescribed herein.

3.1.5 Maintenance of Plant Documentation: The Contractor will update Plant documentation (all associated documents, forms, and electronic drawings) as changes in equipment, materials, and processes occur or as directed by the COR. The documentation must be updated after changes are completed so that the documentation is updated to the final level of the change. The updated document must be sent to the COR for review and approval within 15 calendar days of the completion of the change. The changes in the documentation will be highlighted so as to be easily recognizable with new or additional information in light blue and obsolete information struck through. This may be also accomplished by the use of “Track Changes” functions in the documents. Once the changes are approved by the COR, the Contractor will remove the obsolete information, leaving the highlighted information until the next change. A change record will be maintained for each document in accordance with standard ISO document control methodologies and BEP policies.

3.2 Workforce and Personnel:

3.2.1 The Contractor shall hire, train, administer, manage and supervise the workforce necessary to perform the Services.

3.2.1.1 Under no circumstances shall any contract employee be hired to fulfill the requirements of the position for which they have applied that they do not already meet the requirements for the position unless otherwise noted. The BEP Plant is not to be a training facility. A contractor employee should only need to become familiarized with the work prescribed herein for which they will be performing and require the training as prescribed herein. If the Contractor proposes a new employee, the background investigation begins, and it is determined either that the person does not meet the requirements or they withdraw, the Contractor shall replace the person at the Contractor’s full expense. This means that the Contractor shall bear the government’s cost of the background investigation.

3.2.1.2 If after hiring a contract employee, the Contractor finds that the employee does not or cannot fulfill the requirement for the positions for which they were hired, the Contractor must remove the contractor employee from this contract and will be required to replace the removed contractor employee at the Contractor's full expense. This means that the Contractor shall bear the government's cost of the background investigation.

3.2.1.3 The Contractor is required to have a system by which they evaluate all contract employees to ensure that they are performing to the expected level of the position for which they are employed as prescribed herein. The evaluation shall be on an annual basis and be documented. The evaluation shall include required objectives and targets to maintain being part of the contract. The evaluations shall be sent to the COR for review within 30 days of the completion of the evaluations.

3.2.1.4 If the COR observes a contract employee that appears to not be performing to the required level of performance as prescribed herein, that action will be brought to the attention of the appropriate level of management of the Contractor for corrective action as appropriate. The Contracting Officer reserves the right to remove personnel from this contract if they do not meet the qualifications and/or performance of the required position.

3.2.1.5 The COR will provide the Contractor the methods and language to request access to the BEP computer network locations required and Maximo. The Contractor shall be responsible for submitting these requests. After the requests have been completed, the COR shall be notified within 3 calendar days so that the correct access can be verified by the COR. If the individual contractor has issues accessing the applications, it is the Contractor's responsibility to work with the applicable system BEP representatives to correct the issues.

3.2.2 The Contractor shall maintain satisfactory standards of personnel competency, conduct, appearance, and integrity and shall be responsible for taking such disciplinary action with respect to their personnel as necessary.

3.2.3 Under no circumstances will any Contractor be allowed to sleep, nap, or rest on, or between shifts on BEP premises. If the COR observes this behavior by any individual, the individual will be immediately removed from the premises and will not be allowed to return. The Contractor will replace the removed individual at the Contractor's expense. This requirement would not be applicable in the event of a natural or man-made disaster beyond the control of the Contractor, including but not limited to acts of God or of the public enemy, fires, floods, earthquakes, or other catastrophe. Reference Clause 52.212-4(f), Contract Terms and Conditions-Commercial Items (May 2015).

3.2.4 Ensuring there is sufficient personnel to perform Services at all times throughout the performance of the contract. **3.2.4.1** Sufficient personnel means the Contractor has an adequate number of capable, knowledgeable, trained and experienced and qualified individuals at all times to perform the Services as specified herein throughout the performance of this effort. The

contractor must maintain a minimum of two (2) individuals on-site at all times, with one (1) individual being a supervisor or equivalent, Plant Manager or Assistant Plant Manager. In addition, if one of the plant systems is in operation, an individual fulfilling the role of Laboratory Technician must be on site to perform system analysis as contained herein. Due to safety issues, and in compliance with BEP and OSHA safety requirements, at no time shall the Contractor allow any individual to be on duty for greater than 1.5 shifts without being sent off-site for rest.

3.2.4.2 Outside of a natural or man-made disaster as noted above, the COR or CO may authorize an exception to the above minimum two (2) individual requirement for special circumstances that may arise during the performance of the contract. Such exceptions, if authorized, shall be granted only for a limited period of time and shall not release or hold harmless the Contractor from its responsibility of performing these Services in accordance with the contract. The Contractor shall provide a written request no less than seventy-two (72) hours in advance of requesting such an exception.

3.2.4.3 Personnel that have been hired to fulfill roles under Section 4.10.1 are strictly prohibited from performing in a role listed under Section 4.10.2 as back up, in excess of sixteen (16) hours within any seven (7) calendar day period, whether individually or as a group. Specifically, when any personnel hired under Section 4.10.1 fill-in for a person that may be out (such as covering their shift), for any reason, fulfilling a role listed under Section 4.10.2 for 16 hours, no other person from the group of personnel hired under Section 4.10.1 may fill-in for a person or persons hired under Section 4.10.2 again until 7 calendar days have passed.

3.2.5 The Contractor shall develop and establish an Emergency Operation Plan as outlined in Section 8.1.11 below. The plan shall provide details for providing any additional support or coverage needed to respond to emergency conditions, including spills, instances requiring additional expertise (e.g. welding, specialized engineering, spills, etc.) or instances of personnel illness, vacation and training.

3.3 Materials:

The Contractor shall be responsible for evaluating, testing, recommending, scheduling, maintaining, inventorying, tracking, supplying and stocking all materials necessary to perform the Services. All materials must be obtained in conformance with the materials respective specification, as/if applicable, and with Attachments 12 and 13. All WWPP materials are required to be managed in Maximo within 4 months of award of the contract. This time period may only be extended if there are technical issues with the use of Maximo. Inadequate training is not a technical issue. An extension will not be granted for non-technical issues. In any case, monthly implementation progress reports will be required to be submitted to the COR as part of the Monthly Status Report (**Ref. Section 8.1.21**). An adequate inventory of materials shall be readily available and warehoused within the Plant in order to perform the Services. Additional materials may be stored and warehoused at the BEP's Landover Warehouse in order to provide a means for quick replenishment of on hand stock.

3.3.1 Reserved.

3.3.2 The inventory of chemicals should be maintained in sufficient quantity, yet still produce ample turns per year (a minimum of four (4) are recommended) to ensure fresh chemicals except for safety stock materials. A treatment system being shut down because there is no treatment or process chemicals means the chemicals are not being maintained in sufficient quantities. In any event, at no time may expired materials be used in the WWPP, or for the support of the WWPP. As such, all applicable materials and their respective expiration dates must be tracked and managed by the Contractor. This must be sent to the COR upon request.

3.3.3 The Contractor shall utilize only materials recommended by the original equipment manufacturer or the BEP for maintenance, repair and/or other such purposes. Attachments 14 through 19 provide specifications for the chemicals currently being used by BEP. In addition, Attachments 20 and 21 provide specifications for the containers in use. Materials may be substituted, added or subtracted only if advance approval is provided in writing by the COR. Attachment 22 provides a listing of process and treatment chemical estimated usages based on past annual usage amounts and projected annual amounts for the systems (**Ref. Section 2.1.20**). The Contractor is responsible for procurement, use and inventory management of these materials as prescribed herein. The BEP already has contracts in place for the bulk purchase of 50% Sodium Hydroxide and 50% Sodium Sulfated Castor Oil. As such, the Contractor will not be responsible for the procurement of these two materials for the WSRP until later through a modification of the contract, however, will be responsible for inventory management and providing information to the COR/BEP such that these materials may be shipped in to the BEP in a manner that will support the operation of the BEP in accordance with the materials management methods prescribed herein. The specifications for these two materials (Attachment 18 and 19) are provided for information for the operation of the Plant. After the modification mentioned earlier any required on-site testing of the raw materials or external testing as needed, will become the responsibility of the Contractor. Attachment 23 is a listing of spare parts and supplies with annual past usage amounts for the systems (**Ref. Section 2.1.19**).

Attachment 26 is a listing of equipment with annual past usage amounts for the systems (**Ref. Section 2.1.19**).

3.3.4 Some Materials (process chemicals, boxes, and lids only) may need to be delivered to BEP's Landover Warehouse prior to delivery for use in the Plant. The Contractor shall provide a three (3) business day advance notice for scheduling and coordinating the transfer of Materials from the Landover Warehouse to the Plant. Additionally, the Contractor shall copy the COR on all requests for materials from the Landover Warehouse.

3.3.4.1 BEP's Landover Warehouse Information:

Items needing to be delivered to the BEP Landover Warehouse shall be delivered to the following address:

U. S. Department of the Treasury Bureau of Engraving and Printing

3201 Pennsylvania Drive

Landover, MD 20785

Receiving hours for deliveries is **7:30 a.m. to 2:30 p.m.**, local time, Monday through Friday, excluding U.S. Government holidays and BEP Year-End- Shutdown (which normally occurs between December 24 and January 1).

The Contractor shall call the Landover Warehouse appointment line at (202) 874-0874 at least at least twenty-four (24) hours in advance to schedule deliveries. The appointment line is staffed from 7:00 am to 3:00 pm Monday through Friday. The following information must be provided:

- Name of supplier/manufacturer
- Contact Person with phone number
- Contract/Purchase Order Number
- Total number of cartons or pallets
- Total weight
- Date and Time of Delivery

3.3.4.2 All safety stock materials stored at the Landover Warehouse must be used at least on an annual basis in order to ensure their freshness and the integrity of the storage container.

3.3.4.3 The Contractor shall submit a list of safety stock materials for approval by the COR within 60 calendar days after contract award and update the list for approval by the COR within 15 calendar days of a change, either addition or subtraction that is proposed and approved by the COR.

3.3.5 Changes in materials levels that may impact the operation of the Plant shall, with no exception, be brought to the attention of the COR immediately.

3.4 Repairs and Maintenance:

The Contractor shall perform any and all necessary management, repairs, maintenance and other such tasks and duties required to ensure that the Plant systems, equipment, components and parts are functioning as designed and that they are functioning properly under both normal and emergency conditions so that Plant systems are maintaining treatment at adequate levels and meet Regulation/ Publications/Code requirements throughout the performance of the contract.

3.4.1 The Contractor shall be responsible for the management of all equipment (assets), spare parts, and materials through the BEP provided enterprise asset management application Maximo.

3.4.2 The Contractor shall be responsible for learning and utilizing Maximo accurately to the fullest extent possible up to and including requesting changes in the system, by submitting the written request to the COR which must include justification and desired outcomes to better utilize the system for the purpose of efficient operation of the Plant. **3.4.2.1** Maximo training will not be provided by BEP. Maximo training, if needed, will be the sole responsibility of the Contractor.

3.4.3 The Contractor shall be responsible for but not limited to: developing job plans, identifying work assets and safety plans, labor requirements including costs, materials requirements, services, and tools for all service requests and scheduling of work orders.

3.4.4 The Contractor shall be responsible for collecting any required data and entering it into the Maximo system by whatever means necessary in accordance with BEP policy.

3.4.5 The Contractor is required to complete the transition to the Maximo system within Six (6) months of contract award for the Plant. The Contractor is required to coordinate with BEP personnel to correctly identify, tag, log and expand/associate as needed (Parent – Child relationships); equipment (assets) in Maximo. The Contractor will be required to keep the system up to date with changes in the Plant throughout performance of this contract. This period may only be extended if there are technical issues with the use of Maximo. Inadequate training and/or insufficient personnel are not technical issues. An extension will not be granted for non-technical issues. In any case, monthly implementation progress reports that detail the status, issues, and actions being taken by the Contractor to remove issues will be required to be submitted to the COR as part of the Monthly Status Report (**Ref. Section 8.1.21**).

3.5 Strategic Initiatives:

The Contractor shall be responsible for working on and completing annual BEP strategic initiatives as assigned by the COR on an annual basis. These are milestones and deliverables within the scope of the WWPP functions whose progress are to be reported on a monthly basis to the COR (**Ref. Section 8.1.26**).

3.6 Sampling and Testing, Monitoring, Etc.:

The Contractor shall be responsible for monitoring, calibrating, sampling and testing and performing all other such tasks and duties required to provide reasonable assurance that the Plant systems, equipment, components and parts are functioning as designed and that they are functioning properly under both normal and emergency conditions so that Plant systems are maintaining treatment at adequate levels and meet applicable Regulation/Publications/Code as well as to provide assurance that those materials, tools, and equipment being used or brought into/or shipped out of the Facility and/or Landover Warehouse are in line with Regulation/Publications/Code requirements and safety measures are in place to handle and use

the materials, tools, and equipment. This shall be documented in a Sampling and Testing Plan (Ref. Section 8.1.27).

3.7 Tools and Equipment:

The contractor shall Identify, provide and utilize the proper tools and equipment to perform the work. For example, the contractor shall provide its personnel with the necessary Personnel Protective Equipment (PPE) required by OSHA regulations equivalent to the task to be performed.

3.8 Notification:

The Contractor shall immediately verbally notify the COR or designated representative, no later than fifteen (15) minutes of any accident, incident (e.g. fire, release of hazardous materials/waste(s)/substances, spill, etc.); or within one (1) hour any equipment and/or system failure or any other such occurrence that affects the operation of the Plant or safety of workers, the general public, the environment and/or the Plant. (Ref. Section 8.1.13)

3.9 Accident and/or Incident, or other:

3.9.1 Providing as per Section 8.1.1 or 8.1.17 of this document, a written (non-verbal) Accident or Incident Report within twenty-four (24) hours of any incident/ accident encountered.

3.9.2 Following and carrying out the guidance as outlined in the applicable BEP policy, and any requirements or agreements that may be entered into with local fire, safety, environmental, or health officials.

3.9.3 Providing information in the preparation of other reports and investigations concerning an accident or incident.

3.9.4 Notifying the BEP of any need to interrupt or shutdown any utility service, the fire suppression system, HVAC system or security system and providing the required information.

3.9.4.1 Utility services, the fire suppression system, HVAC system or security system shall not be interrupted or shut down by the Contractor to make connections, alterations, modifications or for any other purpose without prior written approval by the COR. The Contractor shall submit any such requests in writing to the COR no less than fifteen (15) business days prior to the date of the proposed interruption or shut down. The request at a minimum shall provide the following information: **3.9.4.1.1** Type of utility (i.e. water, electricity, gas or compressed air) or system(s).

3.9.4.1.2 Area or Area(s) affected, including specific Plant equipment and size of the line and the shut-off valve.

3.9.4.1.3 Hour and date of proposed shut-off.

3.9.4.1.4 Estimated length of time services or the system(s) will be interrupted or shutdown.

3.9.4.1.5 Rationale for interruption or shutdown.

3.9.5 Upon identification of any safety hazard, providing immediate verbal notification to the COR.

3.10 Spills:

Performing clean-up of any and all spills encountered within the Plant. This includes incidental spills as well as spills or releases that require emergency response by trained professionals that are included in the definitions found under the OSHA HAZWOPER Standard.

3.11 Janitorial Services:

Providing housekeeping (e.g. janitorial/cleaning) services for the Plant and any other area that contains equipment covered under this effort.

3.12 Uniforms:

Providing uniforms for all personnel performing under the contract. The use of torn or worn out uniforms is unprofessional and is strictly prohibited. Personnel may not “share” uniforms, whether in part or in whole.

3.13 Parking:

Providing parking, as necessary, for Contractor personnel working on-site at the Plant. BEP does not provide parking.

3.14 Meetings:

As requested and/or scheduled, attending meetings concerning the Plant, providing as necessary information (e.g. reports, slides, handouts) in support of meetings, taking meeting minutes, within 24 hours of the end of the meeting sending minutes for review and approval to the COR only and providing copies to attendees after approval is obtained.

3.15 Labels:

Using pre-printed labels for Plant sludge containers. The labels, including the numbering/ log system that the Contractor will use shall be reviewed and approved by the COR prior to use if the contractor proposes changing the current labels and/or the current tracking system.

3.16 Trash:

Removing trash from the Plant on a daily basis and taking it to the BEP’s trash collection area located within the Facility. In addition, collecting any metallic trash and scrap metal separately and taking it to the BEP’s metal recycling area located within the Facility for disposal. Cleaning-up individual work areas.

3.17 Vendor Warranties:

The contractor shall maintain a list and record of all active warranties.

3.17.1 Executing all warranty provisions.

3.17.2 Investigating the failure of any equipment or material under warranty, difficulties encountered in the enforcement of any warranties and of instances in which the costs of enforcement would exceed the benefits derived and reporting such instances and findings to the COR.

3.17.3 Ensuring warranties are not voided unless authorized by the BEP. In the event this occurs, the Contractor will be responsible for the warranty repair that has been voided and not authorized by BEP.

3.18 Deliverables:

Providing the deliverables defined herein as well as those listed in Section 8.0 of this document.

3.18.1 General: Deliverables and other documentation submitted by the Contractor in support of the contract shall be compatible with a PC operating in the current BEP version of Windows environment (currently Windows 10) using Microsoft Word, Microsoft PowerPoint, Microsoft Excel, Microsoft Outlook, and Microsoft Project. Microsoft Access is strictly prohibited from use. Deliverables and other documentation

shall be properly marked in order to describe what is being provided i.e. include a title, indication of the period of coverage, the contract number and name of the Contractor.

3.18.2 Document Control: Version control shall be appropriately applied and maintained to Deliverables and other documentation created in support of this effort. This means that when documentation and Deliverables are updated the correct version and date are applied, that the previous version is saved and that submitted changes are appropriately reviewed and approved prior any being implemented. This includes the original submittals when previous documents are used as a basis for the deliverable.

3.18.3 Periodic Review: Deliverables and other documentation shall be reviewed and updated on a periodic basis in order to ensure that it maintains full compliance with contract requirements, updates in Regulations/Publications/Codes, changes in processes, policies and procedures, etc. The minimum review for any document is once per year. Given the amounts of documents required under the performance of this contract, reviews must be staggered and shall not be attempted to be done all at once. All document deliverables that are submitted for approval, as required during performance, must be updated within 5 working days of receiving comments/corrections/technical direction from the COR. Verification of updates will be performed on a periodic basis or as the COR deems necessary in order to satisfy the intent of the update.

3.18.4 Data Rights: The Government will maintain ownership and "unlimited rights to all applications, source codes, and data generated in the performance of and at the end of the task. "Unlimited rights" means the rights of the Government to use, disclose, reproduce, prepare

derivative works, distribute copies to the public, and perform publicly and display publicly, in any manner and for any purpose, and to have or permit others to do so. FAR 52.227-14 – Rights in Data – General will be included in this contract.

3.19 Inventory:

3.19.1 Initial - The Contractor shall conduct an initial inventory of items i.e. materials, supplies, spare parts, tools, etc. within the Plant and the Landover Warehouse within two (2) weeks of award. Findings of this initial inventory shall be documented and provided to the COR for review, reconciliation and approval.

3.19.2 Final - The Contractor shall conduct an inventory of items as noted above one (1) week prior to the expiration or termination of the contract.

3.20 Asset management:

The Contractor shall implement and conduct inventory reviews utilizing Maximo as needed for the proper operation and management of the Plant and in accordance with BEP policy as implemented and augmented throughout the period of performance.

3.21 Quality Control Inspections:

As part of a Contractor's Quality Management System (QMS) (**Ref. Section 8.1.25**), the Contractor shall perform weekly inspections by off-site personnel, individuals who are familiar with wastewater treatment plant operations and this specific contract requirements

and contract management. All aspects of the contract shall be represented and audited in the inspection forms, i.e. plant operations, specific contract items (deliverables, requirements, etc.), and contract management aspects.

3.21.1 Weekly inspection report form(s) shall be developed by the Contractor and submitted for approval for use to the COR during phase-in. Once approved, it/they shall be used as part of the weekly inspection and submitted in accordance with Section 8.1.18.

3.22 Reserved.

3.23 Safety Equipment Inspections: The Contractor shall inspect all safety equipment on a monthly basis, the first full calendar week of every month. The inspections shall be documented on the individual device's inspection tags, with all columns on the tag completed. If a device does not currently have an inspection tag the Contractor will be responsible for placing the tag at or on the device. These monthly inspections will also be a part of the Maintenance Plan. The inspections include, but are not limited to, Fire Extinguishers, Emergency Lights, Emergency Exit Signs, Emergency Eye-wash/showers, etc.

3.24 Conservation: Participating in and following all BEP conservation programs as provided for in the BEP EMS Procedures, Treasury Directives, Procurement Guidelines, etc.

3.25 Recycling Plant: The BEP may be working on improvements involving the design, construction and implementation of and operation of the WSRP throughout the performance of the contract. The Contractor must be aware that tasks undertaken by other contractors in support of the design and installation may be performed within the current Plant. During these activities, the Contractor personnel may be required to wear appropriate construction PPE including hard hats, safety shoes, and hearing protection as appropriate. The Contractor will be required to attend meetings in support of these efforts as requested. The Contractor shall notify the COR as soon as possible if it determines that any of its tasks are affected by the improvements. Once installed, the Contractor will be responsible for operation and maintaining the improvements. This will include developing all documentation for the improvements as is prescribed herein for the plant in a manner consistent with the requirements of this contract. The Contractor will also be responsible for decontamination and cleaning of any equipment that will be removed from service because of improvements in the Plant.

3.26 Wastes: Preparation of the generated hazardous and non-hazardous wastes (hereinafter “sludge”) generated by the Plant, including any instances of spills. Preparation includes, but not limited to; filling, weighing, labeling, packaging, palletizing and moving the applicable containers concerning the sludge generated by the Plant to the identified staging area and/or onto trucks for transportation out of the Plant. The Contractor shall also be responsible for repackaging any returned wet containers and any damaged containers before transport from the Plant as deemed inappropriate for shipment by the COR. The Contractor shall also monitor all containers for this condition and address issues as they occur. **3.26.1** No leaking or damaged containers may be shipped from the Plant. If any additional disposal/remedy costs are incurred by the BEP for containers having lost integrity, containing non-profile materials, or material on the outside of the container, etc., the Contractor shall reimburse BEP for any additional charges to rectify the issue by the BEP’s disposal contractor.

3.26.2 To ensure that container integrity is intact, containers must be closed and stationed for observation for no less than 48 hours before containers will be allowed to be shipped from the Plant.

3.26.3 All hazardous waste containers must be inspected by the COR before being allowed to leave the plant unless the COR or the COR’s delegate, is unavailable. Hazardous waste containers must be moved to the BEP 90 day storage area within 3 days of being filled.

3.26.4 The Contractor shall develop, maintain and submit a Hazardous Waste Record in accordance with Section 8.1.16 of this document. The record shall include the WWPP profile number, the BEP Waste Profile number, the date the container is filled and the date the container is shipped, or leaves the Plant.

3.27 Monitoring and Testing: Conducting and performing sampling and testing of the generated wastewater and sludge in accordance with the Sampling and Testing Plan and as frequently as needed to optimize Plant operations and ensure that the Plant maintains compliance with the

standards as set forth in the Regulations/ Publications/ Code. In addition to Attachment 1, the BEP Wastewater Discharge permit, Attachment 25 provides a listing, schedule and additional information regarding outside laboratory analysis (**Ref. Section 2.1.19**) required under this contact as prescribed in this section. **3.27.1** Duties include operating a composite sampler and recording information concerning the chain-of-custody during compliance sampling and testing. An electronic copy (pdf) of the completed laboratory Chain of custody shall be provided to the COR within twenty-four (24) hours after sampling is completed.

3.27.2 Due to limitations of the Plant's lab, the Contractor shall coordinate, where necessary (discharge permit compliance samples, except for pH) testing performed by an out-side lab that is qualified, experienced and certified to perform such testing. The COR must approve the Contractor's choice in labs if different labs are proposed than the currently used labs or if an issues that arises that causes the current lab to not be able to be used. The Contractor will recommend labs based on the discharge permit requirements. The COR will evaluate the recommended labs and approve the labs for use based on fulfilling the permit requirements.

3.27.3 The Contractor shall provide complete results of the sampling and testing to the COR within ten (10) calendar days of the samples' collection date. In addition to the actual lab results, the Contractor shall review all outside lab analysis results submitted for analysis under this contract and summarize the results as all are compliant with the discharge permit or requirements that are being analyzed for, or there are issues with the results and state the issues.

3.27.4 The Contractor shall develop and submit a Sampling and Testing Plan in accordance with Section 8.1.27 below, and once approved by the COR, implement the plan.

3.27.5 The Contractor shall develop test procedures in coordination with BEP's Office of Quality Operations and the equipment manufacturer to monitor and control the process equipment. These test procedures and process controls must be submitted to the COR for review and approval. This includes the testing of incoming materials to ensure

quality. Although the test procedures and control procedures will be developed in coordination with other parties, it is the sole responsibility of the Contractor to perform the developed and agreed upon testing on a timely basis. This may require the purchase of new test equipment as needed which BEP will purchase if approved. Any additionally acquired test equipment will become the responsibility of the Contractor to operate and maintain the same as all other laboratory equipment in the onsite lab.

3.27.6 The Contractor shall perform Compatibility Testing on new inks, or other materials to ensure that there are no issues with the processing, and operation of the WWPP as needed. The Contractor shall maintain procedures for all compatibility testing and will coordinate with the materials requestors to perform the tests as needed. The Contractor shall issue Compatibility Test reports within 10 calendar days of obtaining all materials required to perform the testing. The

report shall be issued to the COR for review and approval before the material may be approved for use in BEP.

3.28 Storm Water:

Perform any storm water sampling, measurements or analysis as directed by the COR following the principles that are included herein with respect to sampling and analysis of the parameters of the Plant.

3.28.1 The Contractor will be required to manage and maintain storm water abatement measures as deemed appropriate by the applicable storm water requirements throughout the performance of this contract.

3.28.2 The Contractor will be required to perform and document weekly inspections in order to comply with storm water requirements throughout the performance of this contract.

3.28.3 The Contractor shall submit Maximo service requests for issues noted in weekly storm water inspections within 3 calendar days of the inspection's completion, when applicable, and will report issues that require submission of Maximo service requests separately to the COR in addition to the required inspection report within 3 calendar days of the inspection.

3.28.4 The Contractor shall be provided the BEP current Storm Water Pollution Prevention Plan (SWPPP) by the COR. The Contractor shall be responsible for keeping the plan up to date as regulations change and making changes as applicable projects change, dictating needed updates to the plan. Plan updates shall be provided to the COR for review and approval as prescribed herein this PWS.

3.28.5 The Contractor shall be responsible for developing, coordinating, and providing required SWPPP training to contractors associated with applicable projects. The training will be documented, and records of the training shall maintained as part of the SWPPP and provided to the COR within three (3) calendar days of completion of the training.

3.29 Reserved.

3.30 Process Improvements: Throughout performance, the Contractor may submit proposals for Process Improvements. The Government may also request submission of proposals from the Contractor for Process improvements as well. Process Improvements elements will be negotiated and funded at the time of the requirement if needed and will be exercised under the applicable CLIN for engineering labor, equipment and/or supplies (and the corresponding option year CLIN's).

3.30.1 Process improvements are considered changes to the Plant which are not a part of Maintenance or Repair of the Plant but are specifically intended to improve the management, operation, and maintenance of the Plant. For example, Process Improvements may consist of but

are not limited to; **3.30.1.1** Modifying the Plant in order to use new chemicals, new technologies or other methods and processes in the wastewater treatment process,

3.30.1.2 Modifying the Plant in order to meet changes in Regulations/Publications/Code,

3.30.1.3 Substituting, adding or subtracting Materials in order to reduce costs and improve processes and,

3.30.1.4 Making other types of significant improvements in the operation, management and maintenance of the Plant.

3.30.2 The Government has the right to accept or reject proposals submitted by the Contractor and is not responsible for any costs associated with the development of these proposals. The Contractor shall title proposals submitted by them as “Process Improvements – Contractor Proposed”.

3.30.3 In the instance where the Government is making the request for a Process Improvement, the Contractor shall submit proposals for such improvements no later than fifteen (15) business days from the date of written request from the COR or CO. The Contractor shall title such proposals as “Process Improvements – Government Directed”.

3.30.4 The following is a listing of the projects required to be completed by the Contractor during the term of this contract. Materials may yet need to be purchased, or will be provided by BEP and the Contractor will install the materials and implement the projects under the funded labor CLINs herein this PWS. If the Contractor does not fill the labor role CLINs that perform the installations and implementations of the projects, that does not relieve the Contractor from being required to complete the projects at their own cost within the term of this contract. The Contractor shall provide installation and implementation timelines for each of the below projects within 90 days of contract award for approval by the COR. Once approved, the project statuses shall be reported on in the monthly status report as noted in Section 8.1.21.

3.30.4.1 Valve Tagging and ANSI Pipe Labeling: The valves and pipes throughout the plant shall be tagged and labeled in order to facilitate the efficient operation and documentation of the Plant. The system has been designed and tags are obtained by submitting requests to the BEP sign shop through Maximo. The Contractor is required to complete identifying and tagging throughout the plant, where the system has not yet been implemented and incorporate the tags into the Contractor’s system operations documentation.

3.30.4.2 93% Sulfuric Acid Drum Filling Station: There is a requirement for procurement and storage of 93% Sulfuric Acid in 55-gallon drums in the Landover Warehouse to be used as a safety stock supply in instances where there are extended delays in bulk shipments of 93% Sulfuric Acid to the Plant. In the event that 93% Sulfuric Acid cannot be procured in the drums that meet the material specification to fulfill this safety stock storage requirement, the system needs to be installed and implemented that will allow for the filling of drums from the bulk tank

in a safe manner. The system will also allow for filling the bulk tank from drums stored in the safety stock storage location. The new containers will be properly labeled by the Contractor and placed in a safety stock supply storage location. The COR may provide drawings for the Contractor's installation and implementation.

3.30.4.3 50% Sodium Hydroxide Drum Filling Station: There is a requirement to be able to safely provide the BEP Shops with small amounts of 50% Sodium Hydroxide in order for the shops personnel to make up a cleaning solution to flush and clean the lines from the presses to the WWPP. There is also a requirement for procurement and storage of 50% Sodium Hydroxide in 55-gallon drums in the Landover Warehouse to be used as a safety stock supply in instances where there are extended delays in bulk shipments of 50% Sodium Hydroxide to the Plant. In the event that 50% Sodium Hydroxide cannot be procured in the drums that meet the material specification to fulfill this safety stock storage requirement, the system needs to be installed and implemented that will allow for the filling of drums from the bulk tank in a safe manner. The system will also allow for filling the bulk tank from drums stored in the safety stock storage location. The new containers will be properly labeled by the Contractor and placed in a safety stock supply storage location. The COR may provide drawings for the Contractor's installation and implementation.

3.30.4.4 50% Sodium Sulfated Castor Oil Drum Filling Station: There is a requirement for procurement and storage of 50% Sodium Sulfated Castor Oil in 55-gallon drums in the Landover Warehouse to be used as a safety stock supply in instances where there are extended delays in bulk shipments of 50% Sodium Sulfated Castor Oil to the Plant. In the event that 50% Sodium Sulfated Castor Oil cannot be procured in the drums that meet the material specification to fulfill this safety stock storage requirement, the system needs to be installed and implemented that will allow for the filling of drums from the bulk tank in a safe manner. The system will also allow for filling the bulk tank from drums stored in the safety stock storage location. The new containers will be properly labeled by the Contractor and placed in a safety stock supply storage location. The COR may provide drawings for the Contractor's installation and implementation.

3.31 Emergency Technician Support (Ref. Section 2.1.22): Emergency support shall be provided on an "as needed" basis and must be authorized by the CO or COR, or their designate prior to the Contractor obtaining this type of support. Emergency support is

considered to be required to correct failures which constitute an immediate danger to workers, property, impact production or jeopardize the Plant's compliance with Regulations/Publications, specifically the Permit and are separate from the herein prescribed Maintenance services provided by Contractor's personnel whereas Emergency support pertains to emergency situations that may arise during the performance of the contract that require additional or specialized support above and beyond what the Contractor can provide in order to diagnose, resolve or fix the problem. This support excludes any emergencies related to a warranty that requires the Contractor to provide technician services. It also excludes all routine and preventative

maintenance and emergencies created due to actions or lack of action on the part of the Contractor, its personnel or subcontractor.

3.31.1 In these instances the technician(s) responding to the emergency shall be on-site within two (2) hours of the Contractor receiving authorization from the BEP. The COR may grant an exception to the above two (2) hour response requirement depending on the type of emergency and support needed. The technician shall submit an Emergency Technician Report in accordance with Section 8.1.12 of this document and provide it to the COR or authorized individual prior to leaving the BEP facility.

3.32 Calibration of equipment: Conducting and performing calibration of Plant equipment as needed (all pH, temperature, and ORP meters must be calibrated/verified at least weekly by Plant personnel) in order to maintain Plant operations and ensure that the Plant maintains compliance with the standards as set forth in the Regulations/ Publications/ Codes. **3.32.1 (Ref. Section 2.1.19)** As required, calibrating all process control equipment in the Plant on an at least semi-annually basis by utilizing outside personnel proficient in the calibration of the controls. Equipment includes, but is not limited to; tank level gauges, flow meters, scales, lab balances, ORP and pH, temperature probes and other laboratory equipment, assuring the information provided on the computer for all of the process equipment and the Programmable Logic Controller (PLC) for the PWPP is the same as the level, flow rate, and pH in the tanks, and pipes, and assuring the feedback loops from the computer to the instrumentation are accurate. Calibration services shall be performed by a qualified technician and shall conform to industry standards for the equipment being calibrated. Certificates of calibration shall be provided for each piece of equipment that is calibrated and/or verified.

3.32.2 Although the Contractor is not required to have the lab hood air flow calibrated on a periodic basis, the Contractor shall provide the filters (from the contractor managed supplies) to be changed on the developed PM basis, to the lab hood inspection contractor that will perform the lab hood air flow calibration.

3.33 PLC Software Back-up. The Contractor will be responsible for backing-up the PWPP and WSWPP PLC programs on at least a semi-annual basis. The program back-ups shall be provided to the COR on CD/DVD/BD media in protective sleeves, labeled and dated accordingly for each system.

3.34 Process Improvements Engineering (Ref. Section 2.1.21): Performing any and all necessary engineering tasks and duties (e.g. civil, mechanical, chemical and electrical) required supporting Section 3.30 Process improvements. Engineering work will be assigned by task orders within the contract. Proposals for task orders must include a scope of the work to be completed, hours to complete the objective, resources required and time schedule.

Proposals will be submitted to the COR for approval. No work may begin on a task order until it has been approved by the COR and issued a specific task order number.

3.35 Training: The Contractor shall ensure that all personnel have been properly trained and certified in performing Services as specified herein. The Contractor shall also ensure that all employees attend the appropriate subsequent and/or recurrent training required during the performance of the contract in order to remain fully trained, certified and qualified to perform Services throughout the life of the contract. The Contractor shall be responsible for maintaining records of personnel training, certifications, licenses and qualifications throughout the performance of the contract and make them available to the COR upon request. The Contractor shall submit written confirmation to the COR that training has been completed.

3.35.1 Training Plan: The Contractor shall develop and submit a Training Plan in accordance with Section 8.1.31 below and once approved by the COR, implement the plan. The Plan shall include a description of every class, a matrix of all required training and the Contractor personnel that is required to accomplish each specific training class with target dates for each training.

3.35.1.1 The Contractor shall notify, in writing, the COR of the status of and completion of training on a monthly basis in the Monthly Status Report (**Ref. Section 8.1.21**) and include certificates of completion for each Contractor when/as each training class is completed.

3.35.1.2 The Contractor will also be required to update the plan as training needs change within thirty (30) calendar days of the change. Changes to the plan will be submitted for approval to the COR.

3.35.1.3 The Contractor will be additionally required to report on BEP required training as it occurs throughout the period of performance of this contract as noted above.

3.35.2 Mandatory Training Requirements: Unless otherwise already obtained by Contractor personnel within the previous twelve (12) months and the associated certification provided to the COR in writing, the following training is mandatory for all Contractor personnel performing under the contract and shall be conducted as indicated below. Copies of certifications of previous training must be approved by the COR in order to receive credit for that training towards this effort.

3.35.2.1 29 CFR 1910.134 Respirator Training shall be conducted within sixty (60) calendar days after contract award and annually thereafter.

3.35.2.1.1 The Contractor shall certify, in writing, that all personnel performing under the contract are fit to wear respirators to the COR as part of the annual medical testing requirement within thirty (30) calendar days of the medical evaluation.

3.35.2.2 Plant Safety First Aid Training shall be conducted annually for the personnel administering first aid to other Contractor's employees. This training shall be American Red Cross certified training.

3.35.2.3 As prescribed by the BEP's policies and procedures identified Contractor personnel shall complete the BEP's required internal training classes.

3.35.2.4 Plant Standard Operating Procedures. Training in the Plant Standard Operating Procedures shall be performed within sixty (60) calendar days after contract award and annually thereafter by the Contractor.

3.35.2.5 49 CFR 172.704 Hazardous Materials Transportation training shall be conducted within sixty (60) calendar days after contract award and recurrent training shall occur every other year thereafter or as required by regulations, whichever is sooner.

3.35.2.6 Forklift training shall be conducted within sixty (60) calendar days after contract award and annually thereafter, as applicable.

3.35.2.7 29 CFR 1910.120 Hazwoper Training shall be conducted within sixty (60) calendar days after contract award and refresher training annually thereafter as required by regulations.

3.36 Corrosion Monitoring (Ref. Section 2.1.19): Conducting and performing corrosion monitoring of the Plant's sulfuric acid piping and tank in order to prevent failures of the tank and associated piping that may potentially cause any damage to the Plant or injury to personnel. The monitoring must meet the requirements specified in Attachment 27 of this document. All reports of Corrosion Monitoring shall be submitted to the COR within forty-five (45) calendar days after the completion of the test, whether the feed and fill piping only or additionally the sulfuric acid storage tank. If any findings are reported by the tests, the Contractor shall create a matrix of the findings and their reference from the report. The matrix will provide the system where the finding was located, the proposed remedy, the Maximo work order number, the Contractor who is scheduled to perform the repair, the date the repair was made, and the follow-up inspection date to ensure the repair was sufficient, and who performed the follow up inspection. This matrix shall be reported in the subsequent Monthly Status Reports until all repairs have been completed and verified.

4.0 Contractor Personnel:

All Contractor personnel performing under this effort shall be competent, dependable, knowledgeable, trained, certified and experienced in and qualified in performing the Services as described herein. Refer to Section 4.10 below for additional details.

Personnel fulfilling the roles of the Program Manager, Plant Manager, and the Assistant Plant Manager must be able to obtain and maintain a BEP High Risk Public Trust Security Clearance. All other roles must be able to obtain and maintain a BEP Low Risk Public Trust Security Clearance. All Contractor personnel shall be knowledgeable in how to use Human– Machine Interface (HMI)/ SCADA software which operates the applicable portions of the Plant. This software is run on various computer(s) that are located in the Plant office and in the plants. The operation of the computers is the Contractor's responsibility. The maintenance of these computers is the responsibility of BEP. When maintenance of the computers is necessary, the Contractor will work with the BEP to facilitate the required maintenance.

4.1 Conduct: Contractor personnel shall conduct themselves at all times in a proper, professional, friendly, courteous, businesslike manner, and are subject to the same policies, rules and regulations as BEP employees. In addition, Contractor personnel shall demonstrate and maintain open and professional communication with other individuals while on the job.

4.1.1 Sleeping: No Contractor shall sleep or “nap” while on BEP property. Any Contractor observed sleeping or napping whether on shift or off shift, on BEP property shall be immediately removed from the contract and must be replaced by the Contractor with the entire cost of replacement being solely the responsibility of the Contractor.

4.2 Dress: Contractor personnel performing under this effort shall dress in uniforms that are of the same color and type typically worn for similar customers and include the individual’s name affixed in a permanent manner that is easily readable. A “taped” name on a uniform is strictly prohibited. Uniforms shall be maintained in good repair and kept clean. Contractor personnel shall also wear steel toe shoes in accordance with ANSI standards while working at the Plant. PPE and other identified Tools and Equipment shall be worn as appropriate. **4.2.1** Contractor personnel must be in their uniforms at the start of their designated shift. They shall not be going to get into their uniforms at the beginning of their shift. They must be in uniform and ready for work at the beginning of their designated shift.

4.3 Appearance: Contractor personnel shall present a neat and well-groomed appearance at all times while performing their duties at the Plant. Neat and well-groomed appearance includes the ability to be fit to wear respirators as per 29 CFR 1910.134 Respiratory Protection. Facial hair that obstructs the proper wearing of a respirator is strictly prohibited.

4.4 English Language Requirement: Contractor personnel performing under the contract shall be fluent in the English language both verbally and written and be able to read and understand English.

4.5 Citizenship: Contractor personnel performing under the contract shall be U.S. citizens.

4.6 Reserved.

4.7 Contact information: The Contractor shall provide a Personnel Contact List as indicated in Section 8.1.23 of this document.

4.8 Software (Ref. Section 6.2): Contractor personnel shall be knowledgeable and experienced in the use of Human–Machine Interface (HMI) or System Control and Data Acquisition (SCADA) software and maintenance management software. In addition, they shall be proficient in the use of Microsoft Outlook, Microsoft Word, and Microsoft Excel. The use of Microsoft Access is strictly prohibited because BEP does not support the program or any software that uses it as a basis for its function.

4.8.1 All Contractors shall check their BEP issued email every day at least once each shift to keep up to date with information pertinent to the operations of the BEP.

4.8.2 All Contractors shall check their Maximo assignments every day at least once per shift to keep up to date with information pertinent to the operation of the WWPP.

4.9 Escort: Contractor personnel who have the appropriate BEP security clearance may be required to or requested by the Government to act as an escort to individuals or groups of individuals needing access to the Plant.

4.10 Specific Roles and Qualifications: Contractor personnel cannot perform multiple roles. Only the roles listed in this section will be utilized by the Contractor. The Contractor is strictly prohibited from referring to a role provided by a different name, for the purposes of this Contract. Only the role names and associated education, experience and capabilities listed in this section may be used.

In order to be considered as having the requisite experience for each role, the experience must have been gained in the last 15 years. Any experience gained prior to 15 years ago is not considered relevant experience and therefore may not be used to indicate an individual meets the requirements of the role for which they are being proposed. The resume' must clearly support that the candidate meets the required qualifications to be considered for the applicable role. Merely stating or certifying that an individual meets the required qualifications is not sufficient and is not acceptable.

The Contractor shall provide all proposed candidate's resume to fill a role to the COR for review. After review, the COR may request that the candidate be interviewed by the COR, if they deem it necessary. The COR, their delegate or CO must approve the candidate before any onboarding process may begin. In no instance shall the Contractor propose a candidate that does not clearly meet the qualifications for the role that they are proposed to fill. All labor positions are under Sections 2.1.1 through 2.1.18.

4.10.1 Managerial Roles:

4.10.1.1 Program Manager: Individuals performing the plant manager role shall possess at a minimum:

4.10.1.1.1 Education: A bachelor's degree in an applicable science (e.g. chemistry, biology, physics), or an engineering discipline (e.g. civil, mechanical, chemical) pertaining to the work they are performing, plus four (4) years of technical experience in an industrial wastewater pretreatment, chemical process plant, or similar industrial facility. As an alternative, a High School diploma or General Education Development (GED) certificate, plus eight (8) years of experience working in a Program Management/Managerial role in the industrial wastewater, chemical processing, or similar industrial field, may substitute for a bachelor's degree.

4.10.1.1.2 Experience: A minimum of four (4) years with a bachelor's degree of related technical experience, or eight (8) years of related technical experience in a management capacity, including the following responsibilities: 1. Contract Management and Deliverables

2. Environmental Regulations Oversight

3. Safety Management

4. Stakeholder Management

4.10.1.1.3 Capabilities: Demonstrated capabilities to work with a wide degree of personnel technical levels; Oversee technical, schedule, and cost performance of programs through subordinate managers and/or supervisors; managing subordinates and/or experienced professionals and technical personnel; ensuring compliance with contract requirements and company policies.

4.10.1.2 Plant Manager: Individuals performing the plant manager role shall possess at a minimum:

4.10.1.2.1 Education: High School diploma or General Education Development (GED) certificate.

4.10.1.2.2 Experience: Four (4) years as plant manager or five (5) years as an assistant plant manager in overseeing the general operation of an industrial wastewater pretreatment plant.

4.10.1.2.3 Capabilities: Demonstrated capabilities in coordinating with multi- disciplinary trades, coordinating individuals and multiple tasks, managing personnel, providing timely and prudent direction and guidance, handling and resolving issues and overseeing the operation of an industrial wastewater pretreatment plant. Have strong communication and writing skills.

4.10.1.3 Assistant Plant Manager: Individuals performing the assistant plant manager role shall possess at a minimum:

4.10.1.3.1 Education: High School diploma or General Education Development (GED) certificate.

4.10.1.3.2 Experience: Four (4) years as an assistant plant manager or five (5) years as an industrial wastewater pretreatment plant supervisor.

4.10.1.3.3 Capabilities: Have demonstrated capabilities in coordinating work, troubleshooting issues, supervising and managing personnel, providing timely and prudent direction and guidance in the operation of an industrial wastewater pretreatment plant. Have strong communication and writing skills.

4.10.1.4 Maintenance Manager: Individuals performing the maintenance manager role shall possess at a minimum:

4.10.1.4.1 Education: High School diploma or General Education Development (GED) certificate.

4.10.1.4.2 Experience: Four (4) years as a maintenance manager overseeing the general maintenance of an industrial wastewater pretreatment or chemical process plant. Must have experience in utilizing computerized maintenance management software. General manufacturing (non-chemical in nature) maintenance experience is not acceptable.

4.10.1.4.3 Capabilities: Must have demonstrated capabilities in coordinating and scheduling work, troubleshooting issues, supervising and managing personnel, providing timely and prudent direction and guidance in the maintenance of an industrial wastewater pretreatment or chemical process plant. Have strong communication and writing skills.

4.10.2 Non-Managerial Roles:

4.10.2.1 Supervisor: Individuals performing within a supervisor type of role shall possess at a minimum: **4.10.2.1.1 Education:** High School diploma or General Education Development (GED) certificate.

4.10.2.1.2 Experience: Individuals performing within a supervisor type of role shall possess at a minimum four (4) years of experience in supervising operators working in an industrial wastewater pretreatment or chemical process plant.

4.10.2.2 Operator: Individuals performing within an operator type of role shall possess at a minimum:

4.10.2.2.1 Education: High School diploma or General Education Development (GED) certificate.

4.10.2.2.2 Experience: Four (4) years of experience in the operation of a wastewater pretreatment plant.

4.10.2.3 Laborer: Individuals performing within a laborer type of role shall possess at a minimum:

4.10.2.3.1 Education: High School diploma or General Education Development (GED) certificate

4.10.2.3.2 Experience: Knowledge of the proper handling of chemicals and safety aspects of chemicals and equipment including using a forklift, pallet jack, and simple hand tools and have experience in working around chemicals.

4.10.2.4 Laboratory Technician: Individuals performing the laboratory technician role shall possess at a minimum: **4.10.2.4.1 Education:** A bachelor's degree in an applicable science (e.g. chemistry, biology, physics), or an engineering discipline (e.g. civil, mechanical, chemical) pertaining to the work they are performing. As an alternate to having a bachelor degree, an associate's degree in the above listed disciplines can be used in conjunction with an additional 2 years of experience as required in Section 4.10.2.1.2 to substitute for not having a bachelor's degree.

4.10.2.4.2 Experience: A minimum of a bachelor's degree including the techniques listed or two (2) years with an associate's degree of related laboratory experience including the following techniques:

1. Thermal gravimetric analysis
2. Ultra-Violet/Visible/Near infra-red spectroscopy
3. Titration
4. Statistical data processing
5. Lab test reports
6. Laboratory quality control methods

4.10.2.4.3 Capabilities:

Be able to work with a wide degree of personnel technical levels; develop laboratory test methods; program laboratory equipment as necessary; develop, implement, and complete chemical studies to understand and document the chemical functions and interactions of process tanks; interpret and explain technical information into easily understood wording; provide project status reports; and other such requirements of wastewater pretreatment and/or chemical process plants as needed.

4.10.2.4.3.1 Be able to become aware of and familiar with, the safety and environmental requirements, compliance requirements, the relevant technologies and equipment of wastewater pretreatment and/or chemical process plants.

4.10.2.4.3.2 Be able to address problems, review, analyze and integrate the technical work of others.

4.10.2.4.3.3 Be able to perform non-routine and complex assignments involving responsibility for planning and conducting a complete project of relatively limited scope or a portion of a larger and more diverse project.

4.10.2.5 Office Automation Assistant: Individuals performing within an office automation assistant type of role shall possess at a minimum:

4.10.2.5.1 Education: Associates degree or successful completion of a minimum 2- year vocational technical training above High School diploma or General Education Development (GED) certificate.

4.10.2.5.2 Experience: Four (4) years of related work experience.

4.10.2.5.3 Capabilities:

Be able to perform clerical support in an office/industrial setting to include utilizing automated software (e.g. Microsoft Excel, Microsoft Word, Microsoft PowerPoint, Microsoft Outlook) to setup, input, consolidate, extract data and producing and editing reports, correspondence, training records or other documents. Type/word-process (minimum of 30 wpm), edit, format, and print a variety of documents including correspondence, reports, technical notes, presentation, briefing materials and other deliverables. Make necessary corrections in document formatting, grammar, capitalization, punctuation, and spelling.

4.10.2.6 Maintenance technician: Individuals performing within a maintenance technician type of role shall possess at a minimum:

4.10.2.6.1 Education: High School diploma or General Education Development (GED) certificate.

4.10.2.6.2 Experience: Four (4) years of related work experience.

4.10.2.6.3 Capabilities:

4.10.2.6.3.1 Be able to perform repair, maintenance, installation, and calibration of equipment that is electrical, electronic, and mechanical in nature. Must be able to install equipment, i.e. tanks, pumps, piping, mixers, motors, electrical, and electronics. Must have comprehensive knowledge of mechanical and electrical/electronic principles related to complex multi-component assemblies and devices; for example, various material transfer pumps and electrical components.

4.10.2.6.3.2 Be able to use common and industrial hand tools and equipment such as wrenches, screwdrivers, grease guns, saws, drills, air tools, VOA meters and pumps.

4.10.2.6.3.3 Be able to use electronic/electrical test equipment to diagnose and correct equipment and control system problems.

4.10.2.6.3.4 Be able to read and interpret drawings, schematics and blueprints.

5.0 General Information

5.1 Place of Performance: The place of performance is the Bureau of Engraving & Printing's Washington, DC facility located at:

301 14th Street SW, Washington, DC 20228

5.2 Period of Performance: The period of performance includes a Phase-in Period (**Ref. Sections 2.1.1 through 2.1.9**), one (1) 12-month Base Year, and four (4) 12-month option years that may be exercised. The Phase-in Period of this contract shall be from 1 NOV 2026 through 31 OCT 2031. The Base Period of this contract shall be from 1 NOV 2026 through 31 OCT 2027. Refer to the SF1449 form for further details.

5.3 Hours of Work: Normal operating hours are twenty-four (24) hours a day, seven (7) days a week, three hundred sixty-five (365) days a year, including all Federal Holidays and BEP's Y.E.S. Period. The BEP's Y.E.S. Period typically occurs between December 25th and January 1st of each year. The COR will notify the Contractor of any change to the schedule. The Federal Government Holidays consist of:

New Years Day	1st day of January
Martin Luther King Jr.'s Birthday	3rd Monday of January
Presidents Day	3rd Monday of February
Memorial Day	Last Monday of May
Juneteenth	19th day of June
Independence Day	4th day of July
Labor Day	1st Monday of September
Columbus Day	2nd Monday of October
Veterans Day	11th day of November
Thanksgiving Day	4th Thursday of November
Christmas Day	25th day of December

5.4 Contractor required Licenses/Certifications: Individuals performing within the roles of assistant plant manager or supervisor, shall hold a current Association of Boards of Certification (ABC) Class III or higher Wastewater Treatment or equivalent certification. Operators shall hold a current Association of Boards of Certification (ABC) Class II or equivalent certification. In addition, individuals performing within the role of plant manager shall hold a current Association of Boards of Certification (ABC) Class IV certification or equivalent. The COR will make the appropriate determination and approval or rejection concerning equivalency. Training must be provided by the Contractor for obtaining the required certifications if needed; and maintaining certifications where needed; and shall be included in the Training Plan for each individual.

5.4.1 In instances where Contractor personnel do not have this type or full level of certification, the Contractor shall have them obtain the appropriate ABC wastewater certification or equivalent within the maximum timeframes as outlined below:

Plant Manager: Class IV certification, to be achieved within 12 months of date of contract award. Progress must be shown as follows: Class I shall be achieved within 3 months of contract award. Class II shall be achieved within 6 months of contract award. Class III shall be achieved within 9 months of contract award. Class IV shall be achieved within 12 months of contract award. If the

contractor filling the role however begins with a Class II certification, they must achieve the Class IV within 6 months; if beginning with a Class III they must achieve the Class IV within 3 months.

Assistant Plant Manager and Supervisors: Class III certification, to be achieved within 9 months of date of contract award. Progress must be shown as follows: Class I shall be achieved within 3 months of contract award. Class II shall be achieved within 6 months of contract award. Class III shall be achieved within 9 months of contract award. If the contractor filling the role however begins with a Class II certification, they must achieve the Class III within 3 months.

Operators: Class II certification, to be achieved within 6 months of date of contract award. Progress must be shown as follows: Class I shall be achieved within 3 months of contract award. Class II shall be achieved within 6 months of contract award.

If an individual is unable to obtain the required certification within the specified period as outlined above, the individual will be removed immediately and replaced at the Contractor's cost with an individual who already has the required final certification.

5.5 Security Considerations: SECURITY CLEARANCE OF CONTRACTOR'S EMPLOYEES

5.5.1 CONTRACTOR FITNESS (ONBOARDING PROCESS) [JUN 2014]

Contractor Access and Background Clearance. The bureau has been delegated authority from Office of Personnel Management (OPM) to conduct background investigations and to make suitability determinations for employment and facility access per 5 CFR 731. As identified by the Bureau, Contractor and subcontractor employees shall be subjects of background investigations, conducted by the BEP Office of Personnel Security, before assignment to performance of the work or **before facility access is granted**.

The COR shall provide the Contractor with the document Contractor Request for Investigation on e-QIP within three (3) calendar days after contract award. When this form is transmitted to the COR electronically to begin the onboarding process, it must be submitted securely/encrypted to protect the individual's Personally Identifiable Information (PII).

After receipt of the above form, the Contractor shall ensure that all contractor employees and subcontractor employees complete the e-QIP application within the time allotted. Only contractor employees and subcontractor employees identified in the contractor's proposals as direct labor requiring facility access to the BEP on a regular basis will be processed for agency access clearances and subsequently be provided authorized access to the Bureau if the agency access clearance is favorably completed. Upon notice by the COR that the Internet database known as "e-QIP" has been initiated for their employees, the contractor's non-key personnel employees will have **ten (10) calendar days** to access the "e-Qip" database, or the access will be cancelled. If the online questionnaire is not completed within the ten (10) calendar days, the

system will automatically delete the employee's name from the database. The Contractor is responsible for ensuring that their employees successfully complete the

e- QIP on-line questionnaire in a timely manner. Once the e-Qip Application has been successfully completed the COR will notify the contractor that the employee has been accepted and he can come in and be fingerprinted. At that time the additional forms listed will be issued to the contractor that will need, by the employee, to be completed and submitted at the time the employee arrives to be fingerprinted, which is the final process needed to start the Security Clearance process.

1. Form 306, Declaration for Federal Employment.
2. Criminal Records Release
3. Disclosure and Authorization
4. HSPD-12, Homeland Security Presidential Directive 12.

Once all documents have been completed, the Contractor shall coordinate with the COR to schedule a time for all contractor and subcontractor employees to be fingerprinted at the BEP.

The Bureau reserves the right to deny access to its facilities if the contractor or subcontractor employee is deemed unsuitable, based upon adjudicative guidelines established in 5 CFR 731& 732, Executive Orders 10450 and 12968, and BEP policies and directives. **Failure to submit the required security information or to truthfully answer all questions contained in security questionnaires and forms may constitute grounds for denial of agency access clearance.**

Please note that if an individual or individuals, who have been approved by NBIS eApp, do not come in within seven (7) calendar days to be fingerprinted, that individual or individuals paper work is purged from the system, and the individual will have to apply for and complete a new NBIS eApp application before any additional action can be taken in the security application process.

Effective immediately, the Bureau will only provide escorts for only those individuals, who have completed the NBIS eAPP requirement and have been fingerprinted. These individuals will be allowed on site while their paperwork is being reviewed by OPM and the BEP Office of Personnel Security Division.

5.5.2 PERSONAL IDENTIFICATION VERIFICATION [JUN 2014]

All contractor personnel performing under this order, contract, or agreement are required to participate in the Personal Identification Verification (PIV) process and will be required to wear a PIV badge while working at the BEP. The contractor must submit their requests for a PIV card through the COR for approval. Once COR approval is obtained, and a Physical Security Request form has been signed by the COR, the PIV office will coordinate the necessary appointment with the contractor.

5.6 Badges: A BEP issued PIV identification badge will be provided by the Government for Contractor personnel performing under this effort. The identification badge shall be worn by Contractor personnel above the waist, clearly visible, with picture side front forward at all times while on-site at BEP Facilities. The only exception to this requirement is when the Contractor is performing as an entrant in a Confined Space event. Upon exiting the confined space, the Contractor must wear the respective badge. No other identification of the Contractor or employee shall be worn or displayed on the uniform unless required by law or other formal agreement. All issued badges are to be returned to the COR as Contractor personnel are dismissed or terminated, or upon termination or expiration of the contract.

5.7 Section 508 Compliance: This is not applicable under this contract because per BEP IT policy any information that is stored on a shared drive within the IT infrastructure is not required to be subject to Section 508 requirements. If this policy is changed during the life of this contract however, the Contractor will be required to comply with Section 508 as applicable under BEP IT policy.

5.8 Interface Coordination: The Contractor will be required to coordinate their work or interact with other contractors, other Federal or Local agencies, and BEP employees. This may be done only as strictly directed by the COR or their delegate. **5.8.1 Email Signature:** Whenever the Contractor or any subcontractors communicates with anyone using the BEP email system or in to the BEP email system, the Contractor shall provide an email signature for that Contractor that must include the following information at a minimum: **5.8.1.1** First Name, Middle Initial, Last Name, Suffix, if applicable;

5.8.1.2 Official Company Name;

5.8.1.3 Company Contact Address;

5.8.1.4 BEP Room Number, if applicable;

5.8.1.5 BEP Phone Number, if applicable;

5.8.1.6 BEP Fax number, if applicable;

5.8.1.7 Office Phone Number, if different from above;

5.8.1.8 Office Fax number, if applicable.

5.9 Travel: No travel costs are associated with this contract.

5.10 Other Direct Costs: ODC's for incidental supplies shall only be paid when authorized by the Government.

5.11 Post Award Conference: The Government will schedule and conduct a post award meeting with the Contractor after contract award. The objectives of this meeting would be to; introduce key participants and explain their roles, review Deliverables, review the performance work

statement and tasks to ensure a common understanding of the requirements and objectives as well as other matters of importance and relevance. The day(s) and time(s) of any such a meeting will be determined after contract award.

5.12 Task Order/Contract Transition: The Contractor may need to participate in a Transition Period (i.e. a Phase-In Period and/or Phase-Out period) in order to ensure a proper, orderly, smooth and successful transition of work from one contractor to another. Prior to and during these periods the Contractor shall begin preparing for the transition of responsibility in order to ensure that the succeeding contractor is capable and able to assume full responsibility at the completion of the transition. **5.12.1 Phase-In period (Ref. Sections 2.1.1 through 2.1.9):** The Contractor shall take all actions to ensure a proper, orderly, smooth and successful transition of work from the predecessor contractor to themselves; thereby ensuring their ability to assume full responsibility of performance of the contract. During this Phase-In period, the Contractor shall become familiar with the Plant and the work and personnel requirements of the contract. This includes, but is not limited to; obtaining security clearances, hiring personnel, obtaining documentation, meeting any required training requirements, developing plans and procedures (e.g. Quality Control Program), establishing a program/management office and participating in meetings with the BEP, contractor and other concerned parties to discuss the transition.

5.12.1.1 During the Phase-In period, the Contractor will be provided copies of existing policies and procedures as well as plans that are used in the support the Plant. The Contractor may use this information as a guide in developing its own policies and procedures in order to satisfy some of the Deliverable requirements outlined in Section 8.0 below. They are however strictly prohibited from using the provided documents as their own.

5.12.2 Phase-Out period: The Contractor will be required to participate in a Phase-Out period in order to ensure a proper, orderly, smooth and successful transition of work from one contractor to another. Prior to and during this period the Contractor shall begin preparing for the transition of responsibility in order to ensure the succeeding contractor is capable and able to assume full responsibly at the completion of the Phase-Out period. Some examples include but are not limited to; (i) the Contractor shall provide the applicable Deliverables identified in Section 8.0 of this document along with other pertinent information to the Government, (ii) hold meetings with the BEP and other parties to discuss the transition.

The Phase-Out period is for the Contractor to; (i) provide orientation and on-the-job training to the succeeding contractor personnel concerning the operation, management, projects and maintenance of the Plant and (ii) turn over applicable documentation, equipment, materials and/or other items used in support of and purchased under the contract. During this Phase-Out period, the Contractor shall remain responsible for the performance of Services until the end of the Phase-Out period wherein the succeeding contractor will assume full responsibility for all areas of operations in performance of the Services.

5.12.2.1 The BEP estimates the Phase-Out period being no more than eight (8) weeks in length and occur in conjunction with the period of performance of the contract. Required manning for the Phase-Out period is not expected to exceed the Contractor's defined manning requirements in support of this effort. If as part of the Phase-Out period additional staff or services are requested (e.g. classroom training) by the BEP to support the Phase-Out period, this shall be subject to negotiation.

5.13 Subcontracting: Subcontracting shall be performed in accordance with Attachment A, Subcontracting Plan or the prime contractor's master subcontracting plan.

6.0 Government Furnished Resources

The Government shall provide the equipment, software, facilities, materials and supplies, information and services referenced below without cost to the Contractor and in an "As-Is" condition. Government-furnished Property (hereinafter GFP) is inclusive of Government provided equipment, software, facilities, materials and supplies, and information.

6.1 Equipment: Attachments 7, 9, and 10 of this document provides a listing of the equipment to be provided by the Government in performance of this contract. Any equipment not specifically listed therein is the responsibility of the Contractor.

6.2 Software: The Government will provide the software and associated hardware that operates the Plant. The Government will be responsible for the maintenance of this software and associated hardware. The Contractor is responsible for coordinating with the Government on the scheduling of the software maintenance as/if needed.

6.3 Facilities: The Government will provide the BEP Plant as defined herein for use in performance of this effort. Space within the Plant may be used by the Contractor for offices, storage area, or other requirements for the performance of this contract only.

6.4 Supplies and Materials: The Government will provide any existing inventory of supplies and materials remaining from the previous contract. Supplies and materials may consist of, but not be limited to; chemicals, repair parts, tools, PPE, materials and lubricants. **6.4.1** The Government may also allow the Contractor, during the performance of the contract access to supplies contained in the BEP's storeroom to be utilized for the operation and maintenance of the Plant.

6.5 Information: The following information will be provided by the Government in performance of the effort; **6.5.1** "As built" drawings of the current Plant from 1992 showing the mechanical, electrical, architectural and structural design of the Plant.

6.5.2 Operations Manuals and associated documentation for the existing Plant.

6.5.3 As built drawings of the new equipment from installation showing the mechanical, electrical, architectural and structural design of the Plant.

6.5.4 Operations Manuals and associated documentation for the new equipment from the manufacturer.

6.5.5 The Government will also provide various policy and procedure documents and other examples concerning the current operation, management and maintenance of the Plant. These documents and examples are to act as a guide to the Contractor and not as a template to use on how to perform the Services instead the Contractor is responsible for developing the policies and procedures on how they will perform these Services.

6.6 Services: Services to be provided by the Government include: **6.6.1 Security:** The Government will provide general security of the Facility, including a security system.

6.6.2 Plant Overview: The Government will provide a basic overview of the Plant, Plant equipment and general operations after contract award; however, this is not similar to or to the extent of the orientation and training provided under Transition.

6.6.3 Hazardous and Non-Hazardous Waste Disposal: The Government will provide for the disposal of all hazardous and non-hazardous waste generated at the Plant.

6.6.4 Reporting: The Government will be responsible for reporting to outside organizations or agencies, as required by law, regarding the operation, management, engineering, and maintenance of the Plant. Contractor personnel shall not, at any time during the period of performance of the contract, represent themselves as employees or agents of the U.S. Government. The Contractor shall have no responsibilities for reporting to outside environmental regulatory agencies. This shall be a BEP responsibility only.

6.6.5 Facility: The Government will be responsible for the maintenance of utilities and fire suppression system supplied to the Plant as well as the HVAC system and security system. In addition, the Government will be responsible for the maintenance of the building structure, all doors and the Security Office.

6.6.6 Utilities and Fire Suppression System: The Government will furnish existing utilities services as currently installed in the Plant such as water, electric and gas and existing fire suppression system for Contractor use in performance of the contract. All extensions, wiring, hoses, etc., required for connection to such utilities or fire suppression system or security system shall be furnished by the Contractor. The Contractor will be required to participate in all BEP utility conservation programs.

6.6.7 Telephone: The Government will provide telephone equipment and services for local and on-site use. The Government provided telephone service shall be used for only official Government business. Long distance and Federal Telecommunications System (FTS) telephone equipment and services will not be provided by the Government. The Contractor is responsible for procuring and installing of equipment and service for obtaining such services as well as paying for usage.

6.6.8 Internet Access: The Government will provide internet access. Usage shall be limited to and conducted in strict accordance with BEP policy. The Contractor is strictly prohibited from viewing any videos of any type on Government provided equipment except those associated with required training.

6.6.9 Training: The Government will provide BEP internal training as noted herein. The Contractor is required to complete all BEP internal training throughout performance of the effort. All other training that is required during performance of this effort will be the sole responsibility of the Contractor and is not reimbursable.

6.6.10 Movement of Materials: The Government will provide transportation for those Materials stored at the BEP Landover Warehouse to the BEP Facility's loading dock. The Contractor is required to move the Materials into the Plant from the hall that the Materials will be delivered. The delivery of current bulk chemicals required under this contract should only occur between the hours of 1:00 a.m. and 4:00 a.m. local time. The delivery of future bulk chemicals may change as conditions dictate. The Contractor will be notified of the changes in delivery times by the COR as applicable. Skids of chemicals shall be delivered to the D Street loading dock as noted below. In addition, all the sludge box shipments shall be occur between the hours of 1:00 a.m. and 4:00 a.m. local time from the Plant dock, however this may change as well as conditions dictate. The delivered Materials must be moved into the Plant within 4 hours of being delivered to the basement hall to prevent blocking the hall.

6.6.11 BEP's Plant Information

6.6.11.1 Plant Delivery Location: Items needed to be delivered to the Plant shall be delivered to the following address:

The Bureau of Engraving and Printing Annex Building

Shipping and Receiving

301 14th Street, S. W.

Washington, D. C. 20228-0001

Receiving hours for deliveries are **8:00 a.m. to 2:15 p.m.**, local time, Monday through Friday, excluding U.S. Government holidays and BEP year-end shutdown (which normally occurs between December 24 and January 1). The Contractor shall call the BEP appointment line at (202) 874-2333 at least twenty-four (24) hours in advance to schedule approximate delivery times.

The appointment line is staffed from 8:30 am. to 2:30 pm. Monday through Friday. A voice mail message maybe left after normal working hours. If a message is left, the Contractor must wait for

a call back from Shipping and Receiving to obtain a delivery appointment time and date. The following information should be provided:

Name of Sender (e.g., Contractor) Name of Carrier

Mode of Transportation (e.g., van, truck, etc.) Purchase Order Number

Contract Number

Total Number of Cartons or Pallets Total Weight

Name of Recipient Recipient Phone Number

****Note the following loading dock limitations for deliveries made to Washington D.C.: Over the road vehicles having an overall height exceeding 12'6" (3.8 meters) empty, or an overall length exceeding 42' (12.8 meters) CANNOT be accommodated at our receiving platform.***

6.6.11.2 Plant Truck Well Dock: In addition, to the above, the Plant's truck well dock (located on the 15th Street) may be used during the day, however, not between 4:00 AM and 7:30 AM and not between the hours of 8:00 PM - 12:00 AM as it is scheduled by the Government for other deliveries and shipments. The Plant truck well dock is used for deliveries of bulk chemicals and typically shipments of sludge boxes between 1:00 AM - 4:00 AM. These times may be altered for the benefit of BEP operations. The contractor shall follow the same procedures above in regards to scheduling deliveries. In addition, provide notification to the COR.

6.6.11.3 BEP's Landover Warehouse Information: Items needing to be delivered to the BEP Landover Warehouse shall be delivered to the following address:

U. S. Department of the Treasury Bureau of Engraving and Printing

3201 Pennsy Drive, Landover, MD 20785

Receiving hours for deliveries are **7:30 a.m. to 2:30 p.m.**, local time, Monday through Friday, excluding U.S. Government holidays and BEP Y.E.S. period (which normally occurs between December 24 and January 1). The Contractor shall call the Landover Warehouse appointment line at (202) 874- 0874 at least at least twenty-four (24) hours in advance to schedule deliveries. The appointment line is staffed from 7:00 am to 3:00 pm Monday through Friday. The following information should be provided:

- Name of supplier/manufacturer
- Contact Person with phone number
- Contract/Purchase Order Number
- Total number of cartons or pallets
- Total weight

- Date and Time of Delivery

6.6.12 Shipping of Materials and Equipment: The Contractor is required to use the BEP shipping services for Plant materials or equipment that must be sent out for replacement, repair, or calibration. When this occurs, the function must be coordinated through the COR. If BEP shipping services are not used, the Contractor will not be reimbursed for the use of unauthorized shipping services.

6.7 Other:

6.7.1 Items: The Government reserves the right to procure and provide any item (e.g. chemicals, other materials, lubricants, repair parts and spare parts) used in the management and operation of the Plant. The Government will provide sufficient notification to the Contractor in such instances.

6.7.2 Use of Facilities and Equipment: The Government reserves the right to use the facilities and equipment located within the Plant as necessary over the course of the contract.

6.8 Use of Government Furnished Property (GFP): The Contractor shall use GFP for only those purposes authorized under the contract. GFP shall not be used in any manner for any personal advantage, business gain, or other personal endeavor by the Contractor, any subcontractor, or their employees or agents. In addition, GFP shall not be removed from the Plant without prior written approval from the CO or authorized representative.

6.9 Damage, Destruction and Repair: The Contractor shall be responsible for all damages and destruction to GFP caused by negligence of the Contractor, subcontractor(s), or agent(s) during contract performance. The Contractor shall be liable for all costs associated with the repair or replacement of GFP damaged or destroyed through such acts. The Contractor shall report all cases of loss, damage or destruction of GFP to the COR within twenty four (24) hours of the loss, damage or destruction along with an explanation of the cause and corrective actions to be taken by the Contractor to prevent reoccurrence.

7.0 Contractor Furnished Resources: (Non-reimbursable items)

Attachment 24 provides a listing of current items that are non-reimbursable under this contract in addition to specific information provided below.

7.1 Fork Truck and Pallet Jack: The Contractor will be responsible for providing and maintaining its own forklift and pallet jack in performance of services and thereby assuring the items meet all OSHA requirements and are maintained in good working order at all times. The maintenance schedule for the items shall be included within the Contractor's Maintenance Plan (Ref. Section 8.1.19).

7.2 Hand Tools: The hand tools (powered and non-powered) and the associated accessories/attachments that are currently in the Plant will be turned over to the Contractor. The

Contractor will be responsible for replacement of any and all hand tools. At the end of the contract the Contractor will relinquish any and all hand tools used in the Plant to the succeeding Contractor. The hand tools relinquished to the succeeding contractor must be at least equivalent to the amount received from the previous contractor.

7.3 Personal Protective Equipment (PPE): The PPE that are currently in the Plant will be turned over to the Contractor. The Contractor will be responsible for providing, maintaining, and replacing PPE for all personnel working in the Plant. The PPE relinquished to the succeeding contractor must be at least equivalent to the amount received from the previous contractor.

7.4 Janitorial Supplies: The janitorial supplies that are currently in the Plant will be turned over to the Contractor. The Contractor will be responsible for replacement of any and all janitorial supplies. At the end of the contract the Contractor will relinquish any and all janitorial supplies used in the Plant to the succeeding Contractor. The janitorial supplies relinquished to the succeeding contractor must be at least equivalent to the amount received from the previous contractor.

8.0 Deliverables:

The following items shall be developed and submitted and updated by the Contractor during the performance of the contract within the time periods, in the number of copies and submitted to the designated individual or individuals as specified in Section 8.2 below. (**Note:** During transition, the Contractor will be provided copies of existing policies and procedures and plans used to support the current operation, management and maintenance of the Plant. The Contractor may use this documentation until such time it either develops its own or augments and revises the existing documentation to satisfy some of the below deliverable requirements. All deliverables considered “Unacceptable” and/or not in accordance with the elements as stated below will be returned to the contractor for rework, correction and updates. Based on the quality of the deliverable provided, the COR will provide a due date for the resubmission when needed. When the term “calendar day” or the day of the week is used, the deliverable is due by no later than 3:00 PM that day unless otherwise specified. If a holiday or shutdown occurs on the day a deliverable is due, the Contractor is not relieved from the requirement to provide the deliverable on the due date except as otherwise provided for in Section 8.2.

8.1 Descriptions: This section provides the descriptions or required content of the deliverables under the contract. **8.1.1 Accident Report (Ref. Section 3.9.1):** At a minimum the Accident Report shall include: (1) time, (2) date, (3) description of the events surrounding the accident, (4) possible/probable reason(s) for accident, (5) individual or individual(s) involved, (6) location, (7) any resulting damage or destruction and (8) any corrective actions to ensure the accident does not occur again. The Contractor shall, if applicable, also include a copy of the report they submit to their insurance carrier. These reports shall be completed in accordance with the BEP Injury and Illness Reporting Procedure and the BEP Environment, Health & Safety (EHS) Incident Report. **8.1.1.1 Incident / Accident Notification (Ref. Section 3.8):** A verbal notification to the

COR of any incident or accident. The notification must include a brief description of the event and known or potential effects of the event.

8.1.2 Calibration and Automatic Control Calibration Report (Ref. Section 3.32.1) : In coordination with the calibration contractor, a semi-annual report providing a listing of, but not limited to, the following: (1) the equipment that was calibrated and tested, (2) the location of the equipment within the Plant, (3) the instrumentation set points and calibration points, (4) the procedures utilized in the calibrations, (5) traceability of standards used, (6) Copies of certificates of calibration, (7) any special recommendations for future calibrations, and (8) the findings of the calibration and testing along with any corrective action taken or suggested.

8.1.3 Calibration Equipment List: This is a complete listing of equipment to be calibrated, along with the respective frequencies for calibration, equipment status, and control type. The Calibration Equipment List shall be updated as equipment changes and as directed by the COR throughout the performance of the contract in order to assure optimum operation of the Plant as well as capture changes to Plant equipment.

8.1.4 Calibration Plan: A comprehensive plan that describes in detail how the Contractor will implement, monitor and manage Plant equipment in regards to equipment calibration requirements so to assure optimum and continuing operation of the Plant. This plan shall include specific procedures for the calibration of applicable equipment as well as describe the requirement for the development and maintenance of a Calibration Equipment List and Calibration and Automatic Control Calibration Report.

8.1.5 Chemical Inventory Report: A weekly report providing the inventory of, usage of, and the ordering to replenish chemicals that have met the respective minimum inventory level or other inventory requirements. This report along with the Spare Parts Inventory report shall be used to aid the Contractor in ordering chemicals and supplies in a scheduled manner to ensure continuous operation of the Plant.

8.1.6 Safety Stock Chemical List (Ref. Section 3.3.4.3) : A listing of chemicals that will be stored as a back-up for materials used in the plant that are used when the normal flow of materials becomes unavailable for some reason, normally under conditions of inclement weather.

8.1.7 Storm Water Reports

8.1.7.1 Weekly Storm Water Inspection Report is a report of the inspection performed in accordance with the SWPPP (**Ref. Section 3.28.2**). The inspection reports are due to the COR every Wednesday by Noon.

8.1.7.2 SWPPP Training documentation is a record of the training as required by the SWPPP (**Ref. Section 3.28.5**).

8.1.8 Corrosion Monitoring Plan (Ref – Section 3.36): A comprehensive plan that describes in detail how the Contractor will implement, monitor and manage the Plant's sulfuric acid piping and tank in order to prevent failures of the tank and associated piping that may potentially cause any damage to the Plant or injury to personnel. The plan shall also include and describe the requirements for the development and implementation of a Corrosion Report as well as providing information on the vendor who will perform these services. The Contractor shall develop this plan in accordance with Attachment 27.

8.1.9 Corrosion Monitoring Report (Ref. Section 3.36): A report providing a summary of the test results and comparison with previous forecast(s) of the tanks' and associated piping life span. The report shall also compare corrosion rates at specific sampling locations with the previous results and provide conclusions and recommendations. **8.1.9.1** The Contractor shall create, from the report, a spreadsheet that itemizes the findings with the corrective actions that shall include a listing of all of the findings, their locations, details of the issues, the Maximo work order number for the repair, the proposed corrective action that will be accomplished by the Contractor, the proposed repair date, the name of the person performing the repair, the actual date of the repair, the name of the person confirming that the repair was completed successfully, and the date of the confirmation of repair. The person performing the repair cannot be the same person that confirms the repair. The status of these repairs shall be reported in the Monthly Status Report (**Ref. Section 8.1.21**) until all repairs have been confirmed.

8.1.10 Daily Report: A report that covers the previous calendar day (24 hours - 12:00 AM-12:00 AM) of the key operational status for all areas of the Plant including but not limited to:

8.1.10.1 Listing of all personnel on site and the roles they are fulfilling. If any personnel are covering for anyone that is out, in a different role, this must be noted, i.e. Supervisor covering for an operator. If there is a split shift between 2 separate personnel this must be listed well.

8.1.10.2 Operational status,

8.1.10.3 Influent and effluent flows in gallons,

8.1.10.4 Treatment hours, available hours, and downtime hours, (for the WSRP additionally dosing only hours, recycling hours, recycling rate %, and soft water gallons used for making up wiping solution),

8.1.10.5 Operational set points and each daily range used for the period,

8.1.10.6 Current issues,

8.1.10.7 Chart indicating all parameters analyzed for and corresponding results with acceptable ranges listed by the sample collection time,

8.1.10.8 Upcoming scheduled events, if any,

8.1.10.9 Description of the maintenance and projects work performed and corresponding status (e.g. complete or in process) including items sent out for repair, calibration, or any kind of maintenance with the expected return date or completion date (not time period),

8.1.10.10 Outline of the forecasted upcoming/scheduled maintenance and project work scheduled in the next seven (7) calendar days,

8.1.10.11 Upcoming visitors/contractor companies and reason, if any,

8.1.10.12 Scheduled training, if any, and which personnel,

8.1.10.13 For Fridays only, scheduled equipment job tasks for the weekend and respective assignees,

8.1.10.14 For Mondays only, the completed weekend equipment job tasks including associated issues that caused delays of scheduled tasks or which prevented the task from being accomplished along with personnel completing the work items.

8.1.10.15 Listing of containers that have either been removed from the plant, by system, or shipped offsite directly indicating waste stream, container, number of containers, container weight(s); except for sludge boxes which only needs to have the number of boxes, the range of box numbers that have been assigned to the boxes, and the total weight of all of the boxes combined, per shipment.

8.1.11 Emergency Operation Plan (Ref. Section 3.2.5): A comprehensive plan that outlines in detail, the method(s) the Contractor will use to continue performing Services during emergency conditions such as, but not limited to; **8.1.11.1** Personnel illness, vacation and training,

8.1.11.2 Accidents,

8.1.11.3 Incidents,

8.1.11.4 Rescue operations,

8.1.11.5 Strikes,

8.1.11.6 Civil disturbances,

8.1.11.7 Terrorism,

8.1.11.8 Natural disasters (e.g. earthquakes, hurricanes, pandemics),

8.1.11.9 Abnormal weather conditions and

8.1.11.10 Military operations.

The Emergency Operation plan shall address procedures, personnel and means of accomplishing all tasks in the contract under such emergency conditions.

8.1.12 Emergency Technician Report (Ref. Section 3.31.1): A report provided by the Emergency Technician detailing the work performed, an indication of what caused the occurrence of the emergency, and recommendation for correction.

8.1.13 Equipment Status Notification (Ref. Section 3.8): A notification provided by the Contractor to the COR concerning the status of any equipment or systems that are not operating properly or that become non-operational.

8.1.14 Evidence of Insurance: A certificate of insurance from the Contractors Insurance Carrier(s) reflecting the amounts listed in under the Terms and Conditions of the resulting contract (see Section I, Contract Clauses)

8.1.15 Process Improvement Proposals (Ref. Section 3.30): Proposals shall include sufficient details and information concerning the process improvement(s) in question to provide the Government a reasonable and clear determination concerning the proposed process improvement(s). The impact on the Plant, associated cost savings and/or other measurable savings, means to track and measure savings, return on investment, cost to implement the process improvement, parties that need to be involved and what they would be doing (i.e. subcontractors, BEP personnel), time to implement, including number of hours by party, etc. shall be provided as well.

8.1.16 Hazardous Waste Record (Ref. Section 3.26.4): A complete record of all hazardous waste generated and transported from the Plant on a monthly basis. The hazardous waste record shall also include a historical metric of all hazardous waste generated and transported from the Plant.

8.1.17 Incident Report (Ref. Section 3.9): At a minimum the Incident Report shall include:

(1) time, (2) date, (3) quantity of spill, (4) reason for incident, (5) material / waste(s)

/substance(s) that was spilled or released, (6) individual or individual(s) involved, (7) source of the spilled material/waste(s)/substance(s), (8) any resulting damage or destruction and (9) any corrective actions to ensure the incident does not occur again. The Contractor shall, if applicable, also include a copy of the report they submit to their insurance carrier. Incident Reports shall be completed in accordance with the BEP EMS Procedure - Spill Reporting and Response Procedure (75D-02.0-02).

8.1.18 Weekly Inspection Report (Ref. Section 3.21.1): A report providing information concerning the previous week's inspection as per the Contractor's Quality Control Plan.

8.1.19 Maintenance Plan (Ref. Sections 3.23 & 7.1): An overarching and detailed plan that describes how the Contractor will assure the continuous operation, management and maintenance of the Plant. The plan shall include, but not be limited to: providing an outline of the types of Maintenance to be performed, their frequency, the equipment or system to be maintained, procedures to perform the Maintenance, etc. Some specific procedures are to be identified and

provided in a separate plan, however, they are still a part of the Maintenance Plan and they shall include specific information regarding the process or area in question. The Phase-Out Plan (**Ref. Section 8.1.24**) and Emergency Operation Plan (**Ref. Section 3.2.5**), though separate plans, are subcomponents of this Plan.

8.1.20 Maintenance Report: A report reflecting all the Maintenance conducted during the previous month, by system. This shall include any ongoing issues in the Plant and status updates of issues.

8.1.21 Monthly Status Report: A report that includes data and analysis for the previous month of the following, but not limited to information: **8.1.21.1** Operations and maintenance data,

8.1.21.2 Current Plant project status,

8.1.21.3 Inventory of spare parts and equipment, including unit costs and extended costs,

8.1.21.4 Treatment chemical usage and rates, including unit costs and extended costs,

8.1.21.5 Comparisons of chemical treatment consumption and cost averages data trends with prior report conclusions,

8.1.21.6 Influent and effluent flows,

8.1.21.7 Chemicals used per 1000 gallons of treated influent/system,

8.1.21.8 Cost trends of chemical usage,

8.1.21.9 Costs of chemicals,

8.1.21.10 Average influent rate and waste generation trends,

8.1.21.11 Costs to treat/produce 1000 gallons by system,

8.1.21.12 The Hazardous Waste Record,

8.1.21.13 Status of training during the month and copies of applicable completed training certificates with updates to the training required matrix. The report shall also include explanations of any monthly changes as well as unusual changes. The report shall include complete Maximo implementation updates as well, until Maximo is fully implemented as determined by the COR.

8.1.22 Notification of Interruption of Utilities or Fire Suppression System (Ref. Section 3.9.4): A notification provided by the Contractor concerning the need to interrupt or shutdown the Utilities or Fire Suppression System. The notification shall provide the information outlined below.

8.1.22.1 INTERRUPTION OF UTILITIES OR FIRE SUPPRESSION/HVAC/SECURITY SYSTEM: Utility services, the fire suppression system, HVAC system or security system shall not be interrupted or shut down by the Contractor to make connections, alterations, modifications

or for any other purpose without prior written approval by the COR. The Contractor shall submit any such requests in writing to the COR no less than fifteen (15) business days prior to the date of the proposed interruption or shut down. The request at a minimum shall provide the following information;

- Type of utility (i.e. water, electricity, gas or compressed air) or system(s)
- Area or Area(s) affected, including specific Plant equipment and size of the line and the shut-off valve.
- Hour and date of proposed shut-off
- Estimated length of time services or the system(s) will be interrupted or shutdown
- Rational for interruption or shutdown

8.1.23 Personnel Contact List: A list indicating the name, role, duty, and shift (work schedule) and after hours telephone number(s) of Contractor personnel performing work under the contract. The list shall also clearly indicate the person in charge on site at any given time. In addition, provide an outline for escalation if one party cannot be reached, along with appropriate emergency contact numbers. Changes to the list must be approved by the COR.

8.1.24 Phase-Out Plan (Ref. Section 5.12.2): A comprehensive and detailed plan addressing the event wherein the Contractor is replaced by a succeeding contractor during the performance the contract. The Phase-Out Plan shall provide the specific approach, methods, techniques and manpower that will be employed to ensure the successful transition of services and orientation to the succeeding contractor, the time, location and subjects to be discussed as part of the orientation of succeeding contractor, the documentation and items to be turned over by the Contractor (e.g. standard operating procedures, drawings, plans, etc.), listing and description of lessons learned, a listing of any open contracts or orders for Materials, Tools or Equipment, listing of sources/ vendors, including point of contact and address information, used during the performance of the contract, identification of any Maintenance or Repair issues, and any other pertinent information necessary to ensure a smooth and orderly transition.

8.1.25 Quality Management System (QMS): A detailed plan including all supporting documentation on how the Contractor will develop, implement, monitor and manage the necessary quality control actions in order to achieve the quality standards set forth by this contract. The Contractor is not required to use ISO 9000 or be certified externally to ISO 9000. However, if another system is used by the Contractor, it must at a minimum, address all of the elements of ISO 9000 and support the BEP ISO 9000 Quality Management System. In essence, the QMS is a part of the Contractor's overarching quality control program in driving quality within their performance of this contract. In addition, the QMS should document how the Contractor will implement procedures to identify, prevent, correct and ensure non-recurrence of defective services, to monitor and manage the necessary quality control actions in order to

achieve the quality standards set forth by this contract as well as to ensure services are performed in accordance with all applicable Federal, State, and Local laws and regulations and BEP policies and procedures. All methods, procedures, and forms shall support this concept.

8.1.26 Strategic Initiatives Report (Ref. Section 3.5): A monthly report on the status of the annually assigned initiatives. The report shall list each major milestone and deliverable, start date, planned end date, revised end date, percentage complete, issues encountered if the end date must be revised, along with a narrative of what actions the Contractor will take to ensure the end date does not have to be revised again.

8.1.27 Sampling and Testing Plan (Ref. Sections 3.6 & 3.27) : A comprehensive plan that outlines in detail, the following, but not limited to information: the methods, frequency, individuals, measurements, and techniques the Contractor will use in conducting and performing sampling and testing of the wastewater and generated sludge so as to optimize Plant operations and ensure that the Plant maintains compliance with the standards as set forth in the Regulations/Publications/Codes, specifically the Permit. In addition, the plan shall list the items and associated parameters that are to be tested, the levels and ranges of measurement, and a plan of action for when results are found not to be in line with Plant requirements or expectations.

8.1.28 Sampling and Testing Results Report (Ref. Sections 3.6 & 3.27): These are the results of the Sampling and Testing that are from the outside lab(s). The Contractor shall review all outside lab analysis results, provide a summary of the results with applicable limits, and summarize the results in an email as all are compliant with the discharge permit or requirements that are being analyzed for, or there are issues with the results and state the issues.

8.1.29 Spare Parts Inventory & Reconciliation Report: A report that provides, but not limited to the following; **8.1.29.1** The beginning inventory of each part,

8.1.29.2 The amount reported as used for each part,

8.1.29.3 The ending inventory of each part,

8.1.29.4 The part variance,

8.1.29.5 The associated costs individually (unit and extension), and totals for the given month,

8.1.29.6 Explanations of the part variances, and

8.1.29.7 Actions to be taken to prevent reoccurrence of the variance.

This report shall be used along with Maximo and the Chemical Inventory Report by the Contractor to order chemicals and supplies, such as spare parts in a scheduled manner to ensure continuous operation of the Plant. **NOTE:** If Maximo is not used, the Contractor is not relieved of the requirement to provide the deliverable.

8.1.30 Glycol Ether Report: A monthly report of the usage, by material, of materials that contain glycol ethers. The COR will provide the current list of materials that meet this criteria and the Contractor will provide the report of usage on a monthly basis to the COR.

8.1.31 Training Plan (Ref. Sections 3.35.1 & 5.4): A plan covering the training (e.g. licenses, certification, mandatory training) required for Contractor personnel performing under the contract broken down by each individual and their associated individual training requirements, including an overall matrix for each individual contractor and their respective classes.

8.1.32 Training Certificates (Ref. Sections 3.35 & 5.4): Certificate(s) reflecting completed training by Contractor personnel and containing the individuals name and information concerning the training completed (e.g. when, where, number of hours/credits obtained, etc.).

8.1.33 Standard Operating Plan: An overarching and detailed plan that describes how the Contractor will assure the continuous operation of the Plant during Normal Operating Hours throughout performance. The Sampling and Testing Plan, Emergency Operation Plan, Phase-Out Plan and Calibration Plan though separate plans are subcomponents of this Plan.

8.1.34 Vendor Warranty List (Ref. Section 3.17): A comprehensive list of items with warranties still in effect throughout the contract and at the end of the contract. This list shall include the following, but not limited to information: (1) vendor name and contact information, (2) item description, (3) date item purchased, (4) original purchase amount, (5) purchase order number, (6) part number, (7) serial number, (8) system used on or associated with description of use and (9) dates and period of warranty beginning and ending.

8.1.35 System Log Books: A system log book will be maintained for each separate system. The respective log books shall provide the following as a minimum: At the beginning and end of each shift - the management personnel on shift(as defined herein); the non- management personnel on shift (If a management person is fulfilling the role of a non- management person, this must be noted as well); periodic entries in chronological order noting the time of occurrence of: operating characteristics; changes to equipment settings or operation, including the reasoning or justification for changes to equipment; maintenance activities of any kind that occur; any accidents or incidents that occur, along with the respective basic information; any and all personnel who enter and leave the respective areas and their purpose for being in the areas; any items of note that relate to the proper operation of the Plant. When the respective Log Book is filled, it must be delivered to the COR within 5 calendar days of the last entry. Additional items may be added by COR technical direction.

8.1.36 WSWPP pH & Flow Recorder Charts: The WSWPP have paper chart recorders that records the system flow and pH reading from both pH effluent meters. At the end of the month the charts should be put in chronological order and then delivered to the COR by the 5th calendar day of the following month.

8.1.37 Wastewater Flow and pH data: A report providing the total (gallons) influent, effluent, average effluent, minimum and maximum effluent and minimum and maximum and average pH, except the PWPP where average is not required, that are discharged to the sanitary sewer system.

8.1.38 Superfund Amendments and Reauthorization (SARA) Report: A report providing the information on the storage of chemicals. During the performance of the contract, the list of chemicals may have chemicals added to or deleted. Changes must be approved by the COR within 15 calendar days of a proposed change by the Contractor. The data for each chemical must include the type and size of the storage container, the location of the storage, the total amount stored on a weekly basis by volume and pounds, the number of days of storage per year on the respective site, the maximum amount stored during the calendar year at the respective site in pounds/day, and the average amount stored during the calendar year at the respective site in pounds/day.

8.1.39 Semi-Annual Discharge Report: A report that provides the analytical and flow information for applicable discharging systems provided, from the Wastewater Discharge Permit (Attachment 1). The blank form to be used will be provided by the COR during Phase-in.

8.1.40 Monthly pH Report: A report that shows for each applicable system discharge, on a daily basis, the minimum pH, maximum pH, and whether there was a discharge flow or not. The data must be collected every day whether discharging from the respective system or not.

8.1.41 Solvent Usage Report: A monthly report of the usage, by material, of materials that contain solvents. The COR will provide the current list of materials that meet this criteria and the Contractor will provide the report of usage on a monthly basis to the COR.

8.1.42 SPCC Tank Inspections: A monthly inspection of associated Plant tanks on forms provided by the COR. The inspections are to be completed and delivered to the COR by the 5th calendar day of the month for the previous month. Any issues noted in the inspections shall be the responsibility of the Contractor and managed/corrected by the Contractor through the Maximo system.

8.1.43 Quarterly Discharge Report: A report that provides the analytical and flow information for applicable discharging systems provided, for applicable parameters, from the Wastewater Discharge Permit (Attachment 1). The blank form to be used will be provided by the COR during Phase-in.

8.1.44 Monthly Invoice Report: A report that details all items in the monthly invoice, excluding labor, in an excel spreadsheet by CLIN number, separating ancillary service, supplies, and equipment into separate groups. When a supplier's invoice contains multiple items, each item shall be listed separately. Shipping or freight costs and any other special costs shall be treated as separate item(s), if applicable. The following information shall be provided by month and CLIN within 5 calendar days of submitting the monthly invoice: **8.1.44.1 Supplier Name**

8.1.44.2 Suppliers' Invoice #

8.1.44.3 Item Part #/ Item #

8.1.44.4 Item Description with package information if applicable

8.1.44.5 Quantity

8.1.44.6 Unit cost

8.1.44.7 Extended cost

Reference	Deliverable	Due Date	Deliver To
After Contract Award			
8.1.4	Calibration Plan	60 calendar days after contract award.	COR
8.1.6	Safety Stock Chemical List	Within 60 calendar days after contract award and within 15 calendar days after changes are made.	COR
8.1.8	Corrosion Monitoring Plan	120 calendar days after contract award.	COR
8.1.11	Emergency Operation Plan	60 calendar days after contract award.	COR
8.1.14	Evidence of Insurance	15 calendar days following contract award, and within 10 calendar days after renewal.	CO
8.1.19	Maintenance Plan	60 calendar days after contract award.	COR
8.1.23	Personnel Contact List	30 calendar days after contract award and 5 calendar days after personnel changes.	CO & COR
8.1.25	Quality Management System	120 calendar days after contract award.	COR
8.1.27	Sampling and Testing Plan	60 calendar days after contract award.	COR
8.1.31	Training Plan	60 calendar days after contract award.	COR
8.1.33	Standard Operating Plan	60 calendar days after contract award.	COR
Periodically			
8.1.1.1	Incident / Accident Notification	Within fifteen (15) minutes of any incident/accident encountered.	COR
8.1.1	Accident Report	Within twenty-four (24) hours of any accident that occurs within the Plant boundaries.	COR
8.1.2	Calibration and Automatic Control Calibration Report	Within 45 calendar days after any semi-annual calibration services are completed.	COR
8.1.3	Calibration Equipment List	Within 15 calendar days after updates are made.	COR
8.1.5	Chemical Inventory Report	Wednesdays, no later than 12:00 PM EST.	COR
8.1.7.1	Weekly Storm Water Inspection Report	Wednesdays, no later than 12:00 PM EST.	COR
8.1.7.2	SWPPP Training Records	Within 3 calendar days of completion of the training.	COR
8.1.9	Corrosion Monitoring Report	Within 45 calendar days after any testing is completed.	COR

8.1.10	Daily Report	Daily, M-F, no later than 12:00 PM EST	COR
8.1.12	Emergency Technician Report	Before the Emergency Technician leaves the Plant.	COR
8.1.13	Equipment Status Notification	Notify within 1 hour concerning the status of any equipment or systems that are not operating properly or that become non-operational.	COR
8.1.15	Process Improvement Proposal	As applicable and if requested by the Government; no later than fifteen (15) business days from the date of written request from the COR or CO.	COR or CO
8.1.16	Hazardous Waste Record	Included as part of the Monthly Status Report.	COR
8.1.17	Incident Report	Within twenty-four (24) hours of any incident that occurs within the Plant boundaries.	COR
8.1.18	Weekly Inspection Report	Weekly - every Wednesday by 12:00 PM EST.	COR
8.1.20	Maintenance Report	Included as part of the Monthly Status Report.	COR
8.1.21	Monthly Status Report	Monthly – on the 10 th calendar day of each month. If the 10 th falls on a weekend, the report shall be due the following Monday.	COR
8.1.22	Notification of Interruption of Utilities or Fire Suppression System	No less than 15 business days prior to scheduled interruption or shutdown.	COR
8.1.24	Phase-Out Plan	A minimum of 30 calendar days prior to the beginning of the Phase-Out Period.	COR
8.1.28	Sampling and Testing Results Report	Within 10 calendar days of the samples' collection date.	COR
8.1.29	Spare Parts Inventory & Reconciliation Report	Included as part of the Monthly Status Report.	COR
8.1.32	Training Certificates	Included as part of the Monthly Status Report.	COR
8.1.34	Vendor Warranty List	Quarterly, on the 15 th calendar day of the quarter and as part of the Phase-Out Plan. If this day occurs on a weekend, the list will be due the following Monday.	COR
8.1.35	System Log Books	Throughout each and every shift, updated to within two (2) hours of occurrences and functions.	COR
8.1.35	System Log Books	When filled, the respective system log book must be delivered to the COR within 5 calendar days of the last entry. If this day occurs on a weekend, the book will be due the following Monday.	COR
8.1.36	WSWPP pH & Flowmeter Recorder data	On the 5 th calendar day of each month for the previous month. If this day occurs on a weekend, the charts will be due the following Monday.	COR

8.1.37	Wastewater Flow and pH data	On the 2 nd calendar day of each month by 8:00 AM, for the previous month. If this day occurs on a weekend, the data will be due the following Monday.	COR
8.1.38	SARA Report	The Wednesday before MLK Federal Holiday of each year for the previous calendar year.	COR
8.1.39	Semi-Annual Discharge Report	Due on the Monday before Y.E.S. of each year and Monday before the last full week of June of every year for the previous six (6) month period. If the Wastewater Permit is changed, this due date may be amended accordingly by the COR.	COR
8.1.40	Monthly pH Report	Due on the first business day of each month by 8:00 AM.	COR
8.1.41	Solvent Usage Report	On the 2 nd calendar day of each month by 8:00 AM, for the previous month. If this day occurs on a weekend, the data will be due the following Monday.	COR
8.1.42	SPCC Tank Inspections	The inspections are to be completed and delivered to the COR by the 5 th calendar day of the month for the previous month.	COR
8.1.43	Quarterly Discharge Report	On the 3 rd calendar day of each quarter by 8:00 AM, for the previous quarter. If this day occurs on a weekend, the data will be due the following Monday.	COR
8.1.44	Monthly Invoice Report	Due on the 5 th calendar day after submission of the Monthly invoice.	COR
End of Contract			
	Copies of Current Vendor Warranties	5 business days before the end of or termination of the contract.	COR

Performance Requirements Summary

For all Deliverables meeting the AQLs stated in this PWS, “Positive” customer feedback will be reported to the Contractor by summarizing the past year’s surveillance activities under the Contractor Performance Assessment Reporting System (CPARS) administered by the Naval Sea Systems Command (NAVSEA).

For all Deliverables that do not meet the AQL’s stated in this PWS, “Negative” customer feedback will be reported to the Contractor by summarizing the past year’s surveillance activities under the Contractor Performance Assessment Reporting System (CPARS) administered by the Naval Sea Systems Command (NAVSEA).

Performance Requirements Summary				
Performance Requirement	Performance Indicator	Standard	Acceptable Quality Level	Surveillance Method
Emergency Repair Notification 1.3.26.1	Responsiveness – Emergency Repairs	Notification must be within 15 minutes of becoming aware of the issue.	100% of occurrences require COR notification.	Periodic physical surveillance
Repair Notification 1.3.26.2	Responsiveness - Repairs	Notification must be within 24 hours of becoming aware of the issue.	100% of occurrences require COR notification.	Periodic physical surveillance
Fines and Penalties 3.1.1	Environmental and Safety - Assessment of Fines and Penalties	Any fines or penalties assessed against the BEP for any regulatory finding under the requirements of the contract.	No fines or penalties.	Episodic physical surveillance
Plant Shutdown 3.1.1.1	Environmental and Safety - Responsibility and Liability	If the Contractor fails to maintain the Plant in 100% operational status and/or in compliance with the Regulations/Publications/Codes, resulting in shutdowns/stoppages the BEP will assess damages and pass that amount onto the Contractor for reimbursement.	No shutdowns that result in damages to BEP.	Episodic physical surveillance
Housekeeping 3.1.2	Quality - House keeping	Maintain good housekeeping as prescribed.	No more than 3 occurrences of poor housekeeping observed in a month.	Periodic physical surveillance

Odor Control 3.1.3	Quality - Odor control	No malodorous odors go beyond Plant.	No more than one report or episode of odor emanating from Plant in a year.	Episodic physical surveillance
Roll-up Doors 3.1.4	Quality - Roll-up Doors	All Plant roll-up doors must be kept closed unless material or equipment is being transferred through them.	No more than two observances of door(s) remaining open for >15 minutes after being used in a month.	Periodic physical surveillance
Maintenance of Plant Documentation 3.1.5	Quality - Maintenance of Plant Documents	Updated documents must be sent to the COR for review and approval within 15 calendar days of the completion of the change.	No instances of Plant documentation not being updated as required in a month are allowed.	Episodic physical surveillance
Maximum Work Hours in 24 Hour Period 3.2.4.1	Safety - Maximum Work Hours in 24 Hour Period	Contractor shall not allow any individual to be on duty for greater than 1.5 shifts without being sent off-site for rest.	No instances allowed.	Periodic physical surveillance
Proper Role Utilization 3.2.4.3	Management - Proper Role Utilization	Management personnel may not cover for Non-Management Personnel for more than 16 hours in a 7 calendar day period, individually or collectively.	No instances allowed.	Periodic physical surveillance
Materials 3.3	Management - Materials	All current materials are required to be managed in Maximo.	Management of materials in Maximo must be completely implemented for all current materials within 4 months of contract award unless a technical issue with Maximo exists.	Periodic physical surveillance
Safety Stock Materials 3.3.4.2	Environmental and Safety - Materials	All safety stock materials stored at the Landover warehouse are required to be used at least annually and replenished.	No instances of exceeding 1 year storage before being used.	Periodic physical surveillance
Changes in materials levels 3.3.5	Responsiveness - Changes in Materials Levels	Changes in materials levels that may impact the operation of the Plant shall be brought to the attention of the COR immediately	No exceptions.	Periodic physical surveillance

Equipment 3.4.5	Management - Equipment	All assets are required to be managed in Maximo.	Management of assets in Maximo must be completely implemented for all assets within 6 months of contract award unless a technical issue with Maximo exists.	Periodic physical surveillance
Accident or Incident Notification 3.8	Environmental and Safety - Notification	Immediately notifying, verbally COR of accidents and/or incidents.	100% of occurrences require COR notification.	Periodic physical surveillance
Accident or Incident Report 3.9.1	Environmental and Safety - Report	Providing a written (non-verbal) Accident or Incident Report of any incident/accident encountered.	Report must be submitted within twenty-four (24) hours of occurrence.	Periodic physical surveillance
Safety Hazard Identification Notification 3.9.5	Safety - Safety Hazard Identification Notification	Upon identification of any safety hazard, providing verbal notification.	Notification must be provided immediately.	Periodic physical surveillance
Uniforms 3.12	Management - Uniforms	The use of torn or worn out uniforms or safety shoes are unprofessional and are strictly prohibited. Personnel may not “share” uniforms.	No exceptions.	Periodic physical surveillance
Meetings 3.14	Management - Meetings	Taking meeting minutes at requested meetings and submitting for review and approval.	Meeting minutes must be submitted for review and approval within 24 hours of the end of the meeting.	Periodic physical surveillance
Periodic Review 3.18.3	Quality - Documents	Deliverables and other applicable documentation shall be reviewed and updated on a periodic basis.	The minimum review for any document is once per year.	Periodic physical surveillance
Safety Equipment Inspections 3.23	Safety - Safety Equipment Inspections	Documented safety equipment inspections shall be performed on a monthly basis, the first full calendar week of every month.	No exceptions.	Periodic physical surveillance

Chain of Custody 3.27.1	Environmental - Chain of Custody	Chain of custody (pdf) shall be provided 24 hours after sampling is completed.	No exceptions.	Periodic physical surveillance
Sampling Results 3.27.3	Environmental - Sampling Results	Provide complete review of outside lab results of sampling and testing within 10 calendar days of the samples' collection date.	No exceptions.	Episodic physical surveillance
Emergency Technician Report 3.31.1	Management - Emergency Technician Report	Provide report prior to technician leaving the BEP facility.	No exceptions.	Episodic physical surveillance
pH and ORP Meter Calibration 3.32	Environmental - pH and ORP Meter Calibration	All pH and ORP meters must be calibrated at least weekly.	No exceptions.	Periodic physical surveillance
PLC Program Back-up 3.33	Management - PLC Program Back-up	All Plant PLC programs shall be backed-up on at least a semi-annual basis.	No exceptions.	Periodic physical surveillance
Conduct 4.1.1	Management, Safety - Sleep	No Contractor shall sleep or "nap" while on BEP property.	No exceptions.	Periodic physical or electronic surveillance
Dress 4.2	Management, Safety - Dress, PPE	A "Taped" name on a uniform is strictly prohibited. Uniforms shall be maintained in good repair and kept clean. Contractor personnel shall also wear steel toe shoes in accordance with ANSI standards while working at the Plant. PPE and other identified Tools and Equipment shall be worn as appropriate.	No exceptions.	Periodic physical surveillance
Dress 4.2.1	Management, Safety - Dress, PPE	Contractors must be in uniform and ready for work at the beginning of their designated shift.	No exceptions.	Periodic physical surveillance

Appearance 4.3	Safety - Appearance	Facial hair that obstructs the proper wearing of a respirator is strictly prohibited.	No exceptions.	Periodic physical surveillance
Badges 5.6	Security - Badges	The identification badge shall be worn by Contractor personnel above the waist, clearly visible, with picture side front forward at all times while on-site at BEP Facilities.	The only exception to this requirement is when the Contractor is performing as an entrant in a Confined Space event. Upon exiting the confined space, the Contractor must wear the respective badge.	Periodic physical surveillance
Internet Access 6.6.8	Management – Internet Access	The Contractor is strictly prohibited from viewing any videos of any type on Government provided equipment.	Only those associated with required training or otherwise required by the Government may be viewed.	Periodic physical surveillance
Movement of Materials 6.6.10	Safety - Movement of Materials	The delivered Materials shall be moved into the Plant within 4 hours of being delivered to the basement hall.	No exceptions.	Periodic physical surveillance
Damage, Destruction, and Repair 6.9	Management – Damage, Destruction, and Repair	The Contractor shall report all cases of loss, damage or destruction of GFP to the COR within twenty four (24) hours of the loss, damage or destruction.	No exceptions.	Periodic physical surveillance
Deliverables 8.2	Management – Deliverables	The Contractor shall submit deliverables as prescribed.	No exceptions.	Periodic physical surveillance
PWS General	All other requirements not specifically otherwise referenced in this summary	All requirements of the PWS shall be performed that are not specifically otherwise referenced in this summary, in accordance with the individual respective requirement.	No exceptions.	Periodic physical surveillance