

STATEMENT OF WORK (SOW)

Demolition of Hull

1.0 Background

NUWCDIVNPT requires the demolition of a 2-piece structure consisting of a hull component and hatch which is located at Bldg 47 NAVSTA. This structure is no longer required, and all normal means of disposition have been exhausted.

1.1 Places of Performance

Naval Station Newport RI, building 47.

1.2 Authorized Users

Naval Undersea Warfare Center Division Newport (NUWCDIVNPT) RI. Code 107

1.3 Sponsors

NUWCDIVNPT Code 107

1.4 Types of Funding

Service Cost Center

2.0 Scope

The contractor shall provide all labor, equipment, and materials necessary to demolish the 2-piece structure. The approximate dimensions and estimated weights are as follows:

- Hull Component: 18 feet high, 18 feet wide and 16.5 feet long. Approximate weight: 76,000 lbs.
- Hatch: 12 feet wide, 9 feet long 3.5 feet high. Approximate weight: 12,000 lbs.

2.1 Mitigation Plan: The contractor shall provide a project-specific Mitigation Plan for government review and approval. Work shall not commence until this plan is formally approved in writing by the Contracting Officer or their designated representative. This plan must address, at a minimum: fire risk/safety, environmental risks, the required work footprint, and a site-specific emergency preparedness plan. Work shall not commence until this plan is reviewed by the government.

2.2 Protection of Infrastructure: Contractor is responsible for ensuring existing storage infrastructure is protected from scrap metal disposal process to protect the integrity of the existing roadbed/storage infrastructure. The contractor and Government shall document the existing conditions around the infrastructure using photographs and agree to current conditions prior to the start of any demolition.

- 2.3 Transportation:** The contractor is responsible for the transportation of all scrap metal and waste from Building 47 to a licensed disposal/recycling facility.
- 2.4 Equipment:** The contractor shall provide and coordinate all equipment required for the demolition, including but not limited to, material handling equipment, scrap metal containers, and cutting equipment.
- 2.5 Permits:** The contractor is responsible for securing all necessary demolition and transportation permits, including for any oversized or overweight vehicles. Contractor is responsible for securing a hot work permit. If a crane is required, a lift permit is required to be secured and approved.
- 2.6 Documentation of Disposal:** Upon completion of disposal, the contractor shall provide the government with certified weight tickets from the licensed scrap metal facility and a copy of the official receipt of sale indicating the total monetary value received for the scrap metal.
- 2.7 Proceeds from Scrap Metal:** The contractor shall be entitled to retain all proceeds from the sale of the scrap metal as consideration for the work performed under this contract. The value of this scrap metal shall be factored into the contractor's overall price proposal.

3 Applicable Documents

The contractor shall perform the tasking required in Section 4.0 in accordance with (IAW) the below Applicable Documents (ADs).

NUMBER	TITLE	APPLICABLE SOW TASK(S)
3.1	Department of Defense (DoD) / Navy Issuances	
3.1.1	Unified Facilities Criteria (UFC) 1-900-01	2.3, 4.6.1, 4.6.2, 4.9.1
3.1.2	Unified Facilities Criteria (UFC) 3-810-01	2.1, 2.2, 4.1.1, 4.2.1, 4.6, 4.7.1, 4.9
3.1.3	EM 385-1-1	2.1, 4.1, 4.3, 4.4, 4.5, 4.7, 4.10
3.2	Federal Regulations	
3.2.1	29 CFR 1926	2.1, 4.1, 4.3, 4.4, 4.5, 4.7, 4.10
3.2.2	29 CFR 1926, Subpart T	4.4.1, 4.4.2, 4.5.1, 4.10

3.2.3	29 CFR 1926.62	4.2.1
3.2.4	40 CFR Part 61, Subpart M	4.2.1
3.2.5	40 CFR Part 261	4.2.1, 4.6.2, 4.9.1
3.3	Local Regulations	
3.3.1	NAVSTA Newport Instruction (NAVSTANPTINST)	2.1, 4.4.2

4.0 Technical Requirements

4.1 Planning and Preparation

4.1.1 Site Assessment: The contractor shall conduct a comprehensive site assessment to evaluate the structure and its surroundings. This assessment must identify all potential hazards, including but not limited to, the proximity of adjacent structures, utilities, and any environmental concerns. The findings shall be incorporated into the Mitigation Plan (see SOW Section 2.1).

4.1.2 Permits and Regulations: The contractor is responsible for identifying and obtaining all necessary federal, state, and local permits for the demolition work as described herein. The contractor shall ensure all work complies with the safety and environmental standards listed in Section 3.0.

4.3 Demolition and Debris Management

4.3.1 Structural Demolition: The contractor shall dismantle and demolish the structure in a controlled and safe manner.

4.3.2 Cutting and Separation: Any on-site cutting or other "hot work" requires a permit from the NAVSTA Newport Fire Department. The contractor is responsible for obtaining this permit and ensuring all conditions are met. All materials shall be cut and separated into manageable sections for safe handling and removal.

4.3.3 Controlled Collapse: The use of explosives or implosion for a controlled collapse is not anticipated for this project. However, should the contractor's proposed demolition method involve any form of planned, large-scale controlled collapse, it must be designed and overseen by certified demolition experts. Such a plan would require specific, additional government review and approval prior to execution.

4.3.4 Debris Sorting and Recycling: The contractor shall sort all demolished materials. All recyclable metals shall be segregated for recycling.

4.3.5 Disposal: The contractor shall dispose of all non-recyclable materials in a manner that adheres to all applicable federal, state, and local waste disposal regulations.

4.4 Site Cleanup and Safety

4.4.1 Site Cleanup: Upon completion of demolition and removal activities, the contractor shall clear the site of all remaining project-related debris and materials, returning the work footprint to its original condition as documented per SOW Section 2.2.

4.4.2 Post-Demolition Safety Inspection: The contractor shall conduct a joint post-demolition inspection with a government representative to ensure the site is safe and no hazards remain.

4.4.3 Safety and Emergency Preparedness: The contractor shall ensure all personnel are trained and equipped in accordance with the regulations cited in Section 3.0. A site-specific emergency preparedness plan, including procedures for accidents or injuries, shall be submitted with the Mitigation Plan.

4.5 Documentation and Review

4.5.1 Documentation: The contractor shall maintain a complete record of the demolition project. This record shall be submitted to the government as a final project closeout package and must include, at a minimum, all permits, safety inspection logs, and disposal/recycling receipts (as required by SOW Section 2.6).

4.5.2 Post-Project Review: At the government's request, the contractor shall participate in a post-project review to discuss performance and identify any lessons learned.

4.6 Environmental Protection

4.6.1 Waste Management: The contractor shall implement strategies to maximize the recycling of metal components and reduce the generation of non-recyclable waste.

4.6.2 Air and Water Quality: The contractor shall actively manage the work site to minimize dust and airborne contaminants through methods such as water spraying or other dust suppression measures. The contractor shall also implement containment measures to prevent runoff of any pollutants into nearby water sources.

5.0 Installation Access

5.1 Installation Access: Contractor personnel shall comply with all security, badging, and vehicle access regulations required for performance at NAVSTA Newport. The contractor is responsible for coordinating base access for all its employees and subcontractors.

5.2 Conduct: While on the government installation, contractor personnel shall adhere to all local regulations and instructions concerning conduct and safety.

6.0 Security Compliance

6.1 Program Protection

SECURITY: All Contractor personnel shall adhere to the Security provisions of 32 CFR Part 117 – National Industrial Security Program Operating Manual (NISPOM). While performing work at a Government Facility, Contractor personnel shall comply with the security regulations of the host facility. Applicable FAR, DFARS, NMCARS clauses, and NAVSEA text shall be adhered to in the performance of this contract. Security incidents shall be promptly reported through the companies Facility Security Officer (FSO), to the Contracting Officer's Representative (COR), Technical Point of Contact (TPOC), and the Cognizant Security Office to NUWCDIVNPT Security.

Controlled Unclassified Information (CUI) including Legacy FOUO and Covered Defense Information (meeting the definition of 48 CFR 252.204–7012(a)) generated and/or provided under this contract shall be marked and safeguarded as specified in DoD Instruction 5200.48, CUI available at:

<https://www.esd.whs.mil/Portals/54/Documents/DD/issuances/dodi/520048p.PDF>. Any product containing Covered Defense Information shall be assigned a distribution statement (distribution statements B through F) in accordance with DoDI 5230.24 (Distribution Statements on Technical Documents); and DoDI 5230.24, Enclosure 3 Procedures, available at <https://www.esd.whs.mil/Portals/54/Documents/DD/issuances/dodi/523024p.pdf>

INFORMATION SECURITY: If the work is performed at the Contractor's facility, the Contractor shall implement and maintain security procedures and controls to prevent unauthorized disclosure of classified information and controlled unclassified information (CUI) and to control distribution of CUI in accordance with National Industrial Security Program Operating Manual (NISPOM) codifying 32 CFR Part 117, NISPOM Rule, and SECNAV M-5510.36B. If the work is performed at the Government's facility, the Contractor shall comply with facility policy.

CUI INCIDENT REPORTING AND RESPONSE: The Contractor shall promptly report any unauthorized, inadvertent, or illegal release or disclosure of CUI to the Contracting Officer's Representative / Technical Point of Contact (TPOC), Procuring Contracting Officer, and the Security Office. Contractor personnel shall coordinate this effort through the relevant industry site FSO.

PUBLIC RELEASE: Any controlled unclassified information pertaining to this contract shall not be released for public dissemination, including posting to any social media sites such as Facebook or Twitter, unless it has been approved for public release by appropriate U.S. Government authority. Proposed public releases shall be submitted for approval prior to release through the appropriate U.S. Government Office.

6.2 Operations Security (OPSEC)

OPSEC is a process that identifies critical information to determine if friendly actions can be observed by adversary intelligence systems, determines if information obtained by adversaries could be interpreted to be useful to them, and then executes selected measures that eliminate or reduce adversary exploitation of friendly critical information.

The Contractor shall develop and implement, and update and maintain an OPSEC program to protect controlled unclassified and classified activities, information, equipment, and material used or developed by the Contractor and any subcontractor during performance of the contract. The Contractor shall be responsible for the subcontractor implementation of the OPSEC requirements. The Contractor developed OPSEC program may include Information Assurance and Communications Security (COMSEC). The OPSEC program shall be in accordance with National Security Presidential Memorandum (NSPM) 28, and at a minimum shall include:

- 1) Assignment of responsibility for OPSEC direction and implementation.
- 2) Issuance of procedures and planning guidance for the use of OPSEC techniques to identify vulnerabilities and apply applicable countermeasures.
- 3) Establishment of OPSEC education and awareness training. To include initial and annual OPSEC training.
- 4) Provisions for management, annual review, and evaluation of OPSEC programs.
- 5) Flow down of OPSEC requirements to subcontractors when applicable.

While performing aboard Government sites, the contractor shall: comply with all OPSEC instructions and policies; include OPSEC as part of its ongoing security awareness program and take all required Agency training; Be responsive to the Supporting OPSEC Manager on a non-interference basis; and Protect sensitive unclassified information and activities, which could compromise classified information or operations, or degrade the planning and execution of operations performed by the Requiring Organization and contractor in support of the mission.

6.3 Electronic Spillage

Electronic Spillage (ES) is defined as a situation where information of higher classification than a system is authorized to process is introduced into that system, intentionally or otherwise. If a Contractor is determined to be responsible for an ES, all direct and indirect costs incurred by the Government for ES remediation will be charged to the Contractor.