

**STATEMENT OF WORK
TEST, EVALUATION, REPAIR, MODIFICATION & UPGRADE
OF ELECTRONIC WARFARE SYSTEMS
IN SUPPORT OF THE
AIRBORNE ELECTRONIC ATTACK FLEET SUPPORT TEAM
& ORGANIC DEPOT**



Prepared by the
Airborne Electronic Attack (AEA) Fleet Support Team (FST) & Organic Depot
NSWC Crane Division
Version 1.3
May 20, 2025

Distribution Statement A: Approved for public release: distribution is unlimited.

1 SCOPE

This Statement of Work (SOW) sets forth the Government's requirements for the test, evaluation, repair, modification, and upgrade of Prime Mission Equipment (PME) Weapon Replaceable Assemblies (WRAs), Shop Replaceable Assemblies (SRAs), and components utilized in Electronic Warfare Systems.. Additionally, this tasking includes maintenance and repair of Government Furnished Equipment (GFE).

1.1 BACKGROUND

The impetus behind this SOW tasking is that the Government has a requirement to move repair of Legacy PME to commercial, off-site facilities to free up Government lab space for the Organic Depot Repair of PME utilized in newer/developing systems that require a higher level of Organic Government Engineering and Logistics Support.

2 APPLICABLE DOCUMENTS

The following documents of the revision or issue in effect at the date of award, form a part of this SOW. In the event of conflict between the documents referenced herein and the contents of this SOW, the contents of this SOW shall prevail.

2.1 DEPARTMENT OF DEFENSE SPECIFICATIONS, STANDARDS, MANUALS & INSTRUCTIONS

DoDD 5500.07	Ethics & Standards of Conduct, 15 May 2024
DoDD 5205.02E	DoD Operations Security (OPSEC) Program, w/Change 2, 20 Aug 2020
DoDD 5240.06	Counterintelligence Awareness and Reporting (CIAR), w/Change 3, 31 Aug 2020
DODI 4161.02	Accountability & Management of Government Contract Property, w/Change 2, 31 Aug 2018
DODI 5000.64	Accountability & Management of DOD Equipment and Other Accountable Property, w Change 3, 10 June 2019
DODI 5200.48	Controlled Unclassified Information (CUI), 06 Mar 2020
DODI 8582.01	Security of Non-DoD Information Systems Processing Unclassified Nonpublic DoD Information, 09 Dec 2019

DoDM 4140.01 Vol 6	DoD Supply Chain Material Management Procedures: Material Returns, Retention, and Disposition, w/Change 4, 03 Nov 2022
MIL-STD-129R	Military Marking for Shipment & Storage, w/Change 3, 25 Feb 2023
NAVSEAINST 5200.15	General Equipment – Accountability & Management, 27 Jan 2021
NSACRANEINST 5100.13A	NSA Crane Smoking and Tobacco Use Policy, 07 Mar 2013
NSACRANEINST 5510.1	Information Personnel and Industrial Security Manual, 20 Jan 2014
NSWCCRANEINST 3070.1B	Operations Security Program, 11 Mar 2025
NSWCCRANENOTE 3070	Operations Security Critical Information and Indicators List, 25 Feb 2025
NSWCCRANEINST 4855.10B	Electrostatic Control Program, 01 Oct 2021
NSWCCRANEINST 5100.1B	Occupational Health & Safety Program, 09 Feb 2023
NSWCCRANEINST 5100.2A	Contractor Environmental, Occupational Health & Safety Program, 13 Mar 2023
NSWCCRANEINST 5239.2B	Cybersecurity, 03 Feb 2023
NSWCCRANEINST 5530.1E	Naval Surface Warfare Center Crane Division Physical Security Policy Manual, 15 Apr 24
NSWCCRANENOTE 5530	Updates to 5530.1E Physical Security Policy Manual, 22 Aug 24
NSWCCRANEINST 5870.1D	Inventions Made By NSWC Crane Personnel & Support Contractors, 20 Aug 2020
NSWCCRANEINST 12735.1A	Workplace Violence Prevention, 12 July 2019
OPNAVINST 4440.26C	Accountability and Management of Operating Materials and Supplies & Government Furnished Property, w/Change Transmittal 1, 06 May 2025

SECNAVINST 5200.43A	Government Furnished Property, Accountability and Management, w/Change Transmittal 1, 04 Aug 2022
SECNAVINST 5510.34B	Disclosure of Classified Military Information and Controlled Unclassified Information to Foreign Governments, International Organizations, and Foreign Representatives, 11 Mar 2019

2.2 OTHER PUBLICATIONS

29 CFR 1910	Occupational Safety and Health Standards
32 CFR 117	National Industrial Security Program Operating Manual (NISPOM), Title 32, Part 117 of the Code of Federal Regulations
IPC-A-610J	Acceptability for Electronic Assemblies, Revision J, March 2024
IPC-7711/21D	Rework, Modification and Repair of Electronic Assemblies, Revision D, 06 Feb 2024
IPC-WHMA-A-620E	Requirements and Acceptance for Cable and Wire Harness Assemblies, Revision E, October 2022
ISO 9001:2015	Quality Management System – Requirements, 15 Sep 2015
NIST SP 800-171 Rev 3	Protecting Unclassified Information in Nonfederal Information Systems and Organizations, May 2024

2.3 ORDER OF PRECEDENCE

In the event of a conflict between the text of this document and the references cited herein, the text of this document takes precedence. Nothing in this document supersedes applicable Federal, State or Local Laws and regulations unless a specific exemption has been obtained.

2.4 AVAILABILITY OF DOCUMENTS

Government standards and handbooks are available from the Standardization Document Order Desk, 700 Robbins Avenue, Building 4D, Philadelphia, PA 19111-5094. Non-Government Publications are available from the National Standards Institute, 11 West 42nd Street, New York, NY 10036.

3 REQUIREMENTS

The Contractor shall conduct test, evaluation, repair, modification, and upgrades of PME, SRAs and Components utilized in Electronic Warfare Systems.

The test, evaluation, repair, modification and upgrades shall be executed via a phased approach. More specifically, the Government will contract on a per phase basis, dependent on the specific items/test equipment to be transferred to the Contractor to execute the subject test, evaluation, repair, modification and upgrades as well as test equipment maintenance/repair. The only phase that is assured to be contracted for is Phase 1, with Phase 2 being an option under the resulting contract.

The Contractor shall provide test, evaluation, repair, modification, and upgrade for the items listed in the applicable phase under Appendix A. The items in Appendix A include, but are not limited to, Radio Frequency (RF), Digital, and Analog assemblies; AC/DC Power Supplies; and RF Waveguide and Antenna Assemblies. Throughout the Period of Performance of the resulting contract, Appendix A may be modified by a bilateral modification to add additional items to Appendix A.

The Contractor shall provide labor, materials (beyond any provided Government Furnished Material (GFM)), any needed supplemental equipment (beyond any provided GFE), and facilities to perform the subject tasking. Additionally, the Contractor shall conduct maintenance and repair on the GFE Test Equipment (Manual & Automated Test Equipment). Furthermore, the Contractor shall conduct cable manufacturing, as needed to repair the next higher assembly. See Section 4 for information, materials, and equipment to be provided by the Government. As required, the Contractor may request replacement calibrated equipment for the Test Equipment and/or unique parts/material. As the situation allows, the Government may provide free issue GFM to repair, modify, upgrade PME, when adequate inventory is available.

The Contractor is authorized to conduct test & evaluation and repair up to the BER Repair Thresholds cited in Appendix A on a per repair basis. If/when the test & evaluation and the associated repair exceed the applicable BER Repair Threshold, the Contractor shall stop work and contact the Technical POC or COR to determine whether the Government would like the Contractor to either stop the repair or continue with the repair above the applicable repair threshold.

The Contractor shall conduct this tasking in accordance with IPC-A-610J, IPC-7711/21D, and IPC-WHMA-A-620E.

3.1 PROGRAM SUPPORT

The Contractor shall designate a Program Manager and Contracts Representative as Points of Contact (POCs) for all correspondence to and from the Government. The Program Manager and Contracts

Representative shall be available to the Government, as needed, via email and phone for the duration of the contract. The Program Manager shall report any Engineering/Technical issues pertaining to this contract to the Government. The Program Manager shall also be responsible to provide oversight of the program and management of the functional organizations supporting the program. The Contractor shall plan, schedule, and manage the effort to ensure internal control and timely completion of the tasks specified herein.

3.1.1 STATUS REPORTING

The Contractor shall submit a Bi-weekly (every two weeks) Status Report detailing the status of efforts under this contract. This report shall provide a roll-up of the status of all PME assets in each phase of this effort (TT&E, Repair/Modification/Upgrade) as well as status on an individual item basis. Furthermore, the average TAT (as defined in 3.7.5) across the entire contract for PME, as well as at the individual item level for PME, shall be calculated and reported. The Contractor shall also provide status on maintenance, repair, calibration, and modifications of GFE Test Equipment. Additionally, the Contractor shall report status of employee's completing their training requirements; see SOW 7.2 & 7.2.1. An attachment to the report shall be provided to show a breakout of the total cost incurred during the reporting period (every two weeks) and for the entire contract Period of Performance for Labor, Material, ODC cost. Additionally, the report shall show the breakout of Labor, Material, ODC per repair/Serial Number, with the attachment updated every two weeks to show final costs of Labor, Material, ODC per repair/Serial Number and to provide a history of the cost of all repairs for the Cost CLIN's. (CDRL A001)

3.1.2 AS NEEDED/AD-HOC STATUS MEETINGS

Monthly Status Meetings will be held at the Government or Contractor facility, unless the decision is made to hold it via telecom. When meetings are held at the Contractor's facility, the Contractor shall provide reasonable conference facilities and shall arrange necessary administrative assistance, as required. In the event of unique situations, meetings outside the monthly time increment may be required.

3.1.3 OBTAINING PARTS THROUGH NSWC CRANE DIVISION DEPOT, DLA, & NAVSUP

The Contractor shall obtain parts to repair PME/GFE Test Equipment via NSWC Crane Division Depot, the Defense Logistics Agency (DLA) website, and/or the Naval Supply System Command (NAVSUP) website. Upon the establishment of material needs the Contractor shall view current inventory status of GFM available at NSWC Crane Division Depot via Shop Workload Management System (SWMS) and/or ERP. If inventory is available it will be provided to the Contractor as GFM. Otherwise the Contractor will need to procure via DLA, NAVSUP or open market (subject to NSWC Crane Depot approval prior to placement of open market purchase).

3.1.4 PRODUCTION CONTROL SUPPORT

The Contractor shall provide planning and estimating of the use of labor, equipment, and materials in specific operations that employ systems and methods in the test & evaluation, repair, modification, and upgrade of Electronic Warfare Systems. The Contractor shall track all material and status in the Navy Enterprise Resource Planning (Navy ERP) and Shop Workload Management System (SWMS), which may

require Navy Marine Corps Intranet (NMCI) access and Common Access Cards (CAC). If NMCI connectivity is not in place at the Contractor's facility, the Contractor may request that the Government provide 1-2 NMCI laptops as GFP.

3.2 PME INDUCTION & NOTIFICATION PROCESS, OBSOLESCENCE & TURN-AROUND TIME (TAT)

3.2.1 INDUCTION

The Contractor shall induct the item and conduct the effort cited under 3.3.1 within 3 calendar days after the item is picked up from the Government Facility. The Contractor shall conduct the effort cited under 3.3.2 within 11 calendar days after the item is picked up from the Government Facility.

3.2.2 REPAIR/MODIFICATION/UPGRADES INDUCTION

After conducting the initial receipt and test & evaluation, the Contractor shall proceed to induct the item for repair, modification and/or upgrade unless the item is subject to No Fault Found (NFF), Beyond Economical Repair (BER), or Obsolescence/Diminishing Manufacturing Sources & Material Shortages (DMSMS).

3.2.3 NFF NOTIFICATION

The Contractor shall notify the Government Technical Point of Contact (TPOC) within 10 calendar days after conducting the initial receipt and test & evaluation, if the item is subject to NFF, as defined in 3.7.2.

3.2.4 BER NOTIFICATION

The Contractor shall notify the Government TPOC within 14 calendar days after conducting the initial receipt and test & evaluation if the item is considered a *potential candidate* for a Beyond Economical Repair (BER) determination, as defined in 3.7.3, and shall provide a report detailing the analysis that supports the BER determination to the TPOC, along with a detailed labor and material cost breakout associated with proceeding with repairing the item, in order to support this analysis. The Contractor shall await written direction from the Government Contracting Officer (KO) or TPOC as to whether the Contractor shall 1) Dispose of the item; 2) Return the item to NSWC Crane Division, in as-is condition; and/or 3) Proceed with the repair, even though it's above the BER Threshold listed in Appendix A. The Government KO and/or TPOC has the authority for making a final determination as to whether the item is BER. (CDRL A002)

3.2.5 OBSOLESCENCE / DIMINISHING MANUFACTURING SOURCES & MATERIAL SHORTAGES (DMSMS)

Obsolescence Management includes reverse engineering of obsolete components associated with the PME specified in Appendix A. The Contractor shall notify the Government TPOC/KO within 14 calendar days after conducting the initial receipt and test & evaluation if the anticipated repair, modification, or upgrade of the applicable item cannot be completed due to obsolescence or a DMSMS issue. The Contractor shall await the Government KO's written guidance as to how the parts and/or material will be obtained/provided or whether to 1) Dispose of the item or 2) Return the item to NSWC Crane Division, in as-is condition. Additionally, if this is identified during the repair, modification, or upgrade the Contractor shall immediately stop work and notify the Government TPOC/KO of the obsolescence/DMSMS issue. The Government may then utilize the applicable Fleet Support Team (FST) to identify a suitable replacement or provide stored material to facilitate the repair.

If the FST is unable to address the situation and the TPOC/KO determines that the item still needs repaired, and the Government KO so notifies the Contractor, the Government will provide any authorized data (tech data packages, drawings, specs, etc.) to the Contractor. The Contractor shall then investigate alternate sources within industry for compatible replacement parts that meet the required quality requirements and do not affect the form, fit, or function (FFF) of the end item. This investigation will be done under a separately priced negotiated contract line item (CLIN). A technical report detailing the replacement component and associated labor cost data, material cost data, a technical data package of the component, and the Engineering Change Proposal (ECP) data, as well as delivery of one manufactured component that is form, fit, and function compatible, shall be provided to the Government. However, if a suitable replacement component is not found, the Contractor will notify the Government TPOC/KO. (CDRL A002)

As of the date the Government KO receives notice of the obsolescence/DMSMS issue, the delivery date will be suspended and reestablished by mutual agreement by the parties without penalty.

3.2.6 TURN-AROUND TIME (TAT)

The TAT sought for each individual PME asset is cited in Appendix A and an assessment of the Contractor's performance shall include the Contractor's ability to meet the TAT in Appendix A for the subject items. (Note: The TAT calculation excludes parts/components with a production lead-time greater than 30 days or greater than the end items overall TAT goal).

3.3 PME INITIAL RECEIPT, TEST & EVALUATION, REPAIR, MODIFICATION, UPGRADE

3.3.1 INITIAL RECEIPT

The Contractor shall verify the GFP is listed on the correct Navy document (i.e. DD1149, DD1348, Custody Receipt documents, etc.). GFP must undergo a visual inspection. In the event the WRA, SRA, or component is determined to be subject to Missing on Induction (MOI), as defined in 3.7.1, the Contractor shall notify the Government TPOC within three business days. The Government will then provide the missing parts/components to the Contractor or direct the Contractor to procure the subject parts via DLA, NAVSUP, or open market (subject to Government TPOC approval prior to placement of open market purchase) and install them as part of the repair. If during testing, evaluation, repair, modification or upgrade it is determined additional parts/components are missing, the Government will work with the Contractor as needed to satisfy the requirement. Upon the verification of the GFP matching the associated documentation, the Contractor shall provide a signed copy of the DD1149 or DD1348 to the Government for ERP processing and Key Supporting Documentation (KSD).

3.3.2 TEST & EVALUATION

Once the effort under 3.3.1 is complete, the Contractor shall induct the item(s) per 3.2.1 and conduct test & evaluation of the applicable item(s) listed in Appendix A. The Contractor shall screen the item for possible causes of failure by performing a visual inspection, cleaning the unit, disassembly, testing the unit per the applicable Acceptance Test Procedure (ATP) utilizing the provided GFP Test Equipment, and any other applicable troubleshooting methods. The Contractor shall classify the item into one of the following four (4) categories: NFF, Repairable/Modification/Upgrade, BER, Obsolescence/DMSMS. NFF shall be handled per 3.2.3 & 3.3.3. Repairable/Modification/Upgrade shall be handled per 3.2.2 & 3.3.4. BER shall be handled per 3.2.4. Obsolescence/DMSMS shall be handled per 3.2.5. The Contractor shall document in SWMS the failure(s) for each item in the Repairable/Modification/Upgrade, BER, and Obsolescence/DMSMS categories.

3.3.3 NO FAULT FOUND (NFF)

If the item is NFF, as defined in 3.7.2, and there are no outstanding Engineering Change Orders (ECOs), Technical Directives (TD's) and/or Avionics Changes (AVC's)(see 3.6.1), and the Government hasn't directed any modifications or upgrades, the Contractor shall re-certify the item as Ready for Issue (RFI) Serviceable Operating Condition, as defined in 3.7.4, stamp appropriate MIL-STD RFI Tags, return the item back to NSWC Crane, and provide a Test Report (along with scanned test data sheets and calibration data showing the item successfully passed) to the Government. (CDRL A003)

If the item is NFF but there are outstanding ECO's, TD's, AVC's(see 3.6.1), and/or the Government has directed modifications or upgrades, the Contractor shall incorporate the subject ECO's, TD's, AVC's,

and/or modifications/upgrades, test the unit per the applicable Acceptance Test Procedure (ATP) utilizing the provided GFP Test Equipment, re-certify the item as Ready for Issue (RFI) Serviceable Operating Condition (as defined in 3.7.4), stamp appropriate MIL-STD RFI Tags, return the item back to NSWC Crane, and provide a Test Report (along with scanned test data sheets and calibration data showing the item successfully passed) to the Government.. (CDRL A003)

3.3.4 REPAIR, MODIFICATION, UPGRADE

If faults are found, the Contractor shall repair the item. Repairs could include the removal and replacement of SRAs and/or Circuit Card Assemblies (CCAs); removal and replacement at the component level, utilizing approved soldering procedures and equipment (to include surface mount, thru-hole, wiring, connector replacement, etc.) cited in 2.2; repair of chassis assemblies, wiring harnesses, harness fabrication and re-wiring; reassembly and alignment; calibration; painting; as well as incorporation of applicable modifications and upgrades as directed by the Government. The Contractor shall repair, modify, and or upgrade the unit to the latest approved drawings and specification control drawings, in order to bring the item to the most up-to-date configuration. The subject items shall be repaired, modified, upgraded to a RFI serviceable operating condition, as defined in 3.7.4, with this being verified by testing the unit per the ATP, utilizing the provided GFE Test Equipment. (Note: This may involve installing the repaired unit in its Next Higher Assembly (NHA), and having the NHA pass the subject ATP testing). Once repaired, the Contractor shall re-certify the item as RFI Serviceable Operating Condition (as defined in 3.7.4), stamp appropriate MIL-STD RFI Tags, return the item back to NSWC Crane, and provide a Test Report (along with scanned test data sheets and calibration data showing the item successfully passed) to the Government. (CDRL A003)

Note: Cannibalization of NHAs may be required to obtain components to repair other assemblies or to provide required parts. This process may include the removal and replacement of components in a test bed in order to pass final testing.

3.4 TEST EQUIPMENT MAINTENANCE, REPAIR, & MODIFICATIONS

The Contractor shall maintain and repair the GFE Test Equipment (both manual and automated test equipment) by ensuring the test equipment undergoes regular maintenance and is calibrated. In the event test equipment is going out of calibration or encounters a failure, the Contractor shall contact the Government to coordinate calibration support, acquire repair parts and/or technical assistance from the Government, and obtain assistance from the Government in order to conduct modifications to the test equipment, on an as needed basis. Calibrated test Equipment shall be picked up and/or delivered to Crane by the Contractor.

3.5 RESERVED

3.6 GENERAL AND SPECIAL INSTRUCTIONS

3.6.1 ECO'S, TD's, AVC's

Incorporate Engineering Change Orders (ECO's), Technical Directives (TD's) and/or Avionics Changes (AVC's) into assemblies/subassemblies as necessary to support repair of the unit. For ECO's, these shall be limited to Minor, Class II ECO's which are required for safety purposes, to maintain functional or performance reliability, that DO NOT affect the form, fit, function, compatibility, or interfacing of the unit. Any changes that may affect the form, fit, function, compatibility, and/or interfacing (CLASS I Changes) shall be performed ONLY upon the written approval of the Government TPOC or KO.

3.6.2 PARTS DISPOSAL

Parts disposal shall be IAW FAR Part 45 – Government Property and Contractor's Property Management System. Removed non-functioning consumable parts become the property of the Contractor and will be disposed of in accordance with proper Supply DEMIL coding, good commercial practice and applicable laws and regulations. The removed failed consumable parts shall not be reused.

3.6.3 EQUIPMENT IDENTIFICATION TAGS / DECALS

Upon completion of rework, the Contractor shall ensure that the unit possesses the applicable MIL-STD-129R identification tag, decal, or other suitable marking affixed to each item on an area easily located and contain, at a minimum, the following information:

- National Stock Number (NSN)
- Part Number
- Item Description/Nomenclature
- Serial Number
- Unit of Issue and Quantity
- Quality Assurance Inspector Stamp for RFI assets, with date of stamping/RFI.

3.6.4 PACKAGING & SHIPPING INSTRUCTIONS

The Contractor shall retain all accompanying non-serviceable paperwork (VIDS/MAF's, DD1577-2 Unserviceable Tags, failure write-ups, etc) received with the unit and return to the Government when the asset is Ready for Issue (RFI) via scanned image or paper copies. The Contractor shall provide at least one copy of the Wide-Area-Work-Flow (WAWF) Shipping/Receiving Report to the COR/TPOC along with the aforementioned incoming and final QA documents for records retention purposes. SRAs shall be packaged by best commercial practices for transportation to NSWC Crane.

Packaging and shipping of WRAs/SRAs will be in accordance with 32 CFR 117 as well as the DD 254 requirements, for COMSEC, and GFE reusable white pelican cases.

3.6.5 PACKAGE MARKINGS

Package markings will be in accordance with commercial practice. The Contractor shall not reference National Stock Numbers (NSN's) on the equipment packaging. The Contractor shall clearly identify, by decal, sticker, or other markings, the following information on the exterior of the shipping container:

- Part Number
- Serial Number
- Quantity

3.7 DEFINITION OF TERMS

3.7.1 MISSING ON INDUCTION (MOI)

MOI is defined as a unit that when received by the Contractor is found to have missing major repairable components/assemblies/subassemblies (Power Supplies, CCA's, etc.). Units having only minor items missing such as fuses, switches, handles, lamps, connectors, buttons, screws, nuts, and bolts are not to be classified as MOI.

3.7.2 NO FAULT FOUND (NFF)

An item that is inspected, tested, and deemed to not require any repairs. The item is found to be fully functional, operable, satisfies its intended function, and performs within its design specifications.

3.7.3 BEYOND ECONOMICAL REPAIR (BER)

An item is to be considered a potential candidate for a BER determination when the cost of repair is estimated to exceed the threshold amount listed in Appendix A.

3.7.4 READY FOR ISSUE (RFI) SERVICEABLE OPERATING CONDITION

The condition in which a repairable assembly is capable of meeting all operating and functional requirements for which it was designed.

3.7.5 TURN AROUND TIME (TAT)

TAT starts on the date when the Contractor picks up the item from the Government facility and it ends on the date that the item is back at the Government facility. The TAT calculation excludes parts/components with a production lead-time greater than 30 days or greater than the end items overall TAT goal).

3.7.6 DEPOT MAINTENANCE INTER-SERVICE SUPPORT AGREEMENT (DMISA)

The DMISA is a formal agreement similar to a contract whereby one military Service (the Agent) agrees to provide depot maintenance support for another Service (the Principal). It may also be used when a Service is the Agent and another federal department agency or element thereof is the Principal. DMISA assets will be picked up by the contractor and returned by the contractor to NSWC Crane upon RFI or Non-Serviceable condition.

3.7.7 CONCURRENT REPAIR

Consist of assets that are subassemblies, Shop Repairable Assemblies (SRAs) of a next higher assembly, Weapons Replaceable Assemblies (WRAs) that are being repaired or assembled by the Government. Concurrent SRAs will be removed from the WRA, picked up by the Contractor and upon RFI status returned to the Government to be installed in the WRA.

3.8 QUALITY PROGRAM

The Contractor shall maintain a quality system that is certified to ISO-9001:2015 or equivalent.

3.9 CONTRACTOR FACILITY & STORAGE REQUIREMENTS

See SOW attachment as this information is Distribution Statement D, Controlled Unclassified Information (CUI).

3.10 TRANSITION OF WORKLOAD

The Contractor will have up to 185 days from the date of contract award and funds being applied to transition the Government Depot workload to their facilities, and take sole responsibility for this workload. The Contractor shall be required to install the GFE to include electrical, cooling (water and air) requirements, and the Contractor shall be familiar with the physical constraints of the existing interface

cabling. The Government will ship the GFE to the Contractor's site and provide technical support as requested in the interface cabling requirements between test beds.

At the Contractor's request, and in order to assist in the transition, the Government will allow Contractor personnel (1-2 FTEs) to work within the Government facility for up to 125 days prior to the movement of the test equipment to adequately train and certify the workforce. These 1-2 FTEs will then serve to train the remaining personnel once the workload has transitioned to the Contractor's facility. The aforementioned personnel will require a secret clearance to operate within the Government labs and Common Access Cards (CAC) may be provided to visiting Contractor employee's during this timeframe, dependent upon the length of stay and other factors, if so approved by the Contracting Officer's Representative.

4 GOVERNMENT FURNISHED PROPERTY (GFP)

GFP is required for completion of tasks under this SOW.

4.1 PROCUREMENT INTEGRATED ENTERPRISE ENVIRONMENT (PIEE) GFP MODULE REPORTING & ACCOUNTABILITY

All Government Furnished Property is property of the U.S. Government and shall not be transferred to any individual or agency, public or private, without the express written approval of the originating Contracting Officer except as required for the specific performance of tasks under this contract/order. Accountability for Government Property under this contract/order shall be managed in accordance with FAR Part 45, DFARS Part 245 and DFARS PGI Part 245 as well as the Government Property clauses in the contract whether acquired by the prime or subcontractors (Contractor Acquired Property), provided by the Government, or received directly from another commercial source as a deliverable from a Government issued contract. Additional Government Property accountability requirements are outlined in the following Directives and Instructions and shall be adhered to as applicable:

- DoDI 4161.02, Accountability & Management of Government Contract Property
- DoDM 4140.01, DoD Supply Chain Material Management Procedures: Material Returns, Retention and Disposition, Volume 6
- DoDI 5000.64, Accountability & Management of DoD Equipment and Other Accountable Property
- OPNAVINST 4440.26C, Operating Materials & Supplies and Government Furnished Material Management
- SECNAVINST 5200.43A, Government Furnished Property, Accountability and Management
- NAVSEAINST 5200.15, General Equipment Accountability & Management

4.1.1 RECEIPT REPORTING

FAR 52.245-1(f)(1)(ii) requires the contractor to report receipt of all GFP. Reporting of Government Furnished Property (DFARS 252.245-7005) and DoDI 4161.02, Accountability and Management of

Government Contract Property Instruction requires that contractors, as part of the required receipt of any Government property, report to the DoD IUID Registry using WAWF, DLMS transactions, or direct update of the registry. Contractors shall ensure appropriate accountable property records are maintained utilizing the data reported in the DoD IUID Registry and its integral GFP Module in the Procurement Integrated Enterprise Environment (PIEE). At the time of reporting receipt of GFP in the GFP Module, the contractor will also send an email notification to cran_gfpaccounta.fct@navy.mil to ensure the NSWC Crane Property Management Division is notified.

4.1.2 SHIPPING NOTIFICATION

DoDI 4161.02 requires use of electronic transactions when transferring Government property to a contractor and upon return of property to DoD. The contractor shall use the GFP Module in PIEE when returning GFP back to the Government. At the time of creating the shipping document to return GFP using the GFP Module, the contractor will also send an email notification to cran_gfpaccounta.fct@navy.mil to ensure the NSWC Crane Property Management Division is notified.

4.1.3 CONTRACTOR-ACQUIRED PROPERTY (CAP)

FAR 52.245-1 defines CAP as property acquired, fabricated, or otherwise provided by the Contractor for performing a contract, and to which the government has title. To request CAP conversion to GFP or contractor to buy back, the contractor must utilize the CAP Pre-screening capability within the PIEE GFP Module.

4.1.4 LOST, DAMAGED OR STOLEN GFP REPORTING

FAR clause 52.245-1 requires the contractor to investigate and report to the Government all incidents of property loss as soon as the facts become known. DFARS 252.245-7005 further requires the contractor to report lost, damaged or stolen government property using the Property Loss functionality within the PIEE GFP Module.

4.1.5 EXCESS PROPERTY REPORTING

SECNAVINST 5200.43A requires unused or excess GFP be properly dispositioned as soon as the excess is identified without waiting for formal contract closeout processing. Recovering excess property from the contractor will be completed by the return of GFP back to the government via a DD-1149 or utilizing the GFP Module Plant Clearance capability as soon as possible to ensure the property is available to fill other requirements and can potentially reduce the administrative costs of the contract. The Government-appointed Plant Clearance Officer (PLCO) will accept or reject the request to excess GFP using the GFP Module Plant Clearance capability.

4.2 INVENTORY REPORTING

FAR 52.245-1 requires the contractor to periodically perform, record, and disclose physical inventory results. While the FAR clause does not define “periodically,” frequency of on-hand inventory count are in the Contract Data Requirements List (CDRL) identified in this contract.”

4.2.1 GFP REPORTING

The contractor shall provide data deliverables IAW the listed CDRLs by contract and contract order number (if applicable) to provide accountability for all Government furnished property that has been provided in support of the contract. The report shall include the fields required by the Data Item Description noted in the CDRL, DFARS 252.245-7005 and DFARS PGI 245.103-72 for the purpose of accountability. (CDRL A004, A005)

4.3 PROPERTY PASS ISSUANCE

Upon delivery of GFP, including NMCI assets and peripherals, directly for use by contractor personnel via a government issued DD-1149, contractors required to travel to and from a government installation with GFP must maintain a contractor issued OF7-20 with their assigned asset at all times. This includes contractors allowed to telework that will be taking their computer on and off a Government site. Contractors may be required to show proof of issuance at security checkpoints upon entry or departure of the installation. OF7-20 is available at <https://www.gsa.gov/forms-library/property-pass>

4.4 GOVERNMENT FURNISHED INFORMATION

The Government will provide all applicable technical documentation and information as GFI. If additional technical documentation is requested by the Contractor, the Government TPOC will provide to the Contractor if it is available and determined to be applicable to the current workload.

4.5 GOVERNMENT FURNISHED EQUIPMENT/MATERIAL (GFE/GFM)

The Government will provide all applicable test beds and special test equipment to support funded repairs as listed in Appendix A as Government Furnished Equipment (GFE). The Government will provide all existing interface cables required for set-up. The Contractor will be required to maintain all test beds in an operational condition. General Purpose Electronic Test Equipment (GPETE) (i.e. standalone multimeters, oscilloscopes, frequency generators, etc.) will not be provided. The Contractor shall track and maintain all calibrated equipment. GFE test equipment can be returned to NSWC Crane for calibration or will be calibrated on site by Government calibration technicians in the event of a field calibration requirement. Upon initial transfer, the Government will ship the GFE to the Contractor's site and provide technical support as requested on the interface requirements between test beds. The Government will also provide 1-2 NMCI laptops in the event the contractor does not have current NMCI connectivity and assets, upon request.

In addition to the GFE test equipment to be provided, GFM may be provided when components/materials are available from current Government stock for the completion of the funded repair. The Contractor shall pick up the assets to be repaired, as well as any GFM, at the Government's Facility and drop off the repaired assets at the Government's Facility. Additionally, the Contractor shall provide Government bonded storage

for the assets to be repaired (and assets once they are repaired) while work is being planned, in progress, and awaiting shipment. All unused GFM shall be returned to the Government at the completion of the contract.

4.6 GOVERNMENT FURNISHED FACILITIES (GFF)

Contractor personnel performing tasking within NSWC Crane facilities will be authorized access to Government owned or leased facilities which are required for use during the performance of tasks stated in this contract/order. Facilities provided will include general and classified labs, production or office spaces, and other spaces as the tasking requires. The spaces will include standard desks, chairs, lab tables and other items associated to the facilities as needed to perform the tasking. Landlines for phones and network connectivity will be provided as required to accomplish the tasking performed under the contract/order. Facilities the contractor personnel are assigned to at NSWC Crane may be periodically changed as office areas are moved to accommodate facility upgrades, conform to re-organizations within the NSWC Crane Division or incorporate continuous improvement process changes to improve efficiency.

5 DATA DELIVERABLES

The Contractor shall provide the following deliverables IAW the SOW & CDRL requirements:

Data Description	Data Sequence Number	SOW Paragraph	DID Number
Status Report	A001	3.1.1, 7.2, 7.2.1	DI-MGMT-80368A
Technical Report-Study/Services	A002	3.2.4, 3.2.5	DI-MISC-80508B
Test/Inspection Report	A003	3.3.3, 3.3.4	DI-NDTI-80809B
Government Furnished Material (GFM) by National Stock Number (NSN). Baseline Report.	A004	4.2.1	DI-PSSS-80727A
Government Property (GP) Inventory Report. Quarterly Report.	A005	4.2.1	DI-MGMT-80441D
Accident/Incident Report	A006	6.1.5, 7.3.2	DI-MGMT-82188
Contractor's Safety Plan	A007	7.3	DI-SAFT-82080

6 ADMINISTRATIVE

6.1 SECURITY INFORMATION

See SOW attachment as this information is Distribution Statement D, Controlled Unclassified Information (CUI).

7.0 SPECIAL CONDITIONS

7.1 PLACE OF PERFORMANCE

Performance shall take place at Naval Surface Warfare Center – Crane Division for the transition period, for the applicable Phase. After the transition period for the applicable phase, all performance shall take place at the Contractor’s facility(ies).

7.2 LICENSES, CERTIFICATIONS, & TRAINING

The Contractor shall provide capable personnel with qualifications, experience levels, security clearances, and necessary licenses, certifications, and training required by Federal, State, and Local laws and regulations. Training necessary to ensure that personnel performing under this contract maintain the knowledge and skills to successfully perform the required functions is the responsibility of the Contractor.

The following types of certifications or training are required to complete the subject tasking at the applicable site, along with a delineation of when the certifications/training are required and if they are subject to follow-on certifications/training requirements.

Certifications/Training	Government Site (Transition Period)	Contractor Site	Required Prior to Starting Transition Training at Gov Site	Required prior to Performing Tasking At Contractor Site	Requires Annual Recertification's & Re- evaluations
Electrostatic Discharge Training	X	X	X		Every 12 months
Hazards of Electromagnetic Radiation to Ordnance (HERO) Training	X		X		
IPC-7711/21D Certification	X	X	X		Recert Every 24 Months
IPC-A-610J Inspection Certification (Required only for Quality Assurance Inspectors)		X		X	Recert Every 24 Months
IPC-A-620E Inspection Certification (Required only for Quality Assurance Inspectors)		X		X	Recert Every 24 Months

The Contractor shall report status of the employee’s completing their training requirements in the status report (CDRL A001)

7.2.1 ELECTRO-STATIC DISCHARGE TRAINING

Contractors performing tasking at Government (NSWC Crane) facilities shall complete Electro-Static Discharge (ESD) awareness training on an annual basis IAW NSWCCRANEINST 4855.10B.

Contractors may complete the training within the NSWC Crane Enterprise Safety Applications Management System (ESAMS) to meet the ESD requirements: https://esams.cnmc.navy.mil/ESAMS_Gen_2/Login

-or-

Contractors may complete training provided by the contractor or a commercial external source if the training meets the minimum requirements set out in NSWCCRANEINST 4855.10B, Ch 1, Section 4. Labor may not be direct charged to the Contract for the completion of the ESD training regardless of whether provided by the contractor or via ESAMS.

If utilizing ESAMS for ESD training, the contractor shall provide the following information to the COR for all employees performing under the Contract requiring ESD certification prior to execution of any covered tasking:

Contract #
Company Name
Employee Name
NSWC Crane Division Supported

The contractor shall document all employees involved in ESD covered tasking, and shall include the following information as a running tally in the bi-weekly status report (CDRL A001)

Employee Name
Source of Training
Completion Date of Training
Test Score

7.3 OCCUPATIONAL SAFETY, HEALTH AND ENVIRONMENTAL REQUIREMENTS

The contractor shall be responsible for ensuring the safety of all company employees, other working personnel, and Government property. The contractor is solely responsible for compliance with the Occupational Safety and Health Act (OSHA) (Public Law 91-596) and the resulting applicable standards, OSHA Standard 29 CFR 1910 (general) and for the protection, safety and health of their employees and any subcontractors assigned under this contract. These regulations apply to all related work, as defined in the regulations. Nothing contained in this contract shall be construed as relieving the Contractor from any obligations which it may have for compliance with the aforesaid regulations.

The contractor must have on record a corporate safety plan IAW the Occupational Safety and Health Act. The Corporate Safety Plan shall be made available to the NSWC Crane Safety Office to review upon request by the COR. (CDRL A007)

Prior to starting work at the Government Site the contractor shall ensure all employees have appropriate personal annual mandatory safety training in the following areas to perform tasking on a Government facility:

- NSW Crane Hazards of Electromagnetic Radiation to Ordnance (HERO), located on ESAMS (see 7.2.1)

The following safety training shall be completed prior to an employee of the contractor (or subcontractor) commencing work requiring the training:

Government Site Performance:

- Electrostatic Discharge Training
- IPC-7711-21D Certification

Without government assistance, the contractor shall make certain that all safety requirements are met, safety equipment is provided, and safety procedures are documented as part of its safety plan.

7.3.1 INSPECTIONS

The contractor shall cooperate fully with health, safety, or environmental inspectors from local, State, or Federal agencies. The contractor shall coordinate response to inspection requests or requests for data made by all external agencies with the COR.

7.3.2 ACCIDENT/INCIDENT REPORTING

The contractor shall report all mishaps involving damage to property or injury to personnel. The contractor shall provide written documentation to the COR of the circumstances surrounding any potentially dangerous situation through the most prudent means available based on the situation. (CDRL A006)

7.3.3 SAFETY REPORTS

The contractor shall not release any safety related reports to any state, local, or other federal agency or local base authority without written approval of the COR. Stipulations of the release may include copies or other actions required by the COR.

7.3.4 PERSONAL PROTECTION EQUIPMENT (PPE)

PPE is provided by the Contractor company to its employees unless otherwise agreed upon by the Contracting Officer in writing.

7.4 CONTROL OF CONTRACTOR PERSONNEL

Comply with the requirements of NSACRANEINST 5510.1. All persons engaged in work while on Government property shall be subject to search of their persons (no bodily search) and vehicles at any time by the Government, and shall report any known or suspected security violations to the NSWC Crane Division Security Department. Assignment, transfer, and reassignment of Contractor personnel shall be at the discretion of the Contractor. However, when the Government directs, the Contractor shall remove from contract/task order performance any person who endangers life, property, or national security through improper conduct. All Contractor personnel engaged in work while on Government property shall be subject to the Standards of Conduct contained in DoDD 5500.07. Within 15 working days of contract award, the Contractor shall provide a list of employees working under this contract, containing employee names, security clearance levels, and labor categories. This list shall be updated and submitted to the Government within forty-eight hours after changes occur.

The control of contractor at other Government locations shall be governed by those Government Base's local instructions.

7.5 CONTRACTOR IDENTIFICATION

7.5.1 IDENTIFICATION BADGES

Obtain identification badges from the Government for access to Government facilities. The identification badge shall be visible at all times while employees are on NSWC Crane property. The Contractor shall furnish all requested information required to facilitate issuance of identification badges and shall conform to applicable regulations concerning the use and possession of the badges. The Contractor shall be responsible for ensuring that all identification badges issued to Contractor employees are returned to the NSWC Crane Security Department within forty-eight hours following the completion of the contract/task order, relocation, or termination of an employee issued an identification badge, and upon request by the Contracting Officer.

The use of identification badges at other Government locations shall be governed by those Government Base's local instructions.

7.5.2 GENERAL IDENTIFICATION

This contract is for non-personal services as defined by FAR Subpart 37.104. As such, Contractor employees shall identify themselves as Contractor personnel by introducing themselves or being introduced as Contractor personnel and displaying badges or other visible identification for meetings with Government personnel. In addition, Contractor personnel shall appropriately identify themselves as Contractor employees in telephone conversations and in formal and informal written correspondence.

7.6 SMOKING REGULATIONS

Smoking on NSWC Crane premises shall be in approved areas only in accordance with NSACRANEINST 5100.13A – Smoking in vehicles is prohibited.

Smoking at other Government locations shall be governed by those Government Base's local instructions.

7.7 RELEASE OF INFORMATION

All technical data provided to the Contractor shall be protected from the public. All other information under this contract may not be disclosed by any means without prior approval of the authorized representative of the Contracting Officer. Dissemination or public disclosure includes, but is not limited to, permitting access to such information by foreign nationals by any other person or entity, or publication of technical or scientific papers, or advertising or any other proposed public release. The Contractor shall provide adequate physical protection to such information so as to preclude access by any person or entity not authorized such access.

7.8 NON-PERSONAL SERVICES

The Government will neither supervise Contractor employees nor control the method by which the Contractor performs the required tasks. Under no circumstances will the Government assign tasks to, or prepare work schedules for individual Contractor employees. It shall be the responsibility of the Contractor to manage its employees and to guard against any actions that are of the nature of personal services, or give the perception of personal services. If the Contractor feels that any actions constitute, or are perceived to constitute personal services, it shall be the Contractor's responsibility to notify the COR and/or CS immediately. Support services under this contract shall not be used to perform work of a policy/decision making or management nature, i.e., inherently Governmental functions. All decisions relative to programs supported by the Contractor shall be the sole responsibility of the Government.

7.9 CONTRACTOR WORK SCHEDULES

NSWC Crane core duty hours for on-site Contractor personnel and the Contractor's liaison facility personnel assigned to this effort are 0900 to 1430 hours, Monday through Friday, during regular Government workdays. Government personnel are afforded flextime schedules depending on the applicable work schedule. In addition Government personnel in some work areas may be on a compressed work schedule with every other Friday as a Regular Day Off. On-site contractors are allowed in Government spaces only when Government personnel are present. Contractor work schedules are to be established by the contractor program manager in such a manner as to ensure the tasking assigned is completed in the most cost effective and efficient manner in accordance with company timekeeping policies. Flex-time and compressed work schedules may not be allowed for employees involved with training, specific testing

operations where the workday is established based on range operation schedules and availability or other specific tasking.

Additionally, the Contractor may be required to have its personnel work a flexible or fixed schedule, to meet special Government needs or circumstances.

The Contractor may be required to respond to an emergency and work outside of regular working hours to perform the work when the need arises. The COR will notify the contractor if coverage outside of regular working hours is required. If overtime is required and not approved in the task order, the contractor must obtain Contracting Officer to charge overtime to the task order.

The contractor shall notify the Government if any work schedule changes required by the Government have cost or schedule impact IAW FAR 52.243-2, Alt I, Changes—Cost Reimbursement.

7.10 GOVERNMENT FACILITY INFORMATION

7.10.1 CLOSED DAYS

All closed days will be designated by the Commander, NSWC Crane Division. Closed days will be associated with holidays, National Security, and/or inclement weather/dangerous conditions. The Contractor shall not be allowed to work on NSWC Crane Division during designated closed days, unless they are deemed to be essential personnel. Essential personnel will be identified by the Government, and communicated to the Contractor prior to the designated closed day, and will be authorized by the COR/Contracting Officer and specified on individual contract/order/or task instruction. In the event the Contractor is prevented from performance as the result of an Executive Order or an administrative leave determination applying to the using activity, such time may be charged to leave or indirect charges IAW the company policy. Closed days will also impact asset transportation to and from Government facilities so steps should be taken ahead of time to mitigate work-stoppage conditions.

Closed days at other Government locations shall be governed by those Government Base's local instructions and policies.

7.10.2 INCLEMENT WEATHER

When the Government Agency is closed by the Commander because of inclement weather conditions and/or dangerous conditions, notification of the closing will be broadcast over local radio and television stations.

7.10.3 HOLIDAYS

A list of Government Agency observed holidays and/or closed days in conjunction with holidays will be published at the beginning of each calendar year. Contractor employees will not be allowed to work on Government property on a holiday and/or closed day unless they are deemed to be essential personnel. The Contractor is advised that access to the Government installation may be restricted on these holidays:

New Year's Day	Birthday of Martin Luther King Jr.
President's Day	Memorial Day
Juneteenth	Independence Day
Labor Day	Columbus Day
Veteran's Day	Thanksgiving Day
Christmas Day	

In the event any of the above holidays occur on a Saturday or a Sunday, then such holiday shall be observed by the Contractor IAW the practice as observed by the assigned Government employees at the using activity.

7.11 INVESTIGATIONS

Contractor employees shall cooperate with Government investigative agencies conducting criminal or administrative investigations.

7.12 GOVERNMENT OBSERVATIONS

Government observations, such as Inspector General or higher Headquarters staff are authorized to observe Contractor operations. Efforts will be made to minimize the degree of disturbance on Contractor performance.

7.13 WORK AREA CLEANLINESS

The Contractor shall be responsible for the orderliness and cleanliness of all Government controlled areas being used by the Contractor for office and storage. The space shall be clean, neat, and free from fire hazards, unsanitary conditions, and safety hazards.

7.14 KEY CONTROL

The Contractor shall establish and implement methods of ensuring that all keys issued to the Contractor by the Government are not lost or misplaced and are not used by unauthorized persons. The Contractor shall not duplicate any keys issued to the Contractor by the Government. The Contractor shall develop procedures

covering key control. Key control and accountability shall be IAW the key control requirements set forth in applicable regulations.

7.15 EXISTING CONDITIONS

In the performance of work under this contract, the Contractor is not responsible for any existing conditions (conditions that exist prior to as of the effective date of this contract) at the GFF, and the Government will reimburse the Contractor for any costs or liability the Contractor might incur as a result of these existing conditions. The Contractor shall participate with the Government in a joint inspection of the facilities to establish baseline conditions at the start of the performing period.

7.16 DATA RIGHTS

All data/documentation delivered/created in support of this effort will be delivered and marked IAW FAR Part 27 and DFARS Part 227 clauses identified in the contract. Data required from this contracting action shall be delivered in English with applicable numbering in United States or metric units. The Government will have rights to reproduce and use all submitted deliverables IAW FAR Part 27 and DFARS Part 227 clauses identified in the contract.

7.17 INFORMATION NON-DISCLOSURE

Contractor personnel may be required, from time to time, to sign Non-Disclosure Agreements as applicable to specific SOW tasking. The COR will notify the contractor of the number and type of personnel that will need to sign the Non-Disclosure agreements. The signed Non-Disclosure Agreements shall be executed prior to accessing data or providing support for information that must be safeguarded. The NDA must be returned to the COR for endorsement and retention. Copies of all executed NDAs shall be provided to the COR. NDAs signed apply only to Government owned information. NDAs with NSWC Crane are not applicable to information marked proprietary to Commercial Organizations and do not authorize contractor personnel access to commercial entity proprietary data. Therefore contractor personnel may be required to sign NDAs with third party organizations in order to protect proprietary data of those third party organizations. Contractors being granted access to proprietary data of third party organizations shall notify the Contractor Program Manager and ensure proper third party NDAs are in place prior to accessing the data. If tasking cannot be completed without access to third party proprietary data and the proper NDAs are not in place, the contractor shall immediately notify the COR.

7.18 ADDITIONAL REQUIREMENTS

The Contractor is required to adhere to the following instructions in performance under this contract:

NSWCCRANEINST 3070.1B, NSWCCRANEINST 5100.1B, NSWCCRANEINST 5100.2A,
NSWCCRANEINST 5239.2B, NSWCCRANEINST 5530.1E, NSWCCRANENOTE 5530,
NSWCCRANEINST 5870.1D, NSWCCRANEINST 12735.1A.