

P1080 PRICE SCHEDULE

30 DEC 2025

Provide line item prices, where indicated by blank underlines, for the following items:

Line Item	Description	Quantity	Unit	Unit Price	Sub-Total	Total Price
0001.	BASE PRICE: Total CLIN 0001 Price for Project P-1080 On-Base Power Electrical Improvements CLINs 0001.A thru 0001.AC for Drawing Work Areas A, B, C, D, E, F, G, H, J, L, M, N, O, and Other Costs as noted below. The project objectives are to provide upgrades and modifications to shipyard power distribution, energy storage, and onsite generation to increase capacity, capability, and resiliency of the power system in accordance with the drawings and specifications complete, but excluding work provided in another Priced line Item. See Drawings G-015 thru G-023 for Work Area Designations.	1	LS	\$ _____		\$ _____
0001.A	Subtotal Price for the CLIN 0001 Base Price Scope that is NOT PRICED in SubCLINs Line Items 0001.B thru 0001.AC. Note that the Option pricing identified in CLINs 0002 thru 00016 are specific to those work scopes and are not to be included in CLIN0001.	1	LS	\$ _____	\$ _____	
0001.B	Subtotal of Base Price to Furnish and Install the AC Ductbanks as shown on the drawings complete in accordance with the details on drawings and specifications, but excluding work provided in another line item.	1	LS	\$ _____	\$ _____	
0001.C	Subtotal of Base Price to Furnish and Install DC Ductbank as shown on the Drawings complete in accordance with the details on the drawings and specifications, but excluding work provided in another line item.	1	LS	\$ _____	\$ _____	
0001.D	Subtotal of Base Price for Building 72 Demolition, Renovations and New Construction as shown on the Drawings complete (incl. switchgear, & electrical equipment) in accordance with the details on the drawings and specifications but excluding work provided in another line item.	1	LS	\$ _____	\$ _____	
0001.E	Subtotal of Base Price for Hazardous Materials within buildings and structures including but not limited to asbestos, low-level radiological contaminants, lead based or other hazardous paint, PCBs, and heavy metals that the contractor may encounter in accordance with the drawings and specifications, but excluding work provided in another line item.	1	LS	\$ _____	\$ _____	
0001.F	Subtotal of Base Price to Furnish and Install Wearing Course Pavement complete in accordance with the details on the drawings	1	LS	\$ _____	\$ _____	

	and specifications, but excluding work provided in another line item.					
0001.G	Subtotal of Base Price to Furnish and Install 8 inch Water Main complete in accordance with the drawings and specifications, but excluding work provided in another line item.	1	LS	\$ _____	\$ _____	
0001.H	Subtotal of Base Price to Furnish and Install 12 inch Water Main complete in accordance with the drawings and specifications, but excluding work provided in another line item.	1	LS	\$ _____	\$ _____	
0001.I	Subtotal of Base Price to Furnish and Install Water Service Connections complete in accordance with the drawings and specifications, but excluding work provided in another line item.	1	LS	\$ _____	\$ _____	
0001.J	Subtotal of Base Price to Furnish and Install 15-inch Storm Drain complete in accordance with the drawings and specifications, but excluding work provided in another line item.	1	LS	\$ _____	\$ _____	
0001.K	Subtotal of Base Price to Furnish and Install 18-inch Storm Drain complete in accordance with the drawings and specifications, but excluding work provided in another line item.	1	LS	\$ _____	\$ _____	
0001.L	Subtotal of Base Price for Excavation and Removal of Hazardous Soils during Base Bid Work including, but not limited to sampling, excavation, stockpiling, and testing compete in accordance with the drawings and or specifications, excluding Disposal and or work provided in another line item.	1	LS	\$ _____	\$ _____	
0001.M	Subtotal of Base Price to Furnish and Install Gas Main complete in accordance with the drawings and specifications, but excluding work provided in another line item.	1	LS	\$ _____	\$ _____	
0001.N	Subtotal of Base Price to Furnish, Install B162 and B72 Gas Regulating Stations complete in accordance with the drawings and specifications, but excluding work provided in another line item.	1	LS	\$ _____	\$ _____	
0001.O	Subtotal of Base Price for Excavation of Non-Hazardous Soils (common earth) complete in accordance with the drawings and specifications, but excluding work provided in another line item.	1	LS	\$ _____	\$ _____	
0001.P	Subtotal of Base Price for providing Structural Fill complete in accordance with the drawings and specifications, but excluding work provided in another line item.	1	LS	\$ _____	\$ _____	
0001.Q	Subtotal of Base Price for providing Ordinary Fill complete in accordance with	1	LS	\$ _____	\$ _____	

	the drawings and specifications, but excluding work provided in another line item.					
0001.R	Subtotal of Base Price for providing ¾” Crushed Stone Materials complete in accordance with the drawings and specifications, but excluding work provided in another line item.	1	LS	\$ _____	\$ _____	
0001.S	Subtotal of Base Price for providing 1-1/2” Crushed Stone Materials complete in accordance with the drawings and specifications, but excluding work provided in another line item.	1	LS	\$ _____	\$ _____	
0001.T	Base Scope Unit Price for Ledge Removal and Disposal complete in accordance with the drawings and specifications, but excluding work provided in another line item, and in accordance with Notes Item “i” below.	24,750	CY	\$ _____	\$ _____	
0001.U	Base Scope Unit Price for providing Excavation and Removal of Hazardous Soils for areas not characterized in the contract documents as having Hazardous Soils including not limited to sampling, temporarily stockpiling to accommodate the Government's scheduling of trucks for disposal, and testing (expedited), complete in accordance with the drawings and specifications, but excluding work provided in another line item, and in accordance with Notes Item “h” below.	5,100	CY	\$ _____	\$ _____	
0001.V	Base Scope Unit Price to provide Hazardous Underground Pipe and/or Hazardous Pipe/Insulation Removal per location (up to 10 feet in Length). Pricing to include all testing (expedited), hazardous plan development, required controls and implementation, performance of the work, hygienist, monitoring, replacement with select material and appropriate disposal, complete in accordance with the drawings and specifications, but excluding work provided in another line item, and in accordance with Notes Item “h” below.	100	EA	\$ _____	\$ _____	
0001.W	Base Scope Unit Price to provide Hazardous Material Abatement for Paint Containing Lead, Cadmium, or Chromium Removal within Buildings). Pricing to include all testing (expedited), hazardous plan development, required controls and implementation, performance of the work, hygienist, monitoring, replacement with select material and appropriate disposal, complete in accordance with the drawings and specifications, but excluding work provided in another line item, and in accordance with Notes Item “h” below	1,200	SF	\$ _____	\$ _____	

0001.X	Base Scope Unit Price to provide Hazardous Material Abatement for Lead Dust within Buildings). Pricing to include all testing (expedited), hazardous plan development, required controls and implementation, performance of the work, hygienist, monitoring, replacement with select material and appropriate disposal, complete in accordance with the drawings and specifications, but excluding work provided in another line item, and in accordance with Notes Item “h” below	1,000	SF	\$ _____	\$ _____	
0001.Y	Base Scope Unit Price to provide Hazardous Uranium Tiles Removal within Buildings to Government Provided Dumpsters. Pricing to include all testing (expedited), hazardous plan development, required controls and implementation, performance of the work, hygienist, monitoring, replacement with select material and appropriate disposal, complete in accordance with the drawings and specifications, but excluding work provided in another line item, and in accordance with Notes Item “h” below	400	SF	\$ _____	\$ _____	
0001.Z	Base Scope Unit Price to Furnish and Install Hazardous Pipe Insulation Glove Bag Removal (6”-12” Dia. Pipe). Pricing to testing (expedited), hazardous plan development, required controls and implementation, performance of the work, hygienist, monitoring, replacement with select material and appropriate disposal, complete in accordance with the drawings and specifications, but excluding work provided in another line item, and in accordance with Notes Item “h” below	250	LF	\$ _____	\$ _____	
0001.AA	Base Scope Unit Price to provide Hazardous Pipe Insulation Glove Bag Removal (3/4”- 4” Dia. Pipe). Pricing to include all testing (expedited), hazardous plan development, required controls and implementation, performance of the work, hygienist, monitoring, replacement with select material and appropriate disposal, complete in accordance with the drawings and specifications, but excluding work provided in another line item, and in accordance with Notes Item “h” below	250	LF	\$ _____	\$ _____	
0001.AB	Base Scope Unit Price to provide Hazardous Joint Compound Abatement within Buildings to Government Provided Dumpsters. Pricing to include all testing (expedited), hazardous plan development, required controls and implementation, performance of the work, hygienist,	400	SF	\$ _____	\$ _____	

	monitoring, replacement with select material and appropriate disposal, complete in accordance with the drawings and specifications, but excluding work provided in another line item, and in accordance with Notes Item "h" below					
0001.AC	Base Scope Unit Price to provide Temporary Response to unplanned shipyard rail movements and rapidly restore rail. Pricing to include minor Backfill, Ballast, Crushed Stone, Wood Ties, 100lb Two Rail installation for 60 LF of Roadway (120 lf of rail) , certification complete in accordance with the drawings and specifications, but excluding work provided in another line item, and in accordance with Notes Item "h" below	60	LF	\$ _____	\$ _____	
0002.	OPTION ITEM No. 1: Total CLIN 0002 Price to Furnish and Install the New 16" Water Main from the connection at the Kittery Water District Main to Gate #2 Metering Pit, across Bridge #2, Wyman Ave to the Bldg. 163 Pump Station, and any associated work with regards to intersecting Sanitary Sewer, the Storm Drainage and any Rail Impacts as shown in Work Areas R, S F, and T. Pricing to include excavation, shoring, Bridge 2 Pipe Structural Framing and Supports, New pipe main installation, Testing, Insulation and Jacketing above ground, Backfill, Temporary Paving, Traffic Control, Bridge and Surface Restoration, Environmental Mitigation, Dewatering, Shoring, HAZMAT, SCADA, Vibration Monitoring, Archaeological Monitoring, Site Improvements, Site Restoration, etc., and General Conditions as required per plans and specifications to complete this Option Item. See Drawings G-015 thru G-023 for Work Area Designations.	1	LS	\$ _____		\$ _____
0002.A	Subtotal Price Option No. 1 CLIN 0002 for Scope in this Work Area that is NOT PRICED in the following SubCLINs Line Items 0002.B and 0002.C.	1	LS	\$ _____	\$ _____	
0002.B	Option Item No. 1 Unit Price for Ledge Removal and Disposal complete in accordance with the drawings and specifications, but excluding work provided in another line item, and in accordance with Notes Item "i" below.	2,000	CY	\$ _____	\$ _____	
0002.C	Option Item No. 1 Unit Price for providing Excavation and Removal of Hazardous Soils for areas not characterized in the contract documents as having Hazardous Soils including not limited to sampling, temporarily stockpiling to accommodate the	550	CY	\$ _____	\$ _____	

	Government's scheduling of trucks for disposal (if applicable), and testing (expedited), complete in accordance with the drawings and specifications, but excluding work provided in another line item, and in accordance with Notes Item "h" below.					
0003.	OPTION ITEM No. 2: Total CLIN 0003 Price to furnish and install the work shown in WORK AREA U: WATER STORAGE TANK. Included is the Site Work, and the Tank Structure, tie-in to the Meade Ave Water Main and SCADA to create a fully functioning and integrated water storage tank.	1	LS	\$ _____		\$ _____
0003.A	Subtotal Price Option No. 2 CLIN 0003 for Scope in this Work Area that is NOT PRICED in the following SubCLINs Line Items 0003.B and 0003.C.	1	LS	\$ _____	\$ _____	
0003.B	Option Item No. 2 Unit Price for Ledge Removal and Disposal complete in accordance with the drawings and specifications, but excluding work provided in another line item, and in accordance with Notes Item "i" below.	550	CY	\$ _____	\$ _____	
0003.C	Option Item No. 2 Unit Price for providing Excavation and Removal of Hazardous Soils for areas not characterized in the contract documents as having Hazardous Soils including not limited to sampling, temporarily stockpiling to accommodate the Government's scheduling of trucks for disposal (if applicable), and testing (expedited), complete in accordance with the drawings and specifications, but excluding work provided in another line item, and in accordance with Notes Item "h" below.	150	CY	\$ _____	\$ _____	
0004.	OPTION ITEM No. 3: Total CLIN 0004 Price to Remove the Existing 8" Water Main. Furnish and Installation of the 12" Water Main along Meade Ave to the connection @ Building 403, the abandonment and fill of the existing 8", and any associated work with regards to intersecting Sanitary Sewer, the Storm Drainage shown in Work Area R. Pricing to include excavation, shoring, pipe bedding, pipe main installation, testing, backfill, temporary paving, traffic control, and surface restoration as required per plans and specifications	1	LS	\$ _____		\$ _____
0004.A	Subtotal Price Option No. 3 CLIN 0004 for Scope in this Work Area that is NOT PRICED in the following SubCLINs Line Items 0004.B and 0004.C.	1	LS	\$ _____	\$ _____	

0004.B	Option Item No. 3 Unit Price for Ledge Removal and Disposal complete in accordance with the drawings and specifications, but excluding work provided in another line item, and in accordance with Notes Item “i” below.	600	CY	\$ _____	\$ _____	
0004.C	Option Item No. 3 Unit Price for providing Excavation and Removal of Hazardous Soils for areas not characterized in the contract documents as having Hazardous Soils including not limited to sampling, temporarily stockpiling to accommodate the Government's scheduling of trucks for disposal (if applicable), and testing (expedited), complete in accordance with the drawings and specifications, but excluding work provided in another line item, and in accordance with Notes Item “h” below.	200	CY	\$ _____	\$ _____	
0005.	OPTION ITEM No. 4: Total CLIN 0005 Price to Clean & Line the Existing 16” Water Main along Sicard Street and the Existing 16” Water Main along John Paul Jones Street shown in Work Area R. Pricing includes excavation, shoring, cleaning, lining installation, testing, backfill, temporary paving, traffic control, and surface restoration as required per plans and specifications	1	LS	\$ _____		\$ _____
0006.	OPTION ITEM No. 5: Total CLIN 0006 Price to Furnish and Install the New 20” Water Main from the connection at the Kittery Water District Main to Gate #1 Metering Pit, across Bridge #1 to the Bldg. 163 Pump Station, Removal of the Existing 12” Main, and any associated work with regards to intersecting Sanitary Sewer, the Storm Drainage and Rail Impacts shown in Work Areas R, S, and T. Pricing to include excavation, shoring, Bridge 1 Pipe Structural Framing and Supports, New pipe main installation, Testing, Insulation and Jacketing above ground, Backfill, Temporary Paving, Traffic Control, Bridge and Surface Restoration, Environmental Mitigation, Dewatering, Shoring, HAZMAT, SCADA, Vibration Monitoring, Archaeological Monitoring, Third Party Commissioning, Site Improvements, Site Restoration, etc., and General Conditions as required per plans and specifications to complete this Option Item. See Drawings G-015 thru G-023 for Work Area Designations.	1	LS	\$ _____		\$ _____
0007	OPTION ITEM No. 6: Total CLIN 0007 Price to furnish, install and modify the work shown in Work Area T: WATER PUMP STATION (B163). Included in this	1	LS	\$ _____		\$ _____

	CLIN are the Exterior and Interior Improvements, as well as SCADA system improvements to result in a fully integrated system per plans and specifications to complete this Option Item.					
0008	OPTION ITEM No. 7: Total CLIN 0008 Price for the entire work to furnish and install the work in Work Area V: AUXILIARY SEA WATER SYSTEM (ASW) as required per plans and specifications to complete this Option Item.	1	LS	\$ _____		\$ _____
0008.A	Subtotal Price Option No. 7 CLIN 0008 for Scope in this Work Area that is NOT PRICED in the following SubCLINs Line Items 0008.B and 0008.C.	1	LS	\$ _____	\$ _____	
0008.B	Option Item No. 7 Unit Price for Ledge Removal and Disposal complete in accordance with the drawings and specifications, but excluding work provided in another line item, and in accordance with Notes Item “i” below.	375	CY	\$ _____	\$ _____	
0008.C	Excavation and Removal of Hazardous Soils for areas not characterized in the contract documents as having Hazardous Soils including not limited to sampling, temporarily stockpiling to accommodate the Government's scheduling of trucks for disposal (if applicable), and testing (expedited), complete in accordance with the drawings and specifications, but excluding work provided in another line item, and in accordance with Notes Item “h” below.	100	CY	\$ _____	\$ _____	
0009.	OPTION ITEM No. 8: Total CLIN 0009 Price for the entire work to furnish and install WORK AREA K: BUILDING 243 (SUBSTATION 4). Included in this Subtotal is renovation of the existing Building 243 (Substation 4), and new 15kV Gear, and SCADA system.	1	LS	\$ _____		\$ _____
0010.	OPTION ITEM No. 9: Total CLIN 0010 Price for the entire work to furnish and install the Capacitor Banks as required per plans and specifications to complete this Option Item.	1	LS	\$ _____		\$ _____
0011.	OPTION ITEM No. 10: Total CLIN 0011 Price for the entire work to furnish and install Complete Roadway Milling and Pavement Overlay on roads impacted, including Striping, Markings, and Loop Detectors as required per plans and specifications to complete this Option Item.	1	LS	\$ _____		\$ _____
0012.	OPTION ITEM No. 11A: Total CLIN 0012 Contractor Personal Owned Vehicle Off Installation Parking as required per plans and specifications to complete this Option	1	LS	\$ _____		\$ _____

	Item. Included in this bid option, the Contractor to provide off installation parking and transport for all P1080 Prime and Subcontractor Personal Owned Vehicles (POV). Parking shall be at an offsite parking facility and transport their employees as required to PNSY. The contractor is required to utilize a pre-established parking lot or parking structure either privately owned or coordinated with the Seacoast area commuting options as required per plans and specifications to complete this Option Item.					
0013.	OPTION ITEM No. 11B: Total CLIN 0013 PNSY Employee Parking of Personal Owned Vehicle (POV) at Off Installation Parking Location required per plans and specifications to complete this Option Item. Included in this bid option, Contractor to provide a minimum of 100 parking spots at one or multiple designated parking locations within approximately 1.5 Miles or less of one or both access points to PNSY. The contractor is required to utilize a pre-established parking lot or parking structure that has continuous public walkway paths between PNSY and established parking lot or parking structure.	1	LS	\$ _____		\$ _____
0014.	OPTION ITEM No. 12: Total CLIN 0014 Price for the entire work to furnish and install Two Additional Natural Gas Generators in Work Area P as required per plans and specifications to complete this Option Item.	1	LS	\$ _____		\$ _____
0015.	OPTION ITEM No. 13: Total CLIN 0015 Price for the entire work to furnish and install One Additional Natural Gas Generator in Work Area P as required per plans and specifications to complete this Option Item.	1	LS	\$ _____		\$ _____
0016.	OPTION ITEM No. 14: Total CLIN 0016 Price for the entire work to furnish and install FF&E for buildings B72, and B162 as required per plans and specifications to complete this Option Item.	Gov't Est'd Price: \$14,104		HAR Percent (NTE 5%) 3%	HAR Subtotal \$436	Total FF&E Estimated Price \$14,540

TOTAL PRICE FOR CLINs 0001 - 0016 _____

GENERAL BID NOTES

a. All work required in accordance with the drawings and specifications must be included in the Contractor's proposed price.

b. Evaluation will be made on the total sum of Contract Line Item (CLIN) 0001, and the extended total under Contract Line items 0002, through 0016. For CLINs 0001 through 0016, enter unit price and extended total in space provided. If there is a difference between a unit price and the extended total, the unit price will be held to be the intended bid and the total recomputed accordingly. If an Offeror provided a total but fails to enter a unit price, the total divided by the specified quantity will be held to be the intended unit price. Award is expected to be made on CLIN 0001.

c. The Government reserves the unilateral right to award CLIN(s) 0002 through 0016 to the Contractor at the proposed price within 180 calendar days after the contract award. A firm fixed proposed price is required for all CLINs. No provision is made for economic price adjustment. If Option(s) 1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 11A, 11B, 12, 13, and/or 14 are exercised, the contract completion date remains 1930 calendar days after award of the contract.

d. Evaluation of Options (JUL 1990). Except when it is determined in accordance with FAR 17.206(b) Evaluation not to be in the Government's best interest, the Government will evaluate offers for award purposes by adding the price for the CLINS 0002 through 0016 (Options 1 through 14) to the total price for CLIN 0001. In accordance with FAR 52.217-5 Evaluation of Options, evaluation of options will not obligate the Government to exercise the Option(s).

e. The Government may reject an offer as nonresponsive if it is materially unbalanced as to prices for the basic requirement and the option quantities. An offer is unbalanced when it is based on prices significantly less than cost for some work and prices which are significantly overstated for other work.

f. If any of the CLIN(s) 0002 through 0016 are exercised, additional bonding and consent of surety is required. Consequently, the Performance Bond must reflect 100 percent of the aggregate amount of all Items.

g. All hazardous material and contaminated soils shall be delivered to the PNSY Hazardous Waste Facility in Building 357 for disposal in accordance with the project specifications.

h. The quantities shown for CLIN(s) 0001.U through 0001.AC, and Bid Option CLIN(s) 0002.C, 0003.C, 0004C, and 0008.C, are estimated quantities for the described work that are in addition to the scope of work indicated in the drawings and specifications and must be executed in accordance with the requirements of the contract documents. These quantities are in addition to the base bid and bid option quantities, as determined by the bidder, that must be included in CLIN(s) 0001.A through 0001.S, and Bid Option CLIN(s) 0002.A, 0003.A, and 0004.A, and 0008.A to complete the full scope of work. The bidder is to utilize these quantities to establish unit prices and include this subtotal and quantity in the total bid price for the Base Scope and applicable Bid Options. The actual quantities may vary in location and/or amount. Contractor's Quality Control Manager is to track actual quantities and locations, coordinated with and verified by the Contracting Officer's Representative prior to execution of the work, for each line item as the work progresses and invoice for actual quantities when completed. Applicable locations for these unit price quantities will be any location within the entire project site such that any variation in location will not be cause for a contract modification or change in scope. Actual quantities greater than the estimated amount will be increased via a modification to the contract. Should any quantities not be utilized in performance of the associated scope, the resulting credits shall be available for Government recapture or repurpose.

i. The quantities shown for CLIN(s) 0001.T and Bid Option CLIN(s) 0002.B, 0003.B, 0004.B and 0008.B associated with ledge are estimated quantities that represent the full amount of ledge anticipated to require removal and disposal for the total contract. The bidder is not to include any other ledge removal and disposal scope or cost in other CLINs. The bidder is to utilize these quantities to establish unit prices and include this subtotal and quantity in the total bid price for the Base Scope and applicable Bid Options. The actual quantities may vary in location and/or amount. Contractor's Quality Control Manager is to track actual quantities and locations, coordinated with and verified by the Contracting Officer's Representative prior to execution of the work, for each line item as the work progresses and invoice for actual quantities when completed. Applicable locations for these unit price quantities will be any location within the entire project site such that any variation in location will not be cause for a contract modification or change in scope. Actual quantities greater than the estimated amount will be increased via a modification to the contract. Should any quantities not be utilized in performance of the associated scope, the resulting credits shall be available for Government recapture or repurpose.

