

AIR COOLED CHILLER SCHEDULE													
MARK	LOCATION	TYPE	NOMINAL CAPACITY (TONS)	FLOW (GPM)	EWI (°F)	LWT (°F)	ΔP (FT)	EFFICIENCY (EER)	IPLV (EER)	MCA	MOCP	VOLTS/PH	NOTES
CH-1	CHILLER YARD	AIR COOLED SCROLL HIGH EFFICIENCY	80	174	54.0	44.0	16.7	10.9	15.1	357.6	400	208/3	1,2,3

- NOTES:
1. PROVIDE WITH ACROSS THE LINE STARTER AND SINGLE POINT ELECTRICAL CONNECTION (SEE NOTE 2 FOR SEPARATE BASIN HEATER CONNECTION).
 2. PROVIDE WITH BASIN HEATER.
 3. UNIT SHALL BE PROVIDED WITH FACTORY-APPLIED COATING TO THE CONDENSER COILS. COILS MUST PASS ASTM B117 90, 6000 HOUR SALT SPRAY RESISTANCE TEST AS INSTALLED.

NATURAL GAS-FIRED BOILER SCHEDULE													
MARK	LOCATION	TYPE	MIN INPUT (MBH)	MAX INPUT (MBH)	MAX OUTPUT (MBH)	FLOW GPM	TEMP RISE +F	AFUE %	VENT CONNECTION (IN)	AIR INLET CONNECTION (IN)	GAS CONNECTION (IN)	VOLTS/PH/2	NOTES
B-1	MECH BLDG BB271	CONDENSING WALL MOUNTED	57	285	254	31	20	95	3"	3"	1/2	120/180	1,2
B-2	MECH BLDG BB271	CONDENSING WALL MOUNTED	57	285	254	31	20	95	3"	3"	1/2	120/180	1,2
B-3	MECH BLDG BB271	CONDENSING WALL MOUNTED	57	285	254	31	20	95	3"	3"	1/2	120/180	1,2

- NOTES:
1. PROVIDE WITH 4" CONCENTRIC INTAKE/EXHAUST KIT PER MANUFACTURER'S RECOMMENDATIONS FOR SIDEWALL INSTALLATION.
 2. PROVIDE WITH WALL BRACKET/FLOOR SUPPORT SUITABLE FOR INSTALLATION ON MASONRY WALL.

PUMP SCHEDULE									
MARK	TYPE	SERVICE	LOCATION	FLOW (GPM)	HEAD (FT)	HP	VOLTS/PH	RPM	NOTES
CWP-1,2	IN-LINE CLOSE COUPLED	CHILLED WATER	MECH ROOM RM 107	174	62	5	208/3	3450	1,2
BP-1,2,3	IN-LINE	BOILER CIRCULATOR	MECH BLDG BB271	31	20	1/4	120/1	NOTE 5	1,4,5
HWP-1,2	IN-LINE CLOSE COUPLED	SECONDARY HOT WATER	MECH ROOM RM 107	62	43	2	208/3	1750	1,2,3

- NOTES:
1. PROVIDE WITH SUCTION DIFFUSER AND ISOLATION VALVES.
 2. PUMPS TO OPERATE IN PRIMARY/STANDBY. (ONLY ONE PUMP WILL RUN)
 3. PROVIDE WITH VFD.
 4. PUMPS TO BE CONTROLLED BY CORRESPONDING BOILER: BP-1 (B-1), BP-2 (B-2), BP-3 (B-3).
 5. BOILER PUMP PROVIDED WITH BOILER. RPM TO BE PROVIDED BY BOILER MANUFACTURER.

OUTSIDE AIR CALCULATION (2009 IMC)												
UNIT MARK	SERVED BY	# OF SLEEPING ROOMS	FLOOR AREA (SQ.FT.)	ASHRAE CLASSIFICATION	PEOPLE PER 1000 SF	TOTAL PEOPLE	CFM PER PERSON	CFM PER SQ. FT.	REQUIRED CFM	TOTAL REQUIRED CFM	TOTAL PROVIDED CFM	NOTES
AHU-1A	DOAS-1	14	3,696	BARRACKS SLEEPING AREAS	-	28	5	0.06	362	362	770	1,2,3
AHU-1B	DOAS-2	15	3,960	BARRACKS SLEEPING AREAS	-	30	5	0.06	388	397	850	1,2,3
			78	OFFICE SPACE	5	1	5	0.06	10			1,3
AHU-1C	DOAS-1	707		LAUNDRY	10	7	5	0.12	120	120	120	1
AHU-2A	DOAS-1	15	3,960	BARRACKS SLEEPING AREAS	-	30	5	0.06	388	388	825	1,2,3
AHU-2B	DOAS-2	15	3,960	BARRACKS SLEEPING AREAS	-	30	5	0.06	388	388	825	1,2,3
AHU-3C	DOAS-1	700		LOBBY/PREFUNCTION	30	21	7.5	0.06	200	200	200	1
AHU-3A	DOAS-1	14	3,696	BARRACKS SLEEPING AREAS	-	28	5	0.06	362	362	770	1,2,3
AHU-3B	DOAS-2	14	3,696	BARRACKS SLEEPING AREAS	-	28	5	0.06	362	362	770	1,2,3
AHU-3C	DOAS-1	700		LOBBY/PREFUNCTION	30	21	7.5	0.06	200	200	200	1
TOTAL									2,777	5,330		

- NOTES:
1. PER ASHRAE 62.1-2010.
 2. TOTAL PEOPLE BASED ON TWO OCCUPANTS PER SLEEPING ROOM.
 3. INCREASED AIRFLOW DUE TO ROOM PRESSURIZATION AND EXHAUST REQUIREMENTS.

EXPANSION TANK SCHEDULE					
MARK	LOCATION	SERVES	GALLONS	OPER. WEIGHT (LBS)	NOTES
ET-1	MECH ROOM RM 107	CHILLED WATER	68	778	1,2
ET-2	MECH ROOM RM 107	HOT WATER	44.4	516	1,2

- NOTES:
1. PROVIDE WITH HIGH CAPACITY AIR VENT.
 2. TANK TO BE BLADDER TYPE.

CHILLED WATER BUFFER TANK SCHEDULE				
MARK	LOCATION	SERVES	GALLONS	NOTES
BT-1	MECH ROOM RM 107	CHILLED WATER	120	1

- NOTES:
1. PROVIDE WITH INTERNAL BAFFLE AND HIGH CAPACITY AIR VENT.

COMBINATION AIR / DIRT SEPARATOR TANK SCHEDULE						
MARK	LOCATION	SERVES	CONNECTION SIZE	CONNECTION TYPE	OPER. WEIGHT (LBS)	NOTES
AS-1	MECH ROOM RM 107	CHILLED WATER	4"	FLANGED	165	1,2,3
AS-2	MECH ROOM RM 107	HOT WATER	3"	FLANGED	95	1,2,3

- NOTES:
1. PROVIDE WITH HIGH CAPACITY AUTOMATIC AIR VENT.
 2. AIR SEPARATOR TO BE COALESCING TYPE.

FAN SCHEDULE										
MARK	SERVICE	TYPE	CFM	ESP (IN H2O)	MOTOR SIZE	RPM	DRIVE	VOLTS/PH	WEIGHT (LBS)	NOTES
EF-1	CORE AREA RESTROOMS	IN-LINE	1,040	0.5	822W	1,550	DIRECT	120/1	60	1,3,4
EF-2	MECH BLDG BB271	ROOF MOUNTED	400	0.12	1/2S	1,550	DIRECT	120/1	20	1,2,3

- NOTES:
1. PROVIDE WITH DISCONNECT SWITCH.
 2. FAN TO BE CONTROLLED BY WALL MOUNTED, LINE VOLTAGE THERMOSTAT PROVIDED BY MECHANICAL CONTRACTOR.
 3. PROVIDE FAN WITH ELECTRONIC SPEED CONTROLLER.
 4. FAN TO BE BALANCED TO PROVIDE REQUIRED AIRFLOW AT EXHAUST GRILLES PER PLANS (520 CFM). SCHEDULED CFM FOR FAN HAS BEEN DOUBLED TO ACCOUNT FOR DUCT LEAKAGE IN THE EXISTING EXHAUST RISER.

DEHUMIDIFIER SCHEDULE									
MARK	SERVICE	CONDENSATE REMOVAL (P1/S/DAY)	WATTS	MCA	MOCP	VOLTS/PH	WEIGHT (LBS)	NOTES	
DH-1	MECH ROOMS 106,107,158,206,214,306,314,324,332	95	730	6.8	15	120/1	58	1,2,1	

- NOTES:
1. PROVIDE WITH REMOVABLE (CLEANABLE) FILTER.
 2. PROVIDE WITH HARD-WIRE ELECTRICAL CONNECTION (NO PIGTAIL WITH PLUG).
 3. PROVIDE WITH WALL MOUNTING BRACKET. WHEELS SHALL BE REMOVED FROM HUMIDIFIER PRIOR TO INSTALLATION ON WALL BRACKET.

PACKAGED TERMINAL AIR-CONDITIONING UNIT								
MARK	SERVICE	SUPPLY AIR (CFM)	TOTAL COOLING (MBH)	MCA	MOCP	VOLT/PH/2	NOTES	
PTAC-1	COMM RM 241	340	15.0	8.5	15	208/180	1,2,3,4	

- NOTES:
1. PROVIDE WITH WALL SLEEVE, OUTDOOR GRILLE, AND HARD-WIRE ELECTRICAL KIT.
 2. PROVIDE WITH CONDENSATE PUMP. PUMP TO BE WIRED TO PTAC POWER CIRCUIT.
 3. PROVIDE WITH WALL-MOUNTED DDC THERMOSTAT.
 4. PROVIDE WITH CONDENSER COIL CORROSION PROTECTION, SUITABLE FOR COASTAL INSTALLATION.

UNIT HEATER SCHEDULE								
MARK	LOCATION	TYPE	KW	AIRFLOW (CFM)	MCA	MOCP	VOLT/PH	NOTES
EUH-1	LAUNDRY RM 144	HORIZONTAL	5.0	400	24.1	35	208/1	1,2
EUH-2	LAUNDRY RM 243	HORIZONTAL	5.0	400	24.1	35	208/1	1,2
EUH-3	LAUNDRY RM 343	HORIZONTAL	5.0	400	24.1	35	208/1	1,2
EUH-4	MECH ROOM RM 107	HORIZONTAL	5.0	400	24.1	35	208/1	1,2
EUH-5	MECH BLDG BB271	HORIZONTAL	5.0	400	24.1	35	208/1	1,2

- NOTES:
1. PROVIDE WITH WALL/CEILING MOUNTING BRACKET.
 2. PROVIDE WITH WALL MOUNTED, DDC THERMOSTAT.

LOUVER SCHEDULE						
MARK	LOCATION	TYPE	MIN FREE AREA (%)	SIZE W x H (IN.)	NOTES	
L-1	LAUNDRY RM 139	INTAKE (DRYER MAKEUP)	40	36"x48"	1	
L-2	LAUNDRY RM 139	EXHAUST (DRYER EXHAUST)	40	36"x36"	2	
L-3	LAUNDRY RMS 144,243,343	EXHAUST (DRYER EXHAUST)	40	12"x28"	2	

- NOTES:
1. PROVIDE WITH DRAINABLE BLADES, BIRD SCREEN, AND BAKED FINISH. COLOR BY ARCHITECT.
 2. PROVIDE WITH DRAINABLE BLADES AND BAKED FINISH. COLOR BY ARCHITECT.

DISCLOSURE OF INFORMATION: CONTRACTOR SHALL COMPLY AS FOLLOWS: (A) THE CONTRACTOR SHALL NOT RELEASE TO ANYONE OUTSIDE THE CONTRACTOR'S ORGANIZATION ANY UNCLASSIFIED INFORMATION, REQUESTS OF MEDIA (E.G., TV, NEWSPAPERS, MAGAZINES, ETC.), OR OTHER DOCUMENTS, PERTAINING TO ANY PART OF THIS CONTRACT OR PROGRAM RELATED TO THE CONTRACT, UNLESS: (1) THE CONTRACTING OFFICER HAS GIVEN PRIOR WRITTEN APPROVAL; OR (2) THE INFORMATION IS OTHERWISE IN THE PUBLIC DOMAIN PRIOR TO RELEASE. (B) REQUESTS FOR APPROVAL SHALL IDENTIFY THE SPECIFIC INFORMATION TO BE RELEASED, THE MEDIA TO BE USED, AND THE PURPOSE FOR THE RELEASE. THE CONTRACTOR SHALL SUBMIT ITS REQUEST TO THE CONTRACTING OFFICER AT LEAST 45 DAYS BEFORE THE PROPOSED DATE FOR RELEASE. (C) THE CONTRACTOR AGREES TO INCLUDE A SIMILAR REQUIREMENT IN EACH SUBCONTRACT UNDER THIS CONTRACT. SUBCONTRACTORS SHALL SUBMIT REQUESTS FOR AUTHORIZATION TO RELEASE THROUGH THE PRIME CONTRACTOR TO THE CONTRACTING OFFICER.		FINAL SUBMITTAL 02.29.2016		M-602	
CONTRACTOR SHALL COMPLY AS FOLLOWS: (A) THE CONTRACTOR SHALL NOT RELEASE TO ANYONE OUTSIDE THE CONTRACTOR'S ORGANIZATION ANY UNCLASSIFIED INFORMATION, REQUESTS OF MEDIA (E.G., TV, NEWSPAPERS, MAGAZINES, ETC.), OR OTHER DOCUMENTS, PERTAINING TO ANY PART OF THIS CONTRACT OR PROGRAM RELATED TO THE CONTRACT, UNLESS: (1) THE CONTRACTING OFFICER HAS GIVEN PRIOR WRITTEN APPROVAL; OR (2) THE INFORMATION IS OTHERWISE IN THE PUBLIC DOMAIN PRIOR TO RELEASE. (B) REQUESTS FOR APPROVAL SHALL IDENTIFY THE SPECIFIC INFORMATION TO BE RELEASED, THE MEDIA TO BE USED, AND THE PURPOSE FOR THE RELEASE. THE CONTRACTOR SHALL SUBMIT ITS REQUEST TO THE CONTRACTING OFFICER AT LEAST 45 DAYS BEFORE THE PROPOSED DATE FOR RELEASE. (C) THE CONTRACTOR AGREES TO INCLUDE A SIMILAR REQUIREMENT IN EACH SUBCONTRACT UNDER THIS CONTRACT. SUBCONTRACTORS SHALL SUBMIT REQUESTS FOR AUTHORIZATION TO RELEASE THROUGH THE PRIME CONTRACTOR TO THE CONTRACTING OFFICER.		DEPARTMENT OF THE NAVY NAVAL FACILITIES ENGINEERING COMMAND MARINE CORPS BASE CAMP LEJEUNE, NORTH CAROLINA REPAIR BCO, BLDG. BB270		MECHANICAL DRAWING NO. 60017313	
DES: MSP DR: MSP CHK: JDL SUBMITTED BY: JTR DESIGN DR: THOMAS BURTON, PE APPROVED PWD OR ODC:		DATE: F 80091 SATISFACTORY TO:		DATE: 05/14/06 SCALE: AS NOTED SPEC: 05/14/06 SHEET 83 OF 119	