



**US ArmyCorps
of Engineers**
Norfolk District

Wallops Shoreline Stabilization Project Beach Renourishment

WALLOPS FLIGHT FACILITY

Accomack County, VA

Specifications

100% Design Submittal

(NOT FOR CONSTRUCTION)

January 2026

Prepared By:

United States Army Corps of Engineers
Norfolk District
Engineering Division
Design Branch
803 Front Street
Norfolk, VA 23510

Blank Page

DRAFT
NOT FOR CONSTRUCTION

PROJECT TABLE OF CONTENTS**DIVISION 01 - GENERAL REQUIREMENTS**

01 00 55	02/16	SOIL BORING DATA
01 11 00	02/24	SUMMARY OF WORK
01 14 00	11/22, CHG 1: 02/23	WORK RESTRICTIONS
01 20 00	11/20, CHG 4: 08/24	PRICE AND PAYMENT PROCEDURES
01 30 00	11/20, CHG 3: 08/23	ADMINISTRATIVE REQUIREMENTS
01 32 01.00 10	08/23	PROJECT SCHEDULE
01 33 00	08/18, CHG 4: 02/21	SUBMITTAL PROCEDURES
01 35 26	11/20, CHG 4: 08/23	GOVERNMENTAL SAFETY REQUIREMENTS
01 35 30	04/25	MUNITIONS AND EXPLOSIVES OF CONCERN (MEC) CONSTRUCTION SUPPORT, LOW PROBABILITY SITE
01 42 00	02/19, CHG 1: 08/23	SOURCES FOR REFERENCE PUBLICATIONS
01 45 00	08/23	QUALITY CONTROL
01 45 00.15 10	11/23	RESIDENT MANAGEMENT SYSTEM CONTRACTOR MODE (RMS CM)
01 50 00	11/20, CHG 2: 08/22	TEMPORARY CONSTRUCTION FACILITIES AND CONTROLS
01 57 19	08/22	TEMPORARY ENVIRONMENTAL CONTROLS
01 57 30	08/18	ENVIRONMENTAL PERMIT WORK REQUIREMENTS
01 58 00	08/19, CHG 5: 08/22	PROJECT IDENTIFICATION
01 78 00	05/19, CHG 1: 08/21	CLOSEOUT SUBMITTALS
01 78 23	05/23	OPERATION AND MAINTENANCE DATA

DIVISION 35 - WATERWAY AND MARINE CONSTRUCTION

35 20 23	08/20	DREDGING
35 20 23.13	02/22	NATIONAL DREDGING QUALITY MANAGEMENT PROGRAM - SCOW ULLAGE PROFILE
35 20 23.23	02/22	NATIONAL DREDGING QUALITY MANAGEMENT PROGRAM - HOPPER DREDGE
35 20 24	04/15	BEACH FILL

Appendix A - Geotechnical Exploration Report

Appendix B - Probability Assessment for Munitions and Explosives of Concern

-- End of Project Table of Contents --

SECTION 01 00 55

SOIL BORING DATA
02/16

PART 1 GENERAL

1.1 Soil Classification

The soil was visually classified in the field according to the "Unified Soil Classification System" and described utilizing ASTM D 2488 Standard Practice for Description and Identification of Soils (Visual-Manual Procedure). While it is believed that borings accurately indicate subsurface conditions for boring locations on the date taken, the Government assumes no responsibility for actual conditions which may be encountered in execution of Contract. Should the Contractor rely, for any purpose, upon the accuracy or completeness of said borings, or log thereof, he does so at his own risk. The geotechnical report, including soil boring drilling logs and data, is shown at the end of the specifications as Appendix A: Geotechnical Report. All samples contained in Appendix A: Geotechnical Report were obtained on various dates as designated on the respective boring. All Geotechnical analysis data is available for review at Norfolk District, 803 Front Street, Norfolk, VA 23510 (Attention: Jennifer Spitz, telephone 757-201-7098).

1.2 Sampling Method

There were a total of five (5) soil borings with Standard Penetration Tests (SPT), seven (7) Cone Penetrometer Tests (CPT), and eight (8) Dilatometer test soundings (DMT). All SPT, CPT, and DMT tests were taken at a depth of 70 feet below the seafloor. All boring samples were performed in accordance with ASTM D 1586 Standard Test Method for Standard Penetration Test (SPT).

1.3 Soil Consistency Determination

Estimated consistencies (med. stiff, soft, etc.) are from Terzaghi & Peck "Soil Mechanics in Engineering Practice".

1.4 Boring Elevations and Locations

All boring elevations and locations are approximated.

1.5 Abbreviations (if applicable)

BOH Bottom of Hole	moist moisture
bot bottom	MP medium plasticity
brk broken	mrbl marbled
brwn brown	mst moist
cly clayey	NP nonplastic
const consistency	OD Outside diameter
crs, c coarse	org organic
dk dark	PI Plastic Index
dns dense	PL Plastic Limit
fn, f fine	sam sample
frac fracture	sat saturated
frag fragments (fragmented)	sft soft

grn green
gry gray
HP high plasticity
hrd hard
hrs hours
len lense
lit little
LL Liquid Limit
LP Low Plasticity
lt light
med, m medium & and
mica micaceous
%200 Minus No. 200 Sieve

slt slight(ly)
sly silty
sm some
sta station
tr trace
v very
v.f. very fine
w moisture content
w/ with
wd weathered

PART 2 PRODUCTS (NOT APPLICABLE)

PART 3 EXECUTION (NOT APPLICABLE)

-- End of Section --

DRAFT
NOT FOR CONSTRUCTION

SECTION 01 11 00

SUMMARY OF WORK
02/24

PART 1 GENERAL

1.1 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for information only. When used, a code following the "G" classification identifies the office that will review the submittal for the Government. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Digging Permits

1.2 WORK COVERED BY CONTRACT DOCUMENTS

1.2.1 Project Description

The work includes beach renourishment with sand material dredged offsite from the unnamed "Shoal A" borrow area.

1.2.2 Location

The work is located at the NASA Wallops Flight Facility, approximately as indicated. The exact location will be shown by the Contracting Officer.

1.3 OCCUPANCY OF PREMISES

Building(s) and launch sites near the project site will be occupied during performance of work under this Contract.

Before work is started, arrange with the Contracting Officer a sequence of procedure, means of access, space for storage of materials and equipment, and use of approaches, corridors, and stairways.

1.4 EXISTING WORK

Remove or alter existing work in such a manner as to prevent injury or damage to any portions of the existing work which remain.

Repair or replace portions of existing work which have been altered during construction operations to match existing or adjoining work, as approved by the Contracting Officer. At the completion of operations, existing work must be in a condition equal to or better than that which existed before new work started.

1.5 LOCATION OF UNDERGROUND UTILITIES

When work is occurring on NASA property obtain digging permits from NASA prior to start of excavation, and comply with Installation requirements for locating and marking underground utilities. NASA will be responsible for marking utilities the first time upon dig request from Contractor and

at no cost to the Contractor. Once utilities are marked, Contractor will then be responsible for maintaining markings for the duration of the project.

Identify and mark all other utilities not managed and located by the local utility companies. Scan the construction site with Ground Penetrating Radar (GPR), electromagnetic, or sonic equipment, and mark the surface of the ground, pier deck or paved surface where existing underground utilities or utilities encased in pier structures are discovered. Verify the elevations of existing piping, utilities, and any type of underground or encased obstruction not indicated, or specified to be removed, that is indicated or discovered during scanning, in locations to be traversed by piping, ducts, and other work to be conducted or installed. Verify elevations before installing new work closer than nearest manhole or other structure at which an adjustment in grade can be made.

1.5.1 Notification Prior to Excavation

Notify the Contracting Officer and NASA POC at least 10 days prior to starting excavation work.

1.6 MATERIAL AND EQUIPMENT

The Government will not furnish any material and/or equipment for installation by the Contractor.

1.6.1 Deliveries

Notify the COR at least 7 calendar days in advance of the date on which the materials and equipment are to be delivered. Notification to NASA is not required. Deliveries can be delivered straight to the project site and unbadged delivery drivers can be escorted on base past the island gate by long-term badged employees of the contractor. Contractor Escorts must stay within eyesight of the delivery driver/vehicle until they leave the base.

1.7 OTHER SERVICES

Electrical services can be provided to the Contractor upon request to the COR from NASA. No other services, such as water, sewer, telecommunication, etc., will be provided and will be the responsibility of the Contractor, if needed. See 01 50 00 TEMPORARY CONSTRUCTION FACILITIES AND CONTROLS for additional details.

1.8 SALVAGE MATERIAL AND EQUIPMENT

Salvage material and equipment are not anticipated for the project.

PART 2 PRODUCTS

Not used.

PART 3 EXECUTION

Not used.

-- End of Section --

SECTION 01 14 00

WORK RESTRICTIONS
11/22, CHG 1: 02/23

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

1.2 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for information only. When used, a code following the "G" classification identifies the office that will review the submittal for the Government. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Radio and Laser Equipment; G, R0

List Of Contact Personnel; G, R0

Additional Laydown Areas Plan; G, R0

1.3 CONTRACTOR ACCESS AND USE OF PREMISES

1.3.1 Activity Regulations

Ensure that Contractor personnel employed on the Activity become familiar with and obey environmental regulations and activity regulations including safety, fire, traffic and security regulations. Keep within the limits of the work and avenues of ingress and egress. Wear appropriate personal protective equipment (PPE) in designated areas. Do not enter any restricted areas unless required to do so and until cleared for such entry. Ensure all Contractor equipment, include delivery vehicles, are clearly identified with their company name.

1.3.1.1 Subcontractors and Personnel Contacts

Provide a list of contact personnel of the Contractor and subcontractors including addresses and telephone numbers for use in the event of an emergency. As changes occur and additional information becomes available, correct and change the information contained in previous lists.

1.3.1.2 No Smoking Policy

Smoking is prohibited within 25 feet of any entrance to any building. This includes the use of electronic cigarettes and vaping. Fueling areas shall be areas off limits to smoking. Discarding tobacco materials other than into designated tobacco receptacles is considered littering and is

subject to fines. The Contracting Officer will identify designated smoking areas.

1.3.2 Working Hours

Unless directed otherwise, the Contractor may perform work 24 hours a day, 7 days a week (except for Government holidays per Federal Law) although normal NASA operations working hours are Monday through Friday, from 7:00 a.m. to 5:00 p.m. Badging Office hours are 7:00 am to 3:00 pm on weekdays only (excluding Holidays).

1.3.3 Work Outside Regular Hours

The Contractor shall notify the COR and NASA POC at least two days in advance for any work outside regular hours. Blanket after-hours requests will be entertained. In rare instances where weather (snow, flooding) may impact safe travel in the base, the base may close to non-essential employees until conditions are deemed safe.

Should the Contractor need to suspend work at any time before the contract is complete, the Contractor shall notify the COR and shall not again resume work without notifying the COR in advance.

1.3.3.1 After Hours Notifications

For non-emergencies after normal NASA operation working hours, contractual question are to be directed to 1) COR, 2) NASA's PM - John Saecker at 757-824-1695, or 3) a designated contact.

For emergencies after hours, contact 911 or 757-824-1333

For all other emergencies (hot work permits, etc.) contact Dispatch at 757-824-1300

1.3.4 Exclusionary Period

Goddard Space Flight Center/Wallops Flight Facility (GSFC/WFF) operates an active rocket launch range on Wallops Island and the Main Base Tracking and Data Operations throughout the facility. These launches will be handled and coordinated with the Contractor once known. Upon notification by the COR, the Contractor shall be responsible for keeping its employees out of launch, radio frequency, and aircraft operating hazards zones during operational activities. This may include shutting down or restricting all material placement and grading activities to avoid interruption of critical tracking operations. The Contractor shall be aware of the possibility of down time associated with the above and shall be paid for down time as it occurs.

1.3.5 Radio and Laser Equipment

All Contractor radio and laser equipment shall be reviewed and approved by the Frequency Utilization Manager prior to use on WFF. Allow 30 days for review and approval. Devices in "receive" only mode, and only used in receive only mode while not emitting radio frequency, may but are not guaranteed to bypass this process. The Contractor shall also be required to halt beach placement activities that have the potential of interrupting range instrumentation systems during critical operations, both on the Main Base and Wallops Island.

Activities involving radio equipment offshore or off NASA property does not require review or approval for use.

1.3.6 Occupied Buildings

NASA buildings and launch/operations sites adjacent to the project site are occupied during the performance of work under this contract. No buildings will be available for use by the Contractor, however the NASA POC may be able to schedule buildings and specific rooms for high-level meetings required for the execution of the contract. Contractor shall not enter buildings at Wallops Flight Facility unless for purposes of a meeting that has been scheduled by the COR and the NASA POC. Contractor shall coordinate with the COR if needed.

1.3.7 Utility Cutovers and Interruptions

- a. Make utility cutovers and interruptions after normal working hours or on Saturdays, Sundays, and Government holidays. Conform to procedures required in paragraph WORK OUTSIDE REGULAR HOURS.
- b. Ensure that new utility lines are complete, except for the connection, before interrupting existing service.
- c. Interruption to water, sanitary sewer, storm sewer, telephone service, electric service, air conditioning, heating, fire alarm, compressed air, and other public or private utilities are considered utility cutovers pursuant to the paragraph WORK OUTSIDE REGULAR HOURS.
- d. Operation of Station Utilities: The Contractor must not operate nor disturb the setting of control devices in the station utilities system, including water, sewer, electrical, and steam services. The Government will operate the control devices as required for normal conduct of the work. The Contractor must notify the Contracting Officer giving reasonable advance notice when such operation is required.

1.4 SECURITY REQUIREMENTS

NASA Wallops Flight Facility is a secured facility with controlled access. All contractor functions on the island should relate to the contract only. Badging is required to access the facility and can be in the form of long or short term badging. If a worker plans on being on the base for no more than 30 days in a 365 day period, a short term badge can be issued per occasion. If a worker plans on being on the base for longer than 30 days in a 365 day period, then a long-term badge will be required. All short and long-term badging requests shall be submitted to the NASA POC, with short term badging requests being required at a minimum of 7 days prior to entrance to the base. Long term badging will require completion of a LIST form and typically take 14 days to process.

Foreign Nationals may work on the project, however their approval is not guaranteed and conditions may be applied specific to the applicant. In cases where a NASA escort is required for full-time monitoring, NASA can not guarantee the availability of a government escort full-time on the job. Documentation must be current and up to date.

Exact location of project shown by on construction drawings and by COR.

Contract Clause FAR 52.204-2 Security Requirements and Alternate II apply.

1.5 ADDITIONAL LAYDOWN AREAS USAGE

Laydown and storage areas is noted on the construction drawings. Laydown areas are "as-is" and improvements to areas for purpose of this contract is the responsibility of the Contractor.

Additional laydown areas may be provided to the Contractor beyond what is shown within the construction drawings. Additional laydown areas will belong to NASA Wallops Flight Facility and will require additional coordinations. If additional laydown areas are to be given to the Contractor, the COR will coordinate the requirements with the Contractor. The Contractor shall submit an Additional Laydown Areas Plan and required amendments for SWPPP for the COR and SWPPP governing authority for review and approval. Additional laydown areas will not be approved if they are within or adjacent to wetlands or protected species habitat.

PART 2 PRODUCTS

Not Used

PART 3 EXECUTION

Not Used

-- End of Section --

SECTION 01 20 00

PRICE AND PAYMENT PROCEDURES

11/20, CHG 4: 08/24

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

1.2 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. When used, a code following the "G" classification identifies the office that will review the submittal for the Government. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-03 Product Data

Weight Scale Tickets; G, R0

SD-07 Certificates

Weigh Scale Certification; G, R0

1.3 CONTRACT COST BREAKDOWN

The Contractor must furnish within 30 days after the date of Notice to Proceed, and prior to the submission of its first partial payment estimate, a breakdown of its single job pay item or items which will be reviewed by the Contracting Officer as to propriety of distribution of the total cost to the various accounts. Any unbalanced items as between early and late payment items or other discrepancies will be revised by the Contracting Officer to agree with a reasonable cost of the work included in the various items. This Contract cost breakdown will then be utilized as the basis for progress payments to the Contractor.

1.4 CONTRACTOR'S INVOICE AND CONTRACT PERFORMANCE STATEMENT

1.4.1 Submission of Invoices

If DFARS Clause 252.232-7006 Wide Area WorkFlow Payment Instructions is included in the Contract, provide the documents listed in above paragraph CONTENT OF INVOICE in their entirety as attachments in Wide Area Work Flow (WAWF) for each invoice submitted. The maximum size of each WAWF attachment is two megabytes, but there are no limits on the number of attachments. If a document cannot be attached in WAWF due to system or size restriction, provide it as instructed by the Contracting Officer.

Monthly invoices and supporting forms for work performed through the anniversary award date of the Contract must be submitted to the

Contracting Officer within 5 calendar days of the date of invoice. For example, if Contract award date is the 7th of the month, the date of each monthly invoice must be the 7th and the invoice must be submitted by the 12th of the month.

1.4.2 Final Invoice

- a. A final invoice must be accompanied by the certification required by DFARS 252.247.7023 Transportation of Supplies by Sea, and the Contractor's Final Release. If the Contractor is incorporated, the Final Release must contain the corporate seal. An officer of the corporation must sign and the corporate secretary must certify the Final Release.
- b. For final invoices being submitted via WAWF, the original Contractor's Final Release Form and required certification of Transportation of Supplies by Sea must be provided directly to the respective Contracting Officer prior to submission of the final invoice. Once receipt of the original Final Release Form and required certification of Transportation of Supplies by Sea has been confirmed by the Contracting Officer, the Contractor must then submit final invoice and attach a copy of the Final Release Form and required certification of Transportation of Supplies by Sea in WAWF.
- c. Final invoices not accompanied by the Contractor's Final Release and required certification of Transportation of Supplies by Sea will be considered incomplete and will be returned to the Contractor.

1.5 PAYMENT FOR ONSITE AND OFFSITE MATERIALS

Progress payments may be made to the Contractor for materials delivered on the site, for materials stored off construction sites, or materials that are in transit to the construction sites under the following conditions:

- a. FAR 52.232-5(b) Payments Under Fixed Price Construction Contracts.
- b. Materials delivered on the site but not installed, including completed preparatory work, and off-site materials to be considered for progress payment must be major high cost, long lead, special order, or specialty items, not susceptible to deterioration or physical damage in storage or in transit to the construction site. Materials not acceptable for payment include consumable materials such as nails, fasteners, conduits, gypsum board, glass, insulation, and wall coverings.
- c. Materials to be considered for progress payment prior to installation must be specifically and separately identified in the Contractor's estimates of work submitted for the Contracting Officer's approval in accordance with Schedule of Prices requirement of this Contract. Requests for progress payment consideration for such items must be supported by documents establishing their value and that the title requirements of the clause at FAR 52.232-5 Payments Under Fixed-Price Construction Contracts have been met.
- d. Materials are adequately insured and protected from theft and exposure.
- e. Provide a written consent from the surety company with each payment request for offsite materials.

- f. Materials to be considered for progress payments prior to installation must be stored either in Hawaii, Guam, Puerto Rico, or the Continental United States. Other locations are subject to written approval by the Contracting Officer.
- g. Materials in transit to the job site or storage site are not acceptable for payment.

1.6 SINGLE JOB PAYMENT ITEMS

Payment items for the work of this Contract for which Contract job payments will be made are listed in the BIDDING SCHEDULE and described below. All costs for items of work, which are not specifically mentioned to be included in a particular job or unit price payment item, are included in the listed job item most closely associated with the work involved. The job price and payment made for each item listed constitutes full compensation for furnishing all plant, labor, materials, and equipment, and performing any associated Contractor quality control, environmental protection, meeting safety requirements, tests and reports, and for performing all work required for which separate payment is not otherwise provided.

1.6.1 Mobilization and Demobilization

1.6.1.1 Payment

All costs connected with the mobilization and demobilization of all of the Contractor's plant and equipment as defined below will be paid for at the contractor lump sum price for this item. Sixty percent (60%) of the lump sum price will be paid to the Contractor upon completion of mobilization at the work site. The remaining forty percent (40%) will be paid to the Contractor upon completion of demobilization. In the event the Contracting Officer considers that the amount in this item, sixty percent which represents mobilization and forty percent which represents demobilization, does not bear a reasonable relation to the cost of the work in this contract, the Contracting Officer may require the Contractor to produce cost data to justify this portion of the bid. Failure to justify such price to the satisfaction of the Contracting Officer will result in payment of actual mobilization costs, as determined by the Contracting Officer, at the completion of mobilization, and actual demobilization costs, as determined by the Contracting Officer, at the completion of demobilization. The determination of the Contracting Officer is not subject to appeal.

Mobilization

Mobilization shall include all costs for operations accomplished prior to commencement of actual sand excavation and truck haul, and beach fill placement operations. This shall include transfer of trucks, bulldozers and other like equipment and machinery associated with beach fill placement operations, preparation of the Contractor's staging area and any long term staging area(s) used for off beach equipment and material storage, and any other associated work that is necessary in advance of the actual sand excavation, truck haul, and beach fill.

Demobilization

Demobilization shall include general preparation for transfer of all

equipment and plant as described in Paragraph "Mobilization" above to its home base, cleanup of the Contractor's long term staging area, and transfer of all equipment to its home base.

1.6.1.2 Unit of Measure

Unit of measure: job.

1.7 UNIT PRICE PAYMENT ITEMS

Payment items for the work of this Contract on which the Contract unit price payments will be made are listed in the BIDDING SCHEDULE and described below. The unit price and payment made for each item listed constitutes full compensation for furnishing all plant, labor, materials, and equipment, and performing any associated Contractor quality control, environmental protection, meeting safety requirements, tests and reports, and for performing all work required for each of the unit price items.

1.7.1 Sand Excavation and Beach Fill

1.7.1.1 Payment

Payment to be made for this item includes all costs associated with excavation of sand from the designated borrow area, transporting of the material to the shoreline and placing/grading within the tolerances specified herein to the designated beach to the lines and grades indicated between Station 40+00 to Station 104+00, and all other associated costs of removal and placement of material as indicated and specified exclusive of bond reimbursement and the mobilization and demobilization as defined above. The total cost of the item Sand Excavation and Beach Fill shall be based on the cubic yard price bid for this item and the computed difference in the amount of material measured by the cubic yard in place for the before and after beach fill surveys for each beach fill segment. All hydrographic surveys performed on placement and borrow areas shall be in accordance with EM 1110-2-1003. All topographic surveys performed on placement and borrow areas shall be in accordance with EM 1110-1-1005.

Misplaced Material

Any material that is deposited elsewhere than in places designated or approved by the Contracting Officer will not be paid for, and the Contractor may be required to remove such misplaced material and deposit it where directed by the Contracting Officer at the Contractor's expense.

Monthly Partial Payments

Monthly partial payments will be based on the total volume of material placed and accepted for each beach fill segment as determined by the Contracting Officer.

1.7.1.2 Unit of Measure

Unit of measure: Cubic Yards

1.7.2 Contracting Officer Directed Standby Time

1.7.2.1 Payment

Contracting Officer directed standby time calculated by the day (24 hours or 1 Day), including the contractor's costs for holding his equipment and crew on site for a period of 24 consecutive hours. During the contract period, the Government reserves the right to issue stand by orders to the Contractor, due to NASA's Rocket Launch Schedule for periods up to 24 hours at a cost and in a number as bid by the Contractor on the Bid Schedule Item for this requirement. NASA estimates implementing this standby time for approximately 10 rocket launches throughout the length of the contract. If the Contracting Officer directs that the Contractor be placed in a standby status, the Contractor shall cease all beach fill operations and secure his on beach plant and equipment.

1.7.2.2 Unit of Measure

Unit of measure: Day

1.7.3 Sand Excavation and Beach Fill - South End (BID OPTION)

1.7.3.1 Payment

Payment to be made for this item includes all costs associated with excavation of sand from the designated borrow area, transporting of the material to the shoreline and placing/grading within the tolerances specified herein to the designated beach to the lines and grades indicated between Station 0+00 to Station 40+00, and all other associated costs of removal and placement of material as indicated and specified exclusive of bond reimbursement and the mobilization and demobilization as defined above. The total cost of the item Sand Excavation and Beach Fill shall be based on the cubic yard price bid for this item and the computed difference in the amount of material measured by the cubic yard in place for the before and after beach fill surveys for each beach fill segment. All hydrographic surveys performed on placement and borrow areas shall be in accordance with EM 1110-2-1003. All topographic surveys performed on placement and borrow areas shall be in accordance with EM 1110-1-1005.

Misplaced Material

Any material that is deposited elsewhere than in places designated or approved by the Contracting Officer will not be paid for, and the Contractor may be required to remove such misplaced material and deposit it where directed by the Contracting Officer at the Contractor's expense.

Monthly Partial Payments

Monthly partial payments will be based on the total volume of material placed and accepted for each beach fill segment as determined by the Contracting Officer.

1.7.3.2 Unit of Measure

Unit of measure: Cubic Yards1.7.4 Sand Excavation and Beach Fill - North End (BID OPTION)

1.7.4.1 Payment

Payment to be made for this item includes all costs associated with excavation of sand from the designated borrow area, transporting of the material to the shoreline and placing/grading within the tolerances specified herein to the designated beach to the lines and grades indicated between Station 104+00 to Station 150+00, and all other associated costs of removal and placement of material as indicated and specified exclusive of bond reimbursement and the mobilization and demobilization as defined above. The total cost of the item Sand Excavation and Beach Fill shall be based on the cubic yard price bid for this item and the computed difference in the amount of material measured by the cubic yard in place for the before and after beach fill surveys for each beach fill segment. All hydrographic surveys performed on placement and borrow areas shall be in accordance with EM 1110-2-1003. All topographic surveys performed on placement and borrow areas shall be in accordance with EM 1110-1-1005.

Misplaced Material

Any material that is deposited elsewhere than in places designated or approved by the Contracting Officer will not be paid for, and the Contractor may be required to remove such misplaced material and deposit it where directed by the Contracting Officer at the Contractor's expense.

Monthly Partial Payments

Monthly partial payments will be based on the total volume of material placed and accepted for each beach fill segment as determined by the Contracting Officer.

1.7.4.2 Unit of Measure

Unit of measure: Cubic Yards1.7.5 Contracting Officer Directed Standby Time (BID OPTION)

1.7.5.1 Payment

Contracting Officer directed standby time for Bid Option Sand Excavation and Beach Fill, calculated by the day (24 hours or 1 Day), including the contractor's costs for holding his equipment and crew on site for a period of 24 consecutive hours. During the contract period, the Government reserves the right to issue stand by orders to the Contractor, due to NASA's Rocket Launch Schedule for periods up to 24 hours at a cost and in a number as bid by the Contractor on the Bid Schedule Item for this requirement. NASA estimates implementing this standby time for approximately 10 rocket launches throughout the length of the contract. If the Contracting Officer directs that the Contractor be placed in a standby status, the Contractor shall cease all beach fill operations and secure his on beach plant and equipment.

1.7.5.2 Unit of Measure

Unit of measure: Day

PART 2 PRODUCTS

Not Used

PART 3 EXECUTION

Not Used

-- End of Section --

DRAFT
NOT FOR CONSTRUCTION

SECTION 01 30 00

ADMINISTRATIVE REQUIREMENTS

11/20, CHG 3: 08/23

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

U.S. ARMY CORPS OF ENGINEERS (USACE)

EM 385-1-1

(2024) Safety -- Safety and Occupational Health (SOH) Requirements

1.2 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for information only. When used, a code following the "G" classification identifies the office that will review the submittal for the Government. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

View Location Map

Progress and Completion Pictures

1.3 VIEW LOCATION MAP

Submit, prior to or with the first digital photograph submittals, a sketch or drawing indicating the required photographic locations. Update as required if the locations are moved.

1.4 PROGRESS AND COMPLETION PICTURES

Photographically document site conditions prior to start of construction operations. Include aerial photographs. Provide monthly, and within one month of the completion of work, digital photographs, 1600x1200x24 bit true color minimum resolution in JPEG file format showing the sequence and progress of work. Take a minimum of 20 digital photographs each week throughout the entire project from a minimum of ten different viewpoints selected by the Contractor unless otherwise directed by the Contracting Officer. Submit with the monthly invoice two sets of digital photographs, each set on a separate compact disc (CD) or data versatile disc (DVD), cumulative of all photos to date. Indicate photographs demonstrating environmental procedures. Provide photographs for each month in a separate monthly directory and name each file to indicate its location on the view location sketch. Also provide the view location sketch on the CD or DVD as a digital file. Include a date designator in file names. Photographs provided are for unrestricted use by the Government.

1.5 MINIMUM INSURANCE REQUIREMENTS

Provide the minimum insurance coverage required by FAR 28.307-2 Liability, during the entire period of performance under this contract. Provide other insurance coverage as required by Virginia law.

1.6 SUPERVISION

1.6.1 Superintendent Qualifications

Provide project superintendent with a minimum of 10 years experience in construction with at least 5 of those years as a superintendent on projects similar in size and complexity. The individual must be familiar with the requirements of EM 385-1-1 and have experience in the areas of hazard identification and safety compliance. The individual must be capable of interpreting a critical path schedule and construction drawings. The qualification requirements for the alternate superintendent are the same as for the project superintendent. The Contracting Officer may request proof of the superintendent's qualifications at any point in the project if the performance of the superintendent is in question.

1.6.2 Minimum Communication Requirements

Have at least one qualified superintendent, or competent alternate, capable of reading, writing, and conversing fluently in the English language, on the job-site at all times during the performance of Contract work. In addition, if a Quality Control (QC) representative is required on the Contract, then that individual must also have fluent English communication skills.

1.6.3 Duties

The project superintendent is primarily responsible for managing subcontractors and coordinating day-to-day production and schedule adherence on the project. The superintendent is required to attend partnering meetings, and quality control meetings. The superintendent or qualified alternative must be on-site at all times during the performance of this contract until the work is completed and accepted.

1.6.4 Non-Compliance Actions

The Project Superintendent is subject to removal by the Contracting Officer for non-compliance with requirements specified in the contract and for failure to manage the project to ensure timely completion. Furthermore, the Contracting Officer may issue an order stopping all or part of the work until satisfactory corrective action has been taken. No part of the time lost due to such stop orders is acceptable as the subject of claim for extension of time for excess costs or damages by the Contractor.

1.7 PRECONSTRUCTION CONFERENCE

Immediately after award, prior to commencing any work at the site, coordinate with the Contracting Officer a time and place to meet for the Preconstruction Conference. The conference must take place within 35 calendar days after award of the contract, but prior to commencement of any work at the site. The purpose of this conference is to discuss and develop a mutual understanding of the administrative requirements of the Contract including but not limited to: daily reporting, invoicing, value

engineering, safety, base-access, outage requests, hot work permits, schedule requirements, quality control, schedule of prices or earned value report, shop drawings, submittals, cybersecurity, prosecution of the work, government acceptance, final inspections and contract close-out. Contractor must present and discuss their basic approach to scheduling the construction work and any required phasing.

1.7.1 Attendees

Contractor attendees must include the Project Manager, DOR, Superintendent, Site Safety and Health Officer (SSHO), Quality Control Manager and major subcontractors.

1.8 PARTNERING

Contractor shall host the partnering session within 45 calendar days of contract award. To most effectively accomplish this Contract, the Contractor and Government must form a cohesive partnership with the common goal of drawing on the strength of each organization in an effort to achieve a successful project without safety mishaps, conforming to the Contract, within budget and on schedule. The partnering team must consist of personnel from both the Government and Contractor including project level and corporate level leadership positions. Key Personnel from the supported command, end user, Contractor, key subcontractors and the Designer of Record are required to participate in the Partnering process.

1.8.1 Facilitated (Formal) Partnering

- a. Within 35 calendar days after award and prior to the start of work, host a Formal Partnering session with key personnel from the project team including both Contractor and Government personnel. All costs associated with the Partnering session including the third-party independent Facilitator Consultant, meeting room and other incidental items are the responsibility of the Contractor.
- b. Before the Facilitated (Formal) Partnering session, coordinate with the Facilitator all requirements for incidental items (such as audio-visual equipment, easels, flipchart paper, colored markers, note pads, pens/pencils, colored flash cards) and have these items available at the Partnering session. Provide copies of any documents required for distribution to all attendees. Participants will bear their own costs for meals, lodging and transportation associated with Partnering.
- c. The Initial Partnering Session must be a duration of one day and be held at a location off base as agreed to by the Contracting Officer. Partnering session may take place concurrently with the Pre-Construction Meeting.
- d. Facilitator must be experienced in conducting corporate Partnering sessions and must be a third-party independent facilitating consultant - not an employee of the Contractor. The Facilitator is responsible for leading all aspects of the Partnering session necessary to achieve the Partnering goal.
- e. An outcome of the Partnering session must be an escalation matrix agreed upon by both the Government and Contractor, which identifies key Government and Contractor decision makers by name and anticipated decision durations.

- f. Host follow-on Partnering Sessions at three- to six-month intervals or more frequently if needed and lasting generally a half day or less. Attendees need only be those required to resolve current issues. The same Facilitator used in the Initial Partnering session must lead the follow-on sessions unless an alternative is permitted by the Contractor Officer. All costs associated with follow-on Partnering sessions are the responsibility of the Contractor.

1.9 MOBILIZATION

Contractor shall mobilize to the jobsite within 60 calendar days after contract award . Mobilize is defined as having equipment AND having a physical presence of at least one person from the contractor's team on the jobsite.

PART 2 PRODUCTS

Not Used

PART 3 EXECUTION

Not Used

-- End of Section --

SECTION 01 32 01.00 10

PROJECT SCHEDULE
08/23

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AACE INTERNATIONAL (AACE)

- | | |
|-------------|--|
| AACE 29R-03 | (2011) Forensic Schedule Analysis |
| AACE 52R-06 | (2006) Time Impact Analysis - As Applied in Construction |
| AACE 84R-13 | (2015) Planning and Accounting for Adverse Weather |

AMERICAN SOCIETY OF CIVIL ENGINEERS (ASCE)

- | | |
|------------|--------------------------------|
| ASCE 67-17 | (2017) Schedule Delay Analysis |
|------------|--------------------------------|

U.S. ARMY CORPS OF ENGINEERS (USACE)

- | | |
|-----------|--|
| ER 1-1-11 | (2017) Administration -- Project Schedules |
|-----------|--|

1.2 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for information only. When used, a code following the "G" classification identifies the office that will review the submittal for the Government. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

- Project Scheduler Qualifications; G, R0
- Preliminary Project Schedule; G, R0
- Initial Project Schedule; G, R0
- Periodic Schedule Update; G, R0
- Narrative Report; G, R0

1.3 PROJECT SCHEDULER QUALIFICATIONS

Designate an authorized representative to be responsible for the preparation of the schedule and all required updating and production of reports. The Designated Project Scheduler must have prepared and maintained at least three previous construction schedules for projects of

similar size and complexity to this contract, using Primavera P6.. Representative must have a comprehensive knowledge of CPM scheduling principles and application.

PART 2 PRODUCTS

2.1 SOFTWARE

The scheduling software utilized to produce and update the schedules required herein must be capable of meeting all requirements of this specification.

2.1.1 Government Default Software

The Government uses Primavera P6. Ensure exported schedule files are compatible with the version of P6 used by the Government.

2.1.2 Contractor Software

Scheduling software used by the contractor must be commercially available from the software vendor for purchase with vendor software support agreements available. The software routine used to create the required sdef file must be created and supported by the software manufacturer.

2.1.2.1 Primavera

If Primavera P6 is selected for use, provide the "xer" export file in a version of P6 importable by the Government system. Verify at the SEKO meeting which version of P6 is in use by the Government. Export the schedule in a version of P6 no newer than that used by the Government.

2.1.2.2 Other Than Primavera

If the Contractor chooses software other than Primavera P6, that is compliant with this specification, provide for the Government's use two licenses, two computers, and training for two Government employees in the use of the software. These computers will be stand-alone and not connected to Government network. Computers and licenses will be returned at project completion.

PART 3 EXECUTION

3.1 GENERAL REQUIREMENTS

Prepare for approval a Project Schedule, as specified herein, pursuant to FAR Clause 52.236-15 Schedules for Construction Contracts. Show in the schedule the proposed sequence to perform the work and dates contemplated for starting and completing all schedule activities. The scheduling of the entire project is required. The scheduling of construction is the responsibility of the Contractor. Contractor management personnel must actively participate in its development. Subcontractors, and suppliers working on the project must also contribute in developing and maintaining an accurate Project Schedule. Provide a schedule that is a forward planning as well as a project monitoring tool. Use the Critical Path Method (CPM) of network calculation to generate all Project Schedules. Prepare each Project Schedule using the Precedence Diagram Method (PDM).

3.1.1 Scheduling Expectations Kickoff Meeting(SEK0)

In conjunction with the post award conference or pre construction conference the Government and the Contractor will hold a separate and distinct Scheduling Expectations Kickoff Meeting(SEK0). The intent of this meeting is for the Government to review with the contractor the requirements of the scheduling specification, communicate the Government's expectations regarding schedule development and management, and answer any questions the Contractor may have regarding the schedule requirements.

3.2 BASIS FOR PAYMENT AND COST LOADING

The schedule is the basis for determining contract earnings during each update period and therefore the amount of each progress payment. The aggregate value of all activities coded to a contract CLIN must equal the value of the CLIN. Match the progress payment "Pay Period Thru" date in RMS to the schedule data date.

3.2.1 Activity Cost Loading

Activity cost loading must be reasonable and without front-end loading. Activities with a negative cost loading is not allowed. Provide additional documentation to demonstrate reasonableness if requested by the Contracting Officer.

3.2.2 Withholdings / Payment Rejection

Failure to meet the requirements of this specification may result in the disapproval of the preliminary, initial, or periodic schedule updates and subsequent rejection of payment requests until compliance is met.

In the event that the Contracting Officer directs schedule revisions and those revisions have not been included in subsequent Project Schedule revisions or updates, the Contracting Officer may withhold 10 percent of pay request amount from each payment period until such revisions to the project schedule have been made.

3.3 PROJECT SCHEDULE DETAILED REQUIREMENTS

3.3.1 Level of Detail Required

Develop the Project Schedule to the appropriate level of detail to address major milestones and to allow for satisfactory project planning and execution. Failure to develop the Project Schedule to an appropriate level of detail will result in its disapproval. The Contracting Officer will consider, but is not limited to, the following characteristics and requirements to determine appropriate level of detail:

3.3.2 Activity Durations

Reasonable activity durations are those that allow the progress of ongoing activities to be accurately determined between update periods. Non-procurement activities Original Durations (OD) are not to exceed 20 workdays or 30 calendar days.

3.3.3 Procurement Activities

Include in the schedule activities associated with the critical submittals and their approvals, procurement, fabrication, and delivery of long lead

materials, equipment, fabricated assemblies, and supplies. Long lead procurement activities are those with an anticipated procurement sequence of over 90 calendar days.

3.3.4 Mandatory Activities

Include the following activities in the initial project schedule and all updates.

- a. Submission, review and acceptance of SD-01 Preconstruction Submittals (individual activity for each).
- b. Submission, review and acceptance of features requiring design completion
- c. Submission of information systems layout drawings.
- d. Submission and approval of O & M manuals.
- e. Submission and approval of as-built drawings.
- f. Submission and approval of DD1354 data and installed equipment lists.
- g. Submission and approval of testing and air balance (TAB).
- h. Submission of TAB specialist design review report.
- i. Submission and approval of fire protection specialist.
- j. Contractor's pre-final inspection.
- k. Correction of punch list from Contractor's pre-final inspection.
- l. Government's pre-final inspection.
- m. Correction of punch list from Government's pre-final inspection.
- n. Final inspection.

3.3.5 Government Activities

Show in schedule, Government and other agency activities that could impact progress. These activities include, but are not limited to approvals, environmental permit approvals by Federal or State regulators, inspections, utility tie-in, Government Furnished Equipment (GFE) and Notice to Proceed (NTP) for phasing requirements.

3.3.6 Standard Activity Coding Dictionary

Use the activity coding structure defined in the Standard Data Exchange Format (SDEF) in ER 1-1-11. This exact structure is mandatory. Develop and assign all Activity Codes to activities as detailed herein.

The SDEF format is as follows:

Field	Activity Code	Length	Description
1	WRKP	3	Workers per day
2	RESP	4	Responsible party
3	AREA	4	Area of work
4	MODF	6	Modification Number
5	BIDI	6	Bid Item (CLIN)
6	PHAS	2	Phase of work
7	CATW	1	Category of work
8	FOW	20	Feature of work*
*Some systems require that FEATURE OF WORK values be placed in several activity code fields. The notation shown is for Primavera P6. Refer to the specific software guidelines with respect to the FEATURE OF WORK field requirements.			

3.3.6.1 Workers Per Day (WRKP)

Assign Workers per Day for all field construction or direct work activities, if directed by the Contracting Officer. Workers per day is based on the average number of workers expected each day to perform a task for the duration of that activity.

3.3.6.2 Responsible Party Coding (RESP)

Assign responsibility code for all activities to the Prime Contractor, Subcontractor(s) or Government agency(ies) responsible for performing the activity.

- a. Activities coded with a Government Responsibility code include, but are not limited to: Government approvals, Government design reviews, environmental permit approvals by Federal or State regulators, Government Furnished Property/Equipment (GFP) and Notice to Proceed (NTP) for phasing requirements.
- b. Activities cannot have more than one Responsibility Code. Examples of acceptable activity code values are: DOR (for the designer of record); ELEC (for the electrical subcontractor); MECH (for the mechanical subcontractor); and GOVT (for USACE).

3.3.6.3 Area of Work Coding (AREA)

Assign Work Area code to activities based upon the work area in which the activity occurs. Define work areas based on resource constraints or space constraints that would preclude a resource, such as a particular trade or craft work crew from working in more than one work area at a time due to restraints on resources or space. Examples of Work Area Coding include different areas within a floor of a building, different floors within a building, and different buildings within a complex of buildings.

Activities cannot have more than one Work Area Code.

3.3.6.4 Modification Number (MODF)

Assign a Modification Number Code to any activity or sequence of activities added to the schedule as a result of a Contract Modification, when approved by Contracting Officer. Key all Code values to the Government's modification numbering system. An activity can have only one Modification Number Code.

3.3.6.5 Bid Item Coding (BIDI)

Assign a Bid Item Code to all activities using the Contract Line Item Number (CLIN) to which the activity belongs, even when an activity is not cost loaded. An activity can have only one BIDI Code.

3.3.6.6 Phase of Work Coding (PHAS)

Assign Phase of Work Code to all activities. Examples of phase of work are procurement phase and construction phase. Each activity can have only one Phase of Work code.

- a. Code proposed fast track design and construction phases proposed to allow filtering and organizing the schedule by fast track design and construction packages.
- b. If the contract specifies phasing with separately defined performance periods, identify a Phase Code to allow filtering and organizing the schedule accordingly.

3.3.6.7 Category of Work Coding (CATW)

Assign a Category of Work Code to all activities. Category of Work Codes include, but are not limited to, construction submittal, procurement, fabrication, weather sensitive installation, non-weather sensitive installation, start-up, and testing activities. Each activity can have no more than one Category of Work Code.

3.3.6.8 Feature of Work Coding (FOW)

Assign a Feature of Work Code to appropriate activities based on the Definable Feature of Work to which the activity belongs based on the approved QC plan.

Definable Feature of Work is defined in Section 01 45 00 QUALITY CONTROL. An activity can have only one Feature of Work Code.

3.3.7 Contract Milestones and Constraints

Milestone activities are to be used for significant project events including, but not limited to, project phasing, project start and end activities, or interim completion dates. The use of artificial float constraints such as "zero free float" or "zero total float" are prohibited.

Mandatory constraints that ignore or effect network logic are prohibited. No constrained dates are allowed in the schedule other than those specified herein. Submit additional constraints to the Contracting Officer for approval on a case by case basis.

3.3.7.1 Project Start Date Milestone and Constraint

The first activity in the project schedule must be a start milestone titled "NTP Acknowledged," which must have a "Start On" constraint date equal to the date that the NTP is acknowledged.

3.3.7.2 End Project Finish Milestone and Constraint

The last activity in the schedule must be a finish milestone titled "End Project."

Constrain the project schedule to the Contract Completion Date in such a way that if the schedule calculates an early finish, then the float calculation for "End Project" milestone reflects positive float on the longest path. If the project schedule calculates a late finish, then the "End Project" milestone float calculation reflects negative float on the longest path.

3.3.7.3 Interim Completion Dates and Constraints

Constrain contractually specified interim completion dates to show negative float when the calculated late finish date of the last activity in that phase is later than the specified interim completion date.

3.3.7.3.1 Start Phase

Use a start milestone as the first activity for a project phase. Call the start milestone "Start Phase X" where "X" refers to the phase of work.

3.3.7.3.2 End Phase

Use a finish milestone as the last activity for a project phase. Call the finish milestone "End Phase X" where "X" refers to the phase of work.

3.3.8 Adverse Weather

Ensure anticipated adverse weather is accounted for in the Project Schedule. AACE 84R-13 provides methodologies for techniques in planning for adverse weather. The preferred methodology is the use of a weather calendar. If a method other than a weather calendar is proposed the discuss the reason during the SEKO meeting.

3.3.9 Calendars

Schedule activities on a Calendar to which the activity logically belongs. Develop calendars to accommodate any contract defined work period such as a 7-day calendar for Government Acceptance activities, concrete cure times, etc. Develop the default Calendar to match the physical work plan with non-work periods identified including weekends and holidays. Develop Seasonal Calendar(s) and assign to seasonally affected activities as applicable.

If a weather calendar is used its implementation and execution is to be in accordance with AACE 84R-13

3.3.10 Open Ended Logic

Only two open ended activities are allowed: the first activity "NTP

Acknowledged" is to have no predecessor logic, and the last activity -"End Project" is to have no successor logic. Except as noted above all activities are to have at least a start-to-start or finish-to-start relationship with its predecessor(s) and a finish-to-finish or finish-to-start relationship with its successor(s).

Predecessor open ended logic may be allowed in a time impact analyses upon the Contracting Officer's approval.

3.3.11 Default Progress Data Disallowed

Actual Start and Finish dates must not automatically update with default mechanisms included in the scheduling software. Updating of the percent complete and the remaining duration of any activity must be independent functions. Disable program features that calculate one of these parameters from the other. Activity Actual Start (AS) and Actual Finish (AF) dates assigned during the updating process must match those dates provided in the Contractor Quality Control Reports. Failure to document the AS and AF dates in the Daily Quality Control report will result in disapproval of the Contractor's schedule.

3.3.12 Out-of-Sequence Progress

Activities that have progressed before all preceding logic has been satisfied (Out-of-Sequence Progress) will be allowed only on a case-by-case basis subject to approval by the Contracting Officer. Propose logic corrections to eliminate out of sequence progress or justify not changing the sequencing for approval prior to submitting an updated project schedule. Address out of sequence progress or logic changes in the Narrative Report and in the periodic schedule update meetings.

3.3.13 Added and Deleted Activities

Do not delete activities from the project schedule or add new activities to the schedule without approval from the Contracting Officer. Activity ID and description changes are considered new activities and cannot be changed without Contracting Officer approval.

3.3.14 Original Durations

Activity Original Durations (OD) must be reasonable to perform the work item. OD changes are prohibited unless justification is provided and approved by the Contracting Officer.

3.3.15 Leads, Lags, and Start to Finish Relationships

Lags must be reasonable as determined by the Government and not used in place of realistic original durations, must not be in place to artificially absorb or create float, or to replace proper schedule logic.

- a. Leads (negative lags) are prohibited.
- b. Start to Finish (SF) relationships are prohibited.

3.3.16 Retained Logic

Schedule calculations must retain the logic between predecessors and successors ("retained logic" mode) even when the successor activity(s) starts and the predecessor activity(s) has not finished (out-of-sequence

progress). Software features that in effect sever the tie between predecessor and successor activities when the successor has started and the predecessor logic is not satisfied ("progress override") are not be allowed.

3.3.17 Percent Complete

Update the percent complete for each activity started, based on the realistic assessment of earned value. Activities which are complete but for remaining minor punch list work and which do not restrain the initiation of successor activities may be declared 100 percent complete to allow for proper schedule management. Budgeted cost of activity is to be reduced by the amount needed to correct deficiency. The activity referenced in paragraph COST LOADING of CLOSEOUT ACTIVITIES must have its budgeted cost increased by this amount.

3.3.18 Remaining Duration

Update the remaining duration for each activity based on the number of estimated workdays it will take to complete the activity. Remaining duration may not mathematically correlate with percentage found under paragraph entitled Percent Complete. The remaining duration for unstarted activities are not to be less than its original duration.

3.3.19 Cost Loading of Closeout Activities

Cost load the "Correction of punch list from Government pre-final inspection" activity(ies) not less than 1 percent of the present contract value. Activity(ies) may be declared 100 percent complete upon the Government's verification of completion and correction of all punch list work identified during Government pre-final inspection(s).

3.3.19.1 As-Built Drawings

If there is no separate contract line item (CLIN) for as-built drawings, cost load the "Submission and approval of as-built drawings" activity not less than \$35,000 or 1 percent of the present contract value, which ever is greater, up to \$200,000. Activity will be declared 100 percent complete upon the Government's approval.

3.3.19.2 O & M Manuals

Cost load the "Submission and approval of O & M manuals" activity not less than \$20,000. Activity will be declared 100 percent complete upon the Government's approval of all O & M manuals.

3.3.20 Early Completion Schedule and the Right to Finish Early

An Early Completion Schedule is an Initial Project Schedule (IPS) that indicates all scope of the required contract work will be completed before the contractually required completion date.

- a. No IPS indicating an Early Completion will be accepted without being fully resource-loaded (including crew sizes and manhours) and the Government agreeing that the schedule is reasonable and achievable.
- b. The Government is under no obligation to accelerate work items it is responsible for to ensure that the early completion is met nor is it responsible to modify incremental funding (if applicable) for the

project to meet the contractor's accelerated work.

3.4 PROJECT SCHEDULE SUBMISSIONS

Provide the submissions as described below. The data reports and network diagrams required for each submission are contained in paragraph SUBMISSION REQUIREMENTS. If the Contractor fails or refuses to furnish the information and schedule updates as set forth herein, the Contractor will be deemed not to have provided an estimate upon which a progress payment can be made.

Review comments made by the Government on the schedule(s) do not relieve the Contractor from compliance with requirements of the Contract Documents.

3.4.1 Preliminary Project Schedule Submission

Within 15 calendar days after the NTP is acknowledged, submit the Preliminary Project Schedule defining the planned operations detailed for the first 90 calendar days for approval. The approved Preliminary Project Schedule will be used for payment purposes not to exceed 90 calendar days after NTP. Completely cost load the Preliminary Project Schedule to balance the contract award CLINS shown on the Price Schedule. The Preliminary Project Schedule may be summary in nature for the remaining performance period. It must be early start and late finish constrained and logically tied as specified. The Preliminary Project Schedule forms the basis for the Initial Project Schedule specified herein and must include all of the required plan and program preparations, submissions and approvals identified in the contract (for example, Quality Control Plan, Safety Plan, and Environmental Protection Plan) as well as design activities, planned submissions of all early design packages, permitting activities, design review conference activities, and other non-construction activities intended to occur within the first 90 calendar days. Government acceptance of the associated design package(s) and all other specified Program and Plan approvals must occur prior to any planned construction activities. Activity code any activities that are summary in nature after the first 90 calendar days with Bid Item (CLIN) code (BIDI), Responsibility Code (RESP) and Feature of Work code (FOW).

3.4.2 Initial Project Schedule Submission

Submit the Initial Project Schedule for approval within 42 calendar days after notice to proceed is issued. The schedule must demonstrate a reasonable and realistic sequence of activities which represent all work through the entire contract performance period. No payment will be made for work items not fully detailed in the Project Schedule.

3.4.3 Periodic Schedule Updates

Update the Project Schedule on a regular basis, monthly at a minimum. Provide a draft Periodic Schedule Update for review at the schedule update meetings as prescribed in the paragraph PERIODIC SCHEDULE UPDATE MEETINGS. These updates will enable the Government to assess Contractor's progress.

- a. Update information including Actual Start Dates (AS), Actual Finish Dates (AF), Remaining Durations (RD), and Percent Complete. Updated information is subject to the approval of the Government at the meeting.

- b. AS and AF dates must match the date(s) reported on the Contractor's Quality Control Report for an activity start or finish.

3.5 SUBMISSION REQUIREMENTS

Submit the following items for the Preliminary Schedule, Initial Schedule, and every Periodic Schedule Update throughout the life of the project:

3.5.1 Electronic Scheduling Data

Provide electronic scheduling data containing the current project schedule and all previously submitted schedules in the format of the scheduling software (e.g. .xer). Also include the Narrative Report and all required Schedule Reports. The electronic file is to identify the type of schedule (Preliminary, Initial, Update), full contract number, Data Date and schedule file name. Each schedule must have a unique file name and use project specific settings. The file naming convention is to be determined at SEKO meeting.

3.5.2 Narrative Report

Provide a Narrative Report with each schedule submission. The Schedule Narrative Report is a "stand alone" report in PDF or Word format. Title the report "Schedule Narrative Report". Show the Report date, schedule name, and contract number on the first page. Indicate who is responsible for the schedule update and narrative report. Provide a brief description of the Project Scope. The Narrative Report is expected to communicate to the Government the thorough analysis of the schedule output and the plans to compensate for problems, either current or potential, which are revealed through that analysis. Include the following information at a minimum in the Narrative Report:

- a. Identify and discuss the work scheduled to start in the next update period.
- b. Describe activities along the critical path in addition to activities on the next float path after the critical path.
- c. Describe current and anticipated problem areas, delaying factors and their impact, and an explanation of corrective actions taken or required to be taken. Identify the party responsible for delay, if applicable.
- d. Identify and explain why activities, based on their calculated late dates, should have either started or finished during the update period but did not.
- e. Identify and discuss all schedule changes by activity ID and activity name including what specifically was changed and why the change was needed. Include at a minimum new and deleted activities, logic changes, duration changes, calendar changes, lag changes, resource changes, and actual start and finish date changes.
- f. Identify and discuss out-of-sequence work.
- g. If the longest path changes from a monthly update to the next, provide an explanation of the factors driving the change.
- h. Respond to USACE Schedule Review Comments from the previous update(s).

3.5.3 Schedule Reports

The format, filtering, organizing, and sorting for each schedule report will be as directed by the Contracting Officer. Typically, reports contain Activity Numbers, Activity Description, Original Duration, Remaining Duration, Early Start Date, Early Finish Date, Late Start Date, Late Finish Date, Total Float, Actual Start Date, Actual Finish Date, and Percent Complete. Provide the reports electronically in .pdf format. Provide 3 set(s) of hardcopy reports. The following lists typical reports that will be requested:

3.5.3.1 Activity Report

List of all activities sorted according to activity number.

3.5.3.2 Logic Report

List of detailed predecessor and successor activities for every activity in ascending order by activity number.

3.5.3.3 Total Float Report

A list of all incomplete activities sorted in ascending order of total float. List activities which have the same amount of total float in ascending order of Early Start Dates. Do not show completed activities on this report.

3.5.3.4 Earnings Report by CLIN

A compilation of the Total Earnings on the project from the NTP to the data date, which reflects the earnings of activities based on the agreements made in the schedule update meeting defined herein. Provided a complete schedule update has been furnished, this report serves as the basis of determining progress payments. Group activities by CLIN number and sort by activity number. Provide a total CLIN percent earned value, CLIN percent complete, and project percent complete. The printed report must contain the following for each activity: the Activity Number, Activity Description, Original Budgeted Amount, Earnings to Date, Earnings this period, Total Quantity, Quantity to Date, and Percent Complete (based on cost).

3.5.3.5 Scheduling and Leveling Report

Provide a Scheduling/Leveling Report generated from the current project schedule being submitted.

3.5.4 Network Diagram

The Network Diagram is required for the Preliminary, Initial and Periodic Updates. Depict and display the order and interdependence of activities and the sequence in which the work is to be accomplished. The Contracting Officer will use, but is not limited to, the following conditions to review compliance with this paragraph:

3.5.4.1 Continuous Flow

Show a continuous flow from left to right with no arrows from right to left. Show the activity number, description, duration, and estimated

earned value on the diagram.

3.5.4.2 Project Milestone Dates

Show dates on the diagram for start of project, any contract required interim completion dates, and contract completion dates.

3.5.4.3 Critical Path

Show all activities on the critical path. The critical path is defined as the longest path.

3.5.4.4 Grouping and Sorting

Group and sort activities as directed to assist in the understanding of the activity sequence. Typically, this flow will group activities by major elements of work, category of work, work area and/or responsibility.

3.5.4.5 Cash Flow / Schedule Variance Control (SVC) Diagram

With each schedule submission, provide a SVC diagram showing 1) Cash Flow S-Curves indicating planned project cost based on projected early and late activity finish dates, and 2) Earned Value to-date.

3.6 PERIODIC SCHEDULE UPDATE

3.6.1 Periodic Schedule Update Meetings

Conduct periodic schedule update meetings for the purpose of reviewing the proposed Periodic Schedule Update, Narrative Report, Schedule Reports, and progress payment. Conduct meetings at least monthly within five days of the proposed schedule data date. Provide a computer with the scheduling software loaded and a projector which allows all meeting participants to view the proposed schedule during the meeting. The Contractor's authorized scheduler must organize, group, sort, filter, perform schedule revisions as needed and review functions as requested by the Contractor and/or Government. The Contractor scheduler must attend in person unless virtual attendance is approved by Contracting Officer. The meeting is a working interactive exchange which allows the Government and Contractor the opportunity to review the updated schedule on a real time and interactive basis. The meeting will last no longer than 8 hours. Submit schedule file and narrative to the Government a minimum of two workdays in advance of the meeting. The Contractor's Project Manager must attend the meeting with the authorized representative of the Contracting Officer. Superintendents, foremen and major subcontractors must attend the meeting as required to discuss the project schedule and work. Following the schedule update meeting, make corrections to the schedule and resubmit, following the required schedule naming convention. Include only those changes approved by the Government in the schedule review meeting. Only approved schedules may be used to generate invoices for payment.

3.6.2 Update Submission Following Progress Meeting

Submit the complete Periodic Schedule Update of the Project Schedule containing all approved progress, revisions, and adjustments, pursuant to paragraph SUBMISSION REQUIREMENTS not later than 4 workdays after the periodic schedule update meeting.

3.7 WEEKLY PROGRESS MEETINGS

Conduct a weekly meeting with the Government (or as otherwise mutually agreed to) between the meetings described in paragraph entitled PERIODIC SCHEDULE UPDATE MEETINGS for the purpose of jointly reviewing the actual progress of the project as compared to the as planned progress and to review planned activities for the upcoming two weeks. Use the current approved schedule update for the purposes of this meeting and for the production and review of reports. At the weekly progress meeting, address the status of RFIs, RFPs and Submittals.

3.8 REQUESTS FOR TIME EXTENSIONS

ASCE 67-17 provides delay analysis guidelines. If there is a conflict between the contract and guidance provided in ASCE 67-17, the contract will govern. Provide justification of delay to the Contracting Officer in accordance with the contract provisions and clauses for approval, within 10 days of a delay occurring. Also prepare a time impact analysis for each Government request for proposal (RFP).

3.8.1 Changes That Do Not Cause Delay

If it is determined that a change does not constitute a schedule time extension, a fragnet as described in paragraph FRAGMENTARY NETWORK, is to be created and inserted into the Project schedule.

3.8.2 Time Impact Analysis (Prospective Analysis)

Prepare a time impact analysis for approval by the Contracting Officer based on industry standard AACE 52R-06. Utilize a copy of the last approved schedule prior to the first day of the impact or delay for the time impact analysis. If Contracting Officer determines the time frame between the last approved schedule and the first day of impact is too great, prepare an interim updated schedule to perform the time impact analysis. Unless approved by the Contracting Officer, no other changes may be incorporated into the schedule being used to justify the time impact.

3.8.3 Forensic Schedule Analysis (Retrospective Analysis)

Prepare an analysis for approval by the Contracting Officer based on methodologies identified in industry standard AACE 29R-03. Identify which methodology was chosen and explain why it is more appropriate than other methodologies available.

3.8.4 Fragmentary Network (Fragnet)

Prepare a proposed fragnet for time impact analysis consisting of a sequence of new activities that are proposed to be added to the project schedule to demonstrate the influence of the delay or impact to the project's contractual dates. Clearly show how the proposed fragnet is to be tied into the project schedule including all predecessors and successors to the fragnet activities. The proposed fragnet must be approved by the Contracting Officer prior to incorporation into the project schedule.

3.8.5 Time Extension

The Contracting Officer must approve the Justification of Delay including

the time impact analysis before a time extension will be granted. No time extension will be granted unless the delay consumes all available Project Float and extends the projected finish date ("End Project" milestone) beyond the Contract Completion Date. The time extension will be in calendar days.

Actual delays that are found to be caused by the Contractor's own actions, which result in a calculated schedule delay, are not a cause for an extension to the performance period, completion date, or any interim milestone date.

3.8.6 Impact to Early Completion Schedule

No extended overhead will be paid for delay prior to the original Contract Completion Date for an Early Completion IPS unless the Contractor actually performed work in accordance with that Early Completion Schedule. The Contractor must show that an early completion was achievable had it not been for the impact.

3.9 JUSTIFICATION OF DELAY

Provide a description of the event(s) that caused the delay and/or impact to the work. As part of the description, identify all schedule activities impacted. Show that the event that caused the delay/impact was the responsibility of the Government. Provide a time impact analysis that demonstrates the effects of the delay or impact on the project completion date, or interim completion date(s). Evaluate multiple impacts chronologically; each with its own justification of delay. With multiple impacts consider any concurrency of delay. A time extension and the schedule fragment becomes part of the project schedule and all future schedule updates upon approval by the Contracting Officer.

3.9.1 Non-Compliance

The Contractor shall hold harmless the United States and its officers and employees, from all claims that may arise as a result of the Contractor's negligence in connection with the work performed under the contract, from noncompliance by the Contractor with provisions of the contract drawings, specifications, or permits.

3.10 FAILURE TO ACHIEVE PROGRESS

Should the progress fall behind the approved project schedule for reasons other than those that are excusable within the terms of the contract, the Contracting Officer may require provision of a written recovery plan for approval. The plan must detail how progress will be made-up to include which activities will be accelerated by adding additional crews, longer work hours, extra workdays, etc.

3.10.1 Artificially Improving Progress

Artificially improving progress by means such as, but not limited to, revising the schedule logic, modifying, or adding constraints, shortening activity durations, or changing calendars in the project schedule is prohibited. Indicate assumptions made and the basis for any logic, constraint, duration, and calendar changes used in the creation of the recovery plan. Any additional resources, manpower, or daily and weekly work hour changes proposed in the recovery plan must be evident at the work site and documented in the daily report along with the Schedule

Narrative Report.

3.10.2 Failure to Perform

Failure to perform work and maintain progress in accordance with the supplemental recovery plan may result in an interim and final unsatisfactory performance rating and may result in corrective action directed by the Contracting Officer pursuant to FAR 52.236-15 Schedules for Construction Contracts, FAR 52.249-10 Default (Fixed-Price Construction), and other contract provisions.

3.10.3 Recovery Schedule

Should the Contracting Officer find it necessary, submit a recovery schedule pursuant to FAR 52.236-15 Schedules for Construction Contracts.

3.11 OWNERSHIP OF FLOAT

Except for the provision given in the paragraph IMPACT TO EARLY COMPLETION SCHEDULE, float available in the schedule, at any time, belongs to the Project and is available for Contractor and Government use. This includes activity and project float. Activity float is the number of workdays that an activity can be delayed without causing a delay to the "End Project" finish milestone. Project float (if applicable) is the number of work days between the projected early finish and the "End Project" finish.

3.12 TRANSFER OF SCHEDULE DATA INTO RESIDENT MANAGEMENT SYSTEM

Ensure schedule data is uploaded to RMS. This data is additional supporting data in a form and detail required by the Contracting Officer pursuant to FAR 52.232-5 Payments under Fixed-Price Construction Contracts. The receipt of a proper payment request pursuant to FAR 52.232-27 Prompt Payment for Construction Contracts is contingent upon the Government receiving both acceptable and approvable hard copies and matching electronic versions of the application for progress payment.

3.13 PRIMAVERA P6 MANDATORY REQUIREMENTS

Ensure Primavera P6 settings provide a schedule capable of fulfilling the requirements of the contract. The following settings are mandatory and required in all schedule submissions to the Government:

- a. Activity Codes must be Project Level, not Global or EPS level.
- b. Calendars must be Project Level, not Global or Resource level.
- c. Activity Duration Types must be set to "Fixed Duration & Units".
- d. Percent Complete Types must be set to "Physical".
- e. Time Period Admin Preferences must remain the default "8.0 hr/day, 40 hr/week, 172 hr/month, 2000 hr/year". Set Calendar Work Hours/Day to 24.0 Hour days.
- f. Set Schedule Option for defining Critical Activities to "Longest Path".
- g. Set Schedule Option for defining progressed activities to "Retained Logic".

- h. Set up cost loading using a single lump sum non-labor resource. The Price/Unit must be \$1/hr, Default Units/Time must be "8h/d", and settings "Auto Compute Actuals" and "Calculate costs from units" un-selected.
- i. Activity ID's must not exceed 10 characters.
- j. Activity Names must have a verb-noun structure and contain the most defining and detailed description within the first 30 characters.
- k. The daily ending hour for all work calendars must be the same.

-- End of Section --

DRAFT
NOT FOR CONSTRUCTION

SECTION 01 33 00

SUBMITTAL PROCEDURES

08/18, CHG 4: 02/21

PART 1 GENERAL

1.1 SUMMARY

1.1.1 Submittal Information

The Contracting Officer may request submittals in addition to those specified when deemed necessary to adequately describe the work covered in the respective sections. Each submittal is to be complete and in sufficient detail to allow ready determination of compliance with contract requirements.

Units of weights and measures used on all submittals are to be the same as those used in the contract drawings.

1.1.2 Project Type

The Contractor's Quality Control (CQC) System Manager are to check and approve all items before submittal and stamp, sign, and date indicating action taken. Proposed deviations from the contract requirements are to be clearly identified. Include within submittals items such as: Contractor's, manufacturer's, or fabricator's drawings; descriptive literature including (but not limited to) catalog cuts, diagrams, operating charts or curves; test reports; test cylinders; samples; O&M manuals (including parts list); certifications; warranties; and other such required submittals.

1.1.3 Submission of Submittals

Schedule and provide submittals requiring Government approval before acquiring the material or equipment covered thereby. Pick up and dispose of samples not incorporated into the work in accordance with manufacturer's Safety Data Sheets (SDS) and in compliance with existing laws and regulations.

1.2 DEFINITIONS

1.2.1 Submittal Descriptions (SD)

Submittal requirements are specified in the technical sections. Examples and descriptions of submittals identified by the Submittal Description (SD) numbers and titles follow:

SD-01 Preconstruction Submittals

Submittals that are required prior to or at the start of construction (work) or the next major phase of the construction on a multiphase contract.

Preconstruction Submittals include schedules and a tabular list of locations, features, and other pertinent information regarding products, materials, equipment, or components to be used in the work.

Certificates Of Insurance

Surety Bonds

List Of Proposed Subcontractors

List Of Proposed Products

Baseline Network Analysis Schedule (NAS)

Submittal Register

Schedule Of Prices Or Earned Value Report

Accident Prevention Plan

Work Plan

Quality Control (QC) plan

Environmental Protection Plan

SD-02 Shop Drawings

Drawings, diagrams and schedules specifically prepared to illustrate some portion of the work.

Diagrams and instructions from a manufacturer or fabricator for use in producing the product and as aids to the Contractor for integrating the product or system into the project.

Drawings prepared by or for the Contractor to show how multiple systems and interdisciplinary work will be coordinated.

SD-03 Product Data

Catalog cuts, illustrations, schedules, diagrams, performance charts, instructions and brochures illustrating size, physical appearance and other characteristics of materials, systems or equipment for some portion of the work.

Samples of warranty language when the contract requires extended product warranties.

SD-04 Samples

Fabricated or unfabricated physical examples of materials, equipment or workmanship that illustrate functional and aesthetic characteristics of a material or product and establish standards by which the work can be judged.

Color samples from the manufacturer's standard line (or custom color samples if specified) to be used in selecting or approving colors for the project.

Field samples and mock-ups constructed on the project site establish standards ensuring work can be judged. Includes assemblies or portions of assemblies that are to be incorporated into the project and those that will be removed at conclusion of the work.

SD-06 Test Reports

Report signed by authorized official of testing laboratory that a material, product or system identical to the material, product or system to be provided has been tested in accord with specified requirements. Unless specified in another section, testing must have been within three years of date of contract award for the project.

Report that includes findings of a test required to be performed on an actual portion of the work or prototype prepared for the project before shipment to job site.

Report that includes finding of a test made at the job site or on sample taken from the job site, on portion of work during or after installation.

Investigation reports

Daily logs and checklists

Final acceptance test and operational test procedure

SD-07 Certificates

Statements printed on the manufacturer's letterhead and signed by responsible officials of manufacturer of product, system or material attesting that the product, system, or material meets specification requirements. Must be dated after award of project contract and clearly name the project.

Document required of Contractor, or of a manufacturer, supplier, installer or Subcontractor through Contractor. The document purpose is to further promote the orderly progression of a portion of the work by documenting procedures, acceptability of methods, or personnel qualifications.

Confined space entry permits

Text of posted operating instructions

SD-08 Manufacturer's Instructions

Preprinted material describing installation of a product, system or material, including special notices and (SDS) concerning impedances, hazards and safety precautions.

SD-10 Operation and Maintenance Data

Data provided by the manufacturer, or the system provider, including manufacturer's help and product line documentation, necessary to maintain and install equipment, for operating and maintenance use by facility personnel.

Data required by operating and maintenance personnel for the safe and efficient operation, maintenance and repair of the item.

Data incorporated in an operations and maintenance manual or control system.

SD-11 Closeout Submittals

Documentation to record compliance with technical or administrative requirements or to establish an administrative mechanism.

Submittals required for Guiding Principle Validation (GPV) or Third Party Certification (TPC).

Special requirements necessary to properly close out a construction contract. For example, Record Drawings and as-built drawings. Also, submittal requirements necessary to properly close out a major phase of construction on a multi-phase contract.

1.2.2 Approving Authority

Office or designated person authorized to approve the submittal.

1.2.3 Work

As used in this section, on-site and off-site construction required by contract documents, including labor necessary to produce submittals, construction, materials, products, equipment, and systems incorporated or to be incorporated in such construction. In exception, excludes work to produce SD-01 submittals.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for information only. When used, a code following the "G" classification identifies the office that will review the submittal for the Government. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Submittal Register; G, R0

1.4 SUBMITTAL CLASSIFICATION

1.4.1 Government Approved (G)

Government approval is required for extensions of design, critical materials, variations, equipment whose compatibility with the entire system must be checked, and other items as designated by the Government.

Within the terms of the Contract Clause SPECIFICATIONS AND DRAWINGS FOR CONSTRUCTION, submittals are considered to be "shop drawings."

1.4.2 For Information Only

Submittals not requiring Government approval will be for information only. Within the terms of the Contract Clause SPECIFICATIONS AND DRAWINGS FOR CONSTRUCTION, they are not considered to be "shop drawings."

1.5 PREPARATION

1.5.1 Transmittal Form

Use ENG Form 4025-R transmittal form for submitting both Government-approved and information-only submittals. Submit in accordance with the instructions on the reverse side of the form. These forms or similar forms are included in the RMS CM software that the Contractor is required to use for this contract. Properly complete this form by filling out all the heading blank spaces and identifying each item submitted. Exercise special care to ensure proper listing of the specification paragraph and sheet number of the contract drawings pertinent to the data submitted for each item.

1.5.2 Submittal Format

1.5.2.1 Format of SD-01 Preconstruction Submittals

When the submittal includes a document that is to be used in the project, or is to become part of the project record, other than as a submittal, do not apply the Contractor's approval stamp to the document itself, but to a separate sheet accompanying the document.

Provide data in the unit of measure used in the contract documents.

1.5.2.2 Format for SD-02 Shop Drawings

Provide shop drawings not less than 8 1/2 by 11 inches nor more than 30 by 42 inches, except for full-size patterns or templates. Prepare drawings to accurate size, with scale indicated, unless another form is required. Ensure drawings are suitable for reproduction and of a quality to produce clear, distinct lines and letters, with dark lines on a white background.

- a. Include the nameplate data, size, and capacity on drawings. Also include applicable federal, military, industry, and technical society publication references.
- b. Dimension drawings, except diagrams and schematic drawings. Prepare drawings demonstrating interface with other trades to scale. Use the same unit of measure for shop drawings as indicated on the contract drawings. Identify materials and products for work shown.

Present shop drawings sized 8 1/2 by 11 inches as part of the bound volume for submittals. Present larger drawings in sets. Submit an electronic copy of drawings in PDF format and native electronic format.

1.5.2.2.1 Drawing Identification

Include on each drawing the drawing title, number, date, and revision numbers and dates, in addition to information required in paragraph IDENTIFYING SUBMITTALS.

Number drawings in a logical sequence. Each drawing is to bear the number of the submittal in a uniform location next to the title block. Place the Government contract number in the margin, immediately below the title block, for each drawing.

Reserve a blank space, no smaller than two inches on the right-hand side of each sheet for the Government disposition stamp.

1.5.2.3 Format of SD-03 Product Data

Present product data submittals for each section as a complete, bound volume. Include a table of contents, listing the page and catalog item numbers for product data.

Indicate, by prominent notation, each product that is being submitted; indicate the specification section number and paragraph number to which it pertains.

1.5.2.3.1 Product Information

Supplement product data with material prepared for the project to satisfy the submittal requirements where product data does not exist. Identify this material as developed specifically for the project, with information and format as required for submission of SD-07 Certificates.

Provide product data in units used in the Contract documents. Where product data are included in preprinted catalogs with another unit, submit the dimensions in contract document units, on a separate sheet.

1.5.2.3.2 Standards

Where equipment or materials are specified to conform to industry or technical-society reference standards of such organizations as the American National Standards Institute (ANSI), ASTM International (ASTM), National Electrical Manufacturer's Association (NEMA), Underwriters Laboratories (UL), or Association of Edison Illuminating Companies (AEIC), submit proof of such compliance. The label or listing by the specified organization will be acceptable evidence of compliance. In lieu of the label or listing, submit a certificate from an independent testing organization, competent to perform testing, and approved by the Contracting Officer. State on the certificate that the item has been tested in accordance with the specified organization's test methods and that the item complies with the specified organization's reference standard.

1.5.2.3.3 Data Submission

Collect required data submittals for each specific material, product, unit of work, or system into a single submittal that is marked for choices, options, and portions applicable to the submittal. Mark each copy of the product data identically. Partial submittals will be accepted for expedition of the construction effort.

Submit the manufacturer's instructions before installation.

1.5.2.4 Format of SD-04 Samples

1.5.2.4.1 Sample Characteristics

Furnish samples in the following sizes, unless otherwise specified or unless the manufacturer has prepackaged samples of approximately the same size as specified:

- a. Sample of Equipment or Device: Full size.
- b. Sample of Materials Less Than 2 by 3 inches: Built up to 8 1/2 by 11

inches.

- c. Sample of Materials Exceeding 8 1/2 by 11 inches: Cut down to 8 1/2 by 11 inches and adequate to indicate color, texture, and material variations.
- d. Sample of Linear Devices or Materials: 10 inch length or length to be supplied, if less than 10 inches. Examples of linear devices or materials are conduit and handrails.
- e. Sample Volume of Nonsolid Materials: Pint. Examples of nonsolid materials are sand and paint.
- f. Color Selection Samples: 2 by 4 inches. Where samples are specified for selection of color, finish, pattern, or texture, submit the full set of available choices for the material or product specified. Sizes and quantities of samples are to represent their respective standard unit.
- g. Sample Panel: 4 by 4 feet.
- h. Sample Installation: 100 square feet.

1.5.2.4.2 Sample Incorporation

Reusable Samples: Incorporate returned samples into work only if so specified or indicated. Incorporated samples are to be in undamaged condition at the time of use.

Recording of Sample Installation: Note and preserve the notation of any area constituting a sample installation, but remove the notation at the final clean-up of the project.

1.5.2.4.3 Comparison Sample

Samples Showing Range of Variation: Where variations in color, finish, pattern, or texture are unavoidable due to nature of the materials, submit sets of samples of not less than three units showing extremes and middle of range. Mark each unit to describe its relation to the range of the variation.

When color, texture, or pattern is specified by naming a particular manufacturer and style, include one sample of that manufacturer and style, for comparison.

1.5.2.5 Format of SD-05 Design Data

Provide design data and certificates on 8 1/2 by 11 inch paper.

1.5.2.6 Format of SD-06 Test Reports

Provide reports on 8 1/2 by 11 inch paper in a complete bound volume.

By prominent notation, indicate each report in the submittal. Indicate the specification number and paragraph number to which each report pertains.

1.5.2.7 Format of SD-07 Certificates

Provide design data and certificates on 8 1/2 by 11 inch paper.

1.5.2.8 Format of SD-08 Manufacturer's Instructions

Present manufacturer's instructions submittals for each section. Include the manufacturer's name, trade name, place of manufacture, and catalog model or number on product data. Also include applicable federal, military, industry, and technical-society publication references. If supplemental information is needed to clarify the manufacturer's data, submit it as specified for SD-07 Certificates.

Submit the manufacturer's instructions before installation.

1.5.2.8.1 Standards

Where equipment or materials are specified to conform to industry or technical-society reference standards of such organizations as the American National Standards Institute (ANSI), ASTM International (ASTM), National Electrical Manufacturer's Association (NEMA), Underwriters Laboratories (UL), or Association of Edison Illuminating Companies (AEIC), submit proof of such compliance. The label or listing by the specified organization will be acceptable evidence of compliance. In lieu of the label or listing, submit a certificate from an independent testing organization, competent to perform testing, and approved by the Contracting Officer. State on the certificate that the item has been tested in accordance with the specified organization's test methods and that the item complies with the specified organization's reference standard.

1.5.2.9 Format of SD-09 Manufacturer's Field Reports

Provide reports on 8 1/2 by 11 inch paper.

By prominent notation, indicate each report in the submittal. Indicate the specification number and paragraph number to which each report pertains.

1.5.2.10 Format of SD-10 Operation and Maintenance Data (O&M)

Comply with the requirements specified in Section 01 78 23 OPERATION AND MAINTENANCE DATA for O&M Data format.

1.5.2.11 Format of SD-11 Closeout Submittals

When the submittal includes a document that is to be used in the project or is to become part of the project record, other than as a submittal, do not apply the Contractor's approval stamp to the document itself, but to a separate sheet accompanying the document.

Provide data in the unit of measure used in the contract documents.

1.5.3 Source Drawings for Shop Drawings

1.5.3.1 Source Drawings

The entire set of source drawing files (DWG) will not be provided to the Contractor. Request the specific Drawing Number for the preparation of

shop drawings. Only those drawings requested to prepare shop drawings will be provided. These drawings are provided only after award.

1.5.3.2 Terms and Conditions

Data contained on these electronic files must not be used for any purpose other than as a convenience in the preparation of construction data for the referenced project. Any other use or reuse is at the sole risk of the Contractor and without liability or legal exposure to the Government. The Contractor must make no claim, and waives to the fullest extent permitted by law any claim or cause of action of any nature against the Government, its agents, or its subconsultants that may arise out of or in connection with the use of these electronic files. The Contractor must, to the fullest extent permitted by law, indemnify and hold the Government harmless against all damages, liabilities, or costs, including reasonable attorney's fees and defense costs, arising out of or resulting from the use of these electronic files.

These electronic source drawing files are not construction documents. Differences may exist between the source drawing files and the corresponding construction documents. The Government makes no representation regarding the accuracy or completeness of the electronic source drawing files, nor does it make representation to the compatibility of these files with the Contractor hardware or software. The Contractor is responsible for determining if any conflict exists. In the event that a conflict arises between the signed and sealed construction documents prepared by the Government and the furnished source drawing files, the signed and sealed construction documents govern. Use of these source drawing files does not relieve the Contractor of the duty to fully comply with the contract documents, including and without limitation the need to check, confirm and coordinate the work of all contractors for the project. If the Contractor uses, duplicates or modifies these electronic source drawing files for use in producing construction data related to this contract, remove all previous indication of ownership (seals, logos, signatures, initials and dates).

1.5.4 Electronic File Format

Provide submittals in electronic format, with the exception of material samples required for SD-04 Samples items. In addition to the electronic submittal, provide three hard copies of the submittals. Compile the submittal file as a single, complete document, to include the Transmittal Form described within, and also separately attach the native files which were used to create PDF. The attached files should include the original digital files used to create the submittal. Name the electronic submittal file specifically according to its contents, and coordinate the file naming convention with the Contracting Officer. Electronic files must be of sufficient quality that all information is legible. Use PDF as the electronic format, unless otherwise specified or directed by the Contracting Officer. Generate PDF files from original documents with bookmarks so that the text included in the PDF file is searchable and can be copied. If documents are scanned, optical character resolution (OCR) routines are required. Index and bookmark files exceeding 30 pages to allow efficient navigation of the file. When required, the electronic file must include a valid electronic signature or a scan of a signature.

E-mail electronic submittal documents smaller than 10MB to an e-mail address as directed by the Contracting Officer. Provide electronic documents over 10 MB on an optical disc or through an electronic file

sharing system such as the DOD SAFE Web Application located at the following website: <https://safe.apps.mil/>.

1.6 QUANTITY OF SUBMITTALS

1.6.1 Number of SD-01 Preconstruction Submittal Copies

Unless otherwise specified, submit two sets of administrative submittals.

1.6.2 Number of SD-02 Shop Drawing Copies

Submit six copies of submittals of shop drawings requiring review and approval by a QC organization. Submit seven copies of shop drawings requiring review and approval by the Contracting Officer.

1.6.3 Number of SD-03 Product Data Copies

Submit in compliance with quantity requirements specified for shop drawings.

1.6.4 Number of SD-04 Samples

- a. Submit two samples, or two sets of samples showing the range of variation, of each required item. One approved sample or set of samples will be retained by the approving authority and one will be returned to the Contractor.
- b. Submit one sample panel or provide one sample installation where directed. Include components listed in the technical section or as directed.
- c. Submit one sample installation, where directed.
- d. Submit one sample of nonsolid materials.

1.6.5 Number of SD-05 Design Data Copies

Submit in compliance with quantity requirements specified for shop drawings.

1.6.6 Number of SD-06 Test Report Copies

Submit in compliance with quantity and quality requirements specified for shop drawings, other than field test results that will be submitted with QC reports.

1.6.7 Number of SD-07 Certificate Copies

Submit in compliance with quantity requirements specified for shop drawings.

1.6.8 Number of SD-08 Manufacturer's Instructions Copies

Submit in compliance with quantity requirements specified for shop drawings.

1.6.9 Number of SD-09 Manufacturer's Field Report Copies

Submit in compliance with quantity and quality requirements specified for

shop drawings other than field test results that will be submitted with QC reports.

1.6.10 Number of SD-10 Operation and Maintenance Data Copies

Submit three copies of O&M data to the Contracting Officer for review and approval.

1.6.11 Number of SD-11 Closeout Submittals Copies

Unless otherwise specified, submit two sets of administrative submittals.

1.7 INFORMATION ONLY SUBMITTALS

Submittals without a "G" designation must be certified by the QC manager and submitted to the Contracting Officer for information-only. Provide information-only submittals to the Contracting Officer a minimum of 14 calendar days prior to the Preparatory Meeting for the associated Definable Feature of Work (DFOW). Approval of the Contracting Officer is not required on information only submittals. The Contracting Officer will mark "receipt acknowledged" on submittals for information and will return only the transmittal cover sheet to the Contractor. Normally, submittals for information only will not be returned. However, the Government reserves the right to return unsatisfactory submittals and require the Contractor to resubmit any item found not to comply with the contract. This does not relieve the Contractor from the obligation to furnish material conforming to the plans and specifications; will not prevent the Contracting Officer from requiring removal and replacement of nonconforming material incorporated in the work; and does not relieve the Contractor of the requirement to furnish samples for testing by the Government laboratory or for check testing by the Government in those instances where the technical specifications so prescribe.

1.8 PROJECT SUBMITTAL REGISTER

A sample Project Submittal Register showing items of equipment and materials for when submittals are required by the specifications is provided as at the end of this specification.

1.8.1 Submittal Management

Prepare and maintain a submittal register, as the work progresses. Do not change data that is output in columns (c), (d), (e), and (f) as delivered by Government; retain data that is output in columns (a), (g), (h), and (i) as approved. As an attachment, provide a submittal register showing items of equipment and materials for which submittals are required by the specifications. This list may not be all-inclusive and additional submittals may be required. Maintain a submittal register for the project in accordance with Section 01 45 00.15 10 RESIDENT MANAGEMENT SYSTEM CONTRACTOR MODE(RMS CM). The Government will provide the initial submittal register in electronic format with the following fields completed, to the extent that will be required by the Government during subsequent usage.

Column (c): Lists specification section in which submittal is required.

Column (d): Lists each submittal description (SD Number. and type, e.g., SD-02 Shop Drawings) required in each specification

section.

Column (e): Lists one principal paragraph in each specification section where a material or product is specified. This listing is only to facilitate locating submitted requirements. Do not consider entries in column (e) as limiting the project requirements.

Thereafter, the Contractor is to track all submittals by maintaining a complete list, including completion of all data columns and all dates on which submittals are received by and returned by the Government.

1.8.2 Preconstruction Use of Submittal Register

Submit the submittal register. Include the QC plan and the project schedule. Verify that all submittals required for the project are listed and add missing submittals. Coordinate and complete the following fields on the register submitted with the QC plan and the project schedule:

Column (a) Activity Number: Activity number from the project schedule.

Column (g) Contractor Submit Date: Scheduled date for the approving authority to receive submittals.

Column (h) Contractor Approval Date: Date that Contractor needs approval of submittal.

Column (i) Contractor Material: Date that Contractor needs material delivered to Contractor control.

1.8.3 Contractor Use of Submittal Register

Update the following fields in the Government-furnished submittal register program or equivalent fields in the program used by the Contractor with each submittal throughout the contract.

Column (b) Transmittal Number: List of consecutive, Contractor-assigned numbers.

Column (j) Action Code (k): Date of action used to record Contractor's review when forwarding submittals to QC.

Column (l) Date submittal transmitted.

Column (q) Date approval was received.

1.8.4 Approving Authority Use of Submittal Register

Update the following fields:

Column (b) Transmittal Number: List of consecutive, Contractor-assigned numbers.

Column (l) Date submittal was received.

Column (m) through (p) Dates of review actions.

Column (q) Date of return to Contractor.

1.8.5 Action Codes

1.8.5.1 Contractor Action Codes

DESIGN BID BUILD SUBMITTALS			
Submittal Classifications shown in UFGS Sections	Submittal Classification	Corresponding SpecsIntact Submittal Register Code which is populated in the SI Submittal Register. Software Limitations: (The software shows one character delineation in the SpecsIntact Submittal Register)	RMS - The following Submittal Classifications are populated in RMS when the SpecsIntact Submittal Data File is pulled into RMS)
G	Submittal requires Government Approval	G	GA
BLANK	Submittal is For Information Only (FIO)	BLANK	FIO
S	Submittal is for documentation of Sustainable requirements	S	S/FIO

1.8.6 Delivery of Copies

Submit an updated electronic copy of the submittal register to the Contracting Officer with each invoice request. Provide an updated Submittal Register monthly regardless of whether an invoice is submitted.

1.9 VARIATIONS

Variations from contract requirements require Contracting Officer approval pursuant to contract Clause FAR 52.236-21 Specifications and Drawings for Construction, and will be considered where advantageous to the Government.

1.9.1 Considering Variations

Discussion of variations with the Contracting Officer before submission will help ensure that functional and quality requirements are met and minimize rejections and resubmittals. For variations that include design changes or some material or product substitutions, the Government may require an evaluation and analysis by a licensed professional engineer hired by the contractor.

Specifically point out variations from contract requirements in a transmittal letter. Failure to point out variations may cause the Government to require rejection and removal of such work at no additional

cost to the Government.

1.9.2 Proposing Variations

Check the column "variation" of ENG Form 4025 for submittals that include variations proposed by the Contractor. Set forth in writing the reason for any variations and note such variations on the submittal. The Government reserves the right to rescind inadvertent approval of submittals containing unnoted variations.

1.9.3 Warranting that Variations are Compatible

When delivering a variation for approval, the Contractor warrants that this contract has been reviewed to establish that the variation, if incorporated, will be compatible with other elements of work.

1.9.4 Review Schedule Extension

In addition to the normal submittal review period, a period of 14 calendar days will be allowed for the Government to consider submittals with variations.

1.10 SCHEDULING

Schedule and submit concurrently product data and shop drawings covering component items forming a system or items that are interrelated. Submit pertinent certifications at the same time. No delay damages or time extensions will be allowed for time lost in late submittals. .

- a. Coordinate scheduling, sequencing, preparing, and processing of submittals with performance of work so that work will not be delayed by submittal processing. The Contractor is responsible for additional time required for Government reviews resulting from required resubmittals. The review period for each resubmittal is the same as for the initial submittal.
- b. Submittals required by the contract documents are listed on the submittal register. If a submittal is listed in the submittal register but does not pertain to the contract work, the Contractor is to include the submittal in the register and annotate it "N/A" with a brief explanation. Approval by the Contracting Officer does not relieve the Contractor of supplying submittals required by the contract documents but that have been omitted from the register or marked "N/A."
- c. Resubmit the submittal register and annotate it monthly with actual submission and approval dates. When all items on the register have been fully approved, no further resubmittal is required.

Contracting Officer review will be completed within 14 calendar days after the date of submission.

1.11 GOVERNMENT APPROVING AUTHORITY

When the approving authority is the Contracting Officer, the Government will:

- a. Note the date on which the submittal was received.
- b. Review submittals for approval within the scheduling period specified

and only for conformance with project design concepts and compliance with contract documents.

- c. Identify returned submittals with one of the actions defined in paragraph REVIEW NOTATIONS and with comments and markings appropriate for the action indicated.

Upon completion of review of submittals requiring Government approval, stamp and date submittals. Two copies of the submittal will be retained by the Contracting Officer and two copies of the submittal will be returned to the Contractor.

1.11.1 Review Notations

Submittals will be returned to the Contractor with the following notations:

- a. Submittals marked "approved" or "accepted" authorize proceeding with the work covered.
- b. Submittals marked "approved as noted" or "approved, except as noted, resubmittal not required," authorize proceeding with the work covered provided that the Contractor takes no exception to the corrections.
- c. Submittals marked "not approved," "disapproved," or "revise and resubmit" indicate incomplete submittal or noncompliance with the contract requirements or design concept. Resubmit with appropriate changes. Do not proceed with work for this item until the resubmittal is approved.
- d. Submittals marked "not reviewed" indicate that the submittal has been previously reviewed and approved, is not required, does not have evidence of being reviewed and approved by Contractor, or is not complete. A submittal marked "not reviewed" will be returned with an explanation of the reason it is not reviewed. Resubmit submittals returned for lack of review by Contractor or for being incomplete, with appropriate action, coordination, or change.
- e. Submittals marked "receipt acknowledged" indicate that submittals have been received by the Government. This applies only to "information-only submittals" as previously defined.

1.12 DISAPPROVED SUBMITTALS

Make corrections required by the Contracting Officer. If the Contractor considers any correction or notation on the returned submittals to constitute a change to the contract drawings or specifications, give notice to the Contracting Officer as required under the FAR clause titled CHANGES. The Contractor is responsible for the dimensions and design of connection details and the construction of work. Failure to point out variations may cause the Government to require rejection and removal of such work at the Contractor's expense.

If changes are necessary to submittals, make such revisions and resubmit in accordance with the procedures above. No item of work requiring a submittal change is to be accomplished until the changed submittals are approved.

1.13 APPROVED SUBMITTALS

The Contracting Officer's approval of submittals is not to be construed as a complete check, and indicates only that the general method of construction, materials, detailing and other information are satisfactory.

Approval or acceptance by the Government for a submittal does not relieve the Contractor of the responsibility for meeting the contract requirements or for any error that may exist, because under the Quality Control (QC) requirements of this contract, the Contractor is responsible for ensuring information contained within each submittal accurately conforms with the requirements of the contract documents.

After submittals have been approved or accepted by the Contracting Officer, no resubmittal for the purpose of substituting materials or equipment will be considered unless accompanied by an explanation of why a substitution is necessary.

1.14 APPROVED SAMPLES

Approval of a sample is only for the characteristics or use named in such approval and is not to be construed to change or modify any contract requirements. Before submitting samples, provide assurance that the materials or equipment will be available in quantities required in the project. No change or substitution will be permitted after a sample has been approved.

Match the approved samples for materials and equipment incorporated in the work. If requested, approved samples, including those that may be damaged in testing, will be returned to the Contractor, at its expense, upon completion of the contract. Unapproved samples will also be returned to the Contractor at its expense, if so requested.

Failure of any materials to pass the specified tests will be sufficient cause for refusal to consider, under this contract, any further samples of the same brand or make as that material. The Government reserves the right to disapprove any material or equipment that has previously proved unsatisfactory in service.

Samples of various materials or equipment delivered on the site or in place may be taken by the Contracting Officer for testing. Samples failing to meet contract requirements will automatically void previous approvals. Replace such materials or equipment to meet contract requirements.

1.15 WITHHOLDING OF PAYMENT

Payment for materials incorporated in the work will not be made if required approvals have not been obtained. No payment for materials incorporated in the work will be made if all required Designer of Record or required Government approvals have not been obtained. No payment will be made for any materials incorporated into the work for any conformance review submittals or information only submittals found to contain errors or deviations from the Solicitation or Accepted Proposal.

1.16 CERTIFICATION OF SUBMITTAL DATA

Certify the submittal data as follows on Form ENG 4025: "I certify that the above submitted items had been reviewed in detail and are correct and

in strict conformance with the contract drawings and specifications except as otherwise stated.

____NAME OF CONTRACTOR ____ SIGNATURE OF CONTRACTOR"

PART 2 PRODUCTS

Not Used

PART 3 EXECUTION

Not Used

-- End of Section --

DRAFT
NOT FOR CONSTRUCTION

SECTION 01 35 26

GOVERNMENTAL SAFETY REQUIREMENTS

11/20, CHG 4: 08/23

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN SOCIETY OF MECHANICAL ENGINEERS (ASME)

ASME B30.3	(2020) Tower Cranes
ASME B30.5	(2021) Mobile and Locomotive Cranes
ASME B30.7	(2021) Winches
ASME B30.8	(2020) Floating Cranes and Floating Derricks
ASME B30.9	(2018) Slings
ASME B30.20	(2018) Below-the-Hook Lifting Devices
ASME B30.22	(2023) Articulating Boom Cranes
ASME B30.23	(2022) Personnel Lifting Systems Safety Standard for Cableways, Cranes, Derricks, Hoists, Hooks, Jacks, and Slings
ASME B30.26	(2015; R 2020) Rigging Hardware

AMERICAN SOCIETY OF SAFETY PROFESSIONALS (ASSP)

ASSP A10.22	(2007; R 2017) Safety Requirements for Rope-Guided and Non-Guided Workers' Hoists
ASSP A10.34	(2021) Protection of the Public on or Adjacent to Construction Sites
ASSP A10.44	(2020) Control of Energy Sources (Lockout/Tagout) for Construction and Demolition Operations
ASSP Z244.1	(2016) The Control of Hazardous Energy Lockout, Tagout and Alternative Methods
ASSP Z359.0	(2018) Definitions and Nomenclature Used for Fall Protection and Fall Arrest
ASSP Z359.1	(2020) The Fall Protection Code
ASSP Z359.2	(2017) Minimum Requirements for a Comprehensive Managed Fall Protection

Program

ASSP Z359.3	(2019) Safety Requirements for Lanyards and Positioning Lanyards
ASSP Z359.4	(2013) Safety Requirements for Assisted-Rescue and Self-Rescue Systems, Subsystems and Components
ASSP Z359.6	(2016) Specifications and Design Requirements for Active Fall Protection Systems
ASSP Z359.7	(2019) Qualification and Verification Testing of Fall Protection Products
ASSP Z359.11	(2014) Safety Requirements for Full Body Harnesses
ASSP Z359.12	(2019) Connecting Components for Personal Fall Arrest Systems
ASSP Z359.13	(2013) Personal Energy Absorbers and Energy Absorbing Lanyards
ASSP Z359.14	(2014) Safety Requirements for Self-Retracting Devices for Personal Fall Arrest and Rescue Systems
ASSP Z359.15	(2014) Safety Requirements for Single Anchor Lifelines and Fall Arresters for Personal Fall Arrest Systems
ASSP Z359.16	(2016) Safety Requirements for Climbing Ladder Fall Arrest Systems
ASSP Z359.18	(2017) Safety Requirements for Anchorage Connectors for Active Fall Protection Systems

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 10	(2022; ERTA 1 2021) Standard for Portable Fire Extinguishers
NFPA 51B	(2024) Standard for Fire Prevention During Welding, Cutting, and Other Hot Work
NFPA 70	(2023) National Electrical Code
NFPA 70E	(2024) Standard for Electrical Safety in the Workplace
NFPA 241	(2022) Standard for Safeguarding Construction, Alteration, and Demolition Operations

TELECOMMUNICATIONS INDUSTRY ASSOCIATION (TIA)

TIA-222	(2018H; Add 1 2019) Structural Standard for Antenna Supporting Structures and Antennas and Small Wind Turbine Support Structures
TIA-1019	(2012; R 2016) Standard for Installation, Alteration and Maintenance of Antenna Supporting Structures and Antennas

U.S. ARMY CORPS OF ENGINEERS (USACE)

EM 385-1-1	(2024) Safety -- Safety and Occupational Health (SOH) Requirements
------------	--

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

29 CFR 1910	Occupational Safety and Health Standards
29 CFR 1910.147	The Control of Hazardous Energy (Lock Out/Tag Out)
29 CFR 1910.333	Selection and Use of Work Practices
29 CFR 1915.89	Control of Hazardous Energy (Lockout/Tags-Plus)
29 CFR 1926	Safety and Health Regulations for Construction
29 CFR 1926.16	Rules of Construction
29 CFR 1926.552	Material Hoists, Personal Hoists, and Elevators
29 CFR 1926.553	Base-Mounted Drum Hoists
29 CFR 1926.1400	Cranes and Derricks in Construction
CPL 02-01-056	(2014) Inspection Procedures for Accessing Communication Towers by Hoist

1.2 DEFINITIONS

1.2.1 Competent Person (CP)

The CP is a person designated in writing, who, through training, knowledge and experience, is capable of identifying, evaluating, and addressing existing and predictable hazards in the working environment or working conditions that are dangerous to personnel, and who has authorization to take prompt corrective measures with regards to such hazards.

1.2.2 Competent Person, Cranes and Rigging

The CP, Cranes and Rigging, as defined in EM 385-1-1 Appendix Q, is a person meeting the competent person requirements, who has been designated in writing to be responsible for the immediate supervision, implementation and monitoring of the Crane and Rigging Program, who through training,

knowledge and experience in crane and rigging is capable of identifying, evaluating and addressing existing and potential hazards and, who has the authority to take prompt corrective measures with regard to such hazards.

1.2.3 Competent Person, Excavation/Trenching

A CP, Excavation/Trenching, is a person meeting the competent person requirements as defined in EM 385-1-1 Appendix Q and 29 CFR 1926, who has been designated in writing to be responsible for the immediate supervision, implementation and monitoring of the excavation/trenching program, who through training, knowledge and experience in excavation/trenching is capable of identifying, evaluating and addressing existing and potential hazards and, who has the authority to take prompt corrective measures with regard to such hazards.

1.2.4 Competent Person (CP) Trainer

A competent person trainer as defined in EM 385-1-1 Appendix Q, who is qualified in the training material presented, and who possesses a working knowledge of applicable technical regulations, standards, equipment and systems related to the subject matter on which they are training Competent Persons. A competent person trainer must be familiar with the typical hazards and the equipment used in the industry they are instructing. The training provided by the competent person trainer must be appropriate to that specific industry. The competent person trainer must evaluate the knowledge and skills of the competent persons as part of the training process.

1.2.5 High Risk Activities

High Risk Activities are activities that involve work at heights, crane and rigging, excavations and trenching, scaffolding, electrical work, and confined space entry.

1.2.6 High Visibility Accident

A High Visibility Accident is any mishap which may generate publicity or high visibility.

1.2.7 Load Handling Equipment (LHE)

LHE is a term used to describe cranes, hoists and all other hoisting equipment (hoisting equipment means equipment, including crane, derricks, hoists and power operated equipment used with rigging to raise, lower or horizontally move a load).

1.2.8 Medical Treatment

Medical Treatment is treatment administered by a physician or by registered professional personnel under the standing orders of a physician. Medical treatment does not include first aid treatment even when provided by a physician or registered personnel.

1.2.9 Near Miss

A Near Miss is a mishap resulting in no personal injury and zero property damage, but given a shift in time or position, damage or injury may have occurred (e.g., a worker falls off a scaffold and is not injured; a crane swings around to move the load and narrowly misses a parked vehicle).

1.2.10 Operating Envelope

The Operating Envelope is the area surrounding any crane or load handling equipment. Inside this "envelope" is the crane, the operator, riggers and crane walkers, other personnel involved in the operation, rigging gear between the hook, the load, the crane's supporting structure (i.e. ground or rail), the load's rigging path, the lift and rigging procedure.

1.2.11 Qualified Person (QP)

The QP is a person designated in writing, who, by possession of a recognized degree, certificate, or professional standing, or extensive knowledge, training, and experience, has successfully demonstrated their ability to solve or resolve problems related to the subject matter, the work, or the project.

1.2.12 Recordable Injuries or Illnesses

Recordable Injuries or Illnesses are any work-related injury or illness that results in:

- a. Death, regardless of the time between the injury and death, or the length of the illness;
- b. Days away from work (any time lost after day of injury/illness onset);
- c. Restricted work;
- d. Transfer to another job;
- e. Medical treatment beyond first aid;
- f. Loss of consciousness; or
- g. A significant injury or illness diagnosed by a physician or other licensed health care professional, even if it did not result in (a) through (f) above

1.2.13 Government Property and Equipment

Interpret "USACE" property and equipment specified in USACE EM 385-1-1 as Government property and equipment.

1.2.14 Load Handling Equipment (LHE) Accident or Load Handling Equipment Mishap

A LHE accident occurs when any one or more of the eight elements in the operating envelope fails to perform correctly during operation, including operation during maintenance or testing resulting in personnel injury or death; material or equipment damage; dropped load; derailment; two-blocking; overload; or collision, including unplanned contact between the load, crane, or other objects. A dropped load, derailment, two-blocking, overload and collision are considered accidents, even though no material damage or injury occurs. A component failure (e.g., motor burnout, gear tooth failure, bearing failure) is not considered an accident solely due to material or equipment damage unless the component failure results in damage to other components (e.g., dropped boom, dropped load, or roll over). Document an LHE mishap using the Crane High Hazard

working group mishap reporting form.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for information only. When used, a code following the "G" classification identifies the office that will review the submittal for the Government. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Accident Prevention Plan (APP); G, R0

APP - Construction; G, R0

Dive Operations Plan; G, R0

Severe Storm Plan

SD-06 Test Reports

Monthly Exposure Reports

Notifications and Reports

Accident Reports; G, R0

LHE Inspection Reports

SD-07 Certificates

Crane Operators/Riggers

Standard Lift Plan; G, R0

Critical Lift Plan; G, R0

Naval Architecture Analysis; G,R0

Activity Hazard Analysis (AHA)

Certificate of Compliance

1.4 MONTHLY EXPOSURE REPORTS

Provide a Monthly Exposure Report and attach to the monthly billing request. This report is a compilation of employee-hours worked each month for all site workers, both Prime and subcontractor. Failure to submit the report may result in retention of up to 10 percent of the voucher.

1.5 REGULATORY REQUIREMENTS

In addition to the detailed requirements included in the provisions of this Contract, comply with the most recent edition of USACE EM 385-1-1, and the following federal, state, and local laws, ordinances, criteria, rules and regulations. Submit matters of interpretation of standards to the appropriate administrative agency for resolution before starting

work. Where the requirements of this specification, applicable laws, criteria, ordinances, regulations, and referenced documents vary, the most stringent requirements govern.

1.6 ACTIVE LAUNCH AND HAZARDOUS OPERATIONS RANGE

The location of work for this contract at Wallops Flight Facility is on an active launch and hazardous operations range, many operations which directly impact part of or the entire project area. NASA will alert the Contractor and COR in advance of operations that may impact the work area and describe the constraints associated with each operation. Impacts can range from 1 hour to a full day in duration. In some cases, operations have contingency days which are used and constraints will remain in place for an entire window until an operation is executed. For all hazardous operations, personnel will be required to either move outside a specified area or vacate the island entirely. Equipment and materials may remain in a hazardous area during an operation, however personnel must move to a designated area (provided by NASA POC). The Contractor will be compensated for down time associated with hazardous operations, specific to the work that was compromised.

Offshore activities (i.e.-dredge work) may also be impacted by range operations. Manned vessels must be moved to a safe area. Notice to Mariners (NOTMAR) are issued ahead of range operations and for this contract, the NASA POC will assign a NASA Range POC for marine vessels to contact ahead of an operation. NASA will provide a plan on a per-operation basis to the Contractor for both land and marine impacts, with a list of contacts and instructions for a specific operation.

1.7 SITE QUALIFICATIONS, DUTIES, AND MEETINGS

1.7.1 Personnel Qualifications

1.7.1.1 Site Safety and Health Officer (SSHO)

Provide an SSHO that meets the requirements of EM 385-1-1 Section 1. The SSHO must ensure that the requirements of 29 CFR 1926.16 are met for the project. Provide a Safety oversight team that includes a minimum of one person at each project site to function as the Site Safety and Health Officer (SSHO). The SSHO or an equally-qualified Alternate SSHO must be at the work site at all times to implement and administer the Contractor's safety program and Government-accepted Accident Prevention Plan. The SSHO and Alternate SSHO must have the required training, experience, and qualifications in accordance with EM 385-1-1 Section 01.A.17, and all associated sub-paragraphs.

If the SSHO is off-site for a period longer than 24 hours, an equally-qualified alternate SSHO must be provided and must fulfill the same roles and responsibilities as the primary SSHO. When the SSHO is temporarily (up to 24 hours) off-site, a Designated Representative (DR), as identified in the AHA may be used in lieu of an Alternate SSHO, and must be on the project site at all times when work is being performed. Note that the DR is a collateral duty safety position, with safety duties in addition to their full time occupation.

1.7.1.1.1 Additional Site Safety and Health Officer (SSHO) Requirements and Duties

The SSHO may not serve as the Quality Control Manager. The SSHO may not

serve as the Superintendent.

1.7.1.2 Competent Person Qualifications

Provide Competent Persons in accordance with EM 385-1-1, Appendix Q and herein. Competent Persons for high risk activities include confined space, cranes and rigging, excavation/trenching, fall protection, and electrical work. The CP for these activities must be designated in writing, and meet the requirements for the specific activity (i.e. competent person, fall protection).

The Competent Person identified in the Contractor's Safety and Health Program and accepted Accident Prevention Plan, must be on-site at all times when the work that presents the hazards associated with their professional expertise is being performed. Provide the credentials of the Competent Persons(s) to the Contracting Officer for information in consultation with the Safety Office.

1.7.1.3 Qualified Trainer Requirements

Individuals qualified to instruct the 40 hour contract safety awareness course, or portions thereof, must meet the definition of a Competent Person Trainer, and, at a minimum, possess a working knowledge of the following subject areas: EM 385-1-1, Electrical Standards, Lockout/Tagout, Fall Protection, Confined Space Entry for Construction; Excavation, Trenching and Soil Mechanics, and Scaffolds in accordance with 29 CFR 1926.450, Subpart L.

Instructors are required to:

- a. Prepare class presentations that cover construction-related safety requirements.
- b. Ensure that all attendees attend all sessions by using a class roster signed daily by each attendee. Maintain copies of the roster for at least five years. This is a certification class and must be attended 100 percent. In cases of emergency where an attendee cannot make it to a session, the attendee can make it up in another class session for the same subject.
- c. Update training course materials whenever an update of the EM 385-1-1 becomes available.
- d. Provide a written exam of at least 50 questions. Students are required to answer 80 percent correctly to pass.
- e. Request, review and incorporate student feedback into a continuous course improvement program.

1.7.1.4 Dredging Contract Requirements

1.7.1.4.1 Dredging Safety Personnel Requirements

- a. Provide a minimum of one full time SSHO assigned per project site for the primary working shift.
- b. For a project involving multiple work shifts, provide one full-time SSHO for each additional shift.

- c. For individual dredging projects or sites with a dredge crew and fill crew on watch of eight employees or less, a CDSO must be appointed, instead of an SSHO. The CDSO assumes the same responsibilities as a full-time SSHO.
- d. An example of one dredging project site is reflected in each of the following:
 - (1) a mechanical dredge, tug(s) and scow(s), scow route, and material placement site; or
 - (2) a hydraulic pipeline dredge, attendant plant, and material placement site; or,
 - (3) a hopper dredge (include land-based material placement site - if applicable.)
- e. For Hopper Dredges with the U.S. Coast Guard, documented crews may designate an officer as a Collateral Duty Safety Officer (CDSO) instead of having a full-time SSHO onboard if the officer meets the SSHO training and experience requirements.

1.7.1.4.2 SSHO Requirements for Dredging

- a. In addition to requirements stated elsewhere in this specification, an individual serving as a SSHO must be present at the project site, located so that they have full mobility and reasonable access to all major work operations, for at least one shift in each 24 hour period when work is being performed. The SSHO must be available during their shift for immediate verbal consultation and notification, either by phone or radio.
- b. The SSHO is a full-time, dedicated position, except as noted above, who must report to a senior project (or corporate) official. When the SSHO is permitted to be a collateral duty, the SSHO is not permitted to be in another position requiring continuous mechanical or equipment operations, such as equipment operators.
- c. The SSHO must inspect all work areas and operations during initial set-up and at least monthly observe and provide personal oversight on each shift during dredging operations for projects with many work sites, more often for those with less work sites.

1.7.1.4.3 Collateral Duty Safety Officer (CDSO) Requirements for Dredging

- a. A CDSO is an individual who is assigned collateral duty safety responsibilities in addition to their full-time occupation, and who supports and supplements the SSHO efforts in managing, implementing and enforcing the Contractor's Safety and Health Program. The assigned CDSO must be an individual(s) with work oversight responsibilities, such as master, mate, fill foreman, or superintendent. A CDSO must not be an employee responsible for continuous mechanical or equipment operations, such as an equipment operator.
- b. A CDSO performs safety program tasks as assigned by the SSHO and must report safety findings to the SSHO. The SSHO must document results of safety findings and provide information for inclusion in the CQC reports to the Contracting Officer.

1.7.1.4.4 Safety Personnel Training Requirements for Dredging

A SSHO and a CDSO for dredging Contracts must take either a formal classroom or online OSHA 30-hour Construction Safety Course, or an equivalent 30 hours of formal classroom or online safety and health training covering the subjects of the OSHA 30-hour Course in accordance with EM 385-1-1 Appendix A, paragraph 3.d.(3), applicable to dredging work, and given by qualified instructors. In exception to EM 385-1-1, Section 01.A.17, comply with the following:

- a. The SSHO must maintain competency through having taken 8 hours of formal classroom or online safety and health related coursework every year. Hours spent as an instructor in such courses will be considered the same as attending them, but each course only gets credit once (for example, instructing a 1-hour asbestos awareness course five times in a year provides one hour credit for training).
- b. The SSHO and a CDSO must have a minimum of three years of experience within the past five years in one of the following:
 - (1) Supervising/managing dredging activities
 - (2) Supervising/managing marine construction activities
 - (3) Supervising/managing land-based construction activities
 - (4) Work managing safety programs or processes
 - (5) Conducting hazard analyses and developing controls in activities or environments with similar hazards

1.7.1.5 Crane Operators/Riggers

Provide Operators, Signal Persons, and Riggers meeting the requirements in EM 385-1-1, Section 15.B for Riggers and Section 16.B for Crane Operators and Signal Persons. In addition, for mobile cranes with Original Equipment Manufacturer (OEM) rated capacities of 50,000 pounds or greater, designate crane operators qualified by a source that qualifies crane operators (i.e., union, a Government agency, or an organization that tests and qualifies crane operators). Provide proof of current qualification.

1.7.2 Personnel Duties

1.7.2.1 Duties of the Site Safety and Health Officer (SSHO)

The SSHO must:

- a. Conduct daily safety and health inspections and maintain a written log which includes area/operation inspected, date of inspection, identified hazards, recommended corrective actions, estimated and actual dates of corrections. Attach safety inspection logs to the Contractors' daily production report.
- b. Conduct mishap investigations and complete required accident reports. Report mishaps and near misses.
- c. Use and maintain OSHA's Form 300 to log work-related injuries and illnesses occurring on the project site for Prime Contractors and

subcontractors, and make available to the Contracting Officer upon request. Post and maintain the Form 300A on the site Safety Bulletin Board.

- d. Maintain applicable safety reference material on the job site.
- e. Attend the pre-construction conference, pre-work meetings including preparatory meetings, and periodic in-progress meetings.
- f. Review the APP and AHAs for compliance with EM 385-1-1, and approve, sign, implement and enforce them.
- g. Establish a Safety and Occupational Health (SOH) Deficiency Tracking System that lists and monitors outstanding deficiencies until resolution.
- h. Ensure subcontractor compliance with safety and health requirements.
- i. Maintain a list of hazardous chemicals on site and their material Safety Data Sheets (SDS).
- j. Maintain a weekly list of high hazard activities involving energy, equipment, excavation, entry into confined space, and elevation, and be prepared to discuss details during QC Meetings.
- k. Provide and keep a record of site safety orientation and indoctrination for Contractor employees, subcontractor employees, and site visitors.

Superintendent, QC Manager, and SSHO are subject to dismissal if the above or any other required duties are not being effectively carried out. If either the Superintendent, QC Manager, or SSHO are dismissed, project work will be stopped and will not be allowed to resume until a suitable replacement is approved and the above duties are again being effectively carried out.

1.7.3 Meetings

1.7.3.1 Preconstruction Conference

- a. Contractor representatives who have a responsibility or significant role in accident prevention on the project must attend the preconstruction conference. This includes the project superintendent, Site Safety and Occupational Health Officer, quality control manager, or any other assigned safety and health professionals who participated in the development of the APP (including the Activity Hazard Analyses (AHAs) and special plans, program and procedures associated with it).
- b. Discuss the details of the submitted APP to include incorporated plans, programs, procedures and a listing of anticipated AHAs that will be developed and implemented during the performance of the Contract. This list of proposed AHAs will be reviewed and an agreement will be reached between the Contractor and the Contracting Officer as to which phases will require an analysis. In addition, establish a schedule for the preparation, submittal, and Government review of AHAs to preclude project delays.
- c. Deficiencies in the submitted APP, identified during the Contracting Officer's review, must be corrected, and the APP re-submitted for

review prior to the start of construction. Work is not permitted to begin until an APP is established that is acceptable to the Contracting Officer.

1.7.3.2 Safety Meetings

Conduct safety meetings to review past activities, plan for new or changed operations, review pertinent aspects of appropriate AHA (by trade), establish safe working procedures for anticipated hazards, and provide pertinent Safety and Occupational Health (SOH) training and motivation. Conduct meetings at least once a month for all supervisors at the project location. The SSHO, supervisors, foremen, or CDSOs must conduct meetings at least once a week for the trade workers. Document meeting minutes to include the date, persons in attendance, subjects discussed, and names of individual(s) who conducted the meeting. Maintain documentation on-site and furnish copies to the Contracting Officer on request. Notify the Contracting Officer of all scheduled meetings 7 calendar days in advance.

1.8 ACCIDENT PREVENTION PLAN (APP)

1.8.1 APP - Construction

A qualified person must prepare the written site-specific APP. Prepare the APP in accordance with the format and requirements of EM 385-1-1, Appendix A, and as supplemented herein. Cover all paragraph and subparagraph elements in EM 385-1-1, Appendix A. The APP must be job-specific and address any unusual or unique aspects of the project or activity for which it is written. The APP must interface with the Contractor's overall safety and health program referenced in the APP in the applicable APP element, and made site-specific. Describe the methods to evaluate past safety performance of potential subcontractors in the selection process. Also, describe innovative methods used to ensure and monitor safe work practices of subcontractors. The Government considers the Prime Contractor to be the "controlling authority" for all work site safety and health of the subcontractors. Contractors are responsible for informing their subcontractors of the safety provisions under the terms of the Contract and the penalties for noncompliance, coordinating the work to prevent one craft from interfering with or creating hazardous working conditions for other crafts, and inspecting subcontractor operations to ensure that accident prevention responsibilities are being carried out. The APP must be signed by an officer of the firm (Prime Contractor senior person), the individual preparing the APP, the on-site superintendent, the designated SSHO, the Contractor Quality Control Manager, and any designated Certified Safety Professional (CSP) or Certified Health Physicist (CIH). The SSHO must provide and maintain the APP and a log of signatures by each subcontractor foreman, attesting that they have read and understand the APP, and make the APP and log available on-site to the Contracting Officer. If English is not the foreman's primary language, the Prime Contractor must provide an interpreter.

Submit the APP to the Contracting Officer and NASA within 30 calendar days of Contract award and not less than 10 calendar days prior to the date of the preconstruction conference for acceptance. Work cannot proceed without an accepted APP. Once reviewed and accepted by the Contracting Officer and NASA, the APP and attachments will be enforced as part of the Contract. Disregarding the provisions of this Contract or the accepted APP is cause for stopping of work, at the discretion of the Contracting Officer, until the matter has been rectified. Continuously review and amend the APP, as necessary, throughout the life of the Contract. Changes

to the accepted APP must be made with the knowledge and concurrence of the Contracting Officer, project superintendent, SSHO and Quality Control Manager. Incorporate unusual or high-hazard activities not identified in the original APP as they are discovered. Should any severe hazard exposure (i.e. imminent danger) become evident, stop work in the area, secure the area, and develop a plan to remove the exposure and control the hazard. Notify the Contracting Officer within 24 hours of discovery. Eliminate and remove the hazard. In the interim, take all necessary action to restore and maintain safe working conditions in order to safeguard onsite personnel, visitors, the public (as defined by ASSP A10.34), and the environment.

After hours and emergency contacts are listed in 01 14 00 WORK RESTRICTIONS. Any changes to these contacts will be provided following review of the APP.

1.8.2 Names and Qualifications

Provide plans in accordance with the requirements outlined in Appendix A of EM 385-1-1, including the following:

- a. Names and qualifications (resumes including education, training, experience and certifications) of site safety and health personnel designated to perform work on this project to include the designated Site Safety and Health Officer and other competent and qualified personnel to be used. Specify the duties of each position.
- b. Qualifications of competent and of qualified persons. As a minimum, designate and submit qualifications of competent persons for each of the following major areas: excavation; scaffolding; fall protection; hazardous energy; confined space; health hazard recognition, evaluation and control of chemical, physical and biological agents; and personal protective equipment and clothing to include selection, use and maintenance.

1.8.3 Plans

Provide plans in the APP in accordance with the requirements outlined in Appendix A of EM 385-1-1, including the following:

1.8.3.1 Standard Lift Plan (SLP)

Plan lifts to avoid situations where the operator cannot maintain safe control of the lift. Prepare a written SLP in accordance with EM 385-1-1, Section 16.A.03, using Form 16-2 for every lift or series of lifts (if duty cycle or routine lifts are being performed). The SLP must be developed, reviewed and accepted by all personnel involved in the lift in conjunction with the associated AHA. Signature on the AHA constitutes acceptance of the plan. Maintain the SLP on the LHE for the current lift(s) being made. Maintain historical SLPs for a minimum of three months.

1.8.3.2 Critical Lift Plan - Crane or Load Handling Equipment

Provide a Critical Lift Plan as required by EM 385-1-1, Section 16.H.01, using Form 16-3. In addition, Critical Lift Plans are required for the following:

- a. Lifts over 50 percent of the capacity of barge mounted mobile crane's

hoist.

- b. When working around energized power lines where the work will get closer than the minimum clearance distance in EM 385-1-1 Table 16-1.
- c. For lifts with anticipated binding conditions.
- d. When erecting cranes.

1.8.3.2.1 Critical Lift Plan Planning and Schedule

Critical lifts require detailed planning and additional or unusual safety precautions. Develop and submit a critical lift plan to the Contracting Officer 30 calendar days prior to critical lift. Comply with load testing requirements in accordance with EM 385-1-1, Section 16.F.03.

1.8.3.2.2 Lifts of Personnel

In addition to the requirements of EM 385-1-1, Section 16.H.02, for lifts of personnel, demonstrate compliance with the requirements of 29 CFR 1926.1400 and EM 385-1-1, Section 16.T.

1.8.3.3 Barge Mounted Mobile Crane Lift Plan

Provide a Naval Architecture Analysis and include an LHE Manufacturer's Floating Service Load Chart in accordance with EM 385-1-1, Section 16.L.03.

1.8.3.4 Multi-Purpose Machines, Material Handling Equipment, and Construction Equipment Lift Plan

Multi-purpose machines, material handling equipment, and construction equipment used to lift loads that are suspended by rigging gear, require proof of authorization from the machine OEM that the machine is capable of making lifts of loads suspended by rigging equipment. Written approval from a qualified registered professional engineer, after a safety analysis is performed, is allowed in lieu of the OEM's approval. Demonstrate that the operator is properly trained and that the equipment is properly configured to make such lifts and is equipped with a load chart.

1.8.3.5 Fall Protection and Prevention (FP&P) Plan

The plan must be in accordance with the requirements of EM 385-1-1, Section 21.D and ASSP Z359.2, be site specific, and address all fall hazards in the work place and during different phases of construction. Address how to protect and prevent workers from falling to lower levels when they are exposed to fall hazards above 6 feet. A competent person or qualified person for fall protection must prepare and sign the plan documentation. Include fall protection and prevention systems, equipment and methods employed for every phase of work, roles and responsibilities, assisted rescue, self-rescue and evacuation procedures, training requirements, and monitoring methods. Review and revise, as necessary, the Fall Protection and Prevention Plan documentation as conditions change, but at a minimum every six months, for lengthy projects, reflecting any changes during the course of construction due to changes in personnel, equipment, systems or work habits. Keep and maintain the accepted Fall Protection and Prevention Plan documentation at the job site for the duration of the project. Include the Fall Protection and Prevention Plan documentation in the Accident Prevention Plan (APP).

1.8.3.6 Rescue and Evacuation Plan

Provide a Rescue and Evacuation Plan in accordance with EM 385-1-1 Section 21.N and ASSP Z359.2, and include in the FP&P Plan and as part of the APP. Include a detailed discussion of the following: methods of rescue; methods of self-rescue; equipment used; training requirement; specialized training for the rescuers; procedures for requesting rescue and medical assistance; and transportation routes to a medical facility.

1.8.3.7 Hazardous Energy Control Program (HECP)

Develop a HECP in accordance with EM 385-1-1 Section 12, 29 CFR 1910.147, 29 CFR 1910.333, 29 CFR 1915.89, ASSP Z244.1, and ASSP A10.44. Submit this HECP as part of the Accident Prevention Plan (APP). Conduct a preparatory meeting and inspection with all effected personnel to coordinate all HECP activities. Document this meeting and inspection in accordance with EM 385-1-1, Section 12.A.02. Ensure that each employee is familiar with and complies with these procedures.

1.8.3.8 Excavation Plan

Identify the safety and health aspects of excavation, and provide and prepare the plan in accordance with EM 385-1-1, Section 25.A.

1.9 ACTIVITY HAZARD ANALYSIS (AHA)

Before beginning each activity, task or Definable Feature of Work (DFOW) involving a type of work presenting hazards not experienced in previous project operations, or where a new work crew or subcontractor is to perform the work, the Contractor(s) performing that work activity must prepare an AHA. AHAs must be developed by the Prime Contractor, subcontractor, or supplier performing the work, and provided for Prime Contractor review and approval before submitting to the Contracting Officer. AHAs must be signed by the SSHO, Superintendent, QC Manager and the subcontractor Foreman performing the work. Format the AHA in accordance with EM 385-1-1, Section 1 or as directed by the Contracting Officer. Submit the AHA for review at least 15 working days prior to the start of each activity task, or DFOW. The Government reserves the right to require the Contractor to revise and resubmit the AHA if it fails to effectively identify the work sequences, specific anticipated hazards, site conditions, equipment, materials, personnel and the control measures to be implemented.

AHAs must identify competent persons required for phases involving high risk activities, including confined entry, crane and rigging, excavations, trenching, electrical work, fall protection, and scaffolding.

1.9.1 AHA Management

Review the AHA list periodically (at least monthly) at the Contractor supervisory safety meeting, and update as necessary when procedures, scheduling, or hazards change. Use the AHA during daily inspections by the SSHO to ensure the implementation and effectiveness of the required safety and health controls for that work activity.

1.9.2 AHA Signature Log

Each employee performing work as part of an activity, task or DFOW must review the AHA for that work and sign a signature log specifically

maintained for that AHA prior to starting work on that activity. The SSHO must maintain a signature log on site for every AHA. Provide employees whose primary language is other than English, with an interpreter to ensure a clear understanding of the AHA and its contents.

1.10 DISPLAY OF SAFETY INFORMATION

1.10.1 Safety Bulletin Board

Prior to commencement of work, erect a safety bulletin board at the job site. Where size, duration, or logistics of project do not facilitate a bulletin board, an alternative method, acceptable to the Contracting Officer, that is accessible and includes all mandatory information for employee and visitor review, may be deemed as meeting the requirement for a bulletin board. Include and maintain information on safety bulletin board as required by EM 385-1-1, Section 01.A.07.

1.10.2 Safety and Occupational Health (SOH) Deficiency Tracking System

Establish a SOH deficiency tracking system that lists and monitors the status of SOH deficiencies in chronological order. Use the tracking system to evaluate the effectiveness of the APP. A monthly evaluation of the data must be discussed in the QC or SOH meeting with everyone on the project. The list must be posted on the project bulletin board and updated daily, and provide the following information:

- a. Date deficiency identified;
- b. Description of deficiency;
- c. Name of person responsible for correcting deficiency;
- d. Projected resolution date;
- e. Date actually resolved.

1.11 SITE SAFETY REFERENCE MATERIALS

Maintain safety-related references applicable to the project, including those listed in paragraph REFERENCES. Maintain applicable equipment manufacturer's manuals.

1.12 EMERGENCY MEDICAL TREATMENT

Contractors must arrange for their own emergency medical treatment in accordance with EM 385-1-1. Government has no responsibility to provide emergency medical treatment.

1.13 NOTIFICATIONS and REPORTS

1.13.1 Mishap Notification

Notify the Contracting Officer as soon as practical, but no more than twenty-four hours, after any mishaps, including recordable accidents, incidents, and near misses, as defined in EM 385-1-1 Appendix Q, any report of injury, illness, or any property damage. For LHE or rigging mishaps, notify the Contracting Officer as soon as practical but not more than four hours after mishap. The Contractor is responsible for obtaining appropriate medical and emergency assistance and for notifying fire, law

enforcement, and regulatory agencies. Immediate reporting is required for electrical mishaps, to include Arc Flash; shock; uncontrolled release of hazardous energy (includes electrical and non-electrical); load handling equipment or rigging; fall from height (any level other than same surface); and underwater diving. These mishaps must be investigated in depth to identify all causes and to recommend hazard control measures.

Within notification include Contractor name; Contract title; type of Contract; name of activity, installation or location where accident occurred; date and time of accident; names of personnel injured; extent of property damage, if any; extent of injury, if known, and brief description of accident (for example, type of construction equipment used and PPE used). Preserve the conditions and evidence on the accident site until the Government investigation team arrives on-site and Government investigation is conducted. Assist and cooperate fully with the Government's investigation(s) of any mishap.

1.13.2 Accident Reports

- a. Conduct an accident investigation for recordable injuries and illnesses, property damage, and near misses as defined in EM 385-1-1, to establish the root cause(s) of the accident. Complete the applicable USACE Accident Report Form 3394, and provide the report to the Contracting Officer within 5 calendar days of the accident. The Contracting Officer will provide copies of any required or special forms.
- b. Near Misses: For Army projects, report all "Near Misses" to the GDA, using local mishap reporting procedures, within 24 hrs. The Contracting Officer will provide the Contractor the required forms. Near miss reports are considered positive and proactive Contractor safety management actions.
- c. Conduct an accident investigation for any load handling equipment accident (including rigging accidents) to establish the root cause(s) of the accident. Complete the LHE Accident Report (Crane and Rigging Accident Report) form and provide the report to the Contracting Officer within 30 calendar days of the accident. Do not proceed with crane operations until cause is determined and corrective actions have been implemented to the satisfaction of the Contracting Officer. The Contracting Officer will provide a blank copy of the accident report form.

1.13.3 LHE Inspection Reports

Submit LHE inspection reports required in accordance with EM 385-1-1 and as specified herein with Daily Reports of Inspections.

1.13.4 Certificate of Compliance and Pre-lift Plan/Checklist for LHE and Rigging

Provide a FORM 16-1 Certificate of Compliance for LHE entering an activity under this Contract and in accordance with EM 385-1-1. Post certifications on the crane.

Develop a Standard Lift Plan (SLP) in accordance with EM 385-1-1, Section 16.H.03 using Form 16-2 Standard Pre-Lift Crane Plan/Checklist for each lift planned. Submit SLP to the Contracting Officer for approval within 15 calendar days in advance of planned lift.

1.14 HOT WORK

1.14.1 Permit and Personnel Requirements

Submit and obtain a written permit prior to performing "Hot Work" (i.e. welding or cutting) for activities that generate heat, sparks, or flames from the Wallops Flight Facility Fire Department on a daily basis. A permit is required from the Explosives Safety Office for work in and around where explosives are processed, stored, or handled. CONTRACTORS ARE REQUIRED TO MEET ALL CRITERIA BEFORE A PERMIT IS ISSUED. Provide at least two 20 pound 4A:20 BC rated extinguishers for normal "Hot Work". The extinguishers must be current inspection tagged, and contain an approved safety pin and tamper resistant seal. It is also mandatory to have a designated FIRE WATCH for any "Hot Work" done at this activity. The Fire Watch must be trained in accordance with NFPA 51B and remain on-site for a minimum of one hour after completion of the task or as specified on the hot work permit.

When starting work in the facility, require personnel to familiarize themselves with the location of the nearest fire alarm boxes and place in memory the emergency Fire Division phone number. REPORT ANY FIRE, NO MATTER HOW SMALL, TO THE RESPONSIBLE FIRE DIVISION IMMEDIATELY.

1.14.2 Work Around Flammable Materials

Obtain permit approval from a NFPA Certified Marine Chemist, or Certified Industrial Hygienist for "HOT WORK" within or around flammable materials (such as fuel systems or welding/cutting on fuel pipes) or confined spaces (such as sewer wet wells, manholes, or vaults) that have the potential for flammable or explosive atmospheres.

Whenever these materials, except beryllium and chromium (VI), are encountered in indoor operations, local mechanical exhaust ventilation systems that are sufficient to reduce and maintain personal exposures to within acceptable limits must be used and maintained in accordance with manufacturer's instruction and supplemented by exceptions noted in EM 385-1-1, Section 06.H

1.15 DIVE SAFETY REQUIREMENTS

All diving operations shall be in accordance with USACE EM 385-1-1. Diving operations shall not commence without prior acceptance of a Dive Operation Plan by the COR.

Develop a Dive Operations Plan, AHA, emergency management plan, and personnel list that includes qualifications, for each separate diving operation. Submit these documents to the District Dive Coordinator (DDC) via the Contracting Officer or Government Designated Authority (GDA), for review and approval at least 15 working days prior to commencement of diving operations. These documents must be at the diving location at all times. Provide each of these documents as a part of the project file.

1.16 SEVERE STORM PLAN

In the event of a severe storm warning, the Contractor must comply with the applicable Storm Plan and:

- a. Secure outside equipment and materials and place materials that could

be damaged in protected areas.

- b. Check surrounding area, including roof, for loose material, equipment, debris, and other objects that could be blown away or against existing facilities.
- c. Ensure that temporary erosion controls are adequate.

PART 2 PRODUCTS

Not Used

PART 3 EXECUTION

3.1 CONSTRUCTION AND OTHER WORK

Comply with EM 385-1-1, NFPA 70, NFPA 70E, NFPA 241, the APP, the AHA, Federal and State OSHA regulations, and other related submittals and activity fire and safety regulations. The most stringent standard prevails.

PPE is governed in all areas by the nature of the work the employee is performing. Use personal hearing protection at all times in designated noise hazardous areas or when performing noise hazardous tasks. Safety glasses must be worn or carried/available on each person. Mandatory PPE includes:

- a. Hard Hat
- b. Long Pants
- c. Appropriate Safety Shoes
- d. Appropriate Class Reflective Vests

3.1.1 Worksite Communication

Employees working alone in a remote location or away from other workers must be provided an effective means of emergency communications (i.e., cellular phone, two-way radios, land-line telephones or other acceptable means). The selected communication must be readily available (easily within the immediate reach) of the employee and must be tested prior to the start of work to verify that it effectively operates in the area/environment. Develop an employee check-in/check-out communication procedure to ensure employee safety. See 01 14 00 WORK RESTRICTIONS for additional radio requirements.

3.1.2 Hazardous Material Exclusions

Notwithstanding any other hazardous material used in this Contract, radioactive materials or instruments capable of producing ionizing/non-ionizing radiation (with the exception of radioactive material and devices used in accordance with EM 385-1-1 such as nuclear density meters for compaction testing and laboratory equipment with radioactive sources) as well as materials which contain asbestos, mercury or polychlorinated biphenyls, di-isocyanates, lead-based paint, and hexavalent chromium, are prohibited. The Contracting Officer, upon written request by the Contractor, may consider exceptions to the use of any of the above excluded materials. Low mercury lamps used within

fluorescent lighting fixtures are allowed as an exception without further Contracting Officer approval. Notify the Radiation Safety Officer (RSO) prior to excepted items of radioactive material and devices being brought on base.

3.1.3 Unforeseen Hazardous Material

Contract documents identify materials such as PCB, lead paint, and friable and non-friable asbestos and other OSHA regulated chemicals (i.e. 29 CFR Part 1910.1000). If material(s) that may be hazardous to human health upon disturbance are encountered during construction operations, stop that portion of work and notify the Contracting Officer immediately. Within 14 calendar days the Government will determine if the material is hazardous. If material is not hazardous or poses no danger, the Government will direct the Contractor to proceed without change. If material is hazardous and handling of the material is necessary to accomplish the work, the Government will issue a modification pursuant to FAR 52.243-4 Changes and FAR 52.236-2 Differing Site Conditions.

3.2 UTILITY OUTAGE REQUIREMENTS

Apply for utility outages at least 14 days in advance. At a minimum, the written request must include the location of the outage, utilities being affected, duration of outage, any necessary sketches, and a description of the means to fulfill energy isolation requirements in accordance with EM 385-1-1, Section 11.A.02 (Isolation). Some examples of energy isolation devices and procedures are highlighted in EM 385-1-1, Section 12.D. In accordance with EM 385-1-1, Section 12.A.01, where outages involve Government or Utility personnel, coordinate with the Government on all activities involving the control of hazardous energy.

These activities include, but are not limited to, a review of HEC and HEC procedures, as well as applicable Activity Hazard Analyses (AHAs). In accordance with EM 385-1-1, Section 11.A.02 and NFPA 70E, work on energized electrical circuits must not be performed without prior Government authorization. Government permission is considered through the permit process and submission of a detailed AHA. Energized work permits are considered only when de-energizing introduces additional or increased hazard or when de-energizing is infeasible.

3.3 OUTAGE COORDINATION MEETING

After the utility outage request is approved and prior to beginning work on the utility system requiring shut-down, conduct a pre-outage coordination meeting in accordance with EM 385-1-1, Section 12.A. This meeting must include the Prime Contractor, the Prime and subcontractors performing the work, the Contracting Officer, and the Installation representative. All parties must fully coordinate HEC activities with one another. During the coordination meeting, all parties must discuss and coordinate on the scope of work, HEC procedures (specifically, the lock-out/tag-out procedures for worker and utility protection), the AHA, assurance of trade personnel qualifications, identification of competent persons, and compliance with HEC training in accordance with EM 385-1-1, Section 12.C. Clarify when personal protective equipment is required during switching operations, inspection, and verification.

3.4 CONTROL OF HAZARDOUS ENERGY (LOCKOUT/TAGOUT)

Provide and operate a Hazardous Energy Control Program (HECP) in

accordance with EM 385-1-1 Section 12, 29 CFR 1910.333, 29 CFR 1915.89, ASSP A10.44, NFPA 70E, and paragraph HAZARDOUS ENERGY CONTROL PROGRAM (HECP).

3.4.1 Safety Preparatory Inspection Coordination Meeting with the Government or Utility

For electrical distribution equipment that is to be operated by Government or Utility personnel, the Prime Contractor and the subcontractor performing the work must attend the safety preparatory inspection coordination meeting, which will also be attended by the Contracting Officer's Representative, and required by EM 385-1-1, Section 12.A.02. The meeting will occur immediately preceding the start of work and following the completion of the outage coordination meeting. Both the safety preparatory inspection coordination meeting and the outage coordination meeting must occur prior to conducting the outage and commencing with lockout/tagout procedures.

3.4.2 Lockout/Tagout Isolation

Where the Government or Utility performs equipment isolation and lockout/tagout, the Contractor must place their own locks and tags on each energy-isolating device and proceed in accordance with the HECP. Before any work begins, both the Contractor and the Government or Utility must perform energy isolation verification testing while wearing required PPE detailed in the Contractor's AHA and required by EM 385-1-1, Sections 05.I and 11.B. Install personal protective grounds, with tags, to eliminate the potential for induced voltage in accordance with EM 385-1-1, Section 12.E.06.

3.4.3 Lockout/Tagout Removal

Upon completion of work, conduct lockout/tagout removal procedure in accordance with the HECP. In accordance with EM 385-1-1, Section 12.E.08, each lock and tag must be removed from each energy isolating device by the authorized individual or systems operator who applied the device. Provide formal notification to the Government (by completing the Government form if provided by Contracting Officer's Representative), confirming that steps of de-energization and lockout/tagout removal procedure have been conducted and certified through inspection and verification. Government or Utility locks and tags used to support the Contractor's work will not be removed until the authorized Government employee receives the formal notification.

3.5 FALL PROTECTION PROGRAM

Establish a fall protection program, for the protection of all employees exposed to fall hazards. Within the program include company policy, identify roles and responsibilities, education and training requirements, fall hazard identification, prevention and control measures, inspection, storage, care and maintenance of fall protection equipment and rescue and evacuation procedures in accordance with ASSP Z359.2 and EM 385-1-1, Sections 21.A and 21.D.

3.5.1 Training

Institute a fall protection training program. As part of the Fall Protection Program, provide training for each employee who might be exposed to fall hazards and using personal fall protection equipment.

Provide training by a competent person for fall protection in accordance with EM 385-1-1, Section 21.C. Document training and practical application of the competent person in accordance with EM 385-1-1, Section 21.C.04 and ASSP Z359.2 in the AHA.

3.5.2 Fall Protection Equipment and Systems

Enforce use of personal fall protection equipment and systems designated (to include fall arrest, restraint, and positioning) for each specific work activity in the Site Specific Fall Protection and Prevention Plan and AHA at all times when an employee is exposed to a fall hazard. Protect employees from fall hazards as specified in EM 385-1-1, Section 21.

Provide personal fall protection equipment, systems, subsystems, and components that comply with EM 385-1-1 Section 21.I, 29 CFR 1926.500 Subpart M, ASSP Z359.0, ASSP Z359.1, ASSP Z359.2, ASSP Z359.3, ASSP Z359.4, ASSP Z359.6, ASSP Z359.7, ASSP Z359.11, ASSP Z359.12, ASSP Z359.13, ASSP Z359.14, ASSP Z359.15, ASSP Z359.16 and ASSP Z359.18.

3.5.2.1 Additional Personal Fall Protection Measures

In addition to the required fall protection systems, other protective measures such as safety skiffs, personal floatation devices, and life rings, are required when working above or next to water in accordance with EM 385-1-1, Sections 21.0 through 21.0.06. Personal fall protection systems and equipment are required when working from an articulating or extendible boom, swing stages, or suspended platform. In addition, personal fall protection systems are required when operating other equipment such as scissor lifts. The need for tying-off in such equipment is to prevent ejection of the employee from the equipment during raising, lowering, travel, or while performing work.

3.5.2.2 Personal Fall Protection Equipment

Only a full-body harness with a shock-absorbing lanyard or self-retracting lanyard is an acceptable personal fall arrest body support device. The use of body belts is not acceptable. Harnesses must have a fall arrest attachment affixed to the body support (usually a Dorsal D-ring) and specifically designated for attachment to the rest of the system. Snap hooks and carabiners must be self-closing and self-locking, capable of being opened only by at least two consecutive deliberate actions and have a minimum gate strength of 3,600 lbs in all directions. Use webbing, straps, and ropes made of synthetic fiber. The maximum free fall distance when using fall arrest equipment must not exceed 6 feet, unless the proper energy absorbing lanyard is used. Always take into consideration the total fall distance and any swinging of the worker (pendulum-like motion), that can occur during a fall, when attaching a person to a fall arrest system. Equip all full body harnesses with Suspension Trauma Preventers such as stirrups, relief steps, or similar in order to provide short-term relief from the effects of orthostatic intolerance in accordance with EM 385-1-1, Section 21.I.06.

3.5.3 Horizontal Lifelines (HLL)

Provide HLL in accordance with EM 385-1-1, Section 21.I.08.d.2. Commercially manufactured horizontal lifelines (HLL) must be designed, installed, certified and used, under the supervision of a qualified person, for fall protection as part of a complete fall arrest system which maintains a safety factor of 2 (29 CFR 1926.500). The competent person

for fall protection may (if deemed appropriate by the qualified person) supervise the assembly, disassembly, use and inspection of the HLL system under the direction of the qualified person. Locally manufactured HLLs are not acceptable unless they are custom designed for limited or site specific applications by a Registered Professional Engineer who is qualified in designing HLL systems.

3.5.4 Guardrails and Safety Nets

Design, install and use guardrails and safety nets in accordance with EM 385-1-1, Section 21.F.01 and 29 CFR 1926 Subpart M.

3.5.5 Rescue and Evacuation Plan and Procedures

When personal fall arrest systems are used, ensure that the mishap victim can self-rescue or can be rescued promptly should a fall occur. Prepare a Rescue and Evacuation Plan and include a detailed discussion of the following: methods of rescue; methods of self-rescue or assisted-rescue; equipment used; training requirement; specialized training for the rescuers; procedures for requesting rescue and medical assistance; and transportation routes to a medical facility. Include the Rescue and Evacuation Plan within the Activity Hazard Analysis (AHA) for the phase of work, in the Fall Protection and Prevention (FP&P) Plan, and the Accident Prevention Plan (APP). The plan must be in accordance with the requirements of EM 385-1-1, ASSP Z359.2, and ASSP Z359.4.

3.6 EQUIPMENT

3.6.1 Material Handling Equipment (MHE)

- a. Material handling equipment such as forklifts must not be modified with work platform attachments for supporting employees unless specifically delineated in the manufacturer's printed operating instructions. Material handling equipment fitted with personnel work platform attachments are prohibited from traveling or positioning while personnel are working on the platform.
- b. The use of hooks on equipment for lifting of material must be in accordance with manufacturer's printed instructions. Material Handling Equipment Operators must be trained in accordance with OSHA 29 CFR 1910, Subpart N.
- c. Operators of forklifts or power industrial trucks must be licensed in accordance with OSHA.

3.6.2 Load Handling Equipment (LHE)

The following requirements apply. In exception, these requirements do not apply to commercial truck mounted and articulating boom cranes used solely to deliver material and supplies (not prefabricated components, structural steel, or components of a systems-engineered metal building) where the lift consists of moving materials and supplies from a truck or trailer to the ground; to cranes installed on mechanics trucks that are used solely in the repair of shore-based equipment; to crane that enter the activity but are not used for lifting; nor to other machines not used to lift loads suspended by rigging equipment. However, LHE accidents occurring during such operations must be reported.

- a. Equip cranes and derricks as specified in EM 385-1-1, Section 16.

- b. Notify the Contracting Officer 15 working days in advance of any LHE entering the activity, in accordance with EM 385-1-1, Section 16.A.02, so that necessary quality assurance spot checks can be coordinated. Contractor's operator must remain with the crane during the spot check. Rigging gear must be in accordance with OSHA, ASME B30.9 Standards safety standards.
- c. Comply with the LHE manufacturer's specifications and limitations for erection and operation of cranes and hoists used in support of the work. Perform erection under the supervision of a designated person (as defined in ASME B30.5). Perform all testing in accordance with the manufacturer's recommended procedures.
- d. Comply with ASME B30.5 for mobile and locomotive cranes, ASME B30.22 for articulating boom cranes, ASME B30.3 for construction tower cranes, ASME B30.8 for floating cranes and floating derricks, ASME B30.9 for slings, ASME B30.20 for below the hook lifting devices and ASME B30.26 for rigging hardware.
- e. When operating in the vicinity of overhead transmission lines, operators and riggers must be alert to this special hazard and follow the requirements of EM 385-1-1 Section 11, and ASME B30.5 or ASME B30.22 as applicable.
- f. Do not use crane suspended personnel work platforms (baskets) unless the Contractor proves that using any other access to the work location would provide a greater hazard to the workers or is impossible. Do not lift personnel with a line hoist or friction crane. Additionally, submit a specific AHA for this work to the Contracting Officer. Ensure the activity and AHA are thoroughly reviewed by all involved personnel.
- g. Inspect, maintain, and recharge portable fire extinguishers as specified in NFPA 10, Standard for Portable Fire Extinguishers.
- h. All employees must keep clear of loads about to be lifted and of suspended loads, except for employees required to handle the load.
- i. Use cribbing when performing lifts on outriggers.
- j. The crane hook/block must be positioned directly over the load. Side loading of the crane is prohibited.
- k. A physical barricade must be positioned to prevent personnel access where accessible areas of the LHE's rotating superstructure poses a risk of striking, pinching or crushing personnel.
- l. Maintain inspection records in accordance by EM 385-1-1, Section 16.D, including shift, monthly, and annual inspections, the signature of the person performing the inspection, and the serial number or other identifier of the LHE that was inspected. Records must be available for review by the Contracting Officer.
- m. Maintain written reports of operational and load testing in accordance with EM 385-1-1, Section 16.F, listing the load test procedures used along with any repairs or alterations performed on the LHE. Reports must be available for review by the Contracting Officer.

- n. Certify that all LHE operators have been trained in proper use of all safety devices (e.g. anti-two block devices).
- o. Take steps to ensure that wind speed does not contribute to loss of control of the load during lifting operations. At wind speeds greater than 20 mph, the operator, rigger and lift supervisor must cease all crane operations, evaluate conditions and determine if the lift may proceed. Base the determination to proceed or not on wind calculations per the manufacturer and a reduction in LHE rated capacity if applicable. Include this maximum wind speed determination as part of the activity hazard analysis plan for that operation.
- q. Follow FAA guidelines when required based on project location.

3.6.3 Machinery and Mechanized Equipment

- a. Proof of qualifications for operator must be kept on the project site for review.
- b. Manufacture specifications or owner's manual for the equipment must be on-site and reviewed for additional safety precautions or requirements that are sometimes not identified by OSHA or USACE EM 385-1-1. Incorporate such additional safety precautions or requirements into the AHAs.

3.6.4 Base Mounted Drum Hoists

- a. Operation of base mounted drum hoists must be in accordance with EM 385-1-1 and ASSP A10.22.
- b. Rigging gear must be in accordance with applicable ASME/OSHA standards.
- c. When used on telecommunication towers, base mounted drum hoists must be in accordance with TIA-1019, TIA-222, ASME B30.7, 29 CFR 1926.552, and 29 CFR 1926.553.
- d. When used to hoist personnel, the AHA must include a written standard operating procedure. Operators must have a physical examination in accordance with EM 385-1-1 Section 16.B.05 and trained, at a minimum, in accordance with EM 385-1-1 Section 16.U and 16.T. The base mounted drum hoist must also comply with OSHA Instruction CPL 02-01-056 and ASME B30.23.
- e. Material and personnel must not be hoisted simultaneously.
- f. Personnel cage must be marked with the capacity (in number of persons) and load limit in pounds.
- g. Construction equipment must not be used for hoisting material or personnel or with trolley/tag lines. Construction equipment may be used for towing and assisting with anchoring guy lines.

3.7 EXCAVATIONS

Soil classification must be performed by a competent person in accordance with 29 CFR 1926 and EM 385-1-1.

3.7.1 Utility Locations

Provide a third party, independent, private utility locating company to positively identify underground utilities in the work area and dredge site in addition to any station locating service and coordinated with the station utility department.

3.7.2 Utility Location Verification

Physically verify underground utility locations, including utility depth, by hand digging using wood or fiberglass handled tools when any adjacent construction work is expected to come within 3 feet of the underground system.

-- End of Section --

DRAFT
NOT FOR CONSTRUCTION

SECTION 01 35 30

MUNITIONS AND EXPLOSIVES OF CONCERN (MEC) CONSTRUCTION SUPPORT, LOW
PROBABILITY SITE
04/25

PART 1 GENERAL

1.1 SCOPE OF SECTION

The work required under this Section involves Munitions and Explosives of Concern (MEC) safety support in the form of MEC screening device acceptance, identification of potential MEC, inert ordnance, ordnance fragments, and MEC safety briefings within the dredging prism of the borrow area during performance of dredging activities.

1.2 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for information only. When used, a code following the "G" classification identifies the office that will review the submittal for the Government. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-04 Samples

Discharge End Screening Devices; G, DO

1.3 MEC IN BORROW AREAS

A MEC Probability Assessment was conducted for the Shoal A borrow area. It was determined to be a Low Probability for encountering MEC. A MEC Safety and Work Plan will be provided by the Government. MEC is not anticipated. The Government will be responsible for MEC support if MEC is encountered.

1.4 UNEXPLODED ORDNANCE (UXO) TECHNICIANS

1.4.1 Land-based UXO Technicians

If MEC is identified as being dredged in a frequency that interferes with project schedule, crew safety and emergency response assets that cannot be addressed through mechanical modifications, the Government will provide the following:

Beach fill operations, the government may be required to provide a minimum of two Ordnance and Explosive Safety Specialist (OESS) (As specified in Department of Defense Explosives Safety Board (DDESB), Technical Paper 18, MINIMUM QUALIFICATIONS FOR UNEXPLODED ORDNANCE (UXO) TECHNICIANS AND PERSONNEL). Which is included at the end of this section, as Attachment A

The OESS shall provide 24-hour, 7-days per week, MEC support, on the beach

The OESS shall provide MEC Training and shall inspect the screening devices for damage and presence of MEC

The OESS shall follow the "STANDARD OPERATING PROCEDURES FOR LAND BASED UXO TECHNICIANS PROVIDING MEC SUPPORT", which is included at the end of this section, as Attachment B. Provide support to the Technicians as required and specified in this Attachment.

1.5 PRE AND POST MEC SCREEN SAFETY INSPECTIONS

If the Hopper Dredge is coming from a previous MEC project, the Contractor must ensure the dredge hopper has been flushed and clear of residual material. During the drag head screen inspections, the hopper will be inspected to ensure it is free of material. If residual material exists, the dredge shall conduct a hopper flush over a designated barrow area until free of material. (Flushing out the hopper prior to departure of a MEC project should be conducted as a safe practice not to cross contaminate material possibly containing MEC).

Prior to commencement of any beach fill work, provide a working demonstration that discharge end screening devices work as designed, subject to approval by Contracting Officer.

Beach baskets will be inspected at a minimum by a OESS prior to beach operations. All inspections will be recorded into the daily report to the COR. Photos are required of the inspections.

Post inspections of the hopper dredge and on the beach (beach baskets) will be conducted as previously stated in para.1.5. b. (1), (2) and (3). This will ensure no MEC remains in the screening devices and will ensure no MEC hazards leave the project site. This will also further the safety to crew and personnel prior to departing of a project.

1.6 GOVERNMENT-PROVIDED MEC SPECIALIST OESS

1.6.1 General

The Corps of Engineers Military Munitions Design Center will provide an Ordnance and Explosives Safety Specialist (OESS) to provide pre-dredging MEC safety training prior to the commencement of dredging activities.

1.6.2 Pre-Construction Meeting

The OESS will attend the preconstruction meeting to answer any of the Contractor's questions concerning MEC.

1.6.3 MEC Safety and Work Plan Review

The OESS will review the Contractor's MEC Safety and Work Plan to ensure MEC aspects are adequately addressed. The Contractor's MEC Safety and Work Plan shall communicate the Contractor's understanding of his role and responsibility in the management of dredging and dredged material placement operations to prevent accidents related to MEC.

1.6.4 Worker Education

This training will be provided prior to the start of work on site, and to all newly reporting personnel assigned to the project who have not attended MEC training in the previous twelve months. MEC Training is required once per 12-month period. The MEC training video can be accessed at <https://denix.osd.mil/uxotraining/3RSTraining/index.html>. If OESS are onsite. The OESS shall conduct MEC safety/ awareness/ recognition training

for the Contractor's dredging vessel and shore-based workers.

1.6.5 Quality Assurance (QA)

The Government may wish to inspect MEC screens during dredging. Stop dredging work immediately when notified by the Contracting Officer's Representative (COR) that inspection of MEC screening devices is required during dredging operations.

Upon notification by the OESS or COR that the MEC screening system on the beach has degraded and is not functioning as intended, the Contractor shall stop work and correct the deficiency to prevent MEC from being dredged.

1.7 MEC SAFETY AND WORK PLAN REQUIREMENTS

Prior to commencement of any work, including delivery of any plant, equipment or construction materials to the site, submit a MEC Safety and Work Plan. The MEC Safety and Work Plan shall consist of the items as specified herein.

The MEC Safety and Work Plan shall include the following:

The Government will be responsible for the MEC safety and work plan if needed.

PART 2 PRODUCTS

Not Applicable

PART 3 EXECUTION

3.1 MEC Discharge Screening devices

Prevent MEC from being placed on the beach by:

A screening device will be placed at the discharge end of the pipeline on the beach. The required screening devices shall meet the following requirements:

Design the Discharge End Screening Device to retain all items 0.75 inches in diameter and larger. The openings on the screening device shall be of uniform dimension (i.e., a grid or a series of round holes; slotted openings will not be permitted).

Construct the screening devices using rugged steel or composite material, one-piece, or welded members. The devices shall cover the entire cross-sectional area, except where basket type devices are used on the discharge end. Relief windows in basket type devices will be permitted only to the side opposite the inflow and at least twelve inches from the bottom of the basket, or as directed by the OESS. Size and locate windows to prevent large items, and MEC items from escaping the basket during pumping operations. Keep basket type devices in a level and horizontal position when using relief windows, during pumping operations.

The screening devices shall be removable for easy replacement if damaged. Ensure screening devices provide a production rate that

allows completion of all dredging and beach fill placement within the contract duration.

Demonstrate on-site, subject to approval of the Contracting Officer, the screening devices meet all requirements specified herein.

Maintain adequate replacement parts and additional screening devices on site to ensure production for the work does not stop due to damaged devices, or delays in the inspection process.

Provide minor adjustments to the beach screening baskets as directed by the OESS to accommodate varying types and amounts of material being screened at the beach, at no additional cost to the Government. As an example, relief windows, other than the required screen apertures, sometimes need to be enlarged, reduced, or relocated to minimize residual biological debris in the in the basket during the inflow process and for post flow MEC inspection of residual material.

3.2 DETECTION OF MEC

MEC on the dredge in the drag head or on the deck; stop dredging and beach fill work. No Crew member will attempt to dislodge or move suspect MEC item. Take photos, if possible, as long as no physical contact is made to suspect item. Contact OESS and send photos if available. Arrangements will be made by the Contractor for the crew boat to transport the OESS to the dredge. The OESS will travel to the dredge and ensure a positive identification of MEC item. The OESS will direct the actions and coordinate emergency response after all information is gathered. Contact the OESS directly for all MEC related inquiries, finds, and incidents. The OESS will perform the UXO Technician support duties mentioned above.

3.3 CONTRACTOR SUPPORT

Aid as required by the emergency response agency. This will be coordinated by the OESS and may consist of such activities as digging holes with equipment for detonation of MEC items, and/or providing extra perimeter security during emergency response activities. The Contractor will not be needed or expected to place site workers in hazardous situations during emergency responses to MEC at the project site.

3.4 MEASUREMENT AND PAYMENT

The work specified in this section will not be measured for payment and all costs in connection therewith shall be included in the contract unit price per cubic yard included in the Bid Line Items that pertain to direct dredging cost.

-- End of Section --

SECTION 01 42 00

SOURCES FOR REFERENCE PUBLICATIONS

02/19, CHG 1: 08/23

PART 1 GENERAL

1.1 REFERENCES

Various publications are referenced in other sections of the specifications to establish requirements for the work. These references are identified in each section by document number, date and title. The document number used in the citation is the number assigned by the standards producing organization (e.g., ASTM B564 Standard Specification for Nickel Alloy Forgings). However, when the standards producing organization has not assigned a number to a document, an identifying number has been assigned for reference purposes.

1.2 ORDERING INFORMATION

The addresses of the standards publishing organizations whose documents are referenced in other sections of these specifications are listed below, and if the source of the publications is different from the address of the sponsoring organization, that information is also provided.

AACE INTERNATIONAL (AACE)
1265 Suncrest Towne Centre Drive
Morgantown, WV 26505-1876 USA
Ph: 304-296-8444
Fax: 304-291-5728
Internet: <https://web.aacei.org/>

AMERICAN SOCIETY FOR QUALITY (ASQ)
600 North Plankinton Avenue
Milwaukee, WI 53203
-or-
P.O. Box 3005
Milwaukee, WI 53201-3005
Ph: 800-248-1946; 414-272-8575
Fax: 414-272-1734

E-mail: help@asq.org
Internet: <https://asq.org/>

AMERICAN SOCIETY OF CIVIL ENGINEERS (ASCE)
1801 Alexander Bell Drive
Reston, VA 20191
Ph: 800-548-2723; 703-295-6300
Internet: <https://www.asce.org/>

AMERICAN SOCIETY OF HEATING, REFRIGERATING AND AIR-CONDITIONING
ENGINEERS (ASHRAE)
1791 Tullie Circle, NE
Atlanta, GA 30329
Ph: 404-636-8400 or 800-527-4723
Fax: 404-321-5478
E-mail: ashrae@ashrae.org
Internet: <https://www.ashrae.org/>

AMERICAN SOCIETY OF MECHANICAL ENGINEERS (ASME)
Two Park Avenue
New York, NY 10016-5990
Ph: 800-843-2763
Fax: 973-882-1717
E-mail: customercare@asme.org
Internet: <https://www.asme.org/>

ASSOCIATION OF THE WALL AND CEILING INDUSTRY (AWCI)
513 West Broad Street, Suite 210
Falls Church, VA 22046
Ph: 703-538-1600
Fax: 703-534-8307
Internet: <https://www.awci.org/>

NATIONAL FENESTRATION RATING COUNCIL (NFRC)
6305 Ivy Lane, Suite 140
Greenbelt, MD 20770
Ph: 301-589-1776
Fax: 301-589-3884
E-Mail: info@nfrc.org
Internet: <http://www.nfrc.org>

TECHNICAL ASSOCIATION OF THE PULP AND PAPER INDUSTRY (TAPPI)
15 Technology Parkway South, Suite 115
Peachtree Corners, GA 30092
Ph: 800-332-8686 or 770-446-1400
Fax: 770-446-6947

E-mail: memberconnection@tappi.org
Internet: <http://www.tappi.org>

U.S. ARMY CENTER FOR HEALTH PROMOTION AND PREVENTIVE MEDICINE
(USACHPPM)
5158 Blackhawk Road
Aberdeen Proving Ground, MD 21010-5403
Ph: 800-222-9698
Fax: 1 (410) 436-7142
E-mail: chppmhhc@AMEDD.ARMY.MIL
Internet: <http://chppm-www.apgea.army.mil>

U.S. DEPARTMENT OF COMMERCE (DOC)
1401 Constitution Avenue, NW
Washington, DC 20230
Ph: 202-482-2000
Internet: <https://www.commerce.gov/>
Order Publications From:
National Technical Information Service (NTIS)
5301 Shawnee Road
Alexandria, VA 22312
Ph: 703-605-6060 or 1-800-363-2068
Fax: 703-605-6880
TDD: 703-487-4639
E-mail: info@ntis.gov
Internet: <https://www.ntis.gov/>

U.S. FEDERAL COMMUNICATIONS COMMISSION (FCC)
445 12th Street SW
Washington, DC 20554
Ph: 888-225-5322
TTY: 888-835-5322
Fax: 866-418-0232
Internet: <https://www.fcc.gov/>
Order Publications From:
Superintendent of Documents
U.S. Government Publishing Office (GPO)
732 N. Capitol Street, NW
Washington, DC 20401
Ph: 202-512-1800 or 866-512-1800
Bookstore: 202-512-0132
Internet: <https://www.gpo.gov/>

U. S. GREEN BUILDING COUNCIL (USGBC)
2101 L St NW, Suite 500
Washington, DC 20037
Ph: 202-828-7422
Internet: <https://new.usgbc.org/>

WOOLMARK COMPANY (WBI)
NeueHouse
110 East 25th Street, 3rd Floor
New York, NY 10010
or
WeWork One Culver
10000 Washington Blvd
Culver City, CA 90232
Ph: 347-767-3160
E-mail: woolmark.americas@wool.com

internet: <https://www.woolmark.com/>

PART 2 PRODUCTS

Not used

PART 3 EXECUTION

Not used

-- End of Section --

DRAFT
NOT FOR CONSTRUCTION

SECTION 01 45 00

QUALITY CONTROL
08/23

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by the basic designation only.

ASTM INTERNATIONAL (ASTM)

- | | |
|------------|---|
| ASTM D3740 | (2019) Minimum Requirements for Agencies Engaged in the Testing and/or Inspection of Soil and Rock as Used in Engineering Design and Construction |
| ASTM E329 | (2023) Standard Specification for Agencies Engaged in Construction Inspection, Testing, or Special Inspection |

U.S. ARMY CORPS OF ENGINEERS (USACE)

- | | |
|------------|--|
| EM 385-1-1 | (2024) Safety -- Safety and Occupational Health (SOH) Requirements |
|------------|--|

1.2 PAYMENT

Separate payment will not be made for providing and maintaining an effective Quality Control program. Include all associated costs in the applicable Bid Schedule item.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES.

SD-01 Preconstruction Submittals

Contractor Quality Control (CQC) Plan; G, R0

SD-06 Test Reports

Verification Statement

1.4 GENERAL REQUIREMENTS

Establish and maintain an effective quality control (QC) system that complies with FAR 52.246-12 Inspection of Construction. QC is comprised of plans, procedures, and organization necessary to produce an end product that complies with the Contract requirements. The QC system covers all construction operations, both onsite and offsite, and must be keyed to the proposed construction sequence. The Quality Control Manager,

Superintendent, Site Safety and Health Officer (SSHO), and all on-site supervisors are responsible for the quality of work and are subject to removal by the Contracting Officer for non-compliance with the quality requirements specified in the Contract. The Quality Control Manager must maintain a physical presence at the work site at all times and is the primary individual responsible for all quality control.

1.5 QUALITY CONTROL (QC) PROGRAM REQUIREMENTS

Establish and maintain a QC program as described in this section. The QC program consists of a QC Organization, QC Plan, QC Plan Meeting(s), a Coordination and Mutual Understanding Meeting, QC meetings, three phases of control, submittal review and approval, testing, completion inspections, QC certifications, and documentation necessary to provide materials, equipment, workmanship, fabrication, construction and operations that comply with the requirements of this Contract. The QC program must cover on-site and off-site work and be keyed to the work sequence. No construction work or testing may be performed unless the QC Manager is on the work site. The QC Manager must report to an officer of the firm and not be subordinate to the Project Superintendent or the Project Manager. The QC Manager, Project Superintendent and Project Manager must work together effectively. Although the QC Manager is the primary individual responsible for quality control, all individuals will be held responsible for the quality of work on the job.

1.5.1 Meetings

1.5.1.1 Quality Control Plan Meeting

Prior to submission of the QC Plan, the Contractor may request a meeting with the Contracting Officer to discuss the QC Plan requirements of this Contract.

The purpose of this meeting is to develop a mutual understanding of the QC Plan requirements prior to plan development and submission and to agree on the Contractor's list of Definable Feature of Work (DFOW).

1.5.1.2 Coordination and Mutual Understanding Meeting

After the Preconstruction Conference, before start of construction, and prior to acceptance by the Government of the CQC Plan, meet with the Contracting Officer and discuss the Contractor's quality control system. During the meeting, a mutual understanding of the system details must be developed, including the forms for recording the CQC operations, control activities, testing, administration of the system for both onsite and offsite work, and the interrelationship of Contractor's Management and control with the Government's Quality Assurance. Minutes of the meeting will be prepared by the QC Manager and signed by the Contractor and the Government. Provide a copy of the signed minutes to all attendees and include in the QC Plan. At a minimum the Coordination and Mutual Understanding Meeting must be repeated when a new QC Manager is appointed. There can be other occasions when subsequent conferences will be called by either party to reconfirm mutual understandings or address deficiencies in the CQC system or procedures which can require corrective action by the Contractor.

1.5.1.2.1 Purpose

The purpose of this meeting is to develop a mutual understanding of the QC

details, including documentation, administration for on-site and off-site work, design intent, environmental requirements and procedures, coordination of activities to be performed, and the coordination of the Contractor's management, production, and QC personnel. At the meeting, the Contractor must explain in detail how three phases of control will be implemented for each DFOW, as well as how each DFOW will be affected by each management plan or requirement as listed below:

- a. Waste Management Plan.
- b. Procedures for noise and acoustics management.
- c. Environmental Protection Plan.
- d. Environmental regulatory requirements.

1.5.1.2.2 Coordination of Activities

Coordinate activities included in various sections to assure efficient and orderly installation of each component. Coordinate operations included under different sections that are dependent on each other for proper installation and operation.

1.5.1.2.3 Attendees

As a minimum, the Contractor's personnel required to attend include an officer of the firm, the Project Manager, Project Superintendent, QC Manager, Alternate QC Manager, Environmental Manager, and subcontractor representatives. Each subcontractor who will be assigned QC responsibilities must have a principal of the firm at the meeting.

1.5.1.3 Quality Control (QC) Meetings

After the start of construction, conduct weekly QC meetings led by the QC Manager at the work site with the Project Superintendent, the QC Specialists, the Special Inspector, and the other personnel as necessary. The QC Manager is to prepare the minutes of the meeting and provide a copy to the Contracting Officer within 2 working days after the meeting. The Contracting Officer may attend these meetings. As a minimum, accomplish the following at each meeting:

- a. Review the minutes of the previous meeting.
- b. Review the schedule and the status of work and deficiencies/rework. Review the most current approved schedule (in accordance with schedule specification) and the status of work and deficiencies/rework.
- c. Review the status of submittals and Request For Information (RFIs).
- d. Review the work to be accomplished in the next 3 weeks as defined by the schedule section paragraph WEEKLY PROGRESS MEETINGS in Section 01 32 01.00 10 PROJECT SCHEDULE and all documentation required for that work.
- e. Review Testing Plan and Log including status of tests performed since last QC Meeting.
- f. Resolve QC and production problems. Discuss status of pending change orders.

- g. Address items that may require revising the QC Plan.
- h. Review Accident Prevention Plan (APP) and effectiveness of the safety program.
- i. Review environmental requirements and procedures.
- j. Review Environmental Management Plan.
- k. Review Waste Management Plan.
- l. Review the status of training completion.

1.5.2 Contractor Quality Control (CQC) Plan

Submit no later than 30 days after receipt of notice to proceed, the CQC Plan proposed to implement the requirements FAR 52.246-12 Inspection of Construction. Construction will be permitted to begin only after acceptance of the CQC Plan and other Contract requirements. Work outside of the accepted interim plan will not be permitted to begin until acceptance of a CQC Plan or another interim plan containing the additional work.

1.5.2.1 Content of Contractor Quality Control (CQC) Plan

Provide a CQC Plan, prior to start of construction that includes a table of contents, with major sections identified, pages numbered sequentially, and that documents the proposed methods and responsibilities for accomplishing quality control during the construction of the project. The CQC Plan must at a minimum include the following sections:

- a. A description of the quality control organization and acknowledgment that the CQC staff will implement the three phase control system for all aspects of the work specified.
- b. An organizational chart showing the quality control organization with individual names and job titles and lines of authority up to an executive of the company at the home office.
- c. NAMES AND QUALIFICATIONS: Names and qualifications, in resume format, (including position titles and durations for qualifying experiences) for each person in the QC organization. Include the Construction Quality Management (CQM) for Contractors course certifications for the QC personnel as required by the paragraph CONSTRUCTION QUALITY MANAGEMENT TRAINING.
- d. DUTIES, RESPONSIBILITY AND AUTHORITY OF QC PERSONNEL: Duties, responsibilities, and authorities of each person in the QC organization.
- e. OUTSIDE ORGANIZATIONS: A listing of outside organizations, such as architectural and consulting engineering firms, that will be employed by the Contractor and a description of the services these firms will provide.
- f. APPOINTMENT LETTERS: Letters signed by an officer of the firm appointing the QC Manager and Alternate QC Manager, and stating that they are responsible for implementing and managing the QC program as

described in this Contract. Include in this letter the responsibility of the QC Manager and Alternate QC Manager to implement and manage the three phases of control, and their authority to stop work that is not in compliance with the Contract. Letters of direction are to be issued by the QC Manager to all other QC Specialists or quality control representatives outlining their duties, authorities, and responsibilities. Include copies of the letters in the QC Plan.

- g. SUBMITTAL PROCEDURES AND INITIAL SUBMITTAL REGISTER: Procedures for reviewing, approving, scheduling, and managing submittals, including those of subcontractors, offsite fabricators, suppliers, and purchasing agents. Provide the name(s) of the person(s) in the QC organization authorized to review and certify submittals prior to approval. Provide the initial submittal of the Submittal Register as specified in Section 01 33 00 SUBMITTAL PROCEDURES.
- h. TESTING LABORATORY INFORMATION: Testing laboratory information required by the paragraph ACCREDITATION REQUIREMENTS, as applicable.
- i. TESTING PLAN AND LOG: A Testing Plan and Log that includes the tests required, associated feature of work required, referenced by the specification paragraph number requiring the test, the frequency, and the person responsible for each test.
- j. Procedures to complete construction deficiencies from identification through acceptable corrective action. Establish verification procedures that identified deficiencies have been corrected. This phase is performed prior to beginning work on each definable feature of work, after all required plans, documents, materials are approved, and after copies are at the work site.
- k. Reporting procedures, including proposed reporting formats.
- l. Procedures for submitting and reviewing design changes/variations prior to submission to the Contracting Officer.
- m. LIST OF DEFINABLE FEATURES: A Definable Feature of Work (DFOW) is a task that is separate and distinct from other tasks and has control requirements and work crews unique to that task. A DFOW is identified by different trades or disciplines, or it is work by the same trade in a different environment. A DFOW is by definition any item or activity on the construction schedule, and the schedule specification provides direction regarding how the DFOWs are to be structured. Include in the list of DFOWs for all activities on the Construction Schedule. Although each section of the specifications can generally be considered as a definable feature of work, there are frequently more than one definable features under a particular section. Identify the specification section number and schedule activity ID for each DFOW listed. The DFOW list will be reviewed in coordination with the construction schedule and agreed upon during the Coordination of Mutual Understanding Meeting.
- n. PROCEDURES FOR PERFORMING AND TRACKING THE THREE PHASES OF CONTROL: Identify procedures used to ensure the three phases of control to manage the quality on this project. For each Definable Feature of Work (DFOW), a Preparatory and Initial phase checklist will be filled out during the Preparatory and Initial phase meetings. Conduct the Preparatory and Initial Phases and meetings with a view towards obtaining quality construction by planning ahead and identifying

potential problems for each DFO.

- o. PROCEDURES FOR COMPLETION INSPECTION: Procedures for identifying and documenting the completion inspection process. Include in these procedures the responsible party for punch out inspection, pre-final inspection, and final acceptance inspection.
- p. TRAINING PROCEDURES AND TRAINING LOG: Procedures for coordinating and documenting the training of personnel required by the Contract.
- q. ORGANIZATION AND PERSONNEL CERTIFICATIONS LOG: Procedures for coordinating, tracking and documenting all certifications required for entities such as subcontractors, testing laboratories, suppliers, and personnel. The QC Manager will ensure that certifications are current, appropriate for the work being performed, and will not lapse during any period of the Contract that the work is being performed.

1.5.3 Acceptance of the Quality Control (QC) Plan

The Contracting Officer's acceptance of the Contractor QC Plan, or interim plan applicable to the particular feature of work to be started, is required prior to the start of construction. The Government will consider an interim plan for the first 60 days of operation. Work outside of the accepted interim plan will not be permitted to begin until acceptance of a CQC Plan or another interim plan containing the additional work. The Contracting Officer reserves the right to require changes in the QC Plan and operations as necessary, including removal or addition of personnel, to ensure the specified quality of work. The Contracting Officer reserves the right to interview any member of the QC organization at any time to verify the submitted qualifications. All QC organization personnel are subject to acceptance by the Contracting Officer. The Contracting Officer may require the removal of any individual for non-compliance with quality requirements specified in the Contract.

1.5.4 Notification of Changes

Notify the Contracting Officer, in writing, of any proposed changes in the QC Plan or changes to the QC organization personnel. Proposed changes are subject to acceptance by the Contracting Officer.

1.6 QUALITY CONTROL (QC) ORGANIZATION

1.6.1 Personnel Requirements

The requirements for the CQC organization are a Site Safety and Health Officer (SSHO), QC Manager, and enough qualified personnel to ensure safety and Contract compliance. The SSHO reports directly to a senior project (or corporate) official independent from the QC Manager. The SSHO will also serve as a member of the CQC Staff Personnel identified in the technical provisions as requiring specialized skills to assure the required work is being performed properly. The CQC staff always maintains a presence at the site during progress of the work and have complete authority and responsibility to take any action necessary to ensure Contract compliance. The CQC staff will be subject to acceptance by the Contracting Officer. Provide adequate office space, filing systems and other resources as necessary to maintain an effective and fully functional CQC organization. Promptly complete and furnish all letters, material submittals, shop drawing submittals, schedules, and all other project documentation to the CQC organization. The CQC organization is

responsible for always maintaining these documents and records at the site, except as otherwise acceptable to the Contracting Officer.

1.6.2 Quality Control (QC) Manager

1.6.2.1 Duties

Provide a QC Manager at the work site to implement and manage the QC program. The QC Manager will not serve as the Site Safety and Health Officer (SSHO), as detailed in Section 01 35 26 GOVERNMENTAL SAFETY REQUIREMENTS. The QC Manager must be employed by the Prime Contractor. The QC Manager must attend the Coordination and Mutual Understanding Meeting, perform the three phases of control, perform submittal review and approval, ensure testing is performed and provide QC certifications and documentation required in this Contract. The QC Manager is responsible for managing and coordinating the three phases of control and documentation performed by the QC Specialists, testing laboratory personnel and any other inspection and testing personnel required by this Contract. The QC Manager is the manager of all QC activities.

1.6.2.2 Qualifications

The QC Manager must be a graduate engineer, graduate architect, or a graduate of construction management, with a current professional engineer registration in the state of Virginia and a minimum of 10 years construction experience as a Project Superintendent, QC Manager, Project Manager, Project Engineer or Construction Manager on similar size and type construction Contracts which included the major trades that are part of this Contract. The individual must have at least 4 years experience as a QC Manager. The individual must be familiar with the requirements of EM 385-1-1 and have experience in the areas of hazard identification, safety compliance, and sustainability.

The QC Manager and all members of the QC organization must be capable of reading, writing, and conversing fluently in the English language.

1.6.2.3 Construction Quality Management Training

In addition to the above experience and education requirements, the QC Manager and all members of the QC team must have completed the CQM for Contractors course. If the QC Manager does not have a current certification, obtain the CQM for Contractors course certification within 90 days of award. This course is periodically offered by the Naval Facilities Engineering Systems Command and the Army Corps of Engineers. Contact the Contracting Officer for information on the next scheduled class.

The Construction Quality Management Training certificate expires after 5 years. If the QC Manager's certificate has expired, retake the course to remain current.

1.6.3 Organizational Changes

Maintain the QC staff with personnel as required by the specification section at all times. When it is necessary to make changes to the QC staff, revise the CQC Plan to reflect the changes and submit the changes to the Contracting Officer for acceptance.

1.6.4 Alternate Quality Control (QC) Manager Duties and Qualifications

Designate an alternate for the QC Manager at the work site to serve in the event of the designated QC Manager's absence. The qualification requirements for the Alternate QC Manager must be the same as for the QC Manager.

1.6.5 Quality Control (QC) Specialists

Provide a separate QC Specialist at the work site for each of the areas as listed in the Matrix listed below, who must assist and report to the QC Manager and who may perform production related duties but must be allowed sufficient time to perform their assigned quality control duties. These individuals or specialized technical companies are employees of the Prime or subcontractor. A single person can cover more than one area provided that the single person is qualified to perform quality control activities in each designated and that workload allows. QC Specialists must be physically present at the work site with frequency as indicated in the Experience Matrix below, to participate in the QC Meetings, perform the three phases of control, including participation in Preparatory and Initial Phase meetings, and to perform and document Follow-up inspections as an extension of the QC Manager for each definable feature of work in their area of responsibility. QC Specialist must assist and be present for training events, and Critical System Acceptance inspections by the Government. Qualification, experience, Area of Responsibility, and frequency of QC surveillance are provided in Matrix listed herein.

Experience Matrix		
1. Area	2-1. Qualification	3-1. Area of Responsibility
Civil	2-1. Graduate Civil Engineer or Construction Manager with a professional engineer registration in the state of Virginia 2-2. 2 years experience in the type of work being performed on this project or technician with 5 years related experience	3-1. Area of Responsibility: Beach fill and breakwater construction. 3-2. Frequency of QC surveillance and inspection will be during installation and including final inspection.
Geotechnical	2-1. Graduate Geotechnical Engineer with a professional engineer registration in the state of Virginia 2-2. 2 years experience in the type of work being performed on this project or technician with 5 years related experience	3-1. Area of Responsibility: Beach fill and breakwater construction. 3-2. Frequency of QC surveillance and inspection will be during installation and including final inspection.

1.7 SUBMITTAL AND DELIVERABLES REVIEW AND APPROVAL

Procedures for submission, review and approval of submittals are described

in Section 01 33 00 SUBMITTAL PROCEDURES. Procedures must include field verification of relevant dimensions and component characteristics by the QC organization prior to submittal being sent to the Contracting Officer. The CQC organization is responsible for certifying that all submittals and deliverables are in compliance with the Contract.

1.8 THREE PHASES OF CONTROL

CQC enables the Contractor to ensure that the construction, including that of subcontractors and suppliers, complies with the requirements of the Contract. At least three phases of control must be conducted by the QC Manager to adequately cover both on-site and off-site work for each definable feature of the construction work as follows:

1.8.1 Preparatory Phase

Document the results of the preparatory phase actions by separate minutes prepared by the QC Manager and attach to the daily CQC report. Instruct applicable workers as to the acceptable level of workmanship required to meet Contract specifications.

Notify the Contracting Officer at least 2 business days in advance of each preparatory phase meeting. The meeting will be conducted by the QC Manager and attended by the QC Specialists, the Project Superintendent, and the foreman responsible for the DFO. When the DFO will be accomplished by a subcontractor, that subcontractor's foreman must attend the preparatory phase meeting. This phase is performed prior to beginning work on each definable feature of work, after all required plans/documents/materials are approved/accepted, and after copies are at the work site. Perform the following prior to beginning work on each DFO:

- a. Review each paragraph of the applicable specification sections, reference codes, and standards. Make available during the preparatory inspection a copy of those sections of referenced codes and standards applicable to that portion of the work to be accomplished in the field. Maintain and make available in the field for use by Government personnel until final acceptance of the work.
- b. Review the Contract drawings.
- c. Verify that field measurements are as indicated on construction or shop drawings or both before confirming product orders, to minimize waste due to excessive materials.
- d. Verify that appropriate shop drawings and submittals for materials and equipment have been submitted and approved. Verify receipt of approved factory test results, when required.
- e. Review the testing plan and ensure that provisions have been made to provide the required QC testing.
- f. Examine the work area to ensure that the required preliminary work has been completed and complies with the Contract and ensure any deficiencies/rework items in the preliminary work have been corrected and confirmed by the Contracting Officer.
- g. Review coordination of product/material delivery to designated prepared areas to execute the work.

- h. Examine the required materials, equipment and sample work to ensure that they are on hand and conform to the approved shop drawings and submitted data and are properly stored.
- i. Check to assure that all materials and equipment have been tested, submitted, and approved.
- j. Discuss specific controls to be used, construction methods, construction tolerances, workmanship standards, and the approach that will be used to provide quality construction by planning ahead and identifying potential problems for each DFOW. Ensure any portion of the plan requiring separate Contracting Officer acceptance has been approved.
- k. Review the APP and appropriate Activity Hazard Analysis (AHA) to ensure that applicable safety requirements are met, and that required Safety Data Sheets (SDS) are submitted.
- l. Discussion of procedures for controlling quality of the work including repetitive deficiencies. Document construction tolerances and workmanship standards for that feature of work.
- m. Discuss schedule and execution of the initial control phase and confirmation or construction quality compliance.

1.8.2 Initial Phase

Notify the Contracting Officer at least 2 business days in advance of each initial phase. When construction crews are ready to start work on a DFOW, conduct the initial phase with the QC Specialists, the Project Superintendent, and the foreman responsible for that DFOW. Observe the initial segment of the DFOW to ensure that the work complies with Contract requirements. Document the results of the initial phase in the daily CQC Report and in the Initial Phase Checklist. Repeat the initial phase for each new crew to work on-site when acceptable levels of specified quality are not being met. Indicate the exact location of initial phase for definable feature of work for future reference and comparison with follow-up phases. Perform the following for each DFOW:

- a. Check work to ensure that it is in full compliance with Contract requirements. Review minutes of the preparatory meeting.
- b. Verify adequacy of controls to ensure full Contract compliance. Verify required control inspection and testing comply with the Contract.
- c. Establish level of workmanship and verify that it meets the minimum acceptable workmanship standards. Compare with required sample panels as appropriate.
- d. Resolve any workmanship issues.
- e. Ensure that testing is performed by the approved laboratory.
- f. Check work procedures for compliance with the APP and the appropriate AHA to ensure that applicable safety requirements are met.
- g. Review project specific work plans (i.e., HAZMAT Abatement, Stormwater Management) to ensure all preparatory work items have been completed

and documented.

1.8.3 Follow-Up Phase

Perform the following for on-going DFOW daily, or more frequently as necessary, until the completion of each DFOW. The Final Follow-Up for any DFOW will clearly note in the daily report the DFOW is completed, and all deficiencies/rework items have been completed in accordance with the paragraph DEFICIENCY/REWORK ITEMS LIST. Each DFOW that has completed the Initial Phase and has not completed the Final Follow-up must be included on each daily report. If no work was performed on that DFOW for the period of that daily report, it must be so noted. Document all Follow-Up activities for DFOWs in the daily CQC Report:

- a. Ensure the work including control testing complies with Contract requirements until completion of that particular work feature. Record checks in the CQC documentation.
- b. Maintain the quality of workmanship required.
- c. Ensure that testing is performed by the approved laboratory.
- d. Ensure that deficiencies/rework items are being corrected. Conduct final follow-up checks and correct all deficiencies prior to the start of additional features of work which may be affected by the deficient work.
- e. Do not build upon nor conceal non-conforming work.
- f. Assure manufacturers' representatives have performed necessary inspections if required and perform safety inspections.

1.8.4 Additional Preparatory and Initial Phases

Conduct additional preparatory and initial phases on the same DFOW if the quality of on-going work is unacceptable, if there are changes in the applicable QC organization, if there are changes in the on-site production supervision or work crew, if work on a DFOW has not started within 45 days of the initial preparatory meeting or has resumed after 45 days of inactivity, or if other problems develop.

1.8.5 Notification of Three Phases of Control for Off-Site Work

Notify the Contracting Officer at least 2 weeks prior to the start of the preparatory and initial phases.

1.8.6 Deficiency/Rework Items List

The QC Manager must maintain a list of work that does not comply with the Contract, identifying what items need to be corrected, the activity ID number associated with the item, the date the item was originally discovered, the date the item will be corrected by, and the date the item was corrected.

The list shall be reviewed at each weekly QC Meeting:

- a. There is no requirement to report a deficiency/rework item that is corrected the same day it is discovered.

- b. No successor task may be advanced beyond the preparatory phase meeting until all deficiencies/rework items have been cleared by the QC Manager and concurred with by the Contracting Officer. This must be confirmed as part of the Preparatory Phase activities.
- c. Attach a copy of the "Deficiency/Rework Items List" to the last daily CQC Report of each month.
- d. The Contractor is responsible for including those items identified by the Contracting Officer.
- e. All deficiencies/rework items must be confirmed as corrected by the QC Manager, and concurred by the Contracting Officer, prior to commencement of any completion inspections per paragraph COMPLETION INSPECTIONS unless specifically exempted by the Contracting Officer.
- f. Non-Compliance with these requirements shall be grounds for removal in accordance with paragraph ACCEPTANCE OF THE QUALITY CONTROL (QC) PLAN.
- g. All delays, concurrent or related to failure to manage, monitor, control, and correct deficiencies/rework items are entirely the responsibility of the Contractor and shall not be made the subject, or any component of any request for additional time or compensation.

1.9 TESTING

Perform specified or required tests to verify that control measures are adequate to provide a product which conforms to Contract requirements. Upon request, furnish to the Government duplicate samples of test specimens for possible testing by the Government. Testing includes operation and acceptance tests when specified. Procure the services of an U.S. Army Corps of Engineers approved testing laboratory or establish an approved testing laboratory at the project site. Perform the following activities and record and provide the following data:

- a. Verify that testing procedures comply with Contract requirements.
- b. Verify that facilities and testing equipment are available and comply with testing standards.
- c. Check test instrument calibration data against certified standards.
- d. Verify that recording forms and test identification control number system, including all test documentation requirements, have been prepared.
- e. Record results of all tests taken, both passing and failing on the CQC report for the date taken. Specification paragraph reference, location where tests were taken, and the sequential control number identifying the test. If approved by the Contracting Officer, actual test reports are submitted later with a reference to the test number and date taken. Provide an information copy of tests performed by an offsite or commercial test facility directly to the Contracting Officer. Failure to submit timely test reports as stated results in nonpayment for related work performed and disapproval of the test facility for this Contract.

1.9.1 Laboratory Accreditation Authorities

All testing laboratories must be validated by the USACE Material Testing Center (MTC) for the tests to be performed. Information on the USACE MTC with web-links to both a list of validated testing laboratories and for the laboratory inspection request for can be found at:
<https://mtc.erdc.dren.mil>

1.9.2 Capability Check

The Contracting Officer retains the right to check laboratory equipment in the proposed laboratory and the laboratory technician's testing procedures, techniques, and other items pertinent to testing, for compliance with the standards set forth in this Contract. Laboratories utilized for testing soils, concrete, asphalt, and steel must meet criteria detailed in ASTM D3740 and ASTM E329.

1.9.2.1 Capability Recheck

If the selected laboratory fails the capability check, the Contractor will reimburse the Government for each succeeding recheck of the laboratory or the checking of a subsequently selected laboratory. Such costs will be deducted from the Contract amount due the Contractor.

1.9.2.2 Onsite Laboratory

The Government reserves the right to utilize the Contractor's control testing laboratory and equipment to make assurance tests, and to check the Contractor's testing procedures, techniques, and test results at no additional cost to the Government.

1.9.3 Test Results

Cite applicable Contract requirements, tests or analytical procedures used. Provide actual results and include a statement that the item tested or analyzed conforms or fails to conform to specified requirements. If the item fails to conform, notify the Contracting Officer immediately. Conspicuously stamp the cover sheet for each report in large red letters "CONFORMS" or "DOES NOT CONFORM" to the specification requirements, whichever is applicable. Test results must be signed by a testing laboratory representative authorized to sign certified test reports. Furnish the signed reports, certifications, and other documentation to the Contracting Officer via the QC Manager.

1.10 COMPLETION INSPECTIONS

1.10.1 Punch-Out Inspection

Near the completion of all work or any increment thereof, established by a completion time stated in the Contract Clause entitled "Commencement, Prosecution, and Completion of Work," or stated elsewhere in the specifications, the QC Manager must conduct an inspection of the work and develop a "punch list" of items which do not conform to the approved drawings, specifications, and Contract. Include in the punch list any remaining items on the "Deficiency/Rework Items List", that were not corrected prior to the Punch-Out Inspection as approved by the Contracting Officer in accordance with the paragraph DEFICIENCY/REWORK ITEMS LIST. Include within the punch list the estimated date by which the deficiencies will be corrected. Provide a copy of the punch list to the Contracting

Officer.

The QC Manager, or staff, must make follow-on inspections to ascertain that all deficiencies have been corrected. All punch list items must be confirmed as corrected by the QC Manager and concurred by the Contracting Officer. Once this is accomplished, notify the Government that the facility is ready for the Government "Pre-Final Inspection".

1.10.2 Pre-Final Inspection

The Government and QC Manager will perform this inspection to verify that the facility is complete and ready to be occupied. A Government "Pre-Final Punch List" will be documented by the QC Manager as a result of this inspection. The QC Manager will ensure that all items on this list are corrected and concurred by the Contracting Officer prior to notifying the Government that a "Final" inspection with the Client can be scheduled. All items noted on the "Pre-Final" inspection must be corrected and concurred by the Contracting Officer in a timely manner and be accomplished before the Contract completion date for the work, or any increment thereof, if the project is divided into increments by separate completion dates unless exceptions are directed by the Contracting Officer.

1.10.3 Final Acceptance Inspection

Notify the Contracting Officer at least 14 calendar days prior to the date a final acceptance inspection can be held. State within the notice that all items previously identified on the pre-final punch list will be corrected and acceptable, along with any other unfinished Contract work, by the date of the final acceptance inspection. The Contractor must be represented by the QC Manager, the Project Superintendent, and others deemed necessary. Attendees for the Government will include the Contracting Officer, other Government QA personnel, and personnel representing the Client. Failure of the Contractor to have all Contract work acceptably complete for this inspection will be cause for the Contracting Officer to bill the Contractor for the Government's additional inspection cost in accordance with the Contract Clause entitled "Inspection of Construction."

1.11 QUALITY CONTROL (QC) CERTIFICATIONS

1.11.1 Contractor Quality Control (CQC) Report Certification

Contain the following statement within the CQC Report: "On behalf of the Contractor, I certify that this report is complete and correct and equipment and material used, and work performed during this reporting period is in compliance with the Contract drawings and specifications to the best of my knowledge, except as noted in this report."

1.11.2 Completion Certification

Upon completion of work under this Contract, the QC Manager must furnish a certificate to the Contracting Officer attesting that "the work has been completed, inspected, tested and is in compliance with the Contract." Provide a copy of this final QC Certification for completion to the preparer of the Operation & Maintenance (O&M) documentation.

1.12 DOCUMENTATION AND INFORMATION FOR THE CONTRACTING OFFICER

Maintain current and complete records of on-site and off-site QC program

operations and activities.

Contact the Contracting Officer for sample forms or print from RMS-QCS as needed. Prior to commencing work on construction, the Contractor must obtain a copy set of the current report forms. The report forms will consist of the Contractor Quality Control (CQC) Report, CQC Report (Continuation Sheet), Contractor Production Report, Contractor Production Report (Continuation Sheet), Preparatory Phase Checklist, Initial Phase Checklist, Testing Plan and Log, and Rework Items List. Unless otherwise provided by the Contracting Officer, Contractor may use the forms provided as related material located at:

https://www.wbdg.org/FFC/NAVGRAPH/01_45_00_quality_control_reports.pdf.

1.12.1 Construction Documentation

Reports are required for each day that work is performed and must be attached to the Contractor Quality Control Report prepared for the same day. Maintain current and complete records of on-site and off-site QC program operations and activities. Reports are required for each day work is performed. Account for each calendar day throughout the life of the Contract.

The Project Superintendent and the QC Manager must prepare and sign the Contractor Production and CQC Reports, respectively. Every space on the forms must be filled in. Use N/A if nothing can be reported in one of the spaces. The reporting of work must be identified by terminology consistent with the construction schedule. In the "Remarks" sections of the reports, enter pertinent information including directions received, problems encountered during construction, work progress and delays, conflicts or errors in the drawings or specifications, field changes, safety hazards encountered, instructions given and corrective actions taken, delays encountered, a record of visitors to the work site, quality control problem areas, deviations from the QC Plan, construction deficiencies encountered, and meetings held. For each entry in the report(s), identify the Schedule Activity No. that is associated with the entered remark.

1.12.2 Quality Control Activities

CQC and Contractor Production reports will be prepared daily to maintain current records providing factual evidence that required quality control activities and tests have been performed. Include in these records the work of subcontractors and suppliers on an acceptable form that includes, as a minimum, the following information:

- a. The name and area of responsibility of the Contractors and any subcontractors.
- b. Operating plant/equipment with hours worked, idle, or down for repair.
- c. Work performed each day, giving location, description, and by whom. When a Network Analysis Schedule (NAS) is used, identify each item of work performed each day by NAS activity number.
- d. Control phase activities performed. Preparatory, and Initial phase Checklists associated with the DFOV referenced to the construction schedule. Follow-up phase activities identified to the DFOV. If testing or specific QC Specialist activities are associated with the Follow-up phase activities for a specific DFOV note this and include

those reports.

- e. Test and control activities performed with results and references to specifications and drawings requirements. Identify the control phase (Preparatory, Initial, Follow-up). List of deficiencies noted, along with corrective action in accordance with the paragraph DEFICIENCY/REWORK ITEMS LIST.
- f. Quantity of materials received at the site with statement as to acceptability, storage, and reference to specifications and drawings requirements.
- g. Submittals and deliverables reviewed, with Contract reference, by whom, and action taken.
- h. Offsite surveillance activities, including actions taken.
- i. Job safety evaluations stating what was checked, results, and instructions or corrective actions.
- j. Instructions given/received and conflicts in plans and specifications.

1.12.3 Verification Statement

Indicate a description of trades working on the project; the number of personnel working; weather conditions encountered; and any delays encountered. Cover both conforming and deficient features and include a statement that equipment and materials incorporated in the work and workmanship comply with the Contract.

Furnish the original and one copy of these records in report form to the Government by 10:00 AM the next working day after the date covered by the report. As a minimum, prepare and submit one report for every 7 days of no work and on the last day of a no work period. All calendar days need to be accounted for throughout the life of the Contract. The first report following a day of no work will be for that day only. Reports need to be signed and dated by the QC Manager. Include copies of test reports and copies of reports prepared by all subordinate quality control personnel within the QC Manager Report.

1.12.4 Reports from the Quality Control (QC) Specialist(s)

Document inspection results on a QC specialist report prepared each day work is performed in their area of responsibility. The report must include a description of the visual inspection or observation performed, a written summary of findings, a conclusion on compliance with the Contract documents, and signature of the QC Specialist. In person inspections must be documented with Video/photographs. Video/photographic documentation of deficiencies must include before and after conditions and physical measurements, as necessary. Forward the QC daily report to the QC Manager who must include the report with the submission of their daily QC Report to the Government each day. Every site visit by the QC Specialist must be documented on a QC Specialist daily report.

1.12.5 Quality Control Validation

Establish and maintain the following in an electronic folder. Divide folder into a series of tabbed sections as shown below. Ensure folder is updated at each required progress meeting.

- a. CQC Meeting minutes in accordance with paragraph QUALITY CONTROL (QC) MEETINGS.
- b. All completed Preparatory and Initial Phase Checklists, arranged by specification section, further sorted by DFOV referenced to the construction schedule. Submit each individual Phase Checklist the day the phase event occurs as part of the CQC daily report.
- c. All milestone inspections, arranged by Activity Number referenced to the construction schedule.
- d. An up-to-date copy of the Testing Plan and Log with supporting field test reports, arranged by specification section referenced to the DFOV to which individual reports results are associated. Individual field test reports will be submitted within 2 working days after the test is performed in accordance with the paragraph QUALITY CONTROL ACTIVITIES.
- e. Copies of all Contract modifications, arranged in numerical order. Also include documentation that modified work was accomplished.
- f. An up-to-date copy of the paragraph DEFICIENCY/REWORK ITEMS LIST.
- g. Upon commencement of Completion Inspections of the entire project or any defined portion, maintain up-to-date copies of all punch lists issued by the QC staff to the Contractor and subcontractors and all punch lists issued by the Government in accordance with the paragraph COMPLETION INSPECTIONS.

1.12.6 Testing Plan and Log

As tests are performed, the QC Manager will record on the "Testing Plan and Log" the date the test was performed and the date the test results were forwarded to the Contracting Officer. Attach a copy of the updated "Testing Plan and Log" to the last daily CQC Report of each month. Provide a copy of the final "Testing Plan and Log" to the preparer of the Operation & Maintenance (O&M) documentation.

1.12.7 As-Built Drawings

The QC Manager must ensure the as-built drawings, required by Section 01 78 00 CLOSEOUT SUBMITTALS are kept current on a daily basis and marked to show deviations which have been made from the Contract drawings. The as-built drawings document shall commence with the QC Manager ensuring all amendments, or changes to the Contract prior to Contract award are accurately noted in the initial document set creating the accurate baseline of the Contract prior to any work starting. Ensure each deviation has been identified with the appropriate modifying documentation (e.g., PC No., Modification No., Request for Information No.). The QC Manager or QC Specialist assigned to an area of responsibility must initial each revision. Upon completion of work, the QC Manager will furnish a certificate attesting to the accuracy of the as-built drawings prior to submission to the Contracting Officer.

1.13 NOTIFICATION ON NON-COMPLIANCE

The Contracting Officer will notify the Contractor of any detected non-compliance with the Contract. Take immediate corrective action after receipt of such notice. Such notice, when delivered to the Contractor at

the work site, is deemed sufficient for the purpose of notification. If the Contractor fails or refuses to comply promptly, the Contracting Officer may issue an order stopping all or part of the work until satisfactory corrective action has been taken. No part of the time lost due to such stop orders will be made the subject of a claim for extension of time for excess costs or damages by the Contractor.

1.14 DELIVERY, STORAGE, AND HANDLING

Designate receiving/storage areas for incoming material to be delivered according to installation schedule and to be placed convenient to work area in order to minimize waste due to excessive materials handling and misapplication. Store and handle materials in a manner as to prevent loss from weather and other damage. Keep materials, products, and accessories covered and off the ground, and store in a dry, secure area. Prevent contact with material that may cause corrosion, discoloration, or staining. Protect all materials and installations from damage by the activities of other trades.

PART 2 PRODUCTS

Not Used

PART 3 EXECUTION

Not Used

-- End of Section --

SECTION 01 45 00.15 10

RESIDENT MANAGEMENT SYSTEM CONTRACTOR MODE (RMS CM)

11/23

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this section to the extent referenced. The publications are referred to within the text by the basic designation only.

U.S. ARMY CORPS OF ENGINEERS (USACE)

EM 385-1-1

(2024) Safety -- Safety and Occupational Health (SOH) Requirements

1.2 MEASUREMENT AND PAYMENT

The work of this section is not measured for payment. The Contractor is responsible for the work of this section, without any direct compensation other than the payment received for contract items.

1.3 CONTRACT ADMINISTRATION

The Government will use the Resident Management System (RMS) to assist in its monitoring and administration of this contract. The Government accesses the system using the Government Mode of RMS (RMS GM) and the Contractor accesses the system using the Contractor Mode (RMS CM). The term RMS will be used in the remainder of this section for both RMS GM and RMS CM. The joint Government-Contractor use of RMS facilitates electronic exchange of information and overall management of the contract. The Contractor accesses RMS to record, maintain, input, track, and electronically share information with the Government throughout the contract period in the following areas:

- Administration
- Finances
- Quality Control
- Submittal Monitoring
- Scheduling
- Closeout
- Import/Export of Data

1.3.1 Correspondence and Electronic Communications

For ease and speed of communications, exchange correspondence and other documents in electronic format to the maximum extent feasible. Some documents such as correspondence, including pay requests and payrolls, may be required in paper format with original signatures. Paper documents will govern in the event of discrepancy with the electronic version. Contracting Officer will determine which documents require submission of paper copies.

1.3.2 Other Factors

Other portions of this document have a direct relationship to the

reporting accomplished through RMS. Particular attention is directed to FAR 52.236-15 Schedules for Construction Contracts; FAR 52.232-27 Prompt Payment for Construction Contracts; FAR 52.232-5 Payments Under Fixed-Price Construction Contracts; Section 01 32 01.00 10 PROJECT SCHEDULE; Section 01 33 00 SUBMITTAL PROCEDURES; Section 01 35 26 GOVERNMENTAL SAFETY REQUIREMENTS; and Section 01 45 00 QUALITY CONTROL.

1.4 RMS SOFTWARE

RMS is a web based application. Download, install and be able to utilize the latest version of RMS within 7 calendar days of receipt of the Notice to Proceed. RMS software, user manuals, access and installation instructions, program updates and training information are available from the RMS website (<https://rms.usace.army.mil>). The Government and the Contractor will have different access authorities to the same contract database through RMS. The common database will be updated automatically each time a user finalizes an entry or change.

1.5 CONTRACT DATABASE - GOVERNMENT

The Government will enter the basic contract award data in RMS prior to granting the Contractor access. The Government entries into RMS will generally be related to submittal reviews, correspondence status, and Quality Assurance(QA)comments, as well as other miscellaneous administrative information.

1.6 CONTRACT DATABASE - CONTRACTOR

Contractor entries into RMS establish, maintain, and update data throughout the duration of the contract. Contractor entries generally include prime and subcontractor information, daily reports, submittals, RFI's, schedule updates and payment requests. RMS includes the ability to import attachments and export reports in many of the modules, including submittals. The Contractor responsibilities for entries in RMS typically include the following items:

1.6.1 Administration

1.6.1.1 Contractor Information

Enter all current Contractor administrative data and information into RMS within 7 calendar days of receiving access to the contract in RMS. This includes, but is not limited to, Contractor's name, address, telephone numbers, management staff, and other required items.

1.6.1.2 Subcontractor Information

Enter all missing subcontractor administrative data and information into RMS CM within seven calendar days of receiving access to the Contract in RMS or within seven calendar days of the signing of the subcontractor agreement for agreements signed at a later date. This includes name, trade, address, phone numbers, and other required information for all subcontractors. A subcontractor is listed separately for each trade to be performed.

1.6.1.3 Correspondence

Identify all Contractor correspondence to the Government with a serial number. Prefix correspondence initiated by the Contractor's site office

with "S". Prefix letters initiated by the Contractor's home (main) office with "H". Letters are numbered starting from 0001. (e.g., H-0001 or S-0001). The Government's letters to the Contractor will be prefixed with "C" or "RFP".

1.6.1.4 Equipment

Enter and maintain a current list of equipment planned for use or being used on the jobsite, including the most recent and planned equipment inspection dates in accordance with Section 01 45 00 QUALITY CONTROL.

1.6.1.5 Reports

Track the status of the project using the reports available in RMS. The value of these reports reflects the quality of the data input. These reports include but are not limited to the Progress Payment Request worksheet, Quality Control (QC) comments, Deficiency Tracking Log, Submittal Register Status, and Three-Phase Control worksheets in accordance with Sections 01 20 00 PRICE AND PAYMENT PROCEDURES, Section 01 32 01.00 10 PROJECT SCHEDULE, 01 33 00 SUBMITTAL PROCEDURES, and 01 45 00 QUALITY CONTROL.

1.6.1.6 Request For Information (RFI)

Create and track all Requests For Information (RFI) in the RMS Administration Module for Government review and response. Provide status at weekly progress meeting in accordance with Section 01 32 01.00 10 PROJECT SCHEDULE.

1.6.2 Finances

1.6.2.1 Pay Activity Data

Develop and enter a list of pay activities in conjunction with the project schedule in accordance with Section 01 32 01.00 10 PROJECT SCHEDULE. The sum of pay activities equals the total Contract amount, including modifications. Each pay activity must be assigned to a Contract Line Item Number (CLIN). The sum of the activities assigned to a CLIN equals the amount of each CLIN.

1.6.2.2 Payment Requests

Prepare all progress payment requests using RMS. Update the work completed under the Contract at least monthly, measured as percent or as specific quantities. After the update, generate a payment request and prompt payment certification using RMS. Submit the signed prompt payment certification and payment request as well as supporting data, either electronically or by hard copy.

1.6.3 Quality Control (QC)

Enter and track implementation of the 3-phase QC Control System, QC testing, transferred and installed property and warranties in RMS. Prepare daily reports, identify and track deficiencies, document progress of work, and support other Contractor QC requirements in RMS. Maintain all data on a daily basis. Ensure that RMS reflects all quality control methods, tests and actions contained within the Contractor Quality Control (CQC) Plan and Government review comments. Provide within seven calendar days of Government acceptance of the CQC Plan.

1.6.3.1 Quality Control (QC) Reports

The Contractor's Quality Control (QC) Daily Report in RMS is the official report. The Contractor can use other supplemental formats to record QC data, but information from any supplemental formats are to be consolidated and entered into the RMS QC Daily Report. Any supplemental information may be entered into RMS as an attachment to the report. QC Daily Reports must be finalized and signed in RMS within 24 hours after the date covered by the report. Provide the Government a printed signed copy of the QC Daily Report, unless waived by the Contracting Officer.

1.6.3.2 Deficiency Tracking.

Use the QC Daily Report Module to enter and track deficiencies. Deficiencies identified and entered into RMS by the Contractor or the Government will be sequentially numbered with a QC or QA prefix for tracking purposes. Enter each deficiency into RMS the same day that the deficiency is identified. Monitor, track and resolve all QC and QA entered deficiencies. A deficiency is not considered to be corrected until the Government indicates concurrence in RMS.

1.6.3.3 Three-Phase Control Meetings

Maintain scheduled and actual dates and times of preparatory and initial control meetings in RMS, and upload meeting minutes of the meetings. Worksheets for the three-phase control meetings are generated within RMS.

1.6.3.4 Labor and Equipment Hours

Enter labor and equipment exposure hours on a daily basis. Roll up the labor and equipment exposure data into a monthly exposure report.

1.6.3.5 Accident/Safety Reporting

Both the Contractor and the Government enter safety related comments in RMS as a deficiency. The Contractor must monitor, track and show resolution for safety issues in the QC Daily Report area of the RMS QC Module. In addition, follow all reporting requirements for accidents and incidents as required in EM 385-1-1, Section 01 35 26 GOVERNMENTAL SAFETY REQUIREMENTS and as required by any other applicable Federal, State or local agencies.

1.6.3.6 Definable Features of Work

Enter each feature of work, as defined in the approved CQC Plan, into the RMS QC Module. A feature of work may be associated with a single or multiple pay activities, however a pay activity is only to be linked to a single feature of work.

1.6.3.7 Activity Hazard Analysis

Import activity hazard analysis electronic document files into the RMS QC Module utilizing the document package manager. Prepare activity hazard analysis in accordance with Section 01 35 26 GOVERNMENT SAFETY REQUIREMENTS.

1.6.4 Submittal Management

Enter all current submittal register data and information within the time frame directed by the Contracting Officer. The Contractor will import the information shown in the submittal register following the specification Section 01 33 00 SUBMITTAL PROCEDURES unless otherwise directed by the Contracting Officer. Group electronic submittal documents into transmittal packages to send to the Government, except very large electronic files, samples, spare parts, mock ups, color boards, or where hard copies are specifically required. Track transmittals and update the submittal register in RMS on a daily basis throughout the duration of the Contract. Submit hard copies of all submittals unless waived by the Contracting Officer.

Contractor may request submittals to be added to RMS throughout the lifecycle of the project. Approval/disapproval of Contractor requests is at the discretion of the Contracting Officer. Submittals entry into RMS must be updated daily or as practical for performance of the Contract, as approved by the Contracting Officer.

1.6.5 Schedule

Enter and update the contract project schedule in RMS by either manually entering all schedule data or by importing the Standard Data Exchange Format (SDEF) file, based on the requirements in Section 01 32 01.00 13 PROJECT SCHEDULE.

1.6.6 Closeout

Closeout documents, processes and forms are managed and tracked in RMS by both the Contractor and the Government. Ensure that all closeout documents are entered, completed and documented within RMS.

1.7 IMPLEMENTATION

Use of RMS as described in the preceding paragraphs is mandatory. Ensure that sufficient resources are available to maintain contract data within the RMS system. RMS is an integral part of the Contractor's required management of quality control.

1.8 NOTIFICATION OF NONCOMPLIANCE

Take corrective action within seven calendar days after receipt of notice of RMS non-compliance by the Contracting Officer.

PART 2 PRODUCTS

Not Used

PART 3 EXECUTION

Not Used

-- End of Section --

SECTION 01 50 00

TEMPORARY CONSTRUCTION FACILITIES AND CONTROLS

11/20, CHG 2: 08/22

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 70 (2023) National Electrical Code

NFPA 241 (2022) Standard for Safeguarding Construction, Alteration, and Demolition Operations

U.S. ARMY CORPS OF ENGINEERS (USACE)

EM 385-1-1 (2024) Safety -- Safety and Occupational Health (SOH) Requirements

U.S. FEDERAL HIGHWAY ADMINISTRATION (FHWA)

MUTCD (2009; Rev 2012) Manual on Uniform Traffic Control Devices

1.2 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for information only. When used, a code following the "G" classification identifies the office that will review the submittal for the Government. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Construction Site Plan; G, R0

Traffic Control Plan; G, R0

Haul Road Plan; G, D0

1.3 CONSTRUCTION SITE PLAN

Prior to the start of work, submit for Government approval a site plan showing the locations and dimensions of temporary facilities (including layouts and details, laydown areas, equipment and material storage area (onsite and offsite), and access and haul routes, avenues of ingress/egress to the fenced area and details of the fence installation. Identify any areas which may have to be graveled to prevent the tracking of mud. Indicate if the use of a supplemental or other staging area is desired. Show locations of safety and construction fences, site trailers,

construction entrances, trash dumpsters, temporary sanitary facilities, and worker parking areas.

1.4 DOD CONDITION OF READINESS (COR)

DOD will set the Condition of Readiness (COR) based on the weather forecast for sustained winds 50 knots (58 mph) or greater. Contact the Contracting Officer for the current COR setting.

Monitor weather conditions a minimum of twice a day and take appropriate actions according to the approved Emergency Plan in the accepted Accident Prevention Plan, EM 385-1-1 Section 01 Emergency Planning and the instructions below.

Unless otherwise directed by the Contracting Officer, comply with:

- a. Condition FOUR (Sustained winds of 58 mph or greater expected within 72 hours): Normal daily jobsite cleanup and good housekeeping practices. Collect and store in piles or containers scrap lumber, waste material, and rubbish for removal and disposal at the close of each work day. Maintain the construction site including storage areas, free of accumulation of debris. Stack form lumber in neat piles less than 3.3 feet high. Remove all debris, trash, or objects that could become missile hazards. Review requirements pertaining to "Condition THREE" and continue action as necessary to attain "Condition FOUR" readiness. Contact Contracting Officer for weather and COR updates and completion of required actions.
- b. Condition THREE (Sustained winds of 58 mph or greater expected within 48 hours): Maintain "Condition FOUR" requirements and commence securing operations necessary for "Condition ONE" which cannot be completed within 18 hours. Cease all routine activities which might interfere with securing operations. Commence securing and stow all gear and portable equipment. Make preparations for securing buildings. Reinforce or remove formwork and scaffolding. Secure machinery, tools, equipment, materials, or remove from the jobsite. Expend every effort to clear all missile hazards and loose equipment from general base areas. Contact Contracting Officer for weather and COR updates and completion of required actions. Review requirements pertaining to "Condition TWO" and continue action as necessary to attain "Condition THREE" readiness.
- c. Condition TWO (Sustained winds of 58 mph or greater expected within 24 hours): Secure the jobsite, and leave Government premises.
- d. Condition ONE. (Sustained winds of 58 mph or greater expected within 12 hours): Contractor access to the jobsite and Government premises is prohibited.

PART 2 PRODUCTS

2.1 TEMPORARY SIGNAGE

2.1.1 Bulletin Board

Within one calendar day of mobilization on site and prior to the commencement of work activities, provide a clear weatherproof covered bulletin board not less than 36 by 48 inches in size for displaying the Equal Employment Opportunity poster, a copy of the wage decision contained

in the Contract, Wage Rate Information poster, Safety and Health Information as required by EM 385-1-1 Section 01 and other information approved by the Contracting Officer. Coordinate requirements herein with 01 35 26 GOVERNMENTAL SAFETY REQUIREMENTS. Locate the bulletin board at the project site in a conspicuous place easily accessible to all employees, and in location as approved by the Contracting Officer.

2.1.2 Project Identification Signs

The requirements for the signs, their content, and location are as indicated and as specified in Section 01 58 00 PROJECT IDENTIFICATION. Erect signs within 15 days after receipt of the notice to proceed. Correct the data required by the safety sign daily, with light colored metallic or non-metallic numerals.

2.1.3 Warning Signs

Post temporary signs, tags, and labels to give workers and the public adequate warning and caution of construction hazards according to the EM 385-1-1 Section 04. Attach signs to the perimeter fencing every 150 feet warning the public of the presence of construction hazards. Signs must require unauthorized persons to keep out of the construction site. Correct the data required by safety signs daily. Post signs at all points of entry designating the construction site as a hard hat area.

2.2 TEMPORARY TRAFFIC CONTROL

2.2.1 Haul Roads

Construct access and haul roads necessary for proper prosecution of the work under this Contract in accordance with EM 385-1-1 Section 04. Construct with suitable grades and widths; avoid sharp curves, blind corners, and dangerous cross traffic. Submit haul road plan for approval. Provide necessary lighting, signs, barricades, and distinctive markings for the safe movement of traffic. The method of dust control, although optional, must be adequate to ensure safe operation at all times. Location, grade, width, and alignment of construction and haul roads are subject to approval by the Contracting Officer. Lighting must be adequate to assure full and clear visibility for full width of haul road and work areas during any night work operations.

2.2.2 Barricades

Erect and maintain temporary barricades to limit public access to hazardous areas. Barricades are required whenever safe public access to paved areas such as roads, parking areas or sidewalks is prevented by construction activities or as otherwise necessary to ensure the safety of both pedestrian and vehicular traffic. Securely place barricades clearly visible with adequate illumination to provide sufficient visual warning of the hazard during both day and night.

2.3 TEMPORARY WIRING

Provide temporary wiring in accordance with EM 385-1-1 Section 11, NFPA 241 and NFPA 70. Include monthly inspection and testing of all equipment and apparatus.

PART 3 EXECUTION

3.1 EMPLOYEE PARKING

Construction Contract employees must park privately owned vehicles in an area designated by the Contracting Officer. This area will be within reasonable walking distance of the construction site. Employee parking must not interfere with existing and established parking requirements of the Government installation.

3.2 AVAILABILITY AND USE OF UTILITY SERVICES

3.2.1 Temporary Utilities

Provide temporary utilities required for construction. Materials may be new or used, must be adequate for the required usage, not create unsafe conditions, and not violate applicable codes and standards.

3.2.2 Temporary Connections

At the Contractor's expense and in manner satisfactory to the Contracting Officer, maintain necessary temporary connections and distribution lines. Contractor is responsible for connections of power to the available power source.

3.2.3 Electricity

Electrical services can be provided to the Contractor upon request to the COR from NASA. This electrical energy will be made available to the Contractor from the NASA distribution system at the nearest location where such capacity is available; and, at the option of the Contracting Officer will be supplied at 3 phase, 4 wire, 120/208 volts or 3 wire 440 volts. The Contractor shall provide a disconnect switch suitably protected from the weather and properly fused. The Contractor will be responsible for connect to the available power source, however outage support will be provided by NASA at no additional cost.

Requests for electrical outages shall be submitted, in writing, to the Contracting Officer at least 2 weeks in advance of the period for which the outage is sought, which, as far as practicable, should be limited to the period between 12:00 midnight on Fridays and 10:00 p.m. on the following Sunday.

Outages will be permitted by the Contracting Officer or COR only at times when they will result in minimum interference with research activities, and when adequate labor, equipment and materials are available for restoration of service. The Contractor shall not receive additional payment for such operations required to be performed outside the regular work hours.

3.2.4 Water and Wastewater Services

Water and wastewater services to the existing NASA systems are not available. The Contractor is responsible for wastewater collection and proper disposal off site.

Provide and maintain within the construction area minimum field-type sanitary facilities in accordance with EM 385-1-1 Section 02. Locate the

facilities behind the construction fence or out of the public view. Clean units and empty wastes at least once a week or more frequently into a municipal, district, or station sanitary sewage system, or remove waste to a commercial facility. Obtain approval from the system owner prior to discharge into a municipal, district, or commercial sanitary sewer system. Penalties or fines associated with improper discharge will be the responsibility of the Contractor. Coordinate with the Contracting Officer and follow station regulations and procedures when discharging into the station sanitary sewer system. Maintain these conveniences at all times. Include provisions for pest control and elimination of odors. Government toilet facilities will not be available to Contractor's personnel.

3.2.5 Telephone

The Government will not provide the Contractor with telephone services. Make arrangements and pay all costs for telephone facilities desired. Removal of such utilities at contract completion shall be at the Contractor's expense subject to the approval of the Contracting Officer.

3.2.6 Fire Protection

Provide temporary fire protection equipment for the protection of personnel and property during construction. Remove debris and flammable materials weekly to minimize potential hazards.

3.3 STATION OPERATION AFFECT ON CONTRACTOR OPERATIONS

Construction of other projects on Wallops Flight Facility are ongoing. Increased traffic and congestion may occur due to the additional construction activities and local facility traffic.

Construction of new facility and launch pads are anticipated within the vicinity of the project site and laydown areas. Other contractors are expected to be working in nearby areas. Contractor shall deconflict all work, traffic, deliveries, materials, equipment, and staging from interfering in the work of other contractors.

Launch activities are expected to impact the Contractor's operations throughout the life of the project. During these times, Wallops Flight Facility may set physical blockades (i.e. road and traffic blocks) to secure certain areas. Contractor's equipment can remain in these areas. Instructions will be given ahead of time from NASA once known.

3.3.1 Restricted Access Areas

Work will be occurring in active launch and hazardous operations range. Restrictions can vary depending on the operation (i.e. different classes of launch vehicles, type of hazardous activity - such as pre-launch, transportation of launch vehicles, working on the launch vehicles on pads, launch, etc.). Restrictions will be communicated to the Contractor once known.

3.4 TRAFFIC PROVISIONS

3.4.1 Maintenance of Traffic

- a. Conduct operations in a manner that will not close a thoroughfare or interfere with traffic on railways or highways except with written permission of the Contracting Officer at least 15 calendar days prior

to the proposed modification date, and provide a Traffic Control Plan for Government approval detailing the proposed controls to traffic movement for approval. The plan must be in accordance with State and local regulations and the MUTCD, Part VI. Make all notifications and obtain all permits required for modification to traffic movements outside Station's jurisdiction. Contractor may move oversized and slow-moving vehicles to the worksite provided requirements of the highway authority have been met.

- b. Conduct work so as to minimize obstruction of traffic, and maintain traffic on at least half of the roadway width at all times unless previously coordinated with the NASA Wallops Facility Engineering Office and appropriate NASA Wallops Officials. Obtain approval from the Contracting Officer prior to starting any activity that will obstruct traffic.
- c. Provide, erect, and maintain, at Contractor's expense, lights, barriers, signals, passageways, detours, and other items, that may be required by the Life Safety Signage, overhead protection authority having jurisdiction.
- d. Provide cones, signs, barricades, lights, or other traffic control devices and personnel required to control traffic. Do not use foil-backed material for temporary pavement marking because of its potential to conduct electricity during accidents involving downed power lines.

3.4.2 Protection of Traffic

Maintain and protect traffic on all affected roads during the construction period except as otherwise specifically directed by the Contracting Officer. Measures for the protection and diversion of traffic, including the provision of watchmen and flagmen, erection of barricades, placing of lights around and in front of equipment the work, and the erection and maintenance of adequate warning, danger, and direction signs, will be as required by the State and local authorities having jurisdiction. Provide self-illuminated (lighted) barricades during hours of darkness. Brightly-colored (orange) vests are required for all personnel working in roadways. Protect the traveling public from damage to person and property. Minimize the interference with public traffic on roads selected for hauling material to and from the site. Investigate the adequacy of existing roads and their allowable load limit. Contractor is responsible for the repair of damage to roads caused by construction operations.

3.4.3 Vehicle and Pedestrian Rules

Follow all posted signs and speed limits for vehicle and pedestrian traffic. Follow ingress and egress routes identified on the for access to the beach. All vehicle and pedestrian activities shall be related to the project only.

3.4.4 Dust Control

Dust control methods and procedures must be approved by the Contracting Officer. Coordinate dust control methods with 01 57 19 TEMPORARY ENVIRONMENTAL CONTROLS.

3.5 CONTRACTOR'S TEMPORARY FACILITIES

The Contractor must provide their own construction trailer(s) and an area with available power will be provided by NASA. Contractor-owned or -leased trailers must be identified by Government assigned numbers. Size and location of the number will comply with installation requirements. These plans will need to be submitted by the Contractor and approved by the Contracting Officer. Apply the number to the trailer within 14 calendar days of notification, or sooner, if directed by the Government. Temporary facilities must meet requirements as identified in EM 385-1-1 Section 04.

Contractor is responsible for security of their property. Provide adequate outside security lighting at the temporary facilities. Trailers must be anchored to resist high winds and meet applicable state or local standards for anchoring mobile trailers. Coordinate anchoring with EM 385-1-1 Section 04. The Contract Clause entitled "FAR 52.236-10, Operations and Storage Areas" and the following apply:

3.5.1 Safety

Protect the integrity of any installed safety systems or personnel safety devices. If entrance into systems serving safety devices is required, the Contractor must obtain prior approval from the Contracting Officer. If it is temporarily necessary to remove or disable personnel safety devices in order to accomplish contract requirements, provide alternative means of protection prior to removing or disabling any permanently installed safety devices or equipment and obtain approval from the Contracting Officer.

3.5.2 Administrative Field Offices

Provide and maintain administrative field office facilities within the construction area at the designated site. Government office and warehouse facilities will not be available to the Contractor's personnel.

3.5.3 Quality Control Manager Records and Field Office

Provide on the jobsite an office with approximately 200 square feet of useful floor area for the exclusive use of the QC Manager. Provide a weathertight structure with adequate heating and cooling, toilet facilities, lighting, ventilation, a 4 by 8 foot plan table, a standard size office desk and chair, computer station, and working communications facilities. Provide either a 1,500 watt radiant heater and a window-mounted air conditioner rated at 9,000 Btus minimum or a window-mounted heat pump of the same minimum heating and cooling ratings. Provide a door with a cylinder lock and windows with locking hardware. Make utility connections. Locate as directed and approved. File quality control records in the office and make available at all times to the Government. After completion of the work, remove the entire structure from the site.

3.5.4 Laydown and Staging Areas

Determine laydown and staging areas from the areas identified on the construction drawings. Additional laydown areas not shown on construction drawings may be considered upon approval from the COR and NASA. See 01 14 00 WORK RESTRICTIONS for details about Additional Laydown Areas Usage.

Laydown and staging areas shall not impact any wetlands and shall use the appropriate erosion and sediment control measures, per the latest edition of the Virginia Stormwater Management Handbook.

3.5.5 Appearance of Trailers

- a. Trailers must be roadworthy and comply with all appropriate state and local vehicle requirements. Trailers which are rusted, have peeling paint or are otherwise in need of repair will not be allowed on Installation property. Trailers must present a clean and neat exterior appearance and be in a state of good repair.
- b. Maintain the temporary facilities. Failure to do so will be sufficient reason to require their removal at the Contractor's expense.

3.5.6 Trailers or Storage Buildings

Trailers or storage buildings will be permitted, where space is available, subject to the approval of the Contracting Officer. The trailers or buildings shall be in good condition, free from visible damage rust and deterioration, and meet all applicable safety requirements. Trailers shall be roadworthy and comply with all appropriate state and local vehicle requirements. Failure to maintain storage trailers or buildings to these standards shall result in the removal of non-complying units at the Contractor's expense. A sign not smaller than 24 by 24 inches shall be conspicuously placed on the trailer depicting the company name, business phone number, and emergency phone number. Trailers shall be anchored to resist high winds and must meet applicable state or local standards for anchoring mobile trailers.

3.5.7 Maintenance of Storage Area

- a. Grassed or unpaved areas, which are not established roadways, will be covered with a layer of gravel as necessary or wooden dunnage for sandy areas to prevent rutting and the tracking of mud onto paved or established roadways, should the Contractor elect to traverse them with construction equipment or other vehicles; gravel gradation will be at the Contractor's discretion. Mow and maintain grass located within the boundaries of the construction site for the duration of the project. Grass and vegetation under trailers, and in areas not accessible to mowers will be edged or trimmed neatly.
- b. Cut grass (or annual weeds) within the construction and storage sites to a maximum 4 inch height at least once every two weeks during the growing season unless the grass area is not visible to the public. Maintain grass or weeds on stockpiled earth as described above.

3.5.8 Security Provisions

Provide adequate outside security lighting at the Contractor's temporary facilities. The Contractor will be responsible for the security of its own equipment. In addition, the Contractor will notify the appropriate law enforcement agency and request periodic security checks of the temporary project field office.

3.5.9 Safety Systems

Protect the integrity of all installed safety systems or personnel safety devices. Obtain prior approval from the Contracting Officer if entrance

into systems serving safety devices is required. If it is temporarily necessary to remove or disable personnel safety devices in order to accomplish Contract requirements, provide alternative means of protection prior to removing or disabling any permanently installed safety devices or equipment and obtain approval from the Contracting Officer.

3.5.10 Weather Protection of Temporary Facilities and Stored Materials

Take necessary precautions to ensure that roof openings and other critical openings in the building are monitored carefully. Take immediate actions required to seal off such openings when rain or other detrimental weather is imminent, and at the end of each workday. Ensure that the openings are completely sealed off to protect materials and equipment in the building from damage.

3.5.10.1 Building and Site Storm Protection

When a warning of gale force winds is issued, take precautions to minimize danger to persons, and protect the work and nearby Government property. Precautions must include, but are not limited to, closing openings; removing loose materials, tools and equipment from exposed locations; and removing or securing scaffolding and other temporary work. Close openings in the work when storms of lesser intensity pose a threat to the work or any nearby Government property.

3.5.10.2 Hurricane Condition of Readiness

Unless directed otherwise, comply with:

- a. Condition FOUR (Sustained winds of 50 knots or greater expected within 72 hours): Normal daily jobsite cleanup and good housekeeping practices. Collect and store in piles or containers scrap lumber, waste material, and rubbish for removal and disposal at the close of each work day. Maintain the construction site including storage areas, free of accumulation of debris. Stack form lumber in neat piles less than 4 feet high. Remove all debris, trash, or objects that could become missile hazards. Contact Contracting Officer for Condition Requirements.
- b. Condition THREE (Sustained winds of 50 knots or greater expected within 48 hours): Maintain "Condition FOUR" requirements and commence securing operations necessary for "Condition ONE" which cannot be completed within 18 hours. Cease all routine activities which might interfere with securing operations. Commence securing and stow all gear and portable equipment. Make preparations for securing buildings. Review requirements pertaining to "Condition TWO" and continue action as necessary to attain "Condition THREE" readiness. Contact Contracting Officer for weather and COR updates and completion of required actions.

3.6 GOVERNMENT FIELD OFFICE

3.6.1 Office Space Requirements

1. Area Engineer's Personal Office: Approximately 200 square feet in floor area (1 person). Include a video board of at least 60 inches for presentations and video conferencing. The Contractor will provide signage for the door, labeling the title ("Area Engineer") and the name of the occupant.

Office includes executive:

- a. One (1) bookcase.
- b. Six (6) chair.
- c. One (1) conference table for 4
- d. One (1) motorized standing desk.
- e. One (1) computer chair.
- f. One (1) 3'x4' whiteboard.
- g. One (1) 3'x4' corkboard.
- h. One (1) trashcan.

2. Conference Room: Approximately 300 square feet in floor area. (Flexible seating for up to 20 people). Include a video board of at least 60 inches for presentations and video conferencing. The Contractor will provide signage for the door, labeling the room as "Conference Room." Include a conference table and chairs.
3. Additional Offices: Eight (8) offices, each approximately 100 square feet in floor area (8 people, with 1 person per office).

Each office includes professional:

- a. One (1) bookcase.
- b. One (1) chair.
- c. One (1) motorized standing desk.
- d. One (1) computer chair.
- e. One (1) 3'x4' whiteboard.
- f. One (1) 3'x4' corkboard.
- g. One (1) trashcan.
- h. One (1) sign for each door, labeling the title and the name of the occupant.

4. Plan Storage: Provide a dedicated space or room that includes plans table that can accommodate at least Arch D size drawings (24" x 36"). Include adequate storage for rolled or folded drawings, as well as proper lighting for reviewing plans.

3.6.1.1 Shared Amenities

1. Break Area: Approximately 200 square feet in floor area. Include a refrigerator, microwave, coffee maker, cabinets, sink, tables, and chairs.
2. Toilet Facilities: Separate facilities for men and women, each consisting of one lavatory and one water closet complete with connections to water and sewer mains.
3. Provide heat, air conditioning, lighting, power for a computer, Internet service, refrigerator, microwave, and a mail slot or lockable mailbox.

3.6.1.2 Video Boards

Provide video boards of at least 60 inches in the Area Engineer's personal office, conference room, and welcome desk station. Video boards should support presentations, video conferencing, and displaying important project information.

3.6.1.3 Temporary Facilities

Prior to the start of work, submit for Government approval a site plan showing the locations and dimensions of temporary facilities. Include layouts, details, equipment and material storage areas (onsite and offsite), access and haul routes, avenues of ingress/egress to the fenced area, and details of the fence installation.

3.6.1.4 Sanitary Facilities

Provide adequate sanitary facilities, including portable toilets and handwashing stations, for Construction Contract employees at the project site. Locate the facilities as approved by the Contracting Officer.

3.6.1.5 Bulletin Board

Provide a bulletin board at the project site in a conspicuous place easily accessible to all employees, and in a location approved by the Contracting Officer. The bulletin board should be not less than 36 by 48 inches in size and weatherproof.

3.6.1.6 Site Plan

Prior to the start of work, submit for Government approval a site plan showing the locations and dimensions of temporary facilities, as described in Section 3.6.1.7 Architectural Model. The site plan should be drawn to a suitable scale and include relevant details, as required by the Contracting Officer.

3.6.1.7 Parking

Provide a parking area designated by the Contracting Officer for Construction Contract employees. The parking area should accommodate a minimum of 50 vehicles and must not interfere with existing and established parking requirements of the Government installation. Include the following amenities in the parking area:

1. EV Charging Stations: Install one (1) electric vehicle (EV) charging stations, provided by the Contractor. The charging stations should be Level 2 (240V) or higher, with a minimum charging capacity of 7.2 kW each.
2. Lighting: Provide adequate outside security lighting at the parking area.
3. Signage: Install appropriate signage to designate the parking area, EV charging stations, and any other relevant information.

3.6.1.8 Utilities

Utilities must be connected and disconnected in accordance with local codes and to the satisfaction of the Contracting Officer. Compliance with safety and appearance requirements for temporary facilities stated in previous paragraphs is required.

3.6.1.9 Signage

1. Door Signage: The Contractor will provide signage for each office door, clearly labeling the title and the name of the occupant. Signage

should be professional in appearance and easily readable.

2. Project Identification Signs: Erect signs within 15 days after receipt of the notice to proceed, as indicated in Section 2.1.2.
3. Warning Signs: Post temporary signs, tags, and labels to give workers and the public adequate warning and caution of construction hazards according to EM 385-1-1.

3.6.1.10 Internet Service and Equipment

Provide the following for setting up Communications in the Office:

- a. Provide a High-Speed Business Internet line with Speeds of Up to 200 Mbps download and Up to 20 Mbps upload with connectivity brought into the dedicated communications room.
- b. Provide router/modem to connect to the High Speed Business internet line with additional wireless access and a 24-port network switch to connect to the router/modem to provide additional ethernet ports for devices that need to be hardwired to have connection back to Norfolk District. This equipment will be located in the dedicated communications room
- c. Provide a floor or wall mounted rack for IT equipment and adequate power, lighting and cooling for the room and a UPS backup power supply for IT equipment (minimum of 1500VA w/10 outlet).
- d. Installed at each workstation shall be (2) Category 5e or Category 6 cables, unshielded twisted pair (UTP) plenum rated 24 AWG extended frequency LAN cable (one for voice and one for data) to include two RJ45 and faceplate jacks.
- e. All cable runs shall be continuous from the communications room to the workstation faceplate jack. Data cables shall be terminated to a patch panel rack that can hold 70-90 data lines in the communications room and all data cables shall be tested for Category 5e or Category 6 compliance with a cable test set. Any cables that fail testing shall be repaired or replaced and retested for compliance.
- f. Voice cable shall be terminated on either "66" blocks or "110" blocks for 70-90 voice lines. All data and voice cabling shall be properly labeled at both ends of the wire and labeled on the face of the patch panel and the at a jack faceplate.
- g. All communication outlets shall be terminated back to the communications room and tested for straight through connectivity.
- h. Provide a dedicated phone service to accommodate building occupancy, data, and fax machines. The phone system shall include as a minimum voice mail, conference calls, hands free and transfer capability as determined and established by the Contracting Officer. The office shall have 9 interconnected phones (2 phone lines) and 22 high speed Internet connections, one connection dedicated to the multi-function printer/scanner/fax machines. One phone line and one data connection shall be supplied to each office and modular work space.

3.6.1.11 Janitorial Service

Janitorial service shall be provided twice a week to include vacuuming floors, dusting work areas, emptying trash, and cleaning the restrooms and kitchen. The Contractor is also responsible for maintaining a clean and neat exterior appearance at all times and providing lawn maintenance and grass cutting services once a week.

3.6.1.12 Electric Vehicle Parking

The Contractor shall furnish, set-up, and maintain and mark for "Official Government Use Only", one (1) parking space with a Level 2 (208-240V) electric vehicle charging station capable of providing a minimum of 30 miles range per charging hour.

3.6.2 Trailer-Type Mobile Office

The option is available to, furnish and maintain a trailer-type mobile office acceptable to the Contracting Officer to meet the requirements of the minimum facilities specified above. Securely anchor the trailer to the ground at all four corners to guard against movement during high winds. Coordinate requirements for proper anchoring with EM 385-1-1 Section 04.

3.7 PLANT COMMUNICATIONS

Whenever the individual elements of the plant are located so that operation by normal voice between these elements is not satisfactory, install a satisfactory means of communication, such as telephone or other suitable devices and make available for use by Government personnel.

3.8 CLEANUP

Remove construction debris, waste materials, packaging material and the like from the work site daily. Any dirt or mud which is tracked onto paved or surfaced roadways must be cleaned away. Store all salvageable materials resulting from demolition activities within the fenced area described above or at the supplemental storage area. Neatly stack stored materials not in trailers, whether new or salvaged.

3.9 RESTORATION OF AREAS

Upon completion of the project remove the bulletin board, signs, barricades, haul roads, and all other temporary products from the site. After removal of trailers, materials, and equipment from within the fenced area, remove the fence. Restore areas used during the performance of the Contract to the original or better condition. Remove gravel used to traverse grassed areas and restore the area to its original condition, including top soil and seeding as necessary.

3.9.1 Laydown and Staging Areas

Laydown and staging areas used shall be graded and established with seeding at the end of the construction to original condition. Areas may be left 'as-is' after construction if improvements were made and/or if additional parking/storage space is created (i.e. compacted aggregate). Areas to be left in 'as-is' condition shall be at the discretion of NASA.

-- End of Section --

DRAFT
NOT FOR CONSTRUCTION

SECTION 01 57 19

TEMPORARY ENVIRONMENTAL CONTROLS

08/22

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

1.2 DEFINITIONS

1.2.1 Class I and II Ozone Depleting Substance (ODS)

Class I ODS is defined in Section 602(a) of The Clean Air Act. A list of Class I ODS can be found on the EPA website at the following weblink.
<https://www.epa.gov/ozone-layer-protection/ozone-depleting-substances>.

Class II ODS is defined in Section 602(s) of The Clean Air Act. A list of Class II ODS can be found on the EPA website at the following weblink.
<https://www.epa.gov/ozone-layer-protection/ozone-depleting-substances>.

1.2.2 Contractor Generated Hazardous Waste

Contractor generated hazardous waste is materials that, if abandoned or disposed of, may meet the definition of a hazardous waste. These waste streams would typically consist of material brought on site by the Contractor to execute work, but are not fully consumed during the course of construction. Examples include, but are not limited to, excess paint thinners (i.e., methyl ethyl ketone, toluene), waste thinners, excess paints, excess solvents, waste solvents, excess pesticides, and contaminated pesticide equipment rinse water.

1.2.3 Electronics Waste

Electronics waste is discarded electronic devices intended for salvage, recycling, or disposal.

1.2.4 Environmental Pollution and Damage

Environmental pollution and damage is the presence of chemical, physical, or biological elements or agents which adversely affect human health or welfare; unfavorably alter ecological balances of importance to human

life; affect other species of importance to humankind; or degrade the environment aesthetically, culturally or historically.

1.2.5 Environmental Protection

Environmental protection is the prevention/control of pollution and habitat disruption that may occur to the environment during construction. The control of environmental pollution and damage requires consideration of land, water, and air; biological and cultural resources; and includes management of visual aesthetics; noise; solid, chemical, gaseous, and liquid waste; radiant energy and radioactive material as well as other pollutants.

1.2.6 Hazardous Debris

As defined in paragraph SOLID WASTE, debris that contains listed hazardous waste (either on the debris surface, or in its interstices, such as pore structure) in accordance with 40 CFR 261. Hazardous debris also includes debris that exhibits a characteristic of hazardous waste in accordance with 40 CFR 261.

1.2.7 Hazardous Materials

Hazardous material is any material that: Is defined in 49 CFR 171, listed in 49 CFR 172, regulated as a hazardous material in accordance with 49 CFR 173; or requires a Safety Data Sheet (SDS) in accordance with 29 CFR 1910.1200; or during end use, treatment, handling, packaging, storage, transportation, or disposal meets or has components that meet or have potential to meet the definition of a hazardous waste as defined by 40 CFR 261 Subparts A, B, C, or D. Designation of a material by this definition, when separately regulated or controlled by other sections or directives, does not eliminate the need for adherence to that hazard-specific guidance which takes precedence over this section for "control" purposes. Such material includes ammunition, weapons, explosive actuated devices, propellants, pyrotechnics, chemical and biological warfare materials, medical and pharmaceutical supplies, medical waste and infectious materials, bulk fuels, radioactive materials, and other materials such as asbestos, mercury, and polychlorinated biphenyls (PCBs).

1.2.8 Hazardous Waste

Hazardous Waste is any material that meets the definition of a solid waste and exhibits a hazardous characteristic (ignitability, corrosivity, reactivity, or toxicity) as specified in 40 CFR 261, Subpart C, or contains a listed hazardous waste as identified in 40 CFR 261, Subpart D, or meets a state, local, or host nation definition of a hazardous waste.

1.2.9 Land Application

Land Application means spreading or spraying discharge water at a rate that allows the water to percolate into the soil. No sheeting action, soil erosion, discharge into storm sewers, discharge into defined drainage areas, or discharge into the "waters of the United States" must occur. Comply with federal, state, and local laws and regulations.

1.2.10 Municipal Separate Storm Sewer System (MS4) Permit

MS4 permits are those held by municipalities or installations to obtain NPDES permit coverage for their stormwater discharges.

1.2.11 National Pollutant Discharge Elimination System (NPDES)

The NPDES permit program controls water pollution by regulating point sources that discharge pollutants into waters of the United States.

1.2.12 Clean Water Act Sections 401 & 404 and Section 62.1-44.30 Code of Virginia

These regulate the fill and/or excavation in waters of the U.S., including wetlands.

1.2.12.1 Virginia Marine Resources Commission Authority

Per Section 28.2-1203.3 of the Code of Virginia: Construction and maintenance of Congressionally authorized navigation and flood control projects undertaken by the U.S. Army Corps of Engineers, the U.S. Coast Guard, or other federal agency authorized by Congress to regulate navigable waters or flood control are exempt from regulation.

1.2.13 Oily Waste

Oily waste are those materials that are, or were, mixed with Petroleum, Oils, and Lubricants (POLs) and have become separated from that POLs. Oily wastes also means materials, including wastewaters, centrifuge solids, filter residues or sludges, bottom sediments, tank bottoms, and sorbents which have come into contact with and have been contaminated by, POLs and may be appropriately tested and discarded in a manner which is in compliance with other state and local requirements.

This definition includes materials such as oily rags, "kitty litter" sorbent clay and organic sorbent material. These materials may be land filled provided that: It is not prohibited in other state regulations or local ordinances; the amount generated is "de minimus" (a small amount); it is the result of minor leaks or spills resulting from normal process operations; and free-flowing oil has been removed to the practicable extent possible. Large quantities of this material, generated as a result of a major spill or in lieu of proper maintenance of the processing equipment, are a solid waste. As a solid waste, perform a hazardous waste determination prior to disposal. As this can be an expensive process, it is recommended that this type of waste be minimized through good housekeeping practices and employee education.

1.2.14 Regulated Waste

Regulated waste are solid wastes that have specific additional federal, state, or local controls for handling, storage, or disposal.

1.2.15 Sediment

Sediment is soil and other debris that have eroded and have been transported by runoff water or wind.

1.2.16 Solid Waste

Solid waste is a solid, liquid, semi-solid or contained gaseous waste. A solid waste can be a hazardous waste, non-hazardous waste, or non-Resource Conservation and Recovery Act (RCRA) regulated waste. Types of solid waste typically generated at construction sites may include:

1.2.16.1 Debris

Debris is non-hazardous solid material generated during the construction, demolition, or renovation of a structure that exceeds 2.5-inch particle size that is: a manufactured object; plant or animal matter; or natural geologic material (for example, cobbles and boulders), broken or removed concrete, masonry, and rock asphalt paving; ceramics; roofing paper and shingles. Inert materials may not be reinforced with or contain ferrous wire, rods, accessories and weldments. A mixture of debris and other material such as soil or sludge is also subject to regulation as debris if the mixture is comprised primarily of debris by volume, based on visual inspection.

1.2.16.2 Green Waste

Green waste is the vegetative matter from landscaping, land clearing and grubbing, including, but not limited to, grass, bushes, scrubs, small trees and saplings, tree stumps and plant roots. Marketable trees, grasses and plants that are indicated to remain, be re-located, or be re-used are not included.

1.2.16.3 Non-Hazardous Waste

Non-hazardous waste is waste that is excluded from, or does not meet, hazardous waste criteria in accordance with 40 CFR 261.

1.2.17 Surface Discharge

Surface discharge means discharge of water into drainage ditches, storm sewers, or creeks meeting the definition of "waters of the United States". Surface discharges from construction sites are discrete, identifiable sources and require a permit from the governing agency. Comply with federal, state, and local laws and regulations.

1.2.18 Wastewater

Wastewater is the used water and solids that flow through a sanitary sewer to a treatment plant.

1.2.18.1 Stormwater

Stormwater is any precipitation in an urban or suburban area that does not evaporate or soak into the ground, but instead collects and flows into storm drains, rivers, and streams.

1.2.19 Waters of the United States

Waters of the United States means Federally jurisdictional waters, including wetlands, that are subject to regulation under Section 404 of the Clean Water Act or navigable waters, as defined under the Rivers and Harbors Act.

1.2.20 Wetlands

Wetlands are those areas that are inundated or saturated by surface or groundwater at a frequency and duration sufficient to support, and that under normal circumstances do support, a prevalence of vegetation typically adapted for life in saturated soil conditions.

1.2.21 Universal Waste

The universal waste regulations streamline collection requirements for certain hazardous wastes in the following categories: batteries, pesticides, mercury-containing equipment (for example, thermostats), and lamps (for example, fluorescent bulbs). The rule is designed to reduce hazardous waste in the municipal solid waste (MSW) stream by making it easier for universal waste handlers to collect these items and send them for recycling or proper disposal. These regulations can be found at 40 CFR 273.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for information only. When used, a code following the "G" classification identifies the office that will review the submittal for the Government. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Preconstruction Survey

Regulatory Notifications; G, R0

Environmental Manager Qualifications; G, R0

Virginia DEQ Registration Statement

Employee Training Records; G, R0

Environmental Protection Plan; G, R0

Dirt and Dust Control Plan; G, R0

Solid Waste Management Permit; G, R0

Land Disturbance Permit Application; G, R0

Spill Prevention Control And Countermeasure (SPCC) Plan; G, R0

SD-03 Product Data

Inspection Reports; G, R0

SD-06 Test Reports

Monthly Solid Waste Disposal Report; G, R0

SD-07 Certificates

Employee Training Records; G, R0

Erosion and Sediment Control Inspector Qualifications

SD-11 Closeout Submittals

Regulatory Notifications; G, R0

Assembled Employee Training Records; G, R0

As-Built Topographic Survey

Waste Determination Documentation; G, R0

1.4 ENVIRONMENTAL PROTECTION REQUIREMENTS

Provide and maintain, during the life of the contract, environmental protection as defined. Plan for and provide environmental protective measures to control pollution that develops during construction practice. Plan for and provide environmental protective measures required to correct conditions that develop during the construction of permanent or temporary environmental features associated with the project. Protect the environmental resources within the project boundaries and those affected outside the limits of permanent work during the entire duration of this Contract including waters of the U.S., wetlands, terrestrial vegetation, and federal and state threatened and endangered species. The environmental protection plan must include a requirement to fence off these areas with protective fencing during construction. Comply with NASA, federal, state, and local regulations pertaining to the environment, including protected species, water, air, solid waste, hazardous waste and substances, oily substances, and noise pollution.

Tests and procedures assessing whether construction operations comply with Applicable Environmental Laws may be required. Analytical work must be performed by qualified laboratories; and where required by law, the laboratories must be certified.

1.5 SPECIAL ENVIRONMENTAL REQUIREMENTS

Comply with the special environmental requirements listed in permits from the USACE and VMRC including Incidental Take Statement from National Marine Fisheries Service and U.S. Fish and Wildlife Services attached at the end of this section.

If minor excavation is required in the laydown area and soil removal is necessary, an area will be identified by NASA for disposition. All other environmental considerations and permit restrictions must shall be integrated.

1.5.1 Special Precautions for Red Knot Migrants/American Oystercatchers/ Piping Plovers, Sea Turtles, and Seals on the Beach

The Contractor is advised the Government has consulted with the U.S. Fish and Wildlife Service (USFWS), Virginia Marine Resources Commission (VMRC), Virginia Department of Wildlife Resources (VDWR), National Marine Fisheries Service (NMFS) and qualified EPOC. The Contractor shall be aware that the nesting season for piping plovers and American oystercatchers start March 15 and the NASA Environmental Office will begin daily species monitoring on that day for nesting piping plovers, American oystercatchers, and red knot migrants. Daily monitoring will continue until the last chick fledges or deemed nonviable by the NASA Environmental Office. The Contractor shall also be aware that the nesting season for the sea turtles within the beach fill areas begin on May 1 and the NASA Environmental Office will begin daily species monitoring on that day and continue until the last nest hatches or deemed nonviable by the VDWR or

USFWS. The Contractor shall also be aware that between November to May, gray and harbor seals occasionally haul out to rest and sun themselves on Wallops Island beach.

All Contractor activities shall cease within 1,000 feet of a piping plover, American oystercatcher, or sea turtle nest until the last piping plover or

American oystercatcher chicks have fledged, or the last sea turtle nest has hatched or been deemed nonviable by the VDWR or USFWS staff, whichever is later. If a piping plover, American oystercatcher or sea turtle nest is found before renourishment activities are completed, all activities must cease until the NASA Environmental Office staff has been notified. The Contractor shall continue work to the maximum extent possible remaining outside the 1,000 foot designated radius and maintaining daily coordination with NASA Environmental Office. The Contractor shall coordinate with the COR for use of potential haul roads if necessary to continue construction. All equipment and materials shall be staged in upland areas westward of the beach and outside of sensitive habitats (e.g., marshes, mudflats, dunes, wetlands, nesting areas).

If a sea turtle nest, piping plover nest, or American oystercatcher nest is excavated, the Contractor shall immediately contact NASA Environmental Office at 757-824-1718 or other designated number. If a turtle nest, piping plover nest, or American oystercatcher nest is inadvertently dug up by beach fill construction activities or found by any other means in the area where the Contractor's activities may disturb the nest, the Contractor must stop all activities in the area and protect the discovery until the approved NASA Environmental Office POC is notified and on the scene. The protected species monitor will prepare an Incident Statement on approved forms for all findings, recording the Contract number and title, date and time of discoveries, location and condition of findings, and provide a copy to the Contractor. The protected species monitor will at the same time forward a signed copy of the Incident Statement within 24 hours to the NASA Environmental Office, which will in turn provide information and inform and coordinate with USFWS and VDWR. The Contractor shall acknowledge the time and date of his receipt of the Incident Statement in his Daily Report of Operations and include a copy in his Daily Report of Operations and include a copy in his Daily Report to the Contracting Officer and the Norfolk District Project Manager.

If a seal is discovered on the beach, the Contractor shall immediately contact NASA Environmental Office at 757-824-1718 or other designated number. Contractor staff must maintain 150 feet minimum distance from any seal on Wallops Island beach and at all times shall maintain a path clear of people and equipment between the seal and the ocean.

1.6 QUALITY ASSURANCE

1.6.1 Preconstruction Survey and Protection of Features

This paragraph supplements the Contract Clause PROTECTION OF EXISTING VEGETATION, STRUCTURES, EQUIPMENT, UTILITIES, AND IMPROVEMENTS. Prior to start of any onsite construction activities, perform a Preconstruction Survey of the project site with the Contracting Officer, and take photographs showing existing environmental conditions in and adjacent to the site. Submit a report for the record. Include in the report a plan describing the features requiring protection under the provisions of the Contract Clauses, which are not specifically identified on the drawings as environmental features requiring protection along with the condition of

trees, shrubs and grassed areas immediately adjacent to the site of work and adjacent to the Contractor's assigned storage area and access route(s), as applicable. The NASA Environmental Office will review the survey report and advise the COR as to its accuracy and completeness. The Contractor and the Contracting Officer will sign this survey report upon mutual agreement regarding its accuracy and completeness. Protect those environmental features included in the survey report and any indicated on the drawings, regardless of interference that their preservation may cause to the work under the Contract.

1.6.2 Regulatory Notifications

Provide regulatory notification requirements in accordance with federal, state and local regulations. In cases where the Government will also provide public notification, coordinate with the Contracting Officer. Submit copies of regulatory notifications to the Contracting Officer at least 10 days prior to commencement of work activities. Typically, regulatory notifications must be provided for the following (this listing is not all-inclusive): demolition, renovation, construction, removal or use of a permitted air emissions source, and remediation of controlled substances (asbestos, hazardous waste, lead paint).

1.6.3 Environmental Brief

Attend an environmental brief to be included in the preconstruction meeting. Provide the following information: types, quantities, and use of hazardous materials that will be brought onto the installation; and types and quantities of wastes/wastewater that may be generated during the Contract. Discuss the results of the Preconstruction Survey at this time.

Prior to initiating any work on site, meet with the Contracting Officer and NASA Environmental Office to discuss the proposed Environmental Protection Plan (EPP) or equipment local requirement. Develop a mutual understanding relative to the details of environmental protection, including measures for protecting natural and cultural resources, required reports, required permits, permit requirements (such as mitigation measures), and other measures to be taken. This project requires a Virginia Water Protection Permit (VWPP), USACE 404 Permit, USFWS Biological Opinion, and NOAA Fisheries Biological Opinion, which will be obtained by the Government and attached to these specifications. It also requires adherence to the 404B1 Guidelines.

1.6.4 Environmental Manager

Appoint in writing an Environmental Manager for the project site. The Environmental Manager is directly responsible for coordinating contractor compliance with federal, state, local, and NASA requirements. The Environmental Manager must ensure compliance with Hazardous Waste Program requirements (including hazardous waste handling, storage, manifesting, and disposal); implement the EPP; ensure environmental permits are obtained, maintained, and closed out; ensure compliance with NASA protected species management; ensure compliance with Hazardous Materials (storage, handling, and reporting) requirements; and coordinate any remediation of regulated substances. This can be a collateral position; however, the person in this position must be trained to adequately accomplish the following duties: ensure waste segregation and storage compatibility requirements are met; inspect and manage Satellite Accumulation areas; ensure only authorized personnel add wastes to containers; ensure Contractor personnel are trained in 40 CFR requirements

in accordance with their position requirements; coordinate removal of waste containers; and maintain the Environmental Records binder and required documentation, including environmental permits compliance and close-out. Submit Environmental Manager Qualifications to the Contracting Officer.

1.6.5 Employee Training Records

Prepare and maintain Employee Training Records throughout the term of the contract meeting applicable 40 CFR requirements. Provide Employee Training Records in the Environmental Records Binder. Submit these Assembled Employee Training Records to the Contracting Officer at the conclusion of the project, unless otherwise directed.

Train personnel to meet EPA and state requirements. Conduct environmental protection/pollution control meetings for personnel prior to commencing construction activities. Conduct additional meetings for new personnel and when site conditions change. Include in the training and meeting agenda: methods of detecting and avoiding pollution; familiarization with statutory and contractual pollution standards; installation and care of devices, vegetative covers, and instruments required for monitoring purposes to ensure adequate and continuous environmental protection/pollution control; anticipated hazardous or toxic chemicals or wastes, and other regulated contaminants; recognition and protection of archaeological sites, artifacts, waters of the United States, and endangered species and their habitat that are known to be in the area. Provide copy of the Erosion and Sediment Control Inspector Qualifications as defined by EPA and the Certification as required by the state of Virginia.

1.6.6 Non-Compliance Notifications

The Contracting Officer will notify the Contractor in writing of any observed noncompliance with federal, state or local environmental laws or regulations, permits, and other elements of the Contractor's EPP. After receipt of such notice, inform the Contracting Officer of the proposed corrective action and take such action when approved by the Contracting Officer. The Contracting Officer may issue an order stopping all or part of the work until satisfactory corrective action has been taken. FAR 52.242-14 Suspension of Work provides that a suspension, delay, or interruption of work due to the fault or negligence of the Contractor allows for no adjustments to the contract for time extensions or equitable adjustments. In addition to a suspension of work, the Contracting Officer may use additional authorities under the contract or law.

1.7 ENVIRONMENTAL PROTECTION PLAN

The purpose of the EPP is to present an overview of known or potential environmental issues that must be considered and addressed during construction. Incorporate construction related objectives and targets from the installation's EMS into the EPP. Include in the EPP measures for protecting natural and cultural resources, required reports, and other measures to be taken. Meet with the Contracting Officer or Contracting Officer Representative to discuss the EPP and develop a mutual understanding relative to the details for environmental protection including measures for protecting natural resources, required reports, and other measures to be taken. Submit the EPP within 7 days after notice to proceed and not less than 7 days before the preconstruction meeting. The EPP must also be reviewed and approved by the NASA Environmental Office

prior to start of any onsite construction activities. In coordination with the NASA Environmental Office, rRevisE the EPP throughout the project to include any reporting requirements, changes in site conditions, or contract modifications that change the project scope of work in a way that could have an environmental impact. No requirement in this section will relieve the Contractor of any applicable federal, state, and local environmental protection laws and regulations. During Construction, identify, implement, and submit for approval any additional requirements to be included in the EPP. Maintain the current version onsite.

The EPP includes, but is not limited to, the following elements:

1.7.1 General Overview and Purpose

1.7.1.1 Descriptions

A brief description of each specific plan required by environmental permit or elsewhere in this Contract such as, spill control plan, solid waste management plan, wastewater management plan, air pollution control plan, contaminant prevention plan, traffic control plan Non-Hazardous Solid Waste Disposal Plan.

1.7.1.2 Duties

The duties and level of authority assigned to the person(s) on the job site who oversee environmental compliance, such as who is responsible for adherence to the EPP, who is responsible for spill cleanup and training personnel on spill response procedures, who is responsible for manifesting hazardous waste to be removed from the site (if applicable), and who is responsible for training the Contractor's environmental protection personnel.

1.7.1.3 Procedures

A copy of any standard or project-specific operating procedures that will be used to effectively manage and protect the environment on the project site.

1.7.1.4 Communications

Communication and training procedures that will be used to convey environmental management requirements to Contractor employees and subcontractors.

1.7.1.5 Contact Information

Emergency contact information contact information (office phone number, cell phone number, and e-mail address).

1.7.2 General Site Information

1.7.2.1 Drawings

Drawings showing locations of proposed temporary excavations or embankments for haul roads, stream crossings, jurisdictional wetlands, material storage areas, structures, sanitary facilities, storm drains and conveyances, and stockpiles of excess soil.

1.7.2.2 Work Area

Work area plan showing the proposed activity in each portion of the area and identify the areas of limited use or nonuse. Include measures for marking the limits of use areas, including methods for protection of features to be preserved within authorized work areas and methods to control runoff and to contain materials on site, and a traffic control plan.

Show where any fuels, hazardous substances, solvents, or lubricants will be stored. Provide a spill plan to address any releases of those materials.

1.7.2.3 Documentation

A letter signed by an officer of the firm appointing the Environmental Manager and stating that person is responsible for managing and implementing the Environmental Program as described in this contract. Include in this letter the Environmental Manager's authority to direct the removal and replacement of non-conforming work.

1.7.3 Management of Natural Resources

- a. Land resources
- b. Tree protectionc. Replacement of damaged landscape features
- d. Temporary construction
- e. Stream crossings
- f. Fish and wildlife resources
- g. Wetland areas

1.7.4 Protection of Historical and Archaeological Resources

- a. Objectives
- b. Procedure
- c. Communication with Employees
- d. Coordination with NASA Environmental Office
- e. Inadvertent discovery

1.7.5 Stormwater Management and Control

- a. Ground cover
- b. Erodible soils
- c. Temporary measures
 - (1) Structural Practices
 - (2) Temporary and permanent stabilization
- d. Effective selection, implementation and maintenance of Best Management Practices (BMPs).
- e. Stormwater Pollution Prevention Plan (SWPPP).

1.7.6 Protection of the Environment from Waste Derived from Contractor Operations

Control and disposal of solid and sanitary waste.

Control and disposal of hazardous waste.

This item consist of the management procedures for hazardous waste to be generated. The elements of those procedures will coincide with the Installation Hazardous Waste Management Plan when within an installation. The Contracting Officer will provide a copy of the Installation Hazardous Waste Management Plan as applicable.

As a minimum, include the following:

- a. List of the types of hazardous wastes expected to be generated or encountered.
- b. Procedures to ensure a written waste determination is made for appropriate wastes that are to be generated.
- c. Sampling/analysis plan, including laboratory method(s) that will be used for waste determinations and copies of relevant laboratory certifications.
- d. Methods and proposed locations for hazardous waste accumulation/storage (that is, in tanks or containers).
- e. Management procedures for storage, labeling, transportation, and disposal of waste (treatment of waste is not allowed unless specifically noted).
- f. Management procedures and regulatory documentation ensuring disposal of hazardous waste complies with Land Disposal Restrictions (40 CFR 268).
- g. Management procedures for recyclable hazardous materials such as lead-acid batteries, used oil, and similar.
- h. Used oil management procedures in accordance with 40 CFR 279; Hazardous waste minimization procedures.
- i. Plans for the disposal of hazardous waste by permitted facilities; and Procedures to be employed to ensure required employee training records are maintained.

1.7.7 Prevention of Releases to the Environment

Procedures to prevent releases to the environment

Notifications in the event of a release to the environment

1.7.8 Regulatory Notification and Permits

This project requires a Virginia Water Protection Permit (VWPP), which will be obtained by the Government and attached to these specifications. It also requires adherence to the 404B1 Guidelines. List what notifications and permit applications must be made. Some permits require up to 180 days to obtain. Demonstrate that those permits have been obtained or applied for by including copies of applicable environmental permits. The EPP will not be approved until the permits have been obtained.

1.7.9 Clean Air Act Compliance

1.7.9.1 Haul Route

Submit truck and material haul routes along with a Dirt and Dust Control Plan for controlling dirt, debris, and dust on Installation roadways. As a minimum, identify in the plan the subcontractor and equipment for cleaning along the haul route and measures to reduce dirt, dust, and debris from roadways.

1.7.9.2 Pollution Generating Equipment

Identify air pollution generating equipment or processes that may require federal, state, or local permits under the Clean Air Act. Determine requirements based on any current installation permits and the impacts of the project. Provide a list of all fixed or mobile equipment, machinery or operations that could generate air emissions during the project to the Installation Environmental Office (Air Program Manager). Ensure required permits are obtained prior to installing and operating applicable equipment/processes.

1.7.9.3 Stationary Internal Combustion Engines

Identify portable and stationary internal combustion engines that will be supplied, used or serviced. Comply with 40 CFR 60 Subpart IIII, 40 CFR 60 Subpart JJJJ, 40 CFR 63 Subpart ZZZZ, and local regulations as applicable. At minimum, include the make, model, serial number, manufacture date, size (engine brake horsepower), and EPA emission certification status of each engine. Maintain applicable records and log hours of operation and fuel use. Logs must include reasons for operation and delineate between maintenance/testing, emergency, and non-emergency operation.

1.7.9.4 Monitoring

For the protection of public health, monitor and control contaminant emissions to the air from any potential Hazardous, Toxic, and Radioactive Waste remedial action area sources to minimize short-term risks that might be posed to the community during implementation of any required remedial alternative actions.

1.7.9.5 Compliant Materials

Provide the Government a list of SDSs for all hazardous materials proposed for use on site. Materials must be compliant with all Clean Air Act regulations for emissions including solvent and volatile organic compound contents, and applicable National Emission Standards for Hazardous Air Pollutants requirements. The Government may alter or limit use of specific materials as needed to meet installation permit requirements for emissions.

1.8 LICENSES AND PERMITS

Obtain licenses and permits required for the construction of the project and in accordance with FAR 52.236-7 Permits and Responsibilities. Notify the Government of all equipment that may require permits or special approvals that the Contractor plans to use on site. This paragraph supplements the Contractor's responsibility under FAR 52.236-7 Permits and Responsibilities.

1.9 ENVIRONMENTAL RECORDS BINDER

Maintain on-site a separate three-ring Environmental Records Binder and submit at the completion of the project. Make separate parts within the binder that correspond to each submittal listed under paragraph CLOSEOUT SUBMITTALS in this section.

1.10 SOLID WASTE MANAGEMENT PERMIT

Provide the Contracting Officer with written notification of the quantity of anticipated solid waste or debris that is anticipated or estimated to be generated by construction. Include in the report the locations where various types of waste will be disposed or recycled. Include letters of acceptance from the receiving location or as applicable; submit one copy of the receiving location state and local Solid Waste Management Permit or license showing such agency's approval of the disposal plan before transporting wastes off Government property.

1.10.1 Monthly Solid Waste Disposal Report

Monthly, submit a solid waste disposal report to the Contracting Officer. For each waste, the report will state the classification (using the definitions provided in this section), amount, location, and name of the business receiving the solid waste.

PART 2 PRODUCTS

Not Used

PART 3 EXECUTION

3.1 PROTECTION OF NATURAL RESOURCES

Minimize interference with, disturbance to, and damage to fish, wildlife, and plants, including their habitats. Prior to the commencement of activities, consult with the NASA Environmental Office and COR as applicable, regarding rare species or sensitive habitats that need to be protected. The protection of rare, threatened, and endangered animal and plant species identified, including their habitats, is the Contractor's responsibility. The following species are known and could be affected within the construction area: nesting piping plovers, American oystercatchers, and loggerhead sea turtles; migrant rufa red knot migrants; and resting gray and harbor seals. See section 1.5.1 for more information on potential species affected by the construction activities.

Preserve the natural resources within the project boundaries and outside the limits of permanent work. Restore to an equivalent or improved condition upon completion of work that is consistent with the requirements of the Installation Environmental Office or as otherwise specified. Confine construction activities to within the limits of the work indicated or specified.

3.1.1 Flow Ways

Do not alter water flows or otherwise significantly disturb the native habitat adjacent to the project and critical to the survival of fish and wildlife, except as specified and permitted.

3.1.2 Vegetation

Except in areas to be cleared, do not remove, cut, deface, injure, or destroy trees or shrubs without the Contracting Officer's permission. Do not fasten or attach ropes, cables, or guys to existing nearby trees for anchorages unless authorized by the Contracting Officer. Where such use of attached ropes, cables, or guys is authorized, the Contractor is responsible for any resultant damage.

Protect existing trees that are to remain to ensure they are not injured, bruised, defaced, or otherwise damaged by construction operations. Remove displaced rocks from uncleared areas. Coordinate with the Contracting Officer and Installation Environmental Office to determine appropriate action for trees and other landscape features scarred or damaged by equipment operations.

3.1.3 Streams

Stream crossings must allow movement of materials or equipment without violating water pollution control standards of the federal, state, and local governments. Construction of stream crossing structures must be in compliance with all required permits including, but not limited to, Clean Water Act Section 404, and Section 401 Water Quality.

The Contracting Officer's approval and appropriate permits are required before any equipment will be permitted to ford live streams. In areas where frequent crossings are required, install temporary culverts or bridges. Obtain Contracting Officer's approval prior to installation. Remove temporary culverts or bridges upon completion of work, and repair the area to its original condition unless otherwise required by the Contracting Officer.

3.2 PROTECTION OF MARINE ANIMALS, WILDLIFE AND VEGETATION

The Contractor is informed that the work areas are in a portion of Virginia frequented by migratory birds and is a native habitat for eagles, hawks, egrets, herons, pelicans, terns, and other wildlife that are identified as either endangered species protected by federal law or species of special concern for the Commonwealth of Virginia agencies. If, in the performance of this contract, evidence of the possible disturbance to any such migratory bird or listed species may occur, the Contractor shall notify the Contracting Officer immediately, giving the location and nature of the findings. The Contractor shall advise all personnel associated with the operation of the construction equipment of the civil and criminal provisions of the Endangered Species Act (ESA), the Migratory Bird Act, and the Marine Mammal Protection Act (MMPA). In the event that endangered or protected species are affected by this work, the work under this contract may be suspended or terminated as determined by the Contracting Officer. All employees of the Contractor working at the site and those sub-contractors employed on the work shall be required to read and certify in writing they are aware of the contents of this specification and the Contractor's Environmental Protection Plan. Copies of this SECTION and the Environmental Protection Plan, including a posting warning of the civil and criminal liabilities that violators are subject to for non-compliance to the requirements of them, shall be clearly posted with other required postings on-site for employees.

- a. A training and familiarization program for all contractor

personnel working in the construction area will be required. The training program would be conducted by the NASA Environmental Office and would include basic biological information about all listed species (red knots, American oystercatchers, piping plovers, and sea turtles) and be sufficient to allow personnel to tentatively identify the species and its likely habitat and incorporate appropriate avoidance and minimization measures into their activities. Upon completion of the training, all personnel will sign and verify that they received and understand the training. Signatures will be kept on file in the Environmental Office.

If American oystercatcher/piping plover nests, red knot migrants or sea turtle crawl tracks/sea turtle nests are identified, or any stranded marine mammal or sea turtle is found, contractor personnel shall immediately cease work in the immediate vicinity of the suspected find and contact the COR.

3.3 STORMWATER

Do not discharge stormwater from construction sites including laydown areas to the sanitary sewer. If the water is noted or suspected of being contaminated, it may only be released to the storm drain system if the discharge is specifically permitted. Obtain authorization in advance from the NASA Environmental Office for any release of contaminated water.

Land disturbances greater than 1 acre will require a Construction General Permit (CGP) issued by the State along with an approved Stormwater Management Plan (SWM). Submit an Land Disturbance Permit Application and Virginia DEQ Registration Statement, if needed.

3.3.1 Erosion and Sediment Control Measures

If the land disturbance is over 10,000 square feet, a site-specific Erosion and Sediment Control (ESC) Plan that is compliant with the Virginia Erosion and Stormwater Regulations (9VAC25-875) is required. ESC plans must be pre-approved by a DEQ certified plan reviewer before submission to NASA. The final plan must be approved by NASA WFF SEED at least two weeks prior to any land disturbing work commencing.

Provide erosion and sediment control measures in accordance with state and local laws, Virginia Erosion and Sediment Control Handbook (latest edition), and regulations. Preserve vegetation to the maximum extent practicable. The erosion and sediment controls selected and maintained by the Contractor shall be such that water quality standards are not violated as a result of construction activities. The area of bare soil exposed at any one time by construction operations should be kept to a minimum. Construct or install temporary and permanent erosion and sediment control best management practices (BMPs) as indicated on the drawings. BMPs may include, but not be limited to, vegetation cover, stream bank stabilization, slope stabilization, silt fences, construction of terraces, interceptor channels, sediment traps, inlet and outfall protection, diversion channels, and sedimentation basins. Remove any temporary measures after the area has been stabilized.

Erosion control inspection reports may be compiled as part of a stormwater pollution prevention plan inspection reports.

3.3.2 Work Area Limits

Mark the areas that need not be disturbed under this Contract prior to commencing construction activities. Mark or fence isolated areas within the general work area that are not to be disturbed. Protect monuments and markers before construction operations commence. Where construction operations are to be conducted during darkness, all markers must be visible in the dark. Personnel must be knowledgeable of the purpose for marking and protecting particular objects.

3.3.3 Contractor Facilities and Work Areas

Place field offices, staging areas, stockpile storage, and temporary buildings in areas designated on the drawings or as directed by the Contracting Officer. Move or relocate the Contractor facilities only when approved by the Government. Provide erosion and sediment controls for onsite borrow and spoil areas to prevent sediment from entering nearby waters. Control temporary excavation and embankments for plant or work areas to protect adjacent areas.

3.3.4 Municipal Separate Storm Sewer System (MS4) Management

Comply with the Installation's MS4 permit requirements.

3.4 SURFACE AND GROUNDWATER

3.4.1 Waters of the United States

Do not enter, disturb, destroy, or allow discharge of contaminants into waters of the United States except as authorized herein. The protection of waters of the United States shown on the drawings in accordance with paragraph LICENSES AND PERMITS is the Contractor's responsibility. Authorization to enter specific waters of the United States identified does not relieve the Contractor from any obligation to protect other waters of the United States within, adjacent to, or in the vicinity of the construction site and associated boundaries.

3.5 AIR RESOURCES

Equipment operation, activities, or processes will be in accordance with 40 CFR 64 and state air emission and performance laws and standards.

3.5.1 Preconstruction Air Permits

Notify the Air Program Manager, through the Contracting Officer, at least 6 months prior to bringing equipment, assembled or unassembled, onto the Installation, so that air permits can be secured. Necessary permitting time must be considered in regard to construction activities. Clean Air Act (CAA) permits must be obtained prior to bringing equipment, assembled or unassembled, onto the Installation.

Confirm that these permits have been obtained.

3.5.2 Burning

Burning is prohibited on the Government premises.

3.5.3 Class I ODS Prohibition

Class I ODS are Government property and must be returned to the Government for appropriate management. Coordinate with the Installation Environmental Office to determine the appropriate location for turn in of all reclaimed refrigerant.

3.5.4 Venting of Refrigerant

Accidental venting of a refrigerant is a release and must be reported immediately to the Contracting Officer. Intentional venting of refrigerants (including most Non-ODS substitute refrigerants) is prohibited per 40 CFR 82.

3.5.5 EPA Certification Requirements

Heating and air conditioning technicians must be certified through an EPA-approved program. Maintain copies of certifications at the employees' places of business; technicians must carry certification wallet cards, as provided by environmental law.

3.5.6 Dust Control Plan

Keep dust down at all times, including during nonworking periods. Sprinkle or treat, with dust suppressants, the soil at the site, haul roads, and other areas disturbed by operations. Dry power brooming will not be permitted. Instead, use vacuuming, wet mopping, wet sweeping, or wet power brooming. Air blowing will be permitted only for cleaning nonparticulate debris such as steel reinforcing bars. Only wet cutting will be permitted for cutting concrete blocks, concrete, and bituminous concrete. Do not unnecessarily shake bags of cement, concrete mortar, or plaster. Since these products contain Crystalline Silica, comply with the applicable OSHA standard, 29 CFR 1910.1053 or 29 CFR 1926.1153 for controlling exposure to Crystalline Silica Dust. Dust must be contained so that it does not become air born and affect vehicles, buildings, and antennas.

3.5.6.1 Particulates

Dust particles, aerosols and gaseous by-products from construction activities, and processing and preparation of materials (such as from asphaltic batch plants) must be controlled at all times, including weekends, holidays, and hours when work is not in progress. Maintain excavations, stockpiles, haul roads, permanent and temporary access roads, plant sites, spoil areas, borrow areas, and other work areas within or outside the project boundaries free from particulates that would exceed 40 CFR 50, state, and local air pollution standards or that would cause a hazard or a nuisance. Sprinkling, chemical treatment of an approved type, baghouse, scrubbers, electrostatic precipitators, or other methods will be permitted to control particulates in the work area. Sprinkling, to be efficient, must be repeated to keep the disturbed area damp. Provide sufficient, competent equipment available to accomplish these tasks. Perform particulate control as the work proceeds and whenever a particulate nuisance or hazard occurs. Comply with state and local visibility regulations.

3.5.6.2 Abrasive Blasting

Blasting operations cannot be performed without prior approval of the

Installation Air Program Manager. The use of silica sand is prohibited in sandblasting.

Provide tarpaulin drop cloths and windscreens to enclose abrasive blasting operations to confine and collect dust, abrasive agent, paint chips, and other debris.

3.5.7 Odors

Control odors from construction activities. The odors must be in compliance with state regulations and local ordinances and may not constitute a health hazard.

3.6 WASTE MINIMIZATION

Minimize the use of hazardous materials and the generation of waste. Include procedures for pollution prevention/ hazardous waste minimization in the Hazardous Waste Management Section of the EPP. Obtain a copy of the installation's Pollution Prevention/Hazardous Waste Minimization Plan for reference material when preparing this part of the EPP. If no written plan exists, obtain information by contacting the Contracting Officer. Describe the anticipated types of the hazardous materials to be used in the construction when requesting information.

3.6.1 Salvage, Reuse and Recycle

Identify anticipated materials and waste for salvage, reuse, and recycling. Describe actions to promote material reuse, resale or recycling. To the extent practicable, all scrap metal must be sent for reuse or recycling and will not be disposed of in a landfill.

Include the name, physical address, and telephone number of the hauler, if transported by a franchised solid waste hauler. Include the destination and, unless exempted, provide a copy of the state or local permit (cover) or license for recycling.

3.7 WASTE MANAGEMENT AND DISPOSAL

3.7.1 Waste Determination Documentation

Complete a Waste Determination form if applicable (provided at the pre-construction conference) for Contractor-derived wastes to be generated. All potentially hazardous solid waste streams that are not subject to a specific exclusion or exemption from the hazardous waste regulations (e.g., scrap metal, domestic sewage) or subject to special rules, (lead-acid batteries and precious metals) must be characterized in accordance with the requirements of 40 CFR 262.11 or corresponding applicable state or local regulations. Base waste determination on user knowledge of the processes and materials used, and analytical data when necessary. Consult with the Installation environmental staff for guidance on specific requirements. Attach support documentation to the Waste Determination form. As a minimum, provide a Waste Determination form for the following waste (this listing is not exhaustive): oil- and latex-based painting and caulking products, solvents, adhesives, aerosols, petroleum products, and containers of the original materials.

3.7.2 Releases/Spills of Oil and Hazardous Substances

3.7.2.1 Response and Notifications

Exercise due diligence to prevent, contain, and respond to spills of hazardous material, hazardous substances, hazardous waste, sewage, regulated gas, petroleum, lubrication oil, and other substances regulated in accordance with 40 CFR 300. Maintain spill cleanup equipment and materials at the work site. In the event of a spill, take prompt, effective action to stop, contain, curtail, or otherwise limit the amount, duration, and severity of the spill/release. In the event of any releases of oil and hazardous substances, chemicals, or gases; immediately (within 15 minutes) notify the Installation Fire Department, the Installation Command Duty Officer, the Installation Environmental Office, the Contracting Officer and the state or local authority.

Submit verbal and written notifications as required by the federal (40 CFR 300.125 and 40 CFR 355), state, local regulations and instructions. Provide copies of the written notification and documentation that a verbal notification was made within 20 days. Spill response must be in accordance with 40 CFR 300 and applicable state and local regulations.

Spills of hazardous or toxic materials must be immediately reported Wallops Flight Facility Fire Department via Dispatch at 757-824-1300. A spill response plan will be provided to the Contractor as a supplement to the contract. Wallops Flight Facility will coordinate spill cleanups and cleanup costs shall be borne by the Contractor. All manifests for contractor generated hazardous waste will need to be approved and signed by a duly authorized representative of the NASA Environmental Office.

3.7.2.2 Clean Up

Clean up hazardous and non-hazardous waste spills. Reimburse the Government for costs incurred including sample analysis materials, clothing, equipment, and labor if the Government will initiate its own spill cleanup procedures, for Contractor- responsible spills, when: Spill cleanup procedures have not begun within one hour of spill discovery/occurrence; or, in the Government's judgment, spill cleanup is inadequate and the spill remains a threat to human health or the environment.

3.8 HAZARDOUS MATERIAL MANAGEMENT

Include hazardous material control procedures in the Safety Plan, in accordance with Section 01 35 26 GOVERNMENTAL SAFETY REQUIREMENTS. Address procedures and proper handling of hazardous materials, including the appropriate transportation requirements. Do not bring hazardous material onto Government property that does not directly relate to requirements for the performance of this contract. Submit an SDS and estimated quantities to be used for each hazardous material to the Contracting Officer prior to bringing the material on the installation. Typical materials requiring SDS and quantity reporting include, but are not limited to, oil and latex based painting and caulking products, solvents, adhesives, aerosol, and petroleum products. Use hazardous materials in a manner that minimizes the amount of hazardous waste generated. Containers of hazardous materials must have National Fire Protection Association labels or their equivalent. Certify that hazardous materials removed from the site are hazardous materials and do not meet

the definition of hazardous waste, in accordance with 40 CFR 261 and state and installation requirements.

3.9 PREVIOUSLY USED EQUIPMENT

Clean previously used construction equipment prior to bringing it onto the project site. Equipment must be free from soil residuals, egg deposits from plant pests, noxious weeds, and plant seeds. Consult with the U.S. Department of Agriculture jurisdictional office for additional cleaning requirements.

In accordance with the Wallops Phragmites Control Plan (2014) "To prevent the accidental introduction of *Phragmites australis* (*Phragmites*) to new areas during construction or maintenance activities on Wallops Island, all tracked equipment involved in earth work will be inspected and cleaned to remove any rhizomes and seeds prior to arrival on-site. If tracked equipment is used in earth work where *Phragmites* is known to exist, this portion of the earthwork will be conducted last, or the equipment will be cleaned prior to use on any portion of the site that is known to be free of *Phragmites*. Construction equipment will be cleaned by using physical means and hand tools, such as brushes, brooms, rakes, or shovels, on all track and bucket/blade components to adequately remove all visible dirt and plant debris. If water is used, the water/slurry shall be contained so as to restrict introduction of *Phragmites* rhizomes and seeds into the project site as well as to prevent off-site introduction during surplus material disposal.

3.10 MILITARY MUNITIONS

In the event military munitions, as defined in 40 CFR 260, are discovered or uncovered, immediately stop work in that area and immediately inform the Contracting Officer. See 01 35 30 MUNITIONS AND EXPLOSIVES OF CONCERN (MEC) CONSTRUCTION SUPPORT, LOW PROBABILITY SITE for details.

3.11 PETROLEUM, OIL, LUBRICANT (POL) STORAGE AND FUELING

POL products include flammable or combustible liquids, such as gasoline, diesel, lubricating oil, used engine oil, hydraulic oil, mineral oil, and cooking oil. Store POL products and fuel equipment and motor vehicles in a manner that affords the maximum protection against spills into the environment. Manage and store POL products in accordance with EPA 40 CFR 112, and other federal, state, regional, local laws and regulations, including the WFF ICP. Use secondary containments, dikes, curbs, and other barriers, to prevent POL products from spilling and entering the ground, storm or sewer drains, stormwater ditches or canals, or navigable waters of the United States. Describe in the EPP (see paragraph ENVIRONMENTAL PROTECTION PLAN) how POL tanks and containers must be stored, managed, and inspected and what protections must be provided. Storage of fuel on the project site must be in accordance with EPA, state, and local laws and regulations and paragraph OIL STORAGE INCLUDING FUEL TANKS.

All vehicles must be inspected for leaks immediately prior to work in the beach habitat. Construction vehicles must have leaks repaired and be cleaned thoroughly before being transported to the site or within the laydown area. All wash-water runoff and/or other harmful materials will be appropriately controlled to prevent entry into the beach habitat, including the dune area.

Contractors are encouraged to limit the use of contractor-owned mobile aboveground storage tanks (ASTs) on the facility prior to commencing work. If ASTs are used, the following conditions shall apply:

- a. Contractors are required to notify WFF of ASTs brought to the facility with a capacity greater than 55 gallons (208 liters), and tanks of 660 gallons (3,785 liters) or greater must have FMB and Environmental Office approval and include a storm water pollution prevention plan or other approved spill response plan. If the tank will be in use on WFF for more than 120 days, the Contractor must provide proof that the tank is registered with DEQ.
- b. Possible releases from portable ASTs must be addressed in the Contractor's Hazardous Materials Spill Plan or Contractor's other approved spill response plan. Possible releases must be handled in accordance with NASA WFF's approved Integrated Contingency Plan. WFF requires that contractors provide 110 percent capacity with impermeable secondary containment for all ASTs brought onto the facility by the Contractor.
- c. Tanks associated with portable generators are subject to the same regulations as portable ASTs.

Contractor will be responsible for proper storage and disposal of any hazardous material such as oils and fuels used during the construction of the breakwaters and beach fill operations.

3.11.1 Used Oil Management

Manage used oil generated on site in accordance with 40 CFR 279. Determine if any used oil generated while onsite exhibits a characteristic of hazardous waste. Used oil containing 1,000 parts per million of solvents is considered a hazardous waste and disposed of at the Contractor's expense. Used oil mixed with a hazardous waste is also considered a hazardous waste. Dispose in accordance with paragraph HAZARDOUS WASTE DISPOSAL.

3.11.2 Oil Storage Including Fuel Tanks

Provide secondary containment and overfill protection for oil storage tanks. A berm used to provide secondary containment must be of sufficient size and strength to contain the contents of the tanks plus 5 inches freeboard for precipitation. Construct the berm to be impervious to oil for 72 hours that no discharge will permeate, drain, infiltrate, or otherwise escape before cleanup occurs. Use drip pans during oil transfer operations; adequate absorbent material must be onsite to clean up any spills and prevent releases to the environment. Cover tanks and drip pans during inclement weather. Provide procedures and equipment to prevent overfilling of tanks. If tanks and containers with an aggregate aboveground capacity greater than 1320 gallons will be used onsite (only containers with a capacity of 55 gallons or greater are counted), provide and implement a Spill Prevention Control and Countermeasure (SPCC) plan meeting the requirements of 40 CFR 112. Do not bring underground storage tanks to the installation for Contractor use during a project. Submit the SPCC plan to the Contracting Officer for approval.

Monitor and remove any rainwater that accumulates in open containment dikes or berms. Inspect the accumulated rainwater prior to draining from a containment dike to the environment, to determine there is no oil sheen

present.

3.12 INADVERTENT DISCOVERY OF PETROLEUM-CONTAMINATED SOIL OR HAZARDOUS WASTES

If petroleum-contaminated soil, or suspected hazardous waste is found during construction that was not identified in the Contract documents, immediately notify the Contracting Officer. Do not disturb this material until authorized by the Contracting Officer.

3.13 POST CONSTRUCTION CLEANUP

Clean up areas used for construction in accordance with Contract Clause: "Cleaning Up". Unless otherwise instructed in writing by the Contracting Officer, remove traces of temporary construction facilities such as haul roads, work area, structures, foundations of temporary structures, stockpiles of excess or waste materials, and other vestiges of construction prior to final acceptance of the work. Grade parking area and similar temporarily used areas to conform with surrounding contours.

-- End of Section --

DRAFT
NOT FOR CONSTRUCTION

SECTION 01 57 30

ENVIRONMENTAL PERMIT WORK REQUIREMENTS
08/18

PART 1 GENERAL

1.1 ENVIRONMENTAL PERMITS AND COMMITMENTS

This paragraph supplements the Contractor's responsibility under the contract clause "PERMITS AND RESPONSIBILITIES" to the extent that the Government has obtained the permits from the USACE and VMRC, including Incidental Take Statements from National Marine Fisheries Service and U.S. Fish and Wildlife Service. Comply with the terms and conditions of the attached environmental documents at the end of this section. Complying with all environmental permits and commitments required by Federal, State, Regional, and local environmental laws and regulations is the Contractor's responsibility.

1.2 GENERAL INFORMATION

This SECTION supplements the contractor's responsibility under the CONTRACT CLAUSE "PERMITS AND RESPONSIBILITIES" to the extent that the Government has also entered into a binding agreement to remove the sand and obtain an environmental permit for the required borrow area. In addition, the borrow area is an area in a location where sea turtles and other endangered and threatened species may be encountered during the work. The Contractor is advised the Government has consulted with the National Marine Fisheries Service (NMFS) and U.S. Fish and Wildlife Service (USFWS), Virginia Marine Resources Commission (VMRC), Virginia Department of Wildlife Resources (VDWR), and qualified Environmental Point of Contact (EPOC) regarding the effects of sand excavation, truck haul of the material and beach fill on threatened and endangered species for this contract. To protect these species, the NMFS and USFWS has issued a Biological Opinion and Incidental Take Statement that is included as a part of this Section. The contract plans and specifications have been prepared to comply with the binding agreements established during the planning and development of this project. These special environmental requirements are an outgrowth of environmental commitments made by the NASA Wallops Flight Facility (WFF) during the project development and all transport and placement of sand material under this contract shall be in strict compliance with the conditions set forth in this agreement that are included as a part of this contract at the end of this Section. The Contractor is advised that any deviations from the construction methods and procedures indicated that any plans and specifications that are not prior approved in writing by the Contracting Officer, or any non-compliance with or violation of the conditions stated in this agreement and permits noted herein, shall be cause for the Contracting officer issuing a stop work order. Any stop work issued for any of these causes will not be subject to time extensions or cost recovery by the contractor. Any non-compliance with or violation of the conditions stated in the agreement noted herein may result in criminal and civil penalties against the Contractor.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" designation;

submittals not having a "G" designation are for information only or as otherwise designated. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Operational Plan to Minimize Turtle Takes, G, D0

PART 2 PRODUCTS

Not Used

PART 3 EXECUTION

3.1 SPECIAL PRECAUTIONS FOR SEA TURTLES DURING OPERATIONS

The Contractor shall develop a written Operational Plan to Minimize Turtle Takes during work performed on and after May 1 of any year until the last nest hatches. This Plan shall be prepared in consultation with the National Marine Fisheries Service (NMFS) Northeast Regional Office, Protected Resources Division (attention: Mary Colligan), One Blackburn Drive, Gloucester, Massachusetts 01930. The Contractor shall ensure the adequate instruction and training of all personnel associated with the operation of the work regarding the possible presence of endangered sea turtles and the need to avoid contact and collisions with these animals.

3.2 SPECIAL PRECAUTIONS FOR RED KNOT MIGRANTS/AMERICAN OYSTERCATCHERS/PIPING PLOVERS AND SEA TURTLES ON THE BEACH

The Contractor shall be aware that the nesting season for piping plovers and American oystercatchers start March 15 and the NASA Environmental Office will begin daily species monitoring on that day for nesting piping plovers, American oystercatchers, and red knot migrants, and continue until the last chick fledges or deemed nonviable by the VDWR. The Contractor shall also be aware that the nesting season for the sea turtles within the borrow site and beach fill areas begin on May 1 and the NASA Environmental Office will begin daily species monitoring on that day and continue until the last nest hatches or deemed nonviable by the VDWR.

All Contractor activities shall not begin until the last piping plover or American oystercatcher chicks have fledged, or the last sea turtle nest has hatched or been deemed nonviable by the VDWR staff, whichever is later. If a piping plover, American oystercatcher or sea turtle nest is found before sand mining and renourishment activities are completed, all activities must cease until the NASA Wallops Flight Facility Environmental Office (WFF) staff has been notified, and the VDGIF has made an on-site determination regarding a limit of construction radius around the nest. The Contractor shall continue work to the maximum extent possible remaining outside the VDWR designated radius, in coordination with NASA Wallops Flight Facility operations for use of potential haul roads if necessary to continue construction. All equipment and materials shall be staged in upland areas westward of the beach and outside of sensitive habitats (e.g., marshes, mudflats, dunes, wetlands).

If a sea turtle nest, piping plover nest, or American oystercatcher nest is excavated, the Contractor shall immediately contact NASA Environmental Office (WFF) at 757.824.1718 or other designated number. If a turtle nest,

pipin plover nest, or American oystercatcher nest is inadvertently dug up by the borrow site or beach fill construction activities or found by any other means in the area where the Contractor's activities may disturb the nest, the Contractor must stop all activities in the area and protect the discovery until the approved NASA Environmental Office POC and VDWR is notified and on the scene. The protected species monitor will prepare an Incident Statement on approved forms for all findings, recording the Contract number and title, date and time of discoveries, location and condition of findings, and provide a copy to the Contractor. The protected species monitor will at the same time forward a signed copy of the Incident Statement within 24 hours to the NASA Wallops Environmental Office, which will in turn provide information and inform and coordinate with USFWS and VDWR. The Contractor shall acknowledge the time and date of his receipt of the Incident Statement in his Daily Report of Operations and include a copy in his Daily Report of Operations and include a copy in his Daily Report to the Contracting Officer and the Norfolk District Project Manager.

Foot traffic must be minimized to the maximum extent practicable throughout beach habitat during construction.

-- End of Section --

DRAFT
NOT FOR CONSTRUCTION

SECTION 01 58 00

PROJECT IDENTIFICATION

08/19, CHG 5: 08/22

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

U.S. ARMY CORPS OF ENGINEERS (USACE)

EP 310-1-6a (2006; 2019 Change 2) Project Operation --
Sign Standards Manual, VOL 1

EP 310-1-6b (2006) Sign Standards Manual, VOL 2,
Appendices

1.2 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for information only. When used, a code following the "G" classification identifies the office that will review the submittal for the Government. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Preliminary One Line; G, R0

SD-02 Shop Drawings

Sign Legend Orders; G, R0

SD-04 Samples

Final Rendering Sample; G, R0

Final Framed Rendering and Copies; G, R0

1.3 QUALITY CONTROL

1.3.1 Rendering

Provide the project rendering in accordance with the following drawing stages as required in the SUBMITTALS paragraph. The following submittal data is required to properly identify the appropriate view and approve the final rendering of the facility. The final painted rendering will be used to produce the image for the signboard and framed photographic copies provided to the Contracting Officer.

1.3.1.1 Preliminary One Line Drawings

Provide three different views of the project site in a preliminary single line drawing (black and white) format. These three views will represent the best angles at which to view the proposed facility showing the best design features and the three dimensional character of the facility.

1.3.1.2 Final Rendering Sample

Provide a photographic copy (8 by 10 inches minimum size) of final rendering for approval of color, landscaping, and foreground/background development prior to final submittal.

1.3.1.3 Final Framed Rendering and Copies

Provide final full color rendering of the proposed facility as specified.

1.4 PROJECT IDENTIFICATION SIGN

1.4.1 Construction Project Signs

Furnish the construction project sign package, maintain the signs during construction, and remove the signs from the job site upon completion of the project. The construction project sign package consists of two signs: one for project identification and the other to show the on-the-job safety performance of the contractor. Ensure that the package conforms to the requirements of EP 310-1-6a and EP 310-1-6b, specifically Section 16. Submit the sign legend orders as described in Section 16 of EP 310-1-6a before erecting the signs.

Utilize the Example Graphic of Signage with Dimensions for MILCON Project and follow USACE policy provided in Engineering Pamphlet (EP) 310-1-6a, Sign Standards Manual, VOL 1 for guidelines on fabricating, locating, and mounting construction project signs:

https://www.publications.usace.army.mil/Portals/76/Users/182/86/2486/EP_310-1-6a%20cha

PART 2 PRODUCTS

Not Used

PART 3 EXECUTION

Not Used

-- End of Section --

SECTION 01 78 00

CLOSEOUT SUBMITTALS

05/19, CHG 1: 08/21

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

U.S. ARMY CORPS OF ENGINEERS (USACE)

EM 1110-1-2909	(2012) Engineering and Design -- Geospatial Data and Systems
ERDC/ITL TR-19-6	(2019) A/E/C Graphics Standard, Release 2.1
ERDC/ITL TR-19-7	(2019) A/E/C CAD Standard - Release 6.1

U.S. DEPARTMENT OF DEFENSE (DOD)

UFC 1-300-08	(2009; with Change 2, 2011) Criteria for Transfer and Acceptance of DoD Real Property
--------------	---

1.2 DEFINITIONS

1.2.1 As-Built Drawings

As-built drawings are the marked-up drawings, maintained by the Contractor on-site, that depict actual conditions and deviations from the Contract Documents. These deviations and additions may result from coordination required by, but not limited to: contract modifications; official responses to submitted Requests for Information (RFI's); direction from the Contracting Officer; design that is the responsibility of the Contractor, and differing site conditions. Maintain the as-builts throughout construction as red-lined hard copies on site and red-lined PDF files. These files serve as the basis for the creation of the record drawings.

1.2.2 Record Drawings

The record drawings are the final compilation of actual conditions reflected in the as-built drawings.

1.2.3 Record Model

A model reflecting approved changes during construction including red-lines, requests for information (RFI's), and contract modifications. Include updated construction phase facility/site data for components.

1.2.4 Advanced Modeling

A subset of geospatial technologies as defined in EM 1110-1-2909 to include Building Information Modeling (BIM), Civil Information Modeling

(CIM), Geographic Information Systems (GIS), and Computer-Aided Design (CAD). Advanced modeling is comprised of models and drawings that form a digital representation of the project, or part thereof, that are comprised of model elements with facility data.

1.2.5 USACE CAD/BIM Technology Center

The USACE CAD/BIM Technology Center hosts all standard content for USACE. This content can be accessed through the CAD/BIM Technology Center website, <https://cadbimcenter.erdc.dren.mil/>.

1.3 SOURCE DRAWING FILES

Request the full set of electronic drawings, in the source format, for Record Drawing preparation, after award and at least 30 days prior to required use.

1.3.1 Terms and Conditions

Data contained on these electronic files must not be used for any purpose other than as a convenience in the preparation of construction drawings and data for the referenced project. Any other use or reuse is at the sole risk of the Contractor and without liability or legal exposure to the Government. The Contractor must make no claim and waives to the fullest extent permitted by law, any claim or cause of action of any nature against the Government, its agents or sub consultants that may arise out of or in connection with the use of these electronic files. The Contractor must, to the fullest extent permitted by law, indemnify and hold the Government harmless against all damages, liabilities or costs, including reasonable attorney's fees and defense costs, arising out of or resulting from the use of these electronic files.

These electronic CAD drawing files are not construction documents. Differences may exist between the CAD files and the corresponding construction documents. The Government makes no representation regarding the accuracy or completeness of the electronic CAD files, nor does it make representation to the compatibility of these files with the Contractor hardware or software. In the event that a conflict arises between the signed and sealed construction documents prepared by the Government and the furnished Source drawing files, the signed and sealed construction documents govern. The Contractor is responsible for determining if any conflict exists. Use of these Source Drawing files does not relieve the Contractor of duty to fully comply with the contract documents, including and without limitation, the need to check, confirm and coordinate the work of all contractors for the project. If the Contractor uses, duplicates or modifies these electronic source drawing files for use in producing construction drawings and data related to this contract, remove all previous indicia of ownership (seals, logos, signatures, initials and dates).

1.4 RECORD DRAWINGS

The Government will provide pdf and/or program files at the preconstruction conference that contains one set of "as-designed" electronic CAD files in the specified software and format revised to reflect all amendments and the final contract PDF drawings. The CAD files are provided to enable preparation of as-built or as-constructed drawings. If discrepancies exist between the CAD files and the contract PDF drawings, correct the CAD files to show the contract PDF drawings.

1.4.1 Variation with Contract Drawings

The electronic files provided are not part of the contract documents. If there is any discrepancy between the electronic files and the contract drawings, the contract drawings govern. The Government has no responsibility to modify any Government Furnished Material (GFM) due to changes in the design that occur after award.

Evaluate the content and quality of the GFM upon receipt. If major discrepancies or omissions occur in the GFM, notify the Contracting Officer and indicate the nature of such variations.

1.4.2 Data Loss, Corruption, and Error

Transfer of GFM files may result in corrupted files resulting in data loss and errors. Use of GFM files at own risk. Verify data integrity upon receipt and request a replacement if necessary. Make any adjustment in file structure, format, or software version as needed to make GFM compatible with computer systems and/or software to meet the requirements of the contract.

1.4.3 Modeling Completeness and Quality

The Government makes no guarantee that the GFM provide the level of completeness or quality as required by the contract. Further, the Government makes no guarantee that identified variations will be corrected upon notification.

1.5 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for information only. When used, a code following the "G" classification identifies the office that will review the submittal for the Government. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-03 Product Data

Warranty Management Plan

Spare Parts Data

SD-08 Manufacturer's Instructions

Posted Instructions

SD-10 Operation and Maintenance Data

Operation and Maintenance Manuals; G, R0

SD-11 Closeout Submittals

As-Built Drawings; G, D0

Record Drawings; G, D0

Record Model; G, D0

As-Built Record of Equipment and Materials

Final Approved Shop Drawings; G, D0

Certification of EPA Designated Items; G, D0

Certification Of USDA Designated Items; G, D0

Interim DD FORM 1354; G, R0

Checklist for DD FORM 1354; G, R0

1.6 SPARE PARTS DATA

Submit two copies of the Spare Parts Data list.

- a. Indicate manufacturer's name, part number, and stock level required for test and balance, pre-commissioning, maintenance and repair activities. List those items that may be standard to the normal maintenance of the system.
- b. At acceptance of commissioning, ensure the required stock level is supplied as indicated in subparagraph a for maintenance and repair activities through the facilities warranty period. Provision of spare parts does not relieve the Contractor of responsibilities listed under the contract guarantee provisions.

1.7 QUALITY CONTROL

Additions and corrections to the contract drawings must be equal in quality and detail to that of the originals. Line colors, line weights, lettering, layering conventions, and symbols must be the same as the original line colors, line weights, lettering, layering conventions, and symbols. These must conform to ERDC/ITL TR-12-6 and ERDC/ITL TR-12-1.

1.8 WARRANTY MANAGEMENT

1.8.1 Warranty Management Plan

Develop a warranty management plan which contains information relevant to FAR 52.246-21 Warranty of Construction. At least 30 days before the planned pre-warranty conference, submit one set of the warranty management plan. Include within the warranty management plan all required actions and documents to assure that the Government receives all warranties to which it is entitled. The plan narrative must contain sufficient detail to render it suitable for use by future maintenance and repair personnel, whether tradesmen, or of engineering background, not necessarily familiar with this contract. The term "status" as indicated below must include due date and whether item has been submitted or was accomplished. Submit warranty information, made available during the construction phase, to the Contracting Officer for approval prior to each monthly pay estimate. Assemble approved information in a binder and turn over to the Government upon acceptance of the work. The construction warranty period must begin on the date of project acceptance and continue for the full product warranty period. Conduct a joint 4 month and 9 month warranty inspection, measured from time of acceptance; with the Contractor, Contracting Officer and the Customer Representative. The warranty management plan must include, but is not limited to, the following:

- a. Roles and responsibilities of personnel associated with the warranty process, including points of contact and telephone numbers within the organizations of the Contractors, subcontractors, manufacturers or suppliers involved.
- b. For each warranty, the name, address, telephone number, and e-mail of each of the guarantor's representatives nearest to the project location.
- c. A list and status of delivery of Certificates of Warranty for extended warranty items, including roofs, HVAC balancing, pumps, motors, transformers, and for commissioned systems, such as fire protection and alarm systems, sprinkler systems, and lightning protection systems.
- d. As-Built Record of Equipment and Materials list for each warranted equipment, item, feature of construction or system indicating:
 - (1) Name of item.
 - (2) Model and serial numbers.
 - (3) Location where installed.
 - (4) Name and phone numbers of manufacturers or suppliers.
 - (5) Names, addresses and telephone numbers of sources of spare parts.
 - (6) Warranties and terms of warranty. Include one-year overall warranty of construction, including the starting date of warranty of construction. Items which have warranties longer than one year must be indicated with separate warranty expiration dates.
 - (7) Cross-reference to warranty certificates as applicable.
 - (8) Starting point and duration of warranty period.
 - (9) Summary of maintenance procedures required to continue the warranty in force.
 - (10) Cross-reference to specific pertinent Operation and Maintenance manuals.
 - (11) Organization, names and phone numbers of persons to call for warranty service.
 - (12) Typical response time and repair time expected for various warranted equipment.
- e. The plans for attendance at the 4 and 9 month post-construction warranty inspections conducted by the Government.
- f. Procedure and status of tagging of equipment covered by warranties longer than one year.
- g. Copies of instructions to be posted near selected pieces of equipment where operation is critical for warranty or safety reasons.

1.8.2 Performance Bond

The Performance Bond must remain effective throughout the construction and warranty period.

- a. In the event the Contractor fails to commence and diligently pursue any construction warranty work required, the Contracting Officer will have the work performed by others, and after completion of the work, will charge the remaining construction warranty funds of expenses incurred by the Government while performing the work, including, but not limited to administrative expenses.

- b. In the event sufficient funds are not available to cover the construction warranty work performed by the Government at the Contractor's expense, the Contracting Officer will have the right to recoup expenses from the bonding company.
- c. Following oral or written notification of required construction warranty repair work, respond in a timely manner. Written verification will follow oral instructions. Failure to respond will be cause for the Contracting Officer to proceed against the Contractor.

1.8.3 Pre-Warranty Conference

Prior to contract completion, and at a time designated by the Contracting Officer, meet with the Contracting Officer to develop a mutual understanding with respect to the requirements of this section. At this meeting, establish and review communication procedures for Contractor notification of construction warranty defects, priorities with respect to the type of defect, reasonable time required for Contractor response, and other details deemed necessary by the Contracting Officer for the execution of the construction warranty. In connection with these requirements and at the time of the Contractor's quality control completion inspection, furnish the name, telephone number and address of a licensed and bonded company which is authorized to initiate and pursue construction warranty work action on behalf of the Contractor. This point of contact must be located within the local service area of the warranted construction, be continuously available, and be responsive to Government inquiry on warranty work action and status. This requirement does not relieve the Contractor of any of its responsibilities in connection with other portions of this provision.

1.8.4 Contractor's Response to Construction Warranty Service Requirements

Following oral or written notification by the Contracting Officer, respond to construction warranty service requirements in accordance with the "Construction Warranty Service Priority List" and the three categories of priorities listed below. Submit a report on any warranty item that has been repaired during the warranty period. Include within the report the cause of the problem, date reported, corrective action taken, and when the repair was completed. If the Contractor does not perform the construction warranty within the timeframe specified, the Government will perform the work and back charge the construction warranty payment item established.

- a. First Priority Code 1. Perform onsite inspection to evaluate situation, and determine course of action within 4 hours, initiate work within 6 hours and work continuously to completion or relief.
- b. Second Priority Code 2. Perform onsite inspection to evaluate situation, and determine course of action within 8 hours, initiate work within 24 hours and work continuously to completion or relief.
- c. Third Priority Code 3. All other work to be initiated within 3 work days and work continuously to completion or relief.

PART 2 PRODUCTS

2.1 RECORD DRAWINGS

Prepare the CAD drawing files in AutoCAD Release 2022 format compatible with a Windows 11 operating system.

2.1.1 Additional Drawings

If additional drawings are required, prepare them using the specified electronic file format applying ERDC/ITL TR-19-7 and ERDC/ITL TR-19-6. The title block and drawing border to be used for any new final record drawings must be identical to that used on the contract drawings.

2.1.1.1 Sheet Numbers and File Names

If a sheet needs to be added between two sequential sheets, append a Supplemental Drawing Designator in accordance with ERDC/ITL TR-19-7 Adding a drawing sheet, and ERDC/ITL TR-19-6 Adding or deleting drawing sheets and index sheet procedures.

2.2 ADVANCED MODELING PACKAGE

For each Advanced Modeling Package submittal for both the Interim Record Model Package and the Final Record Model Package, submit in accordance with ERDC/ITL TR-19-7 and also provide the following items:

- a. Advanced Modeling PxP: Provide an electronic copy of the most current approved version of the project Advanced Modeling PxP.
- b. Electronic Files: Provide an electronic list (.txt file or similar), of all submitted electronic files including a description, directory, and file name for each file submitted. Identify which files have been produced from the Model and Facility Data. For all sheet files, include a list of the sheet titles and sheet numbers.
- c. Advanced Modeling Submittal Checklist: Complete the USACE BIM/CIM Advanced Modeling Submittal Checklist and include with each submittal. Download the Checklist from the USACE CAD/BIM Technology Center website.
- d. Advanced Modeling Files: Provide all native Advanced Modeling files associated with the production of the contract drawings and associated as-modeled drawings. Update and maintain in compliance with the Advanced Modeling formatting, content requirement, and standards in order to yield a complete and coordinated document package.
- e. Quality Control (QC) Reports: Provide electronic PDFs of all QC reports and checklist utilized to ensure full compliance with the contract requirements and standards.
- f. CAD Exports of BIM-Generated Sheets and Drawings: Provide supplemental 2D CAD exports from the project BIM model as needed to demonstrate compliance with contract requirements. Export all contract drawings sheets to the CAD format(s).

2.3 CERTIFICATION OF EPA DESIGNATED ITEMS

Submit the Certification of EPA Designated Items as required by FAR 52.223-9 Estimate of Percentage of Recovered Material Content for EPA Designated Items and FAR 52-223-17 Affirmative Procurement of EPA designated items in Service and Construction Contracts. Include on the certification form the following information: project name, project number, Contractor name, license number, Contractor address, and certification. The certification will read as follows and be signed and

dated by the Contractor. "I hereby certify the information provided herein is accurate and that the requisition/procurement of all materials listed on this form comply with current EPA standards for recycled/recovered materials content. The following exemptions may apply to the non-procurement of recycled/recovered content materials:

- a. The product does not meet appropriate performance standards;
- b. The product is not available within a reasonable time frame;
- c. The product is not available competitively (from two or more sources);
- d. The product is only available at an unreasonable price (compared with a comparable non-recycled content product).

2.4 CERTIFICATION OF USDA DESIGNATED ITEMS

Submit the Certification of USDA Designated Items as required by FAR 52-223-1 Bio-based Product Certifications and FAR 52.223-2 Affirmative Procurement of Biobased Products Under Service and Construction Contracts. Include on the certification form the following information: project name, project number, Contractor name, license number, Contractor address, and certification. The certification will read as follows and be signed and dated by the Contractor. "I hereby certify the information provided herein is accurate and that the requisition/procurement of all materials listed on this form comply with current USDA standards for biobased materials content. The following exemptions may apply to the non-procurement of biobased content materials:

- a. The product does not meet appropriate performance standards;
- b. The product is not available within a reasonable time frame;
- c. The product is not available competitively (from two or more sources);
- d. The product is only available at an unreasonable price (compared with a comparable bio-based content product).

2.5 PDF AS-BUILT FILES

Provide electronic PDF "plots" of all contract drawings sheets associated with the as-built drawing submittal. Compile and organize the PDF set to match the contract drawings. Bookmark and label the pages of the PDF file in accordance with ERDC/ITL TR-19-6 and ERDC/ITL TR-19-7.

2.6 REDLINES AND MARKUPS

Provide PDFs of the current working redlines and/or markups complying with the as-builts drawing and markup requirements contained in this specification.

2.7 GEO-DATA-BASE FILES

Provide a SDSFIE/FGDC GeoReferenced personal GeoDataBase. For all information outside of the building walls, provide a personal GeoDataBase in .mdb format using the latest version of Spatial Data Standard for Facilities, Infrastructure, and Environment (SDSFIE) as the database structure. Provide a shell database to define the projection and database structure.

For all drawings within and including the exterior walls, utilize the advanced modeling formats described and referenced herein. Provide a short GeoDataBase read-me file explaining the deliverable. The read-me file will include a description of the software used to create the data, projection, and include the attribute tables used.

2.8 AS-BUILT OR ADVANCED MODELING RE-SUBMISSION REQUIREMENTS

If elements of an as-built submittal or advanced modeling package are rejected, provide the following for each re-submission, in addition to any information required in Section 01 33 00 SUBMITTAL PROCEDURES:

- a. Re-submit all components required under paragraph As-Builts or Advanced Modeling Package, including a new Advanced Modeling Submittal Checklist and updated content in response to Government comments.
- b. Provide a copy of all Government review comments.
- c. Provide a disposition/response to each Government review comment for a back-check of the re-submission deliverable.

PART 3 EXECUTION

3.1 AS-BUILT DRAWINGS

Provide and maintain two black line print copies of the PDF contract drawings for As-Built Drawings. Maintain the as-builts throughout construction as red-lined hard copies on site and red-lined PDF files. Submit As-Built Drawings 30 days prior to Beneficial Occupancy Date (BOD).

3.1.1 Markup Guidelines

Make comments and markup the drawings complete without reference to letters, memos, or materials that are not part of the As-Built drawing. Show what was changed, how it was changed, where item(s) were relocated and change related details. These working as-built markup prints must be neat, legible and accurate as follows:

- a. Use base colors of red, green, and blue. Color code for changes as follows:
 - (1) Special (Blue) - Items requiring special information, coordination, or special detailing or detailing notes.
 - (2) Deletions (Red) - Over-strike deleted graphic items (lines), lettering in notes and leaders.
 - (3) Additions (Green) - Added items, lettering in notes and leaders.
- b. Provide a legend if colors other than the "base" colors of red, green, and blue are used.
- c. Add and denote any additional equipment or material facilities, service lines, incorporated under As-Built Revisions if not already shown in legend.
- d. Use frequent written explanations on markup drawings to describe changes. Do not totally rely on graphic means to convey the revision.

- e. Use legible lettering and precise and clear digital values when marking prints. Clarify ambiguities concerning the nature and application of change involved.
- f. Wherever a revision is made, also make changes to related section views, details, legend, profiles, plans and elevation views, schedules, notes and call out designations, and mark accordingly to avoid conflicting data on all other sheets.
- g. For deletions, cross out all features, data and captions that relate to that revision.
- h. For changes on small-scale drawings and in restricted areas, provide large-scale inserts, with leaders to the applicable location.
- i. Indicate one of the following when attaching a print or sketch to a markup print:
 - 1) Add an entire drawing to contract drawings
 - 2) Change the contract drawing to show changes on the drawing.
 - 3) Provided for reference only to further detail the initial design.
- j. Incorporate all shop and fabrication drawings into the markup drawings.

3.1.2 As-Built Drawings Content

Revise As-Built Drawings and red-lined PDF files in accordance with ERDC/ITL TR-19-6 and ERDC/ITL TR-19-7. Keep these working as-built markup drawings current on a weekly basis and at least one set available on the jobsite at all times. Changes from the contract drawings which are made during construction or additional information which might be uncovered in the course of construction must be accurately and neatly recorded as they occur by means of details and notes. Submit the working as-built markup drawings for approval prior to submission of each monthly pay estimate. For failure to maintain the working and final record drawings as specified herein, the Contracting Officer will withhold 10 percent of the monthly progress payment until approval of updated drawings. Show on the as-built drawings, but not limited to, the following information:

- a. The actual location, kinds and sizes of all sub-surface utility lines. In order that the location of these lines and appurtenances may be determined in the event the surface openings or indicators become covered over or obscured, show by offset dimensions to two permanently fixed surface features the end of each run including each change in direction on the record drawings. Locate valves, splice boxes and similar appurtenances by dimensioning along the utility run from a reference point. Also record the average depth below the surface of each run.
- b. The location and dimensions of any changes within the building structure.
- c. Layout and schematic drawings of electrical circuits and piping.
- d. Correct grade, elevations, cross section, or alignment of roads, earthwork, structures or utilities if any changes were made from

contract plans.

- e. Changes in details of design or additional information obtained from working drawings specified to be prepared or furnished by the Contractor; including but not limited to shop drawings, fabrication, erection, installation plans and placing details, pipe sizes, insulation material, dimensions of equipment, and foundations.
- f. The topography, invert elevations and grades of drainage installed or affected as part of the project construction.
- g. Changes or Revisions which result from the final inspection.
- h. Where contract drawings or specifications present options, show only the option selected for construction on the working as-built markup drawings.
- i. If borrow material for this project is from sources on Government property, or if Government property is used as a spoil area, furnish a contour map of the final borrow pit/spoil area elevations.
- j. Systems designed or enhanced by the Contractor, such as HVAC controls, fire alarm, fire sprinkler, and irrigation systems.
- k. Changes in location of equipment and architectural features.
- l. Modifications.
- m. Actual location of anchors, construction and control joints, etc., in concrete.
- n. Unusual or uncharted obstructions that are encountered in the contract work area during construction.
- o. Location, extent, thickness, and size of stone protection particularly where it will be normally submerged by water.

3.2 RECORD DRAWING FILES

If additional drawings are required, prepare them using the specified electronic file format applying ERDC/ITL TR-19-7 and ERDC/ITL TR-19-6. The title block and drawing border to be used for any new final record drawings must be identical to that used on the contract drawings. Accomplish additions and corrections to the contract drawings using CAD files. Provide all program files and hardware necessary to prepare final PDF record drawings. The Contracting Officer will review final PDF record drawings for accuracy and return them to the Contractor for required corrections, changes, additions, and deletions.

3.2.1 Rename the CAD Drawing files

Rename the CAD Drawing files using the contract number as the Project Code field, (e.g., W91238-15-C-10A-102.DWG) as instructed in the Pre-Construction conference. Use only those renamed files for the Marked-up changes. Make all changes on the layer/level as the original item.

- a. For AutoCAD files (DWG), enter all as-built delta changes and notations on the AS-BUILT layer.

- b. When final revisions have been completed, show the wording "RECORD DRAWING AS-BUILTS" followed by the name of the Contractor in letters at least 3/16 inch high on the cover sheet drawing. Date RECORD DRAWING AS-BUILTS" drawing revisions in the revision block.
- c. Within 14 days after Government approval of all of the working record drawings for a phase of work, prepare the final CAD record drawings for that phase of work and submit PDF drawing files and two sets of prints for review and approval. The Government will promptly return one set of prints annotated with any necessary corrections. Within days revise the CAD files accordingly at no additional cost and submit one set of final prints for the completed phase of work to the Government. Within 20 days of substantial completion of all phases of work, submit the final record drawing package for the entire project. Submit one set of electronic CAD files, and one set of the approved working record PDF and or program files with two sets of prints. The CAD files must be complete in all details and identical in form and function to the CAD drawing files supplied by the Government. Prepare AutoCAD files for transmittal using e-Transmit. Make any transactions or adjustments necessary to accomplish this. The Government reserves the right to reject any drawing files it deems incompatible with the customer's CAD system. Paper prints, drawing files and storage media submitted will become the property of the Government upon final approval. Failure to submit final record PDF drawing files, CAD files and marked prints as specified will be cause for withholding any payment due under this contract. Approval and acceptance of final record drawings must be accomplished before final payment is made.

3.3 RECORD DRAWINGS

Prepare final record drawings after the completion of each definable phase of work as listed in the Contractor Quality Control Plan (such as Foundations, Utilities, or Structural Steel as appropriate for the project). Transfer the changes from the approved working as-built markup drawings to the original electronic CAD drawing files. Modify the as-built CAD drawing files to correctly show the features of the project as-built by bringing the working CAD drawing set into agreement with approved working as-built markup drawings, and adding such additional drawings as may be necessary. Refer to ERDC/ITL TR-19-6. Jointly review the working as-built markup drawings with printouts from working as-built CAD drawing PDF files for accuracy and completeness. Monthly review of working as-built CAD drawing PDF file printouts must cover all sheets revised since the previous review. These PDF drawing files are part of the permanent records of this project. Any drawings damaged or lost must be satisfactorily replaced at no expense to the Government.

Drawing revisions (include within change order price the cost to change working and final record drawings to reflect revisions) and compliance with the following procedures.

- a. Follow directions in the revision for posting descriptive changes.
- b. The revision delta size must be 5/16 inch unless the area where the delta is to be placed is crowded. Use a smaller size delta for crowded areas.
- c. Place a revision delta at the location of each deletion.

- d. For new details or sections which are added to a drawing, place a revision delta by the detail or section title.
- e. For minor changes, place a revision delta by the area changed on the drawing (each location).
- f. For major changes to a drawing, place a revision delta by the title of the affected plan, section, or detail at each location.
- g. For changes to schedules or drawings, place a revision delta either by the schedule heading or by the change in the schedule.

3.3.1 Final Record Drawing Package

Submit the final record PDF and CAD drawings package for the entire project within 20 days of substantial completion of all phases of work. Submit one set of ANSI D size PDF and CAD files, two sets of ANSI D size prints and one set of the approved working record drawings. The package must be complete in all details and identical in form and function to the contract drawing files supplied by the Government.

3.4 FINAL APPROVED SHOP DRAWINGS

Submit final approved project shop drawings 20 days after transfer of the completed facility.

3.5 AS-BUILT RECORD OF EQUIPMENT AND MATERIALS

Furnish one copy of preliminary record of equipment and materials used on the project 15 days prior to final inspection. This preliminary submittal will be reviewed and returned 2 days after final inspection with Government comments. Submit Two sets of final record of equipment and materials 10 days after final inspection. Key the designations to the related area depicted on the contract drawings. List the following data:

RECORD OF DESIGNATED EQUIPMENT AND MATERIALS DATA				
Description	Specification Section	Manufacturer and Catalog, Model, and Serial Number	Composition and Size	Where Used

3.6 OPERATION AND MAINTENANCE MANUALS

Provide project operation and maintenance manuals as specified in Section 01 78 23 OPERATION AND MAINTENANCE DATA.

3.7 CLEANUP

Sweep paved areas and rake clean landscaped areas. Remove waste and surplus materials, rubbish and construction facilities from the site. Recycle, salvage, and return construction and demolition waste from project. Promptly and legally transport and dispose of any trash. Do not burn, bury, or otherwise dispose of trash on the project site.

3.8 REAL PROPERTY RECORD

Refer to UFC 1-300-08 for instruction on completing the DD FORM 1354. Contact the Contracting Officer for any project specific information necessary to complete the DD FORM 1354.

3.8.1 Interim DD FORM 1354

Near the completion of Project, but a minimum of 60 days prior to final acceptance of the work, complete and submit an accounting of all installed property with Interim DD FORM 1354. Include any additional assets, improvements, and alterations from the Draft DD FORM 1354.

3.8.2 Completed DD FORM 1354

For convenience, a blank fillable PDF DD FORM 1354 may be obtained at the following link:

www.esd.whs.mil/Portals/54/Documents/DD/forms/dd/dd1354.pdf

Submit the completed Checklist for DD FORM 1354 of Installed Building Equipment items. Attach this list to the updated DD FORM 1354.

-- End of Section --

SECTION 01 78 23

OPERATION AND MAINTENANCE DATA
05/23

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN SOCIETY OF HEATING, REFRIGERATING AND AIR-CONDITIONING ENGINEERS (ASHRAE)

ASHRAE GUIDELINE 1.4 (2019) Preparing Systems Manuals for Facilities

ASTM INTERNATIONAL (ASTM)

ASTM E1971 (2005; R 2011) Standard Guide for Stewardship for the Cleaning of Commercial and Institutional Buildings

ASTM E2166 (2016; R 2023) Standard Practice for Organizing and Managing Building Data

1.2 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for information only. When used, a code following the "G" classification identifies the office that will review the submittal for the Government. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-10 Operation and Maintenance Data

Facility Data Workbook; G, R0

Training Plan; G, R0

Training Outline; G, R0

Training Content; G, R0

Operation And Maintenance Manual, Progress Submittal; G, R0

Operation And Maintenance Manual, Prefinal Submittal; G, R0

Operation And Maintenance Manual, Final Submittal; G, R0

SD-11 Closeout Submittals

Training Video Recording; G, R0

Validation of Training Completion; G, R0

Training Plan; G, R0

Record Drawings And Utility Systems; G, R0

1.3 MEETINGS

To assure that Operation and Maintenance Manual and Facility Data Workbook requirements are being met through the duration of the project, organize the following meetings and discuss the subsequent topics:

1.3.1 Pre-Construction Meeting

At a minimum, discuss the following:

- a. The requirement for Operation and Maintenance Manuals and Facility Data deliverables under this contract including coordination meetings
- b. Processes and method of gathering Facility Data information during construction
- c. Primary roles and responsibilities associated with the development and delivery of the Operation and Maintenance Manuals and Facility Data deliverables, and
- d. Identify and agree upon a date and attendance list for the meetings described below:

1.3.2 Operation and Maintenance Manual and Facility Data Workbook Coordination Meeting

Facilitate a meeting after the Pre-Construction Meeting prior to the submission of the Operation and Maintenance Manual Progress Submittal. Meeting attendance must include the Contractor's Operation and Maintenance Manual and Facility Data Workbook Preparer, Designer of Record (DOR), Quality Control Manager, the Government's Design Manager (DM), Contracting Officer's Representative, and Government's facility data reviewer. Include any Mechanical, Electrical, and Fire Protection Sub-Contractors.

The purpose of this meeting is to reach a mutual understanding of the scope of work concerning the contract requirements for Operation and Maintenance Manual and coordinate the efforts necessary by both the Government and Contractor to ensure an accurate collection, preparation and timely Government review of Operation and Maintenance Manual.

1.3.3 Submittal Coordination Meeting

Facilitate a meeting following submission and Government review of each design or progress submittal of the Operation and Maintenance Manual and Facility Data Workbook.

- a. Include personnel from the Coordination meeting and any additional personnel identified.
- b. The purpose of this meeting is to demonstrate ongoing compliance with the requirements identified in this specification. Discuss Government review comments and unresolved items preventing completion and Government approval of the Operation and Maintenance Manuals and Facility Data Workbook (FDW).

- c. The applicable deliverables, along with Government remarks associated with review of these submittals serve as the primary guide and agenda for this meeting.

1.3.4 Facility Turnover Meeting

Include Operation and Maintenance Manual in NAVFAC Red Zone (NRZ) facility turnover meetings as specified in Section 01 30 00, ADMINISTRATIVE REQUIREMENTS.

1.4 FACILITY DATA WORKBOOK

Develop an editable, electronic spreadsheet based on the equipment in the Operation and Maintenance Manuals that contains the information required to start a preventive maintenance program. As a minimum, provide Facility Data Workbook as a list of system equipment, location installed, warranty expiration date, manufacturer, model, and serial number.

1.5 OPERATION AND MAINTENANCE MANUAL MEDIA

Assemble Operation and Maintenance Manual into an electronically bookmarked file using the most current version of Adobe Acrobat or similar software capable of producing PDF file format. Provide compact disks (CD) or data digital versatile disk (DVD) as appropriate, so that each one contains operation, maintenance and record files, project record documents, and training videos. Include a complete bookmarked operation and maintenance directory.

1.5.1 CD or DVD Label and Disk Holder or Case

Provide the following information on the disk label and disk holder or case:

- a. Building Number
- b. Project Title
- c. Activity and Location
- d. Construction Contract Number
- e. Prepared For: (Contracting Agency)
- f. Prepared By: (Name, title, phone number and email address)
- g. Include the disk content on the disk label
- h. Date
- i. Virus scanning program used

1.5.2 O&M Manual Tabbed Hard Copy

Provide a hard copy of the O&M manual upon completion of the project. Provide tabs for each section and subsection for ease of navigation by the user.

1.6 O&M MANUAL CONTENT

Organize the book marked Operation and Maintenance Manual into the following Parts in accordance with ASHRAE GUIDELINE 1.4, and as modified and detailed below. Word template for O&M Manual is available at: <https://www.wbdg.org/dod/ufgs/ufgs-01-78-23>.

1.6.1 Part 1: Executive Summary

Provide a summary of the information found in the O&M manual including the purpose of the manual and a description of the manual's organization.

1.6.2 Part 2: Facility Design and Construction

1.6.2.1 General Facility and Systems Description

Provide an overview of the intent for design and use of the facility. Provide a PDF of the Record Drawings prepared in accordance with 01 78 00 CLOSEOUT SUBMITTALS and bookmarked using the sheet title and sheet number. Include uncluttered 11 by 17 inches floor plans with room numbers, type or function of space, and overall facility dimensions on the floor plans. Do not include items such as construction instructions, references, or frame numbers.

Detail the overall dimensions of the facility, number of floors, foundation type, expected number of occupants, and facility Category Code list and generally describe all the facility systems and any special building features (for example, HVAC Controls, Sprinkler Systems, Cranes, Elevators, and Generators). Include photographs marked up and labeled to show key operating components and the overall facility appearance.

1.6.2.2 Basis of Design

Provide a copy of the contract Basis of Design.

1.6.2.3 Contract Documents, RFP, Amendments, and Modifications

Provide the contract construction documents complete, to include specifications, drawings, Request for Proposal, amendments, and modifications.

1.6.2.4 Room Inventory of Real Property and Finishes

Provide a list of installed equipment furnished under this contract. Include all information usually listed on manufacturer's name plate. Include, as applicable, the following information for each piece of equipment installed: description of item, all dimensions, location by room number, model number, serial number, capacity, name and address of manufacturer, name and address of equipment supplier, condition, spare parts list, manufacturer's catalog, and warranty. Real property includes, but is not limited to, floor coverings, wall surfaces, ceiling surfaces, windows, roofing, HVAC filters, plumbing fixtures, and lighting fixtures. Submit the final list 30 days after transfer of the completed facility.

Include spatial data defining actual net square footage and data of each room. Also include the room finish schedule including room names and numbers. Include schedules in the construction drawings in the room inventory. Add a column to each schedule to record what was provided by the contractor during construction. Provide a PDF of room inventory. Key

the designations to the related area depicted on the contract drawings.
List the following data:

RECORD OF DESIGNATED EQUIPMENT AND MATERIALS DATA				
Description	Specification Section	Manufacturer and Catalog, Model, and Serial Number	Composition and Size	Where Used

1.6.3 Part 3: Facilities, Systems, and Assemblies Information

1.6.3.1 Organization

Bookmark information in this section using the current version of ASTM E2166 Unifomat II, UFGS numbers, and document type as outlined in the example below. Bookmark/tab each item to the third level for easy navigation of the manual.

Example as shown in Table below:

PARTS AND SUBPART NUMBERING
3.1 B20 EXTERIOR CLOSURE (System)
3.1.1 B2030 EXTERIOR DOORS (Subsystem)
3.1.1.1 B2030110 GLAZED DOORS (Component)
3.1.1.1.1 Applicable specifications List in UFGS Format
3.1.1.1.2 Manufacturer's Operations and Maintenance Data
3.1.1.1.3 Approved Submittal
3.1.1.1.4 Coordination/Shop Drawings
3.1.1.1.5 Sequence of Operation for Operating Equipment
3.1.1.1.6 Testing Equipment Information and Performance Data
3.1.1.1.7 Routine Maintenance Requirements
3.1.1.1.8 Repair Procedures
3.1.1.1.9 Emergency Procedures & Locations of Applicable Controls
3.1.1.1.10 Warranties
3.1.1.1.11 Record Drawings and Utility Systems
3.1.1.1.12 Contractor / Supplies Listing and Contact Information

1.6.3.2 Related Specifications

Reference each specification related to the subsystem in this section, and locate the actual specification section in Part 2 of the O&M Manual. List specifications in table format as shown in the below example.

UFGS Number	Specification Title	Page Spec Begins in Part 2

1.6.3.3 Manufacturer's Operations and Maintenance Data

Provide a copy of all manufacturer specifications and cutsheets. Provide text-searchable, high-quality document files from the manufacturer's online or electronic documentation. Color documents are preferred. Provide documents specific to the product(s) installed under this Contract. Provide identification and coverage for the parts of each component, assembly, subassembly, and accessory of the end items subject to replacement. Provide Uniformat II Level 3 identification for D20, D30, D40 installed equipment. When possible, do not submit document files containing multiple product catalogs from the same manufacturer, or product data from multiple manufacturers in the same files. Provide documents directly from the manufacturer whenever possible. Do not provide scanned copies of hardcopy documents. Provide identification and coverage for the parts of each component, assembly, subassembly, and accessory of the end items subject to replacement. Include special hardware requirements, such as requirement to use high-strength bolts and nuts. Identify parts by make, model, serial number, and source of supply to allow reordering without further identification. Provide clear and legible illustrations, drawings, and exploded views to enable easy identification of the items. When illustrations omit the part numbers and description, both the illustrations and separate listing must show the index, reference, or key number that will cross-reference the illustrated part to the listed part. Group the parts shown in the listings by components, assemblies, and subassemblies in accordance with the manufacturer's standard practice. Parts data may cover more than one model or series of equipment, components, assemblies, subassemblies, attachments, or accessories, such as typically shown in a master part catalog.

1.6.3.4 Approved Submittals and Certificates

Provide a copy of all submittals documented with the required approval as applicable for each UFGS specification listed in the table outlined in applicable specifications. Include copies of SD-07 Certificates submittals documented with the required approval, SD-08 Manufacturer's Instructions submittals documented with the required approval, and SD-10 Operation and Maintenance Data submittals documents with the required approval.

1.6.3.5 Approved Coordination/Shop Drawings

Drawings, diagrams and schedules specifically prepared to illustrate some portion of the work. Diagrams and instructions from a manufacturer or fabricator for use in producing the product and as aids to the Contractor for integrating the product or system into the project. Drawings prepared

by or for the Contractor to show how multiple systems and interdisciplinary work will be coordinated.

1.6.4 Sequence of Operation for Operating Equipment

Provide record one-line diagrams for each floor, delineating mechanical equipment location within the building. Provide specific instructions, procedures, and illustrations for the following phases of operation for the installed model and features of each system:

1.6.4.1 Safety Precautions and Hazards

List personnel hazards and equipment or product safety precautions for operating conditions. List all residual hazards identified in the Activity Hazard Analysis provided under Section 01 35 26 GOVERNMENTAL SAFETY REQUIREMENTS. Provide recommended safeguards for each identified hazard. Specify if any certifications or licenses are required to operate the equipment.

1.6.4.2 Operator Prestart

Provide procedures required to install, set up, and prepare each system for use.

1.6.4.3 Startup, Shutdown, and Post-Shutdown Procedures

Provide narrative description for Startup, Shutdown and Post-shutdown operating procedures including the control sequence for each procedure.

1.6.4.4 Normal Operations

Provide Control Diagrams with data to explain operation and control of systems and specific equipment. Provide narrative description of Normal Operating Procedures.

1.6.4.5 Emergency Operations

Provide Emergency Procedures for equipment malfunctions to permit a short period of continued operation or to shut down the equipment to prevent further damage to systems and equipment. Provide Emergency Shutdown Instructions for fire, explosion, spills, or other foreseeable contingencies. Provide guidance and procedures for emergency operation of utility systems including required valve positions, valve locations and zones or portions of systems controlled.

1.6.4.6 Operator Service Requirements

Provide instructions for services to be performed by the operator such as lubrication, adjustment, inspection, and recording gauge readings.

1.6.4.7 Environmental Conditions

Provide a list of Environmental Conditions (temperature, humidity, and other relevant data) that are best suited for the operation of each product, component or system. Describe conditions under which the item equipment should not be allowed to run.

1.6.4.8 Operating Log

Provide forms, sample logs, and instructions for maintaining necessary operating records.

1.6.4.9 Additional Requirements for Equipment Control Systems

Provide Data Package 5 and the following for all control systems:

- a. Provide a narrative description on how to perform and apply functions, features, modes, and other operations, including unoccupied operation, seasonal changeover, manual operation, and alarms. Include detailed technical manual for programming and customizing control loops and algorithms.
- b. Submit complete controls equipment schedules, full as-built sequence of operations, wiring and logic diagrams, Input/Output Tables, equipment schedules, copies of checkout tests and calibrations performed by the Contractor (not Cx tests), and all associates information.
- c. Full points list. Provide a listing of rooms with the following information for each room:
 - (1) Floor
 - (2) Room number
 - (3) Room name
 - (4) Air handler unit ID
 - (5) Reference drawing number
 - (6) Air terminal unit tag ID
 - (7) Heating or cooling valve tag ID
 - (8) Minimum cfm
 - (9) Maximum cfm
- d. Full print out of all schedules and set points after testing and acceptance of the system.
- e. Full as-built print out of software program.
- f. Marking of system sensors and thermostats on the as-built floor plan and mechanical drawings with their control system designations.

1.6.4.10 Testing Equipment Information and Performance Data

Include information on test equipment required to perform specified tests and on special tools needed for the operation, maintenance, and repair of components. Provide final set points.

Include completed prefunctional checklists, functional performance test forms, and monitoring reports. Include recommended schedule for retesting and blank test forms. Provide final set points.

1.6.5 Routine Maintenance Requirements

1.6.5.1 Preventive Maintenance Plan, Schedule, and Procedures

Provide manufacturer's schedule for routine preventive maintenance, inspections, condition monitoring (predictive tests) and adjustments required to ensure proper and economical operation and to minimize repairs. Provide instructions stating when the systems should be retested. Provide manufacturer's projection of preventive maintenance work-hours on a daily, weekly, monthly, and annual basis including requirements by type of activity. For periodic calibrations, provide manufacturer's specified frequency and procedures for each separate operation.

- a. Define the anticipated time required to perform each of each test (work-hours), test apparatus, number of personnel identified by responsibility, and a testing validation procedure permitting the record operation capability requirements within the schedule. Provide a remarks column for the testing validation procedure referencing operating limits of time, pressure, temperature, volume, voltage, current, acceleration, velocity, alignment, calibration, adjustments, cleaning, or special system notes. Delineate procedures for preventive maintenance, inspection, adjustment, lubrication and cleaning necessary to minimize repairs.
- b. Repair requirements must inform operators how to check out, troubleshoot, repair, and replace components of the system. Include electrical and mechanical schematics and diagrams and diagnostic techniques necessary to enable operation and troubleshooting of the system after acceptance.

1.6.5.2 Lubrication Data

Include the following preventive maintenance lubrication data, in addition to instructions for lubrication required under paragraph OPERATOR SERVICE REQUIREMENTS:

- a. A table showing recommended lubricants for specific temperature ranges and applications.
- b. Charts with a schematic diagram of the equipment showing lubrication points, recommended types and grades of lubricants, and capacities. Provide procedural instructions for Oil Sampling for all equipment.
- c. A Lubrication Schedule showing service interval frequency.

1.6.6 Repair Procedures

Provide instructions and a list of tools required to repair or restore the product or equipment to proper condition or operating standards. Provide manufacturer's recommended procedures and instructions for correcting problems and making repairs for the installed model and features of each system. Include potential environmental and indoor air quality impacts of recommended maintenance procedures and materials. Specify if any certifications or licenses are required to repair the equipment.

1.6.6.1 Troubleshooting Guides and Diagnostic Techniques

Provide step-by-step procedures to promptly isolate the cause of typical malfunctions. Describe clearly why the checkout is performed and what conditions are to be sought. Identify tests or inspections and test equipment required to determine whether parts and equipment may be reused or require replacement.

1.6.6.2 Wiring Diagrams and Control Diagrams

Provide point-to-point drawings of wiring and control circuits including factory-field interfaces. Provide a complete and accurate depiction of the actual job specific wiring and control work. On diagrams, number electrical and electronic wiring and pneumatic control tubing and the terminals for each type, identically to actual installation configuration and numbering.

1.6.6.3 Removal and Replacement Instructions

Provide step-by-step procedures and a list of required specialty tools and supplies for removal, replacement, disassembly, and assembly of components, assemblies, subassemblies, accessories, and attachments. Provide tolerances, dimensions, settings and adjustments required. Use a combination of text and illustrations.

1.6.6.4 Repair Work-Hours

Provide manufacturer's projection of repair work-hours including requirements by type of craft. Identify, and tabulate separately, repair that requires the equipment manufacturer to complete or to participate.

1.6.6.5 Warranty Information

List and explain the various warranties and clearly identify the servicing and technical precautions prescribed by the manufacturers or contract documents in order to keep warranties in force. Identify if replacement of a subassembly, attachment or accessory requires the entire assembly to be replaced. Include warranty information for primary components of the system. Provide copies of warranties required by Section 01 78 00 CLOSEOUT SUBMITTALS.

1.6.6.6 Extended Warranty Information

List all warranties for products, equipment, components, and sub-components whose duration exceeds one year. For each warranty listed, indicate the applicable specification section, duration, start date, end date, and the point of contact for warranty fulfillment. Also, list or reference the specific operation and maintenance procedures that must be performed to keep the warranty valid. Provide copies of warranties required by Section 01 78 00 CLOSEOUT SUBMITTALS.

1.6.6.7 Record Drawings and Utility Systems

The record drawings are the final compilation of actual conditions reflected in the as-built drawings. Provide record drawings as outlined in 01 78 00 CLOSEOUT SUBMITTALS.

Using Record Source Drawings, show and document details of the actual installation of the utility systems, annotate and highlight the Operation

and Maintenance information. Provide the following drawings at a large enough scale to differentiate designated isolation units from surrounding valves and switches.

1.6.6.8 Personnel Training Requirements

Provide information available from the manufacturers that is needed for use in training designated personnel to properly operate and maintain the equipment and systems.

1.6.6.9 Contractor / Supplier Listing and Contact Information

Provide a list that includes the name, address, telephone number, email and website of the General Contractor and each Subcontractor who installed the product or equipment, or system. For each item, also provide the name address and telephone number of the manufacturer's representative and service organization that can provide replacements most convenient to the project site. Provide the name, address, and telephone number of the product, equipment, and system manufacturers.

1.6.7 Part 4: Facility Operations

1.6.7.1 Completed Facility Operating Plan

Provide a plan that documents that procedures for the operation of systems and assemblies in the facility. The systems that should be included in the Operating Plan include, but are not limited to:

- a. Electrical systems and equipment
- b. Mechanical systems and equipment
- c. Fire Protection systems and equipment
- d. Control Systems and equipment
- e. Architectural and Structural systems, fixtures, structures, and equipment
- f. Vertical transportation such as elevators and escalators

1.6.7.2 Testing Equipment and Special Tool Information

Include information on test equipment required to perform specified tests and on special tools needed for the operation, maintenance, and repair of components. Provide final set points.

1.6.7.3 Testing and Performance Data

Include completed prefunctional checklists, functional performance test forms, and monitoring reports. Include recommended schedule for retesting and blank test forms. Provide final set points.

1.6.7.4 Approved Field Test Reports and Manufacturer's Field Reports

Compile and provide approved Field Test Reports (SD-06) and Manufacturer's Field Reports (SD-09) submittals.

1.6.7.5 Maintenance Plans, Procedures, Checklists, Records, and Spare Parts Inventory

1.6.7.5.1 Maintenance Schedules

Include recommended maintenance schedules for systems and equipment.

1.6.7.5.2 Ongoing Commissioning Operational and Maintenance Record Keeping

Include ongoing commissioning and optimization procedures and documentation to monitor and improve the performance of facility systems.

1.6.7.5.3 Janitorial and Cleaning Plans and Procedures

Include a copy of facility cleaning and janitorial plan with procedures and intended chemicals and equipment.

Provide environmentally friendly cleaning recommendations in accordance with ASTM E1971.

1.6.7.6 Utility Record Drawings

1.6.7.6.1 Utility Schematic Diagrams

Provide a one-line schematic diagram for each utility system such as power, water, wastewater, and gas/fuel. Schematic diagram must show from the point where the utility line is connected to the mainline up to the 5 foot connection point to the facility. Indicate location or area designation for route of transmission or distribution lines; locations of duct banks, manholes/handholes or poles; isolation units such as valves and switches; and utility facilities such as pump stations, lift stations, and substations.

1.6.7.6.2 Enlarged Connection and Cutoff Plans

Provide enlarged floor plans and provide information between the 5 foot utilities connection point and where utilities connect to facility distribution. Enlarge floor plans/elevations of the rooms where the utility enters the building and indicate on these plans the locations of the main interiors and exterior connection and cutoff points for the utilities. Also enlarge floor plans/elevations of the rooms where equipment is located. Include enough information to enable someone unfamiliar with the facility to locate the connection and cutoff points. Indicate designations such as room number, panel number, circuit breaker, or valve number of each utility and equipment connection and cutoff point, and what that connection and cutoff point controls.

1.6.7.6.2.1 Description of Utility Metering and Monitoring Systems

Provide in narrative format a description of the utility metering and monitoring systems. Include locations, function, and related systems.

1.6.7.6.2.2 Procedures for Tracking Utility Use and Reporting

Procedures for usage reporting and tracking in support of establishing and monitoring utility budgets and costs, and in developing annual energy reports.

1.6.7.6.2.3 One-Line Diagrams and Meter Location of System

Provide one-line diagrams and design drawings that highlight meter locations on the site.

1.6.7.6.3 Spare Parts and Supply Lists

Provide lists of spare parts and supplies required for repair to ensure continued service or operation without unreasonable delays. Special consideration is required for facilities at remote locations. List spare parts and supplies that have a long lead-time to obtain.

1.6.8 Part 5: Training

Provide a copy of training plans used for each type of equipment along with training materials used, arranged in specification sequence. Provide a copy of training records, sign-in sheets, and agendas. Include training and documentation on the updating and continued use of the O&M Manual.

1.6.9 Part 6: Cx Project Report and TAB Report

Provide the final Cx Plan and complete Cx reports with evaluation and testing forms and records for each building system. Include relevant commissioned system assemblies test reports including installers checklists of assemblies. Provide all Cx Progress Reports, issues and resolutions logs with resolution or status of each item, and a list of any open items and seasonal or additional testing required.

1.6.10 Part 7: Regulatory Requirements

Provide information describing regulatory and policies compliance requirements or provide a reference to where it is stored.

1.6.11 Part 8: Permits

Provide information requiring frequently asked questions and associated answers or provide a reference to where it is stored.

1.6.12 Part 9: Operations and Maintenance Manual Approval

Provide a signed document stating that the project O&M Manual has been reviewed and confirming agreement with the approach it presents. Include contact information for the signer for coordination of any future changes.

1.7 SCHEDULE OF OPERATION AND MAINTENANCE DATA PACKAGES

Provide the O&M data packages specified in individual technical sections. O&M Data Packages are one of the components of the O&M Manual. The information required in each type of data package follows:

1.7.1 Package Quality

Documents must be fully legible. Operation and Maintenance data must be consistent with the manufacturer's standard brochures, schematics, printed instructions, general operating procedures, and safety precautions.

1.7.2 Data Package 1

- a. Safety precautions and hazards

- b. Cleaning recommendations
- c. Maintenance and repair procedures
- d. Warranty information
- e. Extended warranty information
- f. Contractor information
- g. Spare parts and supply list

1.7.3 Data Package 2

- a. Safety precautions and hazards
- b. Normal operations
- c. Environmental conditions
- e. Preventive maintenance plan, schedule, and procedures
- f. Cleaning recommendations
- g. Maintenance and repair procedures
- h. Removal and replacement instructions
- i. Spare parts and supply list
- k. Warranty information
- l. Extended warranty information
- m. Contractor information

1.7.4 Data Package 3

- a. Safety precautions and hazards
- b. Operator prestart
- c. Startup, shutdown, and post-shutdown procedures
- d. Normal operations
- e. Emergency operations
- f. Environmental conditions
- g. Operating log
- i. Preventive maintenance plan, schedule, and procedures
- j. Cleaning recommendations
- k. Troubleshooting guides and diagnostic techniques

- l. Wiring diagrams and control diagrams
- m. Maintenance and repair procedures
- n. Removal and replacement instructions
- p. Product submittal data
- q. O&M submittal data
- r. Parts identification
- s. Warranty information
- t. Extended warranty information
- u. Testing equipment and special tool information
- v. Testing and performance data
- w. Contractor information
- x. Field test reports

1.7.5 Data Package 4

- a. Safety precautions and hazards
- b. Operator prestart
- c. Startup, shutdown, and post-shutdown procedures
- d. Normal operations
- e. Emergency operations
- f. Operator service requirements
- g. Environmental conditions
- h. Operating log
- j. Preventive maintenance plan, schedule, and procedures
- k. Cleaning recommendations
- l. Troubleshooting guides and diagnostic techniques
- m. Wiring diagrams and control diagrams
- n. Repair procedures
- o. Removal and replacement instructions
- p. Spare parts and supply list
- q. Repair work-hours
- r. Product submittal data

- s. O&M submittal data
- t. Parts identification
- u. Warranty information
- v. Extended warranty information
- w. Personnel training requirements
- x. Testing equipment and special tool information
- y. Testing and performance data
- z. Contractor information
- aa. Field test reports

1.7.6 Data Package 5

- a. Safety precautions and hazards
- b. Operator prestart
- c. Start-up, shutdown, and post-shutdown procedures
- d. Normal operations
- e. Environmental conditions
- f. Preventive maintenance plan, schedule, and procedures
- g. Troubleshooting guides and diagnostic techniques
- h. Wiring and control diagrams
- i. Maintenance and repair procedures
- j. Removal and replacement instructions
- k. Spare parts and supply list
- l. Product submittal data
- m. Manufacturer's instructions
- n. O&M submittal data
- o. Parts identification
- p. Testing equipment and special tool information
- q. Warranty information
- r. Extended warranty information
- s. Testing and performance data

t. Contractor information

u. Field test reports

1.7.7 Changes to Submittals

Provide manufacturer-originated changes or revisions to submitted data if a component of an item is so affected subsequent to acceptance of the O&M Data. Submit changes, additions, or revisions required by the Contracting Officer for final acceptance of submitted data within 30 calendar days of the notification of this change requirement.

PART 2 PRODUCTS

Not Used

PART 3 EXECUTION

3.1 TRAINING

Prior to acceptance of the facility by the Contracting Officer for Beneficial Occupancy, provide comprehensive training for the systems and equipment specified in the technical specifications. The training must be targeted for the building maintenance personnel, and applicable building occupants. Instructors must be well-versed in the particular systems that they are presenting. Address aspects of the Operation and Maintenance Manual submitted in accordance with Section 01 78 00 CLOSEOUT SUBMITTALS. Training must include classroom or field lectures based on the system operating requirements. The location of classroom training requires approval by the Contracting Officer.

3.1.1 Training Plan

Submit a written training plan to the Contracting Officer for approval at least 60 calendar days prior to the scheduled training. Training plan must be approved by the Quality Control Manager (QC) prior to forwarding to the Contracting Officer. Also, coordinate the training schedule with the Contracting Officer and QC. Include within the plan the following elements:

- a. Equipment included in training
- b. Intended audience
- c. Location of training
- d. Dates of training
- e. Objectives
- f. Outline of the information to be presented and subjects covered including description
- g. Start and finish times and duration of training on each subject
- h. Methods (e.g. classroom lecture, video, site walk-through, actual operational demonstrations, written handouts)
- i. Instructor names and instructor qualifications for each subject

- j. List of texts and other materials to be furnished by the Contractor that are required to support training
- k. Description of proposed software to be used for video recording of training sessions.

3.1.2 Training Content

The core of this training must be based on manufacturer's recommendations and the operation and maintenance information. The QC is responsible for overseeing and approving the content and adequacy of the training. Spend 95 percent of the instruction time during the presentation on the OPERATION AND MAINTENANCE DATA. Include the following for each system training presentation:

- a. Start-up, normal operation, shutdown, unoccupied operation, seasonal changeover, manual operation, controls set-up and programming, troubleshooting, and alarms.
- b. Relevant health and safety issues.
- c. Discussion of how the feature or system is environmentally responsive. Advise adjustments and optimizing methods for energy conservation.
- d. Design intent.
- e. Use of O&M Manual Files.
- f. Review of control drawings and schematics.
- g. Interactions with other systems.
- h. Special maintenance and replacement sources.
- i. Tenant interaction issues.

3.1.3 Training Outline

Provide the Operation and Maintenance Manual Files (Bookmarked PDF) and a written course outline listing the major and minor topics to be discussed by the instructor on each day of the course to each trainee in the course. Provide the course outline 14 calendar days prior to the training.

3.1.4 Training Video Recording

Record classroom training session(s) on video. Provide to the Contracting Officer two copies of the training session(s) in DVD video recording format. Capture within the recording, in video and audio, the instructors' training presentations including question and answer periods with the attendees. The recording camera(s) must be attended by a person during the recording sessions to assure proper size of exhibits and projections during the recording are visible and readable when viewed as training.

3.1.5 Unresolved Questions from Attendees

If, at the end of the training course, there are questions from attendees

that remain unresolved, the instructor must send the answers, in writing, to the Contracting Officer for transmittal to the attendees, and the training video must be modified to include the appropriate clarifications.

3.1.6 Validation of Training Completion

Ensure that each attendee at each training session signs a class roster daily to confirm Government participation in the training. At the completion of training, submit a signed validation letter that includes a sample record of training for reporting what systems were included in the training, who provided the training, when and where the training was performed, and copies of the signed class rosters. Provide two copies of the validation to the Contracting Officer, and one copy to the Operation and Maintenance Manual Preparer for inclusion into the Manual's documentation.

3.1.7 Quality Control Coordination

Coordinate this training with the QC in accordance with Section 01 45 00 QUALITY CONTROL.

3.2 SUBMITTAL SCHEDULING

3.2.1 Operation and Maintenance Manual, Progress Submittal

Submit the Progress submittal when construction is approximately 50 percent complete, to the Contracting Officer for approval. Provide Operation and Maintenance Manual Files (Bookmarked PDF). Include the elements and portions of system construction completed up to this point. The purpose of this submittal is to verify progress is in accordance with contract requirements as discussed during the Operation and Maintenance Manual Coordination Meeting.

3.2.2 Operation and Maintenance Manual, Prefinal Submittal

Submit the 100 percent submittal of the Operation and Maintenance Prefinal Submittal to the Contracting Officer for approval within 60 calendar days of the Beneficial Occupancy Date (BOD). This submittal must provide a complete, working document that can be used to operate and maintain the facility. Any portion of the submittal that is incomplete or inaccurate requires the entire submittal to be returned for correction. Any discrepancies discovered during the Government's review of Operation and Maintenance Progress submittal must be corrected prior to the Prefinal submission. The Prefinal Submittal must include Operation and Maintenance Manual Files (Bookmarked PDF).

3.2.3 Operation and Maintenance Manual, Final Submittal

Submit completed Operation and Maintenance Manual Files (Bookmarked PDF) and one hard copy of the Operation and Maintenance Manuals. The Final submittal is due at BOD. Any discrepancies discovered during the Government's review of the Prefinal submittal, including the Field Verification, must be corrected prior to the Final submission.

-- End of Section --

SECTION 35 20 23

DREDGING
08/20

PART 1 GENERAL

1.1 GENERAL INFORMATION

This Section covers furnishing suitable dredging plant and performing all work required to remove the specified materials from within the prescribed work area limits as indicated, and placement of the dredge material within the prescribed material placement areas. The Contractor is responsible for making their own investigation of submerged, surface, and overhead structures in the work areas and other locations they find necessary to traverse. The exact location, depths, and heights of various structures including, but not limited to submarine cables, pipes, highlines, docks, piers, bulkheads, and bridges (as applicable), are not known and it will be necessary for the Contractor to ascertain interference problems and notify the respective owners in advance of dredging operations. The Contractor is responsible for making necessary arrangements with the respective owners of the structure(s) to assure satisfactory completion of dredging in the vicinity with a minimum interruption of service, and must perform their operations in such a manner as will avoid damage to these facilities.

1.2 DEFINITIONS

1.2.1 Maintenance Material

Maintenance material is defined as that comprising shoaling which has occurred since the channel areas were last dredged.

1.2.2 New Work Material

New work material is defined as previously undredged material.

1.2.3 Hard Material

Hard material is defined as material requiring blasting or the use of special equipment for economical removal, and includes boulders or fragments too large to be removed in one piece by the dredge.

1.2.4 Economic Bin Load

An economic bin load is defined as that hopper load, measured in cubic yards (or tons) of dredged material dredged and hauled during a single dredging cycle which will yield, for the particular dredge, the maximum rate of removal and hopper retention of material from the project area and which will result in a minimum cost per cubic yard (or ton) hauled. The economic load is dredged when the retained cubic yards per minute of total cycle time (i.e. pumping, turning, running to and from dump, and dumping) equals the incremental retained cubic yards per pumping minute.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submit the following in accordance with Section 01 33 00

SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Notify Commander, Fifth Coast Guard District

Notify National Marine Fisheries Service

SD-02 Shop Drawings

Submerged Pipelines

SD-03 Product Data

Soundings Or Sweepings

Economic Loading Calculations; G, D0

SD-07 Certificates

Protection Plan

Equipment And Machinery Operator Authorization

1.4 NATIONAL DREDGING QUALITY MANAGEMENT PROGRAM

NATIONAL DREDGING QUALITY MANAGEMENT PROGRAM is required for all dredges employed on the work. See 35 20 23.13 NATIONAL DREDGING QUALITY MANAGEMENT PROGRAM - SCOW ULLAGE PROFILE and 35 20 23.23 NATIONAL DREDGING QUALITY MANAGEMENT PROGRAM - HOPPER DREDGE.

1.5 METHOD OF COMMUNICATION

Provide a system of communication between the dredge crew and the crew at the placement area. A portable two-way radio is acceptable.

1.6 DREDGING NOTIFICATIONS

A Dredging Notification shall be prepared and sent to the agencies identified below identifying the dredging locations, placement areas, and dates the Contractor intends to start and complete dredging. When the Contractor sends a Notification to an agency, proper signatures as required in the Permit shall be affixed. A copy of all Notifications furnished shall at the same time be provided to the Contracting Officer.

a. Dredging Notification to the U.S. Coast Guard

Notify Commander, Fifth Coast Guard District of his intended operations to dredge and request that it be published in the Local Notice to Mariners. This Dredging Notification to U.S. Coast Guard must be given in sufficient time so that it appears in the Notice to Mariners at least 5 workdays prior to the commencement of this contract.

The Local Notice to Mariners (LNM) for the Fifth Coast Guard District is available by phone at (757) 398-6367. Additionally, LNM are on the Internet at:

<http://www.navcen.uscg.gov/?pageName=lnmDistrict®ion=5>, and e-mail address: D5Local@LANTD5.uscg.mil.

The LNM is the primary means for disseminating information concerning aids to navigation, hazards to navigation, and other items of marine information of interest to mariners on the waters of the United States, its territories, and possessions. These notices are essential to all navigators for the purpose of keeping their charts, light lists, Coast Pilots and other nautical publications up to date. These notices are published weekly. They may be obtained free of charge, by making application to the Fifth Coast Guard District, Federal Building, 431 Crawford Street, Portsmouth, Virginia 23704. If the Contractor encounters any objects on the channel bottom during dredging operations or transport of his plant that could be a hazard to navigation, he shall notify the Coast Guard immediately as to location and at the same time notify the Contracting Officer.

- b. Dredging Notification to the National Marine Fisheries Service (NMFS)
Notify National Marine Fisheries Service by email (Incidental.Take@noaa.gov) within 3 days of the commencement of dredging and again within 3 days of the completion of dredging activity.

1.7 OTHER DREDGING OPERATIONS

The Contractor should anticipate the possibility of concurrent operations, adjacent to or nearby the dredge and placement areas in this contract. Delays should be anticipated in transiting to, and through, the placement sites during concurrent dredging and placement operations. As a standard safety precaution, observe all placement site specific restrictions pertaining to the limit of dredges operating within at any given time. Coordination with other dredge plant in the vicinity of the dredge and placement areas is required. It shall be the responsibility of the Contractor on this contract to be fully informed of the extent of the limits of work to be performed by other contractors. Should there be any conflict between these limits, the Contractor shall immediately notify the Contracting Officer of the conflict, and the Contracting Officer's decision shall be final.

1.8 ENVIRONMENTAL COMPLIANCE AND PROTECTION

Comply with conditions and requirements of State or Federal permits. The Government will secure the permit for dredging and placement of material as indicated. Coordinate with the Contracting Officer for placement of excavated materials.

During the life of the contract, provide and maintain environmental protective measures. Also, environmental protective measures required to correct conditions, such as oil spills or debris, that occur during the dredging operations, must be provided. Comply with Federal, State, and local regulations pertaining to water, air, and noise pollution.

1.8.1 Seasonal Restrictions

There are no anticipated seasonal restrictions for hopper or mechanical dredging on this project.

1.9 SECURITY OF WORK AREAS

1.9.1 Placement Site Security and Safety

The placement site is located at the Wallops Island Flight Facility in

Wallops Island, Virginia. This site is owned and operated by the National Aeronautics and Space Administration (NASA). The Contractor is responsible for complying with all NASA safety and security requirements during placement activities and shall restrict access to the beach placement area. The Contractor is informed the Government will not undertake to exclude the public or restrict public access to the beach placement site during the work.

The Contractor may perform the scheduled work 24 hours a day, 7 days a week, however, periodic mandatory shut downs are to be expected. Wallops Island is an active flight facility and launches are anticipated during the course of this contract. The Contractor shall be responsible for coordinating with the Contracting Officer and anticipate shutting down during these events.

All lighting associated with the project shall be limited to the immediate area of active construction only. Such lighting shall be shielded, low-pressure sodium vapor lights directed to the maximum extent practical away from populated areas where applicable and to avoid excessive illumination of the water.

1.9.2 Dredge Site Security and Safety

The dredge site is accessible to the general public. The Contractor is informed the Government will not undertake to exclude the public or restrict public access to the dredging site during the work. The Contractor shall be solely responsible for protection of the public within the dredge site at all times for the duration of the contract and fully comply with the provisions of OSHA safe working practices and the Safety and Accident Prevention requirements of these specifications.

1.10 NOISE CONTROL AND ABATEMENT

The Contractor shall employ the use of properly installed and maintained mufflers, silencers, and manufacturer's recommended sound suppressors on all plant, machinery, and equipment used on this work. The use of sound signals such as whistles, horns, or bells shall not be used if two-way radio communication can accomplish the required function.

1.11 PHYSICAL DATA

1.11.1 Physical Conditions Information

The physical conditions indicated on the drawings, specifications, and attached appendices are the result of site investigations and surveys. Information and data furnished or referred to below is furnished for the Contractor's information; however, it shall be expressly understood that the Government will not be responsible for any interpretation or conclusion drawn from this information or data by the Contractor. The approximate mean range of tide at the dredging areas is noted on the respective drawings. The dredging and disposal areas are exposed, so high winds and seas may at times cause suspension of work.

1.11.2 Additional Information for Local Physical Conditions

The Contractor shall consult the following publications for additional information on local conditions:

- a. United States Coast Pilot 3, Atlantic Coast, Sandy Hook to Cape Henry, published annually by the National Ocean Service.

- b. Tide Tables, High and Low Water Predictions, East Coast of North and South America, published annually by the National Ocean Service.
- c. Tide Current Tables, Atlantic Coast of North America, published annually by the National Ocean Service.
- d. Local Notice to Mariners, published by the 5th U.S. Coast Guard District and the broadcast local notice to mariners.

1.12 RESPONSIBILITY

The Contractor shall hold and save harmless the United States, Commonwealth of Virginia, its officers, and employees from all claims that may arise as a result of the Contractor's negligence in connection with the work performed under the contract, from noncompliance by the Contractor with the provisions of the contract drawings and specifications, or from the instruction of the Contracting Officer.

1.13 CONDITION OF DREDGING AREA

The plans for dredging show the condition of the dredging area at the time of the most recent survey; however, the condition of the dredging area will be verified by a survey made before dredging. The Government has no knowledge of cables, pipes, wrecks, or other artificial obstructions in the dredging area; however, the dredging area may contain trash, debris, aquatic vegetation, cobbles, ballast stone, and other obstructions not shown on the plans for dredging.

1.14 LAYOUT OF WORK AND SURVEYS

1.14.1 General

The Contractor is responsible for the expense and layout of all work and shall utilize a differential GPS electronic survey and dredge positioning system to perform all scheduled dredging operations with accuracies as specified in the Project Classification Requirements as outlined in U.S. Army Corps of Engineers Hydrographic Survey Manual EM 1110-2-1003. The plane of reference shall be mean lower low water (MLLW) as established by National Ocean Service (NOS), as used on the drawing and in these specifications.

1.14.1.1 Dredge Electronic Survey and Positioning System

The Contractor shall provide real time positioning on a computer screen during dredging and dredged material disposal operations, and the Contractor shall have the capability of playback in 15 minute intervals. The position must be recorded on a disk every 60 seconds and submitted to the Contracting Officer on a weekly basis. All electronic survey and dredge positioning systems equipment, and the work accomplished with the use of the systems, must render results in the same coordinate system as indicated on the contract drawings. All completed work shall be reviewed and certified as accurate by the Contractor's Quality Control Manager. This signed certification shall be submitted as a part of the Daily Report of Operations in accordance with the requirements of 01 45 00.15 10 RESIDENT MANAGEMENT SYSTEM CONTRACTOR MODE (RMS CM) to ensure that all work performed with the use of the equipment and systems meets contract requirements. In the event of a system failure, all disposal operations must cease until the navigational capabilities are restored. Backup systems with the capabilities of the main system are acceptable. The contractor must document and log all ocean disposal operations consistent with the specification above in order to maintain compliance with EPA

requirements.

1.14.1.2 Datum and Benchmarks

The plane of reference shall be NAVD88, National Tidal Datum Epoch (NTDE) of 1983-2001, as established by National Ocean Service (NOS), and identified on the drawings and referenced in these specifications. At the dredging site, tidal values will be determined using tidal zoning values developed by NOS. The government will furnish tidal zoning values developed by NOS and, if necessary, will furnish benchmark descriptions for the project at the Preconstruction Conference.

1.15 RESPONSIBILITY FOR TIDE MEASUREMENTS

It shall be the responsibility of the Contractor to obtain tide level measurements and predictions as required to conduct his dredging operations for the duration of the work.

1.16 OYSTER GROUNDS

There are no known oyster grounds in the vicinity of the areas to be dredged.

1.17 INSPECTION

1.17.1 General Inspection Requirements

The presence of the construction representative shall not relieve the Contractor of responsibility for the proper execution of the work in accordance with the specifications. The Contractor will be required:

- a. To furnish, on the request of the Contracting Officer or any construction representative, the use of such boats, boatmen, laborers, and material forming a part of the ordinary and usual equipment and crew of the dredging plant as may be reasonably necessary in inspecting and supervising the dredging.
- b. To furnish, on the request of the Contracting Officer or any construction representative, suitable transportation from all points within the placement area, to and from the various pieces of plant and the staging areas, and within the material placement area as may be reasonably necessary in inspecting and supervising the work. Should the Contractor refuse, neglect, or delay compliance with these requirements, the specific facilities may be furnished and maintained by the Contracting Officer, and any resultant cost incurred by the government will be deducted from any amounts due or to become due the Contractor.
- c. To furnish the Government construction representative a portable radio capable of communicating with the dredge for the duration of work under this contract. The Contractor shall maintain the radio as required.
- d. Hopper dredges shall be provided with a fixed vertical ship ladder system (in compliance with the requirements of ASTM F1166) as the primary means of safe access/egress for works and visitors embarking / disembarking the vessel. A double rung of flat tread Jacob's ladder shall not be used as the vessel's primary means of safe access.

1.17.2 Accommodations

- a. Workspace - The Contractor shall furnish regularly to Government construction representatives on board the dredge a suitable working and storage space, equipped and maintained to the satisfaction of the Contracting Officer or his representative. As a minimum the facilities shall include a desk with chair for plan study, and a file drawer, approximately 15" by 24", capable of being locked with a padlock. The working space need not be a separate room, but shall be properly lighted, ventilated, and heated.
- b. The entire cost to the Contractor for furnishing, equipping, and maintaining the foregoing accommodations shall be included in the contract price. If the Contractor fails to meet these requirements, the Contracting Officer will secure the facilities referred to above, and their costs will be deducted from payments due to the Contractor.

1.18 SPECIAL COAST GUARD REQUIREMENTS

1.18.1 Relocation of Navigation Aids

The Contractor shall not relocate or move any aids to navigation that have been established by the U.S. Coast Guard. If it becomes necessary to have any aid to navigation moved in order to complete dredging operations under this contract, the Contractor shall notify the U.S. Coast Guard in writing at the address above with a copy to the Contracting Officer not less than 45 calendar days prior to such need for movement. The Contractor shall notify the U.S. Coast Guard of the approximate time the navigation aid may be relocated to its original position. All notifications to the U.S. Coast Guard shall at the same time be provided to the Contracting Officer and recorded in the Daily Report of Operations. If the Contractor disturbs or damages any navigation aid during work operations, which includes during mobilization or demobilization of his plant, the Contractor shall immediately stop the activity which disturbed or damaged the navigation aid, take immediate corrective action to prevent further disturbances or damage, and shall notify the Coast Guard immediately as to location, and at the same time notify the Contracting Officer.

1.18.2 Use of Coast Guard Navigation Aid Structures

The Contractor shall not use any Coast Guard or Federal Navigation Aid Structures for installation of temporary tide gauges.

1.19 PLANT

All dredging plant, equipment and machinery and all supporting plant utilized to accomplish the work, shall be subject to inspection and approval by the Government. All plant employed on the work must be kept in good condition at all times. Any leaks or deficiencies shall be promptly and properly repaired.

1.19.1 Minimum Plant Requirements and Contractor Required Certifications

Submit a complete List of Floating Plant to be used in the work, including booster pumps, skiffs, barges, and other related equipment prior to award. The list shall include year and manufacturer, operational capacities, safety features, operating and licensing requirements for operators, Equipment and Machinery Operator Authorization and a description where and how the plant or item of equipment will be employed in the work. The

contractor shall submit a list of designated personnel qualified and authorized to operate machinery and equipment. the list shall be maintained at the job site in a current status at all times. Clearly indicate on which projects the dredge has been used in similar conditions to dredge similar material at a production rate sufficient to accomplish the work as scheduled for this contract.

1.19.1.1 Certification of Attendant and Auxiliary Plant

In addition to the requirements of EM 385-1-1, all supporting floating plant for dredging operations shall have a current marine survey inspection certificate. The only exceptions to this requirement include pipeline support pontoons or floats and outboard skiffs less than 20 feet in length. The certification shall have been issued by an accredited marine surveyor within the previous 12 months. The marine surveyor must be accredited by either the National Association of Marine Surveyors or the Society of Accredited Marine Surveyors. Attendant plant that does not have a valid certification and is greater than 20 feet in length shall not be used on this contract. The certifications and inspection shall be appropriate for the intended use of the plant in all locations specified in this contract.

1.19.1.2 Pre-Award Survey Evaluation

The Government will conduct a Pre-Award Survey to evaluate the verification documents of the Contractor for compliance to all contract requirements. Unless the Contracting Officer determines otherwise, documentation of the inspection for each piece of plant must be in possession of the Contracting Officer within 10 calendar days after bid opening. Inadequate documentation, insufficient plant certifications to meet requirements, and untimely submittal of required documentation will be cause for rejection of the bid. Additionally, as a part of the Pre-Award Survey, the Contractor must make all intended plant available for inspection and acceptance.

Once the dredge(s) and plant have been inspected and accepted by the Government, and have been mobilized to the project site, they shall not be removed from the project site until all scheduled work for the contract has been satisfactorily performed by the Contractor and accepted by the Government, except by written permission of the Contracting Officer or commencement of a seasonal dredge restriction.

1.19.2 Pumping of Bilges

Contractors are warned that pumping oil or bilge water containing oil into navigable waters, or into areas which would permit the oil to flow into such waters, is prohibited by Section 13 of the River and Harbor Act of 1899, approved 3 March 1899 (30 Stat. 1152; 33 U.S.C. 407). Violation of this prohibition is subject to the penalties under the referenced Acts.

1.19.3 Fuel Oil Transfer Operations

In accordance with U.S. Coast Guard regulations 33 CFR PART 156.120, couplings used in fuel oil transfer operations on any vessel with a capacity of 250 or more barrels of oil shall be either a bolted or full-threaded connection, or a quick-connect coupling approved by the Commandant, or an automatic back-pressure shutoff nozzle used to fuel the vessel. An executed fuel oil transfer (Declaration) form signed by the tanker operator shall be submitted to the Contracting Officer for each

refueling operation.

1.19.4 Signal Lights

The Contractor shall display signal lights and conduct his operations in accordance with the General Regulations of the of the Coast Guard. These regulations govern lights and day signals to be displayed on towing vessels with tows on which no signals can be displayed, on vessels working on wrecks, on dredges, on vessels engaged in laying cables or pipe, on vessels engaged in submarine or bank protection operations, on dredge pipe lines, on vessels of more than 65-feet in length moored or anchored in a fairway or channel, and on vessels passing by other vessels of floating plant working in navigable channels, as approved by the Commandant, U. S. Coast Guard.

1.19.5 Bridge-to-Bridge Radio Communication

In order that radio communication may be made with passing vessels, all dredges engaged in work under this contract shall be equipped with bridge-to-bridge radio telephone equipment in accordance with 33 U.S.C. 24, as applicable. The radio telephone equipment shall operate on a single channel very high frequency (VHF), FM, on a frequency of 156.65 megahertz (Channel 13 and 16) with low power output having a communication range of approximately ten miles. The Federal Communications Commission has approved the frequency.

1.19.6 Seagoing Barge Act

All dredges, barges, and vessels used for the transport of dredged material shall meet the applicable requirements of the Seagoing Barge Act (46 U.S.C. et seq). To document compliance with this act, the Contractor shall submit with his bid copies of U.S. Coast Guard Certificate of Inspection for each item of plant. Certification shall also be furnished to the Contracting Officer if additional plant is engaged during the course of the work.

PART 2 PRODUCTS

2.1 CHARACTER OF MATERIAL

The material to be dredged and placed on the beach for replenishment shall be classified in accordance with ASTM D2478 as SP or SW containing not more than 10 percent fines passing a U.S. Standard Sieve No. 200, and not more than 5 percent gravel retained on the U.S. Standard Sieve No. 4. The material dredged must not contain more than 10 percent shell fragments. If the contractor determines that the material placed on the beach does not meet this standard, they shall notify the Contracting Officer Representative immediately.

The material to be removed is from a borrow area. The material to be removed includes material represented in the geotechnical report as well as the shoaling that has occurred since the borrow area was last sampled. Bidders are expected to examine the sites of work and decide for themselves the character of the materials. A geotechnical report summarizing available geotechnical data for the project is provided in Appendix A of these specifications. Local minor variations in the subsurface materials are to be expected and, if encountered, will not be considered as being materially different.

PART 3 EXECUTION

3.1 INSPECTION

Inspect the work, keep records of work performed, and ensure that gages, targets, ranges, and other markers are in place and usable for the intended purpose. Provide, at the request of the Contracting Officer, boats, boatmen, laborers, and materials necessary for inspecting, supervising, and surveying the work. When required, provide transportation for the Contracting Officer and inspectors to and from the placement area and between the dredging plant and adjacent points on shore.

The dredge plant will be inspected by the Contracting Officer, or their representative, prior to beginning work to ensure total dredging plant is in safe working condition. Before any machinery or mechanized equipment is placed in service, it must be inspected and tested by the Contractor and certified to be in safe operating condition.

3.2 DREDGING

3.2.1 Interference with Navigation

Minimize interference with the use of channels and passages. The Contractor is responsible for shifting or moving of dredges or the interruption of dredging operations to accommodate the movement of vessels and floating equipment, if necessary. Adhere to Coast Guard Regulations for passing vessels.

3.2.2 Lights

Each night, between sunset and sunrise and during periods of restricted visibility, provide lights for floating plants, pipelines, ranges, and markers. Also, provide lights for buoys that could endanger or obstruct navigation. When night work is in progress, maintain lights from sunset to sunrise for the observation of dredging operations. Lighting must conform to United States Coast Guard requirements for visibility and color.

3.2.3 Navigation Warnings

Furnish and maintain navigation warning signs along any pipelines. Provide notice to increase public awareness of potential hazards presented by dredge plant equipment by stating the location, date of construction, equipment mooring, marshaling areas, using local newspapers, radios, television, waterway users associations, or other appropriate area specific communication networks. Ensure that an announcement is made through the same networks at the beginning of the dredging operation. Make periodic updates/status announcements at intervals of not more than a month throughout the contract life.

Display a sturdy and prominent warning sign at all public boat marinas within 10 miles of dredging operations or moored equipment. The Contractor is responsible for keeping this sign current with respect to the dredging operations or equipment. The Contractor shall erect and maintain these signs and any other signs necessary to prevent hazards to navigation at their own expense.

3.2.4 Ranges, Gages, and Lines

Provide, set, and maintain ranges, buoys, and markers needed to define the work and to facilitate inspection. The Contractor must coordinate with the U.S. Coast Guard prior to placing any buoy or other aid marker in the water. Buoys and aid markers must be maintained throughout the length of the dredging operation and must not be colored, marked, or placed in a manner that will obstruct or be confused with other navigational aids. All buoys and aid markers must conform to U.S. Coast Guard regulations. Establish and maintain gages in locations observable from each part of the work so that the depth may be determined. Suspend dredging when the gages or ranges cannot be seen or followed.

3.2.5 Dredge Plant and Equipment

- a. The Contractor shall perform the scheduled work using hopper and/or mechanical (clamshell) dredges.
- b. Maintain all dredge plant and associated equipment such as, but not limited to, scows, coamings, barges, and pipelines, to meet the requirements of the work. Promptly repair leaks or breaks along pipelines.

3.2.6 Removal and Transport of Material Dredged From Borrow Area

The Contractor shall remove all material by hopper dredge or mechanical dredge and transport material dredged from the borrow area to a pump out buoy for deposit by a hydraulic pipeline within the beach fill placement area as indicated. The dredge cuts in the borrow area shall not have side slopes steeper than 1 on 3. As much as is practicable, passes of the dredge shall be made such that the bottom is excavated uniformly, leaving a relatively smooth bottom surface. Blasting will not be permitted. The pump out buoy shall be moored no less than 500 feet seaward from the mean low water line. Dredge pipeline shall be placed on the beach and advanced in a manner as approved by the Contracting Officer.

3.2.7 Hopper Dredge Material Pump Out Controls

The Contractor shall provide constant monitoring of the material placement operations at the pump out buoy. Qualified monitoring personnel shall have fully functional two-way radio communications with the dredge operator and on-beach monitors at all times when pump out operations are in progress. Requirements for monitoring material discharge on the beach is specified in SECTION 35 20 24. Frequent communication checks shall be made to assure proper discharge of the hopper and material placement during the pump out operations. In the event of any communications failure or improper material placement is determined, all pump out and placement operations shall be immediately suspended until communications are restored as approved by the Contracting Officer, or in the event of pump out problems or improper material placement, until proper material placement procedures are reestablished by the Contractor as approved by the Contracting Officer.

3.2.8 Examination of Pump Out Buoy and Pipeline

The pump out buoy and pipeline, including connections at the dredge and those used for a submerged line, shall be examined and determined to be in good condition to reasonably expect them to last throughout the job without wearing to the extent of allowing leaks.

3.2.8.1 Leaks

In the event that leaks occur anywhere during pump out of material from the hopper dredge, the contractor will be required to immediately discontinue using the respective equipment until the leaks are stopped. The contractor shall also be required to recover at no cost to the Government any material improperly placed because of a leak or leaks in the equipment.

3.2.9 Examination of Dredge Hopper Bins and Dump Scows

The hopper bins and dump scows shall be examined and determined to be in good condition to reasonably expect them to last throughout the job without wearing to the extent of allowing leaks. In the event that leaks occur anywhere in the hopper bins or scows, the Contractor will be required to immediately discontinue using the respective equipment until the leaks are stopped. The Contractor shall also be required to recover at no cost to the Government any material improperly placed because of a leak or leaks in the equipment.

3.2.10 Layout of Work

The Contractor will be provided layout charts for all dredging areas based on the schedule of work, the Contractor's hydrosurvey requests, and/or the results of Government hydrographic survey monitoring. The most current Government hydrosurvey information will be displayed on the dredging layout charts and provided to the Contractor. All depths are measured from MLLW. Other pertinent information to be included with each layout package will be: payment method, required and maximum dredging depths, coordinates for the material placement site, distance one-way from dredging location to placement site, specific placement site instructions, supplemental tide gauge information, horizontal control locations, and computed hydrosurvey quantities.

The total estimated quantity of material to be removed is computed as that material that is within the specified limits. The quantities listed are estimates only. All estimated quantities are subject to FAR 52.211-18 Variation in Estimated Quantity.

3.2.11 Obstructions and Debris

The Government has no knowledge of existing wrecks, wreckage, or other material of such size or character as to require the use of explosives or special or additional plant for its economical removal.

3.2.12 Dredging Requirements

Dredge Areas

1) Dredge Borrow Area Subarea A1

a) The Government will direct the Contractor to dredge from borrow area Subarea A1 as indicated on the plans. Dredging will be limited to within the areas as identified on the plans and with seven (7) feet of the existing bottom contour elevations of the borrow site. If the material within the designated borrow site is found to be unsuitable for beach placement, the contractor shall inform the Contracting Officer Representative immediately. Refer to project plans and 35 20 23 DREDGING paragraph 2.1 CHARACTER OF MATERIAL for more

information.

b) Material placement will be on the beach at Wallops Island as indicated on the plans site.

3.2.13 Surveys during Progress of Work

Quality of dredging depth will be determined by soundings or sweepings taken behind the dredge as work progresses. The Contractor will take progress soundings or sweepings.

3.2.14 Skimming of Hoppers

Skimming of hoppers must be performed in compliance with environmental requirements and ABS/USCG load line marks.

3.2.15 Salvaged Material

Anchors, chains, firearms, and other articles of value, which are brought to the surface during dredging operations, must remain or become the property of the Government and will be placed on shore at a convenient location near the site of the work, as directed.

3.2.16 Safety of Structures

The prosecution of work must ensure the stability of piers, bulkheads, and other structures lying on or adjacent to the site of the work, insofar as structures may be jeopardized by dredging operations. Repair damage resulting from dredging operations is the responsibility of the Contractor, insofar as such damage may be caused by variation in locations or depth of dredging, or both, from that indicated or permitted under the contract. The Contractor is responsible for coordinating with the owner of the structure for any necessary repairs.

3.2.17 Protection Plan

Prior to blasting, submit a plan for protection of surrounding structures, equipment, and vessels.

3.2.18 Munitions and Explosives of Concern

Refer to 01 35 30 MUNITIONS AND EXPLOSIVES OF CONCERN (MEC) CONSTRUCTION SUPPORT for special plant requirements for screening MEC and other requirements involving safety support and avoidance of potential unexploded ordnance and exploded ordnance, inert ordnance, and ordnance fragments and similar explosives debris material (defined and identified in these specifications as "Munitions and Explosives of Concern", within the dredging prism of the borrow area during performance of dredging activities.

3.2.19 Endangered Species

Refer to 01 57 30 ENVIRONMENTAL PERMIT WORK REQUIREMENTS for required special equipment and operating procedures.

3.3 PLACEMENT OPERATIONS

See also 35 20 24 BEACH FILL for additional information pertaining to

beach nourishment.

3.3.1 Method of Placement

Provide for safe transportation and disposal of dredged materials. Transport and dispose of dredged material in the areas indicated in the contract documents. Place all dredged material by the hydraulic process. Pipeline for offloading must discharge into the placement area.

The Contractor shall use an approved dredge positioning system with tolerances specified in Sections: 35 20 23.13 NATIONAL DREDGING QUALITY MANAGEMENT PROGRAM - SCOW ULLAGE PROFILE and/or 35 20 23.23 NATIONAL DREDGING QUALITY MANAGEMENT PROGRAM - HOPPER DREDGE to ensure accurate placement of dredged material in the placement area.

3.3.2 Placement in Indicated Site(s)

In placing excavated material for fill, uniformly grade and allow for shrinkage. Provide and maintain necessary bulkheads, dikes, ditches, weirs, spillways, and other construction necessary to confine and retain the fill in the dredge fill area.

3.3.3 Misplaced Dredged Material

Any dredged materials deposited at locations other than in areas designated or approved by the Contracting Officer will be considered misplaced material and will not be paid for until the Contractor, at his own expense, removes and deposits such misplaced material where directed. This required removal and redeposit of the misplaced material and any necessary placement site restoration work is not the basis for a time extension or additional compensation under this contract.

3.3.4 Submerged Pipelines

If a leak occurs in the discharge pipeline, immediately discontinue using the line until leaks are repaired. Following a leak, the Contractor should conduct, or request the Government to conduct, a hydrosurvey to ensure that any dredged material discharged through the leak did not accumulate or cause mounding. If accumulation did occur, the Contractor must coordinate with the Government to remove the accumulated material, if deemed necessary. The Contractor is responsible for any resulting costs of repair and restoration.

3.4 PAYMENT

All dredging costs are to be incidental to the cost for beach placement. No separate payment will be made for the dredging work performed.

3.5 QUALITY CONTROL

Establish and maintain quality control for operations to ensure compliance with contractual requirements and maintain records of this quality control for dredging operations.

While performing all dredging work control the horizontal positioning of the dredge with electronic positioning.

3.5.1 Quality Control for Hydrographic Surveys and Survey Equipment

Hydrographic surveys will be conducted to meet USACE Performance Standards as defined in the Hydrographic Surveying Manual EM 1110-2-1003.

Surveys will be performed by using commercially available Real-Time Kinematic (RTK), in NAD 83, Virginia State Plane - South, U.S. survey feet.

Surveys will be performed by single transducer sounding techniques, multi-beam swath type surveys, or a combination of both at the discretion of the Government.

Bottom soundings will be obtained by the single beam survey fathometer operating at a frequency ranging from 190 to 210 Khz.

When the government utilizes multi-beam technology, the operating frequency will range from 380 to 420 Khz.

All fathometers will be calibrated following procedures outlined in the Hydrographic Surveying Manual EM 1110-2-1003.

3.5.2 Inspections and Testing Requirements

Inspections and testing shall be the responsibility of the Contractor, subject to the approval of the Contracting Officer.

3.5.3 Equipment and Machinery Requirements

All measuring equipment, global positioning systems (GPS) and other electronic positioning systems, data plotting and recording equipment, and the procedures associated with each respective item of equipment, shall be subject to the approval of the Contracting Officer. Verification of current calibration for each respective item of equipment, as approved by the Contracting Officer, shall be provided by the Contractor prior to use of the equipment on the work. All records produced by the equipment shall be inspected and certified as complete by the Contractor's Quality Control Representative and included as a part of the Daily Quality Control Report.

3.5.4 Miscellaneous Inspections and Test Records

A copy of the records of all inspections and tests, as well as record of corrective action taken, shall be included in the Quality Control Plan and furnished to the Contracting Officer as a part of the Daily Quality Control Report. The Contractor shall establish and maintain quality control for the dredging work and all other operations in connection with the work in the field to ensure compliance with contract requirements. The Contractor shall inspect for compliance with contract requirements and record the inspection of all operations including but not limited to the following:

- a. The material is placed to the lines, grade, and tolerances specified.
- b. All equipment used in the work is approved and in satisfactory working condition.
- c. Checks to ensure safe work practices performed as specified.
- d. Ensure all equipment and construction materials have been removed from completed work segments.

- e. All results of inspections shall be documented with narrative explanations and photographs as necessary to document the conditions of the field quality. The results and supporting data shall be recorded and provided by the Contractor in the Daily Report of Operations if not otherwise reported via other project requirements.

3.5.5 Reporting and Certificates

All measuring, plotting, and recording equipment and procedures shall be subject to the approval of the Contracting Officer. Verification of their calibration, certified by the Contractor's Quality Control Representative, shall be furnished prior to use on the work. All records produced by the equipment shall be authenticated by the authorized representative of the contractor and then provided to the Contracting Officer with the Daily Report of Operations.

3.6 DAILY REPORTING REQUIREMENT

The Contractor shall prepare and maintain a Report of Operations and furnish copies daily to the Contracting Officer. A copy of the form prescribed for recording the required information is attached at the end of SECTION: 01 45 00.00 10 "QUALITY CONTROL" and any further instructions on the preparation of the report will be furnished at the preconstruction conference noted in Section 01 30 00 ADMINISTRATIVE REQUIREMENTS.

3.7 ECONOMIC LOADING

3.7.1 Dredge Operations - Economic Loading

Conduct hopper dredge operations in a manner that results in the most productive operating cycles and optimizes the amount of material placed in the designated placement site in accordance with economic load. Once the economic load is achieved, the dredge shall discontinue pumping and proceed to the disposal area except that the Contractor may complete the cut in which the dredge is working before proceeding to the placement area.

3.7.2 Determining Economic Load

The pumping-time to achieve economic loading shall be determined using the average of the initial three complete cycles for each acceptance section. These determinations shall be used to establish the operating procedures for the hopper dredge throughout the remainder of the applicable acceptance section. Where conditions vary and/or the distance to the placement area is significantly different, a revised Economic Bin Load may be submitted for approval at any time. Methodology for determining Economic Bin Load shall be in accordance with generally accepted industry practice. Eng Form 2590 1955, Economic Load Test, is included in Appendix D of these specifications for contractor convenience; however, use of this exact form is not required.

3.7.3 Economic Load Calculation

Submit Economic Loading Calculations for acceptance within 1-week after starting dredging and include current economic load summary data on each daily report. No payment will be made until Economic Load calculations are accepted.

3.8 BORROW AREA SURVEYS

3.8.1 Before Dredge Survey

The Contractor shall be responsible for completing before dredging hydrographic surveys of the borrow site prior to commencing dredging operations.

3.9 PLANT REMOVAL

Once the dredge(s) and plant have been inspected and accepted by the Government, and have been mobilized to the project site, they shall not be removed from the project site until all all scheduled work for the contract has been satisfactorily performed by the Contractor and accepted by the Government, except by written permission of the Contracting Officer.

Upon completion of the work, remove all dredging plant, including ranges, buoys, piles, and other markers or obstructions within 15 days.

-- End of Section --

DRAFT
NOT FOR CONSTRUCTION

SECTION 35 20 23.13

NATIONAL DREDGING QUALITY MANAGEMENT PROGRAM - SCOW ULLAGE PROFILE
02/22

PART 1 GENERAL

1.1 DESCRIPTION

The work under this contract requires use of the National Dredging Quality Management Program (DQM) to monitor the dredge's status at all times during the contract and to manage data history. For the purpose of these specifications, a scow is defined as any non-self-propelled vessel used to transport dredged material. This includes, but is not limited to, split-hull scows, pocket scows, hopper barges, and deck barges.

This performance-based specification section identifies the minimum required output and the precision and instrumentation requirements. The requirements may be satisfied using equipment and technical procedures selected by the Contractor.

1.2 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-07 Certificates

National Dredging Quality Management Program Certification, Norfolk District; G

1.3 PAYMENT

Separate payment for installation, operation, and maintenance of the DQM-certified system as specified herein for the duration of the dredging operations is not allowed; all costs in connection therewith are considered a subsidiary obligation of the Contractor and are covered under the contract unit price for beach placement in the bidding schedule.

1.4 NATIONAL DREDGING QUALITY MANAGEMENT PROGRAM CERTIFICATION

1.4.1 Certification

The Contractor is required to have a current certification from DQM for the scow instrumentation system to be used under this contract. Criteria for certification is based on the most recent specification posted on the DQM website

<https://www.sam.usace.army.mil/Missions/Spatial-Data-Branch/Dredging-Quality-Management>
Verify compliance with these criteria by onsite quality assurance (QA) checks conducted by the DQM Support Center Data Acquisition and Analysis Team and by periodic review of the transmitted data. If a system is installed specifically for this contract, in order to ensure that it is capable of transmitting quality data to the DQM database, the QA checks should take place either prior to the start of the contract or, with prior approval of the local USACE District, as soon as practical after dredging commences. DQM Certification is valid for one year from the date of certification and is contingent upon the system's ability to meet the

performance requirements as outlined in paragraph PERFORMANCE REQUIREMENTS. If issues with data quality are not corrected within 48 hours, the system certification will be revoked and additional QA checks by the Data Acquisition and Analysis Team may be necessary. Annual DQM Certification must be based on the following:

A series of QA checks as outlined on the DQM website
<https://www.sam.usace.army.mil/Missions/Spatial-Data-Branch/Dredging-Quality-Management>
Verification of data acquisition and transfer as described in paragraph PERFORMANCE REQUIREMENTS

Review of the Dredge Plant Instrumentation Plan (DPIP) as described in paragraph DREDGE PLANT INSTRUMENTATION PLAN (DPIP)

1.4.2 Quality Assurance (QA)

The Dredging Contractor must have personnel who are familiar with the system instrumentation and who have the ability to recalibrate the sensors on site during the QA process. The Dredging Contractor must coordinate pickup times and locations and provide transportation to and from any platform with a DQM system to team personnel in a timely manner. The Dredging Contractor must also have on site for the QA checks a tug capable of towing the scow. As a general rule, DQM Data Acquisition and Analysis Team personnel will come with personal protective equipment (PPE) consisting of hardhats, steel toe boots, and life jackets. If additional safety equipment is needed, such as eye protection, safety harnesses, work gloves, or personal location beacons, provide these items to the team while on site. Submit a test data package to the DQM database from the system on each scow and have it accepted by the DQM Support Center prior to scow compliance checks. Also submit data collected during the QA Checks from the scow monitoring system to the DQM database and the Data Acquisition and Analysis Team personnel while on site. It is the Dredging Contractor's obligation to inform the QA team if the location designated for the QA checks has any site-specific safety concerns prior to their arrival on site.

The owner or operator of the scow must contact DQM at <https://www.sam.usace.army.mil/Missions/Spatial-Data-Branch/Dredging-Quality-Management> on an annual basis, or at least three weeks prior to the proposed beginning of dredging, to schedule QA checks. This notification is meant to make the Data Acquisition and Analysis Team aware of a target date and the contract on which the plant will be used. At least one week prior to the target date, the Dredging Contractor must contact the Data Acquisition and Analysis Team and verbally coordinate a specific date and location. The Contractor must then follow up this conversation with a written email confirmation. The owner/operator must coordinate the QA checks with all local authorities including, but not limited to, the local USACE Contracting Officer's Representative (COR).

1.4.3 Recertification

Recertification is required for any yard work which produces modification to displacement (for example, a change in scow lines, or repositioning or repainting hull marks), modification to bin volume (change in bin dimensions or addition or subtraction of structure), or changes in sensor type or location; report these changes in the sensor log section of the DPIP. A system does not have to be transmitting data between jobs; however, in order to retain certification during this period, the system sensors or hardware should not be disconnected or removed from the scow.

If the system is powered down, retain calibration coefficients.

1.5 DREDGE PLANT INSTRUMENTATION PLAN (DPIP)

The Contractor must have a digital copy of the DPIP on file with the DQM Support Center. While working on site, the Contractor must also maintain on the dredge a copy of the DPIP which is easily accessible to Government personnel at all times. This document must describe the sensors used, configuration of the system, how sensor data will be collected, how quality control on the data will be performed, and how sensors/data reporting equipment will be calibrated and repaired if they fail. A description of computed scow-specific data and how the sensor data will be transmitted to the DQM database must also be included. The Contractor must submit to the DQM Support Center any addendum or modifications made to the plan, subsequent to its original submission, prior to start of work.

A complete list of the required DPIP contents is provided on the DQM website

<https://www.sam.usace.army.mil/Missions/Spatial-Data-Branch/Dredging-Quality-Management>

Submit to the DQM Support Center any addendum or modifications made to the plan, subsequent to its original submission, prior to the start of work.

Any changes to the computation methods must be approved by the DQM Support Center prior to their implementation.

PART 2 PRODUCTS

Not used.

PART 3 EXECUTION

3.1 REQUIREMENTS FOR REPORTED DATA

Provide, operate, and maintain all hardware and software to meet these specifications. The Contractor is responsible for replacement, repair, and calibration of sensors and other necessary data acquisition equipment needed to supply the required data. Complete repairs within 48 hours of any sensor failure. Notify the Contracting Officer's Representative (COR) upon completion of a repair, replacement, installation, modification, or calibration. The COR may request recalibration of sensors or other hardware components at any time during the contract as deemed necessary.

Keep a log of sensor repair, replacement, installation, modification, and calibration in the onsite copy of the DPIP. The log must contain a three-year history of sensor maintenance, including the time of sensor failures (and subsequent repairs), the time and results of sensor calibrations, the time of sensor replacements, and the time that backup sensor systems were initiated to provide the required data. It must also contain the name of the person responsible for the sensor work. Install sensors that are capable of collecting parameters within specified accuracies and resolutions indicated in the following subparagraphs.

With the exception of position and any value calculated, reported sensor values should represent a weighted average with the highest and lowest values not included in the calculated average for the given interval. The averaging routine used should be consistent across all event triggers. This information should be documented in the DPIP sections that say "Calculations done external to the instrumentation." These data-reporting requirements cover the collection of electronic data on a scow through the entire dredging cycle. Disposal events can consist of both open-water

disposal and offloading. Open-water disposal is the placement of material via bottom doors or split hull. Offloading is the placement of material via either hydraulic or mechanical means.

3.1.1 Scow Name

Assign a unique name for each scow that will remain constant from one dredging operation to the next.

3.1.2 Contract Number

The USACE-assigned contract number for the project will be reported.

3.1.3 Load Number

A DQM load number must document the end of a disposal event for a given SCOW.

3.1.4 Horizontal Positioning

Record horizontal positioning as the geographic coordinates of the vessel as indicated by the location of the Global Positioning System (GPS) antenna. Obtain all locations using a positioning system operating with a minimum accuracy level of 3 to 10 feet horizontal Circular Error Probable (CEP). Report positions as Latitude/Longitude WGS 84 in decimal degrees. West Longitude and South Latitude values are reported as negative.

3.1.5 Date and Time

Report the date and time to the nearest second and referenced to Universal Time Coordinated (UTC) based on a 24-hour format: yyyy-mm-dd hh:mm:ss.

3.1.6 Hull Status

Hull status is meant to reflect a condition when material could be removed or released from the scow. For this contract, hull status must register closed prior to leaving the disposal area.

3.1.6.1 Open-Water Disposal

Indicate an open split hull or open bottom door of a scow by reporting an "OPEN" value. Indicate a closed split hull or closed bottom door of a scow by reporting a "CLOSED" value. An open status must be indicated as the bin starts to open, and a closed status must be indicated only once the bin is fully closed. For pocket scows, the open/closed status must correspond to the compartment which is first to open and last to close.

3.1.7 Offloading

Offloading occurs when the scow is being unloaded, either by hydraulic or mechanical means. When offloading is occurring, a value of "true" must be reported; otherwise, a "false" value must be reported. The only permissible values are "true" and "false".

3.1.8 Course

Provide scow course-over-ground (COG) using industry-standard equipment. Provide scow course-over-ground (to the nearest whole degree) with values from 000 (true north) to 359 degrees referenced to a clockwise positive

direction convention.

3.1.9 Speed

Provide scow speed-over-ground in knots using industry-standard equipment with a minimum accuracy of 1.0 knot and resolution to the nearest 0.1 knot.

3.1.10 Heading

Provide scow heading using industry-standard equipment. The scow heading must be accurate to within 5 degrees and reported to the nearest whole degree with values from 000 (true north) to 359 degrees referenced to a clockwise positive direction convention.

3.1.11 Draft

Report all draft measurements in feet, tenths, and hundredths with an accuracy of plus or minus 0.1 foot relative to observed physical draft readings. Report the measurements at a resolution of two decimal places (hundredths of a foot). The reported forward draft value must be equal to the sum of the visual forward port and starboard draft mark readings divided by two. The reported aft draft value must be equal to the sum of the visual aft port and starboard draft mark readings divided by two. Forward draft, aft draft, and average draft will be reported. Place sensors at an optimum location on the scow to be reflective of observed physical draft mark readings at any trim or list. Minimum accuracies are conditional to relatively calm water. The reported sensor value is an average of at least ten samples per event, with at least one maximum value and one minimum value removed, and the minimum eight remaining values averaged. When the average draft is calculated for the purpose of determining displacement, maintain significant digits for average draft such that if forward draft were 0.15 and aft draft were 0.1, then the average draft would be 0.125.

3.1.12 Displacement

Report scow displacement in long tons, based on the most accurate method available for the scow. The minimum standard of accuracy for displacement is interpolation from the displacement table, based on the average draft. For this contract the density of water used to calculate displacement is 64.21 lbs/cubic foot and is used for an additional interpolation between the fresh and salt water tables.

3.1.13 Bin Ullage Sounding

Report all ullage soundings in feet, tenths, and hundredths with an accuracy of plus or minus 0.1 foot with respect to the combing and be representative of the forward and aft extents of the hopper as close to the centerline as is possible. Report the measurements at a resolution of two decimal places (hundredths of a foot). If sensors must be offset from the centerline of the bin, they should be offset to opposite sides of the vessel. Forward ullage, aft ullage, and average ullage soundings will be reported. The reported sensor value is an average of at least ten samples per event, with at least one maximum value and one minimum value removed, and the minimum eight remaining values averaged. When the average ullage is calculated for the purpose of determining the hopper volume, maintain significant digits for the average ullage such that if the forward ullage were 0.15 and aft ullage were 0.1, then the average ullage would be 0.125. Special arrangements for pocket scows may be made in consultation

with the DQM Support Center.

3.1.14 Bin Volume

Report scow bin volume in cubic yards based on the most accurate method available for the scow. The minimum standard of accuracy for bin volume is interpolation from the bin volume table based on the average ullage soundings.

3.2 NATIONAL DREDGING QUALITY MANAGEMENT PROGRAM SYSTEM REQUIREMENTS

The Contractor's DQM system must be capable of collecting, displaying, and transmitting information to the DQM database. The parameters which must be reported to the DQM database include trip number, date and time, hull status, offloading status, scow course, scow speed, scow heading, draft, displacement, ullage, and bin volume. Provide an easily accessible, permanent visual display on the scow to show in real time the parameters collected by the system in the same units as the data submitted to the DQM database. In the event a reported parameter is calculated based on multiple sensors, the sensor values as used in the equation must be able to be viewed in addition to the required parameter. If a hardware problem occurs, or if a part of the system is physically damaged, the Contractor is be responsible for repairing it within 48 hours of determination of the condition.

3.2.1 Telemetry

The Contractor may select any commercial satellite, cellular phone, or other data communications systems available, as long as it is capable of transmitting real-time data as well as enough additional bandwidth to clear historically queued data when a connection is reobtained. If connectivity is lost, que and transmit unsent data upon restoration of connectivity. Delays in pushing real-time data to the DQM database should not exceed four hours. Exceptions to these requirements may be granted by the DQM Center on a case-by-case basis with consideration for contract-specific requirements, site-specific conditions, and extreme weather events.

The data transmission process from the scow to the DQM database must be automated. The data may be sent from the scow directly to the DQM database or to a shore-based system. Data transmitted to the DQM database should be raw data; use repeatable automated software or programming routine to process any shoreside data. Include a description of this process in the DPIIP.

3.2.2 Data Reporting Frequency

Log disposal activities with high temporal and spatial resolution. Log data as a series of events. Each set of measurements (time, position, etc.) will be considered an event. Collect any required information in paragraph REQUIREMENTS FOR REPORTED DATA, that is not an averaged variable (that is, draft and ullage) within 1 second of the reported time. Measure data with sufficient frequency by the scow system to resolve the events to the accuracy specified in the following table. Any averaged variable must be collected and computed within this sampling interval. Reporting intervals must be consistent and not change for the data collected on a given scow. This interval should be documented by the Contractor in the DPIIP.

Event Type	Event Trigger Descriptions	Event Time Resolution	Event Position Resolution
Loading	No change in position with hull status closed An elapsed time of 1 hour since the last event. NONCLOSURE In the event a scow has completed an open water disposal and transited back to a holding station without closing the hull, the sampling must be changed to once per hour.	1 minute	N/A
Sailing	Change in position with hull status closed Time from the last sample equals 1 minute.	1 second	plus or minus 10 ft
Offloading	Offloading material, hull status reported as open A position must be recorded within 1 minute arrival at the offload location and within one second of the material starting to be removed from scow. The time from the last sample equals 1 minute. STANDBY OFFLOADING In the even a scow is not being actively offloaded at the offload location for a time equal to one hour, the sampling interval must be equal to once an hour.	1 second 1 minute	plus or minus 10 ft
Open Water Disposal	Hull status open A data point must be recorded within 1 second of the hull status going from closed to open and again within 1 second of the hull status going from open to closed. Between these events, report the data at equal interval from 6 to 12 seconds. This interval must always remain consistent for the dredge plant.	1 second	plus or minus 10 ft

Example: The scow is stationary for 1 hour and 15 minutes, and then it sails to the disposal area. You should have a "Loading/Stationary" event at time 0, time 1 hour, and time 1 hour and 15 minutes. Then, for

"Sailing," within 1 second of an elapsed time of 1 minute from the 1 hour and 15 minutes event, another event occurs.

3.2.3 Data Transmission to the Web Service

Use a Simple Object Access Protocol (SOAP) web service to report sensor data to the DQM database. Transmit data as it is collected in real time and pushed to the DQM web service. If the web service is not available or returns an error message, store the data in a queue and transmit upon re-establishment of the connection, starting with the oldest data in the queue and continuing until real-time transmission is restored. Delays in pushing real-time data to the DQM database should not exceed four hours. Exceptions to these requirements may be granted by the DQM Support Center on a case-by-case basis with consideration for contract-specific requirements, site-specific conditions, and extreme weather events.

Contact dqm-support@usace.army.mil to obtain the web service URL and the appropriate key credentials and communication protocol.

The data transmission method call takes two arguments: a string containing the plant identifier assigned by the DQM Support Center and a second string containing the XML-formatted sensor data. The method returns the string "OK" if the data is received. If the data is not received, either the web service or the client application throws an error.

3.2.4 XML-Formatted Sensor Data String

Pass each scow event as a string on one continuous line of data. The example below is broken up by variable for ease of reading:

```
<?xml version="1.0"?>
<SCOW_DREDGING_DATA version="2.5">
  <SCOW_NAME>AU1994</SCOW_NAME>
  <PLANT_IDENTIFIER>1999</PLANT_IDENTIFIER>
  <CONTRACT>W123BA-09-D-0087_RL01</CONTRACT>
  <TRIP_NUMBER>34</TRIP_NUMBER>
  <X_POSITION>-81.670632</X_POSITION>
  <Y_POSITION>41.528987</Y_POSITION>
  <DATE_TIME>2010-08-14 10:50:15</DATE_TIME>
  <SCOW_SPEED>0.0</SCOW_SPEED>
  <SCOW_COURSE>0.0</SCOW_COURSE>
  <HULL_STATUS>OPEN</HULL_STATUS>
  <OFFLOADING>FALSE</OFFLOADING>
  <SCOW_HEADING></SCOW_HEADING>
  <SCOW_FWD_DRAFT></SCOW_FWD_DRAFT>
  <SCOW_AFT_DRAFT></SCOW_AFT_DRAFT>
  <SCOW_AVG_DRAFT></SCOW_AVG_DRAFT>
  <ULLAGE_FWD></ULLAGE_FWD>
  <ULLAGE_AFT></ULLAGE_AFT>
  <ULLAGE_AVG></ULLAGE_AVG>
  <SCOW_BIN_VOLUME></SCOW_BIN_VOLUME>
  <SCOW_DISPLACEMENT></SCOW_DISPLACEMENT>
  <ADDITIONAL_DATA>Some more scow info, if needed</ADDITIONAL_DATA>
</SCOW_DREDGING_DATA>
```

Format DATE_TIME values as YYYY-MM-DD HH:MM:SS, as shown above. If, for any reason, a field has no value, the enclosing XML tags should be sent with nothing between them (for example, <DRAFT_AFT></DRAFT_AFT>). The web service cannot handle a "null" value or any other indicators of no value

collected.

3.2.5 Contractor Data Backup

Maintain an archive of all data sent to the DQM database during the dredging contract. The Contracting Officer's Representative (COR) may require, at no increase in the contract price, that the Contractor provide a copy of these data covering specified time periods. Provide the data in the HTML format which would have been transmitted to the DQM database. Submit data via storage medium acceptable to the COR.

At the end of the dredging contract, contact the DQM Support Center prior to discarding the data. The DQM Support Center will verify that all data has been received and appropriately archived before giving the Contractor discard permission. Record in a separate section at the end of the scow's onsite copy of the DPIIP the following information:

Person who made the call
Date of the call
DQM representative who gave permission to discard

3.3 PERFORMANCE REQUIREMENTS

The Contractor's DQM system must be fully operational at the start of dredging operations and fully certified prior to moving dredge material on the contract (see paragraph NATIONAL DREDGING QUALITY MANAGEMENT PROGRAM CERTIFICATION). To meet contract requirements for operability, in addition to certification, the Contractor's system must provide a data string with values for all parameters while operating, as described within the specifications. Additionally, all hardware must be compliant with DPIIP requirements (see paragraph DREDGE PLANT INSTRUMENTATION PLAN (DPIIP)). Quality data strings are considered to be those providing values for all parameters reported when operating according to the specification. Make repairs necessary to restore data return compliance within 48 hours. Failure by the Contractor to report the required data within the specified time window for scow measurements (see paragraph DATA REPORTING FREQUENCY, and paragraph DATA TRANSMISSION TO THE WEB SERVICE) and failure to receive DQM certification prior to dredging will result in withholding of up to 10 percent of the contract progress payment.

3.4 LIST OF ITEMS TO BE PROVIDED BY THE CONTRACTOR

DPIIP - <https://dqm.usace.army.mil>
<https://www.sam.usace.army.mil/Missions/Spatial-Data-Branch/Dredging-Quality-M>
Paragraph DREDGE PLANT INSTRUMENTATION PLAN (DPIIP)

DQM SYSTEM

Sensor instrumentation - Paragraph REQUIREMENTS FOR REPORTED DATA

SCOW DATA

Event documentation - Paragraph DATA REPORTING FREQUENCY

Data reports - Paragraph DATA TRANSMISSION TO THE WEB SERVICE

QA EQUIPMENT ON THE DREDGE

Clear and accurate draft marks

Ullage tape

-- End of Section --

SECTION 35 20 23.23

NATIONAL DREDGING QUALITY MANAGEMENT PROGRAM - HOPPER DREDGE
02/22

PART 1 GENERAL

1.1 DESCRIPTION

The work under this contract requires use of the National Dredging Quality Management Program (DQM) to monitor the dredge's status at all times during the contract and to manage data history.

This performance-based specification section identifies the minimum required output and the precision and instrumentation requirements. The requirements may be satisfied using equipment and technical procedures selected by the Contractor.

1.2 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-07 Certificates

National Dredging Quality Management Program Certification, Norfolk District; G

1.3 PAYMENT

Separate payment for installation, operation, and maintenance of the DQM-certified system as specified herein for the duration of the dredging operations is not allowed; all costs in connection therewith are considered a subsidiary obligation of the Contractor and are covered under the contract unit price for beach placement in the bidding schedule.

1.4 NATIONAL DREDGING QUALITY MANAGEMENT PROGRAM CERTIFICATION

1.4.1 Certification

The Contractor is required to have a current certification from DQM for the hopper dredge instrumentation system to be used under this contract. Criteria for certification is based on the most recent specification posted on the DQM website:

<https://www.sam.usace.army.mil/Missions/Spatial-Data-Branch/Dredging-Quality-Management>

Verify compliance with these criteria by annual onsite quality assurance (QA) checks conducted by the DQM Support Center Data Acquisition and Analysis Team and by periodic review of the transmitted data. DQM Certification is valid for one year from the date of the annual QA checks. Certification is contingent upon the system's ability to continuously meet the performance requirements as outlined in paragraph PERFORMANCE REQUIREMENTS. If issues with data quality are not corrected within 48 hours, the system certification will be revoked and additional QA checks by the Data Acquisition and Analysis Team may be necessary.

Annual DQM Certification must be based on the following:

- a. A series of quality assurance checks as outlined on the DQM website:
<https://www.sam.usace.army.mil/Missions/Spatial-Data-Branch/Dredging-Quality-Manag>
- b. Verification of data acquisition and transfer as described in paragraph Performance Requirements.
- c. Review of the Dredge Plant Instrumentation Plan (DPIP) as described in paragraph DREDGE PLANT INSTRUMENTATION PLAN (DPIP).

1.4.2 Recertification

The owner or operator of the dredge must contact DQM at <https://www.sam.usace.army.mil/Missions/Spatial-Data-Branch/Dredging-Quality-Managemen> on an annual basis, or at least three weeks prior to certification expiration, to schedule QA checks for renewal. This notification is meant to make the Data Acquisition and Analysis Team aware of a target date for the annual QA checks for the dredge. At least one week prior to the target date, the Contractor must contact the Data Acquisition and Analysis Team and verbally coordinate a specific date and location. The Contractor must then follow up this conversation with a written email confirmation. The owner/operator must coordinate the QA checks with all local authorities, including but not limited to, the local USACE Contracting Officer's Representative (COR).

Recertification is required for any yard work which produces modification to displacement (change in dredge lines, or repositioning or repainting hull marks), modification to bin volume (change in bin dimensions, or addition or subtraction of structure), or changes in sensor type or location; report these changes in the sensor log section of the DPIP. A system does not have to be transmitting data between jobs; however, in order to retain its certification during this period, the system sensors or hardware should not be disconnected or removed from the dredge. If the system is powered down, retain calibration coefficients.

1.5 DREDGE PLANT INSTRUMENTATION PLAN (DPIP)

The Contractor must have a digital copy of the DPIP on file with the DQM Support Center. While working on site, the Contractor must also maintain on the dredge a copy of the DPIP which is easily accessible to Government personnel at all times. This document must describe the sensors used, configuration of the system, how sensor data will be collected, how quality control on the data will be performed, and how sensors/data reporting equipment will be calibrated and repaired if they fail. A description of the computed dredge-specific data and how the sensor data will be transmitted to the DQM database will also be included. A complete list of the required DPIP contents is provided on the DQM website <https://www.sam.usace.army.mil/Missions/Spatial-Data-Branch/Dredging-Quality-Managemen>. Submit to the DQM Support Center any addendum or modifications made to the plan, subsequent to its original submission, prior to the start of work. Any changes to the computation methods must be approved by the DQM Support Center prior to their implementation.

PART 2 PRODUCTS

Not used.

PART 3 EXECUTION

3.1 REQUIREMENTS FOR REPORTED DATA

Provide, operate, and maintain all hardware and software to meet these specifications. The Contractor is responsible for replacement, repair, and calibration of sensors and other necessary data acquisition equipment needed to supply the required data. Complete repairs within 48 hours of any sensor failure. Notify the COR upon completion of a repair, replacement, installation, modification, or calibration. The COR may request recalibration of sensors or other hardware components at any time during the contract as deemed necessary.

Keep a log of sensor repair, replacement, installation, modification, and calibration in the dredge's onboard copy of the DPIIP. The log must contain a three-year history of sensor maintenance, including the time of the sensor failures (and subsequent repairs), the time and results of sensor calibrations, the time of sensor replacements, and the time that backup sensor systems were initiated to provide required data. It must also contain the name of the person responsible for the sensor work. Install sensors that are capable of collecting parameters within specified accuracies and resolutions indicated in the following subparagraphs. Reported sensor values for ullage, draft, and draghead depth should represent a weighted average with the highest and lowest values not included in the calculated average for the given interval. This information should be documented in the DPIIP sections that say "Calculations done external to the instrumentation."

3.1.1 Date and Time

Report the date and time to the nearest second and referenced to UTC time based on a 24-hour format: mm/dd/yyyy hh:mm:ss. The reported time must be the time reported by the GPS in the NMEA string.

3.1.2 Load Number

A load number must document the end of a disposal event. Load numbering will begin at number 1 at the start of the contract and will be incremented by 1 at the completion of each disposal event or emptying of the hopper. Whenever possible, calculate the load number off of the sensors aboard the dredge, which must be a mathematically repeatable routine. Make efforts to include logic that avoids false load number increments. Do not allow the routine to miss any disposal event. If manual incrementing of the load number is in place, pay extra attention to this value in the quality control process.

3.1.3 Horizontal Positioning

Obtain all locations using a positioning system operating with a minimum accuracy level of 3 to 10 feet horizontal Circular Error Probable (CEP). Report positions as Latitude/Longitude WGS 84 in decimal degrees. West Longitude and South Latitude values are reported as negative.

3.1.3.1 Vessel Horizontal Positioning

Record vessel horizontal positioning as geographic coordinates of the vessel as indicated by the location of the GPS antenna.

3.1.3.2 Draghead Horizontal Positioning

Record draghead horizontal positioning as geographic coordinates of the heel on the centerline of the draghead(s). Describe any offset calculations from the GPS antenna in the DPIP.

3.1.4 Hull Status

Monitor open/closed status of the hopper dredge, corresponding to the split/non-split condition of a split-hull hopper dredge. For dredges with hopper doors, the status of a single door that is the first opened during normal disposal operations may be monitored. An "open" value indicates that the hopper door is open or, in the case of split-hull dredges, that the hull is split. A "closed" value indicates that the hopper doors are closed or, in the case of split-hull dredges, that the hull is not split.

For this contract, hull status must register closed prior to leaving the disposal area.

3.1.5 Dredge Course

Provide dredge course-over-ground (COG) using industry-standard equipment. Provide dredge course-over-ground to the nearest whole degree with values from 000 (true north) to 359 degrees referenced to a clockwise positive direction convention.

3.1.6 Dredge Speed

Provide dredge speed-over-ground in knots using industry-standard equipment with a minimum accuracy of 1 knot and resolution to the nearest 0.1 knot.

3.1.7 Dredge Heading

Provide dredge heading using industry-standard equipment. The dredge heading must be accurate to within 5 degrees and reported to the nearest whole degree with values from 000 (true north) to 359 degrees referenced to a clockwise positive direction convention.

3.1.8 Tide

Obtain tide data using appropriate equipment to give the water level with an accuracy of plus or minus 0.1 foot and a resolution of 0.01 foot. Enter tide values above project datum described in the dredging specification with a positive sign and those below with a negative sign.

3.1.9 Draft

Report all draft measurements in feet, tenths, and hundredths with an accuracy of plus or minus 0.1 foot relative to observed physical draft readings. Report the measurements at a resolution of two decimal places (hundredths of a foot). The reported forward draft value is equal to the sum of the visual forward port and starboard draft mark readings divided by two. The reported aft draft value is equal to the sum of the visual aft port and starboard draft mark readings divided by two. Forward draft, aft draft, and average draft will be reported. Place sensors at an optimum location on the vessel to be reflective of observed physical draft mark readings at any trim or list. Minimum accuracies are conditional to relatively calm water. The sensor value reported must be an average of at

least ten samples per event, with at least one maximum value and one minimum value removed, and the minimum eight remaining values averaged. When the average draft is calculated for the purpose of determining displacement, maintain significant digits for average draft such that if forward draft was 0.15 and aft draft was 0.1, the average draft would be 0.125.

3.1.10 Hopper Ullage Sounding

Report all reported ullage soundings in feet, tenths, and hundredths with an accuracy of plus or minus 0.1 foot with respect to the combing and be representative of the forward and aft extents of the hopper as close to the centerline as is possible. Report the measurements at a resolution of two decimal places (hundredths of a foot). Report forward ullage and aft ullage soundings. Mount sensors to avoid discharge flume turbulence, foam, and any structure that could produce sidelobe errors. If sensors must be offset from the centerline of the hopper, they should be offset to opposite sides of the vessel. If more than one fore or one aft sensor are used, place the sensors near the corners of the hopper, and report the average value of the fore sensors and the average value of the aft sensors. The sensor value reported must be an average of at least ten samples per event, with at least one maximum value and one minimum value removed, and the minimum eight remaining values averaged. When the average ullage is calculated for the purpose of determining hopper volume, maintain significant digits for average ullage such that if forward ullage was 0.15 and aft ullage was 0.1, then the average ullage would be 0.125.

3.1.11 Hopper Volume

Report hopper volume in cubic yards, based on the most accurate method available for the dredge. The minimum standard of accuracy for hopper volume is interpolation from the certified hopper volume table, based on the average fore and aft ullage soundings.

3.1.12 Displacement

Report dredge displacement in long tons, based on the most accurate method available for the dredge. The minimum standard of accuracy for displacement is interpolation from the displacement table, based on the average draft. For this contract the density of water used to calculate displacement is 64.21 lbs/cubic foot, and it will be used for an additional interpolation between the fresh and salt water tables.

3.1.13 Empty Displacement

Report empty displacement in long tons, which is the lightship value of the dredge, or the weight of the dredge with no material in the hopper, adjusted for fuel and water consumption.

3.1.14 Draghead Depths

Report draghead depths with an accuracy of plus or minus 0.5 foot and a resolution to the nearest 0.1 foot as measured from the surface of the water with no tidal adjustments. Minimum accuracies are conditional to relatively calm water. The sensor value reported must be an average of at least ten samples per event, with at least one maximum value and one minimum value removed, and the minimum eight remaining values averaged.

3.1.15 Slurry Densities

Use a density metering device, calibrated according to the manufacturer's specifications, to record the slurry density of each dragarm to the nearest 0.001 g/cc with an accuracy of plus or minus 0.01 g/cc. If the manufacturer does not specify a frequency of recalibration, conduct calibration prior to commencement of work.

3.1.16 Slurry Velocities

Use a flow metering device, calibrated according to the manufacturer's specifications, to record the slurry velocity of each dragarm to the nearest 0.01 fps with an accuracy of plus or minus 0.5 fps. If the manufacturer does not specify a frequency of recalibration, conduct calibration prior to commencement of work. Measure the slurry velocity in the same pipeline inside diameter as that used for the slurry density measurement.

3.1.17 Pump RPM

Measure the RPM of any pump being used to move material with the highest level of accuracy that is standard on the vessel operational displays, either at the bridge, at the drag tender's controls, or in the engine room. Dredges with multiple pumps per side must report RPM for the pump that best describes the dredging process (typically the outboard pump).

3.1.18 Sea Suction Valve for Dragarm

If sea suction can be taken to bypass suction through the draghead, the sea suction location and valve status will be reported. The status of the valve will change from "closed" to "open" when the valve starts to open and will register "closed" when the valve is fully closed. When applicable, the state of the latch will be reported as "true" or "false." Report the sea suction location in a standard non-changing name string of no more than 20 characters. These field values will always occur in the XML string as a set. The DQM system can accommodate only up to four unique sea suction locations. Suggested options for the naming convention can be found in the example dataset in paragraph DATA FORMAT.

3.1.19 Pumpout

When the hopper dredge is being pumped out, report a "true" value; when it is not, report a "false" value. The only permissible values are "true" and "false."

3.2 NATIONAL DREDGING QUALITY MANAGEMENT PROGRAM SYSTEM REQUIREMENTS

The Contractor's DQM system must be capable of collecting, displaying, and transmitting information to the DQM database. Record the applicable parameters from paragraph REQUIREMENTS FOR REPORTED DATA as events locally and continually transmitted to the DQM database anytime an Internet connection is available. Equip the Dredge with a DQM computer system, consisting of a computer, monitor, keyboard, mouse, data modem, UPS, and network hub. Provide a standalone computer system, exclusive to the DQM monitoring system, and with USACE DQM software installed on it. If a hardware problem occurs, or if a part of the system is physically damaged, the Contractor is responsible for repairing it within 48 hours of determination of the condition.

3.2.1 Computer Requirements

Provide a dedicated onboard computer for use by the DQM system. This computer must run USACE software and receive data from the Contractor's data-reporting interface. This computer must meet or exceed the following performance specifications:

CPU:	Intel or AMD processor with a (non-overclocked) clock speed of at least 1.6 gigahertz (GHz)
Hard drive:	250 gigabytes (GB); internal
RAM:	4 gigabytes (GB)
Ethernet adapter:	Internal network card with an RJ-45 connector
Ports:	1 free serial port with standard 9-pin connectors; 1 free USB port
Other hardware:	Keyboard, mouse, monitor

Install a fully licensed copy of Windows 10 Professional Operating System or higher on the computer specified above. Also install any necessary manufacturer-provided drivers for the installed hardware. Locate and orient the computer to allow data entry and data viewing, as well as to provide access to data ports for the connection of external hardware.

3.2.2 Software

The DQM computer's primary function is to transmit data to the DQM shoreside database. Do not install software which conflicts with this function on this computer. The DQM computer must have the USACE-provided Dredging Quality Management Onboard Software (DQMOBS) installed on it by DQM personnel along with USACE-selected software for remote support and management.

3.2.3 UPS

Supply an Uninterruptible Power Supply (UPS) for the computer and networking equipment. The UPS must provide backup power at 1 kVA for a minimum of ten minutes. The UPS must interface with the DQM computer to communicate UPS status. Ensure that sufficient power outlets are available to run all specified equipment.

3.2.4 Internet Access

Maintain an Internet connection capable of transmitting real-time data to the DQM server and supporting remote access, as well as enough additional bandwidth to clear historically queued data when a connection is re-obtained. If connectivity is lost, queue and transmit unsent data upon restoration of connectivity. Delays in pushing real-time data to the DQM database should not exceed four hours. Exceptions to these requirements may be granted by the DQM Support Center on a case-by-case basis with consideration for contract-specific requirements, site-specific conditions, and extreme weather events.

Acquire and install all necessary hardware and software to make the Internet connection available for data transmission to the DQM web service. Configure the hardware and software to allow the DQM Support Center remote access to this computer. Coordination between the dredging

company's IT and the DQM Support Center may be required in order to configure remote access through any security, firewall, router, and telemetry systems. Telemetry systems must be capable of meeting these minimum reporting requirements in all operating conditions.

3.2.5 Data Routing Requirements

Onboard sensors must continually monitor dredge conditions, operations and efficiency and route this information into the shipboard dredge-specific system (DSS) computer to assist in guiding dredge operations. Portions of this Contractor-collected information must be routed to the DQM computer on a real-time basis. Use an RS-232 9600- or 19200-baud serial interface to send standard sensor data to the DQM computer. Configure the serial interface as 8 bits, no parity, and no flow control.

3.2.6 Data Reporting Frequency

Log data as a series of events. Each event will consist of a dataset containing dredge information in accordance with paragraph REQUIREMENTS FOR REPORTED DATA. Each set of measurements (time, position, etc.) will be considered an event. Collect any required information in paragraph REQUIREMENTS FOR REPORTED DATA that is not an averaged variable (draft and ullage) within 1 second of the reported time. Send a data string for an event to the DQM computer every 6 to 12 seconds. This interval must remain constant throughout the contract; do not transmit data strings more than once per every 5 seconds. Collect and compute any averaged variable within this sampling interval.

3.2.7 Data Format

Report data as an extensible Markup Language (W3C standard XML 1.0) document as indicated below. Line breaks and spaces are added for readability, but the carriage return, line feed character combination is added only to delineate records (HOPPER_DREDGING_DATA tag) for actual data transmission.

```
{?xml version="1.0"?}
{HOPPER_DREDGING_DATA version = "2.0"}
  <PLANT_IDENTIFIER>integer string</PLANT_IDENTIFIER>
  {DREDGE_NAME} string32 {/DREDGE_NAME}
  {HOPPER_DATA_RECORD}
    {DATE_TIME} time date string {/DATE_TIME}
    {CONTRACT_NUMBER} string32 {/CONTRACT_NUMBER}
    {LOAD_NUMBER} integer string {/LOAD_NUMBER}
    {VESSEL_X coord_type="LL"} floating point string
  {/VESSEL_X}
    {VESSEL_Y coord_type="LL"} floating point string
  {/VESSEL_Y}
    {PORT_DRAG_X coord_type="LL"} floating point string
  {/PORT_DRAG_X}
    {PORT_DRAG_Y coord_type="LL"} floating point string
  {/PORT_DRAG_Y}
    {STBD_DRAG_X coord_type="LL"} floating point string
  {/STBD_DRAG_X}
    {STBD_DRAG_Y coord_type="LL"} floating point string
  {/STBD_DRAG_Y}
    {HULL_STATUS} OPEN/CLOSED string {/HULL_STATUS}
    {VESSEL_COURSE} floating point string {VESSEL_COURSE}
    {VESSEL_SPEED} floating point string {/VESSEL_SPEED}
```

```

{VESSEL_HEADING} floating point string {/VESSEL_HEADING}
{TIDE} floating point string {/TIDE}
{DRAFT_FORE} floating point string {/DRAFT_FORE}
{DRAFT_AFT} floating point string {/DRAFT_AFT}
{ULLAGE_FORE} floating point string {/ULLAGE_FORE}
{ULLAGE_AFT} floating point string {/ULLAGE_AFT}
{HOPPER_VOLUME} floating point string {/HOPPER_VOLUME}
{DISPLACEMENT} floating point string {/DISPLACEMENT}
{EMPTY_DISPLACEMENT} floating point string
{/EMPTY_DISPLACEMENT}
{DRAGHEAD_DEPTH_PORT} floating point string
{/DRAGHEAD_DEPTH_PORT}
{DRAGHEAD_DEPTH_STBD} floating point string
{/DRAGHEAD_DEPTH_STBD}
{PORT_DENSITY} floating point string {/PORT_DENSITY}
{STBD_DENSITY} floating point string {/STBD_DENSITY}
{PORT_VELOCITY} floating point string {/PORT_VELOCITY}
{STBD_VELOCITY} floating point string {/STBD_VELOCITY}
{PUMP_RPM_PORT} floating point string {/PUMP_RPM_PORT}
{PUMP_RPM_STBD} floating point string {/PUMP_RPM_STBD}
{VALVE_1_LOCATION} string32 {VALVE_1_LOCATION}
{VALVE_1_STATUS} open/closed {/VALVE_1_STATUS}
{VALVE_1_LATCHED} true/false {/VALVE_1_LATCHED}
{VALVE_2_LOCATION} string32 {/VALVE_2_LOCATION}
{VALVE_2_STATUS} open/closed {/VALVE_2_STATUS}
{VALVE_2_LATCHED} true/false {/VALVE_2_LATCHED}
{VALVE_3_LOCATION} string32 {/VALVE_3_LOCATION}
{VALVE_3_STATUS} open/closed {/VALVE_3_STATUS}
{VALVE_3_LATCHED} true/false {/VALVE_3_LATCHED}
{VALVE_4_LOCATION} string32 {/VALVE_4_LOCATION}
{VALVE_4_STATUS} open/closed {/VALVE_4_STATUS}
{VALVE_4_LATCHED} true/false {/VALVE_4_LATCHED}
{PUMP_OUT_ON} true/false/unknown string {/PUMP_OUT_ON}
{/HOPPER_DATA_RECORD}

{/HOPPER_DREDGING_DATA}
Carriage Return - ASCII value 13
Line Feed - ASCII value 10

```

Example

```

{?xml version="1.0"?}
{HOPPER_DREDGING_DATA version = "2.0"}
<PLANT_IDENTIFIER>9999</PLANT_IDENTIFIER>
{DREDGE_NAME}Essayons{/DREDGE_NAME}
{HOPPER_DATA_RECORD}
{DATE_TIME}04/11/2002 13:12:05{/DATE_TIME}
{CONTRACT_NUMBER}GDSNWP-11-G-0001{/CONTRACT_NUMBER}
{LOAD_NUMBER}102{/LOAD_NUMBER}
{VESSEL_X coord_type="LL"}-80.123333{/VESSEL_X}
{VESSEL_Y coord_type="LL"}10.123345{/VESSEL_Y}
{PORT_DRAG_X coord_type="LL"}-80.1233371{/PORT_DRAG_X}
{PORT_DRAG_Y coord_type="LL"}10.12335{/PORT_DRAG_Y}
{STBD_DRAG_X coord_type="LL"}-80.123339{/STBD_DRAG_X}
{STBD_DRAG_Y coord_type="LL"}10.123347{/STBD_DRAG_Y}
{HULL_STATUS}CLOSED{/HULL_STATUS}
{VESSEL_COURSE}258{/VESSEL_COURSE}
{VESSEL_SPEED}3.4{/VESSEL_SPEED}
{VESSEL_HEADING}302{/VESSEL_HEADING}

```

```

{TIDE}-0.1{/TIDE}
{DRAFT_FORE}10.05{/DRAFT_FORE}
{DRAFT_AFT}15.13{/DRAFT_AFT}
{ULLAGE_FORE}10.11{/ULLAGE_FORE}
{ULLAGE_AFT}10.22{/ULLAGE_AFT}
{HOPPER_VOLUME}2555.2{/HOPPER_VOLUME}
{DISPLACEMENT}4444.1{/DISPLACEMENT}
{EMPTY_DISPLACEMENT}2345.0{/EMPTY_DISPLACEMENT}
{DRAGHEAD_DEPTH_PORT}55.10{/DRAGHEAD_DEPTH_PORT}
{DRAGHEAD_DEPTH_STBD}53.21{/DRAGHEAD_DEPTH_STBD}
{PORT_DENSITY}1.02{/PORT_DENSITY}
{STBD_DENSITY}1.03{/STBD_DENSITY}
{PORT_VELOCITY}22.1{/PORT_VELOCITY}
{STBD_VELOCITY}23.3{/STBD_VELOCITY}
{PUMP_RPM_PORT}55{/PUMP_RPM_PORT}
{PUMP_RPM_STBD}54{/PUMP_RPM_STBD}
{VALVE_1_LOCATION}Starboard Dragarm{VALVE_1_LOCATION}
{VALVE_1_STATUS}open{/VALVE_1_STATUS}
{VALVE_1_LATCHED>true{/VALVE_1_LATCHED}
{VALVE_2_LOCATION}Port Dragarm{/VALVE_2_LOCATION}
{VALVE_2_STATUS}closed{/VALVE_2_STATUS}
{VALVE_2_LATCHED>false{/VALVE_2_LATCHED}
{VALVE_3_LOCATION}Port Sea Chest{/VALVE_3_LOCATION}
{VALVE_3_STATUS}closed{/VALVE_3_STATUS}
{VALVE_3_LATCHED>false{/VALVE_3_LATCHED}
{VALVE_4_LOCATION}Starboard Sea Chest{/VALVE_4_LOCATION}
{VALVE_4_STATUS}open{/VALVE_4_STATUS}
{VALVE_4_LATCHED>false{/VALVE_4_LATCHED}
{PUMP_OUT_ON>false{/PUMP_OUT_ON}
{/HOPPER_DATA_RECORD}
{/HOPPER_DREDGING_DATA}
{cr}
{lf}
<?xml version="1.0"?>
<HOPPER_DREDGING_DATA version = "2.0">
  <PLANT_IDENTIFIER>9999</PLANT_IDENTIFIER>
  {DREDGE_NAME}Essayons{/DREDGE_NAME}
  {HOPPER_DATA_RECORD}
    {DATE_TIME}04/11/2002 13:12:10{/DATE_TIME}
    {CONTRACT_NUMBER}GDSNP-11-G-0001{/CONTRACT_NUMBER}
    {LOAD_NUMBER}102{/LOAD_NUMBER}
    {VESSEL_X coord_type="LL"}-80.123334{/VESSEL_X}
    {VESSEL_Y coord_type="LL"}10.123346{/VESSEL_Y}
    {PORT_DRAG_X coord_type="LL"}-80.123372{/PORT_DRAG_X}
    {PORT_DRAG_Y coord_type="LL"}10.12336{/PORT_DRAG_Y}
    {STBD_DRAG_X coord_type="LL"}-80.123340{/STBD_DRAG_X}
    {STBD_DRAG_Y coord_type="LL"}10.123348{/STBD_DRAG_Y}
    {HULL_STATUS}CLOSED{/HULL_STATUS}
    {VESSEL_COURSE}259{/VESSEL_COURSE}
    {VESSEL_SPEED}3.5{/VESSEL_SPEED}
    {VESSEL_HEADING}300{/VESSEL_HEADING}
    {TIDE}-0.1{/TIDE}
    {DRAFT_FORE}10.00{/DRAFT_FORE}
    {DRAFT_AFT}15.15{/DRAFT_AFT}
    {ULLAGE_FORE}10.15{/ULLAGE_FORE}
    {ULLAGE_AFT}10.20{/ULLAGE_AFT}
    {HOPPER_VOLUME}2555.5{/HOPPER_VOLUME}
    {DISPLACEMENT}4444.0{/DISPLACEMENT}
    {EMPTY_DISPLACEMENT}2345.0{/EMPTY_DISPLACEMENT}
  
```



```

{DRAGHEAD_DEPTH_PORT}55.15{/DRAGHEAD_DEPTH_PORT}
{DRAGHEAD_DEPTH_STBD}53.19{/DRAGHEAD_DEPTH_STBD}
{PORT_DENSITY}1.00{/PORT_DENSITY}
{STBD_DENSITY}1.01{/STBD_DENSITY}
{PORT_VELOCITY}22.5{/PORT_VELOCITY}
{STBD_VELOCITY}23.3{/STBD_VELOCITY}
{PUMP_RPM_PORT}55{/PUMP_RPM_PORT}
{PUMP_RPM_STBD}54{/PUMP_RPM_STBD}
{VALVE_1_LOCATION}Starboard Dragarm{VALVE_1_LOCATION}
{VALVE_1_STATUS}open{/VALVE_1_STATUS}
{VALVE_1_LATCHED}true{/VALVE_1_LATCHED}
{VALVE_2_LOCATION}Port Dragarm{VALVE_2_LOCATION}
{VALVE_2_STATUS}closed{/VALVE_2_STATUS}
{VALVE_2_LATCHED>false{/VALVE_2_LATCHED}
{VALVE_3_LOCATION}Port Sea Chest{/VALVE_3_LOCATION}
{VALVE_3_STATUS}closed{/VALVE_3_STATUS}
{VALVE_3_LATCHED>false{/VALVE_3_LATCHED}
{VALVE_4_LOCATION}Starboard Sea Chest{/VALVE_4_LOCATION}
{VALVE_4_STATUS}open {/VALVE_4_STATUS}
{VALVE_4_LATCHED} false{/VALVE_4_LATCHED}
{PUMP_OUT_ON>false{/PUMP_OUT_ON}
{/HOPPER_DATA_RECORD}
{/HOPPER_DREDGING_DATA}
{cr}
{lf}

```

3.2.8 Data Reporting

The system must transmit correctly formatted event data XML strings to the DQM database continuously from mobilization until the last USACE post-dredging survey has been accepted. If the Internet connection (paragraph INTERNET ACCESS) is non-operable, perform manual backups from the dredge computer of the XML data string which would have been transmitted to the DQM computer over the serial connection for each day the device is inoperable and submit to the DQM Support Center within 48 hours. This submission does not replace the requirement of correcting the issue affecting the automatic transmission of data. In the event of data transfer, transmission, or hardware failure, maintain a manually recorded disposal log consisting of a series of events. These events are start of dredging, end of dredging, pre-disposal, and post-disposal. Include time stamp (GMT), position (Latitude and Longitude WGS84), draft, ullage, volume, and displacement for each event. Submit disposal logs on a daily basis to the COR during the time when the system is not operational.

3.2.9 Contractor Data Backup

Maintain an archive of all data sent to the DQM computer during the dredging contract. The COR may require, at no increase in the contract price, that the Contractor provide a copy of these data covering specified time periods. Provide the data, transmitted to the DQM computer, in the XML format with no line breaks between the parameters and each record string on a separate line. The naming convention for the files is {dredgename}_{StartYYYYMMddhhmmss}_{EndYYYYMMddhhmmss}.txt. Submit data via storage medium acceptable to the COR.

At the end of the dredging contract, contact the DQM Support Center prior to discarding the data. The DQM Support Center will verify that all data has been received and appropriately archived before giving the Contractor discard permission. Record the following information in a separate

section at the end of the dredge's onboard copy of the DPIIP:

Person who made the call
Date of the call
DQM representative who gave permission to discard

3.3 PERFORMANCE REQUIREMENTS

The Contractor's DQM system must be fully operational at the start of dredging operations and fully certified prior to moving dredge material on the contract (see paragraph NATIONAL DREDGING QUALITY MANAGEMENT PROGRAM CERTIFICATION). To meet contract requirements for operability, in addition to certification, the Contractor's system must provide a data string with all values for all parameters while operating, as described in the specifications. Additionally, all hardware must be compliant with hardware requirements (paragraph COMPUTER REQUIREMENTS). Quality data strings are considered to be those providing values for all parameters reported when operating according to the specification. Make repairs necessary to restore data return compliance within 48 hours. Failure by the Contractor to report the required data within the specified time window for dredge measurements (see paragraph DATA REPORTING FREQUENCY and paragraph DATA REPORTING) will result in withholding of up to 10 percent of the contract progress payment per FAR 52.232-5 Payments under Fixed-Price Construction Contracts.

3.4 LIST OF ITEMS TO BE PROVIDED BY THE CONTRACTOR

DPIIP

<https://www.sam.usace.army.mil/Missions/Spatial-Data-Branch/Dredging-Quality-M>

DQM System

Sensor instrumentation: paragraph REQUIREMENTS FOR REPORTED DATA
DQM computer: paragraph NATIONAL DREDGING QUALITY MANAGEMENT PROGRAM SYSTEM REQUIREMENTS

Dredge Data

Event documentation: paragraph DATA REPORTING
Dredge data backups: paragraph CONTRACTOR DATA BACKUP

QA Equipment on the Dredge

Dragarm depth chain
Ullage tape
Refractometer
Water sampling device

-- End of Section --

SECTION 35 20 24

BEACH FILL
04/15

PART 1 GENERAL

1.1 DESCRIPTION

The work covered by this section consists of furnishing all plant, labor, material, equipment and services and performing all operations in connection with placing beach fill in accordance with the Contract Drawings and these specifications. For the purpose of these specifications, the term "beach fill" shall be interpreted to mean sand material placed within the prescribed limits (construction templates) to construct the berm unless otherwise noted.

1.2 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

U.S. ARMY CORPS OF ENGINEERS (USACE)

- | | |
|----------------|--|
| EM 385-1-1 | (2024) Safety -- Safety and Occupational Health (SOH) Requirements |
| EM 1110-2-1003 | (2013) Hydrographic Surveying Manual |
| EM 1110-1-1005 | (2007) Topographic Survey Manual |

ASTM INTERNATIONAL (ASTM)

- | | |
|------------|--|
| ASTM D1140 | (2025) Standard Test Methods for Determining the Amount of Material Finer than 75 μm (No. 200) Sieve in Soils by Washing |
| ASTM D2216 | (2019) Standard Test Methods for Laboratory Determination of Water (Moisture) Content of Soil and Rock by Mass |
| ASTM D4318 | (2018) Standard Test Methods for Liquid Limit, Plastic Limit, and Plasticity Index of Soils |
| ASTM D6913 | (2025) Standard Test Methods for Particle-Size Distribution (Gradation) of Soils Using Sieve Analysis |
| ASTM D7928 | (2021) Standard Test Method for Particle-Size Distribution (Gradation) of Fine-Grained Soils Using the Sedimentation (Hydrometer) Analysis |

1.3 SUBMITTALS

Government approval is required for submittals marked with a "G" designation. Submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Surveyor's Qualifications; G

Provide qualifications of the independent licensed surveyor(s) for topographic and bathymetric surveying prior to commencing any survey work.

Surveying Procedures and Equipment; G

All surveying procedures, methods, and equipment for topographic surveys, hydrographic surveys and tidal monitoring, shall be submitted as specified in this section for review and approved by the Government Survey Point of Contact prior to the start of any type of surveying work.

Pre-Placement Condition Surveys; G

The pre-placement condition survey data for each continuous stretch of beachfill shall be submitted within five (5) business days after completion of the surveys in that area. Data shall be submitted in the format specified herein. This submission shall include the photographic documentation of the surveys, as specified herein.

Beach Fill Placement Plan; G

Accident Prevention Plan; G

SD-04 Samples

Beach Fill Samples

SD-06 Test Reports

Testing; G

Within 24 hours of conclusion of physical tests, three (3) copies of the test results, including calibration curves and results of the calibration tests.

Sand Fill Material; G

Daily Report of Operations

SD-07 Certificates

Before and After Beachfill Surveys; G

The before-beachfill survey data of a particular station shall be

submitted along with the after-beachfill survey of that same station within five (5) business days after completion of that station survey set. Data shall be submitted in HYPACK, ISRP files, and ASCII x,y,z format.

Testing; G

Qualifications of the commercial testing laboratory or Contractor's testing facilities.

SD-11 Closeout Submittals

Post-Placement Condition Surveys; G

Post-condition surveys shall be completed and submitted for Government review no later than 30 calendar days after acceptance of final beachfill.

Beach Fill Placement Records and Volume Computations; G

1.4 QUALITY ASSURANCE

Quality assurance will be conducted, on a minimum of ten percent of the Contractor's survey work, by the District survey office. To accomplish this, the District survey office will either re-survey areas or observe the Contractor in conducting their surveys.

1.5 HOPPER DREDGE REQUIREMENTS

1.5.1 National Dredging Quality Management Program

The work under this contract for using Hopper Dredging requires use of National Dredging Quality Management Program (DQM) System, formerly known as Silent Inspector (SI), to monitor the dredge's status at all times during the contract, and to track trip number, time-position history, instrument readings, vessel state, compute tons dry solids, report data, and manage data history. Refer to SECTION 35 20 23.23 NATIONAL DREDGING QUALITY MANAGEMENT PROGRAM - HOPPER DREDGE to identify the minimum required output and precision and instrumentation requirements.

1.5.2 Automated Dredge Quality Assurance Monitoring

Dredging and dredged material disposal monitoring of dredging projects using the National Dredging Quality Management Program (DQM) shall be implemented for this project. The DQM system shall be certified by the SI Support Center within one calendar year prior to the initiation of the dredging/disposal. Additional information about the DQM System can be found at <http://dqm.usace.army.mil/>. The DQM system shall be operational throughout the dredging and disposal project. Project data shall be submitted to the DQM National Support Center in accordance with the specifications. The data collected by the DQM system shall, upon request be made available to the Operations Branch and Regulatory Branch of the U.S. Army Corps of Engineers, Norfolk District.

1.6 QUALIFICATIONS OF SURVEYOR

All surveys shall be performed by an independent survey company. All topographic and hydrographic surveys shall be performed under the direction and supervision of a Professional Licensed Surveyor with a

minimum of 5 years current experience in surveying beach profiles. Surveyors shall be Virginia licensed surveyors. The contractor shall submit his Surveying Procedures and Equipment for topographic surveys, hydrographic surveys and tidal monitoring, shall be submitted as specified in this section for review and approved by the Government Survey Point of Contact prior to the start of any type of surveying work.

1.7 BEACH CONSTRUCTION AND PLACEMENT MEASUREMENT REQUIREMENTS

Measurement of quantity to be placed for pay purposes will be based on pre-construction and post-construction cross section surveys and volume computations made by a surveyor licensed in the Commonwealth of Virginia for each fill placement segment released to the Contractor for construction. The Contractor shall give written notice to the Contracting Officer a minimum of 3 calendar days prior to performing the pre-construction and post-construction surveys. All surveys performed shall meet criteria outlined in EM 1110-2-1003 and EM 1110-1-1005 as specified, in the presence of the Contracting Officer or his designated representative(s). The results of the surveys and volume computations shall be provided to the Contracting Officer in the format as specified within 24 hours. The Contracting Officer shall utilize the surveys and volume computations to determine the actual quantities of materials to be placed in the respective beach fill placement segment for acceptance. Due to the constantly changing shoreline, the Contracting Officer may make alterations in the plan dimensions or slopes of the fill section in order to increase or decrease the volume of fill placed along the beach so as to match the total sand quantity allowed under the contract. No separate payment or adjustment in the unit price will be made as a result of these changes so directed by the Contracting Officer since the total cost of the complete work shall be covered by payment for the total cubic yards placed on the beach at the contract price per cubic yard. The Government reserves the right to perform Quality Assurance Surveys at the expense of the Government to verify survey results.

1.7.1 Beach Fill Plan

(a) At least ten (10) work days prior to initiation of beach fill operations, the Contractor shall submit in triplicate to the Contracting Officer for approval of his proposed plan for beach fill placement indicating planned beach fill reaches and the direction and order of beach fill. The plan shall include the type of dredge plant to be utilized, the location and type of any booster pump facilities to be utilized, and the order of work for beach fill placement. The plan shall also include his proposed method of borrow area excavation. The Contracting Officer reserves the right to reject any scenario which in his opinion may be detrimental to the stability of the in-place beach fill, or for any other credible reason. Excavation of sand from the existing beach for use as beach fill will not be permitted.

(b) In the event of a breakdown of dredging equipment which causes fill operations to cease in any work area, the Contractor shall provide verbal notification to the Contracting Officer immediately. The Contractor shall document at a minimum the nature of the problem, the time of problem discovery, the expected duration to effect repairs, and the actual times of shutdown and restarting dredging operations. This documentation shall be provided to the Contracting Officer within 24 hours following breakdown.

1.8 BEACH FILL SURVEYS

1.8.1 Pre-Placement Condition Survey

The beachfill area conditions are dynamic in nature. Conditions existing during the preparation of this contract may not be an accurate representation of the beachfill area conditions existing at the commencement of beachfill operations. Consequently, the Contractor shall obtain pre-placement condition survey cross sections of the entire project area. Survey cross-sections shall be taken on parallel profile lines (ranges) spaced at a maximum of 500 feet intervals and shall extend from the survey baseline to a minimum of 1,900 feet seaward. Elevations along the cross-sections shall be taken at a maximum of 10 foot intervals, with additional elevations taken at breaks in grade and as necessary to describe all hydrographic and topographic features. The pre-placement condition surveys shall be completed and submitted for Government review not later than thirty (30) calendar days after the receipt by him of the notice to proceed.

1.8.2 Before and After Beach Fill Surveys

Before and After Beach Survey Data and Drawings for acceptance shall be taken by the independent professional engineer or surveyor as specified immediately prior to and after fill placement in a respective beach fill placement segment. Before Beach Fill surveys shall be taken within 3 calendar days before fill placement. The COR reserves the right to request Before Beach Fill Surveys immediately or in a 24 hour period, if the long shore current/drift is in the direction of the placement area. Surveys will be taken on parallel profile lines (ranges) spaced at a maximum of 100 feet intervals. Elevations along the cross-sections shall be taken at a maximum of 10 foot intervals, with additional elevations taken at breaks in grade and as necessary to describe all hydrographic and topographic features. The surveys should be taken to the closure depth or when the foreshore slope meets the existing surface. After Beach Fill surveys shall be taken within 3 calendar days after placement. The Before Beach Fill survey data of a particular station shall be submitted along with the after-beachfill survey of that same station within five (5) business days after completion of that station survey set. Data shall be submitted in HYPACK and ASCII x,y,z format.

1.8.3 Post-Placement Condition Surveys

The post placement condition survey (of the entire beach/project area) shall be completed and submitted for Government review no later than thirty (30) calendar days after acceptance of final beach fill.

1.8.4 Beach Fill Placement Records and Survey Data

All original field notes, computations, and other records for the purpose of the layout of surveys and determining volume of the beach fill material placed by the Contractor shall be recorded in duplicating field books, the original pages of which shall be stamped and signed by the licensed surveyor as specified and furnished promptly to the Contracting Officer at the site of the work. The Contractor shall furnish the Contracting Officer the profile data compiled and certified by the licensed surveyor as specified for each respective survey on a computer disk. The survey data shall be recorded digitally on CD-ROM in HYPACK and ASCII x,y,z format. The data shall be submitted to the Government in the following files:

- a. ASCII files compatible with the Interactive Survey Reduction Program (ISRP), 2.8 format using distance offset from the baseline (x) and elevation (z).
- b. ASCII files having a descriptive header for each profile line followed by three columns: Easting (x), Northing (y) and Elevation (z).
- c. Plotted cross section drawings in AutoCAD 2013 or later format and AutoCAD files for each cross section survey taken. Each drawn cross section shall show the station that it was taken from.
- d. Each new before/after beachfill survey disc submittal shall contain compilation of all previous survey data submitted.
- e. The Government reserves the right to change and revise requirements at the Preconstruction Conference the survey data formats as described above.

1.9 REPORTING REQUIREMENTS

The Contractor shall prepare a daily report of operations as applicable on the forms provided and furnish copies thereof in duplicate to the Contracting Officer or designated field representative. An adequate supply of the forms will be furnished to the Contractor at the preconstruction conference, together with additional direction on preparation or submission.

1.10 SAFETY

1.10.1 General

The Contractor shall comply with the Contract Clause ACCIDENT PREVENTION EM 385-1-1, 15 Sep 08, subject: SAFETY AND HEALTH REQUIREMENTS MANUAL, is a part of these specifications.

1.10.2 Accident Prevention Plan

Prior to the commencement of construction, submit a copy of the Accident Prevention Plan for review and approval by the Contracting Officer or authorized representative. The Contractor shall furnish for review by the Government, no later than 10 days after receipt of Notice to Proceed. The program shall be prepared in the following format:

- (a) Administrative Plan
- (b) Job Hazard Analysis
- (c) A copy of company policy statement of accident prevention and any other guidance statements normally provided new employees.

1.10.3 Accident Investigation and Reporting

Accidents shall be investigated by the immediate supervisor of the employee(s) involved and reported to the Contracting Officer or the Government Inspector within one working day after the accident in accordance with Paragraph 02.A.02 of EM 385-1-1.

- (a) The Contractor shall ensure that all accidents which involve loss

of life, occupational disease of the employee, injury incapacitating any person for normal work beyond the day of injury, or damage to property, materials, supplies, or equipment, of \$700.00 or more, and which relate to the dredge, any attendant plant, the dredge working area, or the disposal area, shall be recorded, investigated, and reported to the Contracting Officer or his authorized representative.

(b) Each accident shall be verbally reported to the Government Inspector at the earliest practicable time. Each accident involving loss of life or traumatic injury to any person shall be reported to the Government Inspector verbally, telephonically, or by radio as soon as possible.

(c) The Contractor shall promptly investigate each accident and submit a written, signed report on ENG Form 3394 to the Government Inspector within 48 hours.

(d) A factual record of each accident shall be entered in the Contractor's official daily log book.

1.10.4 Daily Inspections

The Contractor shall institute a daily inspection program to assure all safety requirements are being fulfilled. Reports of daily inspections shall be maintained in the Contractor's official daily log book. The reports shall be records of the daily inspections and resulting actions. Each report will include, as a minimum, the following:

(a) Phase(s) of construction underway during inspection.

(b) Locations of areas inspections were made.

(c) Results of inspection, including nature of deficiencies observed and corrective actions taken, or to be taken, date, and signature of the person responsible for its contents.

PART 2 PRODUCTS

Not used.

PART 3 EXECUTION

3.1 GENERAL

The purpose of this project is to provide sand to the shoreline/ beach area of the NASA Wallops Flight Facility to the locations, lines, grades, and cross sections shown on the drawings. All materials excavated from the borrow area shall be transported to and deposited on the beach area within the aforementioned lines, grades and cross sections in a controlled manner so as to maximize sand retention within the beach fill section and minimize losses to the ocean. This shall be accomplished in a manner acceptable to the Contracting Officer and shall include, but not limited to temporary diking where required, control of the discharge pipe direction and velocity of discharge, and the control of the sand and water mixture.

3.2 INTERRUPTIONS

The Contractor must anticipate that work may be interrupted for more than

four (4) continuous days, including weekends and holidays, storm events, and NASA Wallops Flight Facility rocket launches. The Contractor must coordinate with the COR for the NASA Wallops Flight Facility for the rock launch schedule. The Contractor must take into consideration any means, methods, and measures that may be required to stop work for an extended period of time.

3.3 CONSTRUCTION BASELINE

The Contractor shall stake and flag, every 100 feet, a construction baseline, located such that it provides easy reference by QA and QC personnel. Baseline control coordinates are shown on the contract drawings. The baseline shall be surveyed utilizing surveying procedures and methodology that meet or exceed accuracy tolerances of ± 0.10 feet in the vertical and ± 0.10 feet in the horizontal. In addition, stake and flag the limits of work at 50 foot intervals. The location of the construction baseline is subject to the approval of the COR.

3.4 PRE-PLACEMENT CONDITION SURVEYS

The beachfill area conditions are dynamic in nature. Conditions existing during the preparation of this contract may not be an accurate representation of the beachfill area conditions existing at the commencement of beachfill operations. Due to the dynamic nature of the shoreline, the cross sections shown on the plans do not reflect what will be on the beach at the time of construction. Cross Sections reflect a Typical profile of each station at the time of the latest survey. Consequently, the Contractor shall obtain pre-placement condition survey cross sections. Commencement of beachfill will not be permitted until these surveys have been submitted and approved by the Government.

3.5 PLACEMENT OF BEACH FILL MATERIAL

The beach fill material shall be removed from the borrow area and transported to the shoreline pump buoy as specified in Section 35 20 23 DREDGING. The beach fill material shall be deposited by the hydraulic pipeline in the beach fill placement area segments as indicated and specified.

3.5.1 Beach Fill Placement Area Pre and Post Construction Inspections

Prior to commencement and immediately after completion of the dredged material placement operations, a joint inspection by representatives of the Contractor and the Contracting Officer will be made. The Contractor shall video the shoreline including areas designated for beach access and egress, seawalls, geotubes, structures, old building foundations and wooden pilings, rip rap, dunes, and vegetation, and the existing beach fill condition during the inspection. The purpose of the inspection is to avoid potential claims that allege damages were caused by construction activities. The complete video inspection record of pre-construction and post-construction conditions shall be provided on CD-ROM/ DVD to the Contracting Officer within 48 hours of each respective inspection.

3.5.2 Beach Fill Placement Area Control

(a) The Contractor shall maintain and protect the beach fill in a satisfactory condition at all times until acceptance of the work. Prior to placement of beach fill, the Contractor shall remove from the worksite all snags, driftwood, and similar foreign debris lying within

the limits of the beach fill section. All materials removed shall be disposed of in areas provided by and at the expense of the Contractor and as approved by the Contracting Officer.

(b) The Contractor shall coordinate with the Contracting Officer to maintain the scheduled work in beach fill placement segments to provide a 100-foot long pre-construction section and a 100-foot long final acceptance section to be surveyed while a 100-foot long construction section is being constructed in between the two sections being surveyed. The work area for surveys shall be a 100-linear-foot section of beach along the fill reference line beginning with the project limit or last acceptance area. The pre-placement (original) sections shall be maintained at a minimum 100 feet ahead of the work area. The Contractor shall request in writing if longer or shorter acceptance sections are requested due to weather or site conditions.

Acceptance reaches shall be used for the purpose of closely monitoring the accumulative amounts of beach fill placed. Acceptance reaches will also be used to control the timing for pre-placement and post-placement surveys. Acceptance for payment by the Contracting Officer of a reach will not be made until all beach fill placement (design and construction template) is made within an acceptance reach and final surveys have been approved. Separate acceptance for the dune portion of the beach-fill may be made for an acceptance reach upon approval of the Contracting Officer. In no case, however, will the Contractor be paid more than once for sand placed in any space along any acceptance reach should erosion occur before the entire volume of sand is placed. Unless otherwise approved by the Contracting Officer, acceptance reach stationing shall conform to stationing shown on the contract drawings.

(c) The Contractor shall place the sand starting at the south portion of the project limits and proceed to the north direction along the beach. Once the Contractor begins placement in an acceptance reach, placement in that reach must be completed before proceeding to another acceptance reach. Beach fill placement operations shall proceed in an orderly manner from reach to reach. If more than one dredge and/or pumpout facility is utilized by the Contractor, more than one beach fill operation may be accomplished simultaneously. However, placement of beach fill in more than two locations at any one time will not be permitted unless otherwise specifically approved by the Contracting Officer.

(d) The beach fill placement area control points, including construction staking, gages, range markers, and buoys required to accomplish the work shall be set by an independent professional engineer or surveyor currently registered and licensed in the Commonwealth of Virginia as specified and shall be maintained by him to define the work and to facilitate inspection. The Contractor shall suspend beachfill operations when staking or ranges cannot be seen or followed.

(e) Construction staking used on the beach shall be 1-inch o.d. steel pipe (painted orange) or other approved material that shall be promptly removed as the work areas are accepted by the Government.

(f) Beach fill material shall be placed in a manner to avoid damage or undermining to all existing structures. The Contractor shall be solely responsible for any damage caused by him to, outfalls,

breakwaters, walkways, bulkheads, structures, seawalls, dunes, or any other real property adjacent to the beach fill areas. Any damage to such items due to fault or negligence of the Contractor shall be repaired or replaced at his own expense in a manner as approved by the Contracting Officer. The beach fill material shall be controlled and graded to prevent material from overtopping existing breakwaters, bulkheads, dunes, outfalls or in any way encroaching landward of such structures unless indicated or specified otherwise. The Contractor shall include in his Safety Plan and Environmental Protection Plan to be submitted to the Contracting Officer for approval the details for preventing beach fill material during pipeline placement from flowing westward of the lines indicated and specified. The Contractor shall be responsible for any damage caused by excessive water flowing landward of the beach fill section. Water shall not be permitted to flow westward of the beach fill segment and, to the maximum extent practical, shall not be permitted to pond on the upland side of the beach fill. Any fill sand which is lost in transit or permitted to flow into the offshore waters or onto the upland areas from the point the sand is discharged on the beach will not be subject to payment.

3.5.3 Method of Discharge to Temporarily Contain Material Prior to Spreading

The Contractor shall install a baffle plate, spreader pipes, pocket pipes, or other approved apparatus to the discharge end of the pipeline that precisely controls the placement of the beach fill material and increases the settlement rate of the material to the maximum extent practicable. Temporary longitudinal control dikes shall be constructed as close to the shoreline as practical and in a manner that requires the effluent water to travel a sufficient distance to minimize turbidity prior to returning to the ocean waters. Such longitudinal dikes and outfall devices shall be used to prevent transverse gullying and erosion at the point of deposit and the subsequent loss of material directly into the ocean waters. Once the material has been deposited, the Contractor shall distribute and grade the material to the lines and elevations as indicated and specified.

3.5.4 Beach Fill Construction and Grading

The beach fill material shall be placed along the beach front as indicated in the construction drawings.

3.5.5 Temporary Protection

If beach fill placement operations are temporarily terminated, the Contractor shall be required to place a protective zone of sand at the end of the last completed acceptance reach for each placement location. The protective zone shall transition from the full section at the end of the last acceptance reach to blend smoothly to the existing beach over a distance of approximately 500 linear feet. The exact length and configuration of the protective zone will depend on the location and shall be constructed as approved or directed by the Contracting Officer. The Contractor is required, however to provide his best efforts in placing material to the designated lines and grades. The contractor shall ensure that there are no undrained areas or abrupt mounds within the completed segments. Any beach/dune fill material that is rehandled or moved and placed in its final position by mechanical methods (i.e. bulldozer, rubber tired loader, pan, etc.) shall be placed in layers not exceeding 3 feet in vertical thickness.

3.5.6 Beach Fill Construction, Grading, and Final Acceptance of the Beach Fill Placement Area

The beach fill material shall be placed along the beach front as indicated in the construction drawings. The finished berm shall be constructed at elevation +7.5 feet (NAVD 88) with varying widths as directed by the Contracting Officer for each respective beach fill segment. The remainder of the respective beach fill segment, such as the foreshore graded slope, shall be constructed to slopes shown on the construction drawings. The final graded beach fill segments shall be constructed to an acceptable tolerance of 0.5 foot above or 0.5 foot below the required berm elevation and specified grade. The Contractor shall mark the positions of each grade stake, and remove them after completion of the project. The Contractor shall ensure that there are no undrained areas or abrupt mounds within the completed segments. The Contractor is not required to perform grading in or seaward of the project adjusted mean low water line.

Upon completion of all filling operations in any acceptance reach, the beach fill shall be graded and dressed so as to eliminate any undrained pockets and abrupt mounds or depressions in the beach fill surface as necessary to comply with tolerance requirements specified below. All temporary dikes shall be completely degraded. Final acceptance of each respective beach fill placement area shall include the removal of all dredge discharge pipeline and Contractor equipment, all markings and stakes placed by the Contractor for the control of his work, and clean-up of all trash and debris from all areas affected by the Contractor's operations. Contractor shall be held responsible for accounting for 100% removal of all grade stakes, as they pose a serious public safety hazard as the fill erodes and any remaining stakes become exposed in the surf. The Contractor is not required to perform grading in or seaward of the project adjusted mean low water line. The Contractor shall take minutes of all on-site inspections, and all parties present shall sign the completed inspection conclusions. Copies of all minutes, photographs and video tapes from inspections shall be included separate of the Daily Report of Operations.

3.5.7 Sampling and Testing of Materials

3.5.7.1 Sample Storage

The Contractor shall construct a suitable, secure wooden storage container for holding beach fill samples until picked up by Corps laboratory personnel. The storage container shall be located as directed by the Contracting Officer at or near the field office. It shall be waterproof and lockable with a duplicate set of keys furnished to the Contracting Officer. The container shall be of sufficient size to hold at least 50 ten lb. bag samples. No separate payment will be made for construction of the storage container.

3.5.7.2 Sampling Requirements

During the beach fill placement operation the Contractor shall be required to obtain and provide to the Contracting Officer samples of beach fill material from the location of placement. These samples shall be taken as directed by the Contracting Officer's Representative and will contain 7 to 10 lbs of beach fill. Samples shall be placed in canvas or other appropriate bags furnished by the Contracting Officer and labeled on the bag as well as on a tag attached to the bag as Quality Assurance (QA) tests with the sample number, location, and date and time sample was

taken. This same information shall be recorded in the Contractor's daily quality control report. The samples shall be delivered to the field office and placed in the locked storage container as soon as possible after sampling. Samples will become the property of the Contracting Officer who will use the samples for testing. No separate payment will be made for the taking of the samples and for providing the samples to the Contracting Officer. It is anticipated that approximately 60 to 80 samples will be required over the course of the project.

3.5.7.3 Gradation Tests

The Contractor shall perform gradation tests on sand fill material placed in the beach fill at the rate of one (1) test for each 500 feet of sand placement. The exact location for taking samples for testing shall be as directed by the Contracting Officer. Sampling procedures shall be as specified in the preceding paragraph for samples to be furnished to the Contracting Officer. Samples shall be labeled as Quality Control (QC) tests. Gradation tests will be performed in accordance with ASTM D6913 and ASTM D1140 and utilized ASTM sieve sizes that correspond to the Unified Soil Classification System (USCS) Classifications. Unless otherwise approved the Contracting Officer, the following sieves shall be used at a minimum:

mm Size	Equivalent ASTM Mesh
75	3 in
37.5	1.5 in
25	1 in
19	3/4 in
9.5	0.375 in
8.00	5/16 in
4.75	#4
4.00	#5
2.00	#10
1.00	#18
0.850	#20
0.50	#35
0.425	#40
0.250	#60
0.125	#120
0.0750	#200
0.0625	#230

Hydrometer analysis shall be performed in accordance with ASTM D7928 on the No. 230 Sieve if the percentage by weight of the No. 230 Sieve is greater than 10% of the total sample. If the soils tested are determined

to be fine grained material containing greater than 50% fines passing the No. 200 sieve, perform atterberg limits testing in accordance with ASTM D4318. Conduct moisture content testing in accordance with ASTM D2216. The results of gradation tests shall be tabulated and plotted on the forms furnished by the Contracting Officer or his authorized representative within 48 hours after sampling. All gradation tests shall be performed by a USACE Validated Testing Laboratory. No separate payment will be made for performing gradation tests and all costs thereof shall be considered a subsidiary obligation of the Contractor.

3.5.8 Improperly Placed Beach Fill Material

Any beach fill material placed outside the vertical or horizontal limits of the fill area will not be paid for and shall be regraded or removed as directed by the Contracting Officer at the Contractor's expense.

3.5.9 Pipeline Safety on the Beach

The Contractor shall provide as a part of his Safety Plan and Accident Prevention Plan, drawings showing locations of temporary alignment routes of pipeline, placement of booster pumps if used in the work, and proposed location of temporary ramps over the pipeline for pedestrian and emergency vehicle access along the beach. The location of the pipeline shall be limited to the shortest alignment route from the pump out mooring facility to the respective beach fill area under construction. The Contractor shall construct a barrier as specified to keep personnel at least 250 feet from the discharge end of the pipe in both directions up and down the beach, and no closer than 100 feet of bulkheads, seawalls, structures, or dune lines unless directed otherwise by the Contracting Officer. Warning signs shall be posted by the Contractor in conspicuous and strategic places along the pipeline alignment stating "Danger - High Pressure Discharge From Dredge". The signs shall be at least 2 feet square and their final placement location approved by the Contracting Officer. The Barricade shall as a minimum be orange polypropylene fencing not less than four feet in height with sand fencing posts spaced sufficient to prevent access of the public to the immediate site of the work in a manner as approved by the Contracting Officer. The Contractor shall provide qualified personnel 24-hours per day at the discharge area. At all times during discharge of material on the beach, at least 2 persons shall be assigned on watch duty with whistles, flashlights, and two-way radio communication with the dredge and beach equipment operators whose sole responsibility is to keep the public out of the work area around the discharge pipeline. Work shall not be performed on the beach fill area unless the designated watch persons are on site. Flagmen shall be stationed at each side of the immediate work area near the seaward end of the orange fencing, and shall be capable of communicating with all Contractor equipment operators at all time. The flagmen shall keep the public out of the barricaded work area at all times, and shall inform all Contractor equipment operators immediately if an unauthorized person(s) enters the barricaded work area. In the event that an unauthorized person(s) enters the barricaded work area, all work shall immediately stop until the person(s) has been removed from the barricaded work area. All costs resulting from suspensions of work as specified above shall be the responsibility of the Contractor and at no additional expense to the Government. During night time operations, the dredge discharge pipeline and point of discharge, as well as all ramp areas provided as access across the discharge pipeline, shall be clearly marked and well lighted in accordance with OSHA for site lighting and as approved by the Contracting Officer. Any deviation from the approved plan will require

approval in writing from the Contracting Officer.

3.5.10 Existing Beach Berm Protection

The Contractor shall protect from damage all existing beach berm and sand dunes and maintain in place any existing beach material that is above the required placement elevation for this contract. The Contractor shall not borrow material or grade material from these areas or disturb vegetation on dunes. The operation and movement of vehicles, equipment and personnel on, over, or across sand dunes is specifically prohibited, except at crossing points that have been approved by the Contracting Officer.

3.6 FIELD QUALITY CONTROL

The Contractor shall establish and maintain quality control for the beach fill placement work and all other operations in connection with the work in the field to assure compliance with contract requirements. The Contractor shall inspect for compliance with contract requirements and record the inspection of all operations including but not limited to the following:

- a. The fill material meets classification requirements and is placed within the beach segment to the lines, grade, and tolerance specified.
- b. Beach fill operations are confined within the limits of the designated work area.
- c. The dredge effluent does not flow landward of the fill section or other limits as specified and established by the Contracting Officer.
- d. Damage to the existing and newly constructed beach is held to the minimum from Contractor's operations.
- e. Adequate control is provided to prevent unnecessary loss of material by seaward flow of pipeline effluent.
- f. The pipeline is periodically inspected for leakage as specified.
- g. All joints of pipe for discharge line are tight, sound and in a safe condition.
- h. All equipment used in the work is approved and in satisfactory working condition.
- i. Checks to insure safe work practices around structures and the public is performed at all times as specified.
- j. Checks conducted for proper lines, grades and elevations in finished fill area including proper grading and elimination of undrained pockets and abrupt humps.
- k. Ensure all equipment and construction materials have been removed from completed work segments.
- l. All results of inspections shall be documented with video tapings, narrative explanations and photographs as required to document the conditions of field quality. The results and supporting data shall be recorded and provided by the Contractor in the Daily Report of Operations.

3.7 FINAL CLEAN-UP

Final clean-up shall be performed by the Contractor immediately after completion of all work and shall include the removal of all the Contractor's plant and equipment either for disposal or reuse. Plant and/or equipment to be disposed of shall be disposed of in a manner and at a location approved by the Contracting Officer. No separate payment shall be made for final clean-up and all costs thereof shall be considered a subsidiary obligation of the Contractor.

3.8 MEASUREMENT AND PAYMENT

3.8.1 General

Measurement and payment shall be in accordance with Section 01 20 00 PRICE AND PAYMENT PROCEDURES.

-- End of Section --

DRAFT
NOT FOR CONSTRUCTION