

**MT FLAP BLACKF 12(1) FLAP Rehabilitation Two Medicine Road / MT NP
GLAC 12(2) FLTP Rehabilitation of Two Medicine Road
Glacier, Montana**

The work consists of reconstruction of asphalt pavement roadway, replacement of existing culverts, and mill and overlay of two parking areas and other small items of work.

Project length: 7.22 miles

Tentative Fixed Completion Date: Fall 2027
(Once solicitation is issued, see FAR Clause 52.211-10 for exact date.)

Estimated Price Range: \$15,000,000 and \$25,000,000

Location: 4 Miles NW of East Glacier, MT

**DESCRIPTION OF WORK in US CUSTOMARY UNITS
FP-14**

	One Schedule Sch Name
DIVISION 150 – Project Requirements	
151 Mobilization (yes/no)	Yes
152 Construction Survey & Staking (yes/no)	Yes
153 Contractor Quality Control (yes/no)	Yes
154 Contractor Testing (yes/no)	Yes
155 Construction Schedules (yes/no)	Yes
157 Soil Erosion Control, Fiber Roll	5,500 LNFT
157 Soil Erosion Control, Fiber Roll (Culvert Protection)	6,500 LNFT
157 Soil Erosion Control, Check Dam	340 EACH
157 Soil Erosion Control, Check Dam (Fiber Roll)	180 EACH
158 Watering for Dust Control	LPSM

	One Schedule Sch Name
DIVISION 200 – Earthwork	
201 Clearing & Grubbing	21.6 ACRE
203 Removal of Pipe Culvert	63 EACH
203 Removal of Sign	43 EACH
203 Removal of Curb	32 LNFT
203 Removal of Curb & Gutter, Concrete	650 LNFT
203 Removal of Sidewalk, Asphalt	250 SQYD
203 Removal of Sidewalk, Concrete	23 SQYD
203 Plug, Existing Pipe	4 EACH
204 Roadway Excavation	11,500 CUYD
204 Subexcavation	4,500 CUYD
204 Select Borrow	12,500 CUYD
204 Boulder	14 EACH
207 Separation Geotextile, Woven	300 SQYD
207 Separation Geotextile, Non-Woven	7,500 SQYD
207 Geogrid, Stabilization	6,500 SQYD
207 Reinforcement Geosynthetic, Type 2	1,500 SQYD
211 Roadway Obliteration, Method 2	4,300 SQYD
DIVISION 250 – Slope Reinforcement and Retaining Walls	
251 Placed Riprap, Class 2	150 CUYD
251 Placed Riprap, Class 3	175 CUYD
251 Placed Riprap, Class 4	550 CUYD
251 Placed Riprap, Class 5	440 CUYD
DIVISION 300 – Aggregate and Base Courses	
301 Aggregate Base Grading D (Leveling Course)	9,500 CUYD
301 Aggregate Base Grading D	5,000 CUYD
303 Ditch Reconditioning	7.26 MILE
304 Full Depth Reclamation, Method 2, 6-INCH Depth	93,000 SQYD

	One Schedule Sch Name
DIVISION 400 – Asphalt Pavements & Surface Treatments	
401 Asphalt Concrete Pavement, Gyratory Mix, ½-INCH, or ¾-INCH Nominal Maximum Size Aggregate, 0.3 to <3 Million ESAL (type III roughness)	23,500 TON
401 Tack Coat	35 TON
401 Asphalt Pavement Milling, 3-INCH Depth	3,500 SQYD
DIVISION 600 – Incidental Construction	
602 12-INCH Pipe Culvert	70 LNFT
602 18-INCH Pipe Culvert	2,160 LNFT
602 24-INCH Pipe Culvert	630 LNFT
602 36-INCH Pipe Culvert	670 LNFT
602 48-INCH Pipe Culvert	940 LNFT
602 120-INCH Pipe Culvert	180 LNFT
602 End Section for 12-INCH Pipe Culvert	1 EACH
602 End Section for 18-INCH Pipe Culvert	33 EACH
602 End Section for 24-INCH Pipe Culvert	12 EACH
602 End Section for 36-INCH Pipe Culvert	10 EACH
602 End Section for 48-INCH Pipe Culvert	5 EACH
605 Standard Underdrain System	1,380 LNFT
607 Lining 18-INCH Pipe Culvert	230 LNFT
607 Lining 24-INCH Pipe Culvert	310 LNFT
607 Lining 30-INCH Pipe Culvert	130 LNFT
607 Lining 36-INCH Pipe Culvert	130 LNFT
609 Curb, Concrete, 12-INCH Depth	240 LNFT
609 Curb & Gutter, Concrete, 12-INCH Depth	660 LNFT
610 Sidewalk, Exposed Aggregate Colored Concrete	470 SQYD
610 Pad, Concrete	290 SQYD
611 Water System	LPSM
612 Sewer System	LPSM
619 Bollard	6 EACH
625 Turf Establishment (Hydraulic Method)	24 ACRE
626 Plantings, Wetland Plant, Container Grown (Drummond's Willow or Booth's Willow)	40 EACH
626 Plantings, Wetland Plant, Container Grown (Engelmann's Spruce)	10 EACH

	One Schedule Sch Name
629 Rolled Erosion Control Product	2,650 SQYD
633 Sign System	660 SQFT
634 Pavement Markings, Type D, Solid (Yellow)	69,000 LNFT
634 Pavement Markings, Type D, Solid (White)	80,000 LNFT
634 Pavement Markings, Type D, Solid (White, Crosswalks & Stop Lines)	300 LNFT
634 Pavement Markings, Type D, Broken (Yellow)	6,800 LNFT
634 Pavement Markings, Type D, Dotted (White)	1,810 LNFT
634 Pavement Markings, Type D, "STOP" Word Message	2 EACH
634 Pavement Markings, Type D, Accessibility Symbol	10 EACH
635 Temporary Traffic Control, Barricade Type 3	12 EACH
635 Temporary Traffic Control, Drum	100 EACH
635 Temporary Traffic Control, Portable Traffic Barrier	1,020 LNFT
635 Temporary Traffic Control, Construction Sign	320 SQFT
635 Temporary Traffic Control, Flagger	3,800 HOUR
635 Temporary Traffic Control, Traffic Control Supervisor	225 DAY
636 System Installation, Electrical	LPSM
636 Utility Box, Pullbox (Electrical)	38 EACH
636 Utility Box, Pullbox (Communications)	38 EACH
636 Utility Trench	38,700 LNFT
647 Environmental Design, Streambed Channel Reconstruction	95 LNFT
647 Environmental Design, Wetlands Mitigation	1,100 SQYD
670 Project Lump Sum (Blackfeet Impact Fee)	CTSM