

SALIENT CHARACTERISTICS

BLDG. 3 ACS INSTALLATION

1 December 2025

1.0. DESCRIPTION OF SERVICES. The contractor shall deliver and install standalone access control system (ACS), Infraguard Revision 7 panels, uninterrupted power supply, panel batteries, laser jet printer, and ACS and access control training for Bldg. 3.

2.0. SCOPE OF WORK DEFINED. The contractor will deliver via the approved shipping method and install ACS equipment.

3.0. GOVERNMENT FACILITIES AND SERVICES. The Government shall receive shipment at 1001 West Boston Ave, Bldg. 3 Fairchild AFB WA, 99011, Fairchild AFB.

4.0. GENERAL INFORMATION.

4.1. Hours of Operation: Normal hours of operation are Monday through Friday 7am – 4pm. Work will not be completed on federal holidays.

5.0. CONTINUATION OF MISSION ESSENTIAL FUNCTIONS. IAW DoDI 1100.22 (Policy and Procedures for Determining Workforce Mix), and any applicable Air Force implementation, unless otherwise directed by an authorized Government representative, it is determined that services provided under this contract are not mission essential for performance during a crisis.

6.0. SALIENT CHARACTERISTICS.

6.1. Contractor/vendor will provide and install:

6.1.1. One (1) Advantor standalone SFXi access control system with closed network switch.

6.1.2. One (1) computer monitors keyboard, and mouse compatible with SFXi.

6.1.3. One (1) uninterrupted power supply, APC SMX1500RM2UC SMART-UPS SMX 1500VA Tower/Rack.

6.1.4. One (1) CIS C9200CX-12T-2X2G-A With DNA License and rackmount

6.1.5. One (1) Laser Jet black and white printer.

6.1.6. Four (4) Infraguard II Rev 7, model IG2PCBASTD panel.

6.1.7. Two (2) ALT EFLOW6N8 12/24VDC 6A 8 Fuse Power Supply

6.1.8. Ten (10) 12-volt, 7 Amp Hour, model BAT YA-NP712GNVT Battery 12V 7AH.

6.1.9. Nine (9) HID 921PHRNEK0001U RPK40-H PIV Class Readers

6.1.10. One (1) HID 920PHRNEK0003U RP40-H PIV Class Reader.

6.1.11. Access Control System training for up to 10 personnel.

6.1.12. One hundred (100) proximity cards, site code 65 start sequence 1001.