

STATEMENT OF WORK
Project No 516-22-112
Upgrade Pharmacy IV Mixing Room – USP 797/800 Compliance
Lee County VA Health Care Center – Cape Coral, FL

1. Background and Objective

- 1.1. The Department of Veterans Affairs requires this project to upgrade the Pharmacy IV Mixing Rooms to achieve compliance with USP 797 and USP 800, which govern sterile and hazardous drug compounding environments. The existing IV mixing rooms do not fully meet current regulatory standards for air quality, pressurization, hazardous drug containment, or workflow safety. Without these upgrades; the pharmacy cannot maintain required sterile compounding operations.
- 1.2. The objective of this project is to perform construction, mechanical, electrical, and architectural upgrades that bring Rooms 1B164, 1B165, and 1B166 into full USP-compliant operation, ensuring safe medication preparation for Veterans and staff. This project occurs within the operating Lee County HCC, requiring special attention to safety, infection control, security, and minimal operational disruption, as required in VA specification Section 01 00 00.

2. General Requirements

- 2.1. The contractor shall fully prepare the site for construction, including all demolition, alterations, and building work required
- 2.2. All work shall comply with VA design manuals, project drawings, and specifications
- 2.3. Contractor staff shall comply with VA security procedures and must obtain proper identification badges

3. Site Preparation and Intent

- 3.1. Prepare the site for construction operations, including removal of designated building elements and protection of existing finishes
- 3.2. Provide all labor, materials, tools, and equipment necessary to complete the project in accordance with contract documents
- 3.3. Coordinate site visits and access with the COR

4. Security and Access Control

- 4.1. Implement the VA-required Security Plan covering physical and administrative security for the duration of the project
- 4.2. Ensure all workers display badges and follow VA Police instructions
- 4.3. Secure all sensitive information and follow EDMS procedures for electronic document control

5. Operations and Storage Areas

- 5.1. Confine all construction activities and storage to areas approved by the COR
- 5.2. Maintain clear access to medical center roads, entrances, and pathway
- 5.3. Limit material deliveries into occupied buildings to no more than two days of supply
- 5.4. Minimize noise, vibration, and disruption to clinical operations

6. Utility Coordination

- 6.1. Maintain continuous utility service to the facility (water, electricity, communications, fire protection, HVAC)
- 6.2. Submit requests for utility shutdowns at least 7 days in advance; major shutdowns require 15 days notice
- 6.3. Provide temporary utility systems where needed to prevent operational interruptions
- 6.4. Ensure all utility work is coordinated with the COR

7. Construction Phasing and Scheduling

- 7.1. Work shall be phased to avoid disruption to 24/7 medical center operations.
- 7.2. Submit a phased construction plan detailing activities, dates, tempo protections, and system interruptions
- 7.3. Provide the COR with two weeks' notice before starting work in any room or area
- 7.4. Coordinate all work to align with clinical scheduling requirements

8. Alterations and Protection of Existing Conditions

- 8.1. Perform a pre-construction survey of existing conditions, documenting surfaces, equipment, and finishes
- 8.2. Protect all existing materials, equipment, and building components from damage throughout construction
- 8.3. Immediately repair and restore any damaged utilities, finishes, or systems
- 8.4. At project completion, restore all disturbed areas to original or better condition

9. Environmental and Waste Handling

- 9.1. Remove all demolition debris, equipment, and waste from the site per VA requirements
- 9.2. Government-retained items must be stored where directed by the COR
- 9.3. PCB-containing equipment, if encountered, shall be disposed of according to EPA and DOT requirements

10. Testing, Balancing, and Commissioning

- 10.1. Submit a detailed written Testing and Commissioning Plan before commencing work
- 10.2. Pre-test all systems prior to requesting final testing
- 10.3. Conduct final testing in presence of the COR and provide all instruments, labor, and materials required
- 10.4. All system components must be operating simultaneously during testing (HVAC supply/return, exhaust, controls, etc)

11. Documentation and As-Built Requirements

- 11.1. Maintain two complete sets of continuously updated as-built drawings
- 11.2. Submit as-built drawings in electronic PDF format at the end of each construction phase
- 11.3. Apply the same requirements to all shop drawings

12. Warranty Management

- 12.1. Submit a Warranty Management Plan 30 days before the pre-warranty conference
- 12.2. Participate in joint 4-month and 9-month warranty inspections with the VA
- 12.3. Follow priority response codes (1, 2, 3) for warranty service, with response times ranging from 4 hours to 3 days
- 12.4. Tag all warranted equipment with VA-approved labels

13. Training and O&M Manuals

- 13.1. Provide complete operation and maintenance manuals (electronic and hard copy) for all installed equipment
- 13.2. Provide factory-trained personnel to conduct training for VA staff
- 13.3. Ensure training includes operation, maintenance, safety, and system integration

14. Construction Signage

- 14.1. Provide and install a VA-compliant construction sign as shown in project drawings
- 14.2. Maintain and remove signage at project completion