

	Questions	Responses
1	Drawings and specifications indicate 7 new curb valves and 2 new post indicator valves to be installed as part of this project's scope. Our team has worked in St.Albans and knows in order to swap these valves the entire facility would need to be shut down and drained. Would the VA be open to allowing the contractor to keep the existing curb valves in place and install a new curb valve downstream without needing a facility shut down? This would reduce the total facility shutdowns from 9 to 2.	All existing curb valves must be replaced without impacting the facility; the facility's water supply must be maintained at all times. Note of clarification: There are only 6 Fire Hydrants and there are 3 post-indicator valves. Please see the attached document for photographs of all hydrants and PIVs for removal and replacement in the SOW.