

AMENDMENT OF SOLICITATION/MODIFICATION OF CONTRACT				1. CONTRACT ID CODE		PAGE 1 OF 4 PAGES	
2. AMENDMENT/MODIFICATION NO. AMENDMENT NO. 0001		3. EFFECTIVE DATE 3/20/26		4. REQUISITION/PURCHASE REQ. NO.		5. PROJECT NO. (If applicable) 26-0410	
6. ISSUED BY CODE		N40085		7. ADMINISTERED BY (If other than Item 6) CODE			
NAVFAC Mid-Atlantic Resident Officer in Charge of Construction 1107A Birch Street Camp Lejeune, NC 28547-2521				See Item 6			
8. NAME AND ADDRESS OF CONTRACTOR (No., street, county, State and ZIP Code)				(X)		9A. AMENDMENT OF SOLICITATION NO.	
				X		N40085-26-R-9018	
						9B. DATED (SEE ITEM 11) 2/24/26	
						10A. MODIFICATION OF CONTRACT/ORDER NO.	
						10B. DATED (SEE ITEM 11)	
CODE		FACILITY CODE					
11. THIS ITEM ONLY APPLIES TO AMENDMENTS OF SOLICITATIONS							
☒ The above numbered solicitation is amended as set forth in Item 14. The hour and date specified for receipt of Offers ☒ is extended, ☐ is not extended. Offers must acknowledge receipt of this amendment prior to the hour and date specified in the solicitation or as amended, by one of the following methods: (a) By completing items 8 and 15, and returning <u>1</u> copies of the amendment; (b) By acknowledging receipt of this amendment on each copy of the offer submitted; or (c) By separate letter or telegram which includes a reference to the solicitation and amendment numbers. FAILURE OF YOUR ACKNOWLEDGMENT TO BE RECEIVED AT THE PLACE DESIGNATED FOR THE RECEIPT OF OFFERS PRIOR TO THE HOUR AND DATE SPECIFIED MAY RESULT IN REJECTION OF YOUR OFFER. If by virtue of this amendment your desire to change an offer already submitted, such change may be made by telegram or letter, provided each telegram or letter makes reference to the solicitation and this amendment, and is received prior to the opening hour and date specified.							
12. ACCOUNTING AND APPROPRIATION DATA (If required)							
13. THIS ITEM ONLY APPLIES TO MODIFICATION OF CONTRACTS/ORDERS. IT MODIFIES THE CONTRACT/ORDER NO. AS DESCRIBED IN ITEM 14.							
CHECK ONE	A. THIS CHANGE ORDER IS ISSUED PURSUANT TO: (Specify authority) THE CHANGES SET FORTH IN ITEM 14 ARE MADE IN THE CONTRACT ORDER NO. IN ITEM 10A.						
	B. THE ABOVE NUMBERED CONTRACT/ORDER IS MODIFIED TO REFLECT THE ADMINISTRATIVE CHANGES (such as changes in paying office, appropriation date, etc.) SET FORTH IN ITEM 14, PURSUANT TO THE AUTHORITY OF FAR 43.103(b).						
	C. THIS SUPPLEMENTAL AGREEMENT IS ENTERED INTO PURSUANT TO AUTHORITY OF:						
	D. OTHER (Specify type of modification and authority)						
E. IMPORTANT: Contractor ☐ is not, ☐ is required to sign this document and return _____ copies to the issuing office.							
14. DESCRIPTION OF AMENDMENT/MODIFICATION (Organized by UCF section headings, including solicitation/contract subject matter where feasible.) 26-0410, Roof Repairs FC571, FC520, FC525, FC573, FC574 Amendment 0001, Answer Requests for information The time and date for receipt of proposals has been changed to 1 April 2026 at 3:00PM. This amendment should be acknowledged when your proposal is submitted. Failure to acknowledge the amendment may constitute grounds for rejection of a proposal. See Continuation Page(s) Except as provided herein, all terms and conditions of the document referenced in Item 9A or 10A, as heretofore changed, remains unchanged and in full force and effect.							
15A. NAME AND TITLE OF SIGNER (Type or print)				16A. NAME AND TITLE OF CONTRACTING OFFICER (Type or print)			
15B. CONTRACTOR/OFFEROR		15C. DATE SIGNED		16B. UNITED STATES OF AMERICA		16C. DATE SIGNED	
(Signature of person authorized to sign)				(Signature of Contracting Officer)			

NSN 7540-01-152-8070
Previous edition unusable

STANDARD FORM 30 (REV. 10-83)
Prescribed by GSA FAR (48 CFR) 53.243

CONTINUATION SHEET

1. QUESTION: Note 2 under General Requirements for Bldg. FC571. "Remove existing Lightning Protection If Applicable". NOTE 13 Does say Reinstall if applicable. What determines if its applicable?

ANSWER: Intent is to remove lightning protection and not reinstall.

2. QUESTION: Note 2 under General Requirements for Bldgs. FC520, 525, 573 and 574 states "Remove existing Lightning Protection If Applicable". There are no notes to reinstall the existing lightening protection. Is the intent to leave the Lightning protection off the building? Is the intent to reinstall the existing lightening protection? Is the intent to install new lightening protection? If new lightening protection is required, please provide design requirements.

ANSWER: Intent is to remove lightning protection and not reinstall.

3. QUESTION: Note 9 under General Requirements for Building FC520, 525, 573, 574 states "Install panel clips as per the manufactures recommendation for a 150 mph Wind in accordance with the Uniform Building Code for North Carolina". Panel clip spacing based on the Wind Uplift Calculations takes into consideration the pull-out strength of the roof deck substrate. Does the Government know if the plywood roof decks are 5/8" plywood or 3/4" plywood?

ANSWER: Government does not have this information.

4. QUESTION: Note 10 under General Requirements for Building FC571 states "Install panel clips as per the manufactures recommendation for a 150 mph Wind in accordance with the Uniform Building Code for North Carolina". Panel clip spacing based on the Wind Uplift Calculations takes into consideration the pull-out strength of the roof deck substrate. Does the Government know if the plywood roof decks are 5/8" plywood or 3/4" plywood?

ANSWER: Government does not have this information.

5. QUESTION: During our site visit we noticed the downspouts are not typical downspouts on all 5 different buildings. All 5 buildings show the downspouts dropping out of the bottom of the gutters, running down the parapet wall about 2 feet and turning back into and through the existing parapet wall piping the rainwater back into the building into pvc piping installed in the attic. Our experience over the last 10 to 15 years has included provisions in the contract drawings to provide 6"x6"x1/4" Steel Downspouts to channel the water out of the building down and tying into a rain leader below grade. The Tubular Steel provides protection of the downspout from potential damage that could crush or bend the typical light gaug!3 aluminum downspouts. I have included a typical Tubular Steel DS detail from a project we are doing now here at Camp

Lejeune. There is currently no work included in this projects scope of work to do anything with the existing gutters and downspouts other than to clean them. Does the government want to leave the downspouts turning back into the attic space or are 6x6 tubular steel downspouts needed on these 5 buildings.

ANSWER: Demolish existing metal gutters & downspouts. Infill downspout leader openings and finish to match existing aggregate covered precast parapet panels. Provide new 6" wide x 6" deep gutter with 4x4 downspout leader. Install new 6"x6"x1/4" steel downspout as per downspout detail (attachment provided). Location of new downspouts shall be each side of existing dormers and each side of stairwell. Note: In lieu of steel pipe pipe outlet connecting to drain pipe, provide 4" galv. steel pipe outlet at 4" above existing grade and concrete splashblock at each outlet.

6. QUESTION: On both files with “..Roof Repairs SOW” in the title – on sheet A1 General Note #23 states “Contractor shall review asbestos inspection survey before commencing work”. We don’t see where an asbestos survey is provided in the RFP to be able to identify any asbestos containing materials to be demolished with the roof. Will this be provided? Without a survey there is no way for us to know exactly what the material is and quantity to be removed.

ANSWER: Asbestos reports have been provided.

7. QUESTION: On both files with “...Roof Repairs SOW” in the title– on sheet A1 under Hazardous Materials – Notes: #2 states if found contractor to abate asbestos if found. If we are to include abatement we must be able to verify type and quantity to be removed to estimate accurately. Will the asbestos surveys be provided?

ANSWER: Asbestos reports have been provided.

8. QUESTION: Plans set states to remove and replace permanent fall protection. Does the replacement fall protection system/connections need to be identical to the old system/connections?

ANSWER: Install per attached specification Section 11 24 24 PERMANENT HORIZONTAL FALL PROTECTION, METAL ROOFING.

9. QUESTION: In several documents including Combined Div 01 DBB SPECS, 01 11 00 para 1.2 and 01 14 00 para 1.2 special scheduling is “as described in the attached project description”. Is there a separate attachment with that title that describes preferred phasing in detail?

ANSWER: There were no additional phasing guidelines provided. The only special scheduling specified was included in the RFP.

10. QUESTION: The RFP dated 2/23/2026 has listed 5 barracks that need new roofs to include demo of the existing roofs and installing new standing seam metal roofs. The Contract completion date is shown as 360 days after award. There is typically 60 days needed after the

award to hold the Preconstruction conference, issue all Purchase Orders and get Admin and Technical submittals in, and approved to allow procurement of materials needed to start work. This only leaves 300 calendar days to complete all 5 buildings to include punch out and final inspections. $300/5 = 60$ calendar days per building. Actual workdays estimating 5 workdays a week leave only about 44 work days to complete all scopes on each building to avoid completing late and incurring LDs. Our Experience with these barracks with this scope of work will require a minimum of 3 to 4 months per building to take inconsideration inclement weather and other mitigating factors. Will the Government consider increasing the time allowed to do all 7 buildings a minimum of 720 days?

ANSWER: PWO has no objections to this. The contract CCD has been extended to 720 days.

11. A revised Pricing Sheet has been provided.
12. A site visit roster has been provided.
13. All other terms and conditions remain unchanged.