

**FUEL PROGRAM PREVENTIVE MAINTENANCE AND CORRECTIVE
MAINTENANCE**

PERFORMANCE WORK STATEMENT

**SOUTH ATLANTIC DIVISION – AIR FORCE
SAD-AF2**

~~17 November 2025~~

5 May 2026

U. S. Army Engineering and Support Center

Huntsville, Alabama

Rev #	<u>Date</u>	<u>Description</u>
Rev 01	<u>5 May 2026</u>	<u>Five (5) Quarterly PM events, Five (5) Semi-Annual PM events, and Ten (10) Annual PM events outlined in Appendix I along with ESOs only for 10 week contract</u>

TABLE OF CONTENTS

PERFORMANCE WORK STATEMENT

Section 1 – General Information

Section 2 – Definitions

Section 3 – Maintenance Activities and Submittals

Section 4 – Applicable Criteria

Section 5 – Performance Requirements Summary

APPENDICIES

Appendix A – Preventive Maintenance and Service Order Process Requirements

- Attachment 1 Service Order Form
- Attachment 2 Contractor Travel Expense Report

Appendix B – Reporting Requirements and Templates

- Attachment 1: Three Week Look Ahead Schedule Template
- Attachment 2: Monthly Report Template
- **Attachment 3: Preventive Maintenance Report Template**
- Attachment 4: Service Order Tracker

Appendix C – Contract Specifications

- **01 33 00 Submittal Procedures**
- 01 35 26 Governmental Safety Requirements
- 01 45 00.00 10 Quality Control
- 01 45 00.15 10 Resident Management System Contractor Mode (RMSCM)
- 01 78 23 Operation and Maintenance Data
- ~~**Fuels Program Requirements – Joint Sealant and Crack Repair**~~

Appendix D – Antiterrorism/Operations Security Compliance and Installation Access

~~**Appendix E – Sample Installation Status Reports**~~

Appendix F – Component Unique Identifier

Appendix G – UFC 3-460-03 Maintenance Table

~~**Appendix H – Corrective Maintenance Incidental to Maintenance Activities**~~

Appendix I – Contract Site List and Support Level

Appendix J – Existing Preventive Maintenance Schedules

Appendix K – Real Property / Equipment Data

- **K1 - Air Force Real Property Inventory-NEXGEN**
- **K2 – DLA Real Property Inventory-EBS**

Appendix L – Existing Facility Maintenance Plans

Appendix M – Essential Mission Criteria

SECTION 1 – GENERAL INFORMATION

1.0 Introduction

The HNC Fuels Program (referred to as RMMR by the Defense Logistics Agency) is a comprehensive maintenance program that provides vital preventive maintenance and corrective services to the United States Government to sustain a worldwide robust fueling capability in support of federal petroleum facilities and petroleum systems. The program is divided in two distinct services, Preventive Maintenance and Corrective Maintenance (PMCM).

The Preventive Maintenance (PM) program adheres to the inspection and maintenance criteria outlined in Unified Facilities Criteria (UFC) 3-460-03 (Attachment G), Petroleum Fuel System Maintenance, for military land-based liquid petroleum fuel facilities. These criteria are applicable to all branches of the Department of Defense (DoD) and the Defense Logistics Agency (DLA). This contract requires a Contractor experienced in repair, maintenance, and operation of federal petroleum facilities and petroleum systems ensuring those systems are in compliance with codes, criteria, regulations, and laws of the United States/host nation (local and national). UFC 3-460-03 applies to all real property facilities used for storing, distributing, and dispensing fuels for reciprocating and jet engine aircraft, automotive fuels, lubricating oils, and diesel fuel. In addition to a well-maintained system or facility, the PM portions will return written reports detailing systems evaluated, corrective actions taken, and documenting facility, system, and component deficiencies.

The Corrective Maintenance (CM) program provides a contract vehicle for corrective action of deficiencies to petroleum facilities, petroleum systems, and supporting DLA capitalized facilities as well as emergency response capability to ensure the safe and reliable accomplishment of the applicable fuels delivery mission. Other repairs may be requested by each DLA Capitalized Site for components, equipment, or systems in support of fuels delivery mission.

This contracting effort is part of a continuously improving Government approach to providing effective fuel systems Preventive Maintenance and Corrective Maintenance Services. The Government recognizes a successful Contractor as one that takes ownership of the physical condition of the assigned Installation fuel delivery systems, executes continuous process improvement to increase efficiencies and reduce cost, and establishes a responsive rapport with Installation representatives, the USACE program management office, and the DLA customer program managers.

1.1 Purpose

The purpose of this contract is to provide all required PM and CM Services identified through a Facility Maintenance Plan (FMP) prepared by the Contractor to provide pertinent details of how the Contractor will perform Preventive Maintenance, Emergency Repair, Corrective Maintenance, and provide a program of Records Management for petroleum facilities, petroleum systems, and supporting DLA Capitalized facilities on Government Installations in compliance with all codes, criteria, regulations, laws of the United States (local, state, and federal), and/or host nation laws as applicable. The Contractor must provide all labor, management, supervision, Quality Control, transportation, supplies, vehicles, tools, materials, facilities, equipment, and incidentals necessary to conduct work described in this Performance Work Statement (PWS).

PM tasks are defined as recurring, periodic, or scheduled work to preserve a system or facility by preventing its deterioration, prevent component failure, prevent unscheduled outages, and identify components requiring replacement or repair. PM tasks involve routine inspections, testing of petroleum fuel systems, and identifying required repairs. PM tasks help ensure product quality, safe working conditions, and environmental protection.

CM is defined as the restoration of a real property to such a condition that it may effectively be utilized for its designated purpose by overhaul, re-processing or replacement of constituent parts or materials that have deteriorated by action or elements or usage and that have not been corrected through maintenance.

Periodic testing of systems/components, on a quarterly, semi-annual, and annual basis as described in Appendix G of this PWS are included within the definition of maintenance and repair.

Corrective Repair requirements are described in Appendix A, Service Order Process Requirements. The award for services under this scope of work will be limited to the services identified in the contract line items awarded in the contract and its modifications.

1.2 Scope and Authority

The Contractor must properly maintain, and repair capitalized funded petroleum facilities and petroleum systems in order to provide compliance with applicable codes, criteria, and federal, state, local and/or host nation regulations. The list of Sites, facilities, and equipment/components included in this order are identified in Appendices I, K, and L. The Contractor must provide all labor, management, supervision, Quality Control, transportation, supplies, vehicles, tools, materials, facilities, equipment, and incidentals necessary to conduct work described in this PWS.

The Government reserves the right to perform the following as in scope modifications to the contract:

- A. Add, remove, or realign Installations/Sites to or from the initial Installation/Site list.
- B. Add or remove facilities/equipment to or from the initial facility list.
- C. Add or remove services performed at any Installation/Site.

These additions/deletions will be considered in scope and will be performed as a contract modification to be negotiated between the Government and Contractor, via. Request for Proposal (RFP).

Additionally, repair activities may only be performed by Service Order at the included Installations/Sites on Capitalized assets specifically identified on the Government provided Real Property Inventory.

The anticipated services start dates for all Sites is identified in Appendix I. For any sites added to the contract through a modification, the associated start date will be documented within the text of the contract modification. For sites with an anticipated start date after contract award, a notice to proceed (NTP) will be issued by the (KO) before services can begin.

1.2.1 Centrally Managed Programs

The Government utilizes Centrally Managed Programs (CMPs) to perform work on certain systems/components of the petroleum facilities within the Installations. Contractors performing work under its CMP have primacy over any maintenance/repair/inspection conflict and/or overlap at any federally funded petroleum facility. Therefore, any Contractor performing work under this contract should concede authority and allow the CMP Contractor to perform the required maintenance/repair/inspection work at the designated facility. The Contractor will contact the KO within 48 hours of identification of a conflict.

The following are centrally managed programs applicable to fuel systems and further details are provided in the current version of UFC 3-460-03: Tank Integrity Management Program, Pipeline Integrity Management Program, Cathodic Protection System Integrity Management Program, Maritime Fuel Facilities/Piers Program, Marine Loading Arm Program, Underwater Hose Program, Dredging Program, Rails Program, Demolition Program, Automated Fuel Handling Equipment/Automatic Tank Gauging Program.

The Contractor must advise the KO or the Contracting Officer's Representative (COR) of significant, unforeseen site conditions affecting this contract within 24 hours of discovery or before departing the Site if the departure is scheduled for less than 24 hours from the discovery of the unforeseen site condition. The Contractor must take appropriate measures to obtain clarification of any direction or contract requirement which is not fully understood and incorporate such information into the work being performed. The contractor shall notify the KO within one (1) calendar day of any contract requirement that cannot be performed as specified in the PWS.

1.2.2 Post Award Meeting

Reserved

1.2.3 Kickoff Meeting

Reserved

1.2.4 Initial Site Visits

Reserved

1.3 Public Disclosures

The Contractor must make no public announcement or disclosure relative to information contained or developed under this contract, except as authorized by the KO.

1.4 RESERVED

1.5 Personnel Requirements

The Contractor must provide personnel possessing the skills, knowledge, and training to satisfactorily perform the services required by this contract. Personnel performing work under this Performance Work Statement will remain employees of the Contractor (or Subcontractor)

and will not be considered employees of the Government. Subcontractor personnel, if utilized, must be capable of performing position duties as if employed by the prime Contractor, who will have responsibility to provide subcontracted services equivalent to prime contract personnel.

The Contractor is allowed to subcontract work (unless otherwise specified), self-perform work, or a combination of both. The Contractor must ensure that all technicians are qualified to perform the work. The Contractor will be responsible for achieving response requirements for multiple simultaneous field actions while maintaining capability for potential emergency repairs and still performing required field actions within the period available so as to minimize impacts on facility mission requirements. Prime and Subcontractor personnel must be able to obtain Site access to include acquisition of necessary credentials and/or security clearance.

The Contractor will supplement these required personnel with the appropriate level of administrative and maintenance personnel to effectively manage the contract requirements.

All Key Personnel of the Contractor must be included in the firm fixed price for both onsite and offsite activities. Key personnel include the Project Manager, Deputy Project Manager, Quality Control Manager, Safety Manager and Site Manager(s).

Refer to contract clauses and Appendix D Antiterrorism/Operations Security Compliance.

1.5.1 Prime Contractor Qualifications

The prime Contractor will be solely responsible for the fulfillment of the requirements of this contract and will be the sole contact except as agreed to in advance. The Contractor must have, as a minimum, the following qualifications:

- A. 5+ years of demonstrated experience on federal installations in maintenance and repair of petroleum fuel storage and distribution facilities.
- B. Working knowledge of U.S. and host nation practices for the operation, inspection, maintenance, repair, and testing of petroleum facilities; and U.S. and host nation practices for the environmental protection requirements for petroleum facilities.
- C. Demonstrated Project Management, scheduling and engineering capabilities to execute the requirements of this PWS.

1.5.2 Subcontractor Qualifications

The Contractor may use subcontractors for maintenance and/or repair. These agreements are between the prime and sub and any service provided must be included in the prime Contractor's Service Order portfolio.

All required subcontractor certifications must be maintained by the prime Contractor and updated upon expiration. Subcontractor qualifications must be approved by the prime Contractor prior to the start of any work activity. Copies of required certifications must be provided to the Government within one (1) calendar day of request or submitted as part of Service Order Portfolio.

1.5.3 Project Manager

The Project Manager must be an employee of the prime Contractor and will be the party responsible for the overall performance of the contract and will report to the program manager or other corporate officer of the Contractor. The Project Manager shall be physically located within a state or territory of the United States located in UTC Zones UTC -4 through UTC -10 (Quebec Time Zone through Whiskey Time Zone).

The Project Manager must have a minimum of five (5) years of experience in management of projects performing maintenance and repair. Acceptable experience includes managing maintenance and repair projects on petroleum facilities similar to those facilities specified herein, in a complex maintenance environment, in commercial construction of petroleum facilities, or military construction/maintenance contracts. The Project Manager must have experience planning and executing projects, to include managing multiple projects simultaneously throughout their lifecycle including management of budget, schedule, and coordination of all technical requirements. The Project Manager must have knowledge of the applicable codes and criteria surrounding repair and maintenance of Petroleum, Oils, and Lubricants (POL) infrastructure and/or similar experience. The Project Manager must be able to convey information clearly in writing and orally in English.

This position is considered to be critical to the successful performance of this contract. Prior to replacing the person proposed for this position, the Contractor must obtain written consent of the KO. In order to obtain such consent, the Contractor must provide advance notice (14 calendar days unless there are mitigating circumstances deemed acceptable by the Government) of the proposed changes and must demonstrate that the qualifications of the proposed substitute personnel are generally equivalent to or better than the qualifications of the personnel being replaced.

The Project Manager's resume must be submitted to the KO for approval in accordance with Appendix C 01 45 00.00 10 Quality Control. The Project Manager must have no other duties within or outside of this contract and must be a full-time employee dedicated to this contract.

1.5.3.1 Deputy Project Manager

Not required for this contract.

1.5.4 Quality Control Manager

The QC Manager must have a minimum of five (5) years of experience on Operation and Maintenance of Petroleum Fuel Systems. The QC Manager and Alternate QC Manager must comply with the requirements as identified in UFGS 01 45 00.00 10 Quality Control.

This position is considered to be critical to the successful performance of this contract. Prior to replacing the person proposed for this position, the Contractor must obtain written consent of the KO (14 calendar days unless there are mitigating circumstances deemed acceptable by the Government). In order to obtain such consent, the Contractor must provide advance notice of the proposed changes and must demonstrate that the qualifications of the proposed substitute personnel are generally equivalent to or better than the qualifications of the personnel being replaced.

The QC Manager's resume must be submitted to the KO for approval in accordance with

Appendix C 01 45 00.00 10 Quality Control. The QC Manager must have no other duties within or outside of this contract and must be a full-time employee of the prime Contractor dedicated to this contract.

1.5.5 Project Engineer

The project engineer must be a graduate engineer with a minimum of three (3) years of engineering experience on petroleum fuel systems.

The project engineer must be responsible for the overall technical acceptability of all maintenance and repair performed under the contract in accordance with all applicable criteria referenced in Section 4. The project engineer must review and technically approve all Service Orders and Work Plans submitted under the contract. The project engineer must be employed by the prime Contractor. The project engineer must be approved by the Government, and any change in personnel must also be approved by the Government (14 calendar days prior, unless there are mitigating circumstances deemed acceptable by the Government). The Project Engineer is not required to be a full-time employee (FTE) dedicated to this contract and may have additional responsibilities either within or outside of this contract.

The Contractor must clearly identify who is responsible for this function and may not change their approach without KO approval.

1.5.6 Scheduler

The Contractor must designate a Scheduler who is responsible for the preparation of the schedule and all required updating and production reports. The designated scheduler must have two years of experience developing schedules for projects similar in size and type to this contract. The scheduler is not required to be a dedicated position, but the Contractor must clearly identify who is responsible for this function and may not change their approach without KO approval. The Project Scheduler is not required to be a FTE dedicated to this contract and may have additional responsibilities either within or outside of this contract.

1.5.7 Maintenance Manager

The Maintenance Manager must be responsible for the Contractor's overall approach for performing Preventive Maintenance activities required by this contract. This includes but is not limited to developing and documenting maintenance procedures as well as coordinating and scheduling maintenance events. The maintenance manager is not required to be an FTE dedicated to this contract and may have additional responsibilities either within or outside of this contract. The Contractor must clearly identify who is responsible for this function and may not change their approach without KO approval.

1.5.8 Safety Manager

The requirements for the Safety Manager can be found Appendix C, in Section 01 35 26 Governmental Safety Requirements. This position is considered to be critical to the successful performance of this contract. Prior to replacing the person proposed for this position, the Contractor must obtain written consent of the KO. In order to obtain such consent, the Contractor must provide advance notice (14 calendar days prior unless there are mitigating circumstances

deemed acceptable by the Government) of the proposed changes and must demonstrate that the qualifications of the proposed substitute personnel are generally equivalent to or better than the qualifications of the personnel being replaced. The Safety Manager must personally digitally sign all Service Orders on the SO form. The digital signature must include the date.

The Safety Manager must have no other duties within or outside of this contract and must be a full-time employee of the prime Contractor dedicated to this contract.

1.5.9 Site Manager

The prime Contractor must provide a minimum of two (2) Site Managers that are an employee of the prime Contractor. The Site Managers will be responsible for the Sites included in this contract. The Contractor shall designate Site Managers as follows:

Each of the two (2) required site managers shall be dedicated to their assigned group of sites. The physical location of the Site Managers must be considered so all duties and travel restrictions can be met with ease for each geographical Site indicated in this PWS. Additional site managers (if proposed) that exceed the minimum requirements can be shared as needed across all sites included in the contract.

The Site Manager(s) must be on-site during the following activities at the Sites under their responsibility:

- A. All Preventive Maintenance activities.
- B. During all medium and high complexity repair work.

The Site Manager(s) must perform the following tasks: oversee all prime and sub-Contractor activities, ensure compliance with all applicable construction codes, standards and local regulations, ensure on-site quality control, ensure on-site safety requirements are met, coordinate on-site logistics by direct communication with the FMSRs and other Government personnel, and be responsible for all on-site and Contractor controlled documentation. Site Managers must comply with the requirements as identified in UFGS 01 45 00.00 10 Quality Control.

The Site Manager(s) must have a minimum of five (5) years of experience in performing liquid fuels maintenance on various types of fuel systems that can include marine loading arms, bulk fuel facilities, hot pit fueling systems, gas station dispensing systems, cathodic protection systems, and leak detection systems. Three (3) years of experience must be Site Management or Construction Management experience.

Each Site Manager must be dedicated to their assigned group of Sites and the Contractor must identify Site Manager Site assignments. Each required Site Manager must be a full-time employee with no other duties outside this contract. Site Managers proposed in addition to the minimum requirements of this PWS may have duties outside of this contract, but all other requirements apply.

Prior to replacing the person proposed for this position, the Contractor must obtain written consent of the KO. In order to obtain such consent, the Contractor must provide advance notice 14 calendar days prior unless there are mitigating circumstances deemed acceptable by the

Government) of the proposed changes and must demonstrate that the qualifications of the proposed substitute personnel are generally equivalent to or better than the qualifications of the personnel being replaced.

1.5.10 Safety/SSHO/Safety Competent Qualified Individual

Reference Appendix C, Section 01 35 26 Governmental Safety Requirements.

1.5.11 Site Supervisor

The contractor must designate a site supervisor who will have a physical presence at the site during low complexity service order repair work. The Site Supervisor is not required to be an employee of the prime contractor. The site supervisor will be responsible for all repair related activities at the site and be responsible for reporting daily activities to the Site Manager. Site Supervisors must comply with the requirements as identified in UFGS 01 45 00.00 10 Quality Control. The QC Manager must maintain a list of approved Site Supervisors which may be requested at any time by the government.

The site supervisor must have a minimum of five (5) years of experience in performing liquid fuels maintenance on various types of fuel systems to include bulk fuel facilities, hot fueling fuel systems, gas station dispensing systems, cathodic protection systems, and leak detection systems. Three (3) years of experience must be supervisory experience.

Prior to replacing the person proposed for this position, the contractor must obtain written consent of the KO. In order to obtain such consent, the contractor must provide advance notice (14 calendar days prior unless there are mitigating circumstances deemed acceptable by the Government) of the proposed changes and must demonstrate that the qualifications of the proposed substitute personnel are generally equivalent to or better than the qualifications of the personnel being replaced.

1.6 Safety

The Contractor must comply with the latest version of U.S. Army Corps of Engineers (USACE) Safety and Health Requirements Manual 385-1-1 (EM 385-1-1), including any interim revisions, in effect at the time this solicitation is issued in addition to the requirements described in Section 01 35 26 Governmental Safety Requirements.

Confined space entry (CSE) may be required for some sites. Refer to the existing Facility Maintenance Plans in Appendix L.

1.7 Quality Control

The Contractor shall comply with Appendix C, Section 01 45 00.00 10 Quality Control.

1.8 Hours of Operation

Hours of Operation - All maintenance, repair, and testing services must be provided during the normal duty hours of each applicable Installation, excluding legal Federal holidays listed below or National Holidays (OCONUS). The Contractor must submit to the Government a written request to deviate from normal duty hours at least 14 calendar days prior to off-hour work.

Special allowance may be made for emergency response work. Below is a list of U.S. Federal.

New Year's Day
President's Day
Juneteenth
Labor Day
Veteran's Day
Christmas Day

Martin Luther King Jr.'
Memorial Day
Independence Day
Columbus Day
Thanksgiving Day

1.9 Additional Personnel Requirements

1.9.1 Conduct of Personnel

The KO may remove any Contractor or Subcontractor employee working under this contract for reasons of misconduct, security, or if any employee is found to be or suspected to be under the influence of alcohol, drugs, or other incapacitating agent. The Contractor's employees will be subject to dismissal from any Government Installation upon determination by the KO that such action is in the best interests of the Government. Such removal will not be the basis for a claim by the Contractor and will not relieve the Contractor of the requirement to provide sufficient personnel to perform the services as required herein. Refer to Appendix D for further security requirements.

1.9.2 Security Requirements

The Contractor's personnel or any representative of the Contractor entering the Installations where the job sites are located under this contract must abide by all security regulations of the Installation and will be subject to security checks. All prime and subcontract employees that will access a military Installation more than once every six months are required to secure a Common Access Card (CAC). Additional access requirements may apply, and the Contractor is responsible for complying with all Installation requirements. If anyone is to access the Installation network, then this must be identified in the CAC request and will require additional approval by the Installation.

1.9.3 Installation Access

The Contractor must comply with each installation's access requirements and as described in Appendix D. Government furnished identification must be returned to the Government within 14 calendar days of the employee ceasing to perform work for the Contractor under this contract.

1.9.4 Contractor Personnel Identification

Seven (7) calendar days after contract award, the Contractor must submit to the KO or their designated representative, in writing, the names, telephone numbers, and work assignments of the Contractor representative, alternate, management, and supervisory personnel scheduled to

perform work under this contract. The submission shall be included in the Contractor's Transition Plan, refer to Paragraph 1.25.1, include an organizational chart showing where the personnel fit in the organization and the lines of authority to the senior corporate officer who will make decisions related to this contract. The Contractor must comply with all requirements as described in Appendix D.

The Contractor must submit to the KO or his/her designated representative written list of employees who will perform work under this PWS. This list will include each employee's name, work assignment, training, certification, qualifications, and experience. Resumes must be submitted meeting all requirements of paragraph 1.5 and its subsections. The submission shall be included in the Contractor's Transition Plan, refer to paragraph 1.25.1.

The Contractor must submit in writing any changes in staff for Government approval 14 calendar days prior to implementation of the change.

1.9.5 Antiterrorism/Operations Security Compliance

The Contractor must comply with the requirements described in Appendix D Antiterrorism / Operations Security Compliance

1.10 Written Records

The Contractor must provide a written record of all conferences, meetings, discussions, verbal directions, telephone conversations, etc., with Government representative(s) relative to this contract in which the Contractor and/or a designated representative(s) participates. These records must be dated and must identify the contract number and the paragraph references, if applicable, participating personnel, subject discussed, and conclusions reached. Meeting minutes and verbal direction must be submitted via RMS CM as correspondence within five (5) calendar days of occurrence.

1.11 Maintenance Records

The contractor must create and maintain onsite maintenance records in support of fueling missions for each Site. These items are identified in the PWS Appendix G. The contractor is responsible for providing updates to existing Maintenance Records based on current conditions clarifying equipment, components, manufacturer information, inclusion of Component Unique Identifier (CUID), and other updates as required. The component unique identifier CUID, per Appendix F, must be inserted in the FMPs and on the upper right corner of the first page of component specific documents (manufacturer O&M requirements, cut sheets, warranty documentation, etc.). The contractor shall provide maintenance records of newly installed equipment, assemblies, and subassemblies. Compile, prepare, maintain, and aggregate into one Maintenance Binder all existing and new records to include all items indicated below.

The Maintenance Binder must include, but not be limited to:

- A. Date Log of Maintenance Binder update with FMSR digital signature validating date received. In the event no changes are identified during the maintenance visit, the updated maintenance binder must document that no changes were identified.

- B. Submittal Register
- C. Updates to the Facility Maintenance Plan to include all tabs.
- D. Operation and Maintenance Data as per UFGS 01 78 23.
- E. Guarantee/warranty on all equipment and materials furnished by the Contractor.
- F. As-Built Drawings or Schematics if provided by the Installation. The Contractor is required to update any provided as-built drawings or schematics to incorporate revisions due to work performed under this contract. As-built drawing and schematic updates will be completed by Service Order as required by the Government.
- G. All Preventive Maintenance reports including documentation of testing, calibration, and completed maintenance tasks for each facility asset identified in the FMP.
- H. Updated facility deficiency list with repair status.
- I. Preventive Maintenance Schedule to include dates, UFC frequencies (Q/SA/A), and QC Audits.
- J. Copies of all permits, certifications, and state inspection reports that are related to the execution of maintenance tasks of this contract.

~~Within 60 calendar days of completing each Initial Site Visit, the Contractor shall deliver initial Maintenance Binders—both digital (via government-approved electronic file transfer) and hard copy—to the FMSR and maintain them thereafter. The FMSR must digitally sign the delivery confirmation, validating receipt, and provide this signed receipt to CEHNC via RMS.~~

Maintenance Binders are living documents and serve as a repository of all maintenance activities performed throughout each contract year; a binder should be provided for each active contract year. If the 6-month extension is exercised, the Contractor shall update the maintenance binder using the final option year data. Binders – both digital (via government-approved electronic file transfer) and hard copy – must be updated and distributed to the FMSR within 30 calendar days after each preventive maintenance visit, component replacement with a new warranty item, or data update.

~~Within 30 calendar days after the Period of Performance (POP) end date for each contract year, final Maintenance Binders—both digital (via government-approved electronic file transfer) and hard copy—shall be provided to the FMSRs, containing all maintenance record files conducted throughout the contract year. Each FMSR confirms receipt of the final binders by providing a digital signature and date. Within five (5) calendar days of FMSR signature and no later than 45 calendar days after POP end date of each contract year, contractor shall submit Final digital binders and FMSR signed receipt to USACE HNC via RMS as part of the Transition from Base/Option Years and at Contract Closeout.~~

Maintenance binders must also be maintained and updated within the contractor's Computer Maintenance Management System (CMMS).

1.12 Site Specific Requirements

The Contractor must prepare and submit all documentation relating to the maintenance and repair of facilities and systems included herein that is required by any local, state, international, or federal regulation or regulatory body. All employees including Subcontractors must hold all applicable certifications for the work being performed. All required certifications must be submitted to the Government upon request. In some cases, fuel system assets may route through areas outside the strict confines of military installations. These are normally on leased land or through easements that would typically include but not limited to pipelines, high/low point drains, pits, and sumps that facilitate conveyance of fuel from one military site to another. There may be Preventive Maintenance and Corrective Maintenance requirements for these assets from time to time. As a result, there may be local government compliance and coordination requirements associated with this work.

Additionally, site specific requirements shall be recorded and updated in each sites Facility Maintenance Plan. Site specific requirements include but are not limited to, special considerations, local requirements, travel limitations, specialized equipment required, confined space entry, etc. All known site-specific requirements have been identified in each Site's FMP, located in Appendix L.

1.13 Contract Schedule

The Contractor must develop and maintain an overall Project Schedule, a Preventive Maintenance Schedule, and a Three-Week Look-Ahead Schedule.

1.13.1 Project Schedule.

The Contractor must develop and update an overall project schedule for maintenance and repair activities as well as all contract required deliverables and activities (i.e. ISVs, ISRs, FMPs, etc.) and maintenance and repair activities for all Sites. The initial schedule (which will be established as the baseline schedule) must contain all maintenance activities scheduled throughout the period of performance (PoP) for the contract (see below requirements for maintenance schedule). The project schedule must be separable by Service.

The project schedule must be updated on a monthly basis. Each maintenance visit to be conducted at each Site must be an activity on the schedule. Subcontractors must be identified with each activity. Schedules must be prepared using software products interoperable with Oracle Primavera or Microsoft Project.

The Contractor must submit the schedules for Government acceptance in accordance with Appendix C, Section 01 33 00 Submittal Procedures. Any changes to the schedule must be submitted as part of an updated schedule with changes clearly marked for acceptance by the KO or their designated representative.

The Contractor must provide updates with a variance measured in days between scheduled and actual performance. The Contractor shall provide a recovery plan as requested by the Government if the completion of Corrective Maintenances or Preventive Maintenance activities are behind the accepted schedule.

In the request for a PWS deviation, the Contractor shall provide a written explanation for any missed PM activities or events and the explanation must include the below items at a minimum.

Note that this does not remove the requirement to contact the COR immediately while onsite if maintenance cannot be performed. The Contractor shall notify the KO or COR, while onsite, of any PM tasks that cannot be performed due to access or any other issue.

- Reason for missed event and written documentation from the FMSR and CEHNC KO providing concurrence and approval for the missed event (PWS change).
- Date deductive Engineering Change Proposal (ECP) will be sent to CEHNC.
- Reschedule date if appropriate.

1.13.2 Preventive Maintenance Schedule

The Contractor must develop Site specific schedules for Preventive Maintenance, inspection, and testing activities to be conducted at Installations included in this contract. **The schedule must also include the anticipated QC Audits for each Site.** The schedules must specify Preventive Maintenance, **irregular maintenance tasks**, inspections, and testing requirements for petroleum fuel systems and related appurtenances in accordance with this PWS. **The Contractor must submit the initial Preventive Maintenance schedules to the Government for approval no later than seven (7) calendar days after the start of the Period of Performance (POP).**

The Contractor must perform Preventive Maintenance, **including irregular interval maintenance** according to the last applicable maintenance schedules for the locations included in this contract until final maintenance schedules are developed by the Contractor and approved by the Government. **Maintenance activities must occur regardless of the kickoff meeting, initial site visit, or facility maintenance plan.** The Government has provided the last applicable maintenance schedule (Appendix J). The Government will provide the latest maintenance report for each Site included in this contract and any updates to the maintenance schedules after award. **The Contractor must submit the final Preventive Maintenance schedules including irregular maintenance to the Government for approval no later than 14 calendar days after the start of the Period of Performance.**

The maintenance schedule must be coordinated with the FMSR to prevent mission degradation and to allow preplanning of fuels systems operation schedules. The Contractor will confirm work scheduling with the FMSR at least thirty (30) calendar days before the start of any work on the petroleum systems and must identify any needed Installation support or resources that are anticipated.

- The Contractor must provide a tentative schedule of maintenance activities to be performed while onsite. This must include petroleum fuel systems that will receive maintenance by day.

A follow up confirmation will be made 14 calendar days before start of work at which time the Contractor and FMSR should further discuss the tentative schedule of onsite maintenance activities. The Contractor must contact the FMSR by phone and via email for all coordination. A final notification to the FMSR prior to start of work be made within five (5) calendar days.

The Contractor must adjust their onsite schedule of activities to accommodate mission schedule and operations of the Installation. Documentation of this communication must be provided with the applicable daily report.

Mission schedule and operations availability can impact planned maintenance schedules. Governments fueling mission takes priority over performance of Preventive maintenance. The Contractor must develop their maintenance schedule and schedule of onsite activities to include flexibility for operations and mission schedule requirements.

The KO or their designated representative must be notified if adjustments in the schedule are required to accommodate Installation operational needs. Changes to the schedule that requires the maintenance to shift by more than one week must be submitted for Government acceptance prior to implementation.

The Contractor must accommodate each Site's existing Preventive Maintenance schedule when preparing the schedule. The Contractor must coordinate the maintenance schedule with the FMSR prior to submission to the Government.

The PM Schedule shall be reviewed in each bi-weekly project call with the Contractor and the CEHNC PM. Note that this does not remove the requirement to contact the COR immediately while onsite if maintenance cannot be performed.

1.13.3 Three-Week Look-Ahead Schedule

The requirements for the Three-Week Look-Ahead Schedule are provided in Appendix B, Reporting Requirements.

1.14 Reporting

The Contractor must provide required reports in accordance with the requirements of Appendix A Preventive Maintenance and Service Order Process Requirements and Appendix B Reporting Requirements.

1.15 Submittals

Submittal requirements are detailed in Appendix C, Section 01 33 00 Submittal Procedures. The Contractor must perform all tasks required by this specification section. Hard copies when required by the KO should be mailed to the following:

Agency:
US Army Engineering and Support Center, Huntsville
PO Box 1600
Huntsville, AL 35807-4301
ATTN: Project Manager

1.16 Computer Maintenance Management System (CMMS)

A Computerized Maintenance Management System (CMMS) is software designed to automate and streamline both preventive and corrective maintenance operations. The Contractor is required to provide such a database management system to manage all maintenance and repair

activities; acceptable examples include Maximo, Express Maintenance, or ECOBPM, but an Excel-type database is not considered a sufficient CMMS. While Excel may be utilized for minor reporting and tracking, it must not be relied upon as the overall maintenance management software. This system will maintain a maintenance database, service order database, track miscellaneous minor repairs, and manage corrective maintenance incidental to preventive maintenance, and must be fully operational and ready for use by the time of the first scheduled preventive maintenance (PM) visit.

1.16.1 Maintenance Database

The site visits outlined in the maintenance schedule will include actions to develop and maintain an electronic database encompassing inventory, maintenance requirements, deficiencies, and problem areas requiring corrective work. This database will also support updates to real property and facility asset inventory records. Information gathered from Preventive Maintenance, inspections, and tests will be used to schedule necessary maintenance and repair work through Contractor efforts. All findings from maintenance, repair, inspection, and testing activities will be recorded both electronically and manually as required by this Performance Work Statement (PWS). The Government reserves the right to request reports or other pertinent information from this database at any time during the contract period and may request unlimited/unrestricted access to the Contractor-developed database if requested reports or documentation are deemed unsatisfactory.

1.16.2 Service Order Database

To facilitate efficient tracking of maintenance activities, all Service Orders will be computerized using a Computerized Maintenance Management System (CMMS) as defined previously. This system will maintain, at a minimum, records of all minor/emergency repairs performed on specified equipment (including Government real property inventory information) at the designated facility, per Service Order. Records will be maintained throughout the duration of each order and transferred to the Government upon contract completion. The Government will also be granted unlimited/unrestricted access to the Contractor-developed database.

1.17 Resident Management System Contractor Module (RMS CM)

The Contractor must utilize RMS CM for all Administration, Schedules, Payments, Submittals, Correspondence, Requests For Information (RFIs), QC, and Reports. The Contractor must comply with all requirements in Appendix C 01 45 00.15 10 RMS CM. The Contractor may be required to use other RMS modules as directed by the Government. RMS CM must be used from the time of award throughout the life of the contract.

1.18 Permits and Licenses

Contractor is responsible for identifying, obtaining and renewing all permits from Federal, host nation, State, local, or Installation agencies to carry out the requirements specified in this contract or detailed on an individual order.

The Contractor and any applicable Subcontractors must meet all local, state, host nation, and federal licensing requirements to carry out the work specified in this contract or detailed on an

individual order.

The Contractor must maintain a list of Contractors and their applicable licensing. The Contractor must submit this information to the Government on a quarterly basis within RMS. Expiration dates must be tracked by the Contractor.

It is the Contractor's responsibility to follow and be in compliance with all permit requirements.

1.19 Operations and Maintenance Documentation

Operations and Maintenance documentation (e.g., facility drawings, equipment data, etc.), to the extent that such documentation is available, will be made available to the Contractor.

The Contractor shall be responsible for providing Operation and Maintenance Documentation per UFGS 01 78 23 Operation and Maintenance Data.

1.20 Accuracy of Government Furnished Information

The Contractor must verify all information provided by the Government including, but not limited to:

- A. Operation and Maintenance Information
- B. Facility Descriptions
- C. Facility Numbers
- D. Facility Location
- E. Facility Condition
- F. Available Utilities
- G. Equipment Lists
- H. Equipment Location
- I. Equipment Type
- J. Equipment Condition
- K. Preventive Maintenance Schedule

The Contractor must provide any updated information to the Government based on their verifications within 45 calendar days of completion of the Initial Site Visit.

1.21 Technical Library

The Contractor will provide and maintain a general technical library of all regulations and manufacturers' publications that apply to the equipment, system and accessories for the purpose of properly troubleshooting problems with each specific piece of equipment or system components. This information must be made available to the Government upon request.

The Contractor's library must be updated to include new or updated codes and standards as applicable. Changes to services due to updated codes and standards will be incorporated by contract modification as required.

A list of all documents contained in the library must be provided to the Government annually.

1.22 Payment Requests/Invoices

Payment requests must be prepared using RMS CM in accordance with Appendix C 01 45 00.15 10 RMS CM. A signed copy of the invoice must also be emailed to the USACE Inbox at: DESCInvoice@usace.army.mil

Contractors will submit their draft invoices with the contract # and delivery order # to the COR via email for pre-approval five (5) business days prior to the end of the month for review. If the government does not accept the draft invoice within five (5) business days – submit the invoice to the inbox for processing.

All invoices will be submitted to the DESC invoice inbox within the first seven (7) calendar days of each month for the previous month. A single Invoice is to be submitted monthly for each contract and include maintenance and Corrective Maintenance activities.

Service Orders invoiced must include all completed and signed Service Orders including FMSR dated digital signature verifying completion of work, if applicable. Maintenance activities being invoiced must include completed and approved reports per the PWS with Code "A" on the 4025 prior to submission to HNC. The Contracting Officer can request additional documentation to support invoiced amounts.

1.23 Warranty

The Contractor must provide a minimum of one (1) year warranty to cover all parts, materials, and labor for all work performed by the Contractor or Subcontractors. The warranty period starts the date of the FMSR acceptance of the completed work. Any request for warranty work must be issued by the KO. The Contractor is responsible for knowing which equipment and components are covered by the original warranty and the warranty duration.

Prior to performing any maintenance or repair work, the Contractor must report to the KO any defect in workmanship, material, or parts, and any improper installation of equipment and components that are covered by a warranty. The Contractor is responsible for knowing which equipment and components are covered by the original warranty and the warranty duration.

Following oral or written notification by the Contracting Officer, respond to warranty service requirements. Submit a report on any warranty item that has been repaired during the warranty period. Include within the report the cause of the problem, date reported, corrective action taken, and when the repair was completed.

Manufacturer's warranties on parts or equipment installed by this contract must be included and maintained as part of the Maintenance Records as required by the PWS. This requirement includes all equipment and materials with a warranty exceeding the Contractor's minimum one-year warranty. The provided information must be sortable by Installation/Site. The warranted

equipment list must include at a minimum:

- A. Item Name
- B. Model and Serial Number
- C. Location where installed
- D. Name and phone numbers of manufacturers or suppliers
- E. Names, addresses and telephone numbers of sources of spare parts
- F. Warranties and terms of warranty. Include one-year overall warranty, including the starting date of warranty. Items which have warranties longer than one year must be indicated with separate warranty expiration dates
- G. Cross-reference to warranty certificates as applicable
- H. Starting point and duration of warranty period
- I. Summary of maintenance procedures required to continue the warranty in force
- J. Cross-reference to specific pertinent Operation and Maintenance manuals
- K. Organization, names and phone numbers of persons to call for warranty service
- L. Typical response time and repair time expected for various warranted equipment

A warranty database shall be maintained and updated by the Contractor and provided to the Government in RMS quarterly.

1.24 Data Rights

The provisions/terms and conditions set forth in DFAR 252.227.7015 (November 2023), Technical Data – Commercial Products and Commercial Services shall apply to this award.

1.25 Contract Transition

1.25.1. Transition from Previous Contract

RESERVED

1.25.2. Transition between Base and all Option Years

RESERVED

1.25.3. Final Contract Year

The Contractor must provide the following Close-Out requirements for the Final Option Year:

- A. Changes from the Final Preventive Maintenance Schedule provided during transition – must show all PM during the Final Option Year.

- B. Service Order/Deficiency tracker – This tracker is a list of all Service Orders or deficiencies that will remain open and executed under the new contract. This will be discussed during the 90-Day Sync Meeting.

C. QC Audits

- D. Completed and updated Maintenance Records/Binders – this includes all documents per paragraph 1.11.

~~During the 90-Day Sync Meeting, the Contractor must develop a Service Order schedule, in consultation with the Government, that will be approved for execution prior to the Final PoP end. Contract Closeout. The Contractor must clearly indicate on the schedule the planned initiation, execution, and completion dates of Service Orders or deficiencies from the approved deficiency list.~~

~~Service Orders approved during the 90-Day Sync must be prioritized and validated for completion no later than 90 calendar days after Final PoP end.~~

The Contractor must complete invoicing for the Final Option Year within 60 calendar days of completion of the last Service Order. The Release of Claims must be provided with the final invoice.

1.26 In the event the Government exercises the optional 6-month extension period, the extension shall extend the last option year previously exercised by the Government. All terms, conditions, and pricing applicable to that last exercised option year shall remain in full force and effect during the extension period. Recurring and Scheduled Meetings with the Government

The Contractor must participate in the following meetings to update the Government on contract performance and to provide input on programmatic discussions. Other meetings are required as listed in the PWS or as directed by the KO.

1.26.1. Ninety (90) Day Sync Meeting

RESERVED

1.26.2. Rapid Improvement Event

RESERVED

1.26.3. Program Manager Visit

RESERVED

1.26.4. Bi-Weekly Meeting

A one (1) to two (2) hour meeting held every two (2) weeks by teleconference between the Government and the Contractor to discuss the ongoing activities of the contract. The Contractor's Project Manager, Service Order Manager or Project Engineer, and other staff as necessary must attend.

1.26.5. Monthly FMSR Meeting

A one (1) to two (2) hour meeting held monthly by teleconference to discuss any issues, concerns, or comments presented by the FMSRs and other Government staff. The Contractor's Project Manager, Service Order Manager or Project Engineer, and other staff as necessary must attend.

1.26.6. Program Manager's Meeting

A one (1) to two (2) hour meeting held monthly by teleconference to discuss programmatic issues, or concerns. The Contractor's Program Manager must attend.

1.27 Protection of Endangered and Threatened Species (Flora and Fauna)

The Contractor must not disturb endangered and threatened species and their habitat. The Contractor must carefully protect in-place and report immediately to the KO endangered and threatened species discovered in the course of work. The Contractor must stop work in the immediate area of the discovery until directed by the KO to resume work.

1.28 Government Facilities and Services

The Government will furnish or make available to the Contractor certain Government-owned facilities and utilities for use in connection with this contract. Workshop and administrative office space and utilities may be made available to the Contractor but is not guaranteed. The Contractor must provide all required workspace and utilities for their staff.

The Government will furnish water and electricity at existing outlets required for the work to be performed under the contract at no cost to the Contractor. Information concerning the location of existing outlets may be secured from the KO. The Contractor must provide and maintain, at its expense, the necessary service lines from the existing Government outlets to the worksite. Provide and maintain Contractor backflow prevention devices on connections to domestic water lines and electrical transformer provisions on Contractor connections to electric lines. Meet all Federal, State, local, and Installation codes and regulations for backflow prevention devices and electrical transformer provisions. Services required by the Contractor, for which there are no available Government outlets, must be provided by the Contractor at no cost to the Government.

If any utilities or other services must be discontinued (even temporarily) due to scheduled contract work, the Contractor must notify the KO, affected tenants, and customers. If the discontinued service is due to an emergency breakdown the Contractor must notify the KO, affected tenants and customers as soon as practicable.

1.29 Work Control

The Contractor must implement all necessary work control procedures to ensure timely accomplishment of work requirements, as well as to permit tracking and reporting of work in progress. The Contractor must plan and schedule work to assure material, labor, and equipment are available to complete work requirements within the specified time limits and in conformance with the quality standards established herein. Verbal scheduling and work status updates must be provided when requested by the KO. A status update of any item of work must be provided within two hours of the inquiry during regular working hours, and by 0800 the following workday for inquiries after regular working hours.

SECTION 2 – DEFINITIONS

The following definitions are provided for clarification:

Ancillary Equipment and Appurtenances: Any device including, but not limited to, piping, fittings, flanges, valves, and pumps used to distribute, meter, or control the flow of petroleum products to and from underground storage tanks (USTs) and aboveground storage tanks (ASTs).

Automotive Gasoline/MOGAS: Various product grades generally satisfying American Society for Testing and Materials (ASTM) D4814. NATO product designations F-46, F-57, and F-67 apply.

Building: A roofed and floored facility enclosed by exterior walls and consisting of one or more levels that is suitable for single or multiple functions and that protects human beings and their properties from direct harsh effects of weather such as rain, wind, sun, etc.

Class III Facility: Facility primarily used for bulk storage and distribution of fuel to other locations and/or to support aircraft fueling operations.

Contract Line Item (CLIN): Work will be ordered via order by negotiating firm-fixed quantities of each CLIN according to the estimated effort required to complete the task.

CONUS: Continental United States. Contiguous States and the 48 contiguous States and the District of Columbia.

Contracting Officer (KO): A person duly appointed with the authority to enter into and administer contracts on behalf of the Government.

Contracting Officer's Representative (COR): An individual designated in writing by the KO to act as an authorized representative of the KO to perform specific contract administrative functions within the (terms and conditions) of the contract. The COR cannot change or direct any work outside the scope of the contract. Only the KO can change any part of the contract relating to cost, scope, or schedule.

Contractor Quality Control Plan (CQC Plan): The Contractor's plan that describes in detail how their QC system will ensure that the work meets the requirements of the contract.

Corrective Maintenance: The restoration of a real property to such a condition that it may effectively be utilized for its designated purpose by overhaul, re-processing or replacement of constituent parts or materials that have deteriorated by action or elements or usage and that have not been corrected through maintenance.

Definable Feature of Work: An individual Service Order, or PM visit are examples of definable features of work.

Defense Federal Acquisition Regulation Supplement (DFARS): The Department of Defense supplement to the Federal Acquisition Regulation. It contains clauses which may or may not be included in the contract. Currently available at:
<https://www.acq.osd.mil/dpap/dars/dfarspgi/current/index.html>

Diesel Fuel: Various product grades generally satisfying ASTM D 975, and Commercial Item Description (CID) A-A-52557 for Post, Camps and Stations procurements. NATO product designation F-504 applies.

Department of Defense (DOD): The executive department of the Government responsible for the national defense of the United States.

Emergency: Per Department of Defense Manual Volume 8 (DODM 4140.25-V8) an emergency is an action required immediately to avoid a loss of mission critical capability, an imminent and substantial threat to human health and safety, or a violation of the law that could result in the assessment of fines or penalties.

Facility: A building, structure, or linear structure whose footprint extends to an imaginary line surrounding a facility at a distance of 5 feet from the foundation that, barring specific direction to the contrary such as a utility privatization agreement, denotes what is included in the basic record for the facility (e.g., landscaping, sidewalks, utility connections). This imaginary line is commonly referred to as the “5-foot line.” A facility will have an RPUIR received from the RPUIR and is entered into a Service RPI system as a unique real property record.

Federal Acquisition Regulation (FAR): The federal Government’s regulation for the execution of all federal acquisitions and purchases with Contractors and suppliers. It contains clauses which may or may not be included in the contract. Currently available at:
<https://www.acquisition.gov/browse/index/far>

Fuels Maintenance and Service Representative (FMSR): The FMSR will be an onsite employee, designated in writing by the KO, who will assist the Government in validating requirements and providing limited oversight of Maintenance/Repair activities.

Fuels Management Officer (FMO) or equivalent: The FMO is responsible for the safe and efficient receipt, storage, handling, issuing, and accounting of all aviation and ground petroleum products.

Hazardous Product: Product stored in an AST or UST that has a flash point not more than 60°C closed cup, or is subject to spontaneous heating, or is subject to polymerization with release of large amounts of energy when handled and stored without adequate control. The Contractor will exercise the necessary caution in working in that type of environment and will be required to use tools and instruments that are of the explosion proof, non-sparking type.

Installation: A base, camp, post, station, yard, center, homeport facility for any ship, or other activity under the jurisdiction of the Department of Defense, including any leased facility, which is located within any of the States, the District of Columbia, the Commonwealth of Puerto Rico, American Samoa, the Virgin Islands, the Commonwealth of the Northern Mariana Islands, or Guam. Such term does not include any facility used primarily for civil works, rivers and harbors projects, or flood control projects. In the case of an activity in a foreign country, an Installation is any property under the operational control of the Secretary of a MILDEP or the Secretary of Defense, without regard to the duration of operational control. For real property accountability, an Installation must consist of one or more real property sites.

Linear structure: A facility whose function requires that it traverse land (e.g., runway, road, rail

line, pipeline, fence, pavement, electrical distribution line) or is otherwise managed or reported by a linear UM at the CATCODE level.

Maintenance: Work required to preserve and maintain a real property facility or system in such condition that it may be used effectively for its designated functional purpose. Maintenance includes work done to prevent damage which would be more costly to restore than to prevent. Maintenance includes work to sustain components.

Notice to Proceed (NTP): Official Government authorization given by the KO to the Contractor to proceed with a specified portion of the contract.

Pipeline Facilities: New and existing piping, rights-of-way, and any associated equipment, facilities, or buildings.

Preventive Maintenance (PM): Routine, recurring sustainment work performed on all real property facilities. PM is systematic inspection, care, and servicing of equipment, systems, buildings, structures, and grounds facilities performed to detect and correct incipient failures and accomplishing minor maintenance.

Quality Assurance: The act by which the Government assures that the Contractor is following the approved quality control program. Quality Assurance is inherently a Government function.

Quality Control: The act by which the Contractor assures that he is following the requirements of the contract. Quality Control is inherently a Contractor function.

Restoration: In the facilities context, as opposed to the environmental context, repair and replacement work to restore facilities damaged by inadequate sustainment, excessive age, natural disaster, fire, accident, or other causes.

Real Property Inventory (RPI): A detailed record (listing, system) of real property lands, buildings, structures, and linear structures.

Real Property Unique Identifier (RPUID): A non-intelligent code used to permanently and uniquely identify a DoD real property asset.

Satisfactory: Performance meets contractual requirements. The contractual performance of the element or sub-element contains some minor problems for which corrective actions taken by the contractor appear or were satisfactory.

Service Calls: Work that generally does not require detailed planning and is normally accomplished on Service Orders.

Service Order Administrator (SOA): Duly appointed individual responsible for placing/approving in-scope (service) orders against sufficiently funded corrective maintenance Contract Line Items (CLINs) on an awarded contract. Must be appointed by a Contracting Officer (KO) and are not authorized to change the scope of work or negotiate contract price.

Service Truck: A service body upfitted truck, van, or truck/trailer combo that has a defined and inventoried set of parts, tools, and equipment for performing Preventive Maintenance and most common Corrective Maintenance actions. Only this type of truck would be eligible for mileage

reimbursement rates above the Joint Travel Regulations (JTR) rate. A technician using tradesman tools, kits, or parts for a specific repair in a company owned pick-up truck does not meet the definition of a Service Truck.

Site: Physical (geographic) location that is, or was owned by, leased to, or otherwise possessed by a DoD Component on behalf of the United States. Each Site (except for leased) is assigned to a single Installation. A Site may exist in one of three forms:

- Land only, where there are no facilities present and where the land consists of either a single land parcel or two or more contiguous land parcels.
- Facility or facilities only, where the underlying land is neither owned nor controlled by the Government. A stand-alone facility can be a Site. If a facility is not a stand-alone facility, it must be assigned to a Site.
- Land, and all the facilities thereon, where the land consists of either a single land parcel or two or more contiguous land parcels.

Sustainment: Facility maintenance and repair activities necessary to keep energy commodities in good working order over expected service lives.

Touch-Up Coating: A minor maintenance coating repair that can be performed using hand tools or simple power tools that will prolong the life of the equipment or facility and improves the appearance or finish.

Transportation Motor Pool (TMP) facility: A facility that houses vehicles that support the Installation, generally consisting of trucks, busses and vans. This facility usually has gas station-type pumps used to dispense fuel to general purpose and tracked vehicles.

SECTION 3 – MAINTENANCE AND REPAIR ACTIVITIES AND SUBMITTALS

3.0 Scheduled Maintenance Requirements

The Contractor must inspect, assess, repair, and maintain all equipment and systems at Government Sites and DLA capitalized petroleum facilities listed in Appendices I, K, and L per this PWS. Appendix I identifies the required frequency per site for PM.

Maintenance, repair, inspection, testing results, and inventory updates must be electronically and manually recorded and maintained as part of the Maintenance Records by the completion of each scheduled maintenance visit. A scheduled maintenance plan listing equipment and frequency of maintenance must be displayed at each facility.

Maintenance reports must be provided according to the requirements described in Appendix B Reporting Requirements.

The Contractor shall protect Government property during performance of this contract, in accordance with FAR 52.237-2, Protection of Government Buildings, Equipment, and Vegetation. Any damage to Government property resulting from Contractor negligence shall be restored to its original condition at no cost to the Government.

3.1 Facility Maintenance Plans

Contractor must update and maintain the Government provided Facility Maintenance Plans (FMP) in their entirety and implement as part of a detailed preventive maintenance plan. The FMPs must be at a component level that includes scheduled Preventive Maintenance and Corrective Maintenances related to recurring, periodic, and scheduled work on fuel systems to ensure their availability to receive, store, distribute and dispense fuel. FMPs may be found in Appendix L. Contractor shall convert the current FMPs to the most current version of the template provided after award. The Government reserves the right to modify the FMP format anytime during the execution of this task order if changes are proven to improve the documented approach and to request the contractor to utilize the most current version.

In addition to maintaining the FMPs, the contractor shall perform facility and equipment validation and verification of component inventory during the Initial Site Visit for all petroleum facilities, petroleum systems, and supporting DLA capitalized facilities, components, equipment, and systems in support of fuels delivery mission, regardless of whether PM activities are required for that equipment by this contract. Any variances in the Government provided FMPs must be captured within the updated FMPs. Annotate variances in component additions or deletions using red font and for any deletions in equipment, use strikethrough effect.

Submit FMPs for FMSR sign off on validity of components and any variances 30 calendar days after Initial Site Visit. FMPs must be approved prior to inclusion in Maintenance Binder. Prior to submitting FMPs for Government approval, each FMSR must provide proof of signature they have reviewed and agree with their sites FMP. FMPs must be provided to the Government via RMS as an excel workbook immediately after FMSR sign-off ~~but no later than 60 calendar days after Initial Site Visit~~. FMPs are a living document and must be updated as changes occur or upon request by the Government.

The Contractor will ensure maintenance activities are scheduled to prevent or minimize impact to operations.

3.2. Installation Status Report

RESERVED

3.3 Maintenance Tasks

Maintenance tasks are separated into Operator Maintenance (OM) and Systems Maintenance (SM). The Contractor must perform maintenance tasks in accordance with the most current version of UFC 3-460-03 and PWS Appendix G Maintenance Table marked with a responsibility of SM. PWS Appendix G Maintenance Tasks marked with a responsibility of OM are not performed under this contract unless otherwise specified in the Notes of the Maintenance Table. Maintenance frequencies for each site are identified in Appendix I of this PWS.

All required diagnostic inspections, tests/checks, calibrations, adjustments, and repairs must be performed as part of the Preventive Maintenance visit for which they are required. Multiple mobilizations for the same PM event are not allowed unless specifically approved by the KO.

- ~~The interval between quarterly maintenance visits must be between 80 and 100 calendar days.~~
- ~~The interval between semi-annual maintenance visits must be between 170 and 190 calendar days.~~
- ~~The interval between annual maintenance visits must be between 345 and 365 calendar days.~~

Consumables such as oils/lubricants, gaskets, nuts/bolts, filters, touch up paint/coatings, or other items required to complete the Preventive Maintenance task must be replaced as part of the associated task and included in the firm fixed price.

Labor, materials, travel, administrative support, waste disposal, and any other costs required to perform these tasks must be included in the firm fixed price.

The Contractor shall conduct an in and out-brief of the PM visit (prior to departing the site) and obtain a digital signature with date from the FMSR within 24 hours of PM event. The out-brief shall include a line-by-line review of deficiencies identified and/or corrected during the visit and must include before and after photographs of completed repairs. In brief/out briefs may be performed via phone calls if FMSRs are not available in person.

The Contractor shall provide a daily maintenance update to include anticipated crew start and stop times to the FMSR on activities completed and any activities which could not be completed with an explanation.

3.3.1. Preventive Maintenance Report

The report must be developed in accordance with the requirements of Appendix A, Preventive Maintenance and Service Order Process Requirements, and Appendix B, Reporting

Requirements, and must use the provided templates.

3.3.2. Back-up Power Generators Maintenance

Back-up power generator maintenance and repair will be provided under a Government approved Service Order as required unless a contract modification is done to include specific maintenance activities in the firm fixed price for Preventive Maintenance. If performed, the Contractor must follow all requirements listed on air permits while performing preventive maintenance on back-up power generators (e.g. logging motor run times).

3.3.3. Air Compressors

Permanently installed air compressors must be inspected, maintained, and tested according to the manufacturer's guidelines in addition to the following tasks:

- A. Drain the moisture from the tanks
- B. Clean intake vents
- C. Tighten all fasteners
- D. Check hoses

Manufacturer required maintenance activities more frequent than quarterly will be OM responsibility.

3.3.4. Pumps

Pumps must be maintained in accordance with any manufacturer's guidelines that are in addition to Appendix G Maintenance Tasks. Manufacturer required maintenance activities more frequent than quarterly will be performed by site personnel.

3.3.5. Meter Calibration

Meter Calibration must be performed at all sites in accordance with the most current version of UFC 3-460-03 and Appendix G Maintenance Table.

Sites that receive Annual PM only may choose to self-perform one meter calibration per year. These sites are indicated in Appendix I with a maximum frequency of "1".

Sites that receive Annual PM only and choose to have the Contractor perform the semi-annual meter calibration in accordance with UFC 3-460-03 are indicated in Appendix I with a maximum frequency of "1+MC". For those sites, no other semi-annual PM shall be required and the semi-annual meter calibration shall be priced in CLIN 2.

3.3.6. Detachable Pantographs (Mobile Pantographs)

There are no detachable pantographs that require maintenance for the sites identified in this PWS.

3.3.7. Fire Protection Maintenance Tasks

Fire protection system maintenance tasks shall not be priced at this time. These tasks may be modified into the firm fixed price maintenance after contractor gathers all information required from initial site visit to include types of systems and required Inspection, Testing, and Maintenance (ITM). Fire Protection maintenance and repair may be considered under a Government approved Service Order as required until contract modification is awarded.

UFC 3-601-02 Operation and Maintenance: Inspection, Testing, and Maintenance of Fire Protection Systems provides requirements for inspection, testing, and maintenance (ITM) of engineered fire protection features in DOD facilities. ITM shall be performed in accordance with this UFC, NFPA 11,

NFPA 13, NFPA 30, NFPA 30A, and other applicable codes.

3.3.8. Irregular Interval Maintenance Tasks

RESERVED

3.3.9. Fuel Piers and Wharves

There are no fuel piers or wharves that require maintenance for the sites identified in this PWS.

3.4. Corrective Maintenance Associated with Maintenance Activities

RESERVED

3.4.1 Corrective Maintenance Required by Preventive Maintenance

RESERVED

3.4.1.1 Joint Sealant and Crack Repair

RESERVED

3.4.2. Corrective Maintenance Incidental to Maintenance Activities (CMITM)

RESERVED

3.5. Service Orders

Corrective Maintenances that are not included in the requirements of 3.4 and its subsections may be performed through Government Approved Service Orders. The Service Order process and requirements for Service Orders are included in Appendix A. The Government FMSRs can submit Service Order requests at any time to maintain system operability, though the majority of Service Orders should be generated from the deficiencies identified while onsite for Preventive Maintenance.

3.5.1. Service Order Mobilization and Travel

All Installations/Sites included in this contract are located in one geographical region. Government reimbursement for any mobilization costs for service orders will be limited to travel within 350 miles of each Installation unless specifically authorized by the KO prior to travel. Airfare for sites will not be reimbursed unless specifically authorized by the KO. The Contractor will be evaluated on their approach to minimizing travel costs to each site. If regional subcontractors are not available or elect not to bid, the contractor will document this in the SO package (Bid Analysis Form).

Prime Contractor and subcontractor travel costs for Service Orders must be submitted for approval to the Government as described in Appendix A using the Government provided Travel Expense Report. The contractor will include a copy of the approved KO form with the TER form for approval.

Refer to Section 2 Definitions of a Service Truck authorized by this contract. Otherwise, all vehicles are subject to the JTR mileage rate.

The Contractor will be reimbursed for actual travel expenses and allowable taxes, fees, or excise/receipt tax applicable to the area in accordance with the FAR and JTR. The Contractor must submit all supporting documents and receipts as required in this PWS and by FAR 31.205-46 with the invoice. The Contractor must track the available funding and must provide the updated CLIN balance sheet to the PM/COR as part of the bi-weekly meeting.

Full time employees dedicated to this contract shall not be reimbursed for travel labor during business hours. Travel outside business hours must be justified by the Contractor and approved by the KO or SOA.

Travel expenses for the positions listed in Paragraph 1.5 Personnel Requirements will be reimbursed only in instances where the person is required to be onsite during performance of a Service Order by the PWS. This does not apply to Site Managers within their local commuting area.

SECTION 4 –APPLICABLE CRITERIA

4.0 Criteria

Maintenance, repair, and testing must meet the requirements of the latest version of the specified criteria, as in effect on the initial RFP date, and any other applicable criteria.:

A. Military Standards

- 1) MIL-STD 161-G, Identification Methods for Petroleum Product Systems Including Hydrocarbon Missile Fuels
- 2) DLA Manual 4140.25, Volume 1: Management of Bulk Petroleum Products
- 3) UFC 3-460-03, Operation and Maintenance, Maintenance of Petroleum Systems
- 4) AR 200-1, Environmental Protection and Enhancement, Chapter 4.5, Storage Tank Systems
- 5) ASTM D4057 (Sampling)
- 6) ASTM D4177 (Automatic Sampling)
- 7) EM 385-1-1, US Army Corps of Engineers Safety and Health Requirements Manual
- 8) UFC 3-190-06, Protective Coatings and Paints
- 9) UFC 3-460-01, Design: Petroleum Fuel Facilities
- 10) UFC 3-230-02, Operation and Maintenance: Water Supply Systems
- 11) UFC 3-601-02, Operations and Maintenance: Inspection, Testing, and Maintenance of Fire Protection Systems
- 12) UFC 3-600-01, Fire Protection Engineering for Facilities

B. U.S. Environmental Standards

- 1) Title 40, Code of Federal Regulations (CFR) Part 112, Oil Pollution Prevention (Spill Prevention, Control and Countermeasure Plan Rule)
- 2) 40 CFR Part 280, Technical Standards and Corrective Action Requirements for Owners and Operators of Underground Storage Tanks
- 3) State and local standards and regulations

C. Other applicable codes/criteria/regulations not specifically identified above, including:

- 1) 29 CFR Part 1910, Occupational Safety and Health Standards
- 2) NFPA 326-2015 Standard for the Safeguarding of Tans and Containers

- 3) NFPA 30, Flammable and Combustible Liquids Code
- 4) NFPA 30A, Automotive and Marine Service Station Code
- 5) NFPA 70, National Electrical Code
- 6) American National Standards Institute (ANSI) A.13.1, Identification Banding, Coding and Marking of Fuel Facility
- 7) ANSI/American Society of Mechanical Engineers (ASME) B31.3, Process Piping
- 8) ANSI/ASME B31.4, Liquid Transportation Systems for Hydrocarbons, Liquid Petroleum Gas, Anhydrous Ammonia, and Alcohols
- 9) American Petroleum Institute (API) 570, Piping Repair Code: Inspection, Repair, Alteration, and Re-Rating of In-service Piping Systems
- 10) API RP 500, Classification of Locations for Electrical Installations at Petroleum Facilities
- 11) API 510, Pressure Vessel Inspection Code: In-service Inspection, Rating, Repair, and Alteration
- 12) API RP 651, Cathodic Protection of Aboveground Storage Vessels
- 13) API RP 1110, Pressure Testing of Liquid Petroleum Pipelines
- 14) API Std. 2610, Design, Construction, Operation, Maintenance and Inspection of Terminal and Tank Facilities
- 15) Defense Energy Support Center, *Environmental Guide for Fuel Terminals*
- 16) API Standard 653, Tank Inspection, Repair, Alteration, and Reconstruction
- 17) API Standard 650, Welded Tanks for Oil Storage
- 18) NFPA 11, Standard for Low-, Medium-, and High-Expansion Foam
- 19) NFPA 20, Standard for the Installation of Stationary Pumps for Fire Protection
- 20) NFPA 22, Standard for Water Tanks for Private Fire Protection
- 21) NFPA 25, Standard for the Inspection, Testing, and Maintenance of Water-Based Fire Protection Systems
- 22) AWWA M17, American Water Works Association (AWWA) Manual for hydrants and monitors
- 23) 33 CFR 156.170 Equipment Tests and Inspections, Section (f)(1d)

SECTION 5 PERFORMANCE REQUIREMENTS SUMMARY

5.0 Performance

The Contractor will be evaluated in accordance with the below information.

5.1 Performance Evaluation – USACE

The Contractor will be rated on each individual performance requirement below and then will be given an overall performance evaluation for the contract.

A. Quality of Work

- 1) Satisfactory control of scope, schedule, execution, and costs must be demonstrated.
- 2) Implementation of Quality Control inspection process as defined in this PWS and the Contractor's Quality Control Plan.
- 3) Complete and adequate documentation.
 - a. Daily Report Summary is uploaded to RMS weekly unless daily uploads are directed by the Contracting Officer.
 - b. Preventive Maintenance reports are submitted as required by this PWS.
 - c. Inventory updates and Maintenance Records must be provided per the PWS.
 - d. Facility Maintenance Plans are complete and accurate.
 - e. Installation Status Report (ISR) are complete and include all fuel systems.
 - f. No more than 5 percent of total Service Orders sent back for correction (tracked under Out for Corrections) per performance period.
 - g. The Contractor must not receive significant customer complaints for more than 15% of PM events, or 10% of Corrective Maintenances executed within each performance period. The KO will make final determination whether complaints are significant.
- 4) Failure to identify, and correct deficient work
- 5) Adequate reviews of materials and shop drawings
- 6) Incorporation of specified or standard materials

B. Timely Performance:

- 1) Does the Contractor complete activities in a timely manner? This includes administrative activities such as submittal management, response to RFP's, etc.
- 2) Did the Contractor adequately schedule the work?
- 3) Has the Contractor met administrative milestone dates?

- 4) Has the Contractor met physical milestone dates specified by contract or agreed to in the project schedule?
- 5) If the schedule has slipped as a result of the Contractor's fault or negligence, has he taken appropriate corrective action of his own volition?
- 6) Has the Contractor furnished updated project schedules on a timely basis?
- 7) Has the Contractor submitted required subcontracting reports (SF 294 and SF 295) on time?

C. Effectiveness of Management:

- 1) Are the Contractor's on-site and home office management personnel exhibiting the capacity to adequately plan, schedule, resource, organize and otherwise manage the work? If not, describe and relate to other rated elements.
- 2) Is the Contractor complying with its subcontracting plan?

D. Compliance with Safety Standards:

- 1) Has the Contractor implemented an effective safety program; one which minimizes / mitigates potential accidents?

5.2 Performance Evaluation – Customer Feedback

The FMSR will be asked the following yes/no questions on each Service Order and will be provided with a Customer Feedback Survey for additional comments:

- A. Was the work performed in a quality manner?
- B. Was the work performed safely?
- C. Was work performed in a timely manner?
- D. Did the prime Contractor successfully manage the Subcontractor(s)?
- E. Did Contractor have all necessary certifications?
- F. Were there any issues with the work performed?
- G. Did Contractor arrive with all parts, materials, and tools needed to complete the repair?

Table 1: Assessment Items				
Requirement	CPAR Category	Standard	Government Inspection Goal	Allowable Deviation
Facility Maintenance Plan	Management / Quality / Schedule	FMPs must be submitted within timeframes required by PWS.	100% inspection	5% deviation allowed.
Preventive Maintenance Completion	Management / Schedule	100% of the Preventive Maintenance activities must be completed on time per approved schedule	10% onsite inspection of PM activities	Deviation allowed in the case of lack of site availability or Government delay
Installation Status Report	Management / Schedule / Quality	100% of ISRs completed on time.	100% inspection	5% deviation allowed.
Site Coordination	Management	100% Site contact in writing (typically FMSR) 30 calendar days in advance of work with a follow up 14 calendar days before work begins.	100% inspection	5% deviation allowed.
PM Schedule Deviation Communication	Management	100% KO or COR contact immediately in the case of schedule deviation.	100% inspection	5% deviation allowed.
PM Scope Deviation Communication	Management	100% KO or COR contact immediately in the case of scope deviation.	100% inspection	5% deviation allowed.
Preventive Maintenance Deficiency List	Quality, Management	100% of Preventive Maintenance Deficiency Lists submitted within 7 calendar Days of Completion of PM Events.	100% inspection	5% deviation allowed.
Preventive Maintenance Report Completion	Quality, Management	100% of the Preventive Maintenance reports must be submitted within time frames required by PWS.	100% inspection of PM reports	5% deviation allowed.

Emergency Repairs Response	Management, Schedule	100% of the emergency repairs must be responded to within the timeframe specified by the PWS.	Feedback may be obtained via CEHNC customer satisfaction survey, COR records or other government representative	No deviation is allowed for completeness or workmanship. Timeframe deviation is allowed for instances where lead time for materials, logistical difficulties, or work complexity extend the time needed to complete the repair.
Routine Repairs Completion		95% of the routine repairs must be completed within the identified allowable execution timeframes.	10% onsite inspection of low/medium complexity SO's 50% onsite inspection of high complexity SO's	No deviation allowed
Quality Control	Quality Control	95% of the tasks and deliverables required by the approved Quality Control Plan must be completed.	Submission of quality reports, and similar documents	No deviation allowed

Safety	Safety	Maintain high safety Standards. Zero Class A Safety violations where the Contractor is determined at fault.	Submission of accident reports, adverse safety inspection reports, and similar documents.	No deviation allowed. Issuance of a cure notice and possible termination of task order or contract for continuous or uncorrected performance deficiencies, or for failure to complete Performance -Based Milestones / Objectives.
Documentation	Quality Control, Safety	95% of the documentation required by the PWS is submitted as required.	Feedback may be obtained via CEHNC customer satisfaction survey, COR records or other government representative.	No deviation allowed. Issuance of a cure notice and possible termination of task order or contract for continuous or uncorrected performance deficiencies, or for failure to complete Performance -Based Milestones / Objectives.

Submission of Maintenance Records/ Binders	Management , Quality Control, Schedule	95% of maintenance binders provided within timeframe required by PWS	Feedback may be obtained via CEHNC customer satisfaction survey, COR records or other government representative	No deviation allowed
Invoicing	Cost Control, Quality Control	90% of PM activities are invoiced not later than 30 calendar days after PM report acceptance and 90% of CM activities are invoiced no later than 60 calendar days after completion with the exception of Emergency and NTE activities are invoiced no later than 60 calendar days after completed Service Order package approval.	100% inspection	No deviation is allowed
SO Timelines	Management, Schedule	Services orders are completed and executed within the performance metrics set by the PWS.	100% inspection	Deviation is set within the performance metrics.

Customer Satisfaction		Work performed without receiving significant customer complaints for more than 15% of PM events, or 10% of Corrective Maintenances.	Feedback may be obtained via CEHNC customer satisfaction survey, COR records or other government representative	No deviation allowed. All customer complaints must be addressed. KO makes final determination on whether complaint has been properly addressed.
------------------------------	--	---	---	---

All relevant information from the customer as well as information from USACE will be used to determine the Contractor performance evaluation.

Allowable deviation values listed in the table above do not remove the Contractor's responsibility for performing 100% of the work required by the PWS.

APPENDIX A

PREVENTIVE MAINTENCE AND SERVICE ORDER PROCESS REQUIREMENTS

**U.S. Army Engineering and Support Center
Huntsville, AL**

APPENDIX A – PREVENTIVE MAINTENANCE AND SERVICE ORDER PROCESS REQUIREMENTS

SECTION 1 – PREVENTIVE MAINTENANCE PROCEDURE REQUIREMENTS

1.0 General Process

- A. Contractor provides a Preventive Maintenance (PM) Master schedule per the PWS.
 - 1) The schedule is listed as a deliverable in the contract PWS.
 - 2) Schedule shall be separable by Service.
 - 3) The Contractor shall provide a variance (days) between scheduled and actual performance and indicate whether variance is in or out of contract requirement.
 - 4) Schedule date changes must be approved by the COR if outside the acceptable contract variance.
- B. HNC PM sends the schedule out to Department of Logistics Agency – Energy (DLA-E), the respective Service Control Point (SCP), and the Fuel Maintenance Service Representatives (FMSRs).
 - 1) HNC will review the schedule for acceptability.
 - 2) The PM schedule shall be reviewed in each project call with the Contractor and the CEHNC PM shall obtain a written explanation for any missed PM events which shall include:
 - a. Reason for missed event and written documentation from the FMSR and CEHNC Contracting Officer providing concurrence and approval for the missed event.
 - b. Date deductive ECP will be sent to Army Corps of Engineers Huntsville Center (CEHNC).
 - c. Reschedule date if appropriate.
 - 3) The Contractor shall not spread Annual, Semi-Annual, or Quarterly PM work beyond the scheduled dates of PM visit without Contracting Officer approval.
- C. Contractor notifies FMSR 30 calendar days before start of work and a follow up confirmation 14 calendar days before start of work. The Contractor shall notify the site in writing and ensure positive contact is made via a phone call and in writing for the initial and follow-up schedule confirmations.
- D. Contractor arrives at site to conduct Annual, Semi-Annual, or Quarterly Preventive Maintenance to include Corrective Maintenance s Associated with Maintenance Activities.
 - 1) The Contractor must provide a tentative schedule of maintenance activities to be performed while on site 30 calendar days before the start of any work. This must include facilities and systems that will receive maintenance by day
 - 2) A follow up confirmation will be made fourteen (14) calendar days before start of

APPENDIX A – PREVENTIVE MAINTENANCE AND SERVICE ORDER PROCESS REQUIREMENTS

work, at which time the Contractor and FMSR should further discuss the tentative schedule of onsite maintenance activities. The Contractor must contact the FMSR by phone and via email for all coordination.

- 3) The Contractor shall conduct an in-brief with the FMSR of all PM activities to be performed during that event. After PM has been completed, an out-brief with the FMSR prior to leaving the site shall include a line by line review of deficiencies identified during the visit and must include before and after photographs of any completed repairs. At this time, the FMSR and Contractor have the opportunity to combine like work with same priority level. The out-brief also includes concurrence or non-concurrence from the FMSR for each deficiency. Deficiencies identified by the FMSR shall be added to the deficiency list and coded as FMSR.
 - 4) The Contractor shall provide a daily report to the HNC PM and FMSR of all activities completed and any activities that could not be completed with an explanation. The daily report shall include the crew start and stop times with crew mix, all activities not completed for each day, and a list of any deficiencies identified and/or corrected while on site. Guidance on QC daily reports shall comply with UFGS Section 01 45 00 00.10 Quality Control.
- E. Stakeholder Group requirements – The Contractor shall prepare a deficiency list with findings on the Government provided Excel spreadsheets. The Contractor must not deviate from the Government provided spreadsheets unless prior approval from COR. Deficiency list signed by the FMSR must be provided within seven calendar days of completing the PM visit and as part of the Final PM Report.
- 1) The deficiency list shall include all items as identified in the Government furnished spreadsheet. Some items include: facility number associated with each deficiency, scoping information, level of complexity, priority number, Unique Identifier, ROM cost range (\$0-10k, \$10-25k, \$25k-\$50k, \$50k-\$100k, \$100k+), work plan request (with applicable justification), and notes.
 - 2) Corrective Maintenance Required by Preventive Maintenance (Firm Fixed Price) per PWS Paragraph 3.4.1 that were identified and corrected during an PM visit. The FFP corrections must be marked complete or note provided when repairs can be made.
 - 3) Corrective Maintenance Incidental to Maintenance Activities per PWS Paragraph 3.4.2 including subsequent paragraphs. Include balance sheet of each repair made across the contract year and balance sheet of each repair made per installation per year.
 - 4) A status log of all Service Orders (SOs) marked appropriately with complete, cancelled, out for corrections, hold, etc.
 - 5) Any critical items highlighted per the FMSR or Contractor.
- F. Within seven (7) calendar days of completing maintenance, Contractor sends out an email containing all findings in the Government provided Excel spreadsheet with applicable photos to the HNC PM. HNC PM submits deficiency list to stakeholders

APPENDIX A – PREVENTIVE MAINTENANCE AND SERVICE ORDER PROCESS REQUIREMENTS

for review.

- G. Stakeholder group approves deficiencies for Service Order development within 14 calendar days of findings and sends back to HNC for execution. Additional grouping of Service Orders may be requested by the Stakeholder group. HNC SO Desk assigns a Service Order Number to the deficiency and sends to the Contractor to develop repair packages. Work Plan authorization will be indicated on the Service Order. FMSRs will be copied on the final approved SO lists.

NOTE: DLA will communicate changes in approval policy to FMSRs and provide a copy of any relevant guidance to HNC for reference.

- H. Contractor initiates all SOs within the number of days listed in this PWS. FMSR/DLA-E are notified of submission. No further review will be needed from Stakeholder Group so long as Service Order repair stays within ROM price range.
- I. HNC approves Service Orders within 30 calendar days of receipt.
- J. Contractor completes repairs within priority level timelines from PWS.
- K. FMSR verifies the repairs were completed and signs SO package. Contractor routes completed SO package to HNC SO desk.
- L. Full PM Report shall be submitted to HNC in RMS 30 calendar days after completion of PM visit and must meet the requirements for PM Reports as defined in the PWS and Appendix B. HNC reviews within 14 calendar days.
- M. HNC provides PM report (Excel format) to DLA-E/SCP/FMSR to identify corrected and open deficiencies as well as Completed and Open Service Orders.

NOTE: The monthly report will track deficiency aging and scheduled PM events. Deficiencies may be corrected with fixed price line items or via SOs in the system.

APPENDIX A – PREVENTIVE MAINTENANCE AND SERVICE ORDER PROCESS REQUIREMENTS

SECTION 2 – SERVICE ORDER REQUIREMENTS

2.0 General

In reference to this contract, a Service Order (SO) is a document that is initiated and approved by the Government, requesting the Contractor to perform Corrective Maintenance work on federally funded petroleum systems/equipment at various Government installations and/or facilities covered by this contract. The Contractor shall provide all personnel, equipment, tools, materials, supervision, and all other services necessary to perform Corrective Maintenance tasks. The Contractor shall provide a proposed price on the initially submitted Service Order. The price/quantity/process for completing the Corrective Maintenance shall be subject to negotiations and the final price will be annotated on the Service Order. All Service Orders shall be considered firm-fixed price (FFP) agreements between the Contractor and the Government. All Service Orders shall be completed and submitted on the Government-approved Service Order form provided in Attachment 1 of this Appendix.

Service Order Types:

- A. **Routine Service Order** – A Routine Service Order (RSO) shall be submitted for non-emergency Corrective Maintenance as identified during the Preventive Maintenance Visit or as requested by the FMSR and as described in Paragraph 2.1. Submit RSO to CEHNC inbox: *serviceorders@usace.army.mil*
- B. **Long Lead (LL) Service Order** – A type of Routine Service Order as described in Paragraph 2.1.2. Submit LL SO to CEHNC inbox: *serviceorders@usace.army.mil*
- C. **Emergency Service Order** – An emergency Service Order shall be submitted for emergency repairs as requested by the FMSR and as described in Paragraph 2.2. Submit ESO to CEHNC inbox: <mailto:serviceorders@usace.army.mil>; [DLL-CEHNC-FuelsSafety@usace.army.mil](#) and [DLA-FuelsEmergency-NTE@usace.army.mil](#).
- D. **Not To Exceed (NTE) Service Order** – An NTE service shall be submitted if a site visit is required for troubleshooting in order to define the scope and price of a Routine Service Order or if the Contractor is already on site and a repair is requested by the FMSR. NTE SO price limit is at the Contracting Officer's discretion. Specific requirements are described in Paragraph 2.3. Submit NTE SO to CEHNC inbox: [serviceorders@usace.army.mil](#); [DLL-CEHNC-FuelsSafety@usace.army.mil](#) and [DLA-FuelsEmergency-NTE@usace.army.mil](#).

2.1 Routine Service Orders

A Routine Service Order (RSO) is any repair identified during the PM visit or requested from the FMSR that is for non-emergency repairs. During scheduled maintenance visits, the Contractor will identify any deficiencies/possible repairs. The Contractor shall include these deficiencies/repair requirements as outlined in Section 1. The Contractor must identify an assumed NTP date and provided a project completion date based on this date.

APPENDIX A – PREVENTIVE MAINTENANCE AND SERVICE ORDER PROCESS REQUIREMENTS

The FMSR can request a RSO at any time throughout contract duration. The intent is for the majority of Service Orders be originated from the PM Report allowing for proper planning of workload and approval with Stakeholder Group.

The Service Order package shall include at a minimum:

- A. Service Order Form with all cells completed as applicable. Refer to Service Order Form Attachment 1.
- B. Service Order revisions
- C. Task Complexity Determination Matrix
- D. AHA. Each Service Order shall have an AHA which has been approved by the Contractor Safety Manager.
- E. L1 and L2 resumes if not provided with the APP
- F. Specific safety plans
- G. Photos to aerial photos where applicable may be requested at the discretion of the government. The contractor will follow the installation's policy.
- H. Manufacturers Data. Manufacturers catalog cuts and specifications shall be submitted as applicable to document the materials to be supplied. Also, manufacturers' installation procedures or execution specifications shall be included as required to indicate the methods of installation of all materials. The Contractor shall use the manufacturer's data to tie together the shop drawings, catalog cuts, and installation requirements into a comprehensive package that defines the maintenance/repair action.

Service Order package may also include as applicable:

- I. Specifications. Specifications may be edited Unified Facilities Guide Specifications, industry specifications, or manufacturer's product data. Work plan narrative shall specify what specifications will be followed. This is subject to approval by the KO.
- J. Sketches/Schematics/Drawings. Sketches/schematics/drawings shall be submitted to show the detail, location, and relationship of all equipment and material. Maintenance/repair actions involving potential life safety hazards shall be overseen and signed off by a registered professional engineer experienced in the area of the maintenance/repair.
- K. Travel Expense Report submitted following process in paragraph 2.10.5. For NTEs and ESO the TER will be submitted with Service Order Package.
- L. Lock out Tag out
- M. Certificates, Permits, License, Qualifications
- N. Project Schedule (for all repairs exceeding 14 calendar days).

All labor, material, equipment, and/or service shall be included in the Service Order details prior to submitting Service Order for processing.

APPENDIX A – PREVENTIVE MAINTENCE AND SERVICE ORDER PROCESS REQUIREMENTS

Completed work shall be documented in RMS following UFGS 01 45 00 00.10 Quality Control.

FMSR signatures: For RSOs, the FMSR will sign the Deficiency List created during the PM visit validating the requirement. Interim deficiencies submitted by the FMSR will use the Service Order Initiation Form and be signed digitally. The Contractor shall not begin work until receipt of a notice to proceed (NTP) issued by the Contracting Officer (KO) or Service Order Administrator (SOA). Upon completion of the repair, the FMSR will sign the Service Order verifying that the Contractor has completed the repair.

2.1.1 Routine Service Order Prioritization

The FMSR is responsible for determining the priority of a Service Order while reviewing the PM Deficiency List based on the priority determination matrix below. The Government Stakeholder Group for each Service will make the final determination on changes to prioritization assignments. The Contractor shall not change the priority.

PRIORITY DETERMINATION MATRIX				
Instructions: FMSR should estimate the priority of the service order.				
This is meant to be a guide only. Final determination of priority will be determined by the Government Stakeholder Group. Provide justification for factors determined to be high priority.				
FACTOR	PRIORITY NUMBER			
	P1	P2	P3	P0
Level of Urgency	HIGH	MEDIUM	LOW	CRITICAL
Environmental Impact	CRITICAL	MARGINAL	NEGLIGIBLE	CRITICAL
Health and Safety Risk	HIGH	MEDIUM	LOW	CRITICAL
Mission/Operation Impact	> 75%	75% < X > 25 %	< 25%	CRITICAL
OVERALL PRIORITY OF SERVICE ORDER	[Priority Determination – Indicate P1, P2, P3, or P0]			
Justification:	[Only required for P1 and P0]			

Priority 1 (high) – Contractor shall submit the Service Order package within 18 calendar days of initiation and complete the Service Order within 30 calendar days after receiving Notice to Proceed (NTP). If other site visits are scheduled during this timeframe the Service Order can be performed during the same visit; however, for priority 1 Service Orders, the most important factor is time and the Service Order shall be completed as soon as possible.

Priority 2 (medium) – Contractor shall submit the Service Order package within 25 calendar days of initiation and complete the Service Order within 60 calendar days after receiving Notice to

APPENDIX A – PREVENTIVE MAINTENANCE AND SERVICE ORDER PROCESS REQUIREMENTS

Proceed (NTP). The Contractor should make every effort to combine Service Orders at a location or group of locations to complete Service Orders with one mobilization.

Priority 3 (low) – Contractor shall submit the Service Order package within 32 calendar days of initiation and complete the Service Order at the next possible PM visit, or at most within 120 calendar days after receiving Notice to Proceed (NTP). Note that the next possible PM visit could be two PM visits from the time of initiation depending on when the Service Order is initiated (e.g., the FMSR initiates the Service Order shortly before an PM visit). The purpose of the Priority 3 Service Orders is to perform the Service Order at an PM visit unless the site is only receiving annual recurring maintenance. In either case, the Contractor will have 120 calendar days to make every effort to combine Service Orders at a location or group of locations to minimize mobilization costs.

Priority 0 (critical) – Priority 0 can only be used for a follow-on repair related to an Emergency Service Order in the event an immediate permanent repair is not feasible, and a temporary fix has been executed under the ESO. The ESO shall be finalized upon completion of the temporary repair. Contractor shall submit the follow-on Service Order package within five (5) calendar days of receiving P0 service order number and complete the Service Order within 15 calendar days after receiving Notice to Proceed (NTP). If any parts are designated as long lead, then the Service Order must be executed within 15 calendar days after receipt of all parts. If other site visits are scheduled during this timeframe the Service Order can be performed during the same visit; however, for Priority 0 Service Orders, the most important factor is time and the Service Order shall be completed as soon as possible.

2.1.2 Long Lead Service Orders

A Long Lead (LL) Service Order is any RSO repair that cannot be completed within required performance timelines due to long lead time for materials procurement. The Contractor shall identify LL Service Orders with an “LL” on the Service Order form.

In the Service Order description section, the Contractor shall input the estimated time of arrival of the long lead item as applicable and provide a completion date for the Service Order.

All other review, approval, and execution parameters will be the same as a RSO.

2.2 Emergency Service Orders

Emergency Service Orders involve:

- Work that is mission critical (<50% capability)
- Work that is needed to avoid serious impact to life, health, or safety
- Work that is required to avoid or mitigate a negative environmental impact
- Work required to avoid or mitigate a Notice of Violation (NOV)

Upon receiving an emergency request, the Contractor shall gather as much information as possible from the FMSR and submit via email a Not-To-Exceed amount to perform the emergency repair. Contractor shall have the three approved safety submittal requirements – Accident Prevention Plan (APP), Site Specific Addendums (SSA), and Activity Hazard Analysis (AHA) – or approved interim APP, SSA, & AHA in RMS prior to ESO approval. For ESO requests submitted during the APP interim acceptance period, a site-specific AHA and any required site- specific safety plan shall accompany the ESO request. Required safety plans and

APPENDIX A – PREVENTIVE MAINTENANCE AND SERVICE ORDER PROCESS REQUIREMENTS

certifications must be current and complete. Specific submission requirements and approval validations may be addressed with HNC Fuels Program safety team. Contractors shall also have an approved Quality Control Plan or approved Interim Quality Control Plan in RMS prior to ESO approval. Specific submission requirements and approval validations may be addressed with HNC Fuels Project Engineers.

The email notification shall contain:

- A. Contract Number and Name (Region)
- B. CLIN being charged
- C. A statement should be annotated on the emergency service order indicating criteria and nature of the emergency as outlined above in Paragraph 2.2.
- D. Detailed description of emergency service order requested with contractor's mitigation plan to repair.
- E. Not-To-Exceed total with breakdown estimated cost of labor, material, equipment, and travel. An emergency service order shall be priced the same as a RSO. Additional breakdown may be requested by HNC SOA or PCO for more complex or larger service order request.
- F. Any applicable attachments e.g. Safety documentation, certifications, photos, supporting evidence, etc.

The email shall be sent to the designated 24-hour emergency emails below:

KO/Service Order Administrator: serviceorders@usace.army.mil; and DLA-FuelsEmergency-NTE@usace.army.mil.

Safety Manager: DLL-CEHNC-FuelsSafety@usace.army.mil

The Contractor SHALL NOT perform work until all safety documentation has been accepted by safety officer and approval to commence, either verbal or written, given by the KO or SOA.

When an emergency Corrective Maintenance need is identified, it will retain highest priority over any concurrent regular scheduled maintenance and repair work. In the event an immediate permanent repair is not feasible and a temporary fix is in place, the ESO will be closed. A new follow-on service order labeled Priority 0 will be submitted for processing within five (5) calendar days of Contractor receiving the service order number. RSOs with Priority 0 pose an ongoing, high risk for impact to mission readiness, health, safety, or critical property and will be reported on a weekly basis to stakeholders until work completion.

The KO or SOA may request additional engineering review for complex or high dollar ESOs. Any delays in approval due to additional requested reviews will be communicated to the FMSR and DLA-Energy for situational awareness.

APPENDIX A – PREVENTIVE MAINTENANCE AND SERVICE ORDER PROCESS REQUIREMENTS

CEHNC will communicate any changes in ESO status to other Government stakeholders.

Contractors shall not communicate status changes or any other change regarding ESO status to other Government stakeholders. This also applies to any delays due to funding issues.

The Contractor will be paid for emergency Service Orders under the firm-fixed price (FFP) Corrective Maintenance and emergency response CLIN of the Order. As soon as possible following an emergency repair, the Contractor must prepare a complete Service Order package for the emergency Service Order. The completed Service Order package shall follow RSO process except for travel. The Contractor will submit completed and approved Travel Expense Report for each laborer who traveled including all supporting documentation as required by FAR 31.205-46 Travel Cost. Contractor will only be reimbursed for approved lodging costs incurred and must provide receipts for any costs in excess of the limit outlined by the FAR. Failure to provide receipts will result in no payment.

The emergency service order fee shall be a flat rate fee. It shall not be a percentage. The emergency service order fee shall cover any costs associated with an emergency service order that are above and beyond what is generally covered in a routine service order. These costs include, but are not limited to, the contractor's toll free number, after hours monitoring of and fielding requests from installations, and any other overhead type costs that are associated with the emergency response. Travel and per diem to answer an emergency call are not included in the emergency fee.

The completed Service Order package shall also include daily photo documentation of the completed work along with descriptions. The package shall provide reference to the specific QC daily reports in RMS that apply to the work so that the reports can be reviewed as needed alongside the Service Order.

FMSR signatures: For emergency Service Orders, the FMSR will only sign the Service Order once verifying completion of the work.

2.3 Not to Exceed (NTE) Service Orders

NTE Service Orders shall be used for one of the following situations:

- Troubleshooting
- Corrective Maintenance s while Contractor is already on site

Contractor shall clearly denote whether they are onsite or not in the email notification to the NTE Service Order inbox.

2.3.1 Troubleshooting Service Orders:

Troubleshooting Service Orders shall be submitted for costs that will be incurred while identifying the scope of work for a repair request made by a site FMSR. Troubleshooting Service Orders are reserved for complex or undefined repair needs. The troubleshoot request must identify the Contractor's proposed completion date for the troubleshoot Service Order. The Government reserves the right to set a revised completion date, but the Contractor will be given an opportunity to revise their Service Order pricing and approach if the Government's required date is significantly shorter than that proposed by the Contractor.

APPENDIX A – PREVENTIVE MAINTENANCE AND SERVICE ORDER PROCESS REQUIREMENTS

Completed troubleshooting Service Order packages shall include a report of findings. This report should include recommended courses of action along with daily photo documentation and descriptions of the troubleshooting work.

The Contractor SHALL NOT perform work until all safety documentation has been accepted by safety officer.

2.3.2 Contractor On-Site

In the event that a repair is requested by the Government while the Contractor is already on site, the Contractor may submit a NTE for the repair.

The Contractor SHALL NOT perform work until all safety documentation has been accepted by safety officer. In the event that the repair cannot be performed within the NTE limit, the Contractor shall immediately notify the KO. The KO will determine if a RSO should be submitted for approval in accordance with Paragraph 2.1 of this Section or if an NTE increase should be approved. An NTE increase is at the discretion of the KO or SOA (depending on price and authority limits) only.

As soon as possible following the completion of the repairs, the Contractor shall follow up with a written Service Order including detailed price of any repairs made during the site visit as well as detailed information documenting the repair work is inherent to this contract. Completed Contractor on site Service Order packages shall include daily photo documentation of the completed work along with descriptions. The package shall also provide reference to the specific QC daily reports in RMS that apply to the work so that the reports can be reviewed as needed alongside the Service Order.

FMSR Signatures: For NTE Service Orders, the FMSR will only sign the Service Order once verifying completion of the work.

2.4 Response and Completion Times

Unless otherwise stated in the PWS, the response times shall be as follows:

	Normal Duty Hours		(Other Than) Normal Duty Hours	
Classification	Response Time	Completion	Response Time	Completion
Emergency	12 hours after notification from FMSR	72 hours after NTP from KO or OO	12 hours	72 hours
Routine – Priority 1	18 calendar days after Initiation	30 Calendar Days after NTP	Must be performed within Duty Hours unless requested by FMSR	
Routine – Priority 2	25 calendar days after Initiation	60 Calendar Days after NTP	Must be performed within Duty Hours unless requested by FMSR	

**APPENDIX A – PREVENTIVE MAINTENANCE AND SERVICE ORDER PROCESS
REQUIREMENTS**

Routine – Priority 3	32 calendar days after Initiation	120 Calendar Days after NTP	Must be performed within Duty Hours unless requested by FMSR
Routine – Priority 0	5 calendar days after Initiation	15 Calendar Days after NTP	Must be performed within Duty Hours unless requested by FMSR
Troubleshoot	TBD for each SO	TBD for each SO	Must be performed within Duty Hours unless requested by FMSR

The Contractor has responded to routine request when the Contractor has gathered all necessary information required to complete the Service Order and submitted a complete Service Order package to HNC.

The Contractor has responded to an emergency request when the Contractor has gathered all necessary information required to complete the Service Order and submit an NTE request to the KO/SOA.

The Contractor shall notify the Government upon completion of each Service Order.

In the event that the Contractor cannot meet the performance objectives listed above, the Contractor shall notify the Government immediately and provide justification and an estimated completion time. For RSOs notification can be provided on the Service Order form. The KO will provide approval for the delay if it is outside the Contractor's control and justifiable.

The Contractor shall identify the projected Service Order duration, in calendar days from NTP, for all Service Order submissions. This should be included on the Service Order form for Routine service orders and should be included in the initial Service Order request for NTE and Emergency Service Orders.

The Contractor must coordinate with the HNC PM to establish a response and completion time for each Service Order to be executed at logistically challenging locations as determined by the Government.

2.5 Service Order Stages

2.5.1 Initiation Stage

Initiation is defined as the number of days from when the Government requests the Contractor to develop the Service Order (start) until the Prime Contractor submits the Service Order to USACE (end). Service Orders shall be submitted within the response time requirements listed in the table below. Service orders initiated by the Government stakeholder group via the deficiency list process outlined in Appendix A Section 1.0 do not require a signed FMSR initial validation form, as the FMSR's signature on the deficiency list indicates their approval to perform the work.

2.5.2 Review and Approval Stage

Review and approval phase is defined as the time that it takes to process and approve a Service Order. If a Service Order is sent back for corrections, the additional time that the Contractor has

APPENDIX A – PREVENTIVE MAINTENANCE AND SERVICE ORDER PROCESS REQUIREMENTS

the Service Order is considered Out for Correction (OFC) and is added to the initiation phase. The Contractor has up to seven (7) calendar days to correct and resubmit OFC Service Order.

2.5.3 Completion Stage

Completion phase is defined as the number of days from the Service Order NTP to completion of work. Service orders shall be completed within the timelines described in Paragraph 2.4. A Service Order completion report shall be submitted in accordance with Appendix B. The COR should be notified immediately if completed Service Orders submitted for FMSR signature are not returned by the FMSR after seven (7) calendar days.

2.6 Service Order Process Requirements

2.6.1 Service Order Format

All Service Orders shall utilize the format in the Service Order spreadsheet. The SO spreadsheet will be provided after contract award.

The Contractor must convert all SO package documents to pdf files and create a pdf portfolio with all required signature documents and shall submit the pdf portfolio to the Government.

2.6.2 Service Order Numbering

Service order numbering format shall be XYZ-KTR-123, where “XYZ” is the site code, “KTR” is the Contractor’s three letter code, and “123” is the Service Order number

Emergency SOs will be annotated with an “E” at the end of the Service Order number (XYZ-KTR- 123E). NTE Service Order s will be annotated with an “N” at the end of the Service Order number (XYZ-KTR- 123N).

Corrected SOs shall be returned to USACE with a revision number. First revision will be annotated as: XYZ-KTR-123-REV1. Second revision will be annotated as XYZ- KTR-001-REV2. The Contractor is responsible for tracking the revision number.

The government reserves the right to adjust the service order numbering format anytime during the execution of this contract.

2.6.3 Service Order Facility Number Requirements

Multiple facility numbers may be submitted on a single Service Order and should be coordinated with the HNC PM prior to submission. This coordination can be via email or during bi-weekly meetings but should be discussed before submitting Service Order for approval through the Service Order Desk. The cost for the repairs at each facility shall be identified on the Service Order.

2.7 Database Program

The Service Orders shall be tracked by the Contractor using a database program. The database will maintain, at a minimum, all Corrective Maintenance and emergency services performed on specified equipment (to include Government real property inventory information) at the designated facility per Service Order. The Government will be allowed unlimited/unrestricted access to the

APPENDIX A – PREVENTIVE MAINTENANCE AND SERVICE ORDER PROCESS REQUIREMENTS

Contractor developed database.

2.8 Work Plan Preparation

When work plans are required (as determined by the Government) they must be submitted with the Service Order package.

Work plans are intended to highlight areas of concern or areas that need emphasis or additional detail for a specific task or that needs Government review. The intent of a work plan is not to provide a step-by-step procedure or instruction manual for the work to be performed.

Work Plans are not required for routine work and safety is not the only driving factor for submission. Refer to Paragraph 2.10.7 Task Complexity Requirement to determine when a Service Order requires a work plan and consider the below when requesting a work plan.

Generally required for:

- A. Complex coordination requirements
- B. Specialized or complex technical or execution requirements.
- C. Special Permits
- D. Efforts requiring detailed schedules or significant de-confliction efforts
- E. Abnormal conditions (i.e. flooding)
- F. Specialized testing
- G. Test reports (in some cases a test report may be all that is needed)
- H. Manufacturer or third-party involvement
- I. Submittals for high dollar items (conformance reviews)

Contractors are always responsible for the proper planning and execution of work in a safe and efficient manner in compliance with the contract and appropriate regulations and standards.

Labor and development charges must only be for the actual time spent developing and updating documents on a specific Service Order. Labor costs for full time employees dedicated to this contract and required to develop or review the work plan shall not be included in the Service Order. All other labor costs to develop a work plan may be considered. The Contractor must not repeatedly charge for the contents of a work plan that is standardized or copy and pasted from a previous project. The Contractor is encouraged to develop template or standardized work plan packages for work that is likely to be repeated throughout the life of the contract in good faith as a cost savings initiative.

Work Plan Review Meeting. The Contractor shall attend a work plan review meeting following the initial work plan submittal when specified or requested by the KO. The review meeting shall be used by the Contractor to resolve any technical comments or issues and shall be coordinated by the KO or their designated representative.

Each work plan submittal shall be submitted electronically along with the Service Order as a pdf portfolio in order to retain electronic signatures.

APPENDIX A – PREVENTIVE MAINTENANCE AND SERVICE ORDER PROCESS REQUIREMENTS

The material presented in each portfolio shall be presented in the order defined below. Each of the sections within the pdf shall be separated with labeled section tabs. Photos may be included in multiple sections.

- A. Table of Contents. (Not required on Low Complexity Service Order s)
- B. Scope of Work.
- C. Bid Analysis.
- D. Site Specific Addendum. The Service Order shall have the site-specific addendum to the APP for the site that work is to be performed.
- E. AHA. Each Service Order shall have an AHA which has been approved by the Contractor Safety Manager.
- F. L1 and L2 resumes if not provided with the APP
- G. Specific safety plans
- H. Lock out Tag out
- I. Certificates, Permits, License, Qualifications
- J. Site Investigation Report. A copy of the complete site investigation report shall be included.
- K. Work Plan Narrative. The narrative shall include detailed discussions of the work to be performed, all assumptions, photos, a list of specific codes and standards to which the maintenance/repair action will adhere, and all conclusions and recommendations. The Contractor shall indicate coordination with the installation for disposition of all removed equipment and materials.
- L. Asbestos/Lead Based Paint Abatement Plan. The work plan shall include the findings of the Asbestos/lead based paint survey and if applicable, a plan for abatement of any asbestos and lead based paint.
- M. Specifications. Specifications may be edited Unified Facilities Guide Specifications, industry specifications, or manufacturer's product data. Work Plan narrative shall specify what specifications will be followed. This is subject to approval by the KO.
- N. Manufacturer's Data. Manufacturers' catalog cuts and specifications shall be submitted as required to document the materials to be supplied. Also, manufacturers' installation procedures or execution specifications shall be included as required to indicate the methods of installation of all materials. The Contractor shall use the manufacturer's data to tie together the shop drawings, catalog cuts, and installation requirements into a comprehensive package that defines the maintenance/repair action.
- O. Sketches/Schematics/Drawings. Sketches/schematics/drawings shall be submitted to show the detail, location, and relationship of all equipment and material. Maintenance/repair actions involving potential life safety hazards shall be overseen and signed off by a registered professional engineer experienced in the area of the maintenance/repair.

APPENDIX A – PREVENTIVE MAINTENANCE AND SERVICE ORDER PROCESS REQUIREMENTS

- P. Repair Specific Schedule. The repair schedule shall define the timeline of all major activities required to implement the maintenance/repair action, including project phasing. The schedule shall be completed at a level of detail that allows both the Contractor and the facility personnel to understand each major task and phase associated with the maintenance/repair action. Each major task in the schedule shall be approved by facility personnel. The Contractor shall document the phasing required for the entire maintenance/repair action. The repair schedule shall define all equipment shutdown and re-activation dates and the use of any temporary equipment necessary to perform equipment shutdowns. The repair schedule shall be presented in a Gantt type chart using Microsoft Project.

2.9 Approval Authorities

The Contractor will be given Service Order approval by either a KO or a SOA depending on authority limits. The Contractor does not have authority to act upon direction of anyone other than a KO or SOA.

A signed Service Order by an approval authority (e.g., KO or SOA) is the Contractor's authority to proceed. Proper coordination must be made by the Contractor with the installation via the FMSR or designated Government representative prior to the Contractor entering the installation.

ONLY THE KO OR SOA HAS AUTHORITY TO DIRECT THE CONTRACTOR. DIRECTION FROM THE SOA MUST BE WITHIN THE SOA'S DELEGATED AUTHORITY. IF OTHER GOVERNMENT OFFICIALS ATTEMPT TO DIRECT THE CONTRACTOR, CONTRACTOR SHALL IMMEDIATELY NOTIFY THE KO OR SOA.

2.10 Service Order Pricing

2.10.1 General Service Order Pricing Requirements

All pricing must be included in the Contractor's SO package.

Cost of all miscellaneous consumable supplies including safety equipment shall be included in the Preventive Maintenance firm fixed price.

Consumable items that are to be used to directly support the Service Order and will not be utilized again may be priced separately on the Service Order. Fuel shall be priced according to US Energy Information Administration (EIA). Price according to the applicable region.

Service truck charges shall be included in the SO and, shall not exceed \$1 per mile driven, and shall indicate if driver is included. This Service shall also identify if multiple passengers are included. Rates above this limit must be negotiated and approved by the HNC KO with justification provided by the Contractor.

Rental equipment shall be included in the Contractor's SO package. Company owned equipment charges may not exceed published rental rates. Charges must be made at the daily, weekly or monthly rates that are the most economical to the Government.

Administration costs and other expenses related to the preparation of Service Orders will not be reimbursed if a Service Order is rejected or cancelled by the Government. Service Order

APPENDIX A – PREVENTIVE MAINTENANCE AND SERVICE ORDER PROCESS REQUIREMENTS

administration costs and other expenses shall only be reimbursed for Service Orders that are approved by the Contracting Officer or Service Order Administrator. In order to minimize impacts to Contractors, the Government is taking active steps to minimize the total number of Service Order cancellations.

The contractor is obligated to ensure that all material acquisitions undertaken by either the prime contractor or subcontractor comply with the stipulations of the Buy American Act. Signing the SO Package will indicate compliance with these requirements.

2.10.2. Service Order Fee

The contractor shall submit a service order fee in the form of a fixed percentage for each service order. This fee shall apply to all service orders submitted under the awarded task order. The service order fee shall include all prime contractor costs associated with the service order including, but not limited to:

- a. Service order preparation
- b. Service order handling/submission/correction
- c. Subcontractor coordination
- d. Overhead and Profit

The service order fee shall NOT include the cost of the following items:

- a. Work plan development (when approved by the KO)
- b. Emergency service order fee

*Note –ALL prime contractor costs associated with the service order shall be included in the service order fee. The prime contractor service order fee shall be applied to the total subcontracted costs, prime contractor material costs, and on-site prime contractor labor cost. This means the contractor can self-perform the service order and still apply the SO fee to their own labor. The service order fee will not be applied to travel and tax. Labor shall be fully burdened.

Below is a table of how the SO fee will be applied.

APPENDIX A – PREVENTIVE MAINTENCE AND SERVICE ORDER PROCESS REQUIREMENTS

Prime Labor		\$1,000.00
Prime Materials/Equipment/Other		\$5,000.00
Tax (MSE) <i>(example percentage)</i>	5%	\$250.00
Subcontractor Cost		\$300.00
SO Fee (Labor, MSE, Sub) <i>(example percentage)</i>	15%	\$945.00
ESO Fee (\$250) <i>(example Fee)</i>		\$250.00
TOTAL		\$7,745.00

Note that 15% SO Fee and 5% Tax are arbitrary percentages used only for illustrating how the service order fee will be applied.”

2.10.3 Competition Requirements

The contractor shall demonstrate compliance with FAR 52.244-5 Competition in Subcontracting. All routine service orders which have a subcontracted effort and the subcontracted effort is greater than the micro-purchase threshold should have a minimum of 3 quotes for the subcontracted work. The contractor shall use the Appendix A – Attachment 3 Subcontractor Bid Analysis form to document quotes.

2.10.3.1 No Bid from Subcontractors – In the event that a subcontractor elects to not bid on a service order the contractor shall document their effort to solicit from the subcontractor. Documentation shall include bid request date, subcontractor name, contact information (phone and email), date of response, reason for not bidding, confirmation that the subcontractor received all necessary information to prepare a bid. Additionally provide a signature or initial from the subcontractor if obtainable.”

2.10.3.2 Best Value – If the lowest proposed price is not selected the contractor must justify a best value determination taking into consideration price, technical capability, or other applicable factor.

2.10.3.3 Bid Analysis – For the purposes of this agreement, a "viable quote" is defined as either: (1) a complete bid with a detailed breakout of labor, material, equipment, and markup; or (2) a bid that is not an outlier, meaning it does not exceed 10% of the average of the two other closest bids received.

If the contractor receives only one viable quote, as defined above, the contractor must provide a bid analysis. This analysis should include supporting documents such as competitive quotes, estimating software outputs and supplier or catalog pricing using the Appendix A Attachment 3 Subcontractor Bid Analysis Form.

2.10.3.4 Quotes from Subcontractors – The contractor shall include the quotes from the subcontractors in the service order package using Appendix A Attachment 3 titled Subcontractor Bid Analysis Form. Additional breakdown of costs shall be provided to the government if requested by the contracting officer or his/her designated representative. Subcontractor quotes must be typed signed and submitted on company letterhead.

APPENDIX A – PREVENTIVE MAINTENANCE AND SERVICE ORDER PROCESS REQUIREMENTS

2.10.3.5 NTE and Emergency Service Orders – Competition between three subcontractors is not required; however, in lieu of such competition, a bid analysis as outlined in paragraph 2.10.3.3 must be provided with the final Service Order (SO) package.

2.10.3.6 Self-Performance – For any service order containing any single material or equipment cost totaling over the \$3,500.00 (not including tax, shipping, and handling), the contractor shall attach three (3) manufacturer/supplier price quotes.

Note: The terms of the contract requires competition to be utilized anytime the prime contractor subcontracts work.

2.10.4 Contractor Price Certification

The pricing submitted on each service order shall be approved and certified by an authorized representative of the contractor. Individuals authorized to approve pricing shall be listed within the contractors Quality Control Plan or otherwise designated in writing. The contractor certifying official shall sign the service order prior to submission to the government signifying an official price proposal for the service order.

Only onsite labor and labor associated with work plan development shall be charged on Service Orders. All other labor associated with Service Orders shall be included in the firm fixed price.

2.10.5 Travel Cost

Travel Costs include transportation, lodging, meals, and incidental expenses. Travel Costs incurred by Contractor personnel on official company business are allowable subject to the limitations contained in FAR 31.205-46 unless otherwise restricted by this PWS.

Costs for transportation may be based on mileage rates, actual costs incurred, or on a combination thereof, provided the method used results in a reasonable charge. Costs for lodging, meals, and incidental expenses may be based on per diem, actual expenses, or a combination thereof, provided the method used results in a reasonable charge.

Travel within the local commuting area (50 miles) will not be reimbursed.

Estimated travel costs for emergency and NTE Service Orders shall be identified in the ROM cost provided to the SOA during initial request.

The Contractor shall bill for actual travel costs and allowable taxes, fees, or excise/receipt tax applicable to the area in accordance with the FAR and JTR against the Corrective Maintenance CLIN (CLIN 4). The Contractor shall provide all receipts and documentation required to demonstrate the actual costs as part of the invoice package. Invoices with incomplete or unclear travel costs will be rejected.

The Contractor shall perform RSO work on as many Service Orders as practical during each site visit to minimize travel. Bundling of SOs is encouraged to the greatest extent possible while meeting the applicable completion requirements to realize any potential cost savings measures.

APPENDIX A – PREVENTIVE MAINTENANCE AND SERVICE ORDER PROCESS REQUIREMENTS

Travel costs shall not be included on a RSO and will follow the process as outlined below:

A. Travel Costs include transportation, lodging, meals, and incidental expenses. Travel Costs incurred by Contractor personnel on official company business are allowable subject to the limitations contained in FAR 31.205-46 unless otherwise restricted by this PWS.

B. Contractor shall submit an estimated Travel Expense Report for each laborer traveling to include all travel costs and travel labor as indicated in Appendix A, Attachment 2. Submit the estimated travel costs and travel labor through the Service Order desk. All Information located on the Travel Expense Report must be provided; incomplete forms will be returned for resubmission. Service Orders must be approved prior to submitting TER for approval.

C. When submitting a travel estimate, Contractor will assign a tracking number. Naming shall be as follows:

Contract Phase-Contractor Identifier-Number.

Example: **XXX-KTR-0001.**

D. The Service Order desk will forward travel estimate to the SOA who is responsible for approving/disapproving the travel request. Service Order desk will deduct the estimated value from the CLIN tracker.

E. Contractor will receive authorization from the SOA to travel.

F. Contractor will mobilize to site and complete the work.

G. Any changes to the estimated travel shall be resubmitted for approval following the steps above. Contractor shall indicate any changes from the initial approved estimate on the revised Travel Expense Report for each laborer.

H. The Contractor will submit with invoice the approved estimated and approved revised Travel Expense Report for each laborer traveling including all supporting documentation as required by FAR 31.205-46 Travel Cost. *Note: Contractor will only be reimbursed for approved lodging costs incurred and for any travel costs exceeding the FAR regulation with a receipt. Failure to provide receipts will result in no payment.

In order to include travel in the invoice, the SO worked during the travel must be completed and validated by the FMSR.

2.10.6 Complexity

The Contractor shall initially suggest the level of complexity and it shall be designated on the PM Deficiency List. The Government will make the final determination of complexity and the Contractor will be notified when the SO is initiated. Quality Control Complexity will comply with UFGS 01 45 00.00 10 Quality Control.

2.10.7 Task Complexity

APPENDIX A – PREVENTIVE MAINTENANCE AND SERVICE ORDER PROCESS REQUIREMENTS

For Service Orders that are generated based on FMSR requests, each SO will have a separate tab with the following matrix which shall be filled out by the Contractor:

TASK		Impacts			Complexity Rating
	Likelihood	Minor	Moderate	Major	
Coordination with other trades, other contractors, customer, owner/operators, or regulatory	Unlikely	0	1	3	
	Moderate	1	2	3	
	Likely	2	3	3	
Technical complexity of equipment being serviced.	Unlikely	0	1	3	
	Moderate	1	2	3	
	Likely	2	3	3	
Required fuel system outages or outages of supporting utilities	Unlikely	0	1	3	
	Moderate	1	2	3	
	Likely	2	3	3	
Level of unknowns or undefined conditions	Unlikely	0	1	3	
	Moderate	1	2	3	
	Likely	2	3	3	
Logistical difficulty accessing the site or obtaining materials	Unlikely	0	1	3	
	Moderate	1	2	3	
	Likely	2	3	3	
OVERALL COMPLEXITY RATING	0				
Low = 1-5					
Moderate = 6-10					
High = 11-15					

Final determination of complexity as well as what is required to be included with each Service Order is up to the KO or designated representative.

2.10.8 Task Complexity Requirements

After the level of complexity has been determined by the Government, the Contractor shall utilize the table below when determining what to submit with each Service Order package. This is meant to be a guide only. Final determination of complexity as well as what is required to be included with each Service Order submission will be determined by USACE.

Required Content	*Complexity		
	Low	Medium	High
Scope of Work	Yes	Yes	Yes
Estimated Duration in Calendar Days	Yes	Yes	Yes
Pictures	Yes	Yes	Yes
Cost Proposals	Yes	Yes	Yes
SSAPP	Yes	Yes	Yes
AHA	Yes	Yes	Yes
Manufacturers Data	A/R	Yes	Yes

APPENDIX A – PREVENTIVE MAINTENANCE AND SERVICE ORDER PROCESS REQUIREMENTS

WORK PLAN REQUIRED FOR MEDIUM AND HIGH COMPLEXITY			
Table of Contents		Yes	Yes
Work Plan Narrative		Yes	Yes
Sketches		Yes	Yes
Detailed Drawings		A/R	A/R
Project Specific Schedule		A/R	Yes
Specifications		A/R	Yes
Project Specific Quality Control Plan		A/R	A/R
Work Plan Review Meeting/Pre-Con		A/R	A/R
Site Investigation Report		A/R	A/R

* A/R = As Required by Government

The Government reserves the right to add or remove Work Plan package requirements as needed.

Attachments to Appendix A:

Attachment 1: Service Order Form

Attachment 2: Contractor Travel Expense Report

Attachments 3: Subcontractor Bid Analysis Form

Appendix A Attachment 1 Service Order Form

PRIME CONTRACTOR

PART I - SERVICE ORDER INFORMATION

SERVICE ORDER NUM.:

CONTRACTOR:

SUB-CONTRACTOR(S):

FACILITY NUM./NAME:

SITE CODE/SITE NAME:

SERVICE ORDER SUBMISSION DATE:

Expected Deliver Date of LL Item:

Notice of Violation Related?

Is the SO related to Natural Disaster?

CM/MTA Used: (Yes/No):

XYZ-KTR-100

REV #

Contractor Name

Sub-Contractor Name

4302

4303X

72-403

TEXTBA47

8865

9777

8888

9889

4300

STOR JET F1

EXAMPLE NAME 2

3P-B Fuel Tank

Terminal 2

Terminal 3

Terminal 4

Terminal 5

Plan 3-F

Site Name

Does SO Include Long Lead Items?

Expected Start Work Date:

No

29-Apr-21

No

No

COMPLEXITY:

Low

ITEM(S) USED:

JOINT SEALANT/CRACK REPAIR

Service Order Type:

CONTRACT NUMBER:

DLA Work Type Category or UFC Section Ref Work Cat.

SERVICE & PHASE:

FUNDING CLIN:

MAINTENANCE CATEGORY:

UFC REFERENCE:

CUID:

DOB-4302-CENPT-0002

DOB-4302-41-FMT-0002

DUID:

LRUD

Work Plan Required (Yes/No):

No

SO Priority Level:

P2

CONTRACT CM/MTA QUANTITY:

800 LF

SO QUANTITY TOTAL:

200/800 or 900/900

0004AA

Air Compressors

Contract #

Air Compressors

Air Force

SAD-AF2

PART II - SERVICE ORDER SAFETY INFORMATION

TOSM NAME:

REQUIRED SHO LEVEL:

JUSTIFICATION FOR LEVEL OF SHO:

QUALIFIED/COMPETENT PERSON'S NAME:

ANY NEW PLANS REQUIRE SAFETY REVIEW?

ANA Attached

LIST INCLUDED PLANS (SEE EM385-1-1 APPENDIX A):

John Doe

L2 - Dual Hoisted Safety

TEST

John Doe

Yes

No

JOBSITE SHO NAME:

SHO PROOF OF QUALIFICATION?

OPICP PROOF OF QUALIFICATION?

ALL AHAs ARE PREACCEPTED?

John Doe

Included in SO

Included in SO

Yes

LIST INCLUDED AHAs:

No

By signing below, I certify that I have reviewed the safety documents for this service order and they meet all contract, OSHA, and regulatory requirements.

TASK ORDER SAFETY MANAGER SIGNATURE: (MUST BE SIGNED AND DATED)

Service Order Revision Log: Add Drop Down for Rev #

Description:

Date:

SO DESCRIPTION:

Replace PRT Pump/Motor Assembly - CUID: ROB-4302-CENPT-0002 & ROB-4302-ELEMT-0002.

Per the FMGR, the PRT pump/motor assembly for Tank #23 (FAC 4302) requires replacement. It has been noted that the motor is defective as well as the pump.

As to replace the defective pump/motor assembly. A qualified electrician will be present for all efforts to make electrical disconnects and final terminations as required. Work will be IAW NFPA 780 article 500.

MORE INFO

MORE INFO More and Better info.

PART III - SERVICE ORDER PRICING

Contractor Safety Manager

E-SIGNED & DATED

CONTRACTOR (Project Manager):

E-SIGNED & DATED

CONTRACTING OFFICER OR SOA:

Fair and Reasonable - FAR 15.404-1 Technical Analysis

Fair and Reasonable - FAR 15.404-1 Price Analysis

E-SIGNED & DATED

TOTAL COST OF SERVICE ORDER:

\$108,955.00

Labor Category / Description: Confirm All Rates are in Accordance with TO Proposed Rates.

City Superintendent - 1-50 hr day

Doing Work

PRIME FULLY BURDENED LABOR

TOTAL MH

HOURLY RATE

TOTAL COST

10.00

\$100.00

\$1,000.00

5.00

\$17.75

\$88.75

Labor Sub-Totals

\$

1,088.75

Item Description

Item Description

Manufacturer

Man. Part No.

Vendor Part No.

Catalog/Vendor

Catalog #

Vendor Price

PRIME MATERIAL/EQUIPMENT/OTHER

QTY.

UNIT COST

TOTAL COST

Pump/Motor Assembly

R S Corcoran Co.

3000 D (A405)

R S Corcoran Co.

\$5,000.00

2.00

\$5,000.00

\$5,000.00

10.00

\$600.00

\$6,000.00

PRIME Material/Equipment/Other Sub-Totals

\$11,000.00

Subcontractor(s) Name/Task:

Subcontractor A - Remove Defective Pump/Motor Assembly

Something Cost but Not Cheap

And Thing

Subcontractor Total Cost

\$100.00

\$4,000.00

\$0.17

Subcontractor Sub-Totals

\$8,100.17

Travel (NTE's/ESOs Only):

Travel A

Travel B

Travel C

Travel Total Cost

\$800.00

\$11.30

\$87,000.00

Travel Sub-Totals

\$87,811.30

Prime Labor

Prime Materials/Equipment/Other

Tax (MSE) (example percentage)

Subcontractor Cost

Travel Cost

SO Fee (Labor, MSE, Sub) (example percentage)

ESO Fee (S1) (example Fee)

TOTAL

1%

2%

\$1,088.75

\$11,000.00

\$550.00

\$8,100.17

\$87,811.30

\$403.78

\$1.00

\$108,955.00

APPENDIX A - ATTACHMENT 2 - TRAVEL EXPENSE REPORT

CONTRACTOR TRAVEL EXPENSE REPORT

Travel Expense Report						
Travel Request Number: <i>XXX-KTR-0001</i>				CLIN:		
Travel From:				Contractor: <i>Prime or Sub Name</i>		
Travel To:				Labor Category: <i>Foreman, Fuel Technician, etc.</i>		
Date	Description of Expense	Unit Cost	Quantity	Miles	Mileage Reimbursement	Total Cost
	Air Fare From/To					
	Travel Labor					
	Luggage Fee					
	Terminal Parking					
	Ground Transportation (Rental Car, Taxi, Uber, Lift)					
	Fuel for Rental Car only					
	Personal/Company Vehicle (only receive mileage rate no fuel)					
	Meals (Travel Days 0.75%)					
	Meals Full Day					
	M&IE					
	Lodging					
	Lodging taxes and fees					
	Miscellaneous (<i>add description</i>)					
Total Expense						\$0.00
Justification for Travel						
CONTRACTOR eSIGNATURE:						
CONTRACTING OFFICER/SERVICE ORDER ADMINISTRATOR eSIGNATURE:						

Note: Travel expense report must be completed for each individual traveler. Highlighted areas to be filled in by contractor

Reimbursement of expenses required is in accordance with the following:

- 1) All travel related reimbursements are in accordance with the U.S. Government Joint Travel Regulations (JTR). Maximum rates for reimbursement of lodging, meals, and incidentals (i.e. per diem allowances) are set by the U.S. Government according to location of travel.
- 2) Copy of receipts for lodging, airline tickets, and car rental is required and must be submitted with this form. Actual expenses for lodging are reimbursed up to the maximum rate set forth in the current JTR for that location, plus taxes and fees. Allowances for meals and incidental expenses is reimbursed up to a maximum determined by the current JTR. Receipts are required for any allowable individual travel related expense greater than \$75.00.

Revised 13 September 2024

SUBCONTRACTOR BID ANALYSIS FORM									
Service Order #: Prime KTR				Bid Analysis Date:					
Name: Service & Phase:									
Contract #:									
Funding CLIN:		0							
		0							
BID ANALYSIS									
Bidder Company Name:				Subcontractor 1		Subcontractor 2		Subcontractor 3	
Quote Request Date:									
Quote Received Date:									
No Bid Date:									
Quote Not Received:									
Description of Services, Supplies, Equipment	Unit of Measure	# of Units	Unit Price	Extended Total	Unit Price	Extended Total	Unit Price	Extended Total	
1			Refer to Sheet "Subcontractor 1 KO Form"		Refer to Sheet "Subcontractor 2 KO Form"		Refer to Sheet "Subcontractor 3 KO Form"		
2									
3									
4									
5									
6									
7									
8									
9									
10									
FFP LUMP SUM PRICE:									
Check (1) box of Selected Subcontractor:									
BID AND SUBCONTRACTOR SELECTION STATEMENT/JUSTIFICATION									
<i>Please describe why the selected sub was chosen and why their price is fair and reasonable:</i>									
Lowest price, technically acceptable competitive bid selected.									
SOLE SOURCE JUSTIFICATION IAW FAR 16.505(b)(2)									
<i>If only one bid was received or one source was selected, please check (1) applicable box and provide rationale in below. Use Supporting Documentation tab to provide source and price justification via material/equipment quotes, vendor/catalog #, OEM notice, or other means.</i>									
		(A) The agency need for the supplies or services is so urgent that providing a fair opportunity would result in significant impact on mission readiness - rationale provided below							
		(B) Only one awardee is capable of providing the supplies or services required at the level of quality required because the supplies or services ordered are unique or highly specialized. (i.e. proprietary product) - rationale provided below							
		(C) For orders exceeding the simplified acquisition threshold, a statute expressly authorizes or requires that the purchase be made from a specified source. (i.e. brand name items replacing in kind) - rationale provided below							
Rationale for Choosing the Above Selection (include impact statement for urgent requirements):									
Signature & Date:									

APPENDIX B

REPORTING REQUIREMENTS

**U. S. Army Engineering and Support Center
Huntsville, Alabama**

APPENDIX B – REPORTING REQUIREMENTS

1.0 Three Week Look-Ahead Schedule

The contractor shall provide a weekly schedule update detailing a schedule of all on-site activities anticipated for the following three weeks. The contractor shall utilize the template provided in Attachment 1. The report shall be submitted to the government no later than 1300 every Friday each week. The report shall be submitted to the HNC PM and the FMSRs for the Sites included in the Contract.

2.0 Monthly Status Reports

The Contractor shall prepare and submit a monthly progress report describing the work performed since the previous report, work currently underway, and work anticipated. The report shall include any relevant correspondence (email or phone with the FMSR, QA, PM or site) not already provided via email or in meeting minutes and updated recurring maintenance schedule for all sites. If approved work is not on schedule, the Contractor shall state what actions are anticipated to get back on schedule. In addition, the monthly report shall include: a balance sheet showing current available FFP funds for Service Orders, safety program data/info, any customer comments and ratings, data analysis (e.g., Service Orders approved/completed per month per Service, scheduled maintenance funds spent per month per Service, number of backlog Service Orders per Service, average cost of routine/emergency Service Orders per Service, average time from identification to repair for routine/emergency Service Orders per Service, and top 10 recurring maintenance or repairs with frequency of maintenance/repair included) and backup data as required. Photographs of recently performed repairs shall be included. The report shall be submitted no later than the 10th day of each calendar month and shall discuss the previous calendar month's activities. The contractor shall utilize the template provided in Attachment 2; however, HNC COR may request changes or additions to this report as necessary. The report shall be submitted via RMS and electronic mail to the Monthly Report Inbox at: *CEHNC-DLAFuelsMonthlyReports@usace.army.mil*

3.0 Preventive Maintenance Reports

3.1 PM Deficiency List

The contractor must conduct an in and out brief per the PWS Paragraph 3.3. The deficiency list after each PM visit must be provided within the timeframe requirements listed in the PWS.

3.2 Preventive Maintenance Report

The Contractor shall develop a comprehensive recurring maintenance report that contains all of the information in Appendix B, Attachment 3 showing results of all tests, inspection, maintenance, and repair performed. The report shall be completed on the individual component level. The report shall include, but not be limited to, information regarding equipment/systems checked, any readings/measurements taken, inspection, maintenance, and repair performed, noted defects, and any comments/recommendations. The report must include photographs of completed work.

The maintenance report shall include a deficiency log of all deficiencies identified at each site during the entire period of performance of the contract. Deficiencies shall be given a deficiency identification number and sorted in reverse chronologically order by date identified. Service order status for each deficiency shall be identified. The contractor must submit a deficiency list to the Government stakeholder group within 7 calendar days of completion of each PM visit. The deficiency list must be in accordance with Appendix A.

APPENDIX B – REPORTING REQUIREMENTS

Maintenance reports shall be submitted to the KO with FMSR signature within 30 calendar days of the completion of each maintenance visit. The contractor shall utilize the template provided in Attachment 3.

The report shall be submitted via RMS and via electronic mail to the Monthly Report Inbox at: *CEHNC-DLAFuelsMaintenanceReports@usace.army.mil*

An additional copy shall be submitted to the facility FMSR and a copy shall be kept by the contractor.

4.0 Service Order Tracker

Completed SO dates shall be sent to HNC SO Desk every Monday NLT 1200 CST for the previous week utilizing the format provided in Attachment 4 of this Appendix. Updates for service orders not completed must be provided and captured in the appropriate column as outlined in the email in which the tracker is sent. Updates should include specific timeframes and/or dates and not general comments such as “waiting on sub-contractor bid”.

5.0 Bi-weekly Contract Status Meeting Reporting Requirement

The contractor shall provide a meeting agenda for the bi-weekly meeting at least one day prior to meeting date to include at a minimum the following topics of discussion:

- A. Preventive Maintenance
- B. Quality Control
- C. Contract Funding and Invoicing
- D. Safety
- E. Staffing – List of Contract Specific
- F. Base Access
- G. FMSR issues
- H. Other Contract deliverables
- I. Contract Actions
- J. Service Orders – sections for ESOs and high priority RSOs
- K. Metrics
- L. RFIs
- M. Corrective Maintenance Incidental to Maintenance Quantity Tracker
- N. Other topics of discussion

The Government reserves the right to add to or modify the agenda.

Attachments:

Attachment 1: Three Week Look Ahead Schedule

Attachment 2: Monthly Report Template

Attachment 3: Preventive Maintenance Report Template

Attachment 4: Service Order Tracker

APPENDIX B – ATTACHMENT 2

Monthly Report Template

DLA Preventive Maintenance and Corrective Maintenance Program
US Army Corps of Engineers, Engineering and Support Center, Huntsville

Monthly Status Report

Contract No. W912DY-13-G-XXXX

Contract No. XXXX

Contract title

Submission Date:

Submitted By:

Company Name

APPENDIX B – ATTACHMENT 2

TABLE OF CONTENTS

1.0 SERVICE ORDER OVERVIEW 4

2.0 PEVENTATIVE MAINTENANCE OVERVIEW 5

3.0 CURRENT AVAILABLE FUNDS 6

4.0 QUALITY 6

5.0 SAFETY 6

6.0 PHOTOGRAPHS..... 6

7.0 SCHEDULE..... 6

8.0 TOP 10 MAINTENANCE REPAIR ITEMS..... 7

9.0 CORRECTIVE MAINTENANCE INCIDENTAL TO MAINTENANCE ACTIVITIES..... 7

10.0 MISCELLANEOUS MINOR REPAIRS 7

11.0 POINTS OF CONTACT 7

12.0 APPENDICES 7

 Appendix A – Safety Report 7

 Appendix B – Photographs 7

 Appendix C – Schedule..... 7

APPENDIX B – ATTACHMENT 2

1.0 SERVICE ORDER OVERVIEW

Service Order Overview- <i>As of today current option</i>		
SO Category	Number of SOs	Total Cost
Submitted to HNC	93	\$532K
Approved by HNC	46	\$178K
Executed	62	\$195K
Disapproved / Cancelled by HNC	1	\$1K
Awaiting HNC Approval	100	\$859K
In-Progress (have not been to HNC)	107	\$676K

Service Order Overview- <i>During this Period</i>		
SO Category	Number of SOs	Total Cost
Submitted to HNC	93	\$532K
Approved by HNC	46	\$178K
Executed	62	\$195K
Disapproved / Cancelled by HNC	1	\$1K

SO #	General Description	NTP Date	Completed Date	30 days after NTP date	# days to complete	# days less than 30	# days over 30 (from NTP)	Remarks

Every SO submitted during this period shall be included in this table.

APPENDIX B – ATTACHMENT 2

2.0 PREVENTIVE MAINTENANCE OVERVIEW

Table 1 Required & Completed Maintenance Visits
Completed as of today current option

Site Name	Code	Phase	Quarterly		Semi-Annual		Annual	
			Required	Completed	Required	Completed	Required	Completed
Bryant/Richardson	BRY	A5	4	4	2	2	1	1
Camp Santiago	STG	A5	4	4	2	2	1	1
Fort Greely	GRE	A5	4	4	2	2	1	1
Fort Wainwright	WNR	A5	4	4	2	2	1	1
Isla Grande	IGP	A5	4	4	2	2	1	1
Kwajalein Island	KWA	A5	2	1	2	1	1	1
Pohakuloa	PTA	A5	4	4	2	2	1	1
Soto Cano	SCN	A5	2	2	2	2	1	1
Wheeler Army	WHL	A5	4	4	2	2	1	1

Table 2 Number & Total Costs of
Maintenance Visits- *During this period*

Effort	Number of Maintenance Visits this Month	Total Cost
Quarterly Maintenance	14	\$102,654.00
Semi-Annual Maintenance	15	\$103,479.00
Annual Maintenance	5	\$133,036.00

Table 1 Required & Completed Maintenance Visits
Completed during this period

Site Name	Code	Phase	Quarterly		Semi-Annual		Annual	
			Required	Completed	Required	Completed	Required	Completed
Bryant/Richardson	BRY	A5	4	0	2	0	1	0
Camp Santiago	STG	A5	4	0	2	0	1	0
Fort Greely	GRE	A5	4	0	2	0	1	1
Fort Wainwright	WNR	A5	4	1	2	0	1	0
Isla Grande	IGP	A5	4	2	2	0	1	1
Kwajalein Island	KWA	A5	2	3	2	1	1	0
Pohakuloa	PTA	A5	4	4	2	0	1	1
Soto Cano	SCN	A5	2	2	2	1	2	1
Wheeler Army	WHL	A5	4	4	2	1	1	1

APPENDIX B – ATTACHMENT 2

3.0 CURRENT AVAILABLE FUNDS

CLIN	Amount	Balance (Approved SOs)	Balance (Submitted SOs)	Comments

4.0 QUALITY

Customer Feedback Surveys

Sixty-three (63) customer quality feedback surveys were sent for Preventive maintenance and corrective actions during the reporting period. As of the close of this reporting period, 20 surveys were received. These surveys reflected neutral to positive comments on the JV's performance to date.

Question	Total Quantity of Responses	
	Yes	No
Was work performed in a quality manner?		
Was work performed safely?		
Was work performed in a timely manner?		
Did the prime contractor successfully manage the subcontractor?		
Did contractor communicate with you prior to and upon completion of work?		
Was the work area kept clean during and upon completion of work?		
Did contractor have all necessary certifications?		
Were there any issues with the work performed?		
Did contractor arrive with all parts, materials, and tools needed to complete the repair?		

The following comments were received on the surveys:

5.0 SAFETY

A. Reportable Incidents this period:

B. Safety training/briefings this period and (attendees):

Safety reports are included in Appendix A.

6.0 PHOTOGRAPHS

Representative photographs of maintenance repair work are included in Appendix B.

7.0 SCHEDULE

The updated schedule for anticipated CM and PM/ER work is included in Appendix C.

APPENDIX B – ATTACHMENT 2

8.0 TOP 10 CORRECTIVE MAINTENANCE ITEMS

Rank	Maintenance/Repair	Number

9.0 CORRECTIVE MAINTENANCE INCIDENTAL TO MAINTENANCE ACTIVITIES

Provide tracking of all repairs completed under this CLIN for each option year. Refer to Appendix H for list of items that should be tracked in this section.

10.0 MISCELLANEOUS CORRECTIVE MAINTENANCE

Provide quantity of repairs completed under this CLIN for each option year.

11.0 POINTS OF CONTACT

Contract Administrators
Program Manager Project
Manager
Project Engineer
Site Manager

12.0 APPENDICES

Appendix A – Safety Report

Appendix B – Photographs

Appendix C – Schedule

APPENDIX B - ATTACHMENT 3 RECURRING MAINTENANCE REPORT TEMPLATE

Contract47QSHA18D000Y W912DY21F0025

SiteKaneohe

Date26-Apr-22

RM Event(s)Q2, SA1, A BY

☒ Daily

☒ Weekly

☒ Monthly

☒ Quarterly

☒ Semi-annually

☒ Annually

☒ Every 3 years

☒ Every 5 years

☒ Every 10 years

Note: It is advised that "See Description" and "Reference to Other" always be displayed.

☒ See Description

☒ Reference to Other

☒ SM

☒ OM

Warning: Only adds Deficiencies marked "Y" in Col T.

Generate Deficiency List

RM Report Setup Only - See Instructions

Generate UFC Tasks

Applicable Facility Assets										UFC System Level Maintenance Frequency	Responsibility	RM Completion Record Result	Date Completed	Completed By	Deficiencies	Responsible FMSR	Notes	Add to Def List?
UFC Section Reference	Real Property Facility #	Real Property Facility Name	Operational Area	Component Type	Base Asset ID	Component Unique Identifier (CUID)	Make	Model	Capacity/Size									
Signage and Markings (Section 2-7)																		
A. Check permanent signs and markings for adequacy and readability. Repair or replace deteriorated or illegible signs and markings.											Monthly	OM						
B. Inspect the location of Department of Transportation (DOT) regulated underground pipelines and ensure they are marked in accordance with 49 Code of Federal Regulations (CFR) 195.410.											Monthly	OM						
C. Check that all non-DOT regulated pipelines, tanks, valves, pumps, meters, and other equipment are marked in accordance with UFC 3- 460-01 Section 2-17. If markings are missing or insufficient, repair or add markings in accordance with UFC 3-460-01.											Monthly	OM						
D. Ensure petroleum fuel system Emergency Fuel Shutoff (EFSO) push buttons are properly identified at each location. Ensure that signage is properly secured and that the lettering is legible from 25 feet (7.5 meters) away and not faded.											Monthly	OM						
E. Verify enough movable or temporary signs are maintained in good condition to serve anticipated needs; for example: "DANGER," "CLOSED TO TRAFFIC," "KEEP FLAMES AWAY," "MEN WORKING," "NO SMOKING," "DANGER NO OPEN FLAME OR IGNITION SOURCE BEYOND THIS POINT." Use bilingual signs when appropriate.											Annually	OM						
I	2-7	149	Fuel Pier 149	Pier 149	Signs and Markings	All signs and pipeline markings for Fac 149	KAN-149-SIGN-0001	UNK	UNK	UNK		Completed	44666	Contractor		FMSR		
I	2-7	349	WAREHOUSE, GENERAL	WAREHOUSE, GENERAL	Signs and Markings	All signs and pipeline markings for Fac 349	KAN-349-SIGN-0001	UNK	UNK	UNK		Completed	44667	Contractor		FMSR		
I	2-7	370	FUEL OPS/TEST FACILITY	FUELS OPS FAC	Signs and Markings	All signs and pipeline markings for Fac 370	KAN-370-SIGN-0001	UNK	UNK	UNK		Completed	44668	Contractor		FMSR		
I	2-7	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Signs and Markings	All signs and pipeline markings for Fac 1170	KAN-1170-SIGN-0001	UNK	UNK	UNK		Completed	44669	Contractor		FMSR		
I	2-7	1252	BULK FUEL STORAGE TANK F-24	Bulk Storage	Signs and Markings	All signs and pipeline markings for Fac 1252	KAN-1252-SIGN-0001	UNK	UNK	UNK		Deficiency	44670	Contractor	Damaged sign	FMSR	Needs to be replaced	N
I	2-7	1253	BULK FUEL STORAGE TANK F-24	Bulk Storage	Signs and Markings	All signs and pipeline markings for Fac 1253	KAN-1253-SIGN-0001	UNK	UNK	UNK		Completed	44671	Contractor		FMSR		
I	2-7	1254	TRUCK OFFLOAD	Pump Station	Signs and Markings	All signs and pipeline markings for Fac 1254	KAN-1254-SIGN-0001	UNK	UNK	UNK		Completed	44672	Contractor		FMSR		
I	2-7	6479	JET ENGINE FUEL STORAGE	Bulk Storage	Signs and Markings	All signs and pipeline markings for Fac 6479	KAN-6479-SIGN-0001	UNK	UNK	UNK		Completed	44673	Contractor		FMSR		
I	2-7	6496	BULK FUEL STORAGE TANK JP-5	Bulk Storage	Signs and Markings	All signs and pipeline markings for Fac 6496	KAN-6496-SIGN-0001	UNK	UNK	UNK		Completed	44674	Contractor		FMSR		
I	2-7	6503	FUEL STATION	Military Service Station	Signs and Markings	All signs and pipeline markings for Fac 6503	KAN-6503-SIGN-0001	UNK	UNK	UNK		Deficiency	44675	Contractor	Damaged sign	FMSR	Needs to be replaced	N
I	2-7	6504	TRUCK LOAD/ OFFLOAD FACILITY	Load/Offload-Gas/DS-2/Bio-Deisel	Signs and Markings	All signs and pipeline markings for Fac 6504	KAN-6504-SIGN-0001	UNK	UNK	UNK		Completed	44676	Contractor		FMSR		
I	2-7	6645	SMALL CRAFT FUEL STA AND STORAGE	Waterfront	Signs and Markings	All signs and pipeline markings for Fac 6645	KAN-6645-SIGN-0001	UNK	UNK	UNK		Completed	44677	Contractor		FMSR		
I	2-7	6745	BULK FUEL STORAGE TANK E-85	Military Service Station	Signs and Markings	All signs and pipeline markings for Fac 6745	KAN-6745-SIGN-0001	UNK	UNK	UNK		Completed	44678	Contractor		FMSR		
I	2-7	200835	POL PIPELINE	DISTRIBUTION SYSTEM FUEL OIL	Signs and Markings	All signs and pipeline markings for Fac 200835	KAN-200835-SIGN-0001	PIPING	UNK	UNK		Deficiency	44679	Contractor	Missing sign	FMSR	Needs to be replaced	N
I	2-7	206490	FENCING AT FUEL FARM	FENCING AT FUEL FARM	Signs and Markings	All signs and pipeline markings for Fac 206490	KAN-206490-SIGN-0001	FENCING	UNK	4163 LF		Completed	44680	Contractor		FMSR		
I	2-7	1563-1	TRUCK LOAD FACILITY JP5	Load Rack - 1	Signs and Markings	All signs and pipeline markings for Fac 1563	KAN-1563_1-SIGN-0001	UNK	UNK	UNK		Deficiency	44681	Contractor	Faded sign	FMSR	Needs to be replaced	N
I	2-7	64798	JET ENGINE FUEL STORAGE	Filter/Separator	Signs and Markings	All signs and pipeline markings for Fac 64798	KAN-64798-SIGN-0001	UNK	UNK	UNK		Completed	44682	Contractor		FMSR		
I	2-7	6506-1	MOGAS FUEL TANK	Military Service Station	Signs and Markings	All signs and pipeline markings for Military Service Station 6506	KAN-6506_1-SIGN-0001	UNK	UNK	UNK		Completed	44683	Contractor		FMSR		
I	2-7	PL-FTPA	FUEL TRUCK PARKING AREA	FUEL TRUCK PARKING AREA	Signs and Markings	All signs and pipeline markings for Fac PL-FTPA	KAN-PL_FTPA-SIGN-0001	UNK	UNK	UNK		Completed	44684	Contractor		FMSR		
Filter Separators (Section 3-6.2)																		
G. Refer to Section 6-7.2 Differential Pressure Gauges for inspection and maintenance requirements of differential pressure gauges.											Reference to Other	SM						
H. Refer to Section 3-10.2 Automatic Air Vents for inspection and maintenance requirements of automatic air vents.											Reference to Other	SM						
I. Refer to Section 6-6.3 Thermal and Pressure Relief Valves for inspection and maintenance requirements of thermal and pressure relief valves.											Reference to Other	SM						
J. Refer to Section 4-4.2.2 Filter Separator Control Valves for inspection and maintenance requirements of filter separator control valves.											Reference to Other	SM						
A. Open drain under flow conditions until clear fuel is observed from the drain valve.											Daily	OM						
B. Monitor differential pressure of coalescer cartridges. The acceptable maximum differential pressure for a specific filter/separator is dependent on the system flow rate. Monitor and chart differential pressure measurements of filter separators from readings taken during normal operations. Investigate sudden drops or spikes in differential pressure measurement readings.											Daily	OM						
C. Operate filter separator isolation valves.											Quarterly	SM						
D. Inspect components and check operation of water shutoff system.											Quarterly	SM						
E. Change coalescer cartridges. Refer to Section 3-6.2.2 Replacement of Coalescer Cartridges for general instructions on replacement of coalescer cartridges. Military Service-specific SCP may extend the coalescer cartridge replacement frequency based on differential pressure if filters separators are used on high throughput systems. Check expiration date of replacement coalescer cartridges before installation. Frequency: Every 36 months or sooner if required by differential pressure. Routine coalescer changes shall be performed as part of the FFP maintenance activities and priced under CLIN 0006 for Base Year and OY3. Coalescer cartridge changes required due to a repair, out of sequence, or other circumstance beyond normal system operation shall be performed by service order. Coalescer cartridges will be provided by the Government.											See Description	SM						
F. Inspect and clean separator cartridges at time of coalescer cartridge change in accordance with Section 3-6.2.3 Separator Cleaning. Worn or damaged separator cartridges shall be replaced. Frequency: Every 36 months or sooner if required by differential pressure. Routine separator cartridge replacement shall be performed as part of the FFP maintenance activities and priced under CLIN 0006 for Base Year and OY3. Separator cartridges will be provided by the Government.											See Description	SM						
K. Conduct inspections of code rated vessels that meet the requirements of UFC 3-430-07 Operations and Maintenance: Inspection and Certification of Boilers and Unfired Pressure Vessels. Frequency: As required by UFC 3-430-07. This task shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.											See Description	SM						

APPENDIX B - ATTACHMENT 3 RECURRING MAINTENANCE REPORT TEMPLATE

Contract47QSHA18D000Y W912DY21F0025

SiteKaneohe

Date26-Apr-22

RM Event(s)Q2, SA1, A BY

☒ Daily

☒ Weekly

☒ Monthly

☒ Quarterly

☒ Semi-annually

☒ Annually

☒ Every 3 years

☒ Every 5 years

☒ Every 10 years

Note: It is advised that "See Description" and "Reference to Other" always be displayed.

☒ See Description

☒ Reference to Other

☒ SM

☒ OM

Warning: Only adds Deficiencies marked "Y" in Col T.

Generate Deficiency List

RM Report Setup Only - See Instructions

Generate UFC Tasks

Applicable Facility Assets										UFC System Level Maintenance Frequency	Responsibility	RM Completion Record Result	Date Completed	Completed By	Deficiencies	Responsible FMSR	Notes	Add to Def List?
UFC Section Reference	Real Property Facility #	Real Property Facility Name	Operational Area	Component Type	Base Asset ID	Component Unique Identifier (CUID)	Make	Model	Capacity/Size									
I	3-6.2	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Filter/Separator-SY-1	1310 GPM, Working Pressure 275 PSI, Hydrotest 413 PSI, Lid Gasket G-0585, First Stage 1-65685TB QTY 7, Second Stage SO-648 QTY 2	KAN-1170-FLSP-0001	Velcon Filters, LLC	SHV2856275-1	UNK								
I	3-6.2	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Filter/Separator-SY-1	900 GPM, Working pressure 275 PSI, Hydrotest 413 PSI, First Stage 1-65685TB QTY 7, Second Stage SO-648V QTY 2	KAN-1170-FLSP-0002	Three Filters Limited	SHV2856275-1	UNK								
I	3-6.2	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Filter/Separator-SY-2	900 GPM, Working pressure 275 PSI, Hydrotest 413 PSI, First Stage 1-65685TB QTY 7, Second Stage SO-648V QTY 2	KAN-1170-FLSP-0003	Three Filters Limited	SHV2856275-1	UNK								
I	3-6.2	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Filter/Separator-SY-2	1310 GPM, Working Pressure 275 PSI, Hydrotest 413 PSI, Lid Gasket G-0585, First Stage 1-65685TB QTY 7, Second Stage SO-648 QTY 2	KAN-1170-FLSP-0004	Velcon Filters, LLC	SHV2856275-1	UNK								
I	3-6.2	6479	JET ENGINE FUEL STORAGE	Filter/Separator	Filter/Separator	Filter/Separator-SY-1	KAN-6479-FLSP-0001	Velcon Filters, LLC	SHV2856275-1	UNK								
I	3-6.2	6479	JET ENGINE FUEL STORAGE	Filter/Separator	Filter/Separator	Filter/Separator-SY-2	KAN-6479-FLSP-0002	Velcon Filters, LLC	UNK	UNK								
I	3-6.2	1563-1	TRUCK LOAD FACILITY JPS	Load Rack - 1	Filter/Separator	NATLBO SO-430V	KAN-1563_1-FLSP-0001	UNK	HV22332275	UNK								
I	3-6.2	1563-2	TRUCK LOADING FACILITY JPS	Load Rack - 2	Filter/Separator	NATLBO SO-430V	KAN-1563_2-FLSP-0001	UNK	HV22332276	UNK								
I	3-6.2	1563-2	TRUCK LOADING FACILITY JPS	Load Rack - 3	Filter/Separator	Filter/Separator	KAN-1563_2-FLSP-0002	M.E. Industries	UNK	UNK								
H	Basket Strainers (Section 3-6.4)																	
T	A. Monitor and chart differential pressure measurements of basket strainers from readings taken during normal operations. Investigate sudden drops or spikes in differential pressure measurement reading.										Daily	OM						
T	B. Clean and inspect basket and strainer screen. Basket strainer isolation valves shall be closed and the strainer body shall be drained before removing the cover. After cleaning, the strainer screen shall be inserted in the strainer body, and the head tightened and checked for leakage. If strainer is not equipped with means to measure differential pressure, unit shall be opened monthly and inspection. Frequency: Semi-annually if basket strainer is equipped with means to measure differential pressure; otherwise quarterly										See Description	OM						
T	C. Refer to Section 6-7.2 Differential Pressure Gauges for inspection and maintenance requirements of differential pressure gauges.										Reference to Other	SM						
I	3-6.4	1254	TRUCK OFFLOAD	Pump Station	Basket Strainer	Strainer- 150 Class; F/F - PS-1254-1	KAN-1254-BSTR-0001	903XHD MULLER	UNK	6"								
I	3-6.4	1254	TRUCK OFFLOAD	Pump Station	Basket Strainer	Strainer- 150 Class; F/F - PS-1254-2	KAN-1254-BSTR-0002	891XH MULLER	UNK	4"								
I	3-6.4	1254	TRUCK OFFLOAD	Pump Station	Basket Strainer	Strainer- 150 Class; F/F - PS-1254-3	KAN-1254-BSTR-0003	891XH MULLER	UNK	4"								
I	3-6.4	1254	TRUCK OFFLOAD	Pump Station	Basket Strainer	Strainer- 150 Class; F/F - PS-1254-4	KAN-1254-BSTR-0004	891XH MULLER	UNK	4"								
I	3-6.4	6479	JET ENGINE FUEL STORAGE	Bulk Storage	Basket Strainer	Strainer- 150 Class; F/F - 6479A	KAN-6479-BSTR-0001	UNK	UNK	14"								
I	3-6.4	6479	JET ENGINE FUEL STORAGE	Bulk Storage	Basket Strainer	Strainer- 150 Class; F/F - 6479A	KAN-6479-BSTR-0002	UNK	UNK	3"								
I	3-6.4	6479	JET ENGINE FUEL STORAGE	Bulk Storage	Basket Strainer	Strainer- 150 Class; F/F - 6479A	KAN-6479-BSTR-0003	UNK	UNK	3"								
I	3-6.4	6479	JET ENGINE FUEL STORAGE	Bulk Storage	Basket Strainer	Strainer- 150 Class; F/F - 6479A	KAN-6479-BSTR-0004	UNK	UNK	2"								
I	3-6.4	6479	JET ENGINE FUEL STORAGE	Bulk Storage	Basket Strainer	Strainer- 150 Class; F/F - 6479B	KAN-6479-BSTR-0005	Titan	UNK	6"								
I	3-6.4	6479	JET ENGINE FUEL STORAGE	Bulk Storage	Basket Strainer	Strainer- 150 Class; F/F - 6479B	KAN-6479-BSTR-0006	Titan	UNK	6"								
I	3-6.4	6504	TRUCK LOAD/ OFFLOAD FACILITY	Load/Offload-Gas/DS-2/Bio-Deisel	Basket Strainer	Strainer- 150 Class; F/F - 6504 Mogas	KAN-6504-BSTR-0001	UNK	UNK	4"								
I	3-6.4	6504	TRUCK LOAD/ OFFLOAD FACILITY	Load/Offload-Gas/DS-2/Bio-Deisel	Basket Strainer	Strainer- 150 Class; F/F - 6504 Diesel	KAN-6504-BSTR-0002	UNK	UNK	4"								
I	3-6.4	1254A	STRAINER FACILITY	STRAINER STATION	Basket Strainer	Strainer- 150 Class; F/F - PS-1254A-1	KAN-1254A-BSTR-0001	Titan	UNK	10"								
I	3-6.4	1254A	STRAINER FACILITY	STRAINER STATION	Basket Strainer	Strainer- 150 Class; F/F - PS-1254A-2	KAN-1254A-BSTR-0002	Titan	UNK	10"								
I	3-6.4	1563-1	TRUCK LOAD FACILITY JPS	Load Rack - 1	Basket Strainer	Strainer-LR-1	KAN-1563_1-BSTR-0001	UNK	UNK	3"								
I	3-6.4	1563-2	TRUCK LOADING FACILITY JPS	Load Rack - 2	Basket Strainer	Strainer-LR-2	KAN-1563_2-BSTR-0001	UNK	UNK	3"								
I	3-6.4	1563-2	TRUCK LOADING FACILITY JPS	Load Rack - 3	Basket Strainer	Strainer-LR-3	KAN-1563_2-BSTR-0002	UNK	UNK	3"								
H	Positive Displacement Meters (Section 3-7.1)																	
T	A. Inspect counter head for unusual noises and smooth operation.										Monthly	OM						
T	B. Positive displacement meters shall be inspected and calibrated semi-annually or when improper performance is suspected; when unusual sounds or register actions develop; or after repairs have been made which may affect performance. Positive displacement meters are satisfactory when the measurement error in the normal flow direction is within ±0.3% of actual quantity delivered (e.g., ±1.8 gallons for a 600-gallon test (±8.8 liters for a 2275-liter test)). Adjustment of the meter's register will be in accordance with manufacturer's instructions. Identify the next calibration date on meters (example: Mar 14 for March 2014). Use weather resistant label that will remain legible and affixed for at least one year. Frequency: Calibration shall be done by SO if FMSR requests an out of cycle calibration due to circumstances beyond normal operation.										Semi-annually	SM						
T	C. Inspect temperature element operation of meters equipped with temperature compensation feature per manufacturer's operation and maintenance manual. Frequency: Or as required by manufactures' operation and maintenance manual.										Semi-annually	SM						
I	3-7.1	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Positive Displacement Meter	Veeder-Root, Meter PIT A R788700-001; LC, 600GPM	KAN-1170-PDMT-0001	UNK	M-60-1	UNK								

RM Template v0.4.3

2

APPENDIX B - ATTACHMENT 3 RECURRING MAINTENANCE REPORT TEMPLATE

Contract47QSHA18D000Y W912DY21F0025

SiteKaneohe

Date26-Apr-22

RM Event(s)Q2, SA1, A BY

☒ Daily

☒ Weekly

☒ Monthly

☒ Quarterly

☒ Semi-annually

☒ Annually

☒ Every 3 years

☒ Every 5 years

☒ Every 10 years

Note: It is advised that "See Description" and "Reference to Other" always be displayed.

☒ See Description

☒ Reference to Other

☒ SM

☒ OM

Warning: Only adds Deficiencies marked "Y" in Col T.

Generate Deficiency List

RM Report Setup Only - See Instructions

Generate UFC Tasks

Applicable Facility Assets										UFC System Level Maintenance Frequency	Responsibility	RM Completion Record Result	Date Completed	Completed By	Deficiencies	Responsible FMSR	Notes	Add to Def List?	
UFC Section Reference	Real Property Facility #	Real Property Facility Name	Operational Area	Component Type	Base Asset ID	Component Unique Identifier (CUID)	Make	Model	Capacity/Size										
I	3-7.1	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Positive Displacement Meter	Veeder-Root, Meter Pit B R788700-001; LC; 600GPM	KAN-1170-PDMT-0002	Liquid Controls	M-60-1	UNK									
I	3-7.1	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Positive Displacement Meter	Veeder-Root, Meter Pit C R788700-001; LC; 600GPM	KAN-1170-PDMT-0003	Liquid Controls	M-60-2	UNK									
I	3-7.1	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Positive Displacement Meter	Veeder-Root, Meter Pit D R788700-001; LC; 600GPM	KAN-1170-PDMT-0004	Liquid Controls	M-60-3	UNK									
I	3-7.1	6504	TRUCK LOAD/ OFFLOAD FACILITY	Load/Offload-Gas/DS-2/Bio-Deisel	Positive Displacement Meter	Meter Mogas, Veeder-Root 0788700-036; LC; 100GPM	KAN-6504-PDMT-0001	Liquid Controls	UNK	4"									
I	3-7.1	6504	TRUCK LOAD/ OFFLOAD FACILITY	Load/Offload-Gas/DS-2/Bio-Deisel	Positive Displacement Meter	Meter Diesel, Veeder-Root 0788700-036; LC; 100GPM	KAN-6504-PDMT-0002	Liquid Controls	UNK	4"									
I	3-7.1	1254A	STRAINER FACILITY	STRAINER STATION	Meter	Meter	KAN-1254A-PDMT-0001	Liquid Controls	UNK	UNK									
I	3-7.1	1563-1	TRUCK LOAD FACILITY JP5	Load Rack - 1	Positive Displacement Meter	Veeder-Root, Meter Rack-#1 R788700-001; LC; 600GPM	KAN-1563_1-PDMT-0001	UNK	UNK	UNK									
I	3-7.1	1563-2	TRUCK LOADING FACILITY JP5	Load Rack - 2	Positive Displacement Meter	Veeder-Root, Meter Rack-#2 R788700-001; LC; 600GPM	KAN-1563_2-PDMT-0001	Liquid Controls	UNK	UNK									
I	3-7.1	1563-2	TRUCK LOADING FACILITY JP5	Load Rack - 3	Positive Displacement Meter	Veeder-Root, Meter Rack-#3 R788700-001; LC; 600GPM	KAN-1563_2-PDMT-0002	Liquid Controls	UNK	UNK									
H	Centrifugal Pumps (Section 3-8.1)																		
T	J. Refer to Section 9-1.7 Electric Motors for inspection and maintenance requirements of electric motors.										Reference to Other	SM							
T	K. Pumps must be maintained in accordance with any manufacturer's guidelines that are in addition to Appendix G Maintenance Tasks. Manufacturer required maintenance activities more frequent than quarterly must be performed Quarterly.										See Description	SM							
T	A. Check for proper operations while pump is in use. Check suction and discharge pressure gauge for abnormal readings.										Quarterly	SM							
T	B. Check for unusual noise, vibration, overheating of bearings or case.										Quarterly	SM							
T	C. If equipped with lubricating oil charge, check oil level and adjust as necessary.										Quarterly	SM							
T	D. Tighten or replace loose, missing or damaged nuts, bolts, or screws.										Quarterly	SM							
T	E. Inspect suction and discharge isolation dampeners for misalignment and wear.										Quarterly	SM							
T	F. Inspect mechanical seals, if possible, for proper operating temperature, drips, leaks and dirt.										Quarterly	SM							
T	G. Check alignment, clearances, and rotation of shaft and coupler (requires removal of coupler shroud or cover).										Annually	SM							
T	H. Lubricate pump bearings.										Annually	SM							
T	I. If equipped with lubricating oil charge, drain old oil, and fill with new to full mark on sight indicator (also fill bulb).										Annually	SM							
I	3-8.1	1254	TRUCK OFFLOAD	Pump Station	Pump #1	Pump #2	KAN-1254-CENP-0001	Siemens	UNK	600 GPM									
I	3-8.1	1254	TRUCK OFFLOAD	Pump Station	Pump #2	LR36096	KAN-1254-CENP-0002	Siemens	UNK	300 GPM									
I	3-8.1	1254	TRUCK OFFLOAD	Pump Station	Pump #3	LR36096	KAN-1254-CENP-0003	Siemens	UNK	300 GPM									
I	3-8.1	1254	TRUCK OFFLOAD	Pump Station	Pump #4	R53A31-BAR	KAN-1254-CENP-0004	Gorman-Rupp	UNK	150 GPM									
I	3-8.1	6479	JET ENGINE FUEL STORAGE	Bulk Storage	Pump	6479A-1- 24288-01-01	KAN-6479-CENP-0001	Grisworld	UNK	600 GPM									
I	3-8.1	6479	JET ENGINE FUEL STORAGE	Bulk Storage	Pump	6479A-2- 24288-01-01	KAN-6479-CENP-0002	Grisworld	UNK	600 GPM									
I	3-8.1	6479	JET ENGINE FUEL STORAGE	Bulk Storage	Pump	6479A-3	KAN-6479-CENP-0003	Grisworld	UNK	150 GPM									
I	3-8.1	6479	JET ENGINE FUEL STORAGE	Bulk Storage	Pump	6479A-4	KAN-6479-CENP-0004	Grisworld	UNK	75 GPM									
H	Loading Fuel Hoses (Section 3-9.1)																		
T	A. Visually inspect hoses for loose covers, cracks, brittle surface coatings, exposed wire braids, exposed reinforcement, flattening, kinks, and bulges or soft spots which might indicate broken or displaced reinforcement.										Weekly	OM							
T	B. Pressurize hose to normal working pressure. Check flanged and threaded connections for leaks and inspect hose couplers for fluid seepage by pushing at the base of the coupling with your thumbs; a hose softened by fluid seepage must be replaced.										Weekly	OM							
T	C. Check for coupling slippage. Replace hose that shows signs of coupling slippage. Note: When a new hose is placed in service, stencil the date (MM/YYYY) installed and paint a 50 mm (2-inch) band at each coupling. This will aid in identifying if slippage occurs and when testing is due.										Quarterly	SM							
T	D. Refer to Appendix D, Section D-2.4 Loading Hose Hydrostatic Test for loading hose hydrostatic testing requirements and procedures. The date of testing shall be stenciled on each hose. Hoses shall be removed from the system, and all accessories shall be removed from hoses prior to testing. Task deleted in UFC 3-460-03 Change 1.										Annually	SM							
T	E. Conduct test of fuel hose electrical resistivity using an electrostatic meter in accordance with NFPA 77 & API 2003.										Annually	SM							
I	3-9.1	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Loading Fuel Hose, Pit A	2.5" x 10' Pit A	KAN-1170-LDHS-0001	Aeropal	UNK	UNK									
I	3-9.1	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Loading Fuel Hose, Pit B	2.5" x 10' Pit B	KAN-1170-LDHS-0002	Aeropal	UNK	UNK									
I	3-9.1	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Loading Fuel Hose, Pit C	2.5" x 10' Pit C	KAN-1170-LDHS-0003	Aeropal	UNK	UNK									
I	3-9.1	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Loading Fuel Hose, Pit D	2.5" x 10' Pit D	KAN-1170-LDHS-0004	Aeropal	UNK	UNK									
I	3-9.1	1254	TRUCK OFFLOAD	Pump Station	Offloading Fuel Hose	4" X 10" F/F Cam-lok	KAN-1254-OLHS-0001	Aeropal	UNK	2"									
I	3-9.1	1254	TRUCK OFFLOAD	Pump Station	Offloading Fuel Hose	4" X 10" F/F Cam-lok	KAN-1254-OLHS-0002	Aeropal	UNK	2"									
I	3-9.1	6504	TRUCK LOAD/ OFFLOAD FACILITY	Load/Offload-Gas/DS-2/Bio-Deisel	Hose	2" X 12'	KAN-6504-LDHS-0001	Aeropal	UNK	2" X 12'									
I	3-9.1	6504	TRUCK LOAD/ OFFLOAD FACILITY	Load/Offload-Gas/DS-2/Bio-Deisel	Hose	2" X 12'	KAN-6504-LDHS-0002	Aeropal	UNK	2" X 12'									
I	3-9.1	1563-1	TRUCK LOAD FACILITY JP5	Load Rack - 1	Hose	3" X 12'	KAN-1563_1-LDHS-0001	Aeropal	UNK	3"									
I	3-9.1	1563-2	TRUCK LOADING FACILITY JP5	Load Rack - 2	Hose	3" X 12'	KAN-1563_2-LDHS-0001	Aeropal	UNK	3"									
I	3-9.1	1563-2	TRUCK LOADING FACILITY JP5	Load Rack - 3	Hose	3" X 12'	KAN-1563_2-LDHS-0002	Goodyear	UNK	3"									
H	Air Eliminator Tanks (Section 3-10.1)																		
T	C. Refer to Section 8-9.3 Tank Pressure/Vacuum Vents for inspection and maintenance requirements of pressure vacuum vents.										Reference to Other	SM							

RM Template v0.4.3

3

APPENDIX B - ATTACHMENT 3 RECURRING MAINTENANCE REPORT TEMPLATE

Contract47QSHA18D000Y W912DY21F0025

SiteKaneohe

Date26-Apr-22

RM Event(s)Q2, SA1, A BY

☒ Daily

☒ Weekly

☒ Monthly

☒ Quarterly

☒ Semi-annually

☒ Annually

☒ Every 3 years

☒ Every 5 years

☒ Every 10 years

Note: It is advised that "See Description" and "Reference to Other" always be displayed.

☒ See Description

☒ Reference to Other

☒ SM

☒ OM

Warning: Only adds Deficiencies marked "Y" in Col T.

Generate Deficiency List

RM Report Setup Only - See Instructions

Generate UFC Tasks

Applicable Facility Assets										UFC System Level Maintenance Frequency	Responsibility	RM Completion Record Result	Date Completed	Completed By	Deficiencies	Responsible FMSR	Notes	Add to Def List?	
UFC Section Reference	Real Property Facility #	Real Property Facility Name	Operational Area	Component Type	Base Asset ID	Component Unique Identifier (CUID)	Make	Model	Capacity/Size										
T	A. Inspect operation of fuel level probes. Ensure probes operate correctly when the level of fuel in the tank rises to the level of the probe sensing unit.										Annually	SM							
T	B. Remove the float vent valve from the air eliminator tank. Clean and inspect the sealing surfaces of the float vent valve. Ensure the float is buoyant in fuel and test the valve to ensure it closes properly.										Annually	SM							
I	3-10.1	1254	TRUCK OFFLOAD	Pump Station	Air Eliminator	PS-1254-1	KAN-1254-AELT-0001	UNK	UNK	1"									
I	3-10.1	1254	TRUCK OFFLOAD	Pump Station	Air Eliminator	PS-1254-2	KAN-1254-AELT-0002	UNK	UNK	1"									
I	3-10.1	1254	TRUCK OFFLOAD	Pump Station	Air Eliminator	PS-1254-3	KAN-1254-AELT-0003	UNK	UNK	1"									
I	3-10.1	1254	TRUCK OFFLOAD	Pump Station	Air Eliminator	PS-1254-4	KAN-1254-AELT-0004	UNK	UNK	1"									
I	3-10.1	1254	TRUCK OFFLOAD	Pump Station	Air Eliminator	PS-1254-5	KAN-1254-AELT-0005	UNK	UNK	1"									
I	3-10.1	1254	TRUCK OFFLOAD	Pump Station	Air Eliminator	PS-1254-6	KAN-1254-AELT-0006	UNK	UNK	1"									
I	3-10.1	6479	JET ENGINE FUEL STORAGE	Bulk Storage	Air Eliminator	6479A-1	KAN-6479-AELT-0001	UNK	UNK	1"									
I	3-10.1	6479	JET ENGINE FUEL STORAGE	Bulk Storage	Air Eliminator	6479A-2	KAN-6479-AELT-0002	UNK	UNK	1"									
I	3-10.1	6504	TRUCK LOAD/ OFFLOAD FACILITY	Load/Offload-Gas/DS-2/Bio-Diesel	Air Eliminator	6504-Mogas	KAN-6504-AELT-0001	UNK	UNK	4"									
I	3-10.1	6504	TRUCK LOAD/ OFFLOAD FACILITY	Load/Offload-Gas/DS-2/Bio-Diesel	Air Eliminator	6504-Diesel	KAN-6504-AELT-0002	UNK	UNK	4"									
I	3-10.1	1254A	STRAINER FACILITY	STRAINER STATION	Air Eliminator	SF-1254A-1	KAN-1254A-AELT-0001	UNK	UNK	1"									
I	3-10.1	1254A	STRAINER FACILITY	STRAINER STATION	Air Eliminator	SF-1254A-2	KAN-1254A-AELT-0002	UNK	UNK	1"									
I	3-10.1	1563-2	TRUCK LOADING FACILITY JP5	Load Rack - 1	Air Eliminator	AE-LR-3 - 1	KAN-1563-2-AELT-0001	UNK	UNK	UNK									
I	3-10.1	1563-2	TRUCK LOADING FACILITY JP5	Load Rack - 2	Air Eliminator	AE-LR-3 - 2	KAN-1563-2-AELT-0001	UNK	UNK	UNK									
I	3-10.1	1563-2	TRUCK LOADING FACILITY JP5	Load Rack - 3	Air Eliminator	AE-LR-3 - 3	KAN-1563-2-AELT-0001	UNK	UNK	UNK									
H	Dual Rate-of-Flow Control Valves (Section 4-3.2.8)																		
T	C. Refer to Section 4-3.2.1 General System Control Valves for additional inspection and maintenance requirements.										Reference to Other	SM							
T	A. Verify dual rate-of-flow control valve is set to maintain a flow rate of 200 gpm (12.5 lps).										Quarterly	SM							
T	B. Verify check valve feature is operational.										Quarterly	SM							
I	4-3.2.8	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Flow Control Valve	150 Class; Flanged Manual - Pit A	KAN-1170-DRFCVL-0001	OCV	UNK	4"									
I	4-3.2.8	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Flow Control Valve	150 Class; Flanged Manual - Pit B	KAN-1170-DRFCVL-0002	OCV	UNK	4"									
I	4-3.2.8	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Flow Control Valve	150 Class; Flanged Manual - Pit C	KAN-1170-DRFCVL-0003	OCV	UNK	4"									
I	4-3.2.8	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Flow Control Valve	150 Class; Flanged Manual - Pit D	KAN-1170-DRFCVL-0004	OCV	UNK	4"									
I	4-3.2.8	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Flow Control Valve	150 Class; Flanged Manual - SY-1	KAN-1170-DRFCVL-0005	CLA-VAL	UNK	6"									
I	4-3.2.8	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Flow Control Valve	150 Class; Flanged Manual - SY-2	KAN-1170-DRFCVL-0006	CLA-VAL	UNK	6"									
I	4-3.2.8	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Flow Control Valve	150 Class; Flanged Manual - BF	KAN-1170-DRFCVL-0007	CLA-VAL	UNK	4"									
I	4-3.2.8	1252	BULK FUEL STORAGE TANK F-24	Bulk Storage	Flow Control Valve	150 Class; Flanged Manual	KAN-1252-DRFCVL-0001	CLA-VAL	UNK	10"									
I	4-3.2.8	1253	BULK FUEL STORAGE TANK F-24	Bulk Storage	Flow Control Valve	150 Class; Flanged Manual	KAN-1253-DRFCVL-0001	CLA-VAL	UNK	10"									
I	4-3.2.8	1254	TRUCK OFFLOAD	Pump Station	Flow Control Valve	150 Class; Flanged Automatic - PS-1254-1	KAN-1254-DRFCVL-0001	CLA-VAL	UNK	4"									
I	4-3.2.8	1254	TRUCK OFFLOAD	Pump Station	Flow Control Valve	150 Class; Flanged Automatic - PS-1254-2	KAN-1254-DRFCVL-0002	CLA-VAL	UNK	4"									
I	4-3.2.8	1254	TRUCK OFFLOAD	Pump Station	Flow Control Valve	150 Class; Flanged Automatic - PS-1254-3	KAN-1254-DRFCVL-0003	CLA-VAL	UNK	4"									
I	4-3.2.8	6479	JET ENGINE FUEL STORAGE	Filter/Separator 6479B	Flow Control Valve	150 Class; Flanged Automatic - FS-1	KAN-6479-DRFCVL-0001	CLA-VAL	UNK	6"									
I	4-3.2.8	6479	JET ENGINE FUEL STORAGE	Filter/Separator 6479B	Flow Control Valve	150 Class; Flanged Automatic - FS-2	KAN-6479-DRFCVL-0002	CLA-VAL	UNK	6"									
I	4-3.2.8	6479	JET ENGINE FUEL STORAGE	Pump Station 6479A	Flow Control Valve	150 Class; Flanged Automatic - P-1	KAN-6479-DRFCVL-0003	CLA-VAL	UNK	6"									
I	4-3.2.8	6479	JET ENGINE FUEL STORAGE	Pump Station 6479A	Flow Control Valve	150 Class; Flanged Automatic - P-2	KAN-6479-DRFCVL-0004	CLA-VAL	UNK	6"									
I	4-3.2.8	6504	TRUCK LOAD/ OFFLOAD FACILITY	Load/Offload-Gas/DS-2/Bio-Diesel	Flow Control Valve	150 Class; Flanged Automatic - Mogas	KAN-6504-DRFCVL-0001	CLA-VAL	UNK	4"									
I	4-3.2.8	6504	TRUCK LOAD/ OFFLOAD FACILITY	Load/Offload-Gas/DS-2/Bio-Diesel	Flow Control Valve	150 Class; Flanged Automatic - Diesel	KAN-6504-DRFCVL-0002	CLA-VAL	UNK	4"									
I	4-3.2.8	1254A	STRAINER FACILITY	STRAINER STATION	Flow Control Valve	150 Class; Flanged Automatic- SF-1	KAN-1254A-DRFCVL-0001	CLA-VAL	UNK	4"									
I	4-3.2.8	1563-1	TRUCK LOAD FACILITY F24	Load Rack - 1	Flow Control Valve	150 Class; Flanged Manual - LR-1-1	KAN-1563-2-DRFCVL-0001	CLA-VAL	UNK	4"									
I	4-3.2.8	1563-1	TRUCK LOAD FACILITY F24	Load Rack - 1	Flow Control Valve	150 Class; Flanged Automatic - LR-1-4	KAN-1563_1-DRFCVL-0004	CLA-VAL	UNK	4"									
I	4-3.2.8	1563-1	TRUCK LOADING FACILITY F24	Load Rack - 1	Flow Control Valve	150 Class; Flanged Manual - LR-2-2	KAN-1563-1-DRFCVL-0002	CLA-VAL	UNK	4"									
I	4-3.2.8	1563-2	TRUCK LOAD FACILITY F24	Load Rack - 2	Flow Control Valve	150 Class; Flanged Manual - LR-1-2	KAN-1563_1-DRFCVL-0002	CLA-VAL	UNK	4"									
I	4-3.2.8	1563-2	TRUCK LOAD FACILITY F24	Load Rack - 2	Flow Control Valve	150 Class; Flanged Manual - LR-2-1	KAN-1563_2-DRFCVL-0001	CLA-VAL	UNK	4"									
I	4-3.2.8	1563-2	TRUCK LOADING FACILITY F24	Load Rack - 2	Flow Control Valve	150 Class; Flanged Manual - LR-2-1	KAN-1563-2-DRFCVL-0002	CLA-VAL	UNK	4"									
I	4-3.2.8	1563-2	TRUCK LOADING FACILITY JP5	Load Rack - 2	Flow Control Valve	150 Class; Flanged Automatic - LR-2-3	KAN-1563_2-DRFCVL-0004	CLA-VAL	UNK	4"									
I	4-3.2.8	1563-2	TRUCK LOADING FACILITY JP5	Load Rack - 3	Flow Control Valve	150 Class; Flanged Manual - LR-3-2	KAN-1563_2-DRFCVL-0006	CLA-VAL	UNK	3"									
I	4-3.2.8	1563-2	TRUCK LOADING FACILITY JP5	Load Rack - 3	Flow Control Valve	150 Class; Flanged Automatic - LR-3-3	KAN-1563_2-DRFCVL-0007	CLA-VAL	UNK	3"									
I	4-3.2.8	1563-3	TRUCK LOAD FACILITY JP5	Load Rack - 3	Flow Control Valve	150 Class; Flanged Manual - LR-1-3	KAN-1563-3-DRFCVL-0001	CLA-VAL	UNK	4"									
I	4-3.2.8	1563-3	TRUCK LOADING FACILITY JP5	Load Rack - 3	Flow Control Valve	150 Class; Flanged Manual - LR-3-1	KAN-1563-3-DRFCVL-0002	CLA-VAL	UNK	3"									

RM Template v0.4.3

4

APPENDIX B - ATTACHMENT 3 RECURRING MAINTENANCE REPORT TEMPLATE

Contract47QSHA18D000Y W912DY21F0025

SiteKaneohe

Date26-Apr-22

RM Event(s)Q2, SA1, A BY

☒ Daily

☒ Weekly

☒ Monthly

☒ Quarterly

☒ Semi-annually

☒ Annually

☒ Every 3 years

☒ Every 5 years

☒ Every 10 years

Note: It is advised that "See Description" and "Reference to Other" always be displayed.

☒ See Description

☒ Reference to Other

☒ SM

☒ OM

Warning: Only adds Deficiencies marked "Y" in Col T.

Generate Deficiency List

RM Report Setup Only - See Instructions

Generate UFC Tasks

Applicable Facility Assets										UFC System Level Maintenance Frequency	Responsibility	RM Completion Record Result	Date Completed	Completed By	Deficiencies	Responsible FMSR	Notes	Add to Def List?
UFC Section Reference	Real Property Facility #	Real Property Facility Name	Operational Area	Component Type	Base Asset ID	Component Unique Identifier (CUID)	Make	Model	Capacity/Size									
I	6-1.3	1253	BULK FUEL STORAGE TANK F-24	Bulk Storage	Pipeline	Above Ground Pipeline	KAN-1253-AGPL-0003	UNK	UNK	4" X 160 LF								
I	6-1.3	1254	TRUCK OFFLOAD	Pump Station	Pipeline	Above Ground Pipeline	KAN-1254-AGPL-0001	UNK	UNK	6" X 70 LF								
I	6-1.3	1254	TRUCK OFFLOAD	Pump Station	Pipeline	Above Ground Pipeline	KAN-1254-AGPL-0002	UNK	UNK	4" X 120 LF								
I	6-1.3	1254	TRUCK OFFLOAD	Pump Station	Pipeline	Above Ground Pipeline	KAN-1254-AGPL-0003	UNK	UNK	1" X 200 LF								
I	6-1.3	6479	JET ENGINE FUEL STORAGE	Bulk Storage	Pipeline	Above Ground Pipeline	KAN-6479-AGPL-0001	UNK	UNK	6" X 100 LF								
I	6-1.3	6479	JET ENGINE FUEL STORAGE	Bulk Storage	Pipeline	Above Ground Pipeline	KAN-6479-AGPL-0002	UNK	UNK	1" X 140 LF								
I	6-1.3	6504	TRUCK LOAD/ OFFLOAD FACILITY	Load/Offload-Gas/DS-2/Bio-Deisel	Pipeline	Pipeline	KAN-6504-AGPL-0001	UNK	UNK	2" X 120 LF								
I	6-1.3	200835	POL PIPELINE	DISTRIBUTION SYSTEM FUEL OIL	Aboveground Piping	Aboveground Piping	KAN-200835-AGPL-0001	UNK	UNK	12,975 LF								
I	6-1.3	1254A	STRAINER FACILITY	STRAINER STATION	Pipeline	Pipeline	KAN-1254A-AGPL-0001	UNK	UNK	10" X 40 LF								
I	6-1.3	1254A	STRAINER FACILITY	STRAINER STATION	Pipeline	Pipeline	KAN-1254A-AGPL-0002	UNK	UNK	4" X 120 LF								
I	6-1.3	1563-1	TRUCK LOAD FACILITY JP5	Load Rack - 1	Pipeline	Above Ground Pipeline	KAN-1563_1-AGPL-0001	UNK	UNK	6" X 170 LF								
I	6-1.3	1563-2	TRUCK LOADING FACILITY JP5	Load Rack - 2	Pipeline	Above Ground Pipeline	KAN-1563_2-AGPL-0001	UNK	UNK	4" X 120 LF								
I	6-1.3	1563-3	TRUCK LOADING FACILITY JP5	Load Rack - 3	Pipeline	Above Ground Pipeline	KAN-1563_2-AGPL-0002	UNK	UNK	1" X 200 LF								
I	6-1.3	6506-1	MOGAS FUEL TANK	Military Service Station	Pipeline	Pipeline	KAN-6506_1-AGPL-0001	UNK	UNK	4" X 370 LF								
H	Plug Valves - Non-lubricated (Section 6-6.2.2)																	
T	A. Open and close valve to check for ease of operation. Adjust or replace packing as needed.										Quarterly	SM						
T	B. Inspect valve exterior for corrosion and tightness of bolts. Repaint and retighten as required.										Semi-annually	SM						
I	6-6.2.2	6479	JET ENGINE FUEL STORAGE	Pump Suction Line	Plug Valve	150 Class; Flanged 6479A-1	KAN-6479-NPLVL-0001	Mueller	UNK	14"								
I	6-6.2.2	6479	JET ENGINE FUEL STORAGE	Pump Suction Line	Plug Valve	150 Class; Flanged 6479A-2	KAN-6479-NPLVL-0002	Mueller	UNK	14"								
I	6-6.2.2	6479	JET ENGINE FUEL STORAGE	Pump Suction Line	Plug Valve	150 Class; Flanged 6479A-3	KAN-6479-NPLVL-0003	Mueller	UNK	14"								
H	Gate Valves (Section 6-6.2.3)																	
T	A. Open and close valve to check for ease of operation. Adjust or replace packing as needed.										Quarterly	SM						
T	B. Lubricate valve operator stem.										Semi-annually	SM						
T	C. Inspect valve exterior for corrosion and tightness of bolts. Repaint and retighten as required.										Semi-annually	SM						
	Note: Per PWS Touch-up Coating Repair																	
I	6-6.2.3	6503	FUEL STATION	Military Service Station	Gate Valve	Manual - 6503	KAN-6503-GTVL-0001	Apollo	UNK	1-1/2"								
I	6-6.2.3	6645	SMALL CRAFT FUEL STA AND STORAGE	Waterfront	Gate Valve	Gate Valve	KAN-6645-GTVL-0001	UNK	UNK	3"								
I	6-6.2.3	PL-FTPA	FUEL TRUCK PARKING AREA	FUEL TRUCK PARKING AREA	Gate Valve	PL-FTPA-1	KAN-PL_FTPA-GTVL-0001	UNK	UNK	2"								
I	6-6.2.3	PL-FTPA	FUEL TRUCK PARKING AREA	FUEL TRUCK PARKING AREA	Gate Valve	PL-FTPA-2	KAN-PL_FTPA-GTVL-0002	UNK	UNK	2"								
I	6-6.2.3	PL-FTPA	FUEL TRUCK PARKING AREA	FUEL TRUCK PARKING AREA	Gate Valve	PL-FTPA-3	KAN-PL_FTPA-GTVL-0003	UNK	UNK	2"								
I	6-6.2.3	PL-FTPA	FUEL TRUCK PARKING AREA	FUEL TRUCK PARKING AREA	Gate Valve	PL-FTPA-4	KAN-PL_FTPA-GTVL-0004	UNK	UNK	2"								
H	Ball Valves (Section 6-6.2.4)																	
T	E. Refer to Section 6-6.2.10 Manual Valve Gear Operators for inspection and maintenance of gear operators if equipped.										Reference to Other	SM						
T	A. Open and close valve to check for ease of operation.										Quarterly	SM						
T	B. Lubricate overhead ball valve chain operator gears.										Quarterly	SM						
T	C. Adjust packing per manufacturer's specifications.										Quarterly	SM						
T	D. Inspect valve exterior for corrosion and tightness of bolts. Repaint/tighten as required.										Quarterly	SM						
	Note: Per PWS Touch-up Coating Repair																	
I	6-6.2.4	149	Fuel Pier 149	Pier 149	Ball Valve	Valve no. 56; 150 Class; Flanged Manual	KAN-149-BLVL-0009	Apollo	UNK	2"								
I	6-6.2.4	149	Fuel Pier 149	Pier 149	Ball Valve	Valve no. 57; 150 Class; Flanged Manual	KAN-149-BLVL-0010	Apollo	UNK	2"								
I	6-6.2.4	149	Fuel Pier 149	Pier 149	Ball Valve	Ball Valve	KAN-149-BLVL-0001	UNK	UNK	2"								
I	6-6.2.4	149	Fuel Pier 149	Pier 149	Ball Valve	Ball Valve	KAN-149-BLVL-0002	UNK	UNK	2"								
I	6-6.2.4	149	Fuel Pier 149	Pier 149	Ball Valve	Ball Valve	KAN-149-BLVL-0003	UNK	UNK	1"								
I	6-6.2.4	149	Fuel Pier 149	Pier 149	Ball Valve	Ball Valve	KAN-149-BLVL-0004	UNK	UNK	1"								
I	6-6.2.4	149	Fuel Pier 149	Pier 149	Ball Valve	Ball Valve	KAN-149-BLVL-0005	UNK	UNK	1"								
I	6-6.2.4	149	Fuel Pier 149	Pier 149	Ball Valve	Ball Valve	KAN-149-BLVL-0006	UNK	UNK	1"								
I	6-6.2.4	149	Fuel Pier 149	Pier 149	Ball Valve	Ball Valve	KAN-149-BLVL-0007	UNK	UNK	1"								
I	6-6.2.4	149	Fuel Pier 149	Pier 149	Ball Valve	Ball Valve	KAN-149-BLVL-0008	UNK	UNK	1"								
I	6-6.2.4	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Ball Valve	150 Class; Flanged Manual - Pit A-1	KAN-1170-BLVL-0001	Apollo	UNK	4"								
I	6-6.2.4	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Ball Valve	150 Class; Flanged Manual - Pit A-2	KAN-1170-BLVL-0002	Apollo	UNK	4"								
I	6-6.2.4	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Ball Valve	150 Class; Flanged Manual - Pit A-3	KAN-1170-BLVL-0003	Apollo	UNK	4"								
I	6-6.2.4	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Ball Valve	150 Class; Flanged Manual - Pit A-4	KAN-1170-BLVL-0004	Apollo	UNK	1"								
I	6-6.2.4	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Ball Valve	150 Class; Flanged Manual - Pit A-5	KAN-1170-BLVL-0005	Apollo	UNK	1"								
I	6-6.2.4	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Ball Valve	150 Class; Flanged Manual - Pit B-1	KAN-1170-BLVL-0006	Apollo	UNK	4"								
I	6-6.2.4	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Ball Valve	150 Class; Flanged Manual - Pit B-2	KAN-1170-BLVL-0007	Apollo	UNK	4"								

RM Template v0.4.3

6

APPENDIX B - ATTACHMENT 3 RECURRING MAINTENANCE REPORT TEMPLATE

Contract

47QSHA18D000Y W912DY21F0025

Site

Kaneohe

Date

26-Apr-22

RM Event(s)

Q2, SA1, A BY

Region:

POH

☒ Daily

☒ Weekly

☒ Monthly

☒ Quarterly

☒ Semi-annually

☒ Annually

☒ Every 3 years

☒ Every 5 years

☒ Every 10 years

Note: It is advised that "See Description" and "Reference to Other" always be displayed.

☒ See Description

☒ Reference to Other

☒ SM

☒ OM

Warning: Only adds Deficiencies marked "Y" in Col T.

Generate Deficiency List

RM Report Setup Only - See Instructions

Generate UFC Tasks

Applicable Facility Assets										UFC System Level Maintenance Frequency	Responsibility	RM Completion Record Result	Date Completed	Completed By	Deficiencies	Responsible FMSR	Notes	Add to Def List?
UFC Section Reference	Real Property Facility #	Real Property Facility Name	Operational Area	Component Type	Base Asset ID	Component Unique Identifier (CUID)	Make	Model	Capacity/Size									
I	6-6.2.4	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Ball Valve	150 Class; Flanged Manual Pit B-3	KAN-1170-BLVL-0008	Apollo	UNK	4"								
I	6-6.2.4	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Ball Valve	150 Class; Flanged Manual Pit B-4	KAN-1170-BLVL-0009	Apollo	UNK	4"								
I	6-6.2.4	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Ball Valve	150 Class; Flanged Manual Pit B-5	KAN-1170-BLVL-0010	Apollo	UNK	1"								
I	6-6.2.4	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Ball Valve	150 Class; Flanged Manual Pit B-6	KAN-1170-BLVL-0011	Apollo	UNK	1"								
I	6-6.2.4	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Ball Valve	150 Class; Flanged Manual Pit C-1	KAN-1170-BLVL-0012	Apollo	UNK	4"								
I	6-6.2.4	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Ball Valve	150 Class; Flanged Manual Pit C-2	KAN-1170-BLVL-0013	Apollo	UNK	4"								
I	6-6.2.4	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Ball Valve	150 Class; Flanged Manual Pit C-3	KAN-1170-BLVL-0014	Apollo	UNK	4"								
I	6-6.2.4	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Ball Valve	150 Class; Flanged Manual Pit C-4	KAN-1170-BLVL-0015	Apollo	UNK	1"								
I	6-6.2.4	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Ball Valve	150 Class; Flanged Manual Pit C-5	KAN-1170-BLVL-0016	Apollo	UNK	1"								
I	6-6.2.4	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Ball Valve	150 Class; Flanged Manual Pit D-1	KAN-1170-BLVL-0017	Apollo	UNK	4"								
I	6-6.2.4	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Ball Valve	150 Class; Flanged Manual Pit D-2	KAN-1170-BLVL-0018	Apollo	UNK	4"								
I	6-6.2.4	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Ball Valve	150 Class; Flanged Manual Pit D-3	KAN-1170-BLVL-0019	Apollo	UNK	4"								
I	6-6.2.4	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Ball Valve	150 Class; Flanged Manual Pit D-4	KAN-1170-BLVL-0020	Apollo	UNK	1"								
I	6-6.2.4	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Ball Valve	150 Class; Flanged Manual Pit D-5	KAN-1170-BLVL-0021	Apollo	UNK	1"								
I	6-6.2.4	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Ball Valve	150 Class; Flanged Manual LP-SY1-1	KAN-1170-BLVL-0022	PBV-USA	UNK	2"								
I	6-6.2.4	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Ball Valve	150 Class; Flanged Manual LP-SY1-2	KAN-1170-BLVL-0023	PBV-USA	UNK	2"								
I	6-6.2.4	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Ball Valve	150 Class; Flanged Manual LP-SY2-1	KAN-1170-BLVL-0024	PBV-USA	UNK	2"								
I	6-6.2.4	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Ball Valve	150 Class; Flanged Manual LP-SY1-2	KAN-1170-BLVL-0025	PBV-USA	UNK	2"								
I	6-6.2.4	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Ball Valve	150 Class; Flanged Manual SY-1-1	KAN-1170-BLVL-0026	Taylor	UNK	6"								
I	6-6.2.4	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Ball Valve	150 Class; Flanged Manual SY-1-2	KAN-1170-BLVL-0027	Taylor	UNK	6"								
I	6-6.2.4	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Ball Valve	150 Class; Flanged Manual SY-1-3	KAN-1170-BLVL-0028	Taylor	UNK	6"								
I	6-6.2.4	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Ball Valve	150 Class; Flanged Manual SY-1-4	KAN-1170-BLVL-0029	Taylor	UNK	6"								
I	6-6.2.4	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Ball Valve	150 Class; Flanged Manual SY-1-5	KAN-1170-BLVL-0030	Taylor	UNK	4"								
I	6-6.2.4	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Ball Valve	150 Class; Flanged Manual SY-1-6	KAN-1170-BLVL-0031	Taylor	UNK	4"								
I	6-6.2.4	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Ball Valve	150 Class; Flanged Manual SY-1-7	KAN-1170-BLVL-0032	Taylor	UNK	2"								
I	6-6.2.4	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Ball Valve	150 Class; Flanged Manual SY-1-8	KAN-1170-BLVL-0033	Taylor	UNK	2"								
I	6-6.2.4	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Ball Valve	150 Class; Flanged Manual SY-1-9	KAN-1170-BLVL-0034	Taylor	UNK	2"								
I	6-6.2.4	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Ball Valve	150 Class; Flanged Manual SY-1-10	KAN-1170-BLVL-0035	Taylor	UNK	1"								
I	6-6.2.4	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Ball Valve	150 Class; Flanged Manual SY-1-11	KAN-1170-BLVL-0036	Taylor	UNK	1"								
I	6-6.2.4	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Ball Valve	150 Class; Flanged Manual SY-1-12	KAN-1170-BLVL-0037	Taylor	UNK	1"								
I	6-6.2.4	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Ball Valve	150 Class; Flanged Manual SY-1-13	KAN-1170-BLVL-0038	Taylor	UNK	1"								
I	6-6.2.4	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Ball Valve	150 Class; Flanged Manual SY-1-14	KAN-1170-BLVL-0039	Taylor	UNK	3/4"								
I	6-6.2.4	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Ball Valve	150 Class; Flanged Manual SY-1-15	KAN-1170-BLVL-0040	Taylor	UNK	3/4"								
I	6-6.2.4	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Ball Valve	150 Class; Flanged Manual SY-1-16	KAN-1170-BLVL-0041	Taylor	UNK	3/4"								
I	6-6.2.4	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Ball Valve	150 Class; Flanged Manual SY-1-17	KAN-1170-BLVL-0042	Taylor	UNK	3/4"								
I	6-6.2.4	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Ball Valve	150 Class; Flanged Manual SY-2-1	KAN-1170-BLVL-0043	Taylor	UNK	6"								
I	6-6.2.4	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Ball Valve	150 Class; Flanged Manual SY-2-2	KAN-1170-BLVL-0044	Taylor	UNK	6"								
I	6-6.2.4	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Ball Valve	150 Class; Flanged Manual SY-2-3	KAN-1170-BLVL-0045	Taylor	UNK	6"								
I	6-6.2.4	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Ball Valve	150 Class; Flanged Manual SY-2-4	KAN-1170-BLVL-0046	Taylor	UNK	6"								
I	6-6.2.4	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Ball Valve	150 Class; Flanged Manual SY-2-5	KAN-1170-BLVL-0047	Taylor	UNK	4"								
I	6-6.2.4	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Ball Valve	150 Class; Flanged Manual SY-2-6	KAN-1170-BLVL-0048	Taylor	UNK	4"								
I	6-6.2.4	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Ball Valve	150 Class; Flanged Manual SY-2-7	KAN-1170-BLVL-0049	Taylor	UNK	2"								
I	6-6.2.4	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Ball Valve	150 Class; Flanged Manual SY-2-8	KAN-1170-BLVL-0050	Taylor	UNK	2"								
I	6-6.2.4	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Ball Valve	150 Class; Flanged Manual SY-2-9	KAN-1170-BLVL-0051	Taylor	UNK	2"								
I	6-6.2.4	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Ball Valve	150 Class; Flanged Manual SY-2-10	KAN-1170-BLVL-0052	Taylor	UNK	1"								
I	6-6.2.4	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Ball Valve	150 Class; Flanged Manual SY-2-11	KAN-1170-BLVL-0053	Taylor	UNK	1"								
I	6-6.2.4	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Ball Valve	150 Class; Flanged Manual SY-2-12	KAN-1170-BLVL-0054	Taylor	UNK	1"								
I	6-6.2.4	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Ball Valve	150 Class; Flanged Manual SY-2-13	KAN-1170-BLVL-0055	Taylor	UNK	1"								

APPENDIX B - ATTACHMENT 3 RECURRING MAINTENANCE REPORT TEMPLATE

Contract

47QSHA18D000Y W912DY21F0025

Site

Kaneohe

Date

26-Apr-22

RM Event(s)

Q2, SA1, A BY

Region:

POH

☐ Daily

☐ Weekly

☐ Monthly

☐ Quarterly

☐ Semi-annually

☐ Annually

☐ Every 3 years

☐ Every 5 years

☐ Every 10 years

Note: It is advised that "See Description" and "Reference to Other" always be displayed.

☐ See Description

☐ Reference to Other

☐ SM

☐ OM

Warning: Only adds Deficiencies marked "Y" in Col T.

Generate Deficiency List

RM Report Setup Only - See Instructions

Generate UFC Tasks

Applicable Facility Assets										UFC System Level Maintenance Frequency	Responsibility	RM Completion Record Result	Date Completed	Completed By	Deficiencies	Responsible FMSR	Notes	Add to Def List?
UFC Section Reference	Real Property Facility #	Real Property Facility Name	Operational Area	Component Type	Base Asset ID	Component Unique Identifier (CUID)	Make	Model	Capacity/Size									
I	6-6.2.4	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Ball Valve	150 Class; Flanged Manual - SY-2-14	KAN-1170-BLVL-0056	Taylor	UNK	3/4"								
I	6-6.2.4	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Ball Valve	150 Class; Flanged Manual - SY-2-15	KAN-1170-BLVL-0057	Taylor	UNK	3/4"								
I	6-6.2.4	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Ball Valve	150 Class; Flanged Manual - SY-2-16	KAN-1170-BLVL-0058	Taylor	UNK	3/4"								
I	6-6.2.4	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Ball Valve	150 Class; Flanged Manual - SY-2-17	KAN-1170-BLVL-0059	Taylor	UNK	3/4"								
I	6-6.2.4	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Ball Valve	150 Class; Flanged Manual - BF-1	KAN-1170-BLVL-0060	Taylor	UNK	4"								
I	6-6.2.4	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Ball Valve	150 Class; Flanged Manual - BF-2	KAN-1170-BLVL-0061	Taylor	UNK	1"								
I	6-6.2.4	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Ball Valve	150 Class; Flanged Manual - BF-3	KAN-1170-BLVL-0062	Taylor	UNK	1"								
I	6-6.2.4	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Ball Valve	150 Class; Flanged Manual - BF-4	KAN-1170-BLVL-0063	Taylor	UNK	3/4"								
I	6-6.2.4	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Ball Valve	150 Class; Flanged Manual - BF-5	KAN-1170-BLVL-0064	Taylor	UNK	3/4"								
I	6-6.2.4	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Ball Valve	150 Class; Flanged Manual - F/S- Thred-1	KAN-1170-BLVL-0065	Taylor	UNK	1"								
I	6-6.2.4	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Ball Valve	150 Class; Flanged Manual - F/S- Thred-2	KAN-1170-BLVL-0066	Taylor	UNK	1"								
I	6-6.2.4	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Ball Valve	150 Class; Flanged Manual - F/S- Thred-3	KAN-1170-BLVL-0067	Taylor	UNK	3/4"								
I	6-6.2.4	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Ball Valve	150 Class; Flanged Manual - F/S- Thred-4	KAN-1170-BLVL-0068	Taylor	UNK	1/2"								
I	6-6.2.4	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Ball Valve	150 Class; Flanged Manual - F/S- Thred-5	KAN-1170-BLVL-0069	Taylor	UNK	1/2"								
I	6-6.2.4	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Ball Valve	150 Class; Flanged Manual - F/S- Thred-6	KAN-1170-BLVL-0070	Taylor	UNK	1/2"								
I	6-6.2.4	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Ball Valve	150 Class; Flanged Manual - F/S- Thred-7	KAN-1170-BLVL-0071	Taylor	UNK	1/2"								
I	6-6.2.4	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Ball Valve	150 Class; Flanged Manual - F/S- Thred-8	KAN-1170-BLVL-0072	Taylor	UNK	1/2"								
I	6-6.2.4	1252	BULK FUEL STORAGE TANK F-24	Bulk Storage	Ball Valve	150 Class; Flanged Manual - 1252-1	KAN-1252-BLVL-0001	Apollo	UNK	1"								
I	6-6.2.4	1252	BULK FUEL STORAGE TANK F-24	Bulk Storage	Ball Valve	150 Class; Flanged Manual - 1252-2	KAN-1252-BLVL-0002	Apollo	UNK	1"								
I	6-6.2.4	1252	BULK FUEL STORAGE TANK F-24	Bulk Storage	Ball Valve	150 Class; Flanged Manual - 1252-3	KAN-1252-BLVL-0003	Apollo	UNK	1"								
I	6-6.2.4	1252	BULK FUEL STORAGE TANK F-24	Bulk Storage	Ball Valve	150 Class; Flanged Manual - 1252-4	KAN-1252-BLVL-0004	Apollo	UNK	1"								
I	6-6.2.4	1252	BULK FUEL STORAGE TANK F-24	Bulk Storage	Ball Valve	150 Class; Flanged Manual - 1252-5	KAN-1252-BLVL-0005	Apollo	UNK	1"								
I	6-6.2.4	1252	BULK FUEL STORAGE TANK F-24	Bulk Storage	Ball Valve	150 Class; Flanged Manual - 1252-6	KAN-1252-BLVL-0006	Apollo	UNK	1"								
I	6-6.2.4	1252	BULK FUEL STORAGE TANK F-24	Bulk Storage	Ball Valve	150 Class; Flanged Manual - 1252-7	KAN-1252-BLVL-0007	Apollo	UNK	1"								
I	6-6.2.4	1252	BULK FUEL STORAGE TANK F-24	Bulk Storage	Ball Valve	150 Class; Flanged Manual - 1252-8	KAN-1252-BLVL-0008	Apollo	UNK	1"								
I	6-6.2.4	1252	BULK FUEL STORAGE TANK F-24	Bulk Storage	Ball Valve	150 Class; Flanged Manual - 1252-9	KAN-1252-BLVL-0009	Apollo	UNK	1"								
I	6-6.2.4	1252	BULK FUEL STORAGE TANK F-24	Bulk Storage	Ball Valve	150 Class; Flanged Manual - 1252-10	KAN-1252-BLVL-0010	Apollo	UNK	1"								
I	6-6.2.4	1252	BULK FUEL STORAGE TANK F-24	Bulk Storage	Ball Valve	150 Class; Flanged Manual - 1252-11	KAN-1252-BLVL-0011	Apollo	UNK	1"								
I	6-6.2.4	1252	BULK FUEL STORAGE TANK F-24	Bulk Storage	Ball Valve	150 Class; Flanged Manual - 1252-12	KAN-1252-BLVL-0012	Apollo	UNK	1"								
I	6-6.2.4	1252	BULK FUEL STORAGE TANK F-24	Bulk Storage	Ball Valve	150 Class; Flanged Manual - 1252-13	KAN-1252-BLVL-0013	Apollo	UNK	1"								
I	6-6.2.4	1252	BULK FUEL STORAGE TANK F-24	Bulk Storage	Ball Valve	150 Class; Flanged Manual - 1252-14	KAN-1252-BLVL-0014	Apollo	UNK	3/4"								
I	6-6.2.4	1252	BULK FUEL STORAGE TANK F-24	Bulk Storage	Ball Valve	150 Class; Flanged Manual - 1252-15	KAN-1252-BLVL-0015	Apollo	UNK	3/4"								
I	6-6.2.4	1253	BULK FUEL STORAGE TANK F-24	Bulk Storage	Ball Valve	150 Class; Flanged Manual - 1252-1	KAN-1253-BLVL-0001	Apollo	UNK	1"								
I	6-6.2.4	1253	BULK FUEL STORAGE TANK F-24	Bulk Storage	Ball Valve	150 Class; Flanged Manual - 1252-2	KAN-1253-BLVL-0002	Apollo	UNK	1"								
I	6-6.2.4	1253	BULK FUEL STORAGE TANK F-24	Bulk Storage	Ball Valve	150 Class; Flanged Manual - 1252-3	KAN-1253-BLVL-0003	Apollo	UNK	1"								
I	6-6.2.4	1253	BULK FUEL STORAGE TANK F-24	Bulk Storage	Ball Valve	150 Class; Flanged Manual - 1252-4	KAN-1253-BLVL-0004	Apollo	UNK	1"								
I	6-6.2.4	1253	BULK FUEL STORAGE TANK F-24	Bulk Storage	Ball Valve	150 Class; Flanged Manual - 1252-5	KAN-1253-BLVL-0005	Apollo	UNK	1"								
I	6-6.2.4	1253	BULK FUEL STORAGE TANK F-24	Bulk Storage	Ball Valve	150 Class; Flanged Manual - 1252-6	KAN-1253-BLVL-0006	Apollo	UNK	1"								
I	6-6.2.4	1253	BULK FUEL STORAGE TANK F-24	Bulk Storage	Ball Valve	150 Class; Flanged Manual - 1252-7	KAN-1253-BLVL-0007	Apollo	UNK	1"								
I	6-6.2.4	1253	BULK FUEL STORAGE TANK F-24	Bulk Storage	Ball Valve	150 Class; Flanged Manual - 1252-8	KAN-1253-BLVL-0008	Apollo	UNK	1"								
I	6-6.2.4	1253	BULK FUEL STORAGE TANK F-24	Bulk Storage	Ball Valve	150 Class; Flanged Manual - 1252-9	KAN-1253-BLVL-0009	Apollo	UNK	1"								
I	6-6.2.4	1253	BULK FUEL STORAGE TANK F-24	Bulk Storage	Ball Valve	150 Class; Flanged Manual - 1252-10	KAN-1253-BLVL-0010	Apollo	UNK	1"								
I	6-6.2.4	1253	BULK FUEL STORAGE TANK F-24	Bulk Storage	Ball Valve	150 Class; Flanged Manual - 1252-11	KAN-1253-BLVL-0011	Apollo	UNK	1"								
I	6-6.2.4	1253	BULK FUEL STORAGE TANK F-24	Bulk Storage	Ball Valve	150 Class; Flanged Manual - 1252-12	KAN-1253-BLVL-0012	Apollo	UNK	1"								
I	6-6.2.4	1253	BULK FUEL STORAGE TANK F-24	Bulk Storage	Ball Valve	150 Class; Flanged Manual - 1252-13	KAN-1253-BLVL-0013	Apollo	UNK	1"								
I	6-6.2.4	1253	BULK FUEL STORAGE TANK F-24	Bulk Storage	Ball Valve	150 Class; Flanged Manual - 1252-14	KAN-1253-BLVL-0014	Apollo	UNK	3/4"								
I	6-6.2.4	1253	BULK FUEL STORAGE TANK F-24	Bulk Storage	Ball Valve	150 Class; Flanged Manual - 1252-15	KAN-1253-BLVL-0015	Apollo	UNK	3/4"								

RM Template v0.4.3

8

APPENDIX B - ATTACHMENT 3 RECURRING MAINTENANCE REPORT TEMPLATE

Contract

47QSHA18D000Y W912DY21F0025

Site

Kaneohe

Date

26-Apr-22

RM Event(s)

Q2, SA1, A BY

Region:

POH

☒ Daily

☒ Weekly

☒ Monthly

☒ Quarterly

☒ Semi-annually

☒ Annually

☒ Every 3 years

☒ Every 5 years

☒ Every 10 years

Note: It is advised that "See Description" and "Reference to Other" always be displayed.

☒ See Description

☒ Reference to Other

☒ SM

☒ OM

Warning: Only adds Deficiencies marked "Y" in Col T.

Generate Deficiency List

RM Report Setup Only - See Instructions

Generate UFC Tasks

Applicable Facility Assets										UFC System Level Maintenance Frequency	Responsibility	RM Completion Record Result	Date Completed	Completed By	Deficiencies	Responsible FMSR	Notes	Add to Def List?
UFC Section Reference	Real Property Facility #	Real Property Facility Name	Operational Area	Component Type	Base Asset ID	Component Unique Identifier (CUID)	Make	Model	Capacity/Size									
I	6-6.2.4	1253	BULK FUEL STORAGE TANK F-24	Bulk Storage	Ball Valve	150 Class; Flanged Manual - 1252-16	KAN-1253-BLVL-0016	Apollo	UNK	3/4"								
I	6-6.2.4	1254	TRUCK OFFLOAD	Pump Station	Ball Valve	150 Class; Flanged 1254-21	KAN-1254-BLVL-0001	Apollo	Model 211	1"								
I	6-6.2.4	1254	TRUCK OFFLOAD	Pump Station	Ball Valve	150 Class; Flanged 1254-22	KAN-1254-BLVL-0002	Apollo	Model 211	1"								
I	6-6.2.4	1254	TRUCK OFFLOAD	Pump Station	Ball Valve	150 Class; Flanged 1254-23	KAN-1254-BLVL-0003	Apollo	UNK	1"								
I	6-6.2.4	1254	TRUCK OFFLOAD	Pump Station	Ball Valve	150 Class; Flanged 1254-24	KAN-1254-BLVL-0004	Apollo	Model 211	1"								
I	6-6.2.4	1254	TRUCK OFFLOAD	Pump Station	Ball Valve	150 Class; Flanged 1254-25	KAN-1254-BLVL-0005	Apollo	Model 211	1"								
I	6-6.2.4	1254	TRUCK OFFLOAD	Pump Station	Ball Valve	150 Class; Flanged 1254-26	KAN-1254-BLVL-0006	Apollo	Model 211	1"								
I	6-6.2.4	1254	TRUCK OFFLOAD	Pump Station	Ball Valve	150 Class; Flanged 1254-27	KAN-1254-BLVL-0007	Apollo	Model 211	1"								
I	6-6.2.4	1254	TRUCK OFFLOAD	Pump Station	Ball Valve	150 Class; Flanged 1254-1	KAN-1254-BLVL-0008	WCB Flow-Tek	UNK	4"								
I	6-6.2.4	1254	TRUCK OFFLOAD	Pump Station	Ball Valve	150 Class; Flanged 1254-2	KAN-1254-BLVL-0009	WCB Flow-Tek	UNK	4"								
I	6-6.2.4	1254	TRUCK OFFLOAD	Pump Station	Ball Valve	150 Class; Flanged 1254-3	KAN-1254-BLVL-0010	WCB Flow-Tek	UNK	4"								
I	6-6.2.4	1254	TRUCK OFFLOAD	Pump Station	Ball Valve	150 Class; Flanged 1254-4	KAN-1254-BLVL-0011	WCB Flow-Tek	UNK	4"								
I	6-6.2.4	1254	TRUCK OFFLOAD	Pump Station	Ball Valve	150 Class; Flanged 1254-5	KAN-1254-BLVL-0012	WCB Flow-Tek	UNK	4"								
I	6-6.2.4	1254	TRUCK OFFLOAD	Pump Station	Ball valve	150 Class; Flanged 1254-6	KAN-1254-BLVL-0013	WCB Flow-Tek	UNK	4"								
I	6-6.2.4	1254	TRUCK OFFLOAD	Pump Station	Ball valve	150 Class; Flanged 1254-7	KAN-1254-BLVL-0014	WCB Flow-Tek	UNK	4"								
I	6-6.2.4	1254	TRUCK OFFLOAD	Pump Station	Ball valve	150 Class; Flanged 1254-8	KAN-1254-BLVL-0015	WCB Flow-Tek	UNK	4"								
I	6-6.2.4	1254	TRUCK OFFLOAD	Pump Station	Ball Valve	150 Class; Flanged 1254-9	KAN-1254-BLVL-0016	WCB Flow-Tek	UNK	4"								
I	6-6.2.4	1254	TRUCK OFFLOAD	Pump Station	Ball Valve	150 Class; Flanged 1254-10	KAN-1254-BLVL-0017	WCB Flow-Tek	UNK	4"								
I	6-6.2.4	1254	TRUCK OFFLOAD	Pump Station	Ball Valve	150 Class; Flanged 1254-11	KAN-1254-BLVL-0018	WCB Flow-Tek	UNK	4"								
I	6-6.2.4	1254	TRUCK OFFLOAD	Pump Station	Ball Valve	150 Class; Flanged 1254-12	KAN-1254-BLVL-0019	WCB Flow-Tek	UNK	4"								
I	6-6.2.4	1254	TRUCK OFFLOAD	Pump Station	Ball Valve	150 Class; Flanged 1254-13	KAN-1254-BLVL-0020	WCB Flow-Tek	UNK	4"								
I	6-6.2.4	1254	TRUCK OFFLOAD	Pump Station	Ball Valve	150 Class; Flanged 1254-14	KAN-1254-BLVL-0021	WCB Flow-Tek	UNK	4"								
I	6-6.2.4	1254	TRUCK OFFLOAD	Pump Station	Ball Valve	150 Class; Flanged 1254-15	KAN-1254-BLVL-0022	WCB Flow-Tek	UNK	4"								
I	6-6.2.4	1254	TRUCK OFFLOAD	Pump Station	Ball Valve	150 Class; Flanged 1254-16	KAN-1254-BLVL-0023	WCB Flow-Tek	UNK	2"								
I	6-6.2.4	1254	TRUCK OFFLOAD	Pump Station	Ball Valve	150 Class; Flanged 1254-17	KAN-1254-BLVL-0024	WCB Flow-Tek	UNK	1"								
I	6-6.2.4	1254	TRUCK OFFLOAD	Pump Station	Ball Valve	150 Class; Flanged 1254-18	KAN-1254-BLVL-0025	WCB Flow-Tek	UNK	1"								
I	6-6.2.4	1254	TRUCK OFFLOAD	Pump Station	Ball Valve	150 Class; Flanged 1254-19	KAN-1254-BLVL-0026	WCB Flow-Tek	UNK	1"								
I	6-6.2.4	1254	TRUCK OFFLOAD	Pump Station	Ball Valve	150 Class; Flanged 1254-20	KAN-1254-BLVL-0027	UNK	UNK	1"								
I	6-6.2.4	1254	TRUCK OFFLOAD	Pump Station	Ball Valve	150 Class; Flanged/Flange - 1254-21	KAN-1254-BLVL-0028	Apollo	UNK	1"								
I	6-6.2.4	1254	TRUCK OFFLOAD	Pump Station	Ball Valve	150 Class; Flanged/Flange - 1254-22	KAN-1254-BLVL-0029	Apollo	UNK	1"								
I	6-6.2.4	1254	TRUCK OFFLOAD	Pump Station	Ball Valve	150 Class; Flanged/Flange - 1254-23	KAN-1254-BLVL-0030	Apollo	UNK	1"								
I	6-6.2.4	1254	TRUCK OFFLOAD	Pump Station	Ball Valve	150 Class; Flanged/Flange - 1254-24	KAN-1254-BLVL-0031	Apollo	UNK	1"								
I	6-6.2.4	1254	TRUCK OFFLOAD	Pump Station	Ball Valve	150 Class; Flanged/Flange - 1254-25	KAN-1254-BLVL-0032	Apollo	UNK	1"								
I	6-6.2.4	1254	TRUCK OFFLOAD	Pump Station	Ball Valve	150 Class; Flanged/Flange - 1254-26	KAN-1254-BLVL-0033	Apollo	UNK	1"								
I	6-6.2.4	1254	TRUCK OFFLOAD	Pump Station	Ball Valve	150 Class; Flanged/Flange - 1254-27	KAN-1254-BLVL-0034	Apollo	UNK	1"								
I	6-6.2.4	1254	TRUCK OFFLOAD	Pump Station	Ball Valve	150 Class; Flanged/Flange - 1254-28	KAN-1254-BLVL-0035	Apollo	UNK	1"								
I	6-6.2.4	1254	TRUCK OFFLOAD	Pump Station	Ball Valve	150 Class; Flanged/Flange - 1254-29	KAN-1254-BLVL-0036	Apollo	UNK	1"								
I	6-6.2.4	1254	TRUCK OFFLOAD	Pump Station	Ball Valve	150 Class; Flanged/Flange - 1254-30	KAN-1254-BLVL-0037	Apollo	UNK	3/4"								
I	6-6.2.4	1254	TRUCK OFFLOAD	Pump Station	Ball Valve	150 Class; Flanged/Flange - 1254-31	KAN-1254-BLVL-0038	Apollo	UNK	3/4"								
I	6-6.2.4	1254	TRUCK OFFLOAD	Pump Station	Ball Valve	150 Class; Flanged/Flange - 1254-32	KAN-1254-BLVL-0039	Apollo	UNK	3/4"								
I	6-6.2.4	1254	TRUCK OFFLOAD	Pump Station	Ball Valve	150 Class; Flanged/Flange - 1254-33	KAN-1254-BLVL-0040	Apollo	UNK	3/4"								

RM Template v0.4.3

9

APPENDIX B - ATTACHMENT 3 RECURRING MAINTENANCE REPORT TEMPLATE

Contract

47QSHA18D000Y W912DY21F0025

Site

Kaneohe

Date

26-Apr-22

RM Event(s)

Q2, SA1, A BY

Region:

POH

☒ Daily

☒ Weekly

☒ Monthly

☒ Quarterly

☒ Semi-annually

☒ Annually

☒ Every 3 years

☒ Every 5 years

☒ Every 10 years

Note: It is advised that "See Description" and "Reference to Other" always be displayed.

☒ See Description

☒ Reference to Other

☒ SM

☒ OM

Warning: Only adds Deficiencies marked "Y" in Col T.

Generate Deficiency List

RM Report Setup Only - See Instructions

Generate UFC Tasks

Applicable Facility Assets										UFC System Level Maintenance Frequency	Responsibility	RM Completion Record Result	Date Completed	Completed By	Deficiencies	Responsible FMSR	Notes	Add to Def List?
UFC Section Reference	Real Property Facility #	Real Property Facility Name	Operational Area	Component Type	Base Asset ID	Component Unique Identifier (CUID)	Make	Model	Capacity/Size									
I	6-6.2.4	1254	TRUCK OFFLOAD	Pump Station	Ball Valve	150 Class; Flanged/Flange - 1254-34	KAN-1254-BLVL-0041	Apollo	UNK	3/4"								
I	6-6.2.4	1254	TRUCK OFFLOAD	Pump Station	Ball Valve	150 Class; Flanged/Flange - 1254-35	KAN-1254-BLVL-0042	Apollo	UNK	3/4"								
I	6-6.2.4	1254	TRUCK OFFLOAD	Pump Station	Ball Valve	150 Class; Flanged/Flange - 1254-36	KAN-1254-BLVL-0043	Apollo	UNK	3/4"								
I	6-6.2.4	1254	TRUCK OFFLOAD	Pump Station	Ball Valve	150 Class; Flanged/Flange - 1254-37	KAN-1254-BLVL-0044	Apollo	UNK	3/4"								
I	6-6.2.4	1254	TRUCK OFFLOAD	Pump Station	Ball Valve	150 Class; Flanged/Flange - 1254-38	KAN-1254-BLVL-0045	Apollo	UNK	3/4"								
I	6-6.2.4	1254	TRUCK OFFLOAD	Pump Station	Ball Valve	150 Class; Flanged/Flange - 1254-39	KAN-1254-BLVL-0046	Apollo	UNK	3/4"								
I	6-6.2.4	1254	TRUCK OFFLOAD	Pump Station	Ball Valve	150 Class; Flanged/Flange - 1254-40	KAN-1254-BLVL-0047	Apollo	UNK	3/4"								
I	6-6.2.4	1254	TRUCK OFFLOAD	Pump Station	Ball Valve	150 Class; Flanged/Flange - 1254-41	KAN-1254-BLVL-0048	Apollo	UNK	3/4"								
I	6-6.2.4	1254	TRUCK OFFLOAD	Pump Station	Ball Valve	150 Class; Flanged/Flange - 1254-42	KAN-1254-BLVL-0049	Apollo	UNK	3/4"								
I	6-6.2.4	1254	TRUCK OFFLOAD	Pump Station	Ball Valve	150 Class; Flanged/Flange - 1254-43	KAN-1254-BLVL-0050	Apollo	UNK	3/4"								
I	6-6.2.4	1254	TRUCK OFFLOAD	Pump Station	Ball Valve	150 Class; Flanged/Flange - 1254-44	KAN-1254-BLVL-0051	Apollo	UNK	3/4"								
I	6-6.2.4	1254	TRUCK OFFLOAD	Pump Station	Ball Valve	150 Class; Flanged/Flange - 1254-45	KAN-1254-BLVL-0052	Apollo	UNK	3/4"								
I	6-6.2.4	1254	TRUCK OFFLOAD	Pump Station	Ball Valve	150 Class; Flanged/Flange - 1254-46	KAN-1254-BLVL-0053	Apollo	UNK	3/4"								
I	6-6.2.4	1254	TRUCK OFFLOAD	Pump Station	Ball Valve	150 Class; Flanged/Flange - 1254-47	KAN-1254-BLVL-0054	Apollo	UNK	3/4"								
I	6-6.2.4	1254	TRUCK OFFLOAD	Pump Station	Ball Valve	150 Class; Flanged/Flange - 1254-48	KAN-1254-BLVL-0055	Apollo	UNK	3/4"								
I	6-6.2.4	1254	TRUCK OFFLOAD	Pump Station	Ball Valve	150 Class; Flanged/Flange - 1254-49	KAN-1254-BLVL-0056	Apollo	UNK	3/4"								
I	6-6.2.4	1254	TRUCK OFFLOAD	Pump Station	Ball Valve	150 Class; Flanged/Flange - 1254-50	KAN-1254-BLVL-0057	Apollo	UNK	3/4"								
I	6-6.2.4	1254	TRUCK OFFLOAD	Pump Station	Ball Valve	150 Class; Flanged/Flange - 1254-51	KAN-1254-BLVL-0058	Apollo	UNK	3/4"								
I	6-6.2.4	1254	TRUCK OFFLOAD	Pump Station	Ball Valve	150 Class; Flanged/Flange - 1254-52	KAN-1254-BLVL-0059	Apollo	UNK	3/4"								
I	6-6.2.4	1254	TRUCK OFFLOAD	Pump Station	Ball Valve	150 Class; Flanged/Flange - 1254-53	KAN-1254-BLVL-0060	Apollo	UNK	3/4"								
I	6-6.2.4	1254	TRUCK OFFLOAD	Pump Station	Ball Valve	150 Class; Flanged/Flange - 1254-54	KAN-1254-BLVL-0061	Apollo	UNK	3/4"								
I	6-6.2.4	1254	TRUCK OFFLOAD	Pump Station	Ball Valve	150 Class; Flanged/Flange - 1254-55	KAN-1254-BLVL-0062	Apollo	UNK	3/4"								
I	6-6.2.4	6479	JET ENGINE FUEL STORAGE	Supply Line	Ball Valve	150 Class; Flanged 6479A-4	KAN-6479-BLVL-0001	General Valve Co	Model 211	8"								
I	6-6.2.4	6479	JET ENGINE FUEL STORAGE	Supply Line	Ball Valve	150 Class; Flanged 6479A-5	KAN-6479-BLVL-0002	General Valve Co	Model 211	8"								
I	6-6.2.4	6479	JET ENGINE FUEL STORAGE	Supply Line	Ball Valve	150 Class; Flanged 6479A-6	KAN-6479-BLVL-0003	General Valve Co	Model 211	8"								
I	6-6.2.4	6479	JET ENGINE FUEL STORAGE	Supply Line	Ball Valve	150 Class; Flanged 6479A-7	KAN-6479-BLVL-0004	Mueller	UNK	8"								
I	6-6.2.4	6479	JET ENGINE FUEL STORAGE	Supply Line	Ball Valve	150 Class; Flanged 6479A-8	KAN-6479-BLVL-0005	Mueller	UNK	6"								
I	6-6.2.4	6479	JET ENGINE FUEL STORAGE	Supply Line	Ball Valve	150 Class; Flanged 6479A-9	KAN-6479-BLVL-0006	Mueller	UNK	6"								
I	6-6.2.4	6479	JET ENGINE FUEL STORAGE	Supply Line	Ball Valve	150 Class; Flanged 6479A-10	KAN-6479-BLVL-0007	Mueller	UNK	3"								
I	6-6.2.4	6479	JET ENGINE FUEL STORAGE	Supply Line	Ball Valve	150 Class; Flanged 6479A-11	KAN-6479-BLVL-0008	Mueller	UNK	3"								
I	6-6.2.4	6479	JET ENGINE FUEL STORAGE	Supply Line	Ball valve	150 Class; Flanged 6479A-12	KAN-6479-BLVL-0009	Taylor	UNK	2"								
I	6-6.2.4	6479	JET ENGINE FUEL STORAGE	Supply Line	Ball valve	150 Class; Flanged 6479A-13	KAN-6479-BLVL-0010	Taylor	UNK	2"								
I	6-6.2.4	6479	JET ENGINE FUEL STORAGE	Supply Line	Ball valve	150 Class; Flanged 6479A-14	KAN-6479-BLVL-0011	Taylor	UNK	2"								
I	6-6.2.4	6479	JET ENGINE FUEL STORAGE	Supply Line	Ball valve	150 Class; Flanged 6479A-15	KAN-6479-BLVL-0012	Taylor	UNK	3/4"								
I	6-6.2.4	6479	JET ENGINE FUEL STORAGE	Supply Line	Ball valve	150 Class; Flanged 6479A-16	KAN-6479-BLVL-0013	Taylor	UNK	3/4"								
I	6-6.2.4	6479	JET ENGINE FUEL STORAGE	Supply Line	Ball valve	150 Class; Flanged 6479A-17	KAN-6479-BLVL-0014	Taylor	UNK	3/4"								
I	6-6.2.4	6479	JET ENGINE FUEL STORAGE	Supply Line	Ball valve	150 Class; Flanged 6479A-18	KAN-6479-BLVL-0015	Taylor	UNK	3/4"								

RM Template v0.4.3

10

APPENDIX B - ATTACHMENT 3 RECURRING MAINTENANCE REPORT TEMPLATE

Contract

47QSHA18D000Y W912DY21F0025

Site

Kaneohe

Date

26-Apr-22

RM Event(s)

Q2, SA1, A BY

Region:

POH

☐ Daily

☐ Weekly

☐ Monthly

☐ Quarterly

☐ Semi-annually

☐ Annually

☐ Every 3 years

☐ Every 5 years

☐ Every 10 years

Note: It is advised that "See Description" and "Reference to Other" always be displayed.

☐ See Description

☐ Reference to Other

☐ SM

☐ OM

Warning: Only adds Deficiencies marked "Y" in Col T.

Generate Deficiency List

RM Report Setup Only - See Instructions

Generate UFC Tasks

Applicable Facility Assets										UFC System Level Maintenance Frequency	Responsibility	RM Completion Record Result	Date Completed	Completed By	Deficiencies	Responsible FMSR	Notes	Add to Def List?
UFC Section Reference	Real Property Facility #	Real Property Facility Name	Operational Area	Component Type	Base Asset ID	Component Unique Identifier (CUID)	Make	Model	Capacity/Size									
I	6-6.2.4	6479	JET ENGINE FUEL STORAGE	Supply Line	Ball valve	150 Class; Flanged 6479A-19	KAN-6479-BLVL-0016	Taylor	UNK	3/4"								
I	6-6.2.4	6479	JET ENGINE FUEL STORAGE	Supply Line	Ball valve	150 Class; Flanged 6479A-20	KAN-6479-BLVL-0017	Taylor	UNK	3/4"								
I	6-6.2.4	6479	JET ENGINE FUEL STORAGE	Supply Line	Ball valve	150 Class; Flanged 6479A-21	KAN-6479-BLVL-0018	Taylor	UNK	3/4"								
I	6-6.2.4	6479	JET ENGINE FUEL STORAGE	Supply Line	Ball valve	150 Class; Flanged 6479A-22	KAN-6479-BLVL-0019	Taylor	UNK	3/4"								
I	6-6.2.4	6479	JET ENGINE FUEL STORAGE	Supply Line	Ball valve	150 Class; Flanged 6479A-23	KAN-6479-BLVL-0020	Taylor	UNK	3/4"								
I	6-6.2.4	6479	JET ENGINE FUEL STORAGE	Supply Line	Ball valve	150 Class; Flanged 6479A-24	KAN-6479-BLVL-0021	Taylor	UNK	3/4"								
I	6-6.2.4	6479	JET ENGINE FUEL STORAGE	Bulk Storage	Ball Valve	150 Class; Flanged Manual - 6479B - 1	KAN-6479-BLVL-0022	Taylor	UNK	6"								
I	6-6.2.4	6479	JET ENGINE FUEL STORAGE	Bulk Storage	Ball Valve	150 Class; Flanged Manual - 6479B - 2	KAN-6479-BLVL-0023	Taylor	UNK	6"								
I	6-6.2.4	6479	JET ENGINE FUEL STORAGE	Bulk Storage	Ball Valve	150 Class; Flanged Manual - 6479B - 3	KAN-6479-BLVL-0024	Taylor	UNK	6"								
I	6-6.2.4	6479	JET ENGINE FUEL STORAGE	Bulk Storage	Ball Valve	150 Class; Flanged Manual - 6479B - 4	KAN-6479-BLVL-0025	Taylor	UNK	6"								
I	6-6.2.4	6479	JET ENGINE FUEL STORAGE	Bulk Storage	Ball Valve	150 Class; Flanged Manual - 6479B - 5	KAN-6479-BLVL-0026	Taylor	UNK	6"								
I	6-6.2.4	6479	JET ENGINE FUEL STORAGE	Bulk Storage	Ball Valve	150 Class; Flanged Manual - 6479B - 6	KAN-6479-BLVL-0027	Taylor	UNK	3"								
I	6-6.2.4	6479	JET ENGINE FUEL STORAGE	Bulk Storage	Ball Valve	150 Class; Flanged Manual - 6479B - 7	KAN-6479-BLVL-0028	Taylor	UNK	3"								
I	6-6.2.4	6479	JET ENGINE FUEL STORAGE	Bulk Storage	Ball Valve	150 Class; Flanged Manual - 6479A - 25	KAN-6479-BLVL-0029	Taylor	UNK	3/4"								
I	6-6.2.4	6479	JET ENGINE FUEL STORAGE	Bulk Storage	Ball Valve	150 Class; Flanged Manual - 6479A - 26	KAN-6479-BLVL-0030	Taylor	UNK	3/4"								
I	6-6.2.4	6479	JET ENGINE FUEL STORAGE	Bulk Storage	Ball Valve	150 Class; Flanged Manual - 6479A - 27	KAN-6479-BLVL-0031	Taylor	UNK	3/4"								
I	6-6.2.4	6479	JET ENGINE FUEL STORAGE	Bulk Storage	Ball Valve	150 Class; Flanged Manual - 6479A - 28	KAN-6479-BLVL-0032	Taylor	UNK	3/4"								
I	6-6.2.4	6479	JET ENGINE FUEL STORAGE	Bulk Storage	Ball Valve	150 Class; Flanged Manual - 6479A - 29	KAN-6479-BLVL-0033	Taylor	UNK	3/4"								
I	6-6.2.4	6479	JET ENGINE FUEL STORAGE	Bulk Storage	Ball Valve	150 Class; Flanged Manual - 6479A - 30	KAN-6479-BLVL-0034	Taylor	UNK	3/4"								
I	6-6.2.4	6479	JET ENGINE FUEL STORAGE	Bulk Storage	Ball Valve	150 Class; Flanged Manual - 6479A - 31	KAN-6479-BLVL-0035	Taylor	UNK	3/4"								
I	6-6.2.4	6479	JET ENGINE FUEL STORAGE	Bulk Storage	Ball Valve	150 Class; Flanged Manual - 6479A - 32	KAN-6479-BLVL-0036	Taylor	UNK	3/4"								
I	6-6.2.4	6479	JET ENGINE FUEL STORAGE	Bulk Storage	Ball Valve	150 Class; Flanged Manual - 6479A - 33	KAN-6479-BLVL-0037	Taylor	UNK	3/4"								
I	6-6.2.4	6479	JET ENGINE FUEL STORAGE	Bulk Storage	Ball Valve	150 Class; Flanged Manual - 6479A - 34	KAN-6479-BLVL-0038	Taylor	UNK	3/4"								
I	6-6.2.4	6479	JET ENGINE FUEL STORAGE	Bulk Storage	Ball Valve	150 Class; Flanged Manual - 6479A - 35	KAN-6479-BLVL-0039	Taylor	UNK	3/4"								
I	6-6.2.4	6479	JET ENGINE FUEL STORAGE	Bulk Storage	Ball Valve	150 Class; Flanged Manual - 6479A - 36	KAN-6479-BLVL-0040	Taylor	UNK	3/4"								
I	6-6.2.4	6479	JET ENGINE FUEL STORAGE	Bulk Storage	Ball Valve	150 Class; Flanged Manual - 6479A - 37	KAN-6479-BLVL-0041	Taylor	UNK	3/4"								
I	6-6.2.4	6479	JET ENGINE FUEL STORAGE	Bulk Storage	Ball Valve	150 Class; Flanged Manual - 6479A - 38	KAN-6479-BLVL-0042	Taylor	UNK	3/4"								
I	6-6.2.4	6479	JET ENGINE FUEL STORAGE	Bulk Storage	Ball Valve	150 Class; Flanged Manual - 6479A - 39	KAN-6479-BLVL-0043	Taylor	UNK	3/4"								
I	6-6.2.4	6479	JET ENGINE FUEL STORAGE	Bulk Storage	Ball Valve	150 Class; Flanged Manual - 6479A - 40	KAN-6479-BLVL-0044	Taylor	UNK	3/4"								
I	6-6.2.4	6479	JET ENGINE FUEL STORAGE	Bulk Storage	Ball Valve	150 Class; Flanged Manual - 6479A - 41	KAN-6479-BLVL-0045	Taylor	UNK	3/4"								
I	6-6.2.4	6479	JET ENGINE FUEL STORAGE	Bulk Storage	Ball Valve	150 Class; Flanged Manual - 6479B - 1	KAN-6479-BLVL-0046	Taylor	UNK	2"								
I	6-6.2.4	6479	JET ENGINE FUEL STORAGE	Bulk Storage	Ball Valve	150 Class; Flanged Manual - 6479B - 2	KAN-6479-BLVL-0047	Taylor	UNK	1"								
I	6-6.2.4	6479	JET ENGINE FUEL STORAGE	Bulk Storage	Ball Valve	150 Class; Flanged Manual - 6479B - 3	KAN-6479-BLVL-0048	Taylor	UNK	1"								
I	6-6.2.4	6479	JET ENGINE FUEL STORAGE	Bulk Storage	Ball Valve	150 Class; Flanged Manual - 6479B - 4	KAN-6479-BLVL-0049	Taylor	UNK	1"								
I	6-6.2.4	6479	JET ENGINE FUEL STORAGE	Bulk Storage	Ball Valve	150 Class; Flanged Manual - 6479B - 5	KAN-6479-BLVL-0050	Taylor	UNK	1"								
I	6-6.2.4	6479	JET ENGINE FUEL STORAGE	Bulk Storage	Ball Valve	150 Class; Flanged Manual - 6479B - 6	KAN-6479-BLVL-0051	Taylor	UNK	1"								
I	6-6.2.4	6479	JET ENGINE FUEL STORAGE	Bulk Storage	Ball Valve	150 Class; Flanged Manual - 6479B - 7	KAN-6479-BLVL-0052	Taylor	UNK	1"								
I	6-6.2.4	6479	JET ENGINE FUEL STORAGE	Bulk Storage	Ball Valve	150 Class; Flanged Manual - 6479B - 8	KAN-6479-BLVL-0053	Taylor	UNK	1"								
I	6-6.2.4	6479	JET ENGINE FUEL STORAGE	Bulk Storage	Ball Valve	150 Class; Flanged Manual - 6479B - 9	KAN-6479-BLVL-0054	Taylor	UNK	1"								
I	6-6.2.4	6479	JET ENGINE FUEL STORAGE	Bulk Storage	Ball Valve	150 Class; Flanged Manual - 6479B - 10	KAN-6479-BLVL-0055	Taylor	UNK	1"								
I	6-6.2.4	6479	JET ENGINE FUEL STORAGE	Bulk Storage	Ball Valve	150 Class; Flanged Manual - 6479B - 11	KAN-6479-BLVL-0056	Taylor	UNK	1"								
I	6-6.2.4	6479	JET ENGINE FUEL STORAGE	Bulk Storage	Ball Valve	150 Class; Flanged Manual - 6479B - 12	KAN-6479-BLVL-0057	Taylor	UNK	1"								
I	6-6.2.4	6479	JET ENGINE FUEL STORAGE	Bulk Storage	Ball Valve	150 Class; Flanged Manual - 6479B - 13	KAN-6479-BLVL-0058	Taylor	UNK	1"								
I	6-6.2.4	6479	JET ENGINE FUEL STORAGE	Bulk Storage	Ball Valve	150 Class; Flanged Manual - 6479B - 14	KAN-6479-BLVL-0059	Taylor	UNK	1"								
I	6-6.2.4	6479	JET ENGINE FUEL STORAGE	Bulk Storage	Ball Valve	150 Class; Flanged Manual - 6479B - 15	KAN-6479-BLVL-0060	Taylor	UNK	1"								
I	6-6.2.4	6479	JET ENGINE FUEL STORAGE	Bulk Storage	Ball Valve	150 Class; Flanged Manual - 6479B - 16	KAN-6479-BLVL-0061	Taylor	UNK	1"								
I	6-6.2.4	6479	JET ENGINE FUEL STORAGE	Bulk Storage	Ball Valve	150 Class; Flanged Manual - 6479B - 17	KAN-6479-BLVL-0062	Taylor	UNK	1"								
I	6-6.2.4	6479	JET ENGINE FUEL STORAGE	Bulk Storage	Ball Valve	150 Class; Flanged Manual - 6479B - 18	KAN-6479-BLVL-0063	Taylor	UNK	1"								

RM Template v0.4.3

11

APPENDIX B - ATTACHMENT 3 RECURRING MAINTENANCE REPORT TEMPLATE

Contract

47QSHA18D000Y W912DY21F0025

Site

Kaneohe

Date

26-Apr-22

RM Event(s)

Q2, SA1, A BY

Region:

POH

☐ Daily

☐ Weekly

☐ Monthly

☐ Quarterly

☐ Semi-annually

☐ Annually

☐ Every 3 years

☐ Every 5 years

☐ Every 10 years

Note: It is advised that "See Description" and "Reference to Other" always be displayed.

☐ See Description

☐ Reference to Other

☐ SM

☐ OM

Warning: Only adds Deficiencies marked "Y" in Col T.

Generate Deficiency List

RM Report Setup Only - See Instructions

Generate UFC Tasks

Applicable Facility Assets										UFC System Level Maintenance Frequency	Responsibility	RM Completion Record Result	Date Completed	Completed By	Deficiencies	Responsible FMSR	Notes	Add to Def List?
UFC Section Reference	Real Property Facility #	Real Property Facility Name	Operational Area	Component Type	Base Asset ID	Component Unique Identifier (CUID)	Make	Model	Capacity/Size									
I	6-6.2.4	6479	JET ENGINE FUEL STORAGE	Bulk Storage	Ball Valve	150 Class; Flanged Manual - 6479B - 19	KAN-6479-BLVL-0064	Taylor	UNK	1"								
I	6-6.2.4	6479	JET ENGINE FUEL STORAGE	Bulk Storage	Ball Valve	150 Class; Flanged Manual - 6479B - 20	KAN-6479-BLVL-0065	Taylor	UNK	1"								
I	6-6.2.4	6479	JET ENGINE FUEL STORAGE	Bulk Storage	Ball Valve	150 Class; Flanged Manual - 6479B - 21	KAN-6479-BLVL-0066	Taylor	UNK	1"								
I	6-6.2.4	6479	JET ENGINE FUEL STORAGE	Bulk Storage	Ball Valve	150 Class; Flanged Manual - 6479B - 22	KAN-6479-BLVL-0067	Taylor	UNK	1"								
I	6-6.2.4	6479	JET ENGINE FUEL STORAGE	Bulk Storage	Ball Valve	150 Class; Flanged Manual - 6479B - 23	KAN-6479-BLVL-0068	Taylor	UNK	1"								
I	6-6.2.4	6479	JET ENGINE FUEL STORAGE	Bulk Storage	Ball Valve	150 Class; Flanged Manual - 6479B - 24	KAN-6479-BLVL-0069	Taylor	UNK	1"								
I	6-6.2.4	6479	JET ENGINE FUEL STORAGE	Bulk Storage	Ball Valve	150 Class; Flanged Manual - 6479B - 25	KAN-6479-BLVL-0070	Taylor	UNK	1"								
I	6-6.2.4	6479	JET ENGINE FUEL STORAGE	Bulk Storage	Ball Valve	150 Class; Flanged Manual - 6479B - 26	KAN-6479-BLVL-0071	Taylor	UNK	1"								
I	6-6.2.4	6479	JET ENGINE FUEL STORAGE	Bulk Storage	Ball Valve	150 Class; Flanged Manual - 6479B - 27	KAN-6479-BLVL-0072	Taylor	UNK	1"								
I	6-6.2.4	6479	JET ENGINE FUEL STORAGE	Bulk Storage	Ball Valve	150 Class; Flanged Manual - 6479B - 28	KAN-6479-BLVL-0073	Taylor	UNK	1"								
I	6-6.2.4	6479	JET ENGINE FUEL STORAGE	Bulk Storage	Ball Valve	150 Class; Flanged Manual - 6479B - 29	KAN-6479-BLVL-0074	Taylor	UNK	1"								
I	6-6.2.4	6479	JET ENGINE FUEL STORAGE	Bulk Storage	Ball Valve	150 Class; Flanged Manual - 6479B - 30	KAN-6479-BLVL-0075	Taylor	UNK	1"								
I	6-6.2.4	6479	JET ENGINE FUEL STORAGE	Bulk Storage	Ball Valve	150 Class; Flanged Manual - 6479B - 31	KAN-6479-BLVL-0076	Taylor	UNK	1"								
I	6-6.2.4	6479	JET ENGINE FUEL STORAGE	Bulk Storage	Ball Valve	150 Class; Flanged Manual - 6479B - 32	KAN-6479-BLVL-0077	Taylor	UNK	1"								
I	6-6.2.4	6479	JET ENGINE FUEL STORAGE	Bulk Storage	Ball Valve	150 Class; Flanged Manual - 6479B - 33	KAN-6479-BLVL-0078	Taylor	UNK	1"								
I	6-6.2.4	6479	JET ENGINE FUEL STORAGE	Bulk Storage	Ball Valve	150 Class; Flanged Manual - 6479B - 34	KAN-6479-BLVL-0079	Taylor	UNK	1"								
I	6-6.2.4	6479	JET ENGINE FUEL STORAGE	Bulk Storage	Ball Valve	150 Class; Flanged Manual - 6479B - 35	KAN-6479-BLVL-0080	Taylor	UNK	1"								
I	6-6.2.4	6503	FUEL STATION	Military Service Station	Ball Valve	Manual - 6503	KAN-6503-BLVL-0001	Apollo	UNK	1-1/2"								
I	6-6.2.4	6504	TRUCK LOAD/ OFFLOAD FACILITY	Load/Offload-Gas/DS-2/Bio-Deisel	Ball Valve	150 Class; Flanged 6504-1	KAN-6504-BLVL-0001	WCB Flow-Tek	UNK	4"								
I	6-6.2.4	6504	TRUCK LOAD/ OFFLOAD FACILITY	Load/Offload-Gas/DS-2/Bio-Deisel	Ball Valve	150 Class; Flanged 6504-2	KAN-6504-BLVL-0002	WCB Flow-Tek	UNK	4"								
I	6-6.2.4	6504	TRUCK LOAD/ OFFLOAD FACILITY	Load/Offload-Gas/DS-2/Bio-Deisel	Ball Valve	150 Class; Flanged 6504-3	KAN-6504-BLVL-0003	WCB Flow-Tek	UNK	4"								
I	6-6.2.4	6504	TRUCK LOAD/ OFFLOAD FACILITY	Load/Offload-Gas/DS-2/Bio-Deisel	Ball Valve	150 Class; Flanged 6504-4	KAN-6504-BLVL-0004	WCB Flow-Tek	UNK	4"								
I	6-6.2.4	6504	TRUCK LOAD/ OFFLOAD FACILITY	Load/Offload-Gas/DS-2/Bio-Deisel	Ball Valve	150 Class; Flanged 6504-5	KAN-6504-BLVL-0005	WCB Flow-Tek	UNK	4"								
I	6-6.2.4	6504	TRUCK LOAD/ OFFLOAD FACILITY	Load/Offload-Gas/DS-2/Bio-Deisel	Ball Valve	150 Class; Flanged 6504-6	KAN-6504-BLVL-0006	WCB Flow-Tek	UNK	4"								
I	6-6.2.4	6504	TRUCK LOAD/ OFFLOAD FACILITY	Load/Offload-Gas/DS-2/Bio-Deisel	Ball Valve	150 Class; Flanged 6504-7	KAN-6504-BLVL-0007	WCB Flow-Tek	UNK	4"								
I	6-6.2.4	6504	TRUCK LOAD/ OFFLOAD FACILITY	Load/Offload-Gas/DS-2/Bio-Deisel	Ball Valve	150 Class; Flanged 6504-8	KAN-6504-BLVL-0008	WCB Flow-Tek	UNK	4"								
I	6-6.2.4	6504	TRUCK LOAD/ OFFLOAD FACILITY	Load/Offload-Gas/DS-2/Bio-Deisel	Ball Valve	150 Class; Flanged 6504-9	KAN-6504-BLVL-0009	WCB Flow-Tek	UNK	4"								
I	6-6.2.4	6504	TRUCK LOAD/ OFFLOAD FACILITY	Load/Offload-Gas/DS-2/Bio-Deisel	Ball Valve	150 Class; Flanged 6504-10	KAN-6506-BLVL-0027	UNK	UNK	4"								
I	6-6.2.4	6504	TRUCK LOAD/ OFFLOAD FACILITY	Load/Offload-Gas/DS-2/Bio-Deisel	Ball Valve	150 Class; Flanged 6504-11	KAN-6506-BLVL-0028	UNK	UNK	2"								
I	6-6.2.4	6504	TRUCK LOAD/ OFFLOAD FACILITY	Load/Offload-Gas/DS-2/Bio-Deisel	Ball Valve	Manual - 6504A	KAN-6504-BLVL-0012	Apollo	UNK	2"								
I	6-6.2.4	6504	TRUCK LOAD/ OFFLOAD FACILITY	Load/Offload-Gas/DS-2/Bio-Deisel	Ball Valve	150 Class; Flanged Manual - 6504-12	KAN-6504-BLVL-0013	Taylor	UNK	3"								
I	6-6.2.4	6504	TRUCK LOAD/ OFFLOAD FACILITY	Load/Offload-Gas/DS-2/Bio-Deisel	Ball Valve	150 Class; Flanged Manual - 6504-13	KAN-6504-BLVL-0014	Taylor	UNK	1"								
I	6-6.2.4	6504	TRUCK LOAD/ OFFLOAD FACILITY	Load/Offload-Gas/DS-2/Bio-Deisel	Ball Valve	150 Class; Flanged Manual - 6504-14	KAN-6504-BLVL-0015	Taylor	UNK	3/4"								
I	6-6.2.4	6504	TRUCK LOAD/ OFFLOAD FACILITY	Load/Offload-Gas/DS-2/Bio-Deisel	Ball Valve	150 Class; Flanged Manual - 6504-15	KAN-6504-BLVL-0016	Taylor	UNK	3/4"								
I	6-6.2.4	6504	TRUCK LOAD/ OFFLOAD FACILITY	Load/Offload-Gas/DS-2/Bio-Deisel	Ball Valve	150 Class; Flanged Manual - 6504-16	KAN-6504-BLVL-0017	Taylor	UNK	3/4"								
I	6-6.2.4	6504	TRUCK LOAD/ OFFLOAD FACILITY	Load/Offload-Gas/DS-2/Bio-Deisel	Ball Valve	150 Class; Flanged Manual - 6504-17	KAN-6504-BLVL-0018	Taylor	UNK	3/4"								
I	6-6.2.4	6504	TRUCK LOAD/ OFFLOAD FACILITY	Load/Offload-Gas/DS-2/Bio-Deisel	Ball Valve	150 Class; Flanged Manual - 6504-18	KAN-6504-BLVL-0019	Taylor	UNK	3/4"								
I	6-6.2.4	6504	TRUCK LOAD/ OFFLOAD FACILITY	Load/Offload-Gas/DS-2/Bio-Deisel	Ball Valve	150 Class; Flanged Manual - 6504-19	KAN-6504-BLVL-0020	Taylor	UNK	1/4"								

RM Template v0.4.3

12

APPENDIX B - ATTACHMENT 3 RECURRING MAINTENANCE REPORT TEMPLATE

Contract47QSHA18D000Y W912DY21F0025

SiteKaneohe

Date26-Apr-22

RM Event(s)Q2, SA1, A BY

☒ Daily

☒ Weekly

☒ Monthly

☒ Quarterly

☒ Semi-annually

☒ Annually

☒ Every 3 years

☒ Every 5 years

☒ Every 10 years

Note: It is advised that "See Description" and "Reference to Other" always be displayed.

☒ See Description

☒ Reference to Other

☒ SM

☒ OM

Warning: Only adds Deficiencies marked "Y" in Col T.

Generate Deficiency List

RM Report Setup Only - See Instructions

Generate UFC Tasks

Applicable Facility Assets										UFC System Level Maintenance Frequency	Responsibility	RM Completion Record Result	Date Completed	Completed By	Deficiencies	Responsible FMSR	Notes	Add to Def List?
UFC Section Reference	Real Property Facility #	Real Property Facility Name	Operational Area	Component Type	Base Asset ID	Component Unique Identifier (CUID)	Make	Model	Capacity/Size									
I	6-6.2.4	6504	TRUCK LOAD/ OFFLOAD FACILITY	Load/Offload-Gas/DS-2/Bio-Deisel	Ball Valve	150 Class; Flanged Manual - 6504-20	KAN-6504-BLVL-0021	Taylor	UNK	1/4"								
I	6-6.2.4	6504	TRUCK LOAD/ OFFLOAD FACILITY	Load/Offload-Gas/DS-2/Bio-Deisel	Ball Valve	150 Class; Flanged Manual - 6504-21	KAN-6504-BLVL-0022	Taylor	UNK	1/4"								
I	6-6.2.4	6504	TRUCK LOAD/ OFFLOAD FACILITY	Load/Offload-Gas/DS-2/Bio-Deisel	Ball Valve	150 Class; Flanged Manual - 6504-22	KAN-6504-BLVL-0023	Taylor	UNK	1/4"								
I	6-6.2.4	6504	TRUCK LOAD/ OFFLOAD FACILITY	Load/Offload-Gas/DS-2/Bio-Deisel	Ball Valve	150 Class; Flanged Manual - 6504-23	KAN-6504-BLVL-0024	Taylor	UNK	1/4"								
I	6-6.2.4	6745	BULK FUEL STORAGE TANK 6745	Military Service Station	Ball Valve	Manual - 6745	KAN-6745-BLVL-0001	Apollo	UNK	1"								
I	6-6.2.4	1254A	STRAINER FACILITY	STRAINER STATION	Ball Valve	150 Class; Flanged/Flange - 1254A-4	KAN-1254A-BLVL-0001	Kitzo	UNK	4'								
I	6-6.2.4	1254A	STRAINER FACILITY	STRAINER STATION	Ball Valve	150 Class; Flanged/Flange - 1254A-5	KAN-1254A-BLVL-0002	Floteted	UNK	4'								
I	6-6.2.4	1254A	STRAINER FACILITY	STRAINER STATION	Ball Valve	150 Class; Flanged/Flange - 1254A-6	KAN-1254A-BLVL-0003	Apollo	UNK	2'								
I	6-6.2.4	1254A	STRAINER FACILITY	STRAINER STATION	Ball Valve	150 Class; Flanged/Flange - 1254A-7	KAN-1254A-BLVL-0004	Apollo	UNK	2'								
I	6-6.2.4	1254A	STRAINER FACILITY	STRAINER STATION	Ball Valve	150 Class; Flanged/Flange - 1254A-8	KAN-1254A-BLVL-0005	Apollo	UNK	2'								
I	6-6.2.4	1254A	STRAINER FACILITY	STRAINER STATION	Ball Valve	150 Class; Flanged/Flange - 1254A-9	KAN-1254A-BLVL-0006	Apollo	UNK	1"								
I	6-6.2.4	1254A	STRAINER FACILITY	STRAINER STATION	Ball Valve	150 Class; Flanged/Flange - 1254A-10	KAN-1254A-BLVL-0007	Apollo	UNK	1"								
I	6-6.2.4	1254A	STRAINER FACILITY	STRAINER STATION	Ball Valve	150 Class; Flanged/Flange - 1254A-11	KAN-1254A-BLVL-0008	Apollo	UNK	1"								
I	6-6.2.4	1254A	STRAINER FACILITY	STRAINER STATION	Ball Valve	150 Class; Flanged/Flange - 1254A-12	KAN-1254A-BLVL-0009	Apollo	UNK	1"								
I	6-6.2.4	1254A	STRAINER FACILITY	STRAINER STATION	Ball Valve	150 Class; Flanged/Flange - 1254A-13	KAN-1254A-BLVL-0010	Apollo	UNK	3/4"								
I	6-6.2.4	1254A	STRAINER FACILITY	STRAINER STATION	Ball Valve	150 Class; Flanged/Flange - 1254A-14	KAN-1254A-BLVL-0011	Apollo	UNK	3/4"								
I	6-6.2.4	1254A	STRAINER FACILITY	STRAINER STATION	Ball Valve	150 Class; Flanged/Flange - 1254A-15	KAN-1254A-BLVL-0012	Apollo	UNK	3/4"								
I	6-6.2.4	1254A	STRAINER FACILITY	STRAINER STATION	Ball Valve	150 Class; Flanged/Flange - 1254A-16	KAN-1254A-BLVL-0013	Apollo	UNK	3/4"								
I	6-6.2.4	1254A	STRAINER FACILITY	STRAINER STATION	Ball Valve	150 Class; Flanged/Flange - 1254A-17	KAN-1254A-BLVL-0014	Apollo	UNK	3/4"								
I	6-6.2.4	1254A	STRAINER FACILITY	STRAINER STATION	Ball Valve	150 Class; Flanged/Flange - 1254A-18	KAN-1254A-BLVL-0015	Apollo	UNK	1/2"								
I	6-6.2.4	1563-1	TRUCK LOAD FACILITY JP5	Load Rack - 1	Ball Valve	150 Class; Flanged Manual - 1563-1-1	KAN-1563_1-BLVL-0001	Apollo	UNK	1"								
I	6-6.2.4	1563-1	TRUCK LOAD FACILITY JP5	Load Rack - 1	Ball Valve	Ball Valve	KAN-1563_1-BLVL-0002	PBV-USA	UNK	3"								
I	6-6.2.4	1563-1	TRUCK LOAD FACILITY JP5	Load Rack - 1	Ball Valve	Ball Valve	KAN-1563_1-BLVL-0003	Apollo	UNK	4"								
I	6-6.2.4	1563-1	TRUCK LOAD FACILITY JP5	Load Rack - 1	Ball Valve	Ball Valve	KAN-1563_1-BLVL-0004	Apollo	UNK	4"								
I	6-6.2.4	1563-1	TRUCK LOAD FACILITY JP5	Load Rack - 1	Ball Valve	Ball Valve	KAN-1563_1-BLVL-0005	Apollo	UNK	4"								
I	6-6.2.4	1563-1	TRUCK LOAD FACILITY JP5	Load Rack - 1	Ball Valve	Ball Valve	KAN-1563_1-BLVL-0006	Apollo	UNK	1"								
I	6-6.2.4	1563-1	TRUCK LOAD FACILITY JP5	Load Rack - 1	Ball Valve	Ball Valve	KAN-1563_1-BLVL-0007	Apollo	UNK	1"								
I	6-6.2.4	1563-1	TRUCK LOAD FACILITY JP5	Load Rack - 1	Ball Valve	Ball Valve	KAN-1563_1-BLVL-0008	Apollo	UNK	1"								
I	6-6.2.4	1563-1	TRUCK LOAD FACILITY JP5	Load Rack - 1	Ball Valve	Ball Valve	KAN-1563_1-BLVL-0009	Apollo	UNK	1"								
I	6-6.2.4	1563-1	TRUCK LOAD FACILITY JP5	Load Rack - 1	Ball Valve	Ball Valve	KAN-1563_1-BLVL-0010	Apollo	UNK	1"								
I	6-6.2.4	1563-1	TRUCK LOAD FACILITY JP5	Load Rack - 1	Ball Valve	150 Class; Flanged Manual - 1563-1-2	KAN-1563_1-BLVL-0011	Apollo	UNK	1"								
I	6-6.2.4	1563-1	TRUCK LOAD FACILITY JP5	Load Rack - 1	Ball Valve	150 Class; Flanged Manual - 1563-1-3	KAN-1563_1-BLVL-0012	Apollo	UNK	1"								
I	6-6.2.4	1563-1	TRUCK LOAD FACILITY JP5	Load Rack - 1	Ball Valve	150 Class; Flanged Manual - 1563-1-4	KAN-1563_1-BLVL-0013	Apollo	UNK	1"								
I	6-6.2.4	1563-1	TRUCK LOAD FACILITY JP5	Load Rack - 1	Ball Valve	150 Class; Flanged Manual - 1563-1-5	KAN-1563_1-BLVL-0014	Apollo	UNK	1"								
I	6-6.2.4	1563-1	TRUCK LOAD FACILITY JP5	Load Rack - 1	Ball Valve	150 Class; Flanged/Flange - LR-1-1	KAN-1563_1-BLVL-0015	Apollo	UNK	3/4"								
I	6-6.2.4	1563-1	TRUCK LOAD FACILITY JP5	Load Rack - 1	Ball Valve	150 Class; Flanged/Flange - LR-1-2	KAN-1563_1-BLVL-0016	Apollo	UNK	3/4"								
I	6-6.2.4	1563-1	TRUCK LOAD FACILITY JP5	Load Rack - 1	Ball Valve	150 Class; Flanged/Flange - LR-1-3	KAN-1563_1-BLVL-0017	Apollo	UNK	3/4"								
I	6-6.2.4	1563-1	TRUCK LOAD FACILITY JP5	Load Rack - 1	Ball Valve	150 Class; Flanged/Flange - LR-1-4	KAN-1563_1-BLVL-0018	Apollo	UNK	3/4"								
I	6-6.2.4	1563-1	TRUCK LOAD FACILITY JP5	Load Rack - 1	Ball Valve	150 Class; Flanged/Flange - LR-1-5	KAN-1563_1-BLVL-0019	Apollo	UNK	3/4"								
I	6-6.2.4	1563-1	TRUCK LOAD FACILITY JP5	Load Rack - 1	Ball Valve	150 Class; Flanged/Flange - LR-1-6	KAN-1563_1-BLVL-0020	Apollo	UNK	3/4"								
I	6-6.2.4	1563-1	TRUCK LOAD FACILITY JP5	Load Rack - 1	Ball Valve	150 Class; Flanged/Flange - LR-1-7	KAN-1563_1-BLVL-0021	Apollo	UNK	3/4"								
I	6-6.2.4	1563-1	TRUCK LOAD FACILITY JP5	Load Rack - 1	Ball Valve	150 Class; Flanged/Flange - LR-1-8	KAN-1563_1-BLVL-0022	Apollo	UNK	3/4"								
I	6-6.2.4	1563-1	TRUCK LOAD FACILITY JP5	Load Rack - 1	Ball Valve	150 Class; Flanged/Flange - LR-1-9	KAN-1563_1-BLVL-0023	Apollo	UNK	3/4"								

APPENDIX B - ATTACHMENT 3 RECURRING MAINTENANCE REPORT TEMPLATE

Contract

47QSHA18D000Y W912DY21F0025

Site

Kaneohe

Date

26-Apr-22

RM Event(s)

Q2, SA1, A BY

Region:

POH

☐ Daily

☐ Weekly

☐ Monthly

☐ Quarterly

☐ Semi-annually

☐ Annually

☐ Every 3 years

☐ Every 5 years

☐ Every 10 years

Note: It is advised that "See Description" and "Reference to Other" always be displayed.

☐ See Description

☐ Reference to Other

☐ SM

☐ OM

Warning: Only adds Deficiencies marked "Y" in Col T.

Generate Deficiency List

RM Report Setup Only - See Instructions

Generate UFC Tasks

Applicable Facility Assets										UFC System Level Maintenance Frequency	Responsibility	RM Completion Record Result	Date Completed	Completed By	Deficiencies	Responsible FMSR	Notes	Add to Def List?
UFC Section Reference	Real Property Facility #	Real Property Facility Name	Operational Area	Component Type	Base Asset ID	Component Unique Identifier (CUID)	Make	Model	Capacity/Size									
I	6-6.2.4	1563-1	TRUCK LOAD FACILITY JP5	Load Rack - 1	Ball Valve	150 Class; Flanged/Flange - LR-1-10	KAN-1563_1-BLVL-0024	Apollo	UNK	3/4"								
I	6-6.2.4	1563-1	TRUCK LOAD FACILITY JP5	Load Rack - 1	Ball Valve	150 Class; Flanged/Flange - LR-1-11	KAN-1563_1-BLVL-0025	Apollo	UNK	3/4"								
I	6-6.2.4	1563-2	TRUCK LOADING FACILITY JP5	Load Rack - 2	Ball Valve	150 Class; Flanged/Flange - LR-2-1	KAN-1563_2-BLVL-0001	Apollo	UNK	3/4"								
I	6-6.2.4	1563-2	TRUCK LOADING FACILITY JP5	Load Rack - 2	Ball Valve	150 Class; Flanged/Flange - LR-2-2	KAN-1563_2-BLVL-0002	Apollo	UNK	3/4"								
I	6-6.2.4	1563-2	TRUCK LOADING FACILITY JP5	Load Rack - 2	Ball Valve	150 Class; Flanged/Flange - LR-2-3	KAN-1563_2-BLVL-0003	Apollo	UNK	3/4"								
I	6-6.2.4	1563-2	TRUCK LOADING FACILITY JP5	Load Rack - 2	Ball Valve	150 Class; Flanged/Flange - LR-2-4	KAN-1563_2-BLVL-0004	Apollo	UNK	3/4"								
I	6-6.2.4	1563-2	TRUCK LOADING FACILITY JP5	Load Rack - 2	Ball Valve	150 Class; Flanged/Flange - LR-2-5	KAN-1563_2-BLVL-0005	Apollo	UNK	3/4"								
I	6-6.2.4	1563-2	TRUCK LOADING FACILITY JP5	Load Rack - 2	Ball Valve	150 Class; Flanged/Flange - LR-2-6	KAN-1563_2-BLVL-0006	Apollo	UNK	3/4"								
I	6-6.2.4	1563-2	TRUCK LOADING FACILITY JP5	Load Rack - 2	Ball Valve	150 Class; Flanged/Flange - LR-2-7	KAN-1563_2-BLVL-0007	Apollo	UNK	3/4"								
I	6-6.2.4	1563-2	TRUCK LOADING FACILITY JP5	Load Rack - 2	Ball Valve	150 Class; Flanged/Flange - LR-2-8	KAN-1563_2-BLVL-0008	Apollo	UNK	3/4"								
I	6-6.2.4	1563-2	TRUCK LOADING FACILITY JP5	Load Rack - 2	Ball Valve	150 Class; Flanged/Flange - LR-2-9	KAN-1563_2-BLVL-0009	Apollo	UNK	3/4"								
I	6-6.2.4	1563-2	TRUCK LOADING FACILITY JP5	Load Rack - 2	Ball Valve	150 Class; Flanged/Flange - LR-2-10	KAN-1563_2-BLVL-0010	Apollo	UNK	3/4"								
I	6-6.2.4	1563-2	TRUCK LOADING FACILITY JP5	Load Rack - 2	Ball Valve	150 Class; Flanged/Flange - LR-2-11	KAN-1563_2-BLVL-0011	Apollo	UNK	3/4"								
I	6-6.2.4	1563-2	TRUCK LOADING FACILITY JP5	Load Rack - 3	Ball Valve	150 Class; Flanged/Flange - LR-3-1	KAN-1563_2-BLVL-0012	Apollo	UNK	3/4"								
I	6-6.2.4	1563-2	TRUCK LOADING FACILITY JP5	Load Rack - 3	Ball Valve	150 Class; Flanged/Flange - LR-3-1	KAN-1563_2-BLVL-0013	Apollo	UNK	3/4"								
I	6-6.2.4	1563-2	TRUCK LOADING FACILITY JP5	Load Rack - 3	Ball Valve	150 Class; Flanged/Flange - LR-3-1	KAN-1563_2-BLVL-0014	Apollo	UNK	3/4"								
I	6-6.2.4	1563-2	TRUCK LOADING FACILITY JP5	Load Rack - 3	Ball Valve	150 Class; Flanged/Flange - LR-3-1	KAN-1563_2-BLVL-0015	Apollo	UNK	3/4"								
I	6-6.2.4	1563-2	TRUCK LOADING FACILITY JP5	Load Rack - 3	Ball Valve	150 Class; Flanged/Flange - LR-3-1	KAN-1563_2-BLVL-0016	Apollo	UNK	3/4"								
I	6-6.2.4	1563-2	TRUCK LOADING FACILITY JP5	Load Rack - 3	Ball Valve	150 Class; Flanged/Flange - LR-3-1	KAN-1563_2-BLVL-0017	Apollo	UNK	3/4"								
I	6-6.2.4	1563-2	TRUCK LOADING FACILITY JP5	Load Rack - 3	Ball Valve	150 Class; Flanged/Flange - LR-3-1	KAN-1563_2-BLVL-0018	Apollo	UNK	3/4"								
I	6-6.2.4	1563-2	TRUCK LOADING FACILITY JP5	Load Rack - 3	Ball Valve	150 Class; Flanged/Flange - LR-3-1	KAN-1563_2-BLVL-0019	Apollo	UNK	3/4"								
I	6-6.2.4	1563-2	TRUCK LOADING FACILITY JP5	Load Rack - 3	Ball Valve	150 Class; Flanged/Flange - LR-3-1	KAN-1563_2-BLVL-0020	Apollo	UNK	3/4"								
I	6-6.2.4	1563-2	TRUCK LOADING FACILITY JP5	Load Rack - 3	Ball Valve	150 Class; Flanged/Flange - LR-3-1	KAN-1563_2-BLVL-0021	Apollo	UNK	3/4"								
I	6-6.2.4	1563-2	TRUCK LOADING FACILITY JP5	Load Rack - 3	Ball Valve	150 Class; Flanged/Flange - LR-3-1	KAN-1563_2-BLVL-0022	Apollo	UNK	1"								
I	6-6.2.4	1563-2	TRUCK LOADING FACILITY JP5	Load Rack - 3	Ball Valve	150 Class; Flanged/Flange - LR-3-1	KAN-1563_2-BLVL-0023	Apollo	UNK	1"								
I	6-6.2.4	1563-2	TRUCK LOADING FACILITY JP5	Load Rack - 3	Ball Valve	150 Class; Flanged/Flange - LR-3-1	KAN-1563_2-BLVL-0024	Apollo	UNK	1"								
I	6-6.2.4	1563-2	TRUCK LOADING FACILITY JP5	Load Rack - 3	Ball Valve	150 Class; Flanged/Flange - LR-3-1	KAN-1563_2-BLVL-0025	Apollo	UNK	1"								
I	6-6.2.4	1563-2	TRUCK LOADING FACILITY JP5	Load Rack - 3	Ball Valve	150 Class; Flanged/Flange - LR-3-1	KAN-1563_2-BLVL-0026	Apollo	UNK	1"								
I	6-6.2.4	1563-2	TRUCK LOADING FACILITY JP5	Load Rack - 3	Ball Valve	150 Class; Flanged/Flange - LR-3-1	KAN-1563_2-BLVL-0027	Apollo	UNK	3"								
I	6-6.2.4	1563-2	TRUCK LOADING FACILITY JP5	Load Rack - 3	Ball Valve	150 Class; Flanged/Flange - LR-3-1	KAN-1563_2-BLVL-0028	Apollo	UNK	3"								
I	6-6.2.4	1563-2	TRUCK LOADING FACILITY JP5	Load Rack - 3	Ball Valve	150 Class; Flanged/Flange - LR-3-1	KAN-1563_2-BLVL-0029	Apollo	UNK	3"								
I	6-6.2.4	1563-2	TRUCK LOADING FACILITY JP5	Load Rack - 3	Ball Valve	150 Class; Flanged/Flange - LR-3-1	KAN-1563_2-BLVL-0030	Apollo	UNK	3"								
I	6-6.2.4	1563-2	TRUCK LOADING FACILITY JP5	Load Rack - 3	Ball Valve	150 Class; Flanged/Flange - LR-3-1	KAN-1563_2-BLVL-0031	Apollo	UNK	3"								
I	6-6.2.4	1563-2	TRUCK LOADING FACILITY JP5	Load Rack - 3	Ball Valve	150 Class; Flanged/Flange - LR-3-1	KAN-1563_2-BLVL-0032	Apollo	UNK	3"								
I	6-6.2.4	6506-1	MOGAS FUEL TANK	Military Service Station	Ball Valve	150 Class; Flanged Manual - 6506-1-1	KAN-6506_1-BLVL-0001	WCB Flow-Tek	150#	4"								
I	6-6.2.4	6506-1	MOGAS FUEL TANK	Military Service Station	Ball Valve	150 Class; Flanged Manual - 6506-1-2	KAN-6506_1-BLVL-0002	WCB Flow-Tek	150#	4"								
I	6-6.2.4	6506-1	MOGAS FUEL TANK	Military Service Station	Ball Valve	150 Class; Flanged Manual - 6506-1-3	KAN-6506_1-BLVL-0003	WCB Flow-Tek	150#	4"								
I	6-6.2.4	6506-1	MOGAS FUEL TANK	Military Service Station	Ball Valve	150 Class; Flanged Manual - 6506-1-1	KAN-6506_1-BLVL-0004	Apollo	UNK	2"								
I	6-6.2.4	6506-1	MOGAS FUEL TANK	Military Service Station	Ball Valve	150 Class; Flanged Manual - 6506-1-2	KAN-6506_1-BLVL-0005	Apollo	UNK	2"								
I	6-6.2.4	6506-1	MOGAS FUEL TANK	Military Service Station	Ball Valve	150 Class; Flanged Manual - 6506-1-3	KAN-6506_1-BLVL-0006	Apollo	UNK	2"								
I	6-6.2.4	6506-1	MOGAS FUEL TANK	Military Service Station	Ball Valve	150 Class; Flanged Manual - 6506-1-1	KAN-6506_1-BLVL-0007	Apollo	UNK	1"								
I	6-6.2.4	6506-1	MOGAS FUEL TANK	Military Service Station	Ball Valve	150 Class; Flanged Manual - 6506-1-2	KAN-6506_1-BLVL-0008	Apollo	UNK	1"								
I	6-6.2.4	6506-1	MOGAS FUEL TANK	Military Service Station	Ball Valve	150 Class; Flanged Manual - 6506-1-3	KAN-6506_1-BLVL-0009	Apollo	UNK	1"								
I	6-6.2.4	6506-1	MOGAS FUEL TANK	Military Service Station	Ball Valve	Manual - 6506 A	KAN-6506_1-BLVL-0010	Apollo	UNK	3/4"								
I	6-6.2.4	6506-1	MOGAS FUEL TANK	Military Service Station	Ball Valve	Manual - 6506-1-4	KAN-6506_1-BLVL-0011	Apollo	UNK	1/2"								
I	6-6.2.4	6506-2	MOGAS FUEL TANK	Military Service Station	Ball Valve	150 Class; Flanged Manual - 6506-2-1	KAN-6506_2-BLVL-0001	WCB Flow-Tek	150#	4"								
I	6-6.2.4	6506-2	MOGAS FUEL TANK	Military Service Station	Ball Valve	150 Class; Flanged Manual - 6506-2-2	KAN-6506_2-BLVL-0002	WCB Flow-Tek	150#	4"								
I	6-6.2.4	6506-2	MOGAS FUEL TANK	Military Service Station	Ball Valve	150 Class; Flanged Manual - 6506-2-3	KAN-6506_2-BLVL-0003	WCB Flow-Tek	150#	4"								

APPENDIX B - ATTACHMENT 3 RECURRING MAINTENANCE REPORT TEMPLATE

Contract47QSHA18D000Y W912DY21F0025

SiteKaneohe

Date26-Apr-22

RM Event(s)Q2, SA1, A BY

☒ Daily

☒ Weekly

☒ Monthly

☒ Quarterly

☒ Semi-annually

☒ Annually

☒ Every 3 years

☒ Every 5 years

☒ Every 10 years

Note: It is advised that "See Description" and "Reference to Other" always be displayed.

☒ See Description

☒ Reference to Other

☒ SM

☒ OM

Warning: Only adds Deficiencies marked "Y" in Col T.

Generate Deficiency List

RM Report Setup Only - See Instructions

Generate UFC Tasks

Applicable Facility Assets										UFC System Level Maintenance Frequency	Responsibility	RM Completion Record Result	Date Completed	Completed By	Deficiencies	Responsible FMSR	Notes	Add to Def List?
UFC Section Reference	Real Property Facility #	Real Property Facility Name	Operational Area	Component Type	Base Asset ID	Component Unique Identifier (CUID)	Make	Model	Capacity/Size									
I	6-6.2.4	6506-2	MOGAS FUEL TANK	Military Service Station	Ball Valve	150 Class; Flanged Manual - 6506-2-1	KAN-6506_2-BLVL-0004	Apollo	UNK	2"								
I	6-6.2.4	6506-2	MOGAS FUEL TANK	Military Service Station	Ball Valve	150 Class; Flanged Manual - 6506-2-2	KAN-6506_2-BLVL-0005	Apollo	UNK	2"								
I	6-6.2.4	6506-2	MOGAS FUEL TANK	Military Service Station	Ball Valve	150 Class; Flanged Manual - 6506-2-3	KAN-6506_2-BLVL-0006	Apollo	UNK	2"								
I	6-6.2.4	6506-2	MOGAS FUEL TANK	Military Service Station	Ball Valve	150 Class; Flanged Manual - 6506-2-1	KAN-6506_2-BLVL-0007	Apollo	UNK	1"								
I	6-6.2.4	6506-2	MOGAS FUEL TANK	Military Service Station	Ball Valve	150 Class; Flanged Manual - 6506-2-2	KAN-6506_2-BLVL-0008	Apollo	UNK	1"								
I	6-6.2.4	6506-2	MOGAS FUEL TANK	Military Service Station	Ball Valve	150 Class; Flanged Manual - 6506-2-3	KAN-6506_2-BLVL-0009	Apollo	UNK	1"								
I	6-6.2.4	6506-2	MOGAS FUEL TANK	Military Service Station	Ball Valve	Manual - 6506 B	KAN-6506_2-BLVL-0010	Apollo	UNK	3/4"								
I	6-6.2.4	6506-2	MOGAS FUEL TANK	Military Service Station	Ball Valve	Manual - 6506-2-4	KAN-6506_2-BLVL-0011	Apollo	UNK	1/2"								
I	6-6.2.4	6506-3	BULK FUEL STORAGE TANK Bio-Diesel	Military Service Station	Ball Valve	150 Class; Flanged Manual - 6506-3-1	KAN-6506_3-BLVL-0001	WCB Flow-Tek	150#	4"								
I	6-6.2.4	6506-3	BULK FUEL STORAGE TANK Bio-Diesel	Military Service Station	Ball Valve	150 Class; Flanged Manual - 6506-3-2	KAN-6506_3-BLVL-0002	WCB Flow-Tek	150#	4"								
I	6-6.2.4	6506-3	BULK FUEL STORAGE TANK Bio-Diesel	Military Service Station	Ball Valve	150 Class; Flanged Manual - 6506-3-3	KAN-6506_3-BLVL-0003	WCB Flow-Tek	150#	4"								
I	6-6.2.4	6506-3	BULK FUEL STORAGE TANK Bio-Diesel #3	Military Service Station	Ball Valve	150 Class; Flanged Manual - 6506-3-1	KAN-6506_3-BLVL-0004	Apollo	UNK	2"								
I	6-6.2.4	6506-3	BULK FUEL STORAGE TANK Bio-Diesel #3	Military Service Station	Ball Valve	150 Class; Flanged Manual - 6506-3-2	KAN-6506_3-BLVL-0005	Apollo	UNK	2"								
I	6-6.2.4	6506-3	BULK FUEL STORAGE TANK Bio-Diesel #3	Military Service Station	Ball Valve	150 Class; Flanged Manual - 6506-3-3	KAN-6506_3-BLVL-0006	Apollo	UNK	2"								
I	6-6.2.4	6506-3	BULK FUEL STORAGE TANK Bio-Diesel #3	Military Service Station	Ball Valve	150 Class; Flanged Manual - 6506-3-1	KAN-6506_3-BLVL-0007	Apollo	UNK	1"								
I	6-6.2.4	6506-3	BULK FUEL STORAGE TANK Bio-Diesel #3	Military Service Station	Ball Valve	150 Class; Flanged Manual - 6506-3-2	KAN-6506_3-BLVL-0008	Apollo	UNK	1"								
I	6-6.2.4	6506-3	BULK FUEL STORAGE TANK Bio-Diesel #3	Military Service Station	Ball Valve	150 Class; Flanged Manual - 6506-3-3	KAN-6506_3-BLVL-0009	Apollo	UNK	1"								
I	6-6.2.4	6506-3	BULK FUEL STORAGE TANK Bio-Diesel #3	Military Service Station	Ball Valve	Manual - 6506-3-4	KAN-6506_3-BLVL-0010	Apollo	UNK	1/2"								
I	6-6.2.4	6506-3	BIODIESEL READY FUEL STORAGE	Military Service Station	Ball Valve	Manual - 6506 C	KAN-6506_3-BLVL-0011	Apollo	UNK	1/4"								
I	6-6.2.4	6506-4	DIESEL FUEL STORAGE	Military Service Station	Ball Valve	150 Class; Flanged Manual - 6506-4-1	KAN-6506_4-BLVL-0001	WCB Flow-Tek	150#	4"								
I	6-6.2.4	6506-4	DIESEL FUEL STORAGE	Military Service Station	Ball Valve	150 Class; Flanged Manual - 6506-4-2	KAN-6506_4-BLVL-0002	WCB Flow-Tek	150#	4"								
I	6-6.2.4	6506-4	DIESEL FUEL STORAGE	Military Service Station	Ball Valve	150 Class; Flanged Manual - 6506-4-3	KAN-6506_4-BLVL-0003	WCB Flow-Tek	150#	4"								
I	6-6.2.4	6506-4	DIESEL FUEL STORAGE	Military Service Station	Ball Valve	150 Class; Flanged Manual - 6506-4-1	KAN-6506_4-BLVL-0004	Apollo	UNK	2"								
I	6-6.2.4	6506-4	DIESEL FUEL STORAGE	Military Service Station	Ball Valve	150 Class; Flanged Manual - 6506-4-2	KAN-6506_4-BLVL-0005	Apollo	UNK	2"								
I	6-6.2.4	6506-4	DIESEL FUEL STORAGE	Military Service Station	Ball Valve	150 Class; Flanged Manual - 6506-4-3	KAN-6506_4-BLVL-0006	Apollo	UNK	2"								
I	6-6.2.4	6506-4	DIESEL FUEL STORAGE	Military Service Station	Ball Valve	150 Class; Flanged Manual - 6506-4-1	KAN-6506_4-BLVL-0007	Apollo	UNK	1"								
I	6-6.2.4	6506-4	DIESEL FUEL STORAGE	Military Service Station	Ball Valve	150 Class; Flanged Manual - 6506-4-2	KAN-6506_4-BLVL-0008	Apollo	UNK	1"								
I	6-6.2.4	6506-4	DIESEL FUEL STORAGE	Military Service Station	Ball Valve	150 Class; Flanged Manual - 6506-4-3	KAN-6506_4-BLVL-0009	Apollo	UNK	1"								
I	6-6.2.4	6506-4	DIESEL FUEL STORAGE	Military Service Station	Ball Valve	Manual - 6506-4-4	KAN-6506_4-BLVL-0010	Apollo	UNK	1/2"								
I	6-6.2.4	6506-4	DIESEL FUEL STORAGE	Military Service Station	Ball Valve	Manual - 6506 D	KAN-6506_4-BLVL-0011	Apollo	UNK	1/4"								
I	6-6.2.4	6506-5	JP8 FUEL STORAGE	Military Service Station	Ball Valve	150 Class; Flanged Manual - 6506-5-1	KAN-6506_5-BLVL-0001	WCB Flow-Tek	150#	4"								
I	6-6.2.4	6506-5	JP8 FUEL STORAGE	Military Service Station	Ball Valve	150 Class; Flanged Manual - 6506-5-2	KAN-6506_5-BLVL-0002	WCB Flow-Tek	150#	4"								
I	6-6.2.4	6506-5	JP8 FUEL STORAGE	Military Service Station	Ball Valve	150 Class; Flanged Manual - 6506-5-3	KAN-6506_5-BLVL-0003	WCB Flow-Tek	150#	3"								
I	6-6.2.4	6506-5	JP8 FUEL STORAGE	Military Service Station	Ball Valve	150 Class; Flanged Manual - 6506-5-1	KAN-6506_5-BLVL-0004	Apollo	UNK	2"								
I	6-6.2.4	6506-5	JP8 FUEL STORAGE	Military Service Station	Ball Valve	150 Class; Flanged Manual - 6506-5-2	KAN-6506_5-BLVL-0005	Apollo	UNK	2"								
I	6-6.2.4	6506-5	JP8 FUEL STORAGE	Military Service Station	Ball Valve	150 Class; Flanged Manual - 6506-5-3	KAN-6506_5-BLVL-0006	Apollo	UNK	2"								
I	6-6.2.4	6506-5	JP8 FUEL STORAGE	Military Service Station	Ball Valve	150 Class; Flanged Manual - 6506-5-1	KAN-6506_5-BLVL-0007	Apollo	UNK	1"								
I	6-6.2.4	6506-5	JP8 FUEL STORAGE	Military Service Station	Ball Valve	150 Class; Flanged Manual - 6506-5-2	KAN-6506_5-BLVL-0008	Apollo	UNK	1"								
I	6-6.2.4	6506-5	JP8 FUEL STORAGE	Military Service Station	Ball Valve	150 Class; Flanged Manual - 6506-5-3	KAN-6506_5-BLVL-0009	Apollo	UNK	1"								
I	6-6.2.4	6506-5	JP8 FUEL STORAGE	Military Service Station	Ball Valve	Manual - 6506-5-4	KAN-6506_5-BLVL-0010	Apollo	UNK	1/2"								
H	Double Block and Bleed Valves (Section 6-6.2.5)																	
T	H. Refer to Section 6-6.2.10 Manual Valve Gear Operators for inspection and maintenance of gear operators if equipped.										Reference to Other	SM						
T	I. Some double block and bleed valves are equipped with integrated pressure/thermal relief valves. Refer to Section 6-6.3 Thermal and Pressure Relief Valves for inspection and maintenance requirements of pressure/thermal relief valves.										Reference to Other	SM						
T	A. Open and close valve to check for ease of operation.										Quarterly	SM						
T	B. Lubricate overhead valve chain operator gears if equipped.										Quarterly	SM						
T	C. Adjust packing per manufacturer's specifications.										Quarterly	SM						
T	D. Inspect valve exterior for corrosion and tightness of bolts. Repaint and tighten as required.										Quarterly	SM						
	Note: Per PWS Touch-up Coating Repair.																	

RM Template v0.4.3

15

APPENDIX B - ATTACHMENT 3 RECURRING MAINTENANCE REPORT TEMPLATE

Contract47QSHA18D000Y W912DY21F0025

SiteKaneohe

Date26-Apr-22

RM Event(s)Q2, SA1, A BY

☒ Daily

☒ Weekly

☒ Monthly

☒ Quarterly

☒ Semi-annually

☒ Annually

☒ Every 3 years

☒ Every 5 years

☒ Every 10 years

Note: It is advised that "See Description" and "Reference to Other" always be displayed.

☒ See Description

☒ Reference to Other

☒ SM

☒ OM

Warning: Only adds Deficiencies marked "Y" in Col T.

Generate Deficiency List

RM Report Setup Only - See Instructions

Generate UFC Tasks

Applicable Facility Assets										UFC System Level Maintenance Frequency	Responsibility	RM Completion Record Result	Date Completed	Completed By	Deficiencies	Responsible FMSR	Notes	Add to Def List?	
UFC Section Reference	Real Property Facility #	Real Property Facility Name	Operational Area	Component Type	Base Asset ID	Component Unique Identifier (CUID)	Make	Model	Capacity/Size										
T	E. Operate the body cavity drain when valve is in closed position to ensure that the valve is closing properly.										Quarterly	SM							
T	F. Keep the valve operator housing full of lubricant to displace and prevent moisture from accumulating and freezing, in accordance with manufacturer's recommendations.										Semi-annually	SM							
T	G. Remove bottom drain plug and drain valve.										Annually	SM							
I	6-6.2.5	149	Fuel Pier 149	Pier 149	DBB Valve	DBB Valve	KAN-149-DBBVL-0001	UNK	UNK	6"									
I	6-6.2.5	149	Fuel Pier 149	Pier 149	DBB Valve	DBB Valve	KAN-149-DBBVL-0002	UNK	UNK	6"									
I	6-6.2.5	1170	ACFT DIR FUEL ISLAND	Flightline Pits	DBB Valve	150 Class; Flanged Manual - 1170-DBB-1	KAN-1170-DBBLVL-0001	WCC	Model 211	6"									
I	6-6.2.5	1170	ACFT DIR FUEL ISLAND	Flightline Pits	DBB Valve	150 Class; Flanged Manual - 1170-DBB-2	KAN-1170-DBBLVL-0002	WCC	Model 211	6"									
I	6-6.2.5	1170	ACFT DIR FUEL ISLAND	Flightline Pits	DBB Valve	150 Class; Flanged Manual - 1170-DBB-3	KAN-1170-DBBLVL-0003	WCC	Model 211	6"									
I	6-6.2.5	1170	ACFT DIR FUEL ISLAND	Flightline Pits	DBB Valve	150 Class; Flanged Manual - 1170-DBB-4	KAN-1170-DBBLVL-0004	WCC	Model 211	4"									
I	6-6.2.5	1170	ACFT DIR FUEL ISLAND	Flightline Pits	DBB Valve	150 Class; Flanged Manual - 1170-DBB-5	KAN-1170-DBBLVL-0005	WCC	Model 211	4"									
I	6-6.2.5	1170	ACFT DIR FUEL ISLAND	Flightline Pits	DBB Valve	150 Class; Flanged Manual - 1170-DBB-6	KAN-1170-DBBLVL-0006	WCC	Model 211	4"									
I	6-6.2.5	1170	ACFT DIR FUEL ISLAND	Flightline Pits	DBB Valve	150 Class; Flanged Manual - 1170-DBB-7	KAN-1170-DBBLVL-0007	WCC	Model 211	4"									
I	6-6.2.5	1252	BULK FUEL STORAGE TANK F-24	Bulk Storage	DBB Valve	150 Class; Flanged Manual 1252-DBB-1	KAN-1252-DBBVL-0001	WCC	C811	10"									
I	6-6.2.5	1252	BULK FUEL STORAGE TANK F-24	Bulk Storage	DBB Valve	150 Class; Flanged Manual 1252-DBB-2	KAN-1252-DBBVL-0002	WCC	Model 211	6"									
I	6-6.2.5	1252	BULK FUEL STORAGE TANK F-24	Bulk Storage	DBB Valve	150 Class; Flanged Manual 1252-DBB-3	KAN-1252-DBBVL-0003	WCC	Model 211	4"									
I	6-6.2.5	1253	BULK FUEL STORAGE TANK F-24	Bulk Storage	DBB Valve	150 Class; Flanged Manual 1253-DBB-1	KAN-1253-DBBVL-0001	WCC	C811	10"									
I	6-6.2.5	1253	BULK FUEL STORAGE TANK F-24	Bulk Storage	DBB Valve	150 Class; Flanged Manual 1253-DBB-2	KAN-1253-DBBVL-0002	WCC	Model 211	6"									
I	6-6.2.5	1253	BULK FUEL STORAGE TANK F-24	Bulk Storage	DBB Valve	150 Class; Flanged Manual 1253-DBB-3	KAN-1253-DBBVL-0003	WCC	Model 211	4"									
I	6-6.2.5	1254	TRUCK OFFLOAD	Pump Station	DBB Valve	DBB Valve	KAN-1254-DBBVL-0001	General Valve Co	Model 211	6"									
I	6-6.2.5	1254	TRUCK OFFLOAD	Pump Station	DBB Valve	150 Class; Flanged Manual 1254-DBB-2	KAN-1254-DBBVL-0002	General Valve Co	Model 211	6"									
I	6-6.2.5	1254	TRUCK OFFLOAD	Pump Station	DBB Valve	150 Class; Flanged Manual 1254-DBB-3	KAN-1254-DBBVL-0003	General Valve Co	Model 211	4"									
I	6-6.2.5	1254	TRUCK OFFLOAD	Pump Station	DBB Valve	150 Class; Flanged Manual 1254-DBB-4	KAN-1254-DBBVL-0004	General Valve Co	Model 211	4"									
I	6-6.2.5	6479	JET ENGINE FUEL STORAGE	Supply Line	DBB Valve	150 Class; Flanged 6479A-1	KAN-6479-BLVL-0001	General Valve Co	C811	14"									
I	6-6.2.5	6479	JET ENGINE FUEL STORAGE	Supply Line	DBB Valve	150 Class; Flanged 6479A-2	KAN-6479-BLVL-0002	General Valve Co	C811	14"									
I	6-6.2.5	6479	JET ENGINE FUEL STORAGE	Supply Line	DBB Valve	150 Class; Flanged 6479A-3	KAN-6479-BLVL-0003	General Valve Co	C811	14"									
I	6-6.2.5	6479	JET ENGINE FUEL STORAGE	Bulk Storage	DBB Valve	150 Class; Flanged Manual 6479A - 1	KAN-6479-BLVL-0004	True Seal	Model 211	14"									
I	6-6.2.5	6479	JET ENGINE FUEL STORAGE	Bulk Storage	DBB Valve	150 Class; Flanged Manual 6479A - 2	KAN-6479-BLVL-0005	True Seal	Model 211	14"									
I	6-6.2.5	6479	JET ENGINE FUEL STORAGE	Bulk Storage	DBB Valve	150 Class; Flanged Manual 6479A - 3	KAN-6479-BLVL-0006	True Seal	Model 211	14"									
I	6-6.2.5	6479	JET ENGINE FUEL STORAGE	Bulk Storage	DBB Valve	150 Class; Flanged Manual 6479B - 1	KAN-6479-BLVL-0007	True Seal	Model 211	6"									
I	6-6.2.5	6479	JET ENGINE FUEL STORAGE	Bulk Storage	DBB Valve	150 Class; Flanged Manual 6479B - 2	KAN-6479-BLVL-0008	True Seal	Model 211	6"									
I	6-6.2.5	6479	JET ENGINE FUEL STORAGE	Bulk Storage	DBB Valve	150 Class; Flanged Manual 6479B - 3	KAN-6479-BLVL-0009	True Seal	Model 211	6"									
I	6-6.2.5	1254A	STRAINER FACILITY	STRAINER STATION	DBB Valve	150 Class; Flanged/Flange - 1254A-1-1	KAN-1254A-DBBVL-0001	True-seal	MCO	10"									
I	6-6.2.5	1254A	STRAINER FACILITY	STRAINER STATION	DBB Valve	150 Class; Flanged/Flange - 1254A-1-2	KAN-1254A-DBBVL-0002	True-seal	MCO	10"									
I	6-6.2.5	1254A	STRAINER FACILITY	STRAINER STATION	DBB Valve	150 Class; Flanged/Flange - 1254A-1-3	KAN-1254A-DBBVL-0003	True-seal	MCO	10"									
I	6-6.2.5	1254A	STRAINER FACILITY	STRAINER STATION	DBB Valve	150 Class; Flanged/Flange - 1254A-1-4	KAN-1254A-DBBVL-0004	True-seal	MCO	10"									
I	6-6.2.5	1254A	STRAINER FACILITY	STRAINER STATION	DBB Valve	150 Class; Flanged/Flange - 1254A-2	KAN-1254A-DBBVL-0005	True-seal	MCO	6"									
I	6-6.2.5	1254A	STRAINER FACILITY	STRAINER STATION	DBB Valve	150 Class; Flanged/Flange - 1254A-3	KAN-1254A-DBBVL-0006	True-seal	MCO	4"									
H	Butterfly Valves (Section 6-6.2.6)																		
T	A. Open and close valve to check for ease of operation. Ensure that lever operators and locking mechanisms are in place and working properly.										Quarterly	SM							
T	B. Adjust packing per manufacturer's specifications as needed. If butterfly valves are leaking or not shutting off flow, tightening the gland flange to tighten the stem packing or remove the valve from service and replace the seats as necessary.										Quarterly	SM							
T	C. Inspect valve exterior for corrosion and tightness of bolts. Repaint and relighten as required.										Quarterly	SM							
	Note: Per PWS Touch-up Coating Repair																		
I	6-6.2.6	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Butterfly Valve	150 Class; Flanged Manual Pit-B-1	KAN-1170-BFVL-0001	Crane	UNK	4"									
I	6-6.2.6	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Butterfly Valve	150 Class; Flanged Manual Pit-B-2	KAN-1170-BFVL-0002	Crane	UNK	4"									
I	6-6.2.6	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Butterfly Valve	150 Class; Flanged Manual Pit-C-1	KAN-1170-BFVL-0003	Crane	UNK	4"									
I	6-6.2.6	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Butterfly Valve	150 Class; Flanged Manual Pit-C-2	KAN-1170-BFVL-0004	Crane	UNK	4"									

APPENDIX B - ATTACHMENT 3 RECURRING MAINTENANCE REPORT TEMPLATE

Contract47QSHA18D000Y W912DY21F0025

SiteKaneohe

Date26-Apr-22

RM Event(s)Q2, SA1, A BY

☒ Daily

☒ Weekly

☒ Monthly

☒ Quarterly

☒ Semi-annually

☒ Annually

☒ Every 3 years

☒ Every 5 years

☒ Every 10 years

Note: It is advised that "See Description" and "Reference to Other" always be displayed.

☒ See Description

☒ Reference to Other

☒ SM

☒ OM

Warning: Only adds Deficiencies marked "Y" in Col T.

Generate Deficiency List

RM Report Setup Only - See Instructions

Generate UFC Tasks

Applicable Facility Assets										UFC System Level Maintenance Frequency	Responsibility	RM Completion Record Result	Date Completed	Completed By	Deficiencies	Responsible FMSR	Notes	Add to Def List?
UFC Section Reference	Real Property Facility #	Real Property Facility Name	Operational Area	Component Type	Base Asset ID	Component Unique Identifier (CUID)	Make	Model	Capacity/Size									
I	6-6.2.6	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Butterfly Valve	150 Class; Flanged Manual - Pit-D-1	KAN-1170-BFVL-0005	Crane	UNK	4"								
I	6-6.2.6	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Butterfly Valve	150 Class; Flanged Manual - Pit-D2	KAN-1170-BFVL-0006	Crane	UNK	4"								
I	6-6.2.6	1563-1	TRUCK LOADING FACILITY F-24	Load Rack - 1	Butterfly Valve	150 Class; Flanged Manual - LR-1	KAN-1563_1-BTVL-0001	Crane	UNK	6"								
I	6-6.2.6	1563-2	TRUCK LOADING FACILITY F-24	Load Rack - 2	Butterfly Valve	150 Class; Flanged Manual - LR-2	KAN-1563_2-BFVL-0001	Crane	UNK	6"								
H	Check Valves (Section 6-6.2.8)																	
T	A. Use external test lever to make sure the valve is not sticking if equipped. If a check valve is suspected of not checking and cannot be serviced in place, it shall be removed from the piping system and serviced in a shop. Note: Repairs that require servicing the valve in a shop should be performed through a service order.										Quarterly	SM						
T	B. Inspect valve exterior for corrosion and tightness of bolts. Repaint and retighten as required. Note: Per PWS Touch-up Coating Repair.										Quarterly	SM						
I	6-6.2.8	1252	BULK FUEL STORAGE TANK F-24	Bulk Storage	Check Valve	Check Valve	KAN-1252-CKVL-0001	Mueller	UNK	1"								
I	6-6.2.8	1252	BULK FUEL STORAGE TANK F-24	Bulk Storage	Check Valve	Check Valve	KAN-1252-CKVL-0002	Mueller	UNK	1"								
I	6-6.2.8	1252	BULK FUEL STORAGE TANK F-24	Bulk Storage	Check Valve	Check Valve	KAN-1252-CKVL-0003	Mueller	UNK	1"								
I	6-6.2.8	1253	BULK FUEL STORAGE TANK F-24	Bulk Storage	Check Valve	Check Valve	KAN-1252-CKVL-0004	Mueller	UNK	1"								
I	6-6.2.8	1253	BULK FUEL STORAGE TANK F-24	Bulk Storage	Check Valve	Check Valve	KAN-1252-CKVL-0005	Mueller	UNK	1"								
I	6-6.2.8	1253	BULK FUEL STORAGE TANK F-24	Bulk Storage	Check Valve	Check Valve	KAN-1252-CKVL-0006	Mueller	UNK	1"								
I	6-6.2.8	6479	JET ENGINE FUEL STORAGE	Bulk Storage	Check Valve	6479A-1	KAN-6479-CKVL-0001	UNK	UNK	3/4"								
I	6-6.2.8	6479	JET ENGINE FUEL STORAGE	Bulk Storage	Check Valve	6479A-2	KAN-6479-CKVL-0002	UNK	UNK	3/4"								
I	6-6.2.8	6504	TRUCK LOAD/ OFFLOAD FACILITY	Load/Offload-Gas/DS-2/Bio-Deisel	Check Valve	Manual - 6504A	KAN-6504-CKVL-0001	Apollo	UNK	2"								
I	6-6.2.8	6506-1	MOGAS FUEL TANK	Military Service Station	Check Valve	Check Valve	KAN-6506_1_1-CKVL-0001	Mueller	UNK	4"								
I	6-6.2.8	6506-2	MOGAS FUEL TANK	Military Service Station	Check Valve	Check Valve	KAN-6506_2-CKVL-0001	Mueller	UNK	4"								
I	6-6.2.8	6506-3	BIODIESEL READY FUEL STORAGE	Military Service Station	Check Valve	Check Valve	KAN-6506_3-CKVL-0001	Mueller	UNK	4"								
I	6-6.2.8	6506-4	DIESEL FUEL STORAGE	Military Service Station	Check Valve	Check Valve	KAN-6506_4-CKVL-0001	Mueller	UNK	4"								
I	6-6.2.8	6506-5	JP8 FUEL STORAGE	Military Service Station	Check Valve	Check Valve	KAN-6506_5-CKVL-0001	Mueller	UNK	4"								
H	Thermal and Pressure Relief Valves (Section 6-6.3)																	
T	A. Thermal and pressure relief valves shall be inspected for signs of leak-by. Inspect relief valves for leaks by visually inspecting downstream flow indicators (if installed) for flow. If no flow indicators are installed listen for possible leaks. If suspect: isolate and test the relief valve; check opening pressure; and verify re-seating. Malfunctioning valves shall be repaired or replaced. Note: Maintenance procedure shall include process to verify that the valve has properly reseated after all maintenance activities are performed on pressure relief valves or thermal and pressure relief valves. Note: OM for Army, Navy, USMC; SM for AF Frequency: Monthly for Army, Navy, USMC; Quarterly for AF										See Description	SM						
T	B. Ensure manual isolation valves installed upstream and downstream of thermal and pressure relief valves are open with valve handles are removed, wired open or locked. Note: OM for Army, Navy, USMC; SM for AF Frequency: Monthly for Army, Navy, USMC; Quarterly for AF										See Description	SM						
T	C. Inspect valve exterior of thermal and pressure relief valves for corrosion. Repaint as required. Information plates attached to thermal and pressure relief valves shall not be painted over. Note: Per PWS Touch-up Coating Repair										Quarterly	SM						
T	D. Verify thermal and pressure relief valve setting by consulting as-built and historical data.										Annually	SM						
T	E. Thermal and pressure relief valves shall be validated for proper calibration by isolating the valve and using the test connection provided on the piping in conjunction with a hand pump and portable reservoir. The operating pressure shall be checked against the set pressure listed on the stamped information plate attached to the valve. The operating pressure shall be adjusted to the stamped set pressure if necessary. If there is no test connection provided, isolate the relief valve and remove the valve to test. If there is no valve isolation or test connection, consider adding these to simplify future testing. Note: Maintenance procedure shall include process to verify that the valve has properly reseated after all maintenance activities are performed on pressure relief valves or thermal and pressure relief valves.										Annually	SM						
I	6-6.3	149	Fuel Pier 149	Pier 149	Pressure Relief Valve	Pressure Relief Valve 100 PSIG SF-3	KAN-149-PRVL-0001	Taylor	T-8200-1	1"								
I	6-6.3	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Pressure Relief Valve	Pressure Relief Valve 100 PSIG Pit-A	KAN-1170-PRVL-0001	Taylor	T-8200-1	1"/100psi								
I	6-6.3	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Pressure Relief Valve	Pressure Relief Valve 100 PSIG Pit-B	KAN-1170-PRVL-0002	Taylor	T-8200-1	1"/100psi								
I	6-6.3	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Pressure Relief Valve	Pressure Relief Valve 100 PSIG Pit-C	KAN-1170-PRVL-0003	Taylor	T-8200-1	1"/100psi								
I	6-6.3	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Pressure Relief Valve	Pressure Relief Valve 100 PSIG Pit-D	KAN-1170-PRVL-0004	Taylor	T-8200-1	1"/100psi								
I	6-6.3	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Pressure Relief Valve	Pressure Relief Valve 100 PSIG F/S-100	KAN-1170-PRVL-0005	Taylor	T-8200-1	1"/100psi								
I	6-6.3	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Pressure Relief Valve	Pressure Relief Valve 100 PSIG F/S-102	KAN-1170-PRVL-0006	Taylor	T-8200-1	1"/100psi								
I	6-6.3	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Pressure Relief Valve	Pressure Relief Valve 100 PSIG F/S-103	KAN-1170-PRVL-0007	Taylor	T-8200-1	1"/100psi								
I	6-6.3	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Pressure Relief Valve	Pressure Relief Valve 100 PSIG F/S-104	KAN-1170-PRVL-0008	Taylor	T-8200-1	1"/100psi								
I	6-6.3	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Pressure Relief Valve	Pressure Relief Valve 150 PSIG F/S-105	KAN-1170-PRVL-0009	Taylor	T-8200-1	1"/150psi								

APPENDIX B - ATTACHMENT 3 RECURRING MAINTENANCE REPORT TEMPLATE

Contract47QSHA18D000Y W912DY21F0025

SiteKaneohe

Date26-Apr-22

RM Event(s)Q2, SA1, A BY

☒ Daily

☒ Weekly

☒ Monthly

☒ Quarterly

☒ Semi-annually

☒ Annually

☒ Every 3 years

☒ Every 5 years

☒ Every 10 years

Note: It is advised that "See Description" and "Reference to Other" always be displayed.

☒ See Description

☒ Reference to Other

☒ SM

☒ OM

Warning: Only adds Deficiencies marked "Y" in Col T.

Generate Deficiency List

RM Report Setup Only - See Instructions

Generate UFC Tasks

Applicable Facility Assets										UFC System Level Maintenance Frequency	Responsibility	RM Completion Record Result	Date Completed	Completed By	Deficiencies	Responsible FMSR	Notes	Add to Def List?
UFC Section Reference	Real Property Facility #	Real Property Facility Name	Operational Area	Component Type	Base Asset ID	Component Unique Identifier (CUID)	Make	Model	Capacity/Size									
I	6-6.3	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Pressure Relief Valve	Pressure Relief Valve 150 PSIG F/5-106	KAN-1170-PRVL-0010	Taylor	T-8200-1	1"/150psi								
I	6-6.3	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Pressure Relief Valve	Pressure Relief Valve 165 PSIG F/5-107	KAN-1170-PRVL-0011	Taylor	T-8200-1	1"/165psi								
I	6-6.3	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Pressure Relief Valve	Pressure Relief Valve 165 PSIG F/5-108	KAN-1170-PRVL-0012	Taylor	T-8200-1	1"/165psi								
I	6-6.3	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Pressure Relief Valve	Pressure Relief Valve 175 PSIG F/5-109	KAN-1170-PRVL-0013	Taylor	T-8200-1	1"/175psi								
I	6-6.3	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Pressure Relief Valve	Pressure Relief Valve 175 PSIG F/5-110	KAN-1170-PRVL-0014	Taylor	T-8200-1	1"/175psi								
I	6-6.3	1252	BULK FUEL STORAGE TANK F-24	Bulk Storage	Pressure Relief Valve	Pressure Relief Valve 175 PSIG 1252-1	KAN-1252-PRVL-0001	Taylor	T-8200-1	1"								
I	6-6.3	1252	BULK FUEL STORAGE TANK F-24	Bulk Storage	Pressure Relief Valve	Pressure Relief Valve 175 PSIG 1252-2	KAN-1252-PRVL-0002	Taylor	T-8200-1	1"								
I	6-6.3	1252	BULK FUEL STORAGE TANK F-24	Bulk Storage	Pressure Relief Valve	Pressure Relief Valve 175 PSIG 1252-3	KAN-1252-PRVL-0003	Taylor	T-8200-1	1"								
I	6-6.3	1253	BULK FUEL STORAGE TANK F-24	Bulk Storage	Pressure Relief Valve	Pressure Relief Valve 175 PSIG 1252-1	KAN-1253-PRVL-0001	Taylor	T-8200-1	1"								
I	6-6.3	1253	BULK FUEL STORAGE TANK F-24	Bulk Storage	Pressure Relief Valve	Pressure Relief Valve 175 PSIG 1252-2	KAN-1253-PRVL-0002	Taylor	T-8200-1	1"								
I	6-6.3	1253	BULK FUEL STORAGE TANK F-24	Bulk Storage	Pressure Relief Valve	Pressure Relief Valve 175 PSIG 1252-3	KAN-1253-PRVL-0003	Taylor	T-8200-1	1"								
I	6-6.3	1254	TRUCK OFFLOAD	Pump Station	Pressure Relief Valve	Pressure Relief Valve 100 PSIG PS-1	KAN-1254-PRVL-0001	Taylor	T-8200-1	1"								
I	6-6.3	1254	TRUCK OFFLOAD	Pump Station	Pressure Relief Valve	Pressure Relief Valve 100 PSIG PS-2	KAN-1254-PRVL-0002	Taylor	T-8200-1	1"								
I	6-6.3	1254	TRUCK OFFLOAD	Pump Station	Pressure Relief Valve	Pressure Relief Valve 100 PSIG PS-3	KAN-1254-PRVL-0003	Taylor	T-8200-1	1"								
I	6-6.3	1254	TRUCK OFFLOAD	Pump Station	Pressure Relief Valve	Pressure Relief Valve 100 PSIG PS-4	KAN-1254-PRVL-0004	Taylor	T-8200-1	1"								
I	6-6.3	1254	TRUCK OFFLOAD	Pump Station	Pressure Relief Valve	Pressure Relief Valve 100 PSIG PS-5	KAN-1254-PRVL-0005	Taylor	T-8200-1	1"								
I	6-6.3	1254	TRUCK OFFLOAD	Pump Station	Pressure Relief Valve	Pressure Relief Valve 100 PSIG PS-6	KAN-1254-PRVL-0006	Taylor	T-8200-1	1"								
I	6-6.3	1254	TRUCK OFFLOAD	Pump Station	Pressure Relief Valve	Pressure Relief Valve 89 PSIG PS-7	KAN-1254-PRVL-0007	Taylor	T-8200-1	1"								
I	6-6.3	1254	TRUCK OFFLOAD	Pump Station	Pressure Relief Valve	Pressure Relief Valve 89 PSIG PS-8	KAN-1254-PRVL-0008	Taylor	T-8200-1	1"								
I	6-6.3	1254	TRUCK OFFLOAD	Pump Station	Pressure Relief Valve	Pressure Relief Valve 89 PSIG PS-9	KAN-1254-PRVL-0009	Taylor	T-8200-1	1"								
I	6-6.3	1254	TRUCK OFFLOAD	Pump Station	Pressure Relief Valve	Pressure Relief Valve 89 PSIG PS-10	KAN-1254-PRVL-0010	Taylor	T-8200-1	1"								
I	6-6.3	1254	TRUCK OFFLOAD	Pump Station	Pressure Relief Valve	Pressure Relief Valve 185 PSIG PS-11	KAN-1254-PRVL-0011	Taylor	T-8200-1	1"								
I	6-6.3	1254	TRUCK OFFLOAD	Pump Station	Pressure Relief Valve	Pressure Relief Valve 185 PSIG PS-12	KAN-1254-PRVL-0012	Taylor	T-8200-1	1"								
I	6-6.3	1254	TRUCK OFFLOAD	Pump Station	Pressure Relief Valve	Pressure Relief Valve 185 PSIG PS-13	KAN-1254-PRVL-0013	Taylor	T-8200-1	1"								
I	6-6.3	6479	JET ENGINE FUEL STORAGE	Pump Station 6479A	Pressure Relief Valve	Pressure Relief Valve 100 PSIG 6479A-1	KAN-6479-PRVL-0001	Taylor	T-8200-1	1"								
I	6-6.3	6479	JET ENGINE FUEL STORAGE	Pump Station 6479A	Pressure Relief Valve	Pressure Relief Valve 100 PSIG 6479A-2	KAN-6479-PRVL-0002	Taylor	T-8200-1	1"								
I	6-6.3	6479	JET ENGINE FUEL STORAGE	Pump Station 6479A	Pressure Relief Valve	Pressure Relief Valve 100 PSIG 6479A-3	KAN-6479-PRVL-0003	Taylor	T-8200-1	1"								
I	6-6.3	6479	JET ENGINE FUEL STORAGE	Pump Station 6479A	Pressure Relief Valve	Pressure Relief Valve 100 PSIG 6479A-4	KAN-6479-PRVL-0004	Taylor	T-8200-1	1"								
I	6-6.3	6479	JET ENGINE FUEL STORAGE	Pump Station 6479A	Pressure Relief Valve	Pressure Relief Valve 100 PSIG 6479A-5	KAN-6479-PRVL-0005	Taylor	T-8200-1	1"								
I	6-6.3	6479	JET ENGINE FUEL STORAGE	Pump Station 6479A	Pressure Relief Valve	Pressure Relief Valve 100 PSIG 6479A-6	KAN-6479-PRVL-0006	Taylor	T-8200-1	1"								
I	6-6.3	6479	JET ENGINE FUEL STORAGE	Pump Station 6479A	Pressure Relief Valve	Pressure Relief Valve 100 PSIG 6479A-7	KAN-6479-PRVL-0007	Taylor	T-8200-1	1"								
I	6-6.3	6479	JET ENGINE FUEL STORAGE	Bulk Storage	Pressure Relief Valve	Pressure Relief Valve 100 PSIG 6479A-8	KAN-6479-PRVL-0008	Taylor	T-8200-1	1"								
I	6-6.3	6479	JET ENGINE FUEL STORAGE	Bulk Storage	Pressure Relief Valve	Pressure Relief Valve 100 PSIG 6479A-9	KAN-6479-PRVL-0009	Taylor	T-8200-1	1"								
I	6-6.3	6479	JET ENGINE FUEL STORAGE	Bulk Storage	Pressure Relief Valve	Pressure Relief Valve 100 PSIG 6479B-1	KAN-6479-PRVL-0010	Taylor	T-8200-1	1"								
I	6-6.3	6479	JET ENGINE FUEL STORAGE	Bulk Storage	Pressure Relief Valve	Pressure Relief Valve 140 PSIG 6479B-2	KAN-6479-PRVL-0011	Taylor	T-8200-1	1"								
I	6-6.3	6479	JET ENGINE FUEL STORAGE	Bulk Storage	Pressure Relief Valve	Pressure Relief Valve 140 PSIG 6479B-3	KAN-6479-PRVL-0012	Taylor	T-8200-1	1"								
I	6-6.3	6479	JET ENGINE FUEL STORAGE	Bulk Storage	Pressure Relief Valve	Pressure Relief Valve 140 PSIG 6479B-4	KAN-6479-PRVL-0013	Taylor	T-8200-1	1"								
I	6-6.3	6479	JET ENGINE FUEL STORAGE	Bulk Storage	Pressure Relief Valve	Pressure Relief Valve 140 PSIG 6479B-5	KAN-6479-PRVL-0014	Taylor	T-8200-1	1"								
I	6-6.3	6479	JET ENGINE FUEL STORAGE	Bulk Storage	Pressure Relief Valve	Pressure Relief Valve 140 PSIG 6479B-6	KAN-6479-PRVL-0015	Taylor	T-8200-1	1"								
I	6-6.3	1254A	STRAINER FACILITY	STRAINER STATION	Pressure Relief Valve	Pressure Relief Valve 225 PSIG SF-1	KAN-1254A-PRVL-0001	Taylor	T-8200-1	1"								
I	6-6.3	1254A	STRAINER FACILITY	STRAINER STATION	Pressure Relief Valve	Pressure Relief Valve 165 PSIG SF-2	KAN-1254A-PRVL-0002	Taylor	T-8200-1	1"								
I	6-6.3	1254A	STRAINER FACILITY	STRAINER STATION	Pressure Relief Valve	Pressure Relief Valve 100 PSIG SF-3	KAN-1254A-PRVL-0003	Taylor	T-8200-1	1"								
I	6-6.3	1254A	STRAINER FACILITY	STRAINER STATION	Pressure Relief Valve	Pressure Relief Valve 225 PSIG SF-1	KAN-1254A-PRVL-0004	Taylor	T-8200-1	1"								
I	6-6.3	1254A	STRAINER FACILITY	STRAINER STATION	Pressure Relief Valve	Pressure Relief Valve 165 PSIG SF-2	KAN-1254A-PRVL-0005	Taylor	T-8200-1	1"								
I	6-6.3	1254A	STRAINER FACILITY	STRAINER STATION	Pressure Relief Valve	Pressure Relief Valve 100 PSIG SF-3	KAN-1254A-PRVL-0006	Taylor	T-8200-1	1"								
I	6-6.3	1563-1	TRUCK LOAD FACILITY JP5	Load Rack - 1	Pressure Relief Valve	Pressure Relief Valve 125 PSIG LR-3	KAN-1563_1-PRVL-0001	Taylor	T-8200-1	1"								
I	6-6.3	1563-1	TRUCK LOAD FACILITY JP5	Load Rack - 1	Pressure Relief Valve	Pressure Relief Valve 125 PSIG LR-4	KAN-1563_1-PRVL-0002	Taylor	T-8200-1	1"								
I	6-6.3	1563-1	TRUCK LOAD FACILITY JP5	Load Rack - 1	Pressure Relief Valve	Pressure Relief Valve 75 PSIG LR-5	KAN-1563_1-PRVL-0003	Taylor	T-8200-1	1"								

RM Template v0.4.3

18

APPENDIX B - ATTACHMENT 3 RECURRING MAINTENANCE REPORT TEMPLATE

Contract47QSHA18D000Y W912DY21F0025

SiteKaneohe

Date26-Apr-22

RM Event(s)Q2, SA1, A BY

☐ Daily

☐ Weekly

☐ Monthly

☐ Quarterly

☐ Semi-annually

☐ Annually

☐ Every 3 years

☐ Every 5 years

☐ Every 10 years

Note: It is advised that "See Description" and "Reference to Other" always be displayed.

☐ See Description

☐ Reference to Other

☐ SM

☐ OM

Warning: Only adds Deficiencies marked "Y" in Col T.

Generate Deficiency List

RM Report Setup Only - See Instructions

Generate UFC Tasks

Applicable Facility Assets										UFC System Level Maintenance Frequency	Responsibility	RM Completion Record Result	Date Completed	Completed By	Deficiencies	Responsible FMSR	Notes	Add to Def List?	
UFC Section Reference	Real Property Facility #	Real Property Facility Name	Operational Area	Component Type	Base Asset ID	Component Unique Identifier (CUID)	Make	Model	Capacity/Size										
I	6-7.1	6479	JET ENGINE FUEL STORAGE	Bulk Storage	Pressure Gauge	6479B-4 - 0 to 300	KAN-6479-PVGA-0014	Terrice	UNK	1/4"									
I	6-7.1	6504	TRUCK LOAD/ OFFLOAD FACILITY	Load/Offload-Gas/DS-2/Bio-Deisel	Pressure Gauge	6504-1 - 0 to 300	KAN-6504-PVGA-0001	Terrice	UNK	1/4"									
I	6-7.1	6504	TRUCK LOAD/ OFFLOAD FACILITY	Load/Offload-Gas/DS-2/Bio-Deisel	Pressure Gauge	6504-2 - 0 to 300	KAN-6504-PVGA-0002	Terrice	UNK	1/4"									
I	6-7.1	6504	TRUCK LOAD/ OFFLOAD FACILITY	Load/Offload-Gas/DS-2/Bio-Deisel	Pressure Gauge	6504-3 - 0 to 300	KAN-6504-PVGA-0003	Terrice	UNK	1/4"									
I	6-7.1	6504	TRUCK LOAD/ OFFLOAD FACILITY	Load/Offload-Gas/DS-2/Bio-Deisel	Pressure Gauge	6504-1 - 30 to 30	KAN-6504-PVGA-0004	Terrice	UNK	1/4"									
I	6-7.1	6504	TRUCK LOAD/ OFFLOAD FACILITY	Load/Offload-Gas/DS-2/Bio-Deisel	Pressure Gauge	6504-2 - 30 to 30	KAN-6504-PVGA-0005	Terrice	UNK	1/4"									
I	6-7.1	1563-1	TRUCK LOAD FACILITY JP5	Load Rack - 1	Pressure Gauge	LR-100 - 0 to 300	KAN-1563_1-PVGA-0001	Terrice	2-1/2" Dial	1/4"									
I	6-7.1	1563-1	TRUCK LOAD FACILITY JP5	Load Rack - 1	Pressure Gauge	LR-101 - 0 to 300	KAN-1563_1-PVGA-0002	Terrice	2-1/2" Dial	1/4"									
I	6-7.1	1563-1	TRUCK LOAD FACILITY JP5	Load Rack - 1	Pressure Gauge	LR-102 - 0 to 300	KAN-1563_1-PVGA-0003	Terrice	2-1/2" Dial	1/4"									
I	6-7.1	1563-1	TRUCK LOAD FACILITY JP5	Load Rack - 1	Pressure Gauge	LR-103 - 0 to 300	KAN-1563_1-PVGA-0004	Terrice	2-1/2" Dial	1/4"									
I	6-7.1	1563-1	TRUCK LOAD FACILITY JP5	Load Rack - 1	Pressure Gauge	LR-104 - 0 to 300	KAN-1563_1-PVGA-0005	Terrice	2-1/2" Dial	1/4"									
I	6-7.1	1563-1	TRUCK LOAD FACILITY JP5	Load Rack - 1	Pressure Gauge	LR-105 - DP 0 to 15	KAN-1563_1-PVGA-0005	Gammon	2-1/2" Dial	1/4"									
I	6-7.1	1563-1	TRUCK LOAD FACILITY JP5	Load Rack - 1	Pressure Gauge	LR-106 - DP 0 to 15	KAN-1563_1-PVGA-0006	Gammon	2-1/2" Dial	1/4"									
I	6-7.1	1563-2	TRUCK LOADING FACILITY JP5	Load Rack - 2	Pressure Gauge	LR-105 - DP 0 to 15	KAN-1563_2-PVGA-0001	Gammon	2-1/2" Dial	1/4"									
I	6-7.1	1563-2	TRUCK LOADING FACILITY JP5	Load Rack - 2	Pressure Gauge	LR-106 - DP 0 to 15	KAN-1563_2-PVGA-0002	Gammon	2-1/2" Dial	1/4"									
I	6-7.1	1563-2	TRUCK LOADING FACILITY JP5	Load Rack - 2	Pressure Gauge	LR-100 - 0 to 300	KAN-1563_2-PVGA-0003	Terrice	2-1/2" Dial	1/4"									
I	6-7.1	1563-2	TRUCK LOADING FACILITY JP5	Load Rack - 2	Pressure Gauge	LR-101 - 0 to 300	KAN-1563_2-PVGA-0004	Terrice	2-1/2" Dial	1/4"									
I	6-7.1	1563-2	TRUCK LOADING FACILITY JP5	Load Rack - 2	Pressure Gauge	LR-102 - 0 to 300	KAN-1563_2-PVGA-0005	Terrice	2-1/2" Dial	1/4"									
I	6-7.1	1563-2	TRUCK LOADING FACILITY JP5	Load Rack - 2	Pressure Gauge	LR-103 - 0 to 300	KAN-1563_2-PVGA-0006	Terrice	2-1/2" Dial	1/4"									
I	6-7.1	1563-2	TRUCK LOADING FACILITY JP5	Load Rack - 2	Pressure Gauge	LR-104 - 0 to 300	KAN-1563_2-PVGA-0007	Terrice	2-1/2" Dial	1/4"									
I	6-7.1	1563-2	TRUCK LOADING FACILITY JP5	Load Rack - 3	Pressure Gauge	LR-3 - DP 0 to 15	KAN-1563_2-PVGA-0008	Gammon	UNK	UNK									
I	6-7.1	1563-2	TRUCK LOADING FACILITY JP5	Load Rack - 3	Pressure Gauge	Liquid Filled Gauge 0-300 - # 100	KAN-1563_2-PVGA-0009	Terrice	UNK	1/4"									
I	6-7.1	1563-2	TRUCK LOADING FACILITY JP5	Load Rack - 3	Pressure Gauge	Liquid Filled Gauge 0-300 - # 101	KAN-1563_2-PVGA-0010	Terrice	UNK	1/4"									
I	6-7.1	1563-2	TRUCK LOADING FACILITY JP5	Load Rack - 3	Pressure Gauge	Liquid Filled Gauge 0-300 - # 102	KAN-1563_2-PVGA-0011	Terrice	UNK	1/4"									
I	6-7.1	1563-2	TRUCK LOADING FACILITY JP5	Load Rack - 3	Pressure Gauge	Liquid Filled Gauge 30-30 - # 103	KAN-1563_2-PVGA-0012	Terrice	UNK	1/4"									
H	Differential Pressure Gauges (Section 6-7.2)																		
T	A. Verify proper operation of differential gauge in accordance with gauge manufacturer's procedures.										Quarterly	SM							
T	B. Clean outside of gauge glass.										Quarterly	OM							
T	C. Conduct calibration check by comparing readings of the differential process gauge with the readings of a certified differential master calibration gauge which has been calibrated within the last year. The differential process gauge and the differential master calibration gauge shall be connected to the same pressure source for testing. Verify accuracy of gauge is within ±2% of full scale. Calibrate if required.										Annually	SM							
T	D. Some differential pressure gauges have a small gauge protection filter located at the high pressure inlet of the gauge that must be checked and replaced as needed. Filters need to be replaced if the indicator is moving slow or sluggishly inside the sight glass or if the sight glass is dirty. Refer to manufacturer's operation and maintenance manual for filter replacement procedure. Frequency: Annually for inspections and maximum 5 years of service between filter replacements. Note: This task shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.										See Description	SM							
I	6-7.2	1254	TRUCK OFFLOAD	Pump Station	Differential Pressure Gauge	PS-100 - DP 0 to 15	KAN-1254-DPGA-0001	Gammon	UNK	PS-100 - DP 0 to 15									
I	6-7.2	1254	TRUCK OFFLOAD	Pump Station	Differential Pressure Gauge	PS-101 - DP 0 to 15	KAN-1254-DPGA-0002	Gammon	UNK	PS-101 - DP 0 to 15									
I	6-7.2	1254	TRUCK OFFLOAD	Pump Station	Differential Pressure Gauge	PS-102 - DP 0 to 15	KAN-1254-DPGA-0003	Gammon	UNK	PS-102 - DP 0 to 15									
I	6-7.2	1254	TRUCK OFFLOAD	Pump Station	Differential Pressure Gauge	PS-103 - DP 0 to 15	KAN-1254-DPGA-0004	Gammon	UNK	PS-103 - DP 0 to 15									
I	6-7.2	6479	JET ENGINE FUEL STORAGE	Bulk Storage	Differential Pressure Gauge	6479B-1	KAN-6479-DPGA-0001	UNK	UNK	UNK									
I	6-7.2	6479	JET ENGINE FUEL STORAGE	Bulk Storage	Differential Pressure Gauge	6479B-2	KAN-6479-DPGA-0002	UNK	UNK	UNK									
I	6-7.2	1254A	STRAINER FACILITY	STRAINER STATION	Differential Pressure Gauge	SF-1 - DP 0 to 15	KAN-1254A-DPGA-0001	Gammon	UNK	UNK									
I	6-7.2	1254A	STRAINER FACILITY	STRAINER STATION	Differential Pressure Gauge	SF-2 - DP 0 to 15	KAN-1254A-DPGA-0002	Gammon	UNK	UNK									
I	6-7.2	1563-1	TRUCK LOAD FACILITY JP5	Load Rack - 1	Differential Pressure Gauge	PS-103 - DP 0 to 15	KAN-1563_1-DPGA-0001	Gammon	UNK	LR-1 - DP 0 to 15									
I	6-7.2	1563-2	TRUCK LOADING FACILITY JP5	Load Rack - 2	Differential Pressure Gauge	PS-103 - DP 0 to 15	KAN-1563_2-DPGA-0001	Gammon	UNK	LR-2 - DP 0 to 15									
H	Low Point Drains (Section 6-12.1)																		
T	A. Visually inspect low point drains. Ensure that quick-disconnect dust caps are in place and that valves are locked closed.										Weekly	OM							
T	B. Operate low point drains when system is not under operating pressure. If there is an absence of sufficient line pressure close the low point drain and pressurize the system. Once adequate pressure is available, continue draining until the piping fuel sample is clear and bright with no visible water. Note: Verify low point drains are closed after maintenance.										Monthly	OM							
I	6-12.1	149	Fuel Pier 149	Pier 149 Under ground pipeline	Low Point Drain	Pier 149 - LP-1 Under ground pipeline 1170	KAN-149-LPDN-0001	UNK	UNK	UNK									
I	6-12.1	1170	Under ground pipeline 1170	Under ground pipeline	Low Point Drain	Operations tank 6479	KAN-1170-LPDN-0001	UNK	UNK	UNK									
I	6-12.1	1175	Under ground pipeline 1175	Under ground pipeline	Low Point Drain	Military Service Station	KAN-1175-LPDN-0001	UNK	UNK	UNK									
I	6-12.1	6503	FUEL STATION	Military Service Station	Low Point	Military Service Station	KAN-6503-LPDN-0001	UNK	UNK	UNK									
H	Dispenser Nozzles (Section 7-2)																		

RM Template v0.4.3

20

APPENDIX B - ATTACHMENT 3 RECURRING MAINTENANCE REPORT TEMPLATE

Contract47QSHA18D000Y W912DY21F0025

SiteKaneohe

Date26-Apr-22

RM Event(s)Q2, SA1, A BY

☒ Daily

☒ Weekly

☒ Monthly

☒ Quarterly

☒ Semi-annually

☒ Annually

☒ Every 3 years

☒ Every 5 years

☒ Every 10 years

Note: It is advised that "See Description" and "Reference to Other" always be displayed.

☒ See Description

☒ Reference to Other

☒ SM

☒ OM

Warning: Only adds Deficiencies marked "Y" in Col T.

Generate Deficiency List

RM Report Setup Only - See Instructions

Generate UFC Tasks

Applicable Facility Assets										UFC System Level Maintenance Frequency	Responsibility	RM Completion Record Result	Date Completed	Completed By	Deficiencies	Responsible FMSR	Notes	Add to Def List?	
UFC Section Reference	Real Property Facility #	Real Property Facility Name	Operational Area	Component Type	Base Asset ID	Component Unique Identifier (CUID)	Make	Model	Capacity/Size										
T		A. Inspect dispenser nozzle spout. Ensure it is tight, round, has no cracks, or excessive wear. Inspect automatic shutoff hole. Ensure the hole is open and free of obstructions. Inspect nozzle hold-open latch. Ensure the latch is straight, moves freely, and the return spring operates correctly. Inspect body of nozzle. Ensure the body is in good condition and that the valve stem is clean and free of fuel. Inspect the nozzle to hose connection and ensure it is clean and free of fuel.									Daily	OM							
T		B. Dispenser nozzle handles must be inspected for an expiration date established by the manufacturer. Nozzles must be replaced before the indicated expiration date. Task deleted in UFC 3-460-03 Change 1.																	
T		C. Test automatic shutoff feature and ensure it is operating properly. Test automatic shutoff at all nozzle hold-open latch positions.									Annually	SM							
I	7-2	6503	FUEL STATION	Military Service Station	Nozzle, Dispenser	Nozzle, Dispenser	KAN-6503-DSNZ-0001	UNK	UNK	UNK									
I	7-2	6503	FUEL STATION	Military Service Station	Nozzle, Dispenser	Nozzle, Dispenser	KAN-6503-DSNZ-0002	UNK	UNK	UNK									
I	7-2	6503	FUEL STATION	Military Service Station	Nozzle, Dispenser	Nozzle, Dispenser	KAN-6503-DSNZ-0003	UNK	UNK	UNK									
I	7-2	6503	FUEL STATION	Military Service Station	Nozzle, Dispenser	Nozzle, Dispenser	KAN-6503-DSNZ-0004	UNK	UNK	UNK									
I	7-2	6503	FUEL STATION	Military Service Station	Nozzle, Dispenser	Nozzle, Dispenser	KAN-6503-DSNZ-0006	UNK	UNK	UNK									
I	7-2	6503	FUEL STATION	Military Service Station	Nozzle, Dispenser	Nozzle, Dispenser	KAN-6503-DSNZ-0007	UNK	UNK	UNK									
I	7-2	6645	SMALL CRAFT FUEL STA AND STORAGE	Waterfront	Nozzle, Dispenser	Nozzle, Dispenser	KAN-6645-DSNZ-0005	UNK	UNK	UNK									
H	Dispenser Hoses (Section 7-3)																		
T		A. Inspect dispenser hoses and hose whips for gouges, cuts, blisters, or outside wear that may lead to rupture during use. Replace hose or hose whips that show signs of wear. Inspect connection points of hoses and hose whips to the dispenser, breakaways, swivels, and the nozzle and ensure the connection points are clean and free of fuel.									Daily	OM							
I	7-3	6503	FUEL STATION	Military Service Station	Hose, Dispenser	Hose, Dispenser	KAN-6503-DSHS-0001	UNK	UNK	UNK									
I	7-3	6503	FUEL STATION	Military Service Station	Hose, Dispenser	Hose, Dispenser	KAN-6503-DSHS-0002	UNK	UNK	UNK									
I	7-3	6503	FUEL STATION	Military Service Station	Hose, Dispenser	Hose, Dispenser	KAN-6503-DSHS-0003	UNK	UNK	UNK									
I	7-3	6503	FUEL STATION	Military Service Station	Hose, Dispenser	Hose, Dispenser	KAN-6503-DSHS-0004	UNK	UNK	UNK									
I	7-3	6503	FUEL STATION	Military Service Station	Hose, Dispenser	Hose, Dispenser	KAN-6503-DSHS-0005	UNK	UNK	UNK									
I	7-3	6645	SMALL CRAFT FUEL STA AND STORAGE	Waterfront	Hose, Dispenser	1"x100'	KAN-6645-DSHS-0001	UNK	UNK	1"x100'									
H	Breakaways (Section 7-4)																		
T		A. Inspect breakaways for loose connections and signs of damage to poppets. Ensure breakaways are clean and free of fuel.									Daily	OM							
T		B. Inspect breakaway for an expiration date established by the manufacturer. Breakaways must be replaced before the indicated expiration date.									Monthly	OM							
I	7-4	6503	FUEL STATION	Military Service Station	Breakaway, Dispenser	Breakaway, Dispenser	KAN-6503-DSBW-0001	UNK	UNK	UNK									
I	7-4	6503	FUEL STATION	Military Service Station	Breakaway, Dispenser	Breakaway, Dispenser	KAN-6503-DSBW-0002	UNK	UNK	UNK									
I	7-4	6503	FUEL STATION	Military Service Station	Breakaway, Dispenser	Breakaway, Dispenser	KAN-6503-DSBW-0003	UNK	UNK	UNK									
I	7-4	6503	FUEL STATION	Military Service Station	Breakaway, Dispenser	Breakaway, Dispenser	KAN-6503-DSBW-0004	UNK	UNK	UNK									
I	7-4	6503	FUEL STATION	Military Service Station	Breakaway, Dispenser	Breakaway, Dispenser	KAN-6503-DSBW-0005	UNK	UNK	UNK									
I	7-4	6645	SMALL CRAFT FUEL STA AND STORAGE	Waterfront	Breakaway, Dispenser	Breakaway, Dispenser	KAN-6645-DSBW-0001	UNK	UNK	UNK									
H	Swivels (Section 7-5)																		
T		A. Inspect swivel for loose connections and signs of damage. Ensure swivel rotates easily and is clean and free of fuel.									Daily	OM							
T		B. Inspect swivel for expiration date established by manufacturer. Swivels must be replaced before the indicated expiration date.									Monthly	OM							
I	7-5	6503	FUEL STATION	Military Service Station	Swivel, Dispenser	Swivel, Dispenser	KAN-6503-DSSW-0001	UNK	UNK	UNK									
I	7-5	6503	FUEL STATION	Military Service Station	Swivel, Dispenser	Swivel, Dispenser	KAN-6503-DSSW-0002	UNK	UNK	UNK									
I	7-5	6503	FUEL STATION	Military Service Station	Swivel, Dispenser	Swivel, Dispenser	KAN-6503-DSSW-0003	UNK	UNK	UNK									
I	7-5	6503	FUEL STATION	Military Service Station	Swivel, Dispenser	Swivel, Dispenser	KAN-6503-DSSW-0004	UNK	UNK	UNK									
I	7-5	6503	FUEL STATION	Military Service Station	Swivel, Dispenser	Swivel, Dispenser	KAN-6503-DSSW-0005	UNK	UNK	UNK									
I	7-5	6645	SMALL CRAFT FUEL STA AND STORAGE	Waterfront	Swivel, Dispenser	Swivel, Dispenser	KAN-6645-DSSW-0001	UNK	UNK	UNK									
H	Hose Retriever (Section 7-6)																		
T		A. Test hose retriever and ensure it is operating correctly and supporting the hose.									Monthly	OM							
I	7-6	6503	FUEL STATION	Military Service Station	Retriever, Dispenser	Retriever, Dispenser	KAN-6503-HSRTV-0001	UNK	UNK	UNK									
I	7-6	6503	FUEL STATION	Military Service Station	Retriever, Dispenser	Retriever, Dispenser	KAN-6503-HSRTV-0002	UNK	UNK	UNK									
I	7-6	6503	FUEL STATION	Military Service Station	Retriever, Dispenser	Retriever, Dispenser	KAN-6503-HSRTV-0003	UNK	UNK	UNK									
I	7-6	6503	FUEL STATION	Military Service Station	Retriever, Dispenser	Retriever, Dispenser	KAN-6503-HSRTV-0004	UNK	UNK	UNK									
I	7-6	6503	FUEL STATION	Military Service Station	Retriever, Dispenser	Retriever, Dispenser	KAN-6503-HSRTV-0005	UNK	UNK	UNK									
I	7-6	6645	SMALL CRAFT FUEL STA AND STORAGE	Waterfront	Retriever, Reel, Dispenser	Retriever, Reel, Dispenser	KAN-6645-HSRTV-0001	UNK	UNK	UNK									
H	Dispenser Cabinet (Section 7-7)																		

APPENDIX B - ATTACHMENT 3 RECURRING MAINTENANCE REPORT TEMPLATE

Contract47QSHA18D000Y W912DY21F0025

SiteKaneohe

Date26-Apr-22

RM Q2, SA1, A BY

Event(s)

☒ Daily

☒ Weekly

☒ Monthly

☒ Quarterly

☒ Semi-annually

☒ Annually

☒ Every 3 years

☒ Every 5 years

☒ Every 10 years

Note: It is advised that "See Description" and "Reference to Other" always be displayed.

☒ See Description

☒ Reference to Other

☒ SM

☒ OM

Warning: Only adds Deficiencies marked "Y" in Col T.

Generate Deficiency List

RM Report Setup Only - See Instructions

Generate UFC Tasks

Applicable Facility Assets										UFC System Level Maintenance Frequency	Responsibility	RM Completion Record Result	Date Completed	Completed By	Deficiencies	Responsible FMSR	Notes	Add to Def List?	
UFC Section Reference	Real Property Facility #	Real Property Facility Name	Operational Area	Component Type	Base Asset ID	Component Unique Identifier (CUID)	Make	Model	Capacity/Size										
T	A. Inspect outside of cabinet and ensure it is free of damage. Inspect for fuel stains on the concrete island around the cabinet and on the outside of the cabinet. Ensure the cabinet is free of dirt and fuel.										Monthly	OM							
T	B. Open both sides of the cabinet and inspect the inside of the cabinet. Ensure the inside of the cabinet and all of the components inside the cabinet are clean and free of fuel.										Monthly	OM							
T	C. Ensure door panels and locks operate easily. Inspect anchor bolts of cabinet to dispenser island and ensure the bolts are in good condition.										Annually	SM							
I	7-7	6503	FUEL STATION	Military Service Station	Cabinet, Dispenser	Cabinet, Dispenser	KAN-6503-DSCB-0001	UNK	UNK	UNK									
I	7-7	6503	FUEL STATION	Military Service Station	Cabinet, Dispenser	Cabinet, Dispenser	KAN-6503-DSCB-0002	UNK	UNK	UNK									
I	7-7	6503	FUEL STATION	Military Service Station	Cabinet, Dispenser	Cabinet, Dispenser	KAN-6503-DSCB-0003	UNK	UNK	UNK									
I	7-7	6503	FUEL STATION	Military Service Station	Cabinet, Dispenser	Cabinet, Dispenser	KAN-6503-DSCB-0004	UNK	UNK	UNK									
I	7-7	6503	FUEL STATION	Military Service Station	Cabinet, Dispenser	Cabinet, Dispenser	KAN-6503-DSCB-0005	UNK	UNK	UNK									
I	7-7	6645	SMALL CRAFT FUEL STA AND STORAGE	Waterfront	Cabinet, Dispenser	Cabinet, Dispenser	KAN-6645-DSCB-0001	UNK	UNK	UNK									
H	Dispenser Meters (Section 7-8)																		
T	A. Inspect meter and ensure meter is clean and free of fuel. Ensure calibration mechanism is sealed.										Monthly	OM							
T	B. Since moving parts inside meters are subject to wear, periodic calibration is necessary. Meters shall be recalibrated utilizing a certified 5 gallon (20 liter) prover can or other approved method. Meters are considered satisfactory for further operation when the error does not exceed ±0.2% of actual quantity delivered.										Annually	SM							
I	7-8	6503	FUEL STATION	Military Service Station	Meter, Dispenser	Meter, Dispenser	KAN-6503-DSMTR-0001	Gasboy Atlas	9853KX	UNK									
I	7-8	6503	FUEL STATION	Military Service Station	Meter, Dispenser	Meter, Dispenser	KAN-6503-DSMTR-0002	Gasboy Atlas	9853KX	UNK									
I	7-8	6503	FUEL STATION	Military Service Station	Meter, Dispenser	Meter, Dispenser	KAN-6503-DSMTR-0003	Gasboy Atlas	9853KX	UNK									
I	7-8	6503	FUEL STATION	Military Service Station	Meter, Dispenser	Meter, Dispenser	KAN-6503-DSMTR-0004	Gasboy Atlas	9853KX	UNK									
I	7-8	6503	FUEL STATION	Military Service Station	Meter, Dispenser	Meter, Dispenser	KAN-6503-DSMTR-0006	Wayne	G6202D/27AGJ/AH8 W1	UNK									
I	7-8	6503	FUEL STATION	Military Service Station	Meter, Dispenser	Meter, Dispenser	KAN-6503-DSMTR-0007	Wayne	G6202D/27AGJ/AH8 W1	UNK									
I	7-8	6645	SMALL CRAFT FUEL STA AND STORAGE	Waterfront	Meter, Dispenser	Meter, Dispenser	KAN-6645-DSMTR-0001	UNK	UNK	UNK									
H	Dispenser Filters (Section 7-9)																		
T	A. Inspect filter and ensure filter is clean and free of fuel and that filter is labeled with a legible installation date.										Quarterly	OM							
T	B. Replace dispenser filters annually or when a change in flow rate is noted. Note: Routine filter changes shall be performed as part of the maintenance activities. Filter changes required due to a repair or other circumstance beyond normal system operation shall be performed by service order.										Annually	SM							
I	7-9	6503	FUEL STATION	Military Service Station	Filter, Dispenser	Filter, Dispenser	KAN-6503-DSFLR-0001	CIM-TEK	UNK	UNK									
I	7-9	6503	FUEL STATION	Military Service Station	Filter, Dispenser	Filter, Dispenser	KAN-6503-DSFLR-0002	CIM-TEK	UNK	UNK									
I	7-9	6503	FUEL STATION	Military Service Station	Filter, Dispenser	Filter, Dispenser	KAN-6503-DSFLR-0003	CIM-TEK	UNK	UNK									
I	7-9	6503	FUEL STATION	Military Service Station	Filter, Dispenser	Filter, Dispenser	KAN-6503-DSFLR-0004	CIM-TEK	UNK	UNK									
I	7-9	6503	FUEL STATION	Military Service Station	Filter, Dispenser	Filter, Dispenser	KAN-6503-DSFLR-0006	CIM-TEK	UNK	UNK									
I	7-9	6503	FUEL STATION	Military Service Station	Filter, Dispenser	Filter, Dispenser	KAN-6503-DSFLR-0007	CIM-TEK	UNK	UNK									
I	7-9	6645	SMALL CRAFT FUEL STA AND STORAGE	Waterfront	Filter, Dispenser	Filter, Dispenser	KAN-6645-DSFLR-0001	CIM-TEK	UNK	UNK									
H	Dispenser Strainers (Section 7-10)																		
T	A. Inspect and clean strainers. Inspect strainer cover gasket for cracks, distortion, and dry rot. If breaks are detected in strainer mesh, replace the strainer.										Annually	SM							
I	7-10	6503	FUEL STATION	Military Service Station	Strainer, Dispenser	Strainer, Dispenser	KAN-6503-DSSTR-0001	UNK	UNK	UNK									
I	7-10	6503	FUEL STATION	Military Service Station	Strainer, Dispenser	Strainer, Dispenser	KAN-6503-DSSTR-0002	UNK	UNK	UNK									
I	7-10	6503	FUEL STATION	Military Service Station	Strainer, Dispenser	Strainer, Dispenser	KAN-6503-DSSTR-0003	UNK	UNK	UNK									
I	7-10	6503	FUEL STATION	Military Service Station	Strainer, Dispenser	Strainer, Dispenser	KAN-6503-DSSTR-0004	UNK	UNK	UNK									
I	7-10	6503	FUEL STATION	Military Service Station	Strainer, Dispenser	Strainer, Dispenser	KAN-6503-DSSTR-0005	UNK	UNK	UNK									
H	Ground Vehicle Fuel Piping (Section 7-11)																		
T	F. Refer to Section 2.7 Signage and Markings for inspection and maintenance requirements of ground vehicle petroleum fuel pipe markings.										Reference to Other	SM							
T	G. Refer to Section 6-10.1 Aboveground Piping and Equipment Coatings for inspection and maintenance requirements of ground vehicle petroleum fuel pipe coatings.										Reference to Other	SM							
T	A. Visually inspect aboveground lines for leaks. Shut down systems that are found with leaks and repair. * *Note: Recommend shut down of facility to FMSR.										Daily	OM							
T	B. Visually inspect leak detection systems installed on underground piping. Inspections include line leak detectors and leak detection sensors installed in transition sumps and dispenser sumps. Perform leak testing on pressurized underground piping with installed leak detection equipment and record results.										Quarterly	SM							
T	C. Test leak detection systems installed on underground piping used for ground vehicle petroleum fuel products. Underground leak detection systems include discrete detection sensors installed in transition and dispenser sumps, and line leak detectors installed at the outlet of pumps used to supply pressurized liquid petroleum fuel to underground lines. Repair faulty components. Execution of this work may require State certification or license.										Annually	SM							
T	D. Conduct service station aboveground piping annual test as outlined in Appendix G - Petroleum Fuel Pipeline Pressure Testing Guidelines and Criteria. Execution of this work may require State certification or license.										Annually	SM							

APPENDIX B - ATTACHMENT 3 RECURRING MAINTENANCE REPORT TEMPLATE

Contract47QSHA18D000Y W912DY21F0025

SiteKaneohe

Date26-Apr-22

RM Event(s)Q2, SA1, A BY

☒ Daily

☒ Weekly

☒ Monthly

☒ Quarterly

☒ Semi-annually

☒ Annually

☒ Every 3 years

☒ Every 5 years

☒ Every 10 years

Note: It is advised that "See Description" and "Reference to Other" always be displayed.

☒ See Description

☒ Reference to Other

☒ SM

☒ OM

Warning: Only adds Deficiencies marked "Y" in Col T.

Generate Deficiency List

RM Report Setup Only - See Instructions

Generate UFC Tasks

Applicable Facility Assets										UFC System Level Maintenance Frequency	Responsibility	RM Completion Record Result	Date Completed	Completed By	Deficiencies	Responsible FMSR	Notes	Add to Def List?	
UFC Section Reference	Real Property Facility #	Real Property Facility Name	Operational Area	Component Type	Base Asset ID	Component Unique Identifier (CUID)	Make	Model	Capacity/Size										
T	E. Conduct service station underground piping annual test outlined in Appendix G - Petroleum Fuel Pipeline Pressure Testing Guidelines and Criteria. Execution of this work may require State certification or license.										Annually	SM							
I	7-11	6503	FUEL STATION	Military Service Station	Ground Vehicle Fuel Piping	Ground Vehicle Piping	KAN-6503-GVFP-0001	UNK	UNK	UNK									
H	Emergency Shutoff Valves (Shear Valves) (Section 7-12)																		
T	A. Inspect stabilizer bar to ensure that it is securely mounted below the base of the dispenser. Inspect the mounting bolts that secure the emergency shutoff valve to the stabilizer bar.										Monthly	OM							
T	B. Inspect fusible link and ensure it is not obstructed. Ensure valve body is clean and free of fuel.										Monthly	OM							
T	C. Inspect mechanical links of the valve for correct operation. Conduct test of valve to ensure it operates correctly. Execution of this work may require State certification or license.										Annually	SM							
I	7-12	6503	FUEL STATION	Military Service Station	Shear Valve, Emergency Shutoff Valve	Shear Valve, Emergency Shutoff Valve	KAN-6503-ESHLV-0001	OPW	10BH-5830	1-1/2"									
I	7-12	6503	FUEL STATION	Military Service Station	Shear Valve, Emergency Shutoff Valve	Shear Valve, Emergency Shutoff Valve	KAN-6503-ESHLV-0002	OPW	10BH-5830	1-1/2"									
I	7-12	6503	FUEL STATION	Military Service Station	Shear Valve, Emergency Shutoff Valve	Shear Valve, Emergency Shutoff Valve	KAN-6503-ESHLV-0003	OPW	10BH-5830	1-1/2"									
I	7-12	6503	FUEL STATION	Military Service Station	Shear Valve, Emergency Shutoff Valve	Shear Valve, Emergency Shutoff Valve	KAN-6503-ESHLV-0004	OPW	10BH-5830	1-1/2"									
I	7-12	6503	FUEL STATION	Military Service Station	Shear Valve, Emergency Shutoff Valve	Shear Valve, Emergency Shutoff Valve	KAN-6503-ESHLV-0005	OPW	10BH-5830	1-1/2"									
H	EFSO Systems (Section 7-16)																		
T	B. Refer to Section 2-7 Signage and Markings for inspection and maintenance requirements of EFSO pushbutton signs.										Reference to Other	SM							
T	A. Check the operation of the EFSO system by activating the fueling system and then pressing each of the EFSO buttons. Ensure that each button disables power to all of the dispensers and fuel pumps installed at the service station.										Quarterly	SM							
I	7-16	1170	ACFT DIR FUEL ISLAND	Flightline Pits	EFSO Systems	Filter Separator - 1	KAN-1170-EFSO-0001	UNK	UNK	UNK									
I	7-16	1170	ACFT DIR FUEL ISLAND	Flightline Pits	EFSO Systems	Filter Separator - 2	KAN-1170-EFSO-0002	UNK	UNK	UNK									
I	7-16	1170	ACFT DIR FUEL ISLAND	Flightline Pits	EFSO Systems	Fuel Pit Bild.	KAN-1170-EFSO-0003	UNK	UNK	UNK									
I	7-16	6479	JET ENGINE FUEL STORAGE	Bulk Storage Tank	EFSO Systems	ESO	KAN-6479-EFSO-0001	UNK	UNK	UNK									
I	7-16	6479	JET ENGINE FUEL STORAGE	Bulk Storage Tank	EFSO Systems	ESO	KAN-6479-EFSO-0002	UNK	UNK	UNK									
I	7-16	6503	FUEL STATION	Military Service Station	EFSO Systems	ESO-1	KAN-6503-EFSO-0001	UNK	UNK	UNK									
I	7-16	6503	FUEL STATION	Military Service Station	EFSO Systems	ESO-2	KAN-6503-EFSO-0002	UNK	UNK	UNK									
I	7-16	6504	TRUCK LOAD/ OFFLOAD FACILITY	Load/Offload-Gas/DS-2/Bio-Deisel	EFSO Systems	EFSO	KAN-6504-EFSO-0001	UNK	UNK	UNK									
I	7-16	6645	SMALL CRAFT FUEL STA AND STORAGE	Waterfront	EFSO Systems	ESO	KAN-6645-EFSO-0001	UNK	UNK	UNK									
I	7-16	6745	BULK FUEL STORAGE TANK 6745	Military Service Station	EFSO Systems	ESO	KAN-6745-EFSO-0001	UNK	UNK	UNK									
H	Aboveground Field-Erected Tanks (Section 8-4)																		
T	A. Visually inspect for evidence of leaks; shell distortions; signs of settlement; corrosion, condition of tank foundation, condition of coating, insulation systems, and appurtenances. Inspection shall include all components and equipment located inside the containment area such as piping, pipe supports, containment valves, and product saver tanks. Items noted during the inspection will be documented for follow-up action by an authorized inspector. See Appendix F for the Field-Erected Tank Monthly Inspection Checklist.										Monthly	OM							
T	B. Visually inspect bottom edge projection (chime) to ringwall sealant. Seal should be maintained in good working order to prevent corrosion of the underside of the tank bottom.										Monthly	OM							
T	C. Visually inspect the exterior of the tank for leaks, corrosion, or irregularities such as tilting, settling, or out-of-roundness. Give special attention to seams and anchor bolts. Visual inspection shall include all components and equipment located inside the tank containment area such as piping, pipe supports, containment valves, and product saver tanks. Retain records of inspections reports for five years. See Appendix F for the Field-Erected Tank Annual Inspection Checklist.										Annually	OM							
T	D. Perform a formal in-service external inspection of the tank in accordance with API 653 or STI SP001 to evaluate the tank for conditions which may affect the operational integrity of the storage tank, including minimum shell thickness measurements. This inspection must be performed by an applicable certified inspector. Inspection shall include all components and equipment located inside the tank containment area such as piping, pipe supports, containment valves, and product saver tanks. Frequency: Every five years or as required by an appropriately certified tank inspector in the previous API 653 or STI SP001 inspection report. Note: This task shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.										Every 5 years	SM							
T	E. Perform an out-of-service API 653 or STI SP001 inspection to evaluate the tank for conditions which may affect the operational integrity of the tank floor, shell, roof and floating roof or pan. API 653 or STI SP001 provides a checklist to be used as part of the assessment. This inspection must be performed by an appropriately certified API 653 or STI SP001 inspector. Inspection shall include all components and equipment located inside the tank containment area such as piping, pipe supports, containment valves, and product saver tanks. The API 653 or STI SP001 inspector must recommend the date of the next inspection. The inspection interval must be based on the date the Suitability for Service Letter is issued immediately prior to when the tank is returned to service. Frequency: As recommended by the API 653 or STI SP001 inspector. If there is not a previous recommendation, the inspection must be performed within ten years after the tank was placed into operation. Note: This task shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.										Every 10 Years	SM							
I	8-4	1252	BULK FUEL STORAGE TANK F24	Bulk Storage	Tank	Tank	KAN-1252-AGFET-0001	UNK	UNK	28 MBBL									
I	8-4	1253	BULK FUEL STORAGE TANK F24	Bulk Storage	Tank	Tank	KAN-1253-AGFET-0001	UNK	UNK	28 MBBL									
H	Aboveground Shop Fabricated Tanks (Section 8-5.1)																		
T	A. Monthly External Inspection (Identified as P in STI SP001): Visually inspect for exterior signs of corrosion or coating deterioration. Visually inspect weld seams, tank-to-saddle connections, tank supports, tank anchors, foundation and anchor bolts, overfill valves and alarms, normal vents, emergency vents, leak detection probe or water/petroleum accumulation in the interstice on double-walled tanks, leaking valves, fittings, or components, spill containment systems and release prevention barriers. Leaking valves, fittings or components shall be repaired immediately or immediately removed from service and isolated to prevent further discharge. Any irregularities, (e.g., missing valve handles, bolts, nuts, screens) will be assessed for priority and repaired as soon as possible or as required depending on the nature of the defect (See Appendix E for an example of the STI SP001 Standard Monthly Inspection Checklist).										Monthly	OM							
T	B. Annual External Inspection (Identified as P in STI SP001): A more detailed examination of the tank and appurtenances shall be performed on an annual basis (See Appendix E for an example of the STI SP001 Standard Annual Inspection Checklist).										Annually	OM							

APPENDIX B - ATTACHMENT 3 RECURRING MAINTENANCE REPORT TEMPLATE

Contract47QSHA18D000Y W912DY21F0025

SiteKaneohe

Date26-Apr-22

RM Event(s)Q2, SA1, A BY

☐ Daily

☐ Weekly

☐ Monthly

☐ Quarterly

☐ Semi-annually

☐ Annually

☐ Every 3 years

☐ Every 5 years

☐ Every 10 years

Note: It is advised that "See Description" and "Reference to Other" always be displayed.

☐ See Description

☐ Reference to Other

☒ SM

☒ OM

Warning: Only adds Deficiencies marked "Y" in Col T.

Generate Deficiency List

RM Report Setup Only - See Instructions

Generate UFC Tasks

Applicable Facility Assets										UFC System Level Maintenance Frequency	Responsibility	RM Completion Record Result	Date Completed	Completed By	Deficiencies	Responsible FMSR	Notes	Add to Def List?						
UFC Section Reference	Real Property Facility #	Real Property Facility Name	Operational Area	Component Type	Base Asset ID	Component Unique Identifier (CUID)	Make	Model	Capacity/Size															
T	C. Formal External Inspection (Identified as E in STI SP001): A formal external inspection as defined in STI SP001 Standard for the Inspection of Aboveground Storage Tanks shall be conducted by certified STI SP001 inspector. Frequency: As established by SCP based on tank size and category listed in STI SP001 Note: This task shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.										See Description	SM												
	D. Formal Internal Inspection (Identified as I in STI SP001): A formal internal inspection as defined in STI SP001 Standard for the Inspection of Aboveground Storage Tanks shall be performed by a certified STI SP001 inspector. Frequency: As established by SCP based on tank size and category listed in STI SP001 Note: This task shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.										See Description	SM												
	E. Leak Test (Identified as L in STI SP001): A leak test as defined in STI SP001 Standard for the Inspection of Aboveground Storage Tanks shall be performed in accordance with STI SP001 Standard for the Inspection of Aboveground Storage Tanks. Frequency: As established by SCP based on tank size and category listed in STI SP001 Note: This task shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.										See Description	SM												
I	8-5.1	6479	JET ENGINE FUEL STORAGE	Bulk Storage	Tank	Tank	KAN-6479-AGSFP-0001	UNK	UNK	5 MBBL														
I	8-5.1	6496	BULK FUEL STORAGE TANK JP-5	Bulk Storage	Tank	Tank	KAN-6496-AGSFP-0001	UNK	UNK	12 K Gal														
I	8-5.1	6645	SMALL CRAFT FUEL STA AND STORAGE	Waterfront	Tank	Tank	KAN-6645-AGSFP-0001	Containment Solutions	91238	1,000 Gallon														
I	8-5.1	6745	BULK FUEL STORAGE TANK E-85	Military Service Station	Tank	Tank	KAN-6745-AGSFP-0001	Regal Tanks	Fireguard 6k	8,000 Gallon														
I	8-5.1	6506-1	MOGAS FUEL TANK	Military Service Station	Tank 1	BULK FUEL STORAGE TANK Mogas #1	KAN-6506_1-AGSFP-0001	ISOM Brothers	RIVS 1570-1	12,000 Gallon														
I	8-5.1	6506-2	MOGAS FUEL TANK	Military Service Station	Tank 2	BULK FUEL STORAGE TANK Mogas #2	KAN-6506_2-AGSFP-0001	ISOM Brothers	RIVS 1570-2	12,000 Gallon														
I	8-5.1	6506-3	BIODIESEL READY FUEL STORAGE	Military Service Station	Tank 3	BULK FUEL STORAGE TANK Bio-Diesel	KAN-6506_3-AGSFP-0001	ISOM Brothers	RIVS 1570-0	10,000 Gallon														
I	8-5.1	6506-4	DIESEL FUEL STORAGE	Military Service Station	Tank 4	BULK FUEL STORAGE TANK Diesl	KAN-6506_4-AGSFP-0001	ISOM Brothers	RIVS 1570-5	12,000 Gallon														
I	8-5.1	6506-5	JP8 FUEL STORAGE	Military Service Station	Tank 5	BULK FUEL STORAGE TANK F24	KAN-6506_5-AGSFP-0001	ISOM Brothers	RIVS 1570-2	12,000 Gallon														
H	External High Level Shutoff Valves (HLSO) (Section 8-9.6.1)																							
T	A. Activate the tank high-high level alarm and ensure the solenoid valve (if equipped) activates on the HLSO valve. Ensure the HLSO valve closes when the solenoid valve is activated.										Quarterly	SM												
T	B. Isolate, drain, and then vent the external float valve chamber (if equipped). Refill (either manually or via the storage tank product saver tank pump) the float chamber to test the float valve. Ensure the HLSO closes when the float is raised.										Annually	SM												
T	C. Lift the manual test lever of internally mounted float valve (if equipped). Ensure that the HLSO closes when the float of the float valve is raised.										Annually	SM												
I	8-9.6.1	1252	BULK FUEL STORAGE TANK F-24	Bulk Storage	Flow Control Valve	150 Class; Flanged Manual	KAN-1252-EHLSVL-0001	CLA-VAL	UNK	10"														
I	8-9.6.1	1253	BULK FUEL STORAGE TANK F-24	Bulk Storage	Flow Control Valve	150 Class; Flanged Manual	KAN-1253-EHLSVL-0001	CLA-VAL	UNK	10"														
H	Containment Systems (General) (Section 8-10.1)																							
T	A. Inspect containment systems for cleanliness, if accessible.										Daily	OM												
T	B. Secondary containment systems degrade and will collect debris which can clog drainage inlets or prevent drain valves from seating properly. Hydrostatically test the drainage systems to include containment drain inlets, drain lines and containment drain valves to ensure the containment is liquid tight. This test may use opportune rainfall by holding rainwater in the containment system for one hour. Where evaporation is a concern, conduct the testing when this concern would be minimized, such as at night/early morning or during a time of year when this would not be as much of an issue. Record the water level at the start of the 60-minute (minimum) hold period. If the water level drops by 1/8 inch or more, perform and record an investigation to determine the cause and any required repairs. Record the water level at the start of the 60 minute (minimum) hold period. If the water level drops by 1/8 inch or more, perform and record an investigation to determine the cause and any required repairs. Refer to Appendix B for testing procedures and to use to document the testing. American Concrete International (ACI) Standards 224R "Control of Concrete Cracking" and ACI's Concrete Repair Manual are two standards that owners/operators can follow to maintain the integrity of the concrete secondary containment. Note: Hydrostatic Containment testing shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.										Every 3 years	SM												
I	8-10.1	149	Fuel Pier 149	Pier 149	Spill Contaminant	Pier 149 - 1	KAN-149-CSGEN-0001	UNK	UNK	UNK														
I	8-10.1	149	Fuel Pier 149	Pier 149	Spill Contaminant	Pier 149 - 2	KAN-149-CSGEN-0002	UNK	UNK	UNK														
I	8-10.1	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Containment	Pit - A & B	KAN-1170-CSGEN-0001	UNK	UNK	UNK														
I	8-10.1	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Containment	Pit - C & D	KAN-1170-CSGEN-0002	UNK	UNK	UNK														
I	8-10.1	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Containment	Filter Separator - Pits	KAN-1170-CSGEN-0003	UNK	UNK	UNK														
I	8-10.1	1254	TRUCK OFFLOAD	Pump Station	Containment	1254 Pump Station	KAN-1254-CSGEN-0001	UNK	UNK															
I	8-10.1	6479	JET ENGINE FUEL STORAGE	Bulk Storage	Containment	6479A	KAN-6479-CSGEN-0001	UNK	UNK	UNK														
I	8-10.1	6479	JET ENGINE FUEL STORAGE	Bulk Storage	Containment	6479B	KAN-6479-CSGEN-0002	UNK	UNK	UNK														
I	8-10.1	6503	FUEL STATION	Military Service Station	Containment	Military Service Station	KAN-6503-CSGEN-0001	UNK	UNK	UNK														
I	8-10.1	6504	TRUCK LOAD/ OFFLOAD FACILITY	Load/Offload-Gas/DS-2/Bio-Deisel	Containment	Containment	KAN-6504-CSGEN-0001	UNK	UNK	UNK														
I	8-10.1	6745	BULK FUEL STORAGE TANK 6745	Military Service Station	Containment	Containment	KAN-6745-CSGEN-0001	UNK	UNK	UNK														
I	8-10.1	6506-1	MOGAS FUEL TANK	Military Service Station	Containment	Tank 6506 - 1	KAN-6506_1-CSGEN-0001	UNK	UNK	UNK														
I	8-10.1	6506-2	MOGAS FUEL TANK	Military Service Station	Containment	Tank 6506 - 2	KAN-6506_2-CSGEN-0001	UNK	UNK	UNK														
I	8-10.1	6506-3	BULK FUEL STORAGE TANK	Military Service Station	Containment	Tank 6506 - 3	KAN-6506_3-CSGEN-0001	UNK	UNK	UNK														
I	8-10.1	6506-4	DIESEL FUEL STORAGE	Military Service Station	Containment	Tank 6506 - 4	KAN-6506_4-CSGEN-0001	UNK	UNK	UNK														
I	8-10.1	6506-5	JP8 FUEL STORAGE	Military Service Station	Containment	Tank 6506 - 5	KAN-6506_5-CSGEN-0001	UNK	UNK	UNK														
I	8-10.1	PL-FTPA	FUEL TRUCK PARKING AREA	FUEL TRUCK PARKING AREA	Containment	PL-FTPA-Parking Lot	KAN-PL_FTPA-CSGEN-0001	UNK	UNK	UNK														
H	Self-Diking or Vaulted Tank Containment (Section 8-10.4)																							
T	A. Secondary containment structures on self-diking or vaulted tanks shall be inspected visually for integrity breaches with special attention given to pipe penetrations and interstitial drain valves.										Daily	OM												
I	8-10.4	6645	SMALL CRAFT FUEL STA AND STORAGE	Waterfront	Spill Contaminant	Waterfront	KAN-6645-SDVTC5-0001	UNK	UNK	UNK														
H	Electrical Equipment (Section 9-1.2)																							

APPENDIX B - ATTACHMENT 3 RECURRING MAINTENANCE REPORT TEMPLATE

Contract47QSHA18D000Y W912DY21F0025

SiteKaneohe

Date26-Apr-22

RM Event(s)Q2, SA1, A BY

☒ Daily

☒ Weekly

☒ Monthly

☒ Quarterly

☒ Semi-annually

☒ Annually

☒ Every 3 years

☒ Every 5 years

☒ Every 10 years

Note: It is advised that "See Description" and "Reference to Other" always be displayed.

☒ See Description

☒ Reference to Other

☒ SM

☒ OM

Warning: Only adds Deficiencies marked "Y" in Col T.

Generate Deficiency List

RM Report Setup Only - See Instructions

Generate UFC Tasks

Applicable Facility Assets										UFC System Level Maintenance Frequency	Responsibility	RM Completion Record Result	Date Completed	Completed By	Deficiencies	Responsible FMSR	Notes	Add to Def List?	
UFC Section Reference	Real Property Facility #	Real Property Facility Name	Operational Area	Component Type	Base Asset ID	Component Unique Identifier (CUID)	Make	Model	Capacity/Size										
A. Electrical control systems include: deadman control; ground verification systems; EFSO operation; control panels, motor control, and pump start/stop buttons. These systems shall be tested on a periodic basis to ensure proper operation and functionality. In addition, control system Uninterruptible Power Supplies (UPS) must be inspected and replaced as necessary. Note: Repairs shall be performed by SO.											Quarterly	SM							
9-1.2	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Electrical Switch (5 ea)	Pit - A switch -1-5	KAN-1170-ELEQ-0001	UNK	UNK	UNK										
9-1.2	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Electrical Switch (5 ea)	Pit - B switch -1-5	KAN-1170-ELEQ-0002	UNK	UNK	UNK										
9-1.2	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Electrical Switch (5 ea)	Pit - C switch -1-5	KAN-1170-ELEQ-0003	UNK	UNK	UNK										
9-1.2	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Electrical Switch (5 ea)	Pit - D switch -1-5	KAN-1170-ELEQ-0004	UNK	UNK	UNK										
9-1.2	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Electrical Switch	Pit -A Elec. Eye switch	KAN-1170-ELEQ-0005	UNK	UNK	UNK										
9-1.2	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Electrical Switch	Pit -B Elec. Eye switch	KAN-1170-ELEQ-0006	UNK	UNK	UNK										
9-1.2	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Electrical Switch	Pit -C Elec. Eye switch	KAN-1170-ELEQ-0007	UNK	UNK	UNK										
9-1.2	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Electrical Switch	Pit -D Elec. Eye switch	KAN-1170-ELEQ-0008	UNK	UNK	UNK										
9-1.2	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Electrical Switch	Filter Separator Elec. Eye switch	KAN-1170-ELEQ-0009	UNK	UNK	UNK										
9-1.2	6479	JET ENGINE FUEL STORAGE	Bulk Storage	Electrical Switch (6 ea)	6479A - 1 thru 6	KAN-6479-ELEQ-0001	UNK	UNK	UNK										
9-1.2	6504	TRUCK LOAD/ OFFLOAD FACILITY	Load/Offload-Gas/DS-2/Bio-Deisel	Electrical Switch	6504 - 1	KAN-6504-ELEQ-0001	UNK	UNK	UNK										
9-1.2	6504	TRUCK LOAD/ OFFLOAD FACILITY	Load/Offload-Gas/DS-2/Bio-Deisel	Electrical Switch	6504 - 2	KAN-6504-ELEQ-0002	UNK	UNK	UNK										
9-1.2	6504	TRUCK LOAD/ OFFLOAD FACILITY	Load/Offload-Gas/DS-2/Bio-Deisel	Electrical Switch	6504 - 3	KAN-6504-ELEQ-0003	UNK	UNK	UNK										
9-1.2	6504	TRUCK LOAD/ OFFLOAD FACILITY	Load/Offload-Gas/DS-2/Bio-Deisel	Electrical Switch	6504 - 4	KAN-6504-ELEQ-0004	UNK	UNK	UNK										
9-1.2	6506-1	MOGAS FUEL TANK	Military Service Station	Electrical Switch (5 ea)	Tank 6506 - 1 thru 5	KAN-6506_1-ELEQ-0001	UNK	UNK	UNK										
9-1.2	6506-1	MOGAS FUEL TANK	Military Service Station	Electrical Switch	Tank Electrical Panel	KAN-6506_1-ELEQ-0001	UNK	UNK	UNK										
9-1.2	6506-2	MOGAS FUEL TANK	Military Service Station	Electrical Switch	Tank Electrical Panel	KAN-6506_2-ELEQ-0001	UNK	UNK	UNK										
9-1.2	6506-3	BIODIESEL READY FUEL STORAGE	Military Service Station	Electrical Switch	Tank Electrical Panel	KAN-6506_3-ELEQ-0001	UNK	UNK	UNK										
9-1.2	6506-4	DIESEL FUEL STORAGE	Military Service Station	Electrical Switch	Tank Electrical Panel	KAN-6506_4-ELEQ-0001	UNK	UNK	UNK										
9-1.2	6506-5	JP8 FUEL STORAGE	Military Service Station	Electrical Switch	Tank Electrical Panel	KAN-6506_5-ELEQ-0001	UNK	UNK	UNK										
Static Grounding Systems (Section 9-1.6.2)																			
A. Inspect ground reels for corrosion. Ensure ground reels are securely mounted to a rigid base. Inspect clamps for serviceability. Replace clamp if jaws are deformed for corroded, spring is weak, or other defects are evident that would prevent a good connection. Inspect cable wires. Replace if more than one-third of the cable wires are broken.											Quarterly	SM							
B. The connections to the grounding system shall be surveyed and verified for continuity. If a connection is suspected to be loose, perform further testing. In some occasions it is more cost effective to replace the suspected connection instead of performing diagnostic tests.											Annually	SM							
C. Resistance measurement on static grounds: Measure static ground resistance of new and damaged ground rods. Static ground with a resistance greater than 10,000 ohms will be removed or replaced. Static ground mechanically damaged will be repaired and retested.											See Description	SM							
Frequency: When observed to be physically damaged. Note: This task shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.																			
9-1.6.2	149	Fuel Pier 149	Pier 149	Grounding Cable (18 ea)	Pier 149 - GC-1	KAN-149-STGS-0001	UNK	UNK	UNK										
9-1.6.2	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Grounding System (32 ea)	Grounding System (32 ea)	KAN-1170-STGS-0001	UNK	UNK	UNK										
9-1.6.2	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Grounding Reel	Pit - A	KAN-1170-STGS-0002	UNK	UNK	UNK										
9-1.6.2	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Grounding Reel	Pit - B	KAN-1170-STGS-0003	UNK	UNK	UNK										
9-1.6.2	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Grounding Reel	Pit - C	KAN-1170-STGS-0004	UNK	UNK	UNK										
9-1.6.2	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Grounding Reel	Pit - D	KAN-1170-STGS-0005	UNK	UNK	UNK										
9-1.6.2	1252	BULK FUEL STORAGE TANK F-24	Bulk Storage	Ground System (8 ea)	Bulk 1252 - GP-1	KAN-1252-STGS-0001	UNK	UNK											
9-1.6.2	1254	TRUCK OFFLOAD	Pump Station	Ground System (5 ea)	PS- GR-1-5	KAN-1254-STGS-0001	UNK	UNK											
9-1.6.2	6479	JET ENGINE FUEL STORAGE	Bulk Storage	Ground System (25 ea)	6479A-GR-1	KAN-6479-STGS-0001	UNK	UNK	UNK										
9-1.6.2	6503	FUEL STATION	Military Service Station	Ground System (7 ea)	MSS-R1	KAN-6503-STGS-0001	UNK	UNK	UNK										
9-1.6.2	6503	FUEL STATION	Military Service Station	Ground Reel	MSS-Reel	KAN-6503-STGS-0002	UNK	UNK	UNK										
9-1.6.2	6504	TRUCK LOAD/ OFFLOAD FACILITY	Load/Offload-Gas/DS-2/Bio-Deisel	Ground System (3 ea)	6504-Rod	KAN-6504-STGS-0001	UNK	UNK	UNK										
9-1.6.2	6504	TRUCK LOAD/ OFFLOAD FACILITY	Load/Offload-Gas/DS-2/Bio-Deisel	Ground Reel	6504-Reel	KAN-6504-STGS-0002	UNK	UNK	UNK										
9-1.6.2	6645	SMALL CRAFT FUEL STA AND STORAGE	Waterfront	Grounding System (2 ea)	Waterfront-GR-1	KAN-6645-STGS-0001	UNK	UNK	UNK										
9-1.6.2	6745	BULK FUEL STORAGE TANK 6745	Military Service Station	Ground System (9 ea)	BFST-GR- E-85-1	KAN-6745-STGS-0001	UNK	UNK	UNK										
9-1.6.2	1254A	STRAINER FACILITY	STRAINER STATION	Ground Rod	SF- GR-1	KAN-1254A-STGS-0001	UNK	UNK	UNK										
9-1.6.2	1254A	STRAINER FACILITY	STRAINER STATION	Ground Port	SF- GP-1	KAN-1254A-STGS-0002	UNK	UNK	UNK										
9-1.6.2	1254A	STRAINER FACILITY	STRAINER STATION	Ground Reel	SF- G-Reel-1	KAN-1254A-STGS-0003	UNK	UNK	UNK										
9-1.6.2	1563-1	TRUCK LOAD FACILITY JP5	Load Rack - 1	Ground Rod (14 ea)	LR-1 - GR-1	KAN-1563_1-STGS-0001	UNK	UNK	UNK										
9-1.6.2	1563-2	TRUCK LOADING FACILITY JP5	Load Rack - 3	Ground Rod (2 ea)	LR-3 - GR-1	KAN-1563_2-STGS-0001	UNK	UNK	UNK										
9-1.6.2	6506-1	MOGAS FUEL TANK	Military Service Station	Ground System (4)	Tank 6506 - GR-1	KAN-6506_1-STGS-0001	UNK	UNK	UNK										
9-1.6.2	6506-2	MOGAS FUEL TANK	Military Service Station	Ground System (4)	Tank 6506 - GR-1	KAN-6506_2-STGS-0001	UNK	UNK	UNK										
9-1.6.2	6506-3	BIODIESEL READY FUEL STORAGE	Military Service Station	Ground System (4)	Tank 6506 - GR-1	KAN-6506_3-STGS-0001	UNK	UNK	UNK										
9-1.6.2	6506-4	DIESEL FUEL STORAGE	Military Service Station	Ground System (4)	Tank 6506 - GR-1	KAN-6506_4-STGS-0001	UNK	UNK	UNK										
9-1.6.2	6506-5	JP8 FUEL STORAGE	Military Service Station	Ground System (5)	Tank 6506 - GR-1	KAN-6506_5-STGS-0001	UNK	UNK	UNK										

APPENDIX B - ATTACHMENT 3 RECURRING MAINTENANCE REPORT TEMPLATE

Contract47QSHA18D000Y W912DY21F0025

SiteKaneohe

Date26-Apr-22

RM Event(s)Q2, SA1, A BY

☒ Daily

☒ Weekly

☒ Monthly

☒ Quarterly

☒ Semi-annually

☒ Annually

☒ Every 3 years

☒ Every 5 years

☒ Every 10 years

Note: It is advised that "See Description" and "Reference to Other" always be displayed.

☒ See Description

☒ Reference to Other

☒ SM

☒ OM

Warning: Only adds Deficiencies marked "Y" in Col T.

Generate Deficiency List

RM Report Setup Only - See Instructions

Generate UFC Tasks

Applicable Facility Assets										UFC System Level Maintenance Frequency	Responsibility	RM Completion Record Result	Date Completed	Completed By	Deficiencies	Responsible FMSR	Notes	Add to Def List?					
UFC Section Reference	Real Property Facility #	Real Property Facility Name	Operational Area	Component Type	Base Asset ID	Component Unique Identifier (CUID)	Make	Model	Capacity/Size														
I	9-1.6.2	PL-FTPA	FUEL TRUCK PARKING AREA	FUEL TRUCK PARKING AREA	Ground Sytem (4 ea)	PL-FTPA-Rod-1	KAN-PL_FTPA-STGS-0001	UNK	UNK	UNK													
I	9-1.6.2	PL-FTPA	FUEL TRUCK PARKING AREA	FUEL TRUCK PARKING AREA	Ground Reel	PL-FTPA-Reel-1	KAN-PL_FTPA-STGS-0002	UNK	UNK	UNK													
I	9-1.6.2	PL-FTPA	FUEL TRUCK PARKING AREA	FUEL TRUCK PARKING AREA	Ground Reel	PL-FTPA-Reel-2	KAN-PL_FTPA-STGS-0003	UNK	UNK	UNK													
H	Lighting (Section 9-1.8)																						
T	A. Verify proper operation of light switch, lighting contactor, photocell or timer as appropriate. If a lighting contactor is used, listen for the chatter of contacts or buzzing noise. These are indicative of a faulty contactor. Replace if required. Note: Repairs shall be performed through a service order.										Quarterly	SM											
T	B. With the lights turned on, observe individual luminaries for flicker or lights turning on and off. The former is indicative of a faulty choke. The latter is indicative of a faulty starter. Replace the faulty components as required.										Quarterly	SM											
T	C. When light fixtures are located in hazardous areas, verify that the seals are intact and the hazardous rating of the fixture is maintained.										Quarterly	SM											
T	D. Thoroughly clean dust, bugs, and debris from the luminaire. Light solvents or cleaning agents may be used.										Annually	SM											
T	E. Re-Lamping: With the lights turned off, replace the lamps. In order to prevent accidental turning on of the lights, it is mandatory to switch off and lockout the breaker of the lighting circuit. Ensure the replacement lamps are the same type as those they are replacing. Verify the proper operation of all light fixtures after the lamp replacement. Frequency: Annually or as required Note: Re-lamping will be performed through a service order and should be executed in conjunction with an RM visit to avoid mobilization costs.										Annually	SM											
I	9-1.8	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Lighting (18 ea)	Pit - A - 1	KAN-1170-LIGHT-0001	UNK	UNK	UNK													
I	9-1.8	1254	TRUCK OFFLOAD	Pump Station	Explosion Proof Light (4 ea)	PS- EXP-1-4	KAN-1254-LIGHT-0001	UNK	UNK	UNK													
I	9-1.8	6503	FUEL STATION	Military Service Station	Lighting (6 ea)	Lighting Pole Station #1-6	KAN-6503-LIGHT-0001	UNK	UNK	UNK													
I	9-1.8	1563-1	TRUCK LOAD FACILITY JP5	Load Rack - 1	Explosion Proof Light (8 ea)	LR-1 - EXP-1	KAN-1563_1-LIGHT-0001	UNK	UNK	UNK													
I	9-1.8	1563-2	TRUCK LOADING FACILITY JP5	Load Rack - 2	Explosion Proof Light (8 ea)	LR-2 - EXP-1	KAN-1563_2-LIGHT-0001	UNK	UNK	UNK													
I	9-1.8	SL-FTPA	FUEL TRUCK PARKING AREA LIGHTS	FUEL TRUCK PARKING AREA	Lighting (6 ea)	Lighting- Pole - 1 thru 6	KAN-SL_FTPA-LIGHT-0001	UNK	UNK	UNK													
H	Canopies (Section 11-2.2)																						
T	A. Inspect and maintain canopies in accordance with UFC 3-110-03 Roofing Maintenance and Repair. Frequency: As required Note: This task shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.										See Description	SM											
I	11-2.2	1254A	OH COVER FOR PUMP FACILITY	Pump Station	Canopy	Canopy	KAN-1254A-CNPY-0001	UNK	UNK	UNK													
I	11-2.2	1563-1A	OH COVER FOR TRUCK LOAD FAC	Load Rack - 1	Canopy	Canopy	KAN-1563_1A-CNPY-0001	UNK	UNK	UNK													
I	11-2.2	1563-2A	OH COVER FOR TRUCK LOAD FAC	Load Rack - 2	Canopy	Canopy	KAN-1563_2A-CNPY-0001	UNK	UNK	UNK													
I	11-2.2	6479A	OH COVER AT FUEL PUMP HOUSE	Pump Station-6479B	Canopy	Canopy	KAN-6479A-CNPY-0001	UNK	UNK	UNK													
I	11-2.2	6504A	OH COVER FOR TRUCK LOAD FAC	Pump Station	Canopy	Canopy	KAN-6504A-CNPY-0001	UNK	UNK	UNK													
H	Emergency Eyewash/Showers (Section 11.3)																						
T	A. Test operation of the emergency eyewash/shower by pushing on the activation handles. Ensure the water is not brown in color, due to rust in the piping or dirt seeping in from a hole in the buried piping. For systems with tempered water, ensure that the water that is being supplied by the emergency eyewash/shower is between 60 and 100 degrees F (16 and 39 degrees C). For systems with a horn and strobe light, ensure that the horn and strobe light activate when the activation lever on the emergency eyewash/shower is pushed. For systems that interface with Installation or fire emergency systems, pre-coordinate before testing. At some Installations emergency eyewashes and showers act as EFSOs and are tied into the fire alarm systems.										Weekly	OM											
T	B. Inspect portable/package safety showers and eyewash stations for proper operation. Check fluid levels. Where tap water is used, fluid shall be replaced monthly. Less frequent intervals of fluid change, as recommended by the manufacturer, are acceptable where a solution or water additive is used. Ensure packaged eyewash supplies are within the listed expiration date. Tags or labels shall be attached to the unit or adjacent to it, indicating the fluid change schedule.										Monthly	OM											
T	C. Inspect the exterior coatings of permanently installed units and repair damaged coatings or rust.										Quarterly	SM											
T	D. For systems with tempered water systems inspect components of the water heater for correct operation and temperature control. Ensure that the safety valve on the hot water heater tank is not leaking.										Semi-annually	SM											
T	E. Inspect signage and labels on the emergency eyewash/shower. Replace missing labels or signage that has become loose. Signs that are faded shall be replaced.										Annually	SM											
I	11-3	370	Fuel Laboratory	Lab	Eye Wash	Laboratory	KAN-370-EMEWSH-0001	UNK	UNK	UNK													
I	11-3	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Emergency Eye Wash	Pit - A	KAN-1170-EMEWSH-0001	UNK	UNK	UNK													
I	11-3	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Emergency Eye Wash	Pit - C	KAN-1170-EMEWSH-0002	UNK	UNK	UNK													
I	11-3	1170	ACFT DIR FUEL ISLAND	Flightline Pits	Emergency Eye Wash	Pit - D	KAN-1170-EMEWSH-0003	UNK	UNK	UNK													
I	11-3	6504	TRUCK LOAD/ OFFLOAD FACILITY	Load/Offload-Gas/DS-2/Bio-Deisel	Emergency Eye wash	6504 - eye wash	KAN-6504-EMEWSH-0001	UNK	UNK	UNK													
I	11-3	6645	SMALL CRAFT FUEL STA AND STORAGE	Waterfront	Eye Wash Station	Waterfront-EW-1	KAN-6645-EMEWSH-0001	UNK	UNK	UNK													
I	11-3	1563-2	TRUCK LOADING FACILITY JP5	Load Rack - 3	Eye Wash Station	Eye Wash Station	KAN-1563_2-EMEWSH-0001	UNK	UNK	UNK													
I	11-3	PL-FTPA	FUEL TRUCK PARKING AREA	FUEL TRUCK PARKING AREA	Eye Wash	PL-FTPA-EW-1	KAN-PL_FTPA-EMEWSH-0001	UNK	UNK	UNK													
I	11-3	PL-FTPA	FUEL TRUCK PARKING AREA	FUEL TRUCK PARKING AREA	Eye Wash	PL-FTPA-EW-2	KAN-PL_FTPA-EMEWSH-0002	UNK	UNK	UNK													
H	Ventilation Hoods (Section 11-4.1)																						
T	A. Inspect the operation of the doors. Ensure that they close and open smoothly.										Quarterly	SM											
T	B. Inspect the lights inside of the hood to make sure they are operating properly. Replace light bulbs that are no longer working.										Semi-annually	SM											
T	C. Verify that all electrical equipment is properly classified in accordance with NFPA 70 National Electrical Code.										Annually	SM											

RM Template v0.4.3

26

APPENDIX B - ATTACHMENT 3 RECURRING MAINTENANCE REPORT TEMPLATE

Contract

47QSHA18D000Y W912DY21F0025

Site

Kaneohe

Date

26-Apr-22

RM Event(s)

Q2, SA1, A BY

Region:

POH

☒ Daily

☒ Weekly

☒ Monthly

☒ Quarterly

☒ Semi-annually

☒ Annually

☒ Every 3 years

☒ Every 5 years

☒ Every 10 years

Note: It is advised that "See Description" and "Reference to Other" always be displayed.

☒ See Description

☒ Reference to Other

☒ SM

☒ OM

Warning: Only adds Deficiencies marked "Y" in Col T.

Generate Deficiency List

RM Report Setup Only - See Instructions

Generate UFC Tasks

Applicable Facility Assets										UFC System Level Maintenance Frequency	Responsibility	RM Completion Record Result	Date Completed	Completed By	Deficiencies	Responsible FMSR	Notes	Add to Def List?	
UFC Section Reference	Real Property Facility #	Real Property Facility Name	Operational Area	Component Type	Base Asset ID	Component Unique Identifier (CUID)	Make	Model	Capacity/Size										
T	D. Inspect the ventilation system (ductwork, fans, etc.) for signs of disrepair and air leakage and ensure it is operational and pulling air through the hood. Inspect and assure that the lab hood air measuring device for assuring proper air flow is permanently attached and working properly. The ventilation hood shall be inspected and certified by approved by a service specific industrial hygienist or bioenvironmental engineer in accordance with OSHA, 29 CFR 1910.1450 Occupational Exposure to Hazardous Chemicals in Laboratories, and ANSI/AIHA Laboratory Ventilation Z9.5.										Annually	SM							
	Note: General requirements in this section to be performed by RMMR. Certification by the service specific industrial hygienist or bioenvironmental engineer is the responsibility of the site.																		
T	E. Verify negative pressure is present through the ventilation hood to the exhaust.										Annually	SM							
I	11-4.1	370	FUEL OPS/TEST FACILITY	FUELS OPS FAC	Laboratory	Vent Hood and test equipment	KAN-370-VENTHD-0001	UNK	UNK	UNK									

[illegible]

SECTION 01 33 00 SUBMITTAL PROCEDURES
ATTACHMENT 1 - SUBMITTAL REQUIREMENTS

Contract Timeline Schedule **SAD-AF2**

Contract NTP **14-Feb-26**

Due Dates shown are only a representation of deliverables within the allowable date due after NTP per the PWS.
If there is a discrepancy between the PWS and this attachment, the PWS takes precedence.

PWS Reference	Deliverable Title	Due from NTP (Calendar Days if not noted)	Frequency	Due Date	Notes
Paragraph 1.25.1	Transition Plan – Phase-In-Approach	7	Once after Contract Award	21-Feb-26	
Paragraph 1.9.4 and Paragraph 1.25.1	Contractor Personnel Identification	7	As Required	21-Feb-26	Include with Transition Plan
Paragraph 1.9.4 and Paragraph 1.25.1	Organizational Chart	7	As required	21-Feb-26	Include with Transition Plan
Paragraph 1.25.1 and Appendix D	E-Verify	7	As required	21-Feb-26	Include with Transition Plan
Paragraph 1.25.1 and Appendix C, Section 01 45 00.15 10, Paragraph 1.4	Resident Management System Access	7	As required by PWS	21-Feb-26	Include approval access with Transition Plan
Paragraph 1.25.1 and Appendix C, Section 01 45 00.15 10, Paragraph 1.6.4	Submittal Register	7	As required by PWS	21-Feb-26	Include with Transition Plan and as separate submittal as per Section 01 45 00.15 10
Paragraph 1.25.1 and Appendix C, Section 01 45 00.15 10, Paragraph 1.6.1.2	List of proposed subcontractors in RMS	14	Once after Contract Award with updates of additions or deletions of subcontractors during contract duration	28-Feb-26	Within 7 calendar days after receiving access to the contract in RMS access Include with Transition Plan and as separate submittal as per Section 01 45 00.15 10
Appendix C, Section 01 35 26, Paragraph 3.2.1	Site Visit Abbreviated Accident Prevention Plan (SVAAPP)	ASAP after TO Award No site visit permitted without approved SVAAPP	Once after Contract Award	ASAP	
Paragraph 1.2.5	Initial Site Visit Schedule	7	Once after Contract Award and prior to Post-Award Meeting	21-Feb-26	Prior to Post-Award-Meeting Include with Transition Plan
Appendix C, Section 01 35 26, Paragraph 3.2.2	Accident Prevention Plan	15	Once after Contract Award with updates as necessary	6-Mar-26	15 business days after NTP
Paragraph 1.2.3	Post-Award Meeting	14	Once after Contract Award	28-Feb-26	
Paragraph 1.2.4	FMSR Kickoff meeting – Start	7	Once for all sites after Post-Award-Meeting	7-Mar-26	After Post-Award-Meeting Completed no later than 20 calendar days after Post-Award-Meeting
Paragraph 1.13.2	Initial Preventive Maintenance Schedule	7	Once for all sites after FMSR Kickoff Meeting	14-Mar-26	7 calendar days after start of POP
Appendix C, Section 01 35 26, Paragraph 3.2.3	APP Appendix 1 - Site Specific Addendums	30	Once after Contract Award with updates as necessary	16-Mar-26	
Appendix C, Section 01 35 26, Paragraph 3.2.4	APP Appendix 2 - Activity Hazard Analysis (initial grouping of AHAs)	30	Once after Contract Award with updates as necessary	16-Mar-26	
Appendix C, Section 01 45 00.00 10, Paragraph 3.2	Contractor Quality Control Plan	30	Once after Contract Award with updates as requested	16-Mar-26	
Paragraph 1.2.4	FMSR Kick Off meeting – All completed	20	Once for all sites after Post-Award-Meeting	20-Mar-26	After Post-Award-Meeting Completed no later than 20 calendar days after Post-Award-Meeting

Appendix C, Section 01 45 00.00 10, Paragraph 3.3.3	Quality Control Manager and Alternate Quality Control Manager CQM Certificates	90	As required by PWS	15-May-26	If not provided in QC Plan
Appendix C, Section 01 35 26, Paragraph 4.3.2	Contract Safety Manager OSHA 30-Hour Certificate	90	As required by PWS	15-May-26	If not provided in APP
Paragraph 1.2.4	Initial Site Visit	90	Once for each site after NTP	15-May-26	Complete ISVs at every site within 90 days after NTP
Paragraph 1.2.4	FMP Variance in Inventory - Advise	7	Once for each site after ISV		5 business days after each ISV - ADVISE via RMS Submittal
Paragraph 1.13.1	Overall Project Schedule	14	Monthly		
Paragraph 1.13.2	Final Preventive Maintenance Schedule	14	Annually	29-May-26	submit no later than 14 calendar days after start of POP
Paragraph 3.1	FMP to HNC (Including Variance in Inventory) (With FMSR Concurrence)	45	Once for each site after ISV		45 calendar days after each ISV Provide Inventory Variance with FMP per PWS
Paragraph 1.11	Initial Maintenance Records/Binders Digital and Hard Copy to FMSR	60	As required by PWS		60 calendar days after each ISV
Paragraph 1.11	Final Maintenance Records/Binders Digital and Hard Copy to FMSR	30 days after POP end date of each contract year	As required by PWS		
Paragraph 1.11	Final Maintenance Records/Binders to Government via RMS	45 days after POP end date of each contract year	As required by PWS		
Paragraph 1.11	Maintenance Records/Binders Digital and Hard Copy Updates	30 days after each recurring maintenance visit, when any component has been replaced with new warranty item, or when data requires updating.			
Paragraph 3.2	Installation Status Report	30 days after each ISV in base year and within 30 days of completion of first PM visit each option year	As required by PWS		
Paragraph 1.25.1	Carry Over Deficiency Schedule	30	Once for each site after ISV		Schedule must include planned initiation, execution, and completion dates of deficiencies. Work with FMSR to establish work prioritization.
Paragraph 1.26.1	90-Day Syne Meeting	90 days prior to the end of each option year's POP	Annually Prior to Option Year expiration	16-Nov-26	
Appendix C, Section 01 35 26, Paragraph 6.1	Safety Bulletin Board/Information	7	Required prior to any work performed		After SO NTP
Appendix C, Section 01 35 26, Paragraph 7.1	Mishap Notification	24 hours	As required by PWS		Within 24 hours of mishap, including reportable and recordable accidents, incidents, and near misses
Appendix C, Section 01 35 26, Paragraph 7.1	USACE Accident Report ENG Form 3394	10	As required by PWS		Within 10 days of accident

Appendix C, Section 01 35 26, Paragraph 7.1	LHE Accident Report Form	30	As required by PWS		Within 30 days of accident involving any load handling equipment
Appendix A Paragraph 2.1.1	Routine Service Order (RSO) Priority 1	30	As required by PWS		After SO NTP
Appendix A Paragraph 2.1.1	Routine Service Order (RSO) Priority 2	60	As required by PWS		After SO NTP
Appendix A Paragraph 2.1.1	Routine Service Order (RSO) Priority 3	120	As required by PWS		After SO NTP
Appendix A Paragraph 2.1.1	Routine Service Order (RSO) Priority 0	15	As required by PWS		After SO NTP
Appendix A Paragraph 2.1.2	Routine Service Order (RSO) Long Lead	>120	As required by PWS		After SO NTP
Appendix A Paragraph 2.2	Emergency Service Order (ESO)	ASAP	As required by PWS		After SO NTP
Appendix A Paragraph 2.5.2	Out for Corrections (OFC)	5 business days	As required by PWS		
Appendix B Paragraph 1.0	Three Week Look Ahead Schedule	Every Friday NLT 1300 CST	Weekly		
Appendix C, Section 01 35 26, Paragraph 3.3.6	Monthly Exposure Reports	NLT 7 calendar days after end of each month	Monthly		
Appendix B Paragraph 2.0	Monthly Status Report	NLT 10th day of each calendar month	Monthly		
Paragraph 1.11, Paragraph 1.23, Paragraph 3.1, and Appendix C, Section 01 78 23, Paragraph 1.4.5.6	Warranty Items	Provide with Monthly Report and per PWS	Quarterly		
Paragraph 3.3, Appendix A Section 1.0, and Appendix B Paragraph 3.2	Preventive Maintenance Report	30 days after work has been completed	As required by PWS		
Appendix A Section 1.0	Preventive Maintenance Deficiency List	5 business days	Quarterly or as required		After each PM event
Paragraph 1.13.2	FMSR Site Coordination - Initial Notifications	30 days prior to anticipated start of work	As required prior to arrival on site		
Paragraph 1.13.2	FMSR Site Coordination - Final Confirmation	14 days prior to anticipated start of work	As required prior to arrival on site		
Appendix B Paragraph 4.0	Service Order Tracker	Every Monday NLT 1200 CST	Weekly		
Paragraph 1.10	Written Records	5 days after each occurrence	As required by PWS		After each occurrence
Paragraph 1.22	Invoices - COR Review	NLT 5 business days prior to the end of each month	Monthly		
Paragraph 1.22	Invoices - Final	Within first 7 business days of each month	Monthly		
Paragraph 1.25	OY Invoicing	60 days after completion of all option year service orders	As required by PWS		
Appendix C, Section 01 45 00.00 10, Paragraph 3.7.4	QC Audit Site Visit	Annually at each site	Annually or more frequent per QC Plan		As required per PWS Intervals between audit must be 180-375 days at each site
Appendix C, Section 01 45 00.00 10, Paragraph 3.7.4	QC Audit Report	20 calendar days after completion of QC audit at each site			Submitted via RMS
Paragraph 3.4.1	Corrective Maintenance Required by Preventive Maintenance	90	Quarterly or as requested		During PM event or next site visit or within 90 calendar days, whichever is less

Paragraph 3.4.2	Corrective Maintenances Incidental to Maintenance Activities	90	Quarterly or as requested		During PM event or next site visit or within 90 calendar days, whichever is less
Paragraph 1.25.2	Transition Annual Requirements - Documents	90	Once prior to Option Year expiration		Prior to PoP expiration Will be discussed during 90-Day Sync
Paragraph 1.25.3	Close Out Documentation	90	Once prior to contract expiration		Prior to Contract expiration Will be discussed during 90-Day Sync
Paragraph 1.9.4	Change in other personnel	10 business days advanced notice to KO to include resume	As required by PWS		Upon any change to personnel including all key personnel listed in Paragraph 1.5
Appendix D Paragraph 1.0	AT Level 1 Certificate	Complete training within 30 days of Contract Award and submit 5 days after completion of training	Annually and as required by the PWS for new employees		Via website listed in PWS
Appendix D Paragraph 4.0	Watch and/or Corps Watch Certificate	Complete training within 30 days of Contract Award and submit 5 days after completion of training	Annually and as required by the PWS for new employees		Via website listed in PWS
Appendix D Paragraph 4.0	Meeting Minutes	5 Calendar days after Occurrence	As required by PWS		Submit via RMS 01 33 00
Appendix D Paragraph 6.0	OPSEC Certificate	Complete training within 30 days of Contract Award and submit 5 days after completion of training	Annually and as required by the PWS for new employees		Via website listed in PWS
Appendix D Paragraph 17.0	TARP Certificate	NLT contract POP end for each year of the contract	Annually and as required by the PWS for new employees		Training will be conducted by CI Agent via classroom training

APPENDIX C

CONTRACT SPECIFICATIONS

**U.S. Army Engineering and Support Center
Huntsville, AL**

Table of Contents

01 33 00 Submittal Procedures

01 35 26 Governmental Safety Requirements

01 45 00.00 10 Quality Control

**01 45 00.15 10 Resident Management System Contractor Mode (RMS
CM)**

01 78 23 Operation and Maintenance Data

Fuels Program Procedures for Joint Sealant and Crack Repair

SECTION 01 33 00

SUBMITTAL PROCEDURES

08/18, CHG 4: 02/21

PART 1 GENERAL

1.1 SUMMARY

1.1.1 Submittal Information

The Contracting Officer may request submittals in addition to those specified when deemed necessary to adequately describe the work covered in the respective sections. Each submittal is to be complete and in sufficient detail to allow ready determination of compliance with contract requirements.

Contractor's Quality Control Manager to check and approve all items prior to submittal and sign and date indicating action taken.

1.2 DEFINITIONS

1.2.1 Submittal Descriptions (SD)

Submittal requirements are specified in the Performance Work Statement (PWS) and deliverables have been provided in Attachment 1 of this section. Examples and descriptions of submittals identified by the Submittal Description (SD) numbers and titles follow:

SD-01 Pre-Performance Submittals

Submittals that are required prior to or at the start of Preventive Maintenance (PM) activities and Corrective Maintenance (CM) work.

For Government approved division 01 submittals that are required prior to or commencing with the start of work shall be submitted within 30 calendar days of contract award unless specified elsewhere in the PWS.

Pre-Performance Submittals include schedules and a tabular list of locations, features, and other pertinent information regarding products, materials, equipment, or components to be used in the work. This applies to both Preventive Maintenance (PM) and Corrective Maintenance (CM) work required for this contract. Required submittals for Minor Repair work specific to that repair may be included in the Service Order or Independent Project Service Order Portfolio for Government approval and not required to be submitted in RMS.

Transition Plan (including all information from PWS paragraph 1.25.1)

Initial and Final Site Visit Schedules

Initial and Final Maintenance Schedules (provide at Base and each OY)

Submittal Register (Provide at Base and each OY)

Site Visit Abbreviated Accident Prevention Plan (SVAAPP) Accident Prevention Plan (APP)

APP Appendix 1-Site Specific Addendum (SSAs)

APP Appendix 2-Activity Hazard Analysis (AHA)

Contractor Quality Control (CQC) plan

Interim CQC Plan for site specific work

Others as identified in Attachment 1 of this section

Corrective Maintenance not required for submission into RMS to include:

Service Order (SO) Portfolio (including all required items per PWS)

SD-10 Operation and Maintenance Data - PM and CM

Data provided by the manufacturer, or the system provider, including manufacturer's help and product line documentation, necessary to maintain and install equipment, for operating and maintenance use by facility personnel.

Data required by operating and maintenance personnel for the safe and efficient operation, maintenance and repair of the item.

Data incorporated in an operations and maintenance manual or control system.

All Maintenance Records per the PWS.

SD-11 Closeout Submittals - PM and CM

Documentation to record compliance with technical or administrative requirements or to establish an administrative mechanism.

Submittals required for Guiding Principle Validation (GPV) or Third Party Certification (TPC).

Special requirements necessary to properly close out a contract. For example, Record Drawings and as-built drawings. Also, submittal requirements necessary to properly close out a major phase of performance on a multi-phase contract.

All closeout requirements per the PWS.

SO and Submittal Descriptions

Shop Drawings

Drawings, diagrams and schedules specifically prepared to illustrate some portion of the work.

Diagrams and instructions from a manufacturer or fabricator for use in producing the product and as aids to the Contractor for integrating the product or system into the project.

Drawings prepared by or for the Contractor to show how multiple systems and interdisciplinary work will be coordinated.

Product Data

Catalog cuts, illustrations, schedules, diagrams, performance charts, instructions and brochures illustrating size, physical appearance and other characteristics of materials, systems or equipment for some portion of the work.

Samples of warranty language when the contract requires extended product warranties.

Samples - (if applicable)

Fabricated or unfabricated physical examples of materials, equipment or workmanship that illustrate functional and aesthetic characteristics of a material or product and establish standards by which the work can be judged.

Color samples from the manufacturer's standard line (or custom color samples if specified) to be used in selecting or approving colors for the project.

Field samples and mock-ups constructed on the project site establish standards ensuring work can be judged. Includes assemblies or portions of assemblies that are to be incorporated into the project and those that will be removed at conclusion of the work.

Design Data - (if applicable)

Design calculations, mix designs, analyses or other data pertaining to a part of work.

Design submittals, design substantiation submittals and extensions of design submittals.

Test Reports

Report signed by authorized official of testing laboratory that a material, product or system identical to the material, product or system to be provided has been tested in accord with specified requirements. Unless specified in another section, testing must have been within three years of date of contract award for the project.

Report that includes findings of a test required to be performed on an actual portion of the work or prototype prepared for the project before shipment to job site.

Report that includes finding of a test made at the job site or on sample taken from the job site, on portion of work during or after installation.

Investigation reports

Daily logs and checklists

Final acceptance test and operational test procedure

Certificates

Statements printed on the manufacturer's letterhead and signed by responsible officials of manufacturer of product, system or material attesting that the product, system, or material meets specification

requirements. Must be dated after award of project contract and clearly name the project.

Document required of Contractor, or of a manufacturer, supplier, installer or Subcontractor through Contractor. The document purpose is to further promote the orderly progression of a portion of the work by documenting procedures, acceptability of methods, or personnel qualifications.

Confined space entry permits

Text of posted operating instructions

Manufacturer's Instructions

Preprinted material describing installation of a product, system or material, including special notices and (SDS) concerning impedances, hazards and safety precautions.

Manufacturer's Field Reports

Documentation of the testing and verification actions taken by manufacturer's representative at the job site, in the vicinity of the job site, or on a sample taken from the job site, on a portion of the work, during or after installation, to confirm compliance with manufacturer's standards or instructions. The documentation must be signed by an authorized official of a testing laboratory or agency and state the test results; and indicate whether the material, product, or system has passed or failed the test.

Factory test reports.

1.2.2 Approving Authority

Office or designated person authorized to approve the submittal.

1.2.3 Work

As used in this section, on-site and off-site work required by contract documents, including labor necessary to produce submittals, recurring maintenance and minor repair work, materials, products, equipment, and systems incorporated or to be incorporated in such maintenance or repair work. In exception, excludes work to produce SD-01 submittals.

1.3 SUBMITTALS

Government approval is required for all submittals, Service Order Portfolios, and Independent Project Service Order Portfolios. SO and Portfolios are not required to be submitted into RMS unless required by the Contracting Officer. Submit in accordance with Section 01 33 00 SUBMITTAL PROCEDURES.

1.4 SUBMITTAL CLASSIFICATION

1.4.1 Government Approved (G)

Government approval is required for all submittals unless otherwise specified.

1.5 PREPARATION

1.5.1 Transmittal Form

Use the ENG Form 4025-R transmittal form for submitting both Government-approved and information-only submittals. Submit in accordance with the instructions on the reverse side of the form. These forms are included in the RMS CM software that the Contractor is required to use for this contract. Properly complete this form by filling out all the heading blank spaces and identifying each item submitted.

1.5.2 Submittal Format

1.5.2.1 Format of SD-01 Pre-Performance Submittals

When the submittal includes a document that is to be used in the project, or is to become part of the project record, other than as a submittal, do not apply the Contractor's approval stamp to the document itself, but to a separate sheet accompanying the document.

Provide data in the unit of measure used in the contract documents.

1.5.2.2 Format of SD-10 Operation and Maintenance Data (O&M)

Comply with the requirements specified in Section 01 78 23 OPERATION AND MAINTENANCE DATA for O&M Data format.

1.5.2.3 Format of SD-11 Closeout Submittals

Comply with PWS requirements. When the submittal includes a document that is to be used in the project or is to become part of the project record, other than as a submittal, do not apply the Contractor's approval stamp to the document itself, but to a separate sheet accompanying the document.

1.5.2.4 Format for Shop Drawings - SO and Portfolio

Provide shop drawings not less than 8 1/2 by 11 inches nor more than 30 by 42 inches, except for full-size patterns or templates. Prepare drawings to accurate size, with scale indicated, unless another form is required. Ensure drawings are suitable for reproduction and of a quality to produce clear, distinct lines and letters, with dark lines on a white background.

- a. Include the nameplate data, size, and capacity on drawings. Also include applicable federal, military, industry, and technical society publication references.
- b. Dimension drawings, except diagrams and schematic drawings. Prepare drawings demonstrating interface with other trades to scale. Use the same unit of measure for shop drawings as indicated on the contract drawings. Identify materials and products for work shown.

Submit an electronic copy of drawings in PDF format.

1.5.2.4.1 Drawing Identification

Include on each drawing the drawing title, number, date, and revision numbers and dates, in addition to information required in paragraph IDENTIFYING SUBMITTALS.

Number drawings in a logical sequence. Each drawing is to bear the number of the submittal in a uniform location next to the title block. Place the Government contract number in the margin, immediately below the title block, for each drawing.

1.5.2.5 Format of Product Data - SO and Portfolio

Present product data submittals for each SO and per the PWS.

1.5.2.5.1 Product Information

Supplement product data with material prepared for the project where product data does not exist. Identify this material as developed specifically for the project, with information and format as required for submission of SD-07 Certificates .

1.5.2.5.2 Standards

Where equipment or materials are specified to conform to industry or technical-society reference standards as identified in UFC 3-460-01 References, submit proof of such compliance. The label or listing by the specified organization will be acceptable evidence of compliance. In lieu of the label or listing, submit a certificate from an independent testing organization, competent to perform testing, and approved by the Contracting Officer. State on the certificate that the item has been tested in accordance with the specified organization's test methods and that the item complies with the specified organization's reference standard.

1.5.2.5.3 Data Submission

Collect required data submittals for each specific material, product, unit of work, or system into a single submittal that is marked for choices, options, and portions applicable to the submittal. Mark each copy of the product data identically. Include Component Unique Identifier (CUID) for product data. Partial submittals will not be accepted for expedition of the service order unless approved by the Contracting Officer for Long Lead items.

Submit the manufacturer's instructions before installation.

1.5.2.6 Format of Samples - SO and Portfolio

1.5.2.6.1 Sample Characteristics

Furnish samples in the following sizes, unless otherwise specified or unless the manufacturer has prepackaged samples of approximately the same size as specified:

- a. Sample of Equipment or Device: Full size.
- b. Sample of Materials Less Than 2 by 3 inches: Built up to 8 1/2 by 11 inches.
- c. Sample of Materials Exceeding 8 1/2 by 11 inches: Cut down to 8 1/2 by 11 inches and adequate to indicate color, texture, and material variations.
- d. Sample of Linear Devices or Materials: 10 inch length or length to be

supplied, if less than 10 inches. Examples of linear devices or materials are conduit and handrails.

- e. Sample Volume of Nonsolid Materials: Pint. Examples of nonsolid materials are sand and paint.
- f. Color Selection Samples: 2 by 4 inches. Where samples are specified for selection of color, finish, pattern, or texture, submit the full set of available choices for the material or product specified. Sizes and quantities of samples are to represent their respective standard unit.
- g. Sample Panel: 4 by 4 feet.
- h. Sample Installation: 100 square feet.

1.5.2.6.2 Sample Incorporation

Reusable Samples: Incorporate returned samples into work only if so specified or indicated. Incorporated samples are to be in undamaged condition at the time of use.

Recording of Sample Installation: Note and preserve the notation of any area constituting a sample installation, but remove the notation at the final clean-up of the project.

1.5.2.6.3 Comparison Sample

Samples Showing Range of Variation: Where variations in color, finish, pattern, or texture are unavoidable due to nature of the materials, submit sets of samples of not less than three units showing extremes and middle of range. Mark each unit to describe its relation to the range of the variation.

When color, texture, or pattern is specified by naming a particular manufacturer and style, include one sample of that manufacturer and style, for comparison.

1.5.2.7 Format of Design Data - SO and Portfolio

Provide design data and certificates on 8 1/2 by 11 inch paper. Provide a bound volume for submittals containing numerous pages.

1.5.2.8 Format of Test Reports - SO and Portfolio

Provide reports on 8 1/2 by 11 inch paper in a complete bound volume. By prominent notation, indicate each report in the submittal. Indicate the specification number and paragraph number to which each report pertains.

1.5.2.9 Format of Certificates - SO and Portfolio

Provide design data and certificates on 8 1/2 by 11 inch paper. Provide a bound volume for submittals containing numerous pages.

1.5.2.10 Format of Manufacturer's Instructions - SO and Portfolio

Present manufacturer's instructions submittals for each section as a complete, bound volume. Include the manufacturer's name, trade name, place of manufacture, and catalog model or number on product data. Also include applicable federal, military, industry, and technical-society publication

references. If supplemental information is needed to clarify the manufacturer's data, submit it as specified for Certificates.

Submit the manufacturer's instructions before installation.

1.5.2.10.1 Standards

Where equipment or materials are specified to conform to industry or technical-society reference standards as identified in UFC 3-460-01 References, submit proof of such compliance. The label or listing by the specified organization will be acceptable evidence of compliance. In lieu of the label or listing, submit a certificate from an independent testing organization, competent to perform testing, and approved by the Contracting Officer. State on the certificate that the item has been tested in accordance with the specified organization's test methods and that the item complies with the specified organization's reference standard.

1.5.2.11 Format of Manufacturer's Field Reports - SO and Portfolio

Provide reports on 8 1/2 by 11 inch paper in a complete bound volume.

By prominent notation, indicate each report in the submittal. Indicate the specification number and paragraph number to which each report pertains.

1.5.3 Source Drawings for Shop Drawings

1.5.3.1 Source Drawings

The existing source drawing files (DWG) may not be available for Contractor use.

1.5.3.2 Terms and Conditions

Data contained on these electronic files must not be used for any purpose other than as a convenience in the preparation of data for the referenced project. Any other use or reuse is at the sole risk of the Contractor and without liability or legal exposure to the Government. The Contractor must make no claim, and waives to the fullest extent permitted by law any claim or cause of action of any nature against the Government, its agents, or its subconsultants that may arise out of or in connection with the use of these electronic files. The Contractor must, to the fullest extent permitted by law, indemnify and hold the Government harmless against all damages, liabilities, or costs, including reasonable attorney's fees and defense costs, arising out of or resulting from the use of these electronic files.

These electronic source drawing files are not construction documents. Differences may exist between the source drawing files and the corresponding performance documents. The Government makes no representation regarding the accuracy or completeness of the electronic source drawing files, nor does it make representation to the compatibility of these files with the Contractor hardware or software. The Contractor is responsible for determining if any conflict exists. In the event that a conflict arises between the signed and sealed documents prepared by the Government and the furnished source drawing files, the signed and sealed documents govern. Use of these source drawing files does not relieve the Contractor of the duty to fully comply with the contract documents,

including and without limitation the need to check, confirm and coordinate the work of all contractors for the project. If the Contractor uses, duplicates or modifies these electronic source drawing files for use in producing data related to this contract, remove all previous indication of ownership (seals, logos, signatures, initials and dates).

1.5.4 Electronic File Format

Provide submittals in electronic format as described in the PWS, with the exception of material samples required for Samples items. In addition to the electronic submittal, provide hard copies of the submittals as required in the PWS. Compile the submittal file as a single, complete document, to include the Transmittal Form described within. Name the electronic submittal file specifically according to its contents, and coordinate the file naming convention with the Contracting Officer's Representative. Electronic files must be of sufficient quality that all information is legible. Use PDF as the electronic format, unless otherwise specified or directed by the Contracting Officer. Generate PDF files from original documents with bookmarks so that the text included in the PDF file is searchable and can be copied. If documents are scanned, optical character resolution (OCR) routines are required. Index and bookmark files exceeding 30 pages to allow efficient navigation of the file. When required, the electronic file must include a valid electronic signature or a scan of a signature.

E-mail electronic submittal documents as described in the PWS or as directed by the Contracting Officer. Provide electronic documents over 10 MB on an optical disc or through an electronic file sharing system such as the DOD SAFE Web Application located at the following website:
<https://safe.apps.mil/>.

1.6 QUANTITY OF SUBMITTALS

All submittals shall be provided in accordance with the PWS or as directed by the Contracting Officer.

1.7 INFORMATION ONLY SUBMITTALS

Submittals without a "G" designation must be certified by the QC manager and submitted in RMS or to the Contracting Officer for information-only. Approval of the Contracting Officer is not required on information only submittals. The Contracting Officer will mark "receipt acknowledged" on submittals for information and will return only the transmittal cover sheet to the Contractor. Normally, submittals for information only will not be returned. However, the Government reserves the right to return unsatisfactory submittals and require the Contractor to resubmit any item found not to comply with the contract. This does not relieve the Contractor from the obligation to furnish material conforming to the plans and specifications; will not prevent the Contracting Officer from requiring removal and replacement of nonconforming material incorporated in the work; and does not relieve the Contractor of the requirement to furnish samples for testing by the Government laboratory or for check testing by the Government in those instances where the technical specifications so prescribe.

1.8 CONTRACT SUBMITTAL REGISTER

Submittal Register showing contract deliverables for when submittals are

required by the contract.

1.8.1 Submittal Management

Contractor shall prepare and maintain a submittal register throughout the life of the contract. Multiple submittal registers may be created under one Contract (One for Base Year and One for each Option Year).

Maintain a submittal register in accordance with Section 01 45 00.15 10 RESIDENT MANAGEMENT SYSTEM CONTRACTOR MODE (RMS CM). The Contractor shall provide the preliminary submittal register for the Period of Performance deliverable items. The following items shall be provided with the preliminary submittal register and maintained thereafter:

Specification Section: Lists specification section in which submittal is required. The following Specification Sections shall be utilized for the submittal items:

- 01 30 00 ADMINISTRATIVE REQUIREMENTS
(e.g., Monthly reports, biweekly meeting minutes, transition plan)
- 01 32 01.00 10 PROJECT SCHEDULES
(e.g., PM schedules, three week look aheads)
- 01 33 00 SUBMITTAL PROCEDURES
(e.g., FMPs, ISRs, maintenance binders)
- 01 35 26 GOVERNMENTAL SAFETY REQUIREMENTS
(e.g., APP, AHAs, site specific APP)
- 01 45 00.00 10 QUALITY CONTROL
(e.g., QC plan, QC audits)
- 01 78 23 OPERATION AND MAINTENANCE DATA
(e.g., PM reports)

Description of Submittal: Lists each submittal description (SD Number. and type, e.g., SD-02 Shop Drawings) or deliverable required in each specification section.

Type of Submittal: Lists the type of submittal to be reviewed.

Specification Paragraph No.: Lists one principal paragraph in each specification section where the deliverable is specified.

This listing is only to facilitate locating submitted requirements. Classification: Lists the approving authority for each submittal.

Contractor Schedule Dates: Scheduled dates for the approving authority to receive submittals and approval of submittal needed.

Thereafter, the Contractor shall track and maintain all deliverables as required by the PWS, including completion of all data columns and all dates on which submittals are received by and returned by the Government.

Attachment 1 lists all Submittal Requirements (deliverables) for this contract. The government will assist the contractor with RMS submissions

for these deliverables into the appropriate Specification Section as identified above. Note that the submittals listed in the table above is not all inclusive, but is meant to serve as a guide for the most commonly submitted items. The government reserves the right to modify Attachment 1 Submittal Requirements.

1.8.2 Action Codes

1.8.2.1 Government Review Action Codes

"A" - "Approved as submitted"; "Completed"

"B" - "Approved, except as noted on drawings"; "Completed"

"C" - "Approved, except as noted on drawings; resubmission required";
"Resubmit"

"D" - "Returned by separate correspondence"; "Completed"

"E" - "Disapproved (See attached)"; "Resubmit"

"F" - "Receipt acknowledged"; "Completed"

"G" - "Other (Specify)"; "Resubmit"

"X" - "Receipt acknowledged, does not comply with contract requirements";
"Resubmit"

1.8.3 Delivery of Copies

Submit an updated electronic copy of the submittal register to the Contracting Officer with each invoice request. Provide an updated Submittal Register monthly regardless of whether an invoice is submitted.

1.9 GOVERNMENT APPROVING AUTHORITY

When the approving authority is the Contracting Officer or designated Representative, the Government will:

- a. Note the date on which the submittal was received.
- b. Review submittals for approval within the scheduling period specified and compliance with contract documents.
- c. Identify returned submittals with one of the actions defined in paragraph REVIEW NOTATIONS and with comments and markings appropriate for the action indicated.

Upon completion of review of submittals requiring Government approval, stamp and date submittals.

1.10 DISAPPROVED SUBMITTALS

If changes are necessary to submittals, make such revisions and resubmit in accordance with the procedures above. No item of work requiring a submittal change is to be accomplished until the changed submittals are approved.

1.11 APPROVED SUBMITTALS

The Contracting Officer's approval or their designated Representative's approval of submittals is not to be construed as a complete check, and indicates only that the general method of maintenance and repair, documentation, materials, detailing, and other information are satisfactory.

Approval or acceptance by the Government for a submittal does not relieve the Contractor of the responsibility for meeting the contract requirements or for any error that may exist, because under the Quality Control (QC) requirements of this contract, the Contractor is responsible for ensuring information contained with in each submittal accurately conforms with the requirements of the contract documents.

After submittals have been approved or accepted by the Contracting Officer, no resubmittal is necessary.

1.12 APPROVED SAMPLES

Approval of a sample is only for the characteristics or use named in such approval and is not be construed to change or modify any contract requirements. Before submitting samples, provide assurance that the materials or equipment will be available in quantities required in the project. No change or substitution will be permitted after a sample has been approved.

Match the approved samples for materials and equipment incorporated in the work. If requested, approved samples, including those that may be damaged in testing, will be returned to the Contractor, at its expense, upon completion of the contract. Unapproved samples will also be returned to the Contractor at its expense, if so requested.

Failure of any materials to pass the specified tests will be sufficient cause for refusal to consider, under this contract, any further samples of the same brand or make as that material. The Government reserves the right to disapprove any material or equipment that has previously proved unsatisfactory in service.

Samples of various materials or equipment delivered on the site or in place may be taken by the Contracting Officer for testing. Samples failing to meet contract requirements will automatically void previous approvals. Replace such materials or equipment to meet contract requirements.

PART 2 PRODUCTS

Not Used

PART 3 EXECUTION

Not Used

-- End of Section --

SECTION 01 35 26 GOVERNMENTAL SAFETY REQUIREMENTS

Revised 05/2021

1.0 GENERAL

ALL work under this contract will abide by the latest version of the EM 385-1-1, U.S. ARMY CORPS OF ENGINEERS (USACE) Safety and Occupational Health Requirements, including interim changes, in effect on the date of solicitation. In addition to the detailed requirements included in the provisions of this contract, comply with all federal, state, and local (including host nation laws), ordinances, criteria, rules and regulations. If a work element is not covered by regulatory requirements a nationally recognized consensus standard shall apply. Where the requirements of this specification, applicable laws, criteria, ordinances, regulations, manuals, pamphlets and referenced documents vary, the ***most stringent requirements shall govern.***

The suspense dates contained in this Section are firm and shall be met in order to meet not only the requirements of the contract but meeting the customers' requirements to maintain mission capable assets. Poorly developed submittals causing delays in KO/COR acceptance may result in KO action and shall be part of the Contractor Performance Assessment Reporting System (CPARS) safety element, which is a significant evaluation element.

2.0 SAFETY POSITIONS – SUMMARIZED DESCRIPTIONS AND HIGHLIGHTED RESPONSIBILITIES

2.1 Prime Contractor Safety Manager, herein referred to as the **Contract Safety Manager (TOSM)** shall be a full-time employee of the prime contractor and shall have no other duties outside this Contract (TO) (e.g., a different TO or Corporate position). The TOSM shall meet the minimum requirements contained in EM 385-1-1 Chapter 2-3.b, USACE Safety and Occupational Health Requirements . The TOSM's qualifications must clearly show they meet the minimum requirements for the position. The TOSM is responsible for the preparation, execution, training and continuous improvement of the safety program management for this contract.

2.2 Safety and Health Officer (SHO) – A qualified or competent person who is responsible for on-site safety and health on the job site.

NOTE: The TOSM or a SHO (L1, L2, or L3) is required to be on all FUELS jobsites.

2.2.1 Level 1 Safety and Health Officer (L1)

A L1 working under stringent direction and guidance of the TOSM may be a Prime Contractor or Sub-Contractor employee. L1/s shall also meet the minimum requirements contained in EM 385-1-1 Chapter 2-3.b, USACE Safety and Occupational Health Requirements. A L1 is a full time Safety Officer that will be onsite and who through education, experience and training has the technical knowledge and skills needed to anticipate, recognize, and evaluate hazardous conditions and recommend adequate corrective action/s and ensure corrections is/are made in a timely manner. They are responsible for implementing and evaluating their employer's safety

and health program to assure employees (prime and subcontractor) are provided a work environment that is free from any recognized hazards. A L1 shall be accepted by the CEHNC Contracting Officer (KO) and Safety Office.

2.2.2 Level 2 Safety and Health Officer (L2)

A L2 may be a Prime Contractor or Sub-Contractor employee. L2/s shall also meet the minimum requirements contained in EM 385-1-1 Chapter 2-3.b, USACE Safety and Occupational Health Requirements. A L2 is a collateral duty (**Dual Hatted L1**) safety officer who through experience and training has the technical knowledge needed to anticipate, recognize, and evaluate hazardous conditions and recommend adequate corrective action and ensure corrections are made in a timely manner. They are responsible for implementing and evaluating their employer's safety and health program to ensure all employees (prime and subcontractor) are provided a jobsite that is free from any recognized hazards. A L2 is only permitted if they work under stringent direction and guidance of the TOSM, and on projects that have a Risk Assessment Code (RAC) level of low or medium. All L2s shall be accepted by the CEHNC KO and Safety Office.

2.2.3 Level 3 Site Safety and Health Officer Designated Representative (L3)

A L3 may be a Prime Contractor or Sub-Contractor employee. A L3 has additional safety duties in addition to their full-time occupation. In most instances the L3 is the Competent Person for the work task to be performed, e.g., Electrician, Crane Operator, Excavation and Trenching et al. They shall have the technical knowledge needed to anticipate, recognize, and evaluate hazardous conditions and recommend and/or take corrective actions. A L3 is only permitted if they work under stringent direction and guidance of the TOSM, and on projects that have a RAC level of low or medium. All L3s shall be accepted by the CEHNC KO and Safety Office.

3.0 SUBMITTALS

3.1 General Information

Government Designated Authority (GDA) acceptance is required for the following safety submittals:

NOTE: For FUELS safety submittals the KO has determined the GDA will be the FUELS Safety Team.

3.2 Pre-Performance Submittals

Service Orders (SOs) shall not be initiated until the Accident Prevention Plan (APP) and Site-Specific Addendum (SSAs) are submitted, reviewed and accepted by the KO/COR. AHA(s) will be prepared by the prime contractor for each SO request until such time the AHAs listed in Section 8 are reviewed and accepted by FUELS Safety Team in the Resident Management System (RMS) with a Code A, at which time they will be considered as “pre-accepted.” An ENG Form 4025-R will be provided to contractor when submittal(s) are accepted.

3.2.1 Site Visit Abbreviated Accident Prevention Plan (SVAAPP)

This Plan is only applicable for the period of time following post award for the prime contractor to visit each site to gather the specific safety information or other contract information in

development of the APP Site Specific Addendum (SSA) for each location under the TO, Quality Control Plan (QCP), etc. No recurring maintenance or minor repair work is allowed using an SVAAPP, it is only to be used for the prime contractor to visit a Fuels site to collect data listed in the contract as deliverables, e.g., APP, SSA to the APP, QCP, or similar data collection requirements. A blank SVAAPP along with an internet link for a fillable SVAAPP form will be provided at the Post Award Conference. One SVAAPP is required for each site on the Contract.

3.2.2 Accident Prevention Plan (APP)

APP shall:

- A. Be developed and submitted by the Prime Contractor.
- B. The APP shall be submitted in RMS no later than 15 business days following contract award.
- C. Be prepared by a Prime Contractor qualified person, preferably the TOSM, with relevant knowledge, training, skills, abilities and experience to develop a comprehensive APP.
- D. **For the Minimum Plan Requirements for the Accident Prevention Plan see Chapter 2-7. Specific plan requirements apply to all plans required by the PWS. Specific plan requirements are identified in paragraph 7 of each chapter of the EM 385-1-1.** If an item is not applicable because of the nature of the work to be performed, the Prime Contractor shall state this exception and provide a justification. **NOTE: Stating an APP required element will be provided at the SO level is not acceptable for the timely execution of the CEHNC Fuels Safety Program.**
- E. Be written in sufficient detail to ensure each element/sub-element is clearly described so all organizations for which the APP is applicable can understand and implement the safety requirements.
- F. Be job-specific and address any unusual or unique aspects of the project or activity for which it is written.
- G. Submit SSAs once information is acquired, but not later than 30 calendar days following contract award.

Once reviewed and accepted by the KO/COR, the APP, SSAs and AHAs and specific safety plans will be enforced as part of the contract. Service Orders (SOs) shall not be submitted until all APP requirements are approved using a Transmittal Form, ENG Form 4025R, provided by the appropriate CEHNC FUELS Project Manager or FUELS Safety Team.

Disregarding the provisions of this contract or the accepted APP is cause for stopping of work, at the discretion of the KO. The FUELS Project Manager in consultation with the KO and FUELS Safety Team will provide correspondence to the contractor with the reason/s for stop work and the requirements necessary to resume work.

Prime contractor shall review and update the APP:

- As necessary, throughout the life of the contract,

- When a replacement TOSM, Project Manager is assigned to the TO,
- Whenever there is a significant change in hazards, and
- At least annually.

NOTE: When updates are made or following the annual review, a change management process shall document the action(s), i.e. change(s) and/or revisions, and shall be incorporated into the APP immediately following the APP cover sheet. This change document shall provide a brief description of the change, specific paragraph or section changed and/or revised, reason for the change/revision and date of change/revision. Submit the reviewed, changed and/or revised APP in RMS for review and acceptance. **All changes to the APP shall be denoted by placing a vertical line in the margin showing the change.**

If no changes are made during the annual review, a letter from the prime contractor stating the annual review was performed on (date) and no changes were made to the APP is acceptable.

The TOSM shall provide and maintain the APP and a log of signatures by each subcontractor foreman, attesting that they have read and understand the APP, and make the APP and log available on-site to the HNC KO and/or the GDA, PM or Quality Assurance Representative upon request.

3.2.3 Site Specific Addendum (SSA)

Site Specific Addendums (SSAs) are required for each site if more than one site is included in the contract. Each SSA shall be submitted to the KO/COR for acceptance prior to work starting. Each SSA shall only contain detailed site-specific information applicable to a specific location identified in the contract. Do not restate what is already provided in the APP unless the information/details are different. The SSAs shall be attached to the APP as Appendix 1 and be readily available on each specific jobsite. An SSA shall include the following minimum requirements: The Site-Specific Addendum shall include, as a minimum:

- A. Contractor Name
- B. Contract Number
- C. Project Name
- D. Site Specific Project Location
- E. TOSM name/s and responsibilities if different than the APP
- F. Identify point of contact at location (e.g. FMSR)
- G. Emergency Response Plan
 - 1) Names of individuals that are first aid cardiopulmonary resuscitation (CPR) certified when emergency medical services are not accessible within 5 minutes of work location and there are 2 or more workers at the location. At least 2 employees on each shift shall be qualified to administer first aid and CPR certified. If not known,

include in Service Order.

- 2) Location Map to include routes to local hospital/s
- 3) Medical Support Agreement (if applicable to specific location)
- 4) Site Specific Emergency Response plans:
 - a. Procedures and Tests
 - b. Spill Plans
 - c. Fire Fighting Plan
 - d. Posting of Emergency Phone Numbers
 - e. Medical Support

Provide on-site medical support and medical duties for those employees who are designated to perform them. Provide the name(s) of on-site Contractor personnel qualified to administer first aid, cardiopulmonary resuscitation (CPR). In addition, any employee designated to render first aid or medical assistance shall receive Blood-Borne Pathogen (BBP) training. A minimum of two (2) employees shall have current certification in CPR and first-aid per shift/site and BBP training.

Provide the off-site medical arrangements for medical treatment services prior to start of work. This includes effective means of communication to summons medical support services and transportation to the medical facility for treatment beyond first aid. This shall include a highly visible map showing the best route to the medical facility.

Provide the emergency responder rescue services who will be readily available to support such high risk activities such as Confined Space Entry, Falls from heights (Fall Protection), Excavation and Trenching, Working Over or Near Water (if applicable to contract) et al. Rescue services may be provided by the base/installation Fire Department if they have the capability and agree to support and, are within 5 minutes of the jobsite. Other means to provide rescue may be self-performed and 3rd party contract services located on the jobsite in a standby mode.

- H. Installation/Base Security information (contact information)
- I. Installation/Base Confined Space Managers name and contact information
- J. Installation/Base Radiation Safety Officer's name and contact information
- K. Installation/Base Individual/Office responsible for issuing Dig Permit name/s and contact information
- L. Installation/Base Individual/Office responsible for issuing Hot Work Permit name/s and contact information

3.2.4 Activity Hazard Analysis (AHA) ;

Before beginning each activity, task or Definable Feature of Work (DFOW) involving a type of work presenting hazards not experienced in previous work activities, the Contractor(s) performing that work activity must prepare an AHA. **AHAs may be developed by the Prime Contractor, a sub-contractor, any sub-tier contractor, or supplier performing the work and shall be reviewed and approved by the prime contractor's TOSM before submitting to the KO/COR for review and acceptance.** The TOSM shall add their electronic signature to the AHA prior to submitting to the FUELS Safety Team.

Format the AHA in accordance with Chapter 1-6 of EM 385-1-1. Specific AHA requirements are identified in paragraph 6 of each chapter of the EM 385-1-1

NOTE: Regarding pre-accepted AHAs, the Government reserves the right to require the Contractor to revise and resubmit any AHA or require a new AHA be developed if the AHA(s) fail(s) to effectively identify the work sequences, i.e., numbering job steps, specific anticipated hazards, site conditions, and control measures to personnel to include the qualifications described in EM 385-1-1 Chapter 2-6.

Each employee performing work as part of a work activity, job or DFOW identified in a Service Order must review the AHA(s) for that work and sign a signature log specifically maintained for that AHA(s) prior to starting work. The TOSM shall review and maintain copies of signature logs of job site reviewed AHAs. Provide copies to KO/COR upon request. The SHO (L1, L2, or L3) onsite shall use the AHAs during daily inspections to ensure the implementation and effectiveness of the required safety and health controls for that work activity.

Prime Contractor shall review and update the AHAs every 12 months throughout the life of the contract. The review should be performed in conjunction with the APP review. If no updates are required to an AHA, a letter from the prime contractor to the CEHNC Project Manager in RMS must be provided to this effect. If updates are made, resubmit only those AHAs updated to the CEHNC Project Manager via a letter along with the applicable AHA(s) from the prime contractor in RMS. The FUELS Safety Team will review and provide acceptance through RMS.

Utilize the list shown in Table 8-1 below for the minimum required AHAs to be included in the APP. **These AHAs shall be submitted to the KO within 30 calendar days following contract award.** The Fuels Safety Team shall have between 21 and 30 calendar days to review and provide a response in RMS. Once AHAs are accepted with a Code A in RMS, they will be deemed pre-accepted AHAs to be used throughout the life of the contract with the exception of those identified in Section 3.2.5 and the AHA, Electrical - Inspect, Troubleshoot, Remove & Replace and/or Repair found in PWS Appendix C, Section 01 35 26, Paragraph 8.0, which shall be task specific or as directed by the KO/COR.

NOTE: Do not restate the safety requirement(s) listed in EM 385-1-1 or OSHA. The AHA must identify the specific JOB STEPS, i.e. numbering 1, 2, 3, etc., potential HAZARDS in performing each Job Step and the detailed CONTROLS to abate the hazards". The focus shall be on by "Who," "When" and "How" the control will be achieved.

EXAMPLE: If a control for a hazard requires PPE, specify the PPE to be worn to perform the work activity. Do not state, appropriate PPE will be worn. The Control shall be identifiable

and specific to abate the stated hazard, e.g., state the type of gloves, eyewear, footwear, respiratory and/or hearing protection, clothing, etc.

Once pre-accepted, AHAs will not require additional review at the Service Order level except as noted. If a work task is not identified the prime contractor is responsible to submit a new AHA(s) for review and acceptance. A new AHA(s) may be added throughout the life of the contract once direction is given from the FUELS Safety Team to add to the pre-accepted listing. *Note.* For a non-mandatory formatted outline of an AHA see ENG Form 6206 (Activity Hazard Analysis) (See Chapter 1-10.b.)

3.2.5 AHA Change Management

If site conditions or work activities change, field changes are acceptable by “redlining” the AHA as follows:

- A. This AHA shall be reviewed and modified as necessary to address changing site conditions, operations, work activities or change of Competent Person(s)/Qualified Person(s).
- B. The AHA(s) requiring minor change(s)/addition(s), i.e. $\leq 33\%$ of any AHA is “redlined,” or if the overall RAC does not change to an AHA(s) that were submitted with the SO request, “redlining” is acceptable.
- C. Changes or updates to an AHA that do not increase the RAC are not required to be resubmitted for acceptance by the KO/COR.
- D. If the AHA(s) requires moderate changes/additions, i.e., $> 33\%$ of any AHA is “redlined,” and the initial RAC increases due to a changes made to an AHA, the AHA shall be resubmitted to the KO/COR, i.e., FUELS Safety Team, for review and acceptance prior to work proceeding.
- E. If the site conditions or work activities change requiring the submission of a new or pre-accepted AHA, it shall be submitted to the FUELS Safety Team for review and/or acceptance prior to the work commencing.
- F. Change of Competent Person(s)/Qualified Person(s) require prior approval of the TOSM.
- G. Workers/crews shall have in their possession the current AHA(s) that reflect current site conditions, personnel, equipment, and control measures, etc. while the work is being performed.
- H. All new or pre-accepted AHAs that were not submitted with the original SO request shall include the Service Order Desk email address so the documents can be appended to the appropriate portfolio.

3.2.6 AHAs and site-specific plans for activities having higher “Risk Factors”

If/when the Contractor is tasked to perform work which has higher risk factors, they shall submit job specific AHAs and/or plans as specified in EM 385-1-1. Work activities having higher “Risk Factors” that could lead to imminent danger situations and/or conditions necessitating closer

assessment of the work being recommended will require site specific preparations. These activities shall be carefully planned and job/activity specific AHA(s) developed to ensure the residual risk level RAC is no greater than a Medium Risk. The AHA(s) and required plans/procedures for these work activities shall be submitted to the FUELS Safety Team for review and acceptance prior to work being performed. As part of the prime contractor's planning, these new and/or updated AHAs should be submitted with the Service Order request to preclude delays in last minute reviews. Specific AHA requirements are identified in paragraph 6 of each chapter in the EM 385-1-1. See Higher Risk Factor Activities list below. The list is not all inclusive.

NOTE: Regarding the SSA and Sections from the APP, those documents may be provided to prime contractor's subcontractor for review and use; but this should not be necessary since the contract requirements has a provision that the accepted APP shall be provided to each subcontractor for compliance.

Higher risk factor activities are as follows:

- Wearing of Respiratory Protection (not included in a pre-accepted AHA)
- Lead Abatement
- Asbestos Abatement
- Energized Work
- Standard and Critical Lifts
- Fall Protection (not included in a pre-accepted AHA)
- Demolition/Renovation (large scale such as demolishing a building or structure)
- Excavation/Trenching (5' or greater in depth)
- Confined Space Entry
- Abrasive Blasting
- Dive Operations

The contractor is required to have a L1 who shall have no other responsibilities, for maintenance or repair being performed on these higher risk factor activities. If the TOSM determines that a L1 is not necessary, this determination shall be provided to the KO/COR in the Service Order for acceptance. Example: For many standard lifts, an L3 may be utilized but the determination rests with the TOSM. The above list is not meant to exclude additional hazardous work activities that may have a significant risk and does not relieve the contractor from maintaining an acceptable level of safety, in accordance with the EM 385-1-1.

NOTE: When pre-accepted AHAs are used for a Service Order a statement will be provided on the Service Order email stating, "The attached pre-accepted AHAs are required for this task. No new AHA is required for this task, therefore pursuant to the PWS, no USACE Safety

review is required.”

All AHAs may be updated on the jobsite to meet maintenance and repair requirements. AHAs updated on the jobsite are not required to be submitted to the KO/COR for review and acceptance unless the RAC increases.

AHAs not given “pre-accepted” status, i.e., Code A in RMS, may be submitted at the SO Level for review and acceptance. This allows work to be performed for approximately 30 days following the post award to give the prime time to meet contract requirements in preparing and submitting AHAs in RMS within 30 calendar days in order to obtain “pre-accepted” status.

3.2.7 Appendix 6 of APP

Provide copies of Incident Report Forms (3394), Inspection Forms, First Aid Logs, etc. in Appendix 3 of the APP.

3.2.8 Appendix 6 of APP

Provide Competent / Qualified Personnel names and proof of qualifications. (L1s, L2s, L3s, Electricians, Riggers, Confined Space, Fall Protection, Excavation and Trenching, etc.) in Appendix 4 of the APP.

- Contract Safety Manager
- Additional SHOs (L1s, L2s, and L3s)
- Qualified Personnel: Licensed electricians - Master or Journeyman, Crane Operators (certified and designated in writing), Riggers (designated in writing), etc.)
- Competent Personnel (lock out tag out, fall protection, etc.)

NOTE: Proof of competency/qualification for the TOSM and all SHO/s (L1, L2, and L3) must be submitted with the APP in Appendix 4. The competency/qualification must be reviewed and found acceptable by the KO/COR before initiation of work at the job site.

3.2.9 Service Order (SO) Types, i.e., Routine, Emergency, Not to Exceed (NTE),

All required safety documents shall be submitted with each SO type. SOs must provide detailed site-specific information and include at a minimum;

- A. The identification and proof of qualification (if not in APP) of the SHO (L1, L2, or L3) who will be onsite during work.
- B. The identification and proof of qualification for competent persons (e.g., Confined Space, Fall Protection, Excavation & Trenching, etc.) and proof of qualification and/or credentials for qualified persons, (e.g., Electrician, Crane Operator, Rigger, etc., if not in APP). Qualifications shall meet the minimum requirements as defined in each specific chapter of the EM 385-1-1.
- C. Detailed site-specific AHAs for new work activities if no pre-accepted AHAs are on file.

- D. Any additional site-specific plans (e.g., Fall Protection Plan, Confined Space, Respiratory Protection Plan, Critical Lift Plan, Excavation (over 5' in depth), Abrasive Blasting Plan etc.) Plans shall address EM 385-1-1 minimum requirements, examples, Fall Protection Plan shall include all information required by EM 385-1-1, Chapter 21-7 .
Excavation/Trenching plan in accordance with Chapter 25-7.A, Abrasive Blasting Plan IAW Chapter 6-7f.

3.2.10 Work Plan (WP) Development

As part of the prime contractor's assessment of the Service Order (SO) work request, an engineering technical Complexity Determination Work Sheet showing whether a WP is required based on the complexity of the work task. If it is determined by CEHNC Engineering a WP is required, **all Safety documents shall be included in the WP e.g., required AHAs, specific job task plans, e.g., Abrasive Blasting, Excavations (over 5' in depth), Fall Protection, current certifications/qualifications of workers, e.g., Confined Space Training, Crane Operator, Rigger, licenses, e.g., Electrician (Journeyman or Master), etc. and submitted with the SO request.** Information on Work Plans can be found in a specific chapter number (i.e.##-7).

3.2.11 Qualified/Competent Person/s Credentials

License, Certificates, etc. of Qualified/Competent Person/s must be submitted, reviewed and found acceptable by the KO/COR before initiation of work at the job site. The license and/or certifications must include as a minimum Qualified Electrician/s, Confined Space CP, Fall Protection CP, Scaffold CP, Excavation CP, Load Handling Equipment Operator/s, Rigger, Signal Person, and Crane Operator to include their medical clearance. Note: These can be submitted in Part 13, Appendix 3 of the APP.

3.2.12 Designation of Safety and Health Official Certificate (Form 01-1)

The TOSM and all SHOs shall have a Designation of Safety and Health Official Certificate signed by their employer. This certificate shall be submitted to the KO/COR along with the APP, SSAs, Site Specific Work Plans, Activity Hazard Analyses, etc. A copy of this certificate shall be maintained by the SHO. These can be submitted in Part 13, Appendix 3 of the APP.

3.2.13 Certificate of Compliance

Submit for acceptance a signed FORM 16-1 Certificate of Compliance (COC) for each piece of Load Handling Equipment prior to being brought onsite. The COC shall be visually posted on the LHE. (See EM 385-1-1, Chapter 16-8.hh. The ENG Form 6209, Certificate of Compliance can be found at Chapter 16-10.

3.2.14 Radiation Safety Program Requirements

If a device containing a radiation source is used, possessed, transported, stored on or to the jobsite, a Radiation Safety Program in accordance with EM 385-1-1 Chapter 36-6 and 36-7. is required to be part of the APP. For FUELS work activities the radiation generating device is usually an apparatus for taking x-rays of welds to determine the integrity of the weld. In addition to these requirements the Prime Contractor shall include the following:

- A. Ascertain the Base/Installation Radiation Safety Officer (RSO) contact information during the initial site visit and include in each location SSA.
- B. Coordination with Base/Installation RSO prior to Non-Destructive Testing (NDT a.k.a. Non-Destructive Examination (NDE)) being performed using a radiation source. Document this coordination and submit to the KO/COR upon request.
- C. An NDE AHA must be submitted to the KO/COR at the Service Order Level. Ensure the AHA includes the contractor's RSO or equivalent and the Competent Person if different from RSO.

3.3 Post Service Order Submittals (Completion of Service Order)

3.3.1 Mishap Notifications and Reports (See Section 7.1 for specific reporting timelines)

Mishap reporting fillable forms will be provided to the contractor by the KO at post award meeting. The prime contractor shall report all mishaps to the KO in accordance with EM 385-1-1. The ENG 3394, U.S. Army Corps of Engineers Mishap Notification and Investigation Form can be found at Chapter 2-10.

3.3.2 Signed Activity Hazard Analysis (AHA)

Site specific AHA's shall be reviewed prior to any work. These AHA's shall be signed and dated by all employees who are engaged in the performance of the work. Signed AHA's shall be submitted with the applicable payment request.

3.3.3 Signed Daily Safety Briefings

Safety briefings shall be conducted daily prior to work being performed on the jobsite. These shall be signed and dated by all employees. Signed daily safety briefings shall be submitted with the applicable payment request.

3.3.4 Daily Safety Reporting

Each QC daily report shall include a summary of safety related actions performed each day.

3.3.5 Signed/Completed Standard Lift Plan

Signed/completed standard lift plans shall be submitted with the applicable payment request.

3.3.6 Monthly Exposure Reports

Provide Monthly Exposure Hours Report and attach to the monthly billing requests. This report is a compilation of employee-hours worked each month for all site workers, both prime and subcontractors. Failure to submit the report may result in retention of up to 10 percent of the voucher.

Exposure hours shall be submitted to HNC Contracting (CT). The data must be posted in RMS and submitted per CT direction not later than 7 calendar days after the end of each month or as directed by the KO. The information cut-off date will be the last day of each month. Exposure data consists of man-hours expended in direct performance of the work performed on the jobsite.

NOTE: Hours associated with administrative activities such as payroll, human resource, service order managers/technicians, etc., are not to be submitted in the monthly report.

The monthly submission shall be broken down by Contract and identify exposure hours for each Contract. If no hours are worked on the project/task, a report showing “zero (0)” is required. (Failure to submit the report may result in retention of up to 10 percent of the voucher).

4.0 QUALIFICATIONS, DUTIES, AND MEETINGS

4.1 Prime Contractor

The Government considers the Prime Contractor to be the “controlling authority” for the safety and health of the subcontractors. As a minimum the Prime Contractor will:

- A. Describe in the APP the safety protocol for vetting and controlling subcontractors and suppliers who may perform work or support the work under this contract.
- B. Describe in the APP the method(s) to evaluate past safety performance of potential subcontractors in the selection process.
- C. Describe in the APP method(s) to be used to ensure and monitor safe work practices of subcontractors.
- D. Describe in the APP how the prime contractor shall review and approve subcontractor safety submittals, e.g., safety plans, etc.,
- E. Inform their subcontractors of the safety provisions under the terms of the contract and the penalties for noncompliance.
- F. Provide a copy of the accepted APP to each subcontractor. This may be hardcopy or electronic copy.
- G. Coordinate the work to prevent one craft from interfering with or creating hazardous working conditions for other crafts.
- H. Inspect subcontractor operations to ensure APP requirements are being carried out.
- I. Provide an interpreter who is fluent in English and the language being translated, if English is not the foreman’s, supervisor and/or competent person’s primary language.
- J. If a severe hazard exposure (i.e. imminent danger) becomes evident, provide the procedure in the APP to suspend and secure the work area. The procedure shall include a strategy to remove the imminent danger and control and/or eliminate the hazard. Notify the KO within 24 hours of discovery.
- K. Take all necessary action to maintain safe working conditions in order to safeguard onsite personnel, visitors, the public (as defined by ASSP/SAFE A10.34), and the environment.

4.2 Contract Safety Manager Requirement

The TOSM will be a full-time employee of the prime contractor and shall have no other duties

outside this Contract.

This contract requires a minimum of one TOSM, a.k.a. L1, to manage and oversee the implementation of the Prime Contractors Safety Program. The TOSM shall:

- A. Meet the requirements of this specification to serve as the prime contractor’s full-time TOSM.
- B. Manage the safety oversight team that includes a minimum of one person at each project site to function as the SHO (L1, L2, or L3) at all times.
- C. Implement and administer the prime contractor’s safety program and government-accepted APP.
- D. Ensure the requirement of EM 385-1-1, USACE Safety and Occupational Health Requirements are met for work performed under this contract.
- E. Ensure the requirements of 29 CFR 1926.16, Rules of Construction are met for each project.
- F. Determine additional levels of onsite SHO with the names submitted for review and acceptance by the KO/COR as Part 13, Appendix 3 to the APP.
- G. Appoint additional SHOs (L1, L2, or L3) for projects with multiple shifts as required to ensure a Safety and Health Officer is at a project site at all times when work activities are conducted.
- H. Ensure the appropriate level of SHO/s is/are assigned to each location. All SHO’s must be designated in writing on a Site Safety and Health Officer Designation Letter. The mandatory ENG Form 6282, Site Safety and Health Officer (SSHO) Designation Letter can be found at Chapter 2-10.
- I. Do not assign L2s or L3s to projects that have a residual risk level greater than medium. **NOTE:** Please be advised, no work will be performed with a residual risk of high or extremely high on Corps Projects. Controls shall be identified to ensure the residual risk is either medium or low risk.
- J. Assist the Contractor’s project management team responsible for managing, communicating, implementing and enforcing compliance with the Contractor’s APP and other accepted safety and health submittals.
- K. Compile and track safety deficiencies reported by SHO’s or others in the field. Ensure corrective actions are taken to mitigate all identified deficiencies. A deficiency tracking system shall be used by the TOSM. A copy of this tracking document shall be provided to the KO/COR upon request.
- L. Shall develop a “Lessons Learned” program for internal company sharing of safety information to include but not limited to: mishaps - investigation and mitigation measures, property damage, near misses, personal injury or illness. The sharing of lessons learned across the prime contractor’s enterprise, especially those contractors having more

than one contract with HNC FUELS, as a proactive accident prevention tool to aid in accident reduction across FUELS jobsites.

M. Perform annual review of the KO/COR accepted APP.

4.3 Level 1 Safety and Health Officer (SHO) Requirement

A L1 shall:

- Meet the requirements of EM 385-1-1 Chapter 2-3.b(1).
- Have the required training, experience, and qualifications in accordance with this specification, EM 385-1-1, and all associated sub-paragraphs.

NOTE: No work shall be conducted at the site of the work until a SHO L1, L2, or L3 is present as described in this PWS.

4.3.1 Level 1 Safety and Health Officer (L1) Responsibilities

Additionally, an L1 shall:

- A. Be designated by their employer in writing. The mandatory ENG Form 6282, Site Safety and Health Officer (SSHO) Designation Letter can be found at Chapter 2-10.
- B. Be required on to manage and ensure the APP and safety requirements as stated in this PWS, or as indicated by a stated reference within the PWS, are being implemented.
- C. Be a direct hire of the prime contractor or sub-contractor and an employee other than the supervisor.
- D. Report to the TOSM.
- E. Be a full-time responsibility and be present at the project site and have full access to all major work operations during the work shift.
- F. Provide a copy of their OSHA 30-hour training card. Requirements for the 30-hour general industry or construction safety training can be found at Chapter 2-3b., paragraph b.

Note: If the L1 cannot be onsite a qualified L2 or L3 shall be assigned by the TOSM to oversee safety at each location/site.

4.3.2 TOSM and all L1 SHOs shall:

- A. Provide a copy of their OSHA 30-hour training card in the APP (or course completion if within 90 days of having completed the training and card has not yet been issued). They will have completed:
 - 1) The 30-hour OSHA General Industry safety class (may be web-based training if the student is able to directly ask questions of the instructor by chat or phone); or
 - 2) The 30-hour OSHA Construction Industry safety class (may be web-based training if

the student is able to directly ask questions of the instructor by chat/phone), or

- 3) In lieu of formal OSHA 30-hour training, SOH training covering the subjects of the OSHA 30-hour course and this manual may be accepted by the KO in coordination the local SOHO having jurisdiction over the work. The local SOHO will evaluate the proposed equivalent training for applicability to the contract scope of work being performed.

NOTE: The CEHNC FUELS Safety Team will evaluate the proposed equivalent training for applicability to the contract work to be performed.

- 4) Provide proof of employment for:
 - a. Five (5) years of continuous construction industry safety experience in supervising/ managing general construction (managing safety programs or processes or conducting hazard analyses, specifically hazard identification and developing controls), or
 - b. Five (5) years of continuous general industry safety experience in supervising/managing general industry (managing safety programs or processes or conducting hazard analyses, specifically hazard identification and developing controls), or
 - c.

Note. If the Level 1 SSHO has a safety-related degree, third-party, nationally accredited (for example, American National Standards Institute (ANSI), National Commission for Certifying Agencies (NCCA), Council on Engineering and Scientific Specialty Boards (CESB) SOH-related certification or designation requiring a minimum of three years of experience to obtain, only three years of experience is needed.

- 5) Maintain competency through having taken 8 hours of documented formal, on- line, or self-study safety and health related coursework every year. Examples of continuing education activities that meet this requirement are: writing an article, teaching a class, reading/writing professional articles, and attendance/participation in professional societies/meetings.

4.4 Level 2 Safety and Health Officer (L2) Responsibilities

- Meet the requirements of EM 385-1-1 Chapter 2-3.b(2).
- Have the required training, experience, and qualifications in accordance with this specification, EM 385-1-1, and all associated sub-paragraphs.

Note: A L2 is only permitted on M&S projects that have a residual risk of low or medium.

Additionally, an L2 shall:

- A. Be designated by their employer in writing. The mandatory ENG Form 6282, Site Safety

and Health Officer (SSHO) Designation Letter can be found at Chapter 2-10.

- B. Work under stringent direction and guidance of the TOSM.
- C. Be a collateral duty responsibility (dual hatted L1) and possess an OSHA 30-hour training card and proof of employment described in Paragraph 4.3.2 above.
- D. When permitted by contract the L2 shall be present at the project site and have access to all major work operations during the shift.
- E. Be a direct hire of the prime contractor or the subcontractor.
- F. Report directly to TOSM.
- G. Be trained on the Prime contractor's corporate Safety and Occupational Health policies and procedures (APP, AHA, policies, site specific plans and procedures, etc.).
- H. Perform safety program tasks (e.g. ensure training and qualifications of site workers, document safety meetings, AHA reviews and site-specific updates, inspections, etc.) as required and directed by a L1 or corporate safety official.
- I. Report all findings and documentation to the TOSM.
- J. On projects with multiple shifts, appoint equally qualified Alternate L2s as required. L2s shall be identified in both the APP and the AHA.
- K. Appoint an equally qualified Alternate L2 to fulfill the same roles and responsibilities as the primary L2, if off the site of the work for a period longer than 24 hours.
- L. NOT be assigned to projects that have a residual risk greater than medium.

NOTE: Be advised, no work will be performed with a residual risk of high or extremely high on Corps Projects. Controls shall be identified to ensure the residual risk is either medium or low risk.

4.5 Level 3 Safety and Health Officer (L3) Responsibilities

Note: A L3 is only permitted on M&S projects that have a residual risk of low or medium.

All Level 3 SSHOs must be a designated QP or CP according to Chapter 2-22.x(3) that has experience which enables identification of hazards and implementation of controls for the work being performed.

Additionally, an L3 shall:

- A. Be designated in writing. The mandatory ENG Form 6282, Site Safety and Health Officer (SSHO) Designation Letter can be found at Chapter 2-10.
- B. Work under *stringent direction and guidance of TOSM*.
- C. Be a collateral duty responsibility. When permitted by contract be present at the project site and have reasonable access to all major work operations during the shift.

- D. Be an employee of either the prime contractor or a subcontractor.
- E. Report directly to the TOSM.
- F. Be a designated competent/qualified person for the work being performed.
- G. Have training and experience commensurate to the oversight responsibilities.
- H. Have a minimum of 8 hours of training annually and specific knowledge of the potential hazards of the tasks being completed. Examples of continuing education activities that meet this requirement are: writing an article, teaching a class, reading/writing professional articles, attendance/participation in professional societies/meetings, etc.
- I. Meet minimum training requirements for Competent/Qualified Person in OSHA 1926.32(f) and EM 385-1-1, Appendix A. Documentation of required work experience and training shall be submitted (qualifications, certifications, etc.) to the prime contractor for review and acceptance prior to appointing as a L3 for the Service Order work request.
- J. Be trained on the Prime contractor's corporate Safety and Occupational Health policies and procedures (APP, AHA, directives, etc.).
- K. NOT be assigned to projects that have a residual risk greater than medium.

NOTE: Be advised, no work will be performed with a residual risk of high or extremely high on Corps Projects. Controls shall be identified to ensure the residual risk is either medium or low risk.

The Quality Control (QC) Manager, and TOSM are subject to dismissal if the above duties are not being effectively carried out. If QC Manager, or TOSM are dismissed, project work will be stopped and will not be allowed to resume until a suitable replacement is approved and the above duties are again being effectively carried out.

4.6 Post Award Meeting

The Contractor TOSM for each contract award shall attend the post award conference.

5.0 PERSONNEL DUTIES:

5.1 The TOSM shall:

- A. Conduct safety and health inspections when onsite and maintain a written log which includes area/operation inspected, date of inspection, identified hazards, recommended corrective actions, estimated and actual dates of corrections.
- B. Conduct mishap investigations and complete required accident reports. Report all recordable mishaps to the KO within 24 hours.
- C. Use and maintain OSHA's Form 300 to log work-related injuries and illnesses occurring on the project site for Prime Contractors and subcontractors. Post and maintain the Form

300A on the site Safety Bulletin Board as required by OSHA.

- D. Maintain applicable safety reference material on the job site.
- E. Review the APP and AHAs for compliance with EM 385-1-1, and approve, sign, implement and enforce them.
- F. Ensure subcontractor compliance with Safety and Occupational Health Requirements.
- G. Maintain a list of hazardous chemicals on site and their material Safety Data Sheets (SDS).
- H. Provide and keep a record of site safety orientation and indoctrination for contractor employees, subcontractor employees, and site visitors.
- I. Review and digitally sign all service orders, work plans, and all other safety documents submitted to the KO/COR for acceptance.

5.2 The SHO's shall:

- A. Perform safety program tasks (e.g. ensure training and qualifications of site workers, document safety meetings, AHA reviews and site-specific updates, inspections, etc.) as required and directed by a L1 or corporate safety official.
- B. Report and provide all findings and documentation to the TOSM.
- C. In addition to the above, EM 385-1-1 Chapter 2-4.a-h provides additional Roles and Responsibilities.

6.0 DISPLAY OF SAFETY INFORMATION

6.1 Safety Bulletin Board/Information

Within 7 calendar day(s) after commencement of contract work, the contractor must erect a safety bulletin board at the site of work to post mandatory information for employee and visitor review. Where site, size, duration, type of work to be performed and/or logistics of project do not facilitate a fixed type bulletin board, an alternative method (i.e., binder, digital) may be submitted to the KO for approval.

The FUELS Program utilizes mobile crews who travel from location to location to perform RMC activities under this contract, so for effectiveness, an alternate approach shall be used and described in the APP.

Examples:

- A “hardcopy” of the required safety documents may be maintained in the service vehicle and readily available for reference and use by the work crews on the jobsite as well as made available to CEHNC representatives, e.g., Safety, Quality, PMs, Engineering, etc., upon request.
- Use of corporate/project electronic media such as a 10” Tablet or larger is acceptable so

long as it properly maintained and kept up to date. I must be readily available for reference and use by the work crews on the jobsite as well as made available to CEHNC representatives, e.g., Safety, Quality, PMs, Engineering, etc., upon request.

Special Note: Corporate, project or personal cell phones do not meet the electronic media requirement for this alternative. However, a cellphone may be used for quick referencing, but it is not a substitute for the corporate/project provided electronic media.

The alternative method shall be readily available following acceptance of APP and will be deemed as meeting the requirement for a bulletin board. Regardless of methods, fixed or alternative, the required information shall be maintained as described in EM 385-1-1, Chapter 2-8.f(2).

7.0 NOTIFICATIONS and REPORTS

7.1 Mishap Notification

The Prime Contractor PM is responsible for notifying the KO, HNC Project Manager, and FUELS Safety Team as soon as practical, but no more than 24 hours, after any mishap, including reportable and recordable accidents, incidents, and near misses. The Contractor is responsible for immediately securing the jobsite where the mishap occurred and coordinate with the FMSR to ensure the integrity of the mishap location is maintained. The Contractor is responsible for obtaining appropriate medical and emergency assistance and/or for notifying fire, law enforcement, and regulatory agencies as appropriate. The KO or KO/COR i.e., FUELS Safety Team, will provide the Contractor the required mishap reporting forms or internet link at the Post Award Meeting.

- A. Conduct an accident investigation for recordable injuries and illnesses, property damage, and near misses as defined in EM 385-1-1, to establish the root cause(s) of the accident. Complete the applicable USACE Accident Report ENG Form 3394 and provide the report to the KO within 10 calendar day(s) of the accident.
- B. Near miss reports are considered positive and proactive Contractor safety management actions. To assist the Fuels Safety Team with a HNC lessons learned database, please provide all near miss reports within 14 days of occurrence. An email identifying the “Who, What, When, Where, Why & How” will be sufficient along with the actions taken to prevent future occurrence.
- C. Conduct an accident investigation for any load handling equipment accident (including rigging accidents) to establish the root cause(s) of the accident. Complete the LHE (Load Handling Equipment) ENG Form 3394, Accident Report form and provide the report to the KO within 30 calendar days of the accident. Do not proceed with crane operations until cause is determined, and corrective actions have been implemented to the satisfaction of the KO.
- D. In addition to the above, EM 385-1-1, see Chapter 2-4.g(11), Chapter 2-8.d, and Chapter 2-9., Table 2-1. The ENG 3394, U.S. Army Corps of Engineers Mishap Notification and Investigation Form can be found at Chapter 2-10.

8.0 AHAs for Pre-Acceptance

The following list identifies the initial AHAs that shall be developed for the project field activities, with the exception of the Marine Loading Arm (MLA) AHAs unless the contract is for performing MLA work activities. Additional AHAs may be developed as necessary and approved by as a minimum, the TOSM prior to submittal. Any additional AHAs developed to cover work tasks not previously identified or performed will be submitted to the FUELS Safety Team for review and acceptance prior to implementation. If a new AHA is developed and submitted and accepted by the FUELS Safety Team, it may be submitted in RMS for review and acceptance and added to the pre-accepted AHA listing for future use.

The following AHAs will be prepared and submitted for approval under separate cover. These AHAs will be utilized on various service orders as the service order SOW determines. Upon receipt of approval, only the service order number and relevant project information will be added to the AHA header. Table 8-1 contains the AHAs to be submitted for preapproval:

TABLE 8-1

**MINIMUM ACTIVITY HAZARD ANALYSES REQUIRED TO BE
CONTAINED IN THE ACCIDENT PREVENTION PLAN (APP)**

*All AHAs with an * require a site-specific plan in accordance with EM 385-1-1.*

1. Abrasive Blasting *
2. Aerial / Scissor / Bucket Lift
3. Air Compressor / Compressed Air Hazards – (Equipment)
4. Air Compressor / Compressed Air Hazards – (Supplied Air – Respiratory Protection)
5. Alarms – High & Low – (Inspect, Troubleshoot, Remove & Replace and/or Repair)
6. Asbestos Abatement *
7. Asphalt and/or Concrete – (Repair, Removal and/or Replacement)
8. Asphalt and/or Concrete Joint or Crack Sealant Repair (Inspect, Remove & Replace)
9. Barbed or Razor Wire – (Transporting, Handling and Installation)
10. Basket Strainer – (Inspect, Remove and Replace)
11. Bollards – (Repair and/or Replace)
12. Breakaway – (Inspection, Remove and Replace)
13. Bulk Storage Container Placement (Temporary)
14. Coatings / Painting & Minor Touchup Painting
15. Concrete Cutting – (Wet Saw Only)
16. Concrete Placement – (Small or Large Scale)
17. Conductivity Probe – (Inspect, Troubleshoot, Remove & Replace and/or Repair)
18. Confined Space Entry (Permit & Non-Permit Required) *
19. Control of Hazardous Energy (Include worksheet) *
20. Crane Operations *
21. Disconnect Switches – (Inspect, Troubleshoot, Remove & Replace and/or Repair)
22. Dispenser – (Inspect, Troubleshoot, Remove & Replace and/or Repair)
23. Dispenser Pump – (Calibration)
24. Dispenser Sump – (Inspect, Troubleshoot, Remove & Replace and/or Repair)

25. Electrical – (Inspect, Troubleshoot, Remove & Replace and/or Repair)
26. Electrical – (Remove & Replace Conduit)
27. E-stop – (Inspect, Remove & Replace and/or Repair)
28. Excavation and Trenching *
29. Excavation by Hand
30. Excavator Operation – Mini / Compact, Midi, Standard or Large (Heavy) Excavator
31. Eyewash Emergency Shower – (Inspect, Troubleshoot, Remove & Replace and/or Repair)
32. Filter Element – (Remove & Replace)
33. Flange – (Removal & Replace and/or Repair)
34. Flightline Operational Areas
35. Fueling / Refueling / Propane Cylinder Change Out and Operation of Gasoline, Diesel or Propane Powered Generator, Air Compressor or Pressure Washer
36. Gasket – (Inspect, Remove & Replace and/or Repair)
37. Gauge - Pressure – (Inspect, Test, Remove & Replace)
38. Gauge – Tank – (Inspect, Test, Remove & Replace)
39. Gauge Coupling – (Remove, Replace and/or Repair)
40. General Safety Requirements (Shall include at a minimum)
 - a. Mobilization
 - b. Site Setup
 - c. High Traffic Areas
 - d. Ladders – Portable Ladders 20' & below
 - e. Weather (Heat Stress and Cold Stress)
 - f. Biological
 - g. Flora & Faun
 - h. Hand and Power Tools
 - i. Demobilization
41. Ground Wire/Reel/Clamp/Plug/Rod – (Inspect, Remove, Replace/Install, Test)

42. Heating & Air Conditioning (HVAC) – (Inspect, Troubleshoot, Remove & Replace and/or Repair)
43. Heavy Equipment – (Other Than Mini/Compact, Midi, Standard, or Large (Heavy) Hydraulic Excavator)
44. Holiday Testing
45. Hose – (Inspect, Remove & Replace)
46. Hose Retriever – (Inspect, Remove & Replace)
47. Hot Work
48. Hot-Air Tool or Gun
49. Hydrostatic Hose Test
50. Inspect Component
51. Laboratory Hood – (Inspect, Troubleshoot, Repair, Remove and Replace and Test)
52. Laser Alignment (Motor & Pump)
53. Lead Abatement *
54. Leak and Releases – (Inspection, Troubleshooting, Isolation and Repair)
55. Leak Detection – (Inspect, Troubleshoot, Remove & Replace and/or Repair)
56. Load Handling Equipment – (lifting capacity over 2000 lbs)
57. Lubrication – (Swivels, Pumps, Motors, Other Equipment)
58. Meter – (Troubleshoot, Remove & Replace and/or Repair, Calibration)
59. Non-Destructive Examination / Testing (Radiographic, Dye Penetrant, Magnetic Particle, Phased Array Ultrasonic Technology (PAUT), Visual, Air or Water Pressure) Testing
60. Nozzle – (Inspect, Troubleshoot, Remove & Replace and/or Repair/Rebuild)
61. Oil Water Separator (OWS) – (Troubleshoot, Filter Change Out)
62. Overfill Protection – (Valve Install)
63. Pantograph – (Inspect, Troubleshoot, Remove & Replace and/or Repair)
64. Personal Fall Protection (work above 6 feet)
65. Pipe Spool – (Removal & Replace/Install and/or Repair)
66. Piping Removal – (AFFF Piping Removal & Replace/Install and/or Repair)

67. Placards & Labels – (Remove & Replace and/or Install)
 68. Plumbing / Pipe Fitting
 69. Portable Generator – (Operation Inspection, Operation and Use)
 70. Portable Gantry Crane - (lifting capacity 2,000 lbs or less) – (Assemble, Inspect, Operation)
 71. Powered Industrial Trucks (PITS) – (Forklift/Telehandlers)
 72. Preset Meter Register – (Removal & Replace/Install and/or Repair and Test)
 73. Pressure Differential Indicator – (Inspect, Troubleshoot, Remove & Replace and/or Repair)
 74. Pressure Gauge – (Troubleshoot, Test, Remove & Replace and/or Repair)
 75. Pressure Relief Valve – (Inspect, Troubleshoot, Test, Remove & Replace and/or Repair)
 76. Pressure Washing
 - a. Typical pressure (less than 5,000 psi) **
 - b. High Pressure Water Blasting (5,000 to 10,000 psi)
- **Note: The term “pressure washing” typically refers to a washing system not capable of generating more than 5,000 psi. Such systems can be found at a car wash in the form of portable equipment designed for light commercial, home or farm use.
77. High Pressure Jetting – (Using a jetting nozzle)
 78. Pipeline Pressure Testing
 79. Pulser / Veeder Root – (Inspect, Troubleshoot, Remove & Replace and/or Repair)
 80. Pump and Pump Controls – (Inspect, Troubleshoot, Repair, Remove, Rebuild and/or Replace)
 81. Pump - (Inspection and Service – (Only PM)
 82. Regulator – Pressure (Inspect, Remove & Replace)
 83. Rolling Ladders – (Inspection & Use)
 84. Lighting Fixtures/Bulbs/Canopy – (Inspect, Troubleshoot, Remove & Replace and/or Repair)
 85. Scaffolding – (Assembly/Erection, Inspection, Tagging, Use, Disassembly/Dismantling, and Moving)
 86. Shear Valve – (Inspect, Remove & Replace and/or Repair)

87. Site Visit (Collect Data for SO Development)
88. Solenoid – (Inspect, Remove and Replace)
89. Stairs / Walkways / Crossovers Pre-Fab Installation
90. Swivel – (Remove and Replacement)
91. Tank – (Cleaning and Inspection)
92. Temporary Tank – (Placement, Setup and Removal)
93. Thermal Relief Valves – (Remove & Replace or Install)
94. Transport, Load and Unload (Tanks)
95. Truck and Trailer Operations
96. Vacuum Truck – (Operation & Use)
97. Valve – (Inspection, Troubleshoot, Remove & Replace and/or Repair/Rebuild)
98. Valve – (Inspection and Service)
99. Welding – General (non-confined spaces)
100. Welding Operations within Confined Spaces
101. Working Over or Near Water *

MLA AHAs for MLA Contracts Only

MLA 001 Lubrication (Working at elevation) PM	MLA 006 Hydraulic Power PM
MLA 002 Electrical Inspection PM	MLA 007 Hydraulic Power Units
MLA 003 Hydrostatic Pressure Test PM	MLA 008 Corrosion Control
MLA 004 Visual Inspection (Mechanical) PM	MLA 009 Below Deck Pier Inspection
MLA 005 Operation Inspection PM	MLA 010 Visual Inspection (PM) MLA Appurtenance.

FORM 01-1 Designation of Safety and Health Officer Certificate	
This certificate shall be signed by an official of the company that ensures Safety and Health Officer (SHOs) are qualified and designated in writing.	
Prime Contractor Name:	Contract Number:
This form is to designate a qualified SHO (<i>check which applies</i>): Level 1 Safety and Health Officer (L1) ☐ Level 2 Safety and Health Officer (L2) ☐ Level 3 Safety and Health Officer (L3) ☐	
SHO Name:	SHO Phone Number:
I certify that: 1. The above SHO conform to the minimum requirements of the Policy for Safety and Health Officers to include training and experience. 2. The SHO noted above has been trained, qualified and designated in accordance with the requirements in the Policy for Safety and Health Officers. 3. The SHO noted above has been trained on our company's safety policy and procedures. 4. The SHO and company official (staff) are aware that immediate notification to the GDA of any incident or accident is required.	
Company Corporate Official Name/Title:	
Company Corporate Official Signature:	Date:
Additional Information:	
Provide a signed copy of this designation certificate to the Government Designated Authority prior to work. (Submit with Accident Prevention Plan, Site Specific Addendums, Work Orders, etc.) A copy of this certificate shall be maintained by the SHO.	

SECTION 01 45 00.00 10

QUALITY CONTROL

11/16, CHG 1: 02/20

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM INTERNATIONAL (ASTM)

ASTM D3740 (2019) Minimum Requirements for Agencies Engaged in the Testing and/or Inspection of Soil and Rock as Used in Engineering Design and Construction

ASTM E329 (2020) Standard Specification for Agencies Engaged in Construction Inspection, Testing, or Special Inspection

1.2 PAYMENT

Separate payment will not be made for providing and maintaining an effective Quality Control program. Include all associated costs in the applicable **Pricing Worksheet**.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" classification. Submittals not having a "G" are for Contractor Quality Control approval. Submit the following in accordance with Section **01 33 00** SUBMITTAL PROCEDURES:

SD-01 Pre-Performance Submittals

Contractor Quality Control (CQC) Plan and Contractor Interim Quality Control Plan; G

SD-06 Test Reports

Verification Statement

PART 2 PRODUCTS

Not Used

PART 3 EXECUTION

3.1 GENERAL REQUIREMENTS

Establish and maintain an effective quality control (QC) system. QC consist of plans, procedures, and organization necessary to produce an end product which complies with the Contract requirements. The QC system covers all

operations, both onsite and offsite, and be keyed to the proposed activity sequence. The Contractor's Quality Control (QC) staff responsible for the overall quality consists of the Quality Control Manager, Site Manager, and Site Supervisor. The contractor Quality Control Manager will be held responsible for the quality of work and is subject to removal by the Contracting Officer for non-compliance with the quality requirements specified in the Contract. In this context the highest level manager responsible for the overall recurring maintenance and minor repair activities at the site, including quality and production is the Quality Control Manager. Daily QC activities shall be performed by the Quality Control Manager, Site Manager, or Site Supervisor depending on Complexity Matrix and PWS requirements. The Quality Control system must minimize deficiencies while eliminating repeat deficiencies. The Quality Control Manager, Site Manager, or Site Supervisor (depending on PWS requirements and Complexity Matrix) maintains a physical presence at the site at all times and is responsible for all activities at the site, except as otherwise acceptable to the Contracting Officer.

The Contract Safety Manager (TOSM) and Safety and Health Officer (SHO) are also part of the Contractor's Quality Control Team and shall comply with Section 01 35 26 of this PWS.

3.2 CONTRACTOR QUALITY CONTROL (CQC) PLAN

Submit no later than 30 days after receipt of notice to proceed, the Contractor Quality Control (CQC) Plan proposed to implement the requirements of this contract. The Government will consider an interim plan for the first 30 days of operation. Work will be permitted to begin only after acceptance of the CQC Plan or acceptance of an interim plan applicable to the particular feature of work to be started. Work outside of the accepted interim plan will not be permitted to begin until acceptance of a CQC Plan or another interim plan containing the additional work.

3.2.1 Content of the CQC Plan

Include, as a minimum, the following to cover all operations, both onsite and offsite, including work by subcontractors fabricators, suppliers and purchasing agents:

- a. A description of the quality control organization to include Project Managers, Project Coordinators, Project Engineer, Safety Manager, QC Manager, Site Supervisors, SHOs, Safety Competent Qualified Individuals, Maintenance Managers, Site Managers, Scheduler, and any other project personnel identified in contractor's proposal. This will be displayed in an Organizational Chart showing lines of authority and must include names of personnel and position title supporting this Contract.
- b. The name, qualifications (in resume format), duties, responsibilities, and authorities of each person assigned a CQC function.
- c. A copy of the letter to the Safety Manager and QC Manager signed by an authorized official of the firm which describes the responsibilities and delegates sufficient authorities to adequately perform the functions of the Safety Manager and QC Manager, including authority to stop work which is not in compliance with the contract. Letters of direction to all other various quality control representatives

outlining duties, authorities, and responsibilities will be issued by the Safety Manager and QC Manager. Copies of these letters must be furnished to the Government. This letter must state that the Safety and QC Managers have the authority to stop work due to safety concerns per the EM-385-1-1 requirements.

- d. The contractor must maintain a list of qualified Site Managers and Site Supervisors. Qualified Site Managers and Site Supervisors must meet the requirements of the PWS including this section.
- e. Procedures for scheduling, reviewing, certifying, and managing all submittals as required by this Contract. These procedures must be in accordance with Section 01 33 00 SUBMITTAL PROCEDURES.
- f. Control, verification, and acceptance testing procedures for each specific test to include the test name, specification paragraph requiring test, feature of work to be tested, test frequency, and person responsible for each test. (Laboratory facilities approved by the Contracting Officer are required to be used.)
- g. Procedures for tracking preparatory, initial, and follow-up control phases and control, verification, and acceptance tests including documentation.
- h. Procedures for tracking deficiencies from identification through acceptable corrective action. Establish verification procedures that identified deficiencies have been corrected.
- i. Reporting procedures, including proposed reporting formats.
- j. Service Orders - A list of the definable features of work. A definable feature of work is a task which is separate and distinct from other tasks, has separate control requirements, and is identified by different trades or disciplines, or it is work by the same trade in a different environment. Although each section of the specifications can generally be considered as a definable feature of work, there are frequently more than one definable features under a particular section.
- k. Procedures for ensuring compliance with all local, municipal and county rules, regulations, and laws within the delivery nation.
- l. Safety and QC indoctrination procedures for new employees.

3.2.2 Acceptance of Plan

Acceptance (by the Contracting Officer or designated representative) of the Contractor's plan is required prior to the start of work. Acceptance is conditional and will be predicated on satisfactory performance during the Period of Performance. The Government reserves the right to require the Contractor to make changes in the Contractor Quality Control (CQC) Plan and operations including removal of personnel, as necessary, to obtain the quality and safety required.

3.2.3 Notification of Changes

After acceptance of the CQC Plan, notify the Contracting Officer in writing of any proposed change. Proposed changes are subject to acceptance by the Contracting Officer.

3.3 QUALITY CONTROL ORGANIZATION

3.3.1 Personnel Requirements

The requirements for the CQC organization are a Safety and Health Manager, Quality Control Manager, Safety and Health Officer (SHO), Site Manager, and sufficient number of additional qualified personnel to ensure safety and Contract compliance. The Safety Management team does not receive direction or authority from the Quality Control Manager but is instrumental in the success of Quality Control. Refer to Section 01 35 26 GOVERNMENTAL SAFETY REQUIREMENTS for further guidance of Safety personnel. The Contractor's CQC staff have complete authority and responsibility to take any action necessary to ensure safety and Contract compliance. Personnel identified in the technical provisions as requiring specialized skills to assure the required work is being performed properly will also be included as part of the QC organization. The QC staff will be subject to acceptance by the Contracting Officer. The Contractor's CQC staff maintains a presence at the site at all times during progress of the work and have complete authority and responsibility to take any action necessary to ensure Contract compliance. The CQC staff will be subject to acceptance by the Contracting Officer. Provide adequate office space, filing systems and other resources as necessary to maintain an effective and fully functional CQC organization. Promptly complete and furnish all letters, material submittals, shop drawing submittals, schedules and all other project documentation to the CQC organization. The CQC organization is responsible to maintain these documents and records at the site at all times, except as otherwise acceptable to the Contracting Officer.

3.3.2 Quality Control Manager

The Quality Control Manager must have a minimum of 5 years of experience on Operation and Maintenance of Fueling Facilities. The contractor must identify in the QC Plan an Alternate QC Manager to serve in the event of the Quality Control Manager's absence. The Alternate Quality Control Manager must meet the same experience of the Quality Control Manager. The Quality Control Manager and Alternate must be approved by the Contracting Officer and any change in personnel must also be approved by the Contracting Officer.

The Quality Control Manager is responsible for overall management of QC and must have the authority to act in all QC matters for the Contractor. The Quality Control Manager must be employed by the prime Contractor. The Quality Control Manager must report to an officer of the company, not to the project manager. The Quality Control Manager must have no other duties outside this Contract and must not be responsible for performing duties that are the responsibility of other required personnel within the Contract.

3.3.3 Additional Requirement

In addition to the above experience and education requirements, the Contractor Quality Control Manager and Alternate Quality Control Manager are required to have completed the Construction Quality Management (CQM) for Contractors course. If the Quality Control Manager does not have a current certification, obtain the CQM for Contractors course certification within 90 days of award. This course is periodically offered by the Naval Facilities Engineering Command and the Army Corps of Engineers. Contact the Contracting Officer for information on the next scheduled class.

The Construction Quality Management Training certificate expires after 5 years. If the Quality Control Manager's certificate has expired, retake the course to remain current.

3.3.4 Organizational Changes

Maintain the CQC staff at full strength at all times. When it is necessary to make changes to the CQC staff, revise the CQC Plan to reflect the changes and submit the changes to the Contracting Officer for acceptance.

3.4 SUBMITTALS AND DELIVERABLES

Submittals, if needed, have to comply with the requirements in Section 01 33 00 SUBMITTAL PROCEDURES. The CQC organization is responsible for certifying that all submittals and deliverables are in compliance with the contract requirements.

3.5 CONTROL

CQC is the means by which the Contractor ensures that the performance, to include that of subcontractors and suppliers, complies with the requirements of the contract. At least three phases of control are required to be conducted by the Quality Control Manager for each definable feature of work for high complexity service orders and Quality Control Manager may be requested for moderate complexity service orders at the request of the Government.

3.5.1 Contractor Quality Control Complexity Determination

The contractor shall initially recommend what the level of QC complexity is and it shall be designated on the service order. The contractor will provide with each SO, on a separate tab, the following determination matrix.

Note: The example ratings provided show how the color codes and the overall rating are to be displayed. Contractor shall provide his own recommended ratings based on the technical and quality requirements of the work.

The contractor is required to provide effective quality control under all conditions to ensure compliance with the contract and referenced specifications and criteria. Based on task size and complexity, the responsibility for Quality Control may be entrusted to the on-site technicians and supervisory personnel who prove themselves reliable and capable of doing so. After determining the level of complexity, the contractor shall utilize the table below as guidance to recommend at what level the responsibility for Quality Control can be placed. Final determination of complexity ratings and level of QC responsibility is up to the USACE contracting officer or designated representative.

3.5.2 Preparatory Phase

This phase is performed prior to beginning work on each definable feature of work, after all required plans/documents/materials are approved/accepted, and after copies are at the work site. If the Quality Control Manager will not be on site, the preparatory phase can be completed by the on-site Site Manager or Site Supervisor with coordination and input from the Quality Control Manager. This phase includes:

- a. A review of each paragraph of applicable specifications, reference codes, and standards. Make available during the preparatory inspection a copy of those sections of referenced codes and standards applicable to that portion of the work to be accomplished in the field. Maintain and make available in the field for use by Government personnel until final acceptance of the work.
- b. Review of the activity specific work requirements, drawings, schematics, etc. as applicable.
- c. Check to assure that all materials and equipment have been tested, submitted, and approved.
- d. Review of provisions that have been made to provide required control inspection and testing.
- e. Examination of the work area to assure that all required preliminary work has been completed and is in compliance with the Contract.
- f. Examination of required materials, equipment, and sample work to assure that they are on hand, conform to approved shop drawings or submitted data, and are properly stored.
- g. Review of the appropriate activity hazard analysis to assure safety requirements are met.
- h. Discussion of procedures for controlling quality of the work including repetitive deficiencies. Document tolerances and workmanship standards for that feature of work.
- i. Check to ensure that the portion of the plan for the work to be performed has been accepted by the Contracting Officer.
- j. Discussion of the initial control phase.
- k. The Government needs to be notified at least 24 hours in advance of beginning the preparatory control phase. Include a meeting conducted by the Quality Control Manager and attended by the superintendent, other CQC personnel (as applicable), and the foreman responsible for the definable feature. Document the results of the preparatory phase actions by separate minutes prepared by the Quality Control Manager and attach to the daily CQC report. Instruct applicable workers as to the acceptable level of workmanship required in order to meet contract specifications.

3.5.3 Initial Phase

This phase is accomplished at the beginning of a definable feature of work. Accomplish the following:

- a. Check work to ensure that it is in full compliance with contract requirements. Review minutes of the preparatory meeting.
- b. Verify adequacy of controls to ensure full contract compliance. Verify required control inspection and testing are in compliance with the contract.
- c. Establish level of workmanship and verify that it meets minimum

acceptable workmanship standards. Compare with required sample panels as appropriate.

- d. Resolve all differences.
- e. Check safety to include compliance with and upgrading of the safety plan and activity hazard analysis. Review the activity analysis with each worker.
- f. The Government needs to be notified at least 24 hours in advance of beginning the initial phase for definable feature of work. Prepare separate minutes of this phase by the Quality Control Manager and attach to the daily CQC report. Indicate the exact location of initial phase for definable feature of work for future reference and comparison with follow-up phases.
- g. The initial phase for each definable feature of work is repeated for each new crew to work onsite, or any time acceptable specified quality standards are not being met.

3.5.4 Follow-up Phase

Perform daily checks to assure control activities, including control testing, are providing continued compliance with contract requirements, until completion of the particular feature of work. Record the checks in the CQC documentation. Conduct final follow-up checks and correct all deficiencies prior to the start of additional features of work which may be affected by the deficient work.

3.5.5 Additional Preparatory and Initial Phases

Conduct additional preparatory and initial phases on the same definable features of work if: the quality of on-going work is unacceptable; if there are changes in the applicable CQC staff, onsite production supervision or work crew; if work on a definable feature is resumed after a substantial period of inactivity; or if other problems develop.

3.6 TESTS

3.6.1 Testing Procedure

Perform specified or required tests to verify that control measures are adequate to provide a product which conforms to contract requirements. Upon request, furnish to the Government duplicate samples of test specimens for possible testing by the Government. Testing includes operation and acceptance tests when specified. Procure the services of a Corps of Engineers approved testing laboratory or establish an approved testing laboratory at the project site. Perform the following activities and record and provide the following data:

- a. Verify that testing procedures comply with contract requirements.
- b. Verify that facilities and testing equipment are available and comply with testing standards.
- c. Check test instrument calibration data against certified standards.
- d. Verify that recording forms and test identification control number system,

including all of the test documentation requirements, have been prepared.

- e. Record results of all tests taken, both passing and failing on the CQC report for the date taken. Specification paragraph reference, location where tests were taken, and the sequential control number identifying the test. If approved by the Contracting Officer, actual test reports are submitted later with a reference to the test number and date taken. Provide an information copy of tests performed by an offsite or commercial test facility directly to the Contracting Officer. Failure to submit timely test reports as stated results in nonpayment for related work performed and disapproval of the test facility for this Contract.

3.6.2 Testing Laboratories

All testing laboratories must be validated by the USACE Material Testing Center (MTC) for the tests to be performed. Information on the USACE MTC with web-links to both a list of validated testing laboratories and for the laboratory inspection request for can be found at:

<https://mtc.erdcdren.mil/>.

3.6.2.1 Capability Check

The Government reserves the right to check laboratory equipment in the proposed laboratory for compliance with the standards set forth in the contract specifications and to check the laboratory technician's testing procedures and techniques. Laboratories utilized for testing soils, concrete, asphalt, and steel is required to meet criteria detailed in **ASTM D3740** and **ASTM E329**.

3.6.2.2 Capability Recheck

If the selected laboratory fails the capability check, the Contractor will be assessed a charge to reimburse the Government for each succeeding recheck of the laboratory or the checking of a subsequently selected laboratory. Such costs will be deducted from the Contract amount due the Contractor.

3.6.3 Onsite Laboratory

The Government reserves the right to utilize the Contractor's control testing laboratory and equipment to make assurance tests, and to check the Contractor's testing procedures, techniques, and test results at no additional cost to the Government.

3.7 COMPLETION INSPECTION

3.7.1 Punch-Out Inspection

Conduct an inspection of the work by the Quality Control Manager or other QC staff near the end of the work, or any increment of the work established by the Work Plan or Service Order description. Prepare and include in the CQC documentation a punch list of items which do not conform to the approved Work Plan or Service Order specifications, as required by paragraph DOCUMENTATION. Include within the list of deficiencies the estimated date by which the deficiencies will be corrected. Make a second inspection the Quality Control Manager or other QC staff to ascertain that all deficiencies have been corrected. Once this

is accomplished, notify the Government that the facility is ready for the Government Pre-Final inspection. If the Quality Control Manager will not be on site per the cost/complexity matrix, this phase can be completed by the on-site Site Manager or Site Supervisor with coordination and input from the Quality Control Manager.

3.7.2 Pre-Final Inspection

The Government may perform the pre-final inspection to verify that the system or facility is complete. A Government Pre-Final Punch List may be developed as a result of this inspection. Ensure that all items on this list have been corrected before notifying the Government, so that a Final inspection with the customer can be scheduled. Correct any items noted on the Pre-Final inspection in a timely manner. These inspections and any deficiency corrections required by this paragraph need to be accomplished within the time slated for completion of the entire work or any particular increment of the work if the project is divided into increments by separate completion dates. If the Quality Control Manager will not be on site, this phase can be completed by the on-site Site Manager or Site Supervisor with coordination and input from the Quality Control Manager.

3.7.3 Final Acceptance Inspection

The Contractor's Quality Control Inspection personnel, other QC staff or other primary management person, and Government representative are required to be in attendance at the final acceptance inspection. If the Quality Control Manager will not be on site per the cost/complexity matrix, this phase can be completed by the on-site Site Manager or Site Supervisor with coordination and input from the Quality Control Manager.

3.7.4 Quality Control Audits

The primary purpose of Contractor Quality Control is to ensure compliance with the requirements of the contract. Contractor's Quality Control (CQC) Audits are a tool used to determine whether contractors QC policies and procedures are actually resulting in contract compliant work being delivered at the sites. The CQC Audit is a comprehensive site-specific review of the entire scope of the contractor's effort. The emphasis of the CQC Audit is to identify shortfalls and develop corrective policies and procedures to be implemented in the Contractor's Quality Control Program.

The CQC Audit will be conducted by the Quality Control Manager or a qualified designee a minimum once annually. The CQC audit is required for each site under this Contract and all costs (including travel costs) associated with this requirement must be included in the firm fixed price portion of the contract. The CQC audit must occur during performance of a quarterly, semi-annual, or annual PM event as a means to evaluate the performance of PM tasks under this contract.

The contractor must include the anticipated CQC Audit dates as part of the Preventive Maintenance Schedule. Additionally, upcoming CQC Audits must be identified in the contractor's three week look ahead schedule.

Travel costs associated with corrective actions of unsatisfactorily or incomplete work from the QC Audit will be performed at no cost to the Government.

Some factors to consider as part of an effective CQC Audit include but are

not limited to the following:

Audit of PM Site Visits

- a. The CQC Audit will evaluate whether the PM visits are being conducted and reported in accordance with the contract.
- b. All components at the site identified and found in the Site Inventory and FMP.
- c. All of the PM actions and inspections as defined by the FMP for each component being performed and documented in the PM Reports.
- d. All deficiencies at the site are being identified and reported and are based on actual UFC, API, or other regulatory codes and standards.
- e. Firm Fixed price repairs are being performed and tracked as per the contract.
- f. Safety, Environmental, and Base requirements are in compliance.

Audit of Service Orders

- a. The CQC Audit will evaluate whether the previous 12 months of Service Orders completed or in process for the site are being prepared and executed in accordance with the contract.
- b. Service Orders include product data for all materials and supplies that will be or were used on the project.
- c. Service Orders document action taken at the site and end results, including troubleshooting issues found.
- d. Service Orders that include return trips for wrong parts, insufficient tools/equipment, or other issues that indicate planning shortfalls are addressed.
- e. Service Orders are being reviewed by the contractors Project Engineer.
- f. Emergency and NTE Service Order actual labor hours and materials costs are being itemized and charged at contract rates.
- g. Travel expenses are being charged and documented in compliance with the JTR.
- h. Safety, Environmental, and Base requirements are in compliance.

Policies and Procedures

The CQC Audit Report will include a summary of issues identified and a discussion of corrective actions that will be made to policy and/or procedures to improve contract compliance. A sample QC Audit Report can be found enclosed at the end of this section (Attachment 2) but should not alleviate items specified above.

Upon completion of the Quality Control Audit site visit, the Quality Control Manager must submit the Quality Control Audit Report to HNC in RMS no later than 20 calendar days after completing the QC Audit. The interval between annual audits at each site must be between 180 and 375 calendar

days.

3.8 DOCUMENTATION

3.8.1 Quality Control Activities

Maintain current records providing factual evidence that required quality control activities and tests have been performed. These records must be provided to the government by inputting daily QC reports into the USACE Resident Management System (RMS) Quality Module (QM). All sites may be submitted as a single report with individual packages to include attachments. Weekly submission of records or as approved by the Contractor Officer is acceptable, except for emergency repairs. Include in these records the work of subcontractors and suppliers on an acceptable form that includes, as a minimum, the following information:

- a. The name and area of responsibility of the Contractor/Subcontractor.
- b. Operating plant/equipment with hours worked, idle, or down for repair.
- c. Work performed each day, giving location, description, and by whom.
- d. Test and control activities performed with results and references to specifications/drawings requirements. Identify the control phase (Preparatory, Initial, Follow-up). List of deficiencies noted, along with corrective action.
- e. Quantity of materials received at the site with statement as to acceptability, storage, and reference to specifications/drawings requirements.
- f. Submittals and deliverables reviewed, with Contract reference, by whom, and action taken.
- g. Offsite surveillance activities, including actions taken.
- h. Job safety evaluations stating what was checked, results, and instructions or corrective actions.
- i. Instructions given/received and conflicts in plans and specifications.
- j. Checklists and other documentation required which document procedures, checks, and operating parameters for site personnel performing Preventive Maintenance tasks.
- k. Provide documentation of Engineering or Technical quality control activities. For independent reviews, provide, as a minimum, identification of the Independent Technical Review (ITR) team, the ITR review comments, responses and the record of resolution of the comments
- l. Schedule or scope deviations

3.8.2 Verification Statement

Indicate a description of trades working on the project; the number of personnel working; weather conditions encountered; and any delays encountered. Cover both conforming and deficient features and include a statement that equipment and materials incorporated in the work and workmanship comply with the Contract. Furnish the original and one copy of

these records in report form to the Government daily within 24 hours after the date covered by the report, except that reports need not be submitted for days on which no work is performed. As a minimum, prepare and submit one report for every 7 days of no work and on the last day of a no work period. All calendar days need to be accounted for throughout the life of the contract. The first report following a day of no work will be for that day only. Reports need to be signed and dated by the Quality Control Manager. Include copies of test reports and copies of reports prepared by all subordinate quality control personnel within the Quality Control Manager Report.

3.9 NOTIFICATION OF NONCOMPLIANCE

The Contracting Officer will notify the Contractor of any detected noncompliance with the foregoing requirements. Take immediate corrective action after receipt of such notice. Such notice, when delivered to the Contractor at the work site, will be deemed sufficient for the purpose of notification. If the Contractor fails or refuses to comply promptly, the Contracting Officer can issue an order stopping all or part of the work until satisfactory corrective action has been taken. No part of the time lost due to such stop orders will be made the subject of claim for extension of time or for excess costs or damages by the Contractor.

-- End of Section --

APPENDIX C – CONTRACT SPECIFICATIONS

SECTION 01 45 00.00 10
QUALITY CONTROL

ATTACHMENT 1-COST/COMPLEXITY MATRIX AND LEVEL OF QC

Cost/Complexity Based CQC Requirements

TASK		Impacts			Complexity Rating
	Likelihood	Minor	Moderate	Major	
Coordination with other trades, other contractors, customer, owner/operators, or regulatory	Unlikely	0	1	3	
	Moderate	1	2	3	
	Likely	2	3	3	
Technical complexity of equipment being serviced.	Unlikely	0	1	3	
	Moderate	1	2	3	
	Likely	2	3	3	
Required fuel system outages or outages of supporting utilities	Unlikely	0	1	3	
	Moderate	1	2	3	
	Likely	2	3	3	
Level of unknowns or undefined conditions	Unlikely	0	1	3	
	Moderate	1	2	3	
	Likely	2	3	3	
Logistical difficulty accessing the site or obtaining materials	Unlikely	0	1	3	
	Moderate	1	2	3	
	Likely	2	3	3	
OVERALL COMPLEXITY RATING	0				
Low = 1-5					
Moderate = 6-10					
High = 11-15					

Level of QC Responsibility

Required Oversight	Low (1-5) or <\$25k	Mod. (6-10) or \$25k to <\$250k	High (11-15) or ≥\$250k
QC by senior member of staff performing activity (Lead tech, senior electrician, etc.).	Yes	Yes	Yes
CQC by Site Manager or Site Supervisor	Yes	Yes	Yes
CQC by contract designated Contractor Quality Control Manager (Quality Control Manager may be requested for moderate complexity Service Orders at the request of the Government)	No	No	Yes

SECTION 01 45 00.00 10
QUALITY CONTROL

Attachment 2-SAMPLE QC AUDIT

Recurring Maintenance Quality Control Audit

conducted for

HUN

Site Name in this block.

Huntsville ANG, AL

Contract No.: W912DY-13-G-0004-XXXX

Completed on

14 Jan 2017, 10:06 AM

Score

51/65 - 78.46%

Table of Contents

RECURRING MAINTENANCE QUALITY CONTROL AUDIT - 51/65 - 78.46%	1
1.0 SITE INFORMATION	5
1.0 Site Information	5
2.0 BLUF	6
2.0 Bottom Line Up Front (BLUF) - Give a brief overview of the status of the facility and the sub-contractor	6
3.0 PM DOCUMENTATION - 21/25 - 84%	7
All documentation that requires EMPLOYEE REVIEW AND SIGNATURE or that may be REVISED is required to be LOCATED ON-SITE. Documentation that is required to be available for employee reference may be accessed electronically.	7
3.0 PM DOCUMENTATION	7
3.1 Quality Control Documentation When Sub-Contractor is On-site	7
3.2 Sub-Contractor's Health and Safety Program and Documentation available to employees?	7
3.3 Sub-Contractor's Recurring Maintenance Activities	
3.4 Are calibration tags affixed to required equipment? (Tags should be legible and show calibration date and name of company that performed the calibration.)	9 11
3.5 Housekeeping	
13	
4.0 PM QUARTERLY	14
4.0 PM QUARTERLY REQUIREMENTS	14
4.1 Exposed piping condition	14
4.2 System components	14
4.3 Pumps	14
4.4 Valves	14
4.5 Above Ground Storage Tanks	14
4.6 Railcar Off-load Spur	15
4.7 Below ground storage tanks	15
4.8 Swivels and Swing Joints	15
4.9 Ground cables	15
4.10 Disconnect Switches	15
4.11 Surge Arrestors	15
4.12 Class (Type) III Systems	16
4.13 Gaskets	16
4.14 Filter Separators	16

4.15	Micronics	16
4.16	Cathodic Protection	16
4.17	Dikes (Areas around bulk tanks).	16
4.18	AFSS, ATG and Control Panels.	16
4.19	Product Recovery Pump (PRP) Testing	16
4.20	Hydrant System Pressure Locking Nozzles (SPR).	17
4.21	Proper product identification. (i.e., MIL-STD-161, NFPA, NATO, etc)	17
4.22	Lighting	17
4.23	Security	17
4.24	Containment (Loading/unloading areas, refueler truck parking, etc.)	17
5.0	PM SEMI-ANNUAL	18
5.0	SEMI-ANNUAL REQUIREMENTS	18
5.1	Vacuum and Pressure Vents	18
5.2	Liquid Level Gauges, Low Levels	18
5.3	High Level Control Valves and Alarms	18
5.4	Dispensers	18
5.5	Flow Meters	18
6.0	PM ANNUAL - 35/41 - 85.37%	19
6.0	PM ANNUAL INSPECTION	19
6.1	Tank Gauges	19
6.2	Containment Systems	19
6.3	Starters and Contactors	20
6.4	Wiring and Fuse Boxes	20
6.5	Grounding Conductors.	20
6.6	Flow meters	20
6.7	Overfill Protection	21
6.8	Dispenser Calibration	21
6.9	Vapor Recovery System	21
6.10	Pressure Gauges	21
6.11	Pressure Relief Valve and Shear Valve	22
6.12	Static Ground Rods	23
6.13	Hoses (Fuel Loading hoses with pressures greater than 20 PSI.)	23
6.14	Back-up Power Generators	23
6.15	Hydrant Fuel System Control Valves	23
6.16	Hydrant Fuel System Pantographs attached to the fuel system.	23
		24

6.17 Fire Protection Systems	24
6.18 Oil Water Separators	24
6.19 Emergency Eyewash and Shower	24
6.20 Air Compressor	24
6.21 Fuel Laboratory Fume Hood	24
MEDIA	26

1.0 Site Information

Question	Response	Details
1.0 Site Information		
1.1.a Date of QC audit	10 Jan 2017	
1.2 Auditor	XXXXXXXX, QCM	
1.3 FMSR and alternate name.	TSgt Jeremy Ball, TSgt Sam Smith	
1.4 Sub-contractor responsible for this location	XXXX	
1.5 Was an audit out-brief given to the FMSR?	Yes	

2.0 BLUF

Question	Response	Details
2.0 Bottom Line Up Front (BLUF) - Give a brief overview of the status of the facility and the sub-contractor		
		We sat down with the primary and alternate FMSR's to discuss the program and site support XXXXX and XXXXX provides. The primary FMSR (TSgt Ball) observes the operation and has TSgt Smith take the lead requesting repairs, SO SOW accuracy, work completed and overseeing the PM efforts. He stated that he will likely be placed in the primary role as TSgt Ball will be retiring later this year. This location only has an annual PM effort conducted. This limits the number of visits for the subcontractor to have access to performing Preventive Maintenance like other locations that have the full PM effort. The sub-contractor was not on site during this QC effort. The TO PM was on site during the annual PM effort conducted in August 2016. The receiving area of the bulk facility is scheduled for a large SRM project the will encompass repairing/replacing fillstands, off-loading, building canopies, etc. The FMSR limits the repairs to this area to "as needed" to maintain operation and safety but not findings that should be completed for long term repairs due to the project. The hydrant pump and F/S pad is in good condition. We identified several findings of PM checklist items that had deficiencies that will be identified later in this audit. They were reported to the PM and action was taken. We returned on Thursday as we were still traveling in the local area to review actions to confirm they were completed. The PM report had a conflict with findings identified for repair and what was actually reported. This was identified to the PM manager and the PM to correct. They are working to prevent this from happening in the future. TSgt Ball and XXXXX's TO PM are currently reviewing the PM report for accuracy.

3.0 PM Documentation - 19/25 - 76% - 19/25 - 76%

Question	Response	Details
All documentation that requires EMPLOYEE REVIEW AND SIGNATURE or that may be REVISED is required to be LOCATED ON-SITE. Documentation that is required to be available for employee reference may be accessed electronically.		
3.0 PM DOCUMENTATION		Score (19/25) 76%
3.1 Quality Control Documentation When Sub-Contractor is On-site		Score (4/4) 100%
3.1.1 Quality Control Plan (QCP)	N/A	The sub-contractor was not on site to review required paperwork that would accompany them during onsite visits and to observe actual checklist items being performed.
3.1.2 Are QC inspections performed by the sub-contractor?	Yes	XXXXX reports are conducted by the site supervisors during SO repairs and PM efforts.
Appendix 1		
3.1.3 Daily Production & Quality Control Report up-to-date and completed and are deficiencies reconciled?	Yes	
3.1.4 Contractor Quality Control Report up-to-date and completed prior to sub-contractor leaving the site?	Yes	
3.1.5 Before and After Photos.	Yes	
3.1.6 Are all permits available?	N/A	
3.2 Sub-Contractor's Health and Safety Program and Documentation available to employees?		Score (1/1) 100%
3.2.1 Does the name of the SSHO/Qualified Competent person/Site Supervisor on the DPSHC match the onsite person.	N/A	The sub-contractor was not on site to review required paperwork that would accompany them during onsite visits and to observe actual checklist items being performed.

Question	Response	Details
3.2.2 EM 385-1-1	N/A	The sub-contractor was not on site to review required paperwork that would accompany them during onsite visits and to observe actual checklist items being performed.
3.2.3 Visitor and Authorized Entrant Log?	N/A	The sub-contractor was not on site to review required paperwork that would accompany them during onsite visits and to observe actual checklist items being performed.
3.2.4 Emergency and Evacuation Information?	N/A	The sub-contractor was not on site to review required paperwork that would accompany them during onsite visits and to observe actual checklist items being performed.
3.2.5 Overarching Accident Prevention Plan (OAPP) and Form 7?	N/A	The sub-contractor was not on site to review required paperwork that would accompany them during onsite visits and to observe actual checklist items being performed.
3.2.6 Task Specific Activity Hazard Analysis (AHA) and Form 7?	N/A	The sub-contractor was not on site to review required paperwork that would accompany them during onsite visits and to observe actual checklist items being performed.
3.2.7 Site Specific HAZCOM Program (All containers marked and a list of chemical inventory with supporting SDS available)?	N/A	The sub-contractor was not on site to review required paperwork that would accompany them during onsite visits and to observe actual checklist items being performed.
3.2.8 Site Specific Accident Prevention Plan (SSAPP) , and Indoctrination Signatures?	N/A	The sub-contractor was not on site to review required paperwork that would accompany them during onsite visits and to observe actual checklist items being performed.
3.2.9 Operators Certifications (MUST BE CURRENT)?	N/A	The sub-contractor was not on site to review required paperwork that would accompany them during onsite visits and to observe actual checklist items being performed.

Question	Response	Details
3.2.10 Medical Certificates (MUST BE UP TO DATE)?	N/A	The sub-contractor was not on site to review required paperwork that would accompany them during onsite visits and to observe actual checklist items being performed.
3.2.11 Are all hazardous and non-hazardous energy controls in place during inspection of certain PM steps (LOTO for electrical and/or mechanical devices)?	N/A	The sub-contractor was not on site to review required paperwork that would accompany them during onsite visits and to observe actual checklist items being performed.
3.2.12 Federal Labor Laws Postings?	N/A	The sub-contractor was not on site to review required paperwork that would accompany them during onsite visits and to observe actual checklist items being performed.
3.2.13 Sub-contractor Company Specific OSHA 300A Log?	N/A	The sub-contractor was not on site to review required paperwork that would accompany them during onsite visits and to observe actual checklist items being performed.
3.2.14 Initial and Daily Equipment Inspections?	N/A	The sub-contractor was not on site to review required paperwork that would accompany them during onsite visits and to observe actual checklist items being performed.
3.2.15 Site Specific Safety and Health Deficiency List?	N/A	The sub-contractor was not on site to review required paperwork that would accompany them during onsite visits and to observe actual checklist items being performed.
3.2.16 Daily Tailgate Safety Meeting?	Yes	These are tracked with the XXXXX reports that are filed with XXXXX.
3.3 Sub-Contractor's Recurring Maintenance Activities		Score (10/12) 83.3%
3.3.1 Contractor on-site Maintenance activity log up to date?	Yes	
3.3.2 Are there any visible weeps or leaks?	Yes	

Question	Response	Details
3.3.2.a Has the deficiency been identified and reported to the FMSR and documented on the PM report?	Yes	There was a weep in the hydrant pump pad area that the FMSR identified. This was not a finding during the July annual as there was not a weep at that time. The FMSR stated that there are several weeps that only develop during drastic temperature swings like the past few days. He has not reported it as he knows from experience that these will stop weeping when the temperature returns to normal.
3.3.3 Are there any areas that need corrosion control repairs?	Yes	
3.3.3.a Is the deficiency identified on the PM report or has a SO been generated?	Yes	Corrosion control is not an annual requirement. This is under quarterly requirements. Paint complete has been identified mainly in the receipt area which will be covered under the large repair project.
 Appendix 2 Appendi 3		
3.3.4 Are there any areas with rips, cuts or tears to rubberized containment structures?	N/A	
3.3.5 Are there any locations where dissimilar metals come into contact?	No	
3.3.6 Are there any locations where piping is not protected from friction at supports?	No	
3.3.7 Are emergency stop devices installed and clearly labeled?	Yes	
3.3.8 Are emergency eyewash and shower available for operating staff?	Yes	Several showers were leaking from the recent cold snap and the FMSR knows they exist. I mentioned to him that these are covered under the program and can be repaired. He went further to say that this happens every year and they will repair the leaks internally as that is his job.

Question	Response	Details
3.3.9 Are all tanks labeled with product and facility number as outlined in MIL-STD-161?	Yes	The Jet Fuel Jet A markings on the tanks are poorly done and Estes is currently working to correct this workmanship issue. They are having issues with the swing in temperatures and condensation forming on the outside of the tanks preventing completing the job. This should be done in the next week or two depending on winter weather conditions.
  Appendix 4 Appendix 5		
3.3.10 Are all piping labeled with product and directional arrows as outlined per MIL-STD-161?	Yes	
3.3.11 Required PPE (i.e., Hard hat, high visibility outer garment, safety glasses)?	N/A	The sub-contractor was not on site to review required paperwork that would accompany them during onsite visits and to observe actual checklist items being performed.
3.3.12 Proper PPE for the specific job (i.e., welding gear, face shield, leather gloves, etc)?	N/A	The sub-contractor was not on site to review required paperwork that would accompany them during onsite visits and to observe actual checklist items being performed.
3.3.13 Did the contractor complete all required maintenance activities?	Yes	
3.4 Are calibration tags affixed to required equipment? (Tags should be legible and show calibration date and name of company that performed the calibration.) Score (3/7) 42.86%		
3.4.1 Pressure gauges have current stickers?	No	

Question	Response	Details
3.4.1.a Did the sub-contractor apply a current sticker before leaving the site?	No	We identified multiple gauges that did not have the correct dates punched on the sticker. They did perform the required calibration and documented it on the PM report, but when the sticker was applied, the incorrect year was punched. This was identified to the PM and he worked with the sub-contractor to correct. (Later note added: on our return inspection on Thursday, these stickers were replaced with the correct dates.)
 Appendix 6 Appendix 7		
3.4.2 Bulk loading/off-loading meters. Annually (Every 6 months for Navy and Marine Corp locations.)	Yes	
3.4.3 Ground product dispensers calibrated and product identified on each?	Yes	
3.4.4 Pressure Relief Valves/Thermal Relief Valves (PRV/TRV) tested and recorded?	No	

Question	Response	Details
3.4.4.a Did the sub-contractor apply a current sticker or performed all required testing and documentation before leaving the site?	No	The PRVs through this facility had all testing and documentation performed however, the stickers that were applied had the wrong year punched out. This was identified to the PM and he is working to have the correct year changed. (Later note added: on our return inspection on Thursday, these stickers were replaced with the correct dates.)
Appendix 8 Appendix 9		
3.4.5 Are all filter separator (F/S) vessels marked with date of next required filter change?	Yes	
3.4.6 Are hydrostatic hose tests performed and identified on the hose or coupler (hoses over 20 PSI shall be tested annually)?	N/A	No hoses to test at this location.
3.4.7 Are 2" white bands painted on each end of the pressure tested hose by the couples to show slippage and a date when the test was performed?	N/A	
3.6 Housekeeping		Score (1/1) 100%
3.6.1 Does the sub-contractor practice good housekeeping during normal work hours (this includes policing the designated smoking areas if used)?	N/A	The sub-contractor was not on site to review required paperwork that would accompany them during onsite visits and to observe actual checklist items being performed.
3.6.2 When work is completed	Yes	

4.0 PM Quarterly

Question	Response	Details
4.0 PM QUARTERLY REQUIREMENTS		
4.1 Exposed piping condition		
Corrosion Control	1	
Examples		
Pictures of corrosion if any.		
4.2 System components		
4.2.1 Has the sub-contractor been performing this checklist item?	N/A	This section was not completed as this location only receives an annual PM effort.
4.2.2 Are there any visible leaks or weeps when the system is under pressure? (start system and check packing glands, gaskets, seals, etc for leaks, weeps)	N/A	
4.3 Pumps		
4.3.1 Has the sub-contractor been performing this checklist item?	N/A	
4.3.2 Run pumps and check for unusual noises, vibration, etc	N/A	
4.4 Valves		
4.4.1 Has the sub-contractor been performing this checklist item?	N/A	
4.4.2 Are there any visible leaks, drips, seeps?	N/A	
4.4.3 Proper operation of components (Binding, moves freely, etc)	N/A	
4.5 Above Ground Storage Tanks		
4.5.1 Has the sub-contractor been performing this checklist item?	N/A	
4.5.2 Check ground connections for wear, loose, etc	N/A	

Question	Response	Details
4.5.3 Check for leaks, corrosion, etc	N/A	
4.6 Railcar Off-load Spur		
4.6.1 Has the sub-contractor been performing this checklist item?	N/A	
4.6.2 Visually inspect rail joint bonding to ensure jumpers are intact at each joint.	N/A	
4.7 Below ground storage tanks		
4.7.1 Has the sub-contractor been performing this checklist item?	N/A	
4.7.2 Visually check tank domes, manways, associated piping and valves for leaks, corrosion, condition of valves, etc.	N/A	
4.8 Swivels and Swing Joints		
4.8.1 Has the sub-contractor been performing this checklist item?	N/A	
4.8.2 Check for proper operation. Inspect for leaks. Do not grease. If leaking, replace with non-lube components.	N/A	
4.9 Ground cables		
4.9.1 Has the sub-contractor been performing this checklist item?	N/A	
4.9.2 Corrosion, clamps, loose, proper size, etc.	N/A	
4.10 Disconnect Switches		
4.10.1 Has the sub-contractor been performing this checklist item?	N/A	
4.10.2 Are sub-contractors opening and inspecting the disconnect switches for ease of operation, cables, corrosion, box seals, etc.	N/A	
4.11 Surge Arrestors		
4.11.1 Has the sub-contractor been performing this checklist item?	N/A	

Question	Response	Details
4.11.2 Drained, pressure checked.	N/A	
4.12 Class (Type) III Systems		
4.12.1 Has the sub-contractor been performing this checklist item?	N/A	
4.12.2 System inspected and maintained according to requirements.	N/A	
4.13 Gaskets		
4.13.1 Has the sub-contractor been performing this checklist item?	N/A	
4.13.2 Leaks, dry rotted, deteriorated, etc.	N/A	
4.14 Filter Separators		
4.14.1 Has the sub-contractor been performing this checklist item?	N/A	
4.14.2 Filter change dates (Month and year due), Water drains, Water Slug valves, etc.	N/A	
4.15 Micronics		
4.15.1 Have filters been removed and vessel marked "Filters removed"?	N/A	
4.16 Cathodic Protection		
4.16.1 Performed by local operations or by CMP.		
4.17 Dikes (Areas around bulk tanks).		
4.17.1 Has the sub-contractor been performing this checklist item?	N/A	
4.17.2 Cracks and seams are in good condition. (vegetation, missing, etc.,).	N/A	
4.18 AFSS, ATG and Control Panels.		
4.18.1 Report any deficiencies to the FMSR.		
4.19 Product Recovery Pump (PRP) Testing		

Question	Response	Details
4.19.1 Has the sub-contractor been performing this checklist item?	N/A	
4.19.2 Are PRP tested for proper operation, noises, leaks, etc.	N/A	
4.20 Hydrant System Pressure Locking Nozzles (SPR).		
4.20.1 Has the sub-contractor been performing this checklist item?	N/A	
4.20.2 Gaskets, handles, nose seals, bumpers, leaks.	N/A	
4.21 Proper product identification. (i.e., MIL-STD-161, NFPA, NATO, etc)		
4.21.1 Has the sub-contractor been performing this checklist item?	N/A	
4.21.2 Tanks	N/A	
4.21.3 Piping	N/A	
4.22 Lighting		
4.22.1 Has the sub-contractor been performing this checklist item?	N/A	
4.22.2 Perimeter, canopy, interior lighting	N/A	
4.23 Security		
4.23.1 Has the sub-contractor been performing this checklist item?	N/A	
4.23.2 Fence, gates, etc.	N/A	
4.24 Containment (Loading/unloading areas, refueler truck parking, etc.)		
4.24.1 Has the sub-contractor been performing this checklist item?	N/A	
4.24.2 Sealant in good condition, no vegetation, etc.	N/A	

5.0 PM Semi-Annual

Question	Response	Details
5.0 SEMI-ANNUAL REQUIREMENTS		
5.1 Vacuum and Pressure Vents		
5.1.1 Has the sub-contractor been performing this checklist item?	N/A	This section was not completed as this location only receives an annual effort.
5.1.2 Inspected, cleaned, repaired.	N/A	
5.2 Liquid Level Gauges, Low Levels		
5.2.1 Has the sub-contractor been performing this checklist item?	N/A	
5.2.2 Broken face plates, moisture in gauges, etc.	N/A	
5.3 High Level Control Valves and Alarms		
5.3.1 Has the sub-contractor been performing this checklist item?	N/A	
5.3.2 Maintained and tested, housing for electrical devices are grounded.	N/A	
5.4 Dispensers		
5.4.1 Has the sub-contractor been performing this checklist item?	N/A	
5.4.2 Pulleys, belts, meters, hoses, nozzles, breakaways, swivels, expiration dates, etc.	N/A	
5.5 Flow Meters		
5.5.1 Has the sub-contractor been performing this checklist item?	N/A	
5.5.2 Navy and Marine Corp flow meters will be inspected, calibrated and labeled semi-annually.	N/A	

6.0 PM Annual - 34/41 - 80.95%

Question	Response	Details
6.0 PM ANNUAL INSPECTION		Score (34/41) 80.95%
6.1 Tank Gauges		Score (2/2) 100%
6.1.1 Has the sub-contractor been performing this checklist item?	Yes	
6.1.2 Moisture, gauge wheel, accuracy, maintain calibration records.	Satisfactory	
6.2 Containment Systems		Score (3/5) 60%
6.2.1 Has the sub-contractor been performing this checklist item?	Yes	
6.2.2 AST Dikes - Visual inspections for earthen erosion, cracks in concrete, seals, rips in rubber containment, etc.	Unsatisfactory	
6.2.2.a Has the deficiency been identified and documented on the PM report or SO generated?	Yes	Cracks in dike area have been reported on the PM report. Most of these deficiency in cracks are in the receiving area. PM is working to move on these.
 Appendix 10  Appendix 11		
6.2.3 Truck loading and unloading, Refueler parking, pumphouse, etc.	Unsatisfactory	
6.2.3.a Has the deficiency been identified and documented on the PM report or SO generated?	Yes	Cracks and joints have been identified on the PM report. These are being worked by the PM.
 Appendix 12		

Question	Response	Details
6.3 Starters and Contactors		Score (2/2) 100%
6.3.1 Has the sub-contractor been performing this checklist item?	Yes	
6.3.2 Discoloration, pitting, motor brushes, etc.	Satisfactory	
6.4 Wiring and Fuse Boxes		Score (1/3) 33.33%
6.4.1 Has the sub-contractor been performing this checklist item?	Yes	
6.4.2 Exposed wires, conduits, fuse boxes, emergency shutoffs for condition.	Unsatisfactory	
6.4.2.a Has the deficiency been identified and documented on the PM report or SO generated?	No	This electrical connection supports the cathodic protection which is covered under a separate CMP. This should still be identified and the FMSR should contact the help center. I did identify this to TSgt Bell and he said he would report this. I also explained that they should be scheduling an annual cathodic protection inspection done which is covered under that other CMP and he didn't know this.
  Appendix 13 Appendix 14		
6.5 Grounding Conductors.		Score (2/2) 100%
6.5.1 Has the sub-contractor been performing this checklist item?	Yes	
6.5.2 Ground points tested and recorded.	Satisfactory	
6.6 Flow meters		Score (2/2) 100%
6.6.1 Has the sub-contractor been performing this checklist item?	Yes	
6.6.2 Calibrated, recorded and labelled correctly (Month, Day, Year).	Satisfactory	

Question	Response	Details
6.7 Overfill Protection		Score (2/2) 100%
6.7.1 Has the sub-contractor been performing this checklist item?	Yes	
6.7.2 Tested annually	Satisfactory	
6.8 Dispenser Calibration		Score (2/2) 100%
6.8.1 Has the sub-contractor been performing this checklist item?	Yes	
6.8.2 Calibrated, recorded and labelled correctly (Month, Day, Year).	Satisfactory	
6.9 Vapor Recovery System		
6.9.1 Has the sub-contractor been performing this checklist item?	N/A	
6.9.2 Proper operation and configuration.	N/A	
6.10 Pressure Gauges		Score (1/3) 33.33%
6.10.1 Has the sub-contractor been performing this checklist item?	Yes	
6.10.2 Tested, calibrated, recorded and labeled correctly (Month, Day, Year).	Unsatisfactory	

Question	Response	Details
6.10.2.a Has the deficiency been identified on the PM report and/or corrected prior to the sub-Contractor leaving the site?	No	We identified multiple gauges that did not have the correct dates punched on the sticker. They did perform the required calibration and documented it on the PM report, but when the sticker was applied, the incorrect year was punched. This was identified to the PM and he worked with the sub-contractor to correct. (Later note added: on our return inspection on Thursday, these stickers were replaced with the correct dates.)
 Appendix 15 Appendix 16 Appendix 17		
6.11 Pressure Relief Valve and Shear Valve		Score (1/3) 33.33%
6.11.1 Has the sub-contractor been performing this checklist item?	Yes	
6.11.2 Tested, calibrated and recorded correctly (PRV/TRV do not require labeling per the PWS. Some subs apply a sticker. If one sticker is applied, then all must have them).	Unsatisfactory	

Question	Response	Details
6.11.2.a Has the deficiency been identified on the PM report and/or corrected prior to the sub-Contractor leaving the site?	No	The PRVs throughout this facility had all testing and documentation performed however, 2/3 of the stickers that were applied had the wrong year punched out. This was identified to the PM and he is working to have the correct year changed. (Later note added: on our return inspection on Thursday, these stickers were replaced with the correct dates.)
Appendix 18 Appendix 19		
6.12 Static Ground Rods		Score (2/2) 100%
6.12.1 Has the sub-contractor been performing this checklist item?	Yes	
6.12.2 Tested and recorded.	Satisfactory	
6.13 Hoses (Fuel Loading hoses with pressures greater than 20 PSI.)		
6.13.1 Has the sub-contractor been performing this checklist item?	N/A	
6.13.2 Hydrostatic tested, test date marked on hose, 2" wide white band painted at each hose/coupler connection, and recorded.	N/A	
6.14 Back-up Power Generators		Score (2/2) 100%
6.14.1 Has the sub-contractor been performing this checklist item?	Yes	
6.14.2 Inspected annually. Maintenance will be performed under a SO.	Satisfactory	
6.15 Hydrant Fuel System Control Valves		Score (2/2) 100%
6.15.1 Has the sub-contractor been performing this checklist item?	Yes	

Question	Response	Details
6.15.2 Automatic control valves will be inspected and tested.	Satisfactory	
6.16 Hydrant Fuel System Pantographs attached to the fuel system.		Score (2/2) 100%
6.16.1 Has the sub-contractor been performing this checklist item?	Yes	
6.16.2 Inspected and tested for proper operation and leaks?	Satisfactory	
6.17 Fire Protection Systems		Score (1/1) 100%
6.17.1 Has the sub-contractor been performing this checklist item?	Yes	
6.17.2 Inspected for anomalies. Discrepancies will be reported to the Fire Chief and COR.	Satisfactory	
6.18 Oil Water Separators		Score (2/2) 100%
6.18.1 Has the sub-contractor been performing this checklist item?	Yes	
6.18.2 OWS will be Inspected annually for sludge and debris . Cleaning and repairs will require SO.	Satisfactory	
6.19 Emergency Eyewash and Shower		Score (2/2) 100%
6.19.1 Has the sub-contractor been performing this checklist item?	Yes	
6.19.2 Inspected and tested.	Satisfactory	There were multiple showers that were leaking due to the recent cold weather snap. The FMSR has identified these and will repair. They were not leaking during the annual PM effort.
6.20 Air Compressor		
6.20.1 Has the sub-contractor been performing this checklist item?	N/A	
6.20.2 Inspected for proper operation and leaks?	N/A	
6.21 Fuel Laboratory Fume Hood		Score (2/2) 100%

Question	Response	Details
6.21.1 Has the sub-contractor been performing this checklist item?	Yes	
6.21.2 Inspected, tested, recorded and labeled. Maintenance will be completed with a service order.	Satisfactory	

Media



Appendix 1

Appendix 2



Appendix 3

Appendix 4



Appendix 5



Appendix 6

Appendix 7

Appendix 8



Appendix 9

Appendix 10



Appendix 11



Appendix 12



Appendix 13



Appendix 14



Appendix 15

Appendix 16

Appendix 17

Appendix 18

Appendix 19

SECTION 01 45 00.15 10

RESIDENT MANAGEMENT SYSTEM CONTRACTOR MODE (RMS CM)

11/16, CHG 2: 08/19

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this section to the extent referenced. The publications are referred to within the text by the basic designation only.

U.S. ARMY CORPS OF ENGINEERS (USACE)

EM 385-1-1 (2024) Safety and Occupational Health Requirements

1.2 MEASUREMENT AND PAYMENT

The work of this section is not measured for payment. The Contractor is responsible for the work of this section, without any direct compensation other than the payment received for contract items.

1.3 CONTRACT ADMINISTRATION

The Government will use the Resident Management System (RMS) to assist in its monitoring and administration of this contract. The Government accesses the system using the Government Mode of RMS (RMS GM) and the Contractor accesses the system using the Contractor Mode (RMS CM). The term RMS will be used in the remainder of this section for both RMS GM and RMS CM. The joint Government-Contractor use of RMS facilitates electronic exchange of information and overall management of the contract. The Contractor accesses RMS to record, maintain, input, track, and electronically share information with the Government throughout the contract period in the following areas:

Administration

Finances

Quality Control

Submittal Monitoring

Scheduling

Closeout

Import/Export of Data

1.3.1 Correspondence and Electronic Communications

For ease and speed of communications, exchange correspondence and other documents in electronic format to the maximum extent feasible. Some correspondence, including pay requests and payrolls, are also to be provided in paper format with original signatures. Paper documents will

govern, in the event of discrepancy with the electronic version.

1.3.2 Other Factors

Other portions of this document have a direct relationship to the reporting accomplished through RMS. Particular attention is directed to FAR [requirements per the PWS](#); Section 01 33 00 SUBMITTAL PROCEDURES; Section 01 35 26 GOVERNMENTAL SAFETY REQUIREMENTS; and Section 01 45 00.00 10 QUALITY CONTROL.

1.4 RMS SOFTWARE

RMS is a web based application. Download, install and be able to utilize the latest version of RMS within 7 calendar days of receipt of the Notice to Proceed. RMS software, user manuals, access and installation instructions, program updates and training information are available from the RMS website (<https://rms.usace.army.mil>). The Government and the Contractor will have different access authorities to the same contract database through RMS. The common database will be updated automatically each time a user finalizes an entry or change.

1.5 CONTRACT DATABASE - GOVERNMENT

The Government will enter the basic contract award data in RMS prior to granting the Contractor access. The Government entries into RMS will generally be related to submittal reviews, correspondence status, and Quality Assurance (QA) comments, as well as other miscellaneous administrative information.

1.6 CONTRACT DATABASE - CONTRACTOR

Contractor entries into RMS establish, maintain, and update data throughout the duration of the contract. Contractor entries generally include prime and subcontractor information, daily reports, submittals, RFI's, schedule updates and payment requests. RMS includes the ability to import attachments and export reports in many of the modules, including submittals. The Contractor responsibilities for entries in RMS typically include the following items:

1.6.1 Administration

1.6.1.1 Contractor Information

Enter all current Contractor administrative data and information into RMS within 7 calendar days of receiving access to the contract in RMS. This includes, but is not limited to, Contractor's name, address, telephone numbers, management staff, and other required items.

1.6.1.2 Subcontractor Information

Enter all missing subcontractor administrative data and information into RMS CM within 7 calendar days of receiving access to the contract in RMS or within 7 calendar days of the signing of the subcontractor agreement for agreements signed at a later date. This includes name, trade, address, phone numbers, and other required information for all subcontractors. A subcontractor is listed separately for each trade to be performed.

1.6.1.3 Correspondence

Identify all Contractor correspondence to the Government with a serial number. Letters are numbered starting from 0001 (e.g., H-0001 or S-0001).

1.6.1.4 Reports

Track the status of the **contract requirements** utilizing the reports available in RMS. The value of these reports is reflective of the quality of the data input. These reports include the Progress Payment Request worksheet, Quality Control (QC) comments, Submittal Register Status, and Three-Phase Control worksheets.

1.6.1.5 Request For Information (RFI)

Create and track all Requests For Information (RFI) in the RMS Administration Module for Government review and response.

1.6.2 Finances

1.6.2.1 Pay Activity Data

Develop and enter a list of pay activities in conjunction with the project schedule. The sum of pay activities equals the total contract amount, including modifications. Each pay activity must be assigned to a Contract Line Item Number (CLIN). The sum of the activities assigned to a CLIN equals the amount of each CLIN.

1.6.2.2 Payment Requests

Prepare all progress payment requests using RMS. Update the work completed under the contract at least monthly, measured as percent or as specific quantities. After the update, generate a payment request and prompt payment certification using RMS. Submit the signed prompt payment certification and payment request as well as supporting data either electronically or by hard copy. Unless waived by the Contracting Officer, a signed paper copy of the approved payment certification and request is also required and will govern in the event of discrepancy with the electronic version.

1.6.3 Quality Control (QC)

Enter and track implementation of the 3-phase QC Control System, QC testing, transferred and installed property and warranties in RMS. Prepare daily reports, identify and track deficiencies, document progress of work, and support other Contractor QC requirements in RMS. Maintain all data on a daily basis. Ensure that RMS reflects all quality control methods, tests and actions contained within the Contractor Quality Control (CQC) Plan and Government review comments of same within 7 calendar days of Government acceptance of the CQC Plan.

1.6.3.1 Quality Control (QC) Reports

The Contractor's Quality Control (QC) Daily Report in RMS is the official report. The Contractor can use other supplemental formats to record QC data, but information from any supplemental formats are to be consolidated and entered into the RMS QC Daily Report. Any supplemental information may be entered into RMS as an attachment to the report. QC Daily Reports must be finalized and signed in RMS within 24 hours after the date covered by the report. Provide the Government a printed signed copy of the QC Daily

Report, unless waived by the Contracting Officer.

1.6.3.2 Deficiency Tracking.

Use the QC Daily Report Module to enter and track deficiencies. Deficiencies identified and entered into RMS by the Contractor or the Government will be sequentially numbered with a QC or QA prefix for tracking purposes. Enter each deficiency into RMS the same day that the deficiency is identified. Monitor, track and resolve all QC and QA entered deficiencies. A deficiency is not considered to be corrected until the Government indicates concurrence in RMS.

1.6.3.3 Three-Phase Control Meetings

Maintain scheduled and actual dates and times of preparatory and initial control meetings.

1.6.3.4 Labor and Equipment Hours

Enter labor and equipment exposure hours on a daily basis. Roll up the labor and equipment exposure data into a monthly exposure report.

1.6.3.5 Accident/Safety Reporting

Both the Contractor and the Government enter safety related comments in RMS as a deficiency. The Contractor must monitor, track and show resolution for safety issues in the QC Daily Report area of the RMS QC Module. In addition, follow all reporting requirements for accidents and incidents as required in [EM 385-1-1](#), Section 01 35 26 GOVERNMENTAL SAFETY REQUIREMENTS and as required by any other applicable Federal, State or local agencies.

1.6.3.6 Activity Hazard Analysis

Import activity hazard analysis electronic document files into the RMS QC Module utilizing the document package manager.

1.6.4 Submittal Management

Enter all current submittal register data and information into RMS within 7 calendar days of receiving access to the contract in RMS. The information shown on the submittal register following the specification Section 01 33 00 SUBMITTAL PROCEDURES will already be entered into the RMS database when access is granted. Group electronic submittal documents into transmittal packages to send to the Government, except very large electronic files, samples, spare parts, mock ups, color boards, or where hard copies are specifically required. Track transmittals and update the submittal register in RMS on a daily basis throughout the duration of the contract.

1.6.5 Schedule

Enter and update the contract project schedule in RMS.

1.6.6 Closeout

Closeout documents, processes and forms are managed and tracked in RMS by both the Contractor and the Government. Ensure that all closeout documents are entered, completed and documented within RMS.

1.7 IMPLEMENTATION

Use of RMS as described in the preceding paragraphs is mandatory. Ensure that sufficient resources are available to maintain contract data within the RMS system. RMS is an integral part of the Contractor's required management of quality control.

1.8 NOTIFICATION OF NONCOMPLIANCE

Take corrective action within 7 calendar days after receipt of notice of RMS non-compliance by the Contracting Officer.

PART 2 PRODUCTS

Not Used

PART 3 EXECUTION

Not Used

-- End of Section --

SECTION 01 78 23

OPERATION AND MAINTENANCE DATA

08/15, CHG 1: 11/20

PART 1 GENERAL

1.1 SUBMITTALS

Government approval is required for submittals with a "G" classification. Submittals not having a "G" classification are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-10 Operation and Maintenance Data

Operation And Maintenance Manuals; G
Maintenance And Repair Instructions; G
Maintenance Log (PM Reports); G
Facility Maintenance Plan (FMP); G
As-Built Drawings; G
Maintenance Service (schedule); G

SD-11 Closeout Submittals

Maintenance Records; G
Extended Warranty; G
Maintenance Instructions; G
Manufacturer's Guarantee; G
Manufacturer's Instructions; G
Manufacturer's Warranty; G
Operation And Maintenance Manual; G
Warranties; G

1.2 OPERATION AND MAINTENANCE DATA

PWS Appendix G maintenance requirements: The government will provide any available Operation and Maintenance (O&M) Data to the contractor after award. The contractor is responsible for providing updates to existing maintenance records based on current conditions clarifying and updating equipment, components, manufacturer information, inclusion of Component Unique Identifier (CUID), and other updates as required. The contractor shall provide O&M Data of newly installed equipment, assemblies, and subassemblies defining the importance of system interactions, troubleshooting, and long-term preventive operation and maintenance. Compile, prepare, maintain, and aggregate all existing and new O&M data.

Organize and present information in sufficient detail to clearly explain O&M requirements at the system, equipment, component, and subassembly level. Include an index preceding each submittal. Submit in accordance with this section and Section 01 33 00 SUBMITTAL PROCEDURES. Labor associated with this requirement shall be included in the FFP and contractor must identify any assumptions made, estimating methodology, and any constraints related to the material, labor, equipment, and other cost and pricing data in their Basis of Estimate (BoE).

Other DLA Capitalized equipment or systems: For Corrective Maintenance work, the contractor shall provide O&M Data of new equipment, assemblies, and subassemblies defining the importance of system interactions, troubleshooting, and long-term preventive operation and maintenance. Compile, prepare, maintain, and aggregate all new O&M data. Organize and present information in sufficient detail to clearly explain O&M requirements at the system, equipment, component, and subassembly level. Submit in accordance with this section, the PWS, and Section 01 33 00 SUBMITTAL PROCEDURES. Labor associated with this requirement shall be included in the FFP and contractor must identify any assumptions made, estimating methodology, and any constraints related to the material, labor, equipment, and other cost and pricing data in their Basis of Estimate (BoE).

1.2.1 Package Quality

Documents must be fully legible. Operation and Maintenance data must be consistent with the manufacturer's standard brochures, schematics, printed instructions, general operating procedures, and safety precautions.

1.2.2 Package Content

Provide data package content in accordance with paragraph SCHEDULE OF OPERATION AND MAINTENANCE DATA PACKAGES. Comply with the data package requirements specified in the individual technical sections, including the content of the packages and addressing each product, component, and system designated for data package submission. Provide a Data Package as specified in the individual technical section, for items that are commissioned.

1.3 OPERATION AND MAINTENANCE MANUAL FILE FORMAT

Assemble existing and new data packages into electronic Operation and Maintenance Manuals and submit as part of the Maintenance Record per the Performance Work Statement (PWS). Assemble each manual into a composite electronically indexed file using the most current version of Adobe Acrobat or similar software capable of producing PDF file format. Provide hard copies and compact disks (CD) or data digital versatile disk (DVD) as required by the PWS. Include a complete electronically linked operation and maintenance directory with table of contents.

1.4 TYPES OF INFORMATION REQUIRED IN O&M DATA PACKAGES

The following are a detailed description of the data package items listed in paragraph SCHEDULE OF OPERATION AND MAINTENANCE DATA PACKAGES.

1.4.1 Operating Instructions - New Equipment and Systems

Provide specific instructions, procedures, and illustrations for the

following phases of operation for the installed model and features of each system:

1.4.1.1 Safety Precautions and Hazards

List personnel hazards and equipment or product safety precautions for operating conditions. List all residual hazards identified in the Activity Hazard Analysis provided under Section 01 35 26 GOVERNMENT SAFETY REQUIREMENTS. Provide recommended safeguards for each identified hazard.

1.4.1.2 Operator Prestart

Provide procedures required to install, set up, and prepare each system for use.

1.4.1.3 Startup, Shutdown, and Post-Shutdown Procedures

Provide narrative description for Startup, Shutdown and Post-shutdown operating procedures including the control sequence for each procedure.

1.4.1.4 Normal Operations

Provide Control Diagrams with data to explain operation and control of systems and specific equipment. Provide narrative description of Normal Operating Procedures.

1.4.1.5 Emergency Operations

Provide Emergency Procedures for equipment malfunctions to permit a short period of continued operation or to shut down the equipment to prevent further damage to systems and equipment. Provide Emergency Shutdown Instructions for fire, explosion, spills, or other foreseeable contingencies. Provide guidance and procedures for emergency operation of utility systems including required valve positions, valve locations and zones or portions of systems controlled.

1.4.1.6 Operator Service Requirements

Provide instructions for services to be performed by the operator such as lubrication, adjustment, inspection, and recording gauge readings.

1.4.1.7 Environmental Conditions

Provide a list of Environmental Conditions (temperature, humidity, and other relevant data) that are best suited for the operation of each product, component or system. Describe conditions under which the item equipment should not be allowed to run.

1.4.1.8 Operating Log

Provide forms, sample logs, and instructions for maintaining necessary operating records.

1.4.2 Preventive Maintenance

Provide the following information for preventive and scheduled maintenance to minimize repairs for the installed model and features of each system. Include potential environmental and indoor air quality impacts of recommended maintenance procedures and materials.

1.4.2.1 Lubrication Data

Include the following preventive maintenance lubrication data, in addition to instructions for lubrication required under paragraph OPERATOR SERVICE REQUIREMENTS:

- a. A table showing recommended lubricants for specific temperature ranges and applications.
- b. Charts with a schematic diagram of the equipment showing lubrication points, recommended types and grades of lubricants, and capacities.
- c. A Lubrication Schedule showing service interval frequency.

1.4.2.2 Preventive Maintenance Plan, Schedule, and Procedures

Provide manufacturer's schedule for routine preventive maintenance, inspections, condition monitoring (predictive tests) and adjustments required to ensure proper and economical operation and to minimize repairs. Provide instructions stating when the systems should be retested. Provide manufacturer's projection of preventive maintenance work-hours on a daily, weekly, monthly, and annual basis including craft requirements by type of craft. For periodic calibrations, provide manufacturer's specified frequency and procedures for each separate operation.

- a. Define the anticipated time required to perform each of each test (work-hours), test apparatus, number of personnel identified by responsibility, and a testing validation procedure permitting the record operation capability requirements within the schedule. Provide a remarks column for the testing validation procedure referencing operating limits of time, pressure, temperature, volume, voltage, current, acceleration, velocity, alignment, calibration, adjustments, cleaning, or special system notes. Delineate procedures for preventive maintenance, inspection, adjustment, lubrication and cleaning necessary to minimize repairs.
- b. Repair requirements must inform operators how to check out, troubleshoot, repair, and replace components of the system. Include electrical and mechanical schematics and diagrams and diagnostic techniques necessary to enable operation and troubleshooting of the system after acceptance.

1.4.3 Repair

Provide manufacturer's recommended procedures and instructions for correcting problems and making repairs.

1.4.3.1 Troubleshooting Guides and Diagnostic Techniques

Provide step-by-step procedures to promptly isolate the cause of typical malfunctions. Describe clearly why the checkout is performed and what conditions are to be sought. Identify tests or inspections and test equipment required to determine whether parts and equipment may be reused or require replacement.

1.4.3.2 Wiring Diagrams and Control Diagrams

Provide point-to-point drawings of wiring and control circuits including

factory-field interfaces. Provide a complete and accurate depiction of the actual job specific wiring and control work. On diagrams, number electrical and electronic wiring and pneumatic control tubing and the terminals for each type, identically to actual installation configuration and numbering.

1.4.3.3 Repair Procedures

Provide instructions and a list of tools required to repair or restore the product or equipment to proper condition or operating standards.

1.4.3.4 Removal and Replacement Instructions

Provide step-by-step procedures and a list of required tools and supplies for removal, replacement, disassembly, and assembly of components, assemblies, subassemblies, accessories, and attachments. Provide tolerances, dimensions, settings and adjustments required. Use a combination of text and illustrations.

1.4.3.5 Spare Parts and Supply Lists

Provide lists of spare parts and supplies required for repair to ensure continued service or operation without unreasonable delays. Special consideration is required for facilities at remote locations. List spare parts and supplies that have a long lead-time to obtain.

1.4.3.6 Repair Work-Hours

Provide manufacturer's projection of repair work-hours including requirements by type of craft. Identify, and tabulate separately, repair that requires the equipment manufacturer to complete or to participate.

1.4.4 Real Property Equipment

Provide an update to the government provided component list of all installed components existing and new through the life of this contract. Include all information as identified on the Facility Maintenance Plan and submit per the PWS. If a facility, as identified in the Real Property Inventory, does not exist, is inactive, or is slated for demolition, all components associated with that Real Property Facility shall be identified on the Component Inventory as INACTIVE. If any discrepancies exist between the Real Property Inventory and Component Inventory, notify the Contracting Officer or their designated Representative.

1.4.5 Appendices

Provide information required below and information not specified in the preceding paragraphs but pertinent to the maintenance or operation of the product or equipment. Include the following:

1.4.5.1 Product Submittal Data

Provide a copy of Product Data submittals documented with the required approval. Include Service Order Number or Deficiency Number in which this product was replaced.

1.4.5.2 Certificates

Provide a copy of Certificates submittals documented with the required

approval. Include Service Order Number or Deficiency Number in which this certification was required.

1.4.5.3 Manufacturer's Instructions

Provide a copy of SD-08 Manufacturer's Instructions submittals documented with the required approval. Include Service Order Number or Deficiency Number in which these instructions apply.

1.4.5.4 O&M Submittal Data

Provide a copy of SD-10 Operation and Maintenance Data submittals documented with the required approval. Include Service Order Number or Deficiency Number in which the O&M Data applies.

1.4.5.5 Parts Identification

Provide identification for the parts of each component, assembly, subassembly, and accessory of the end items subject to replacement. Include special hardware requirements, such as requirement to use high-strength bolts and nuts. Identify parts by make, model, serial number, and source of supply to allow reordering without further identification. Provide clear and legible illustrations, drawings, and exploded views to enable easy identification of the items. When illustrations omit the part numbers and description, both the illustrations and separate listing must show the index, reference, or key number that will cross-reference the illustrated part to the listed part. Group the parts shown in the listings by components, assemblies, and subassemblies in accordance with the manufacturer's standard practice. Parts data may cover more than one model or series of equipment, components, assemblies, subassemblies, attachments, or accessories, such as typically shown in a master parts catalog. The component unique identifier (CUID) must be inserted on the upper right corner of the first page of component specific documents (manufacturer O&M requirements, cut sheets, warranty documentation, etc.)

1.4.5.6 Warranty Information

List and explain the various warranties and clearly identify the servicing and technical precautions prescribed by the manufacturers or contract documents in order to keep warranties in force. Include warranty information for primary components of the system. Provide copies of warranties required by the PWS.

1.4.5.7 Extended Warranty Information

List all warranties for products, equipment, components, and sub-components whose duration exceeds one year. For each warranty listed, indicate the applicable specification section, duration, start date, end date, and the point of contact for warranty fulfillment. Also, list or reference the specific operation and maintenance procedures that must be performed to keep the warranty valid. Provide copies of warranties required by the PWS.

1.4.5.8 Personnel Training Requirements

Provide information available from the manufacturers that is needed for use in training designated personnel to properly operate and maintain the equipment and systems.

1.4.5.9 Testing Equipment and Special Tool Information

Include information on test equipment required to perform specified tests and on special tools needed for the operation, maintenance, and repair of components. Provide final set points.

1.4.5.10 Testing and Performance Data

Include completed prefunctional checklists, functional performance test forms, and monitoring reports. Include recommended schedule for retesting and blank test forms. Provide final set points.

1.4.5.11 Field Test Reports and Manufacturer's Field Reports

Provide a copy of Field Test Reports and Manufacturer's Field Reports submittals documented with the required approval. **Include Service Order Number or Deficiency Number in which the reports apply.**

1.4.5.12 Contractor Information

Provide a list that includes the name, address, and telephone number of the General Contractor and each Subcontractor who installed the product or equipment, or system. For each item **(new or existing)**, also provide the name address and telephone number of the manufacturer's representative and service organization that can provide replacements most convenient to **each** site. Provide the name, address, and telephone number of the **existing and new** product, equipment, and system manufacturers.

1.5 SCHEDULE OF OPERATION AND MAINTENANCE DATA PACKAGES

Provide the O&M data packages **for new equipment. The component unique identifier (CUID) must be inserted on the upper right corner of the first page of component specific documents (manufacturer O&M requirements, cut sheets, warranty documentation, etc.).** The information required in each type of data package follows:

1.5.1 Data Package **requirements shall include approved Service Order Number or Deficiency Number**

- a. Safety precautions and hazards
- b. Operator prestart
- c. Startup, shutdown, and post-shutdown procedures
- d. Normal operations
- e. Emergency operations
- f. Environmental conditions
- g. Operating log
- h. Lubrication data
- i. Preventive maintenance plan, schedule, and procedures
- j. Cleaning recommendations

- k. Troubleshooting guides and diagnostic techniques
- l. Wiring diagrams and control diagrams
- m. Maintenance and repair procedures
- n. Removal and replacement instructions
- o. Spare parts and supply list
- p. Product submittal data
- q. O&M submittal data
- r. Parts identification
- s. Warranty information
- t. Extended warranty information
- u. Testing equipment and special tool information
- v. Testing and performance data
- w. Contractor information
- x. Field test reports

PART 2 PRODUCTS

Not Used

PART 3 EXECUTION

Not Used

-- End of Section --

APPENDIX D

ANTITERRORISM/OPERATIONS SECURITY COMPLIANCE

**U.S. Army Engineering and Support Center
Huntsville, AL**

SECTION 1-ANTITERRORISM/OPERATIONS SECURITY COMPLIANCE

1.0 Antiterrorism (AT) Level 1 Training (Annually)

All contractor employees, to include subcontractor employees, requiring access to installations, facilities, and controlled access areas shall complete AT Level 1 awareness training within 30 calendar days after contract start date or effective date of incorporation of this requirement into the contract, whichever is applicable. The contractor shall submit certificates of completion for each affected contractor employee and subcontractor employee to the COR (or to the contracting officer if a COR is not assigned) within 5 calendar days after completion of training by all employees and subcontractor personnel. AT Level 1 awareness training is available at the following website: <https://jkodirect.jten.mil>.

2.0 Access and General Protection and Security Policy and Procedures

All contractor and all associated subcontractor employees shall comply with applicable installation, facility and area commander installation/facility access and local security policies and procedures (provided by government representative). The contractor shall also provide all information required for background checks to meet installation access requirements to be accomplished by installation Provost Marshall Office, Director of Emergency Services or Security Office. Contractor workforce must comply with all personnel identity verification requirements (FAR 52.204-9 Personal Identity Verification of Contractor Personnel) as directed by DoD, HQDA, and/or local policy. In addition to the changes otherwise authorized by the changes clause of this contract, should the Force Protection Condition (FPCON) at any individual facility or installation change, the Government may require changes in contractor security matters or processes.

2.1 Common Access Card (CAC) Requirement for Contractors

The contractor and all subcontractor employees will be issued a CAC only if duties involve physical access to multiple DoD facilities or multiple non-DoD federally controlled facilities on behalf of the DoD on a recurring basis for a period of 6 months or more.

2.2 No CAC Required, but Require Access to Department of Defense Facility or Installation

Contractor and all associated subcontractor employees shall comply with adjudication standards and procedures using the National Crime Information Center Interstate Identification Index (NCIC-III) and Terrorist Screening Database (TSDB) (Army Directive 2014-05 / AR 190-13), applicable installation, facility and area commander installation/facility access and local security policies and procedures (provided by government representative, as NCIC and TSDB are available), or, at OCONUS locations, in accordance with status of forces agreements and other theater regulations.

3.0 AT Awareness Training for Contractor Personnel Travelling Overseas

Not Applicable

4.0 Suspicious Activity Reporting Training – Watch and/or Corps Watch Training (Annually)

The contractor and all associated sub-contractors shall review the power point training slides located on the Army One Source website under iWATCH Training for Contractors:

<http://www.myarmyonesource.com/familyprogramsandservices/iwatchprogram/default.aspx>

This developed training will be used to inform employees of the types of behavior to watch for and instruct employees to report suspicious activity to the project manager, security representative or law enforcement entity. This training shall be completed within 30 calendar days of contract award and within 30 calendar days of new employees commencing performance with the results reported to the COR NLT 5 calendar days after the completion of the training.

5.0 Access to Government Information Systems

Not Applicable

6.0 Operations Security (OPSEC) Standing Operating Procedure/Plan

Not Applicable

7.0 OPSEC Training (Annually)

All contractor employees (prime and sub) will complete Level I OPSEC Training within 30 calendar days of their reporting for duty. Additionally, all contractor employees must complete annual OPSEC awareness training for the life of the contract. The contractor shall submit certificates of completion for each affected contractor and subcontractor employee, to the COR or to the contracting officer (if a COR is not assigned), within 5 calendar days after completion of training. OPSEC awareness training is available at the following website:

<http://www.cdse.edu/catalog/operations-security.html>

8.0 Information Assurance (IA)/Information Technology (IT) training

Not Applicable

9.0 IA/IT training certification

Not Applicable

10.0 Contractors Authorized to Accompany the Force

Not Applicable

11.0 Performance or Delivery in a Foreign Country

Not Applicable

12.0 Handling or Access to Classified Information

This contract is not considered to be classified; however, access to restricted or sensitive areas may be required.

APPENDIX D – ANTITERRORISM/OPERATIONS SECURITY COMPLIANCE

The Contractor shall comply with the Security Agreement (DD Form 441), including the National Industrial Security Program Operating Manual (DOD 5220.22-M), any revisions to DOD 5220.22-M and Army Regulation 380-49, Industrial Security. The DD254 is not currently required by this contract.

13.0 Access to Sensitive or Restricted Areas

In the event that the contractor is required to access sensitive or restricted areas, the contractor will be responsible for obtaining the necessary clearances. No government escorts will be provided unless the customer/end user prefers to escort the contractor.

14.0 Individual Clearance

All contractor personnel performing work under this contract must have the required security clearance, per AR 380-67, at the appropriate level at the start of the period of performance. Security Clearances are required to be maintained for the life of the contract.

15.0 E-Verify Program

The Contractor must pre-screen Candidates using the E-Verify Program website at <http://www.uscis.gov/e-verify> to meet the established employment eligibility requirements. The Vendor must ensure that the Candidate has two valid forms of Government issued identification to ensure the correct information is entered into the E-Verify system. An initial list of verified/eligible Candidates must be provided to the COR no later than seven (7) calendar days after the initial contract award.

16.0 Armed Security Guards

Not Applicable

17.0 Threat Awareness Reporting Program.

All new contractor employees will complete annual Threat Awareness and Reporting Program (TARP) Training provided by a Counterintelligence Agent, IAW AR 381-12. The contractor shall submit certificates of completion for each affected contractor and subcontractor employee(s) or a memorandum for the record, to the COR or Contracting Officer, within 5 calendar days after completion of training. Authorized web-based TARP training for CAC card holders is available through ALMS. The preferred method is Live Based training. This is conducted at Army installations annually and Contractors may participate in this training. The FMSR should have knowledge of this annual training and can inform the Contractor of dates.

APPENDIX F - Component Unique Identifier (CUID)

Component Unique Identifier:	Site Code-Facility #-Component Acronym-Sequential #	
Example:	AAD-00063A-RCVL-0001	
NOTE: If component acronym is not listed, the contractor shall request an acronym be established through the HNC Project Manager and Project Engineer via email. Contractors may utilize other means of tracking/labeling assets such as QR codes in addition to the required CUID however, tracking/labeling must correlate with the CUID. This CUID shall be the standard for all DLA capitalized equipment		
DLA Work Type Category	UFC Section Reference Work Category (Revised per Change 1, 29 April 2021)	Component Acronym
Air Compressors	Air Compressors	AIRC
Alarms	Externally Mounted Level Alarms (Section 8-9.9.1)	EMLA
	Internally Mounted Level Alarms (Section 8-9.9.3)	IMLA
Bollard	Bollards	BLRD
Building	Building HVAC	BHVAC
	Building Domestic Water System	BWTR
	Building Waste Water	BWSW
	Building - Lighting	BLTG
	Building - Architectural	BARCH
	Building - Fire Sprinkler System	BFIRE
Containment/Joints	Containment Systems (General) (Section 8-10.1)	CSGEN
	Concrete and Cement Brick Dike/Berm Walls (Section 8-10.2.1)	DKBW
	Dike/Berm Floors (Section 8-10.2.2)	DKBF
	Earthen Dike Walls (Section 8-10.3)	ETHDW
	Self-Diking or Vaulted Tank Containment (Section 8-10.4)	SDVTCS
	Flexible Membrane Liners (Section 8-10.5)	FXML
	Fuel Truck and Rail Car Containment Areas (Section 11-1.1)	FTKRCC
	Remote Spill Containment (Section 11-1.2)	RSCS
	Piers and Wharves Fuel Containment Systems (Section 5-1.2) - Testing	FPWCT
	Fuel Pier/Wharf Containment (PWS Section 3)	FPWC
Corrosion Control/Coatings	Aboveground Piping and Equipment Coatings (Section 6-10.1)	AGPCT
Miscellaneous	Miscellaneous Deactivated Components (Section 12-5)	MDEACT
Electrical/Lighting	Lighting (Section 9-1.8)	LIGHT
Electrical/Power	Electrical Equipment (Section 9-1.2)	ELEQ
	Power Cables (Section 9-1.3)	PWRCBL
	Motor Controls (Section 9-1.4)	MTRCT
	Panelboards (Section 9-1.5)	PNLB
	Electric Motors (Section 9-1.7)	ELEMT
	Electronic Equipment (9-1.9)	ELTREQ
	Card and Key Locks (Section 9-3)	CKLK
Electrical/Protection	Power Grounding Systems (Section 9-1.6.1)	PWRGS
	Static Grounding Systems (Section 9-1.6.2)	STGS
	Cathodic Protection (Section 9-2.1)	CP
	Lightning Surge Arresters (Section 9-2.2.1)	LSAR
	Lightning Protection Systems (Section 9-4)	LPTS
	Ground Verification System (Section 9-5)	GRVS
	Electronic Overfill Protection Systems (Section 9-6)	EOPS
Eyewash/Shower	Emergency Eyewash/Showers (Section 11-3)	EMEWSH
Fencing/ Gates	Fencing	FENC
	Gates	GATE
Filtration	Pre-Filters (Section 3-6.1)	PFVSL
	Filter Separators (Section 3-6.2)	FLSP
	Haypack Filters (Section 3-6.3)	HPKF
	Basket Strainers (Section 3-6.4)	BSTR
	Filter Separator Sump Heaters (Section 3-6.5)	FSSH
	Sidestream Filtration Systems (Section 8-9.11)	SSFTS
Fire Suppression Equipment	Flame Arrestors (Section 8-9.5)	FLMARR
	Foam Fire Protection Systems (Section 8-9.15)	FFPS
	Fire Protection Systems - Wet Pipe	FPRS
Fuel Laboratories	Ventilation Hoods (Section 11-4.1)	VENTHD
Gauges	Pressure and Pressure/Vacuum Gauges (Section 6-7.1)	PVGA
	Differential Pressure Gauges (Section 6-7.2)	DPGA
	Mechanical Tape Gauges (Section 8-9.7)	MTGA
	Mechanically Operated Tape Gauge (Section 8-9.8.1)	MOTGA
	Magnetostrictive Probes (Section 8-9.8.2)	MRPRB
	Servo Gauge (Section 8-9.8.3)	SRVGA
Generators	Back-Up Power Generators	BGEN
Heating Coils	Steam Type Heating Coils (Section 8-9.16.1)	STHC
	Thermal Fluid Type Heating Coils (Section 8-9.16.2)	TFTHC
	Electric Rod Type Heating (Section 8-9.16.3)	ERTH
Hoses	Loading Fuel Hoses (Section 3-9.1)	LDHS
	Offloading Fuel Hoses (Section 3-9.2)	OLHS
	Aircraft Fueling Hoses (Section 4-7.5)	ACFHS
Hydrazine	Hydrazine Charging Units (Section 10-3)	HDZCU
Inspections	Trouble Shoot	TRBST
	API 510 Inspections	API510
	API 653 or STI Inspection	API653
	Coatings Condition Survey	CCS
	Dispenser Nozzles (Section 7-2)	DSNZ
	Dispenser Hoses (Section 7-3)	DSHS
	Breakaways (Section 7-4)	DSBW
	Swivels (Section 7-5)	DSSW
	Hose Retriever (Section 7-6)	HSRTV
	Dispenser Cabinet (Section 7-7)	DSCB
	Dispenser Meters (Section 7-8)	DSMTR
	Dispenser Filters (Section 7-9)	DSFLR
	Dispenser Strainers (Section 7-10)	DSSTR
	Ground Vehicle Fuel Piping (Section 7-11)	GVFP

APPENDIX F - Component Unique Identifier (CUID)

Component Unique Identifier:	Site Code-Facility #-Component Acronym-Sequential #	
Example:	AAD-00063A-RCVL-0001	
NOTE: If component acronym is not listed, the contractor shall request an acronym be established through the HNC Project Manager and Project Engineer via email. Contractors may utilize other means of tracking/labeling assets such as QR codes in addition to the required CUID however, tracking/labeling must correlate with the CUID. This CUID shall be the standard for all DLA capitalized equipment		
DLA Work Type Category	UFC Section Reference Work Category (Revised per Change 1, 29 April 2021)	Component Acronym
Issue/Receive - Ground	Emergency Shutoff Valves (Shear Valves) (Section 7-12)	ESHVL
	Dispenser Sumps (Section 7-13)	DSSMP
	Transition Sumps (Section 7-14)	TRSPM
	Remote Dispenser Pumps (Section 7-15.1)	RDSP
	Self-Contained Dispenser Pumps (Section 7-15.2)	SCDSP
	EFSO Systems (Section 7-16)	EFSO
	Stage I Vapor Recovery (Section 7-17.1)	SIVP
	Stage II Vapor Recovery (Section 7-17.2)	SIIVP
	Vapor Burners (Section 7-17.3)	VPBNR
	Point Sensor - Dry (Section 7-19.1.1)	PSDRY
Issue/Receive - Marine	Automatic Line Leak Detector (Section 7-19.1.2)	ALLD
	Visual Monitoring (Section 7-20.1)	VSLM
	Marine Receipt (Section 5-2)	MRNRCP
	Marine Issue (Section 5-3)	MRNISU
	Marine Loading Arms (Section 5-4)	MRNLA
	Marine Transfer Hoses (Section 5-5.1)	MBTHS
	Underwater Hoses (Section 5-5.2)	UWHS
	Single Point Mooring Systems (Section 5-7.1)	SPMSS
	Multi Point Mooring Systems (Section 5-7.2)	MPMSS
	Submerged Piping Systems (Section 5-8)	SMPS
Liquefied Petroleum	Boom Reels (Section 5-9)	BMRL
	Liquefied Petroleum Tanks (Section 10-1.1)	LPTANK
	Liquefied Petroleum Pipelines (Section 10-1.2)	LPPIPE
	Liquefied Petroleum Vapor Lines (Section 10-1.3)	LPVPL
	LPG Vaporizers (Section 10-1.4)	LPGVPZ
	Petroleum Gas Regulators (Section 10-1.5)	PGREG
Meter/ calibrations	Liquefied Petroleum Gas Hoses (Section 10-1.6)	LPGHS
	Positive Displacement Meters (Section 3-7.1)	PDMT
	Turbine Flow Meters (Section 3-7.2)	TBFMT
Natural Disaster	Orifice Flow Meters (Section 3-7.3)	OFMT
	Natural Disaster	
Natural Gas	CNG Piping (Section 10-2.1)	NGPIPE
	CNG Compressors (Section 10-2.2)	NGCOMP
	CNG Storage (Section 10-2.3)	NGSTOR
	CNG Dispensers (Section 10-2.4)	NGDS
	CNG Dispenser Hoses (Section 10-2.5)	NGDSHS
Nozzle	Hydrant Adapters (Section 4-7.2)	HADP
	Fueling Nozzles (Section 4-7.3)	FLNZ
Other	Fuel Additive Injectors (Section 3-11)	FAIJ
Pantograph	Fixed Pantographs (Section 4-7.1.1)	FXPNT
	Detachable Pantographs (Section 4-7.1.2)	DTPNT
Piping	On-Base Pipelines (Section 6-1.1)	OBPL
	Non-DOT Regulated (Section 6-1.2.1)	NDPL
	Aboveground Piping (Section 6-1.3)	AGPL
	Double-Wall Piping (Section 6-1.4)	DWPL
	Low Point Drains (Section 6-12.1)	LPDN
	High Point Vents (Section 6-12.2)	HPVT
	Sight Flow Indicators (Section 6-12.3)	SFND
	Rope Sensor Systems (Section 6-13.1.1)	RPSS
	Point Sensor - Dry (Section 6-13.1.2)	PSDRY
	Visual Monitoring (Section 6-14.1)	VSLM
Pressure/Temperature Control	Pipe Penetrations (Section 8-10.6)	PPEN
	Deactivated Petroleum Fuel Pipelines (Section 12-3)	DEACPL
	Air Eliminator Tanks (Section 3-10.1)	AELT
	Automatic Air Vents (Section 3-10.2)	AAVT
	Surge Suppressors (Section 4-7.4)	SRGSP
	Thermal and Pressure Relief Valves (Section 6-6.3)	TPRVL
	Pressure Transmitters (Section 6-7.3)	PRTR
	Differential Pressure Transmitters (Section 6-7.4)	DPTR
	Flexible Ball Joints (Section 6-8)	FBLJT
	Dial Thermometer (Section 6-9.1)	DTHMR
Pump	Emergency Vents (Section 8-9.4)	EMGVT
	Centrifugal Pumps (Section 3-8.1)	CENP
	Vertical Inline Pumps (Section 3-8.2)	VILP
	Vertical Turbine/Submerged Turbine Pumps (Section 3-8.3)	VTSP
	Sliding Vane Pumps (Section 3-8.5)	SLVP
	Gear Pumps (Section 3-8.6)	GERP
	Diaphragm Pumps (Section 3-8.7)	DIAP
	Internal Combustion Drives (Section 3-8.8)	ICDR
	Gearboxes (Section 3-8.9)	GRBX
	Deactivated Petroleum Fuel Pumps (Section 12-4)	DEACP
Signage/Markings	Signage and Markings (Section 2-7)	SIGN
Structures	Pumphouse/Filter Buildings (Section 11-2.1)	PFBLDG
	Canopies (Section 11-2.2)	CNPY
	Cranes and Hoists (Section 11-6)	CRNHST
	Aboveground Field-Erected Tanks (Section 8-4)	AGFET
	Geodesic Dome Roofs (Section 8-4.2)	GEODR
	Foundations (Section 8-4.3)	FOUND

APPENDIX F - Component Unique Identifier (CUID)

Component Unique Identifier:	Site Code-Facility #-Component Acronym-Sequential #		
Example:	AAD-00063A-RCVL-0001		
NOTE: If component acronym is not listed, the contractor shall request an acronym be established through the HNC Project Manager and Project Engineer via email. Contractors may utilize other means of tracking/labeling assets such as QR codes in addition to the required CUID however, tracking/labeling must correlate with the CUID. This CUID shall be the standard for all DLA capitalized equipment			
DLA Work Type Category	UFC Section Reference Work Category (Revised per Change 1, 29 April 2021)	Component Acronym	
Tank	Aboveground Shop Fabricated Tanks (Section 8-5.1)	AGSFP	
	Self-Diking or Vaulted Tanks (Section 8-5.2)	SDVT	
	Rectangular Concrete-Encased Tanks (Section 8-5.3)	RCET	
	Single-Walled Underground Shop-Fabricated Tanks (Section 8-5.4.1)	UGSSFT	
	Double-Walled Underground Shop-Fabricated Tanks (Section 8-5.4.2)	UGDSFT	
	Underground Field-Constructed Tanks (Cut and Cover Tanks) (Section 8-6)	UGFET	
	Tank Cleaning (Section 8-7)	TCLEAN	
	Aluminum Honeycomb Floating Pans (Section 8-9.1.1)	AHFP	
	Steel Floating Pans (Section 8-9.1.2)	STLFP	
	Pontoon Floating Pans (Section 8-9.1.3)	PTNFP	
	Floating Roofs (Section 8-9.1.4)	FLTRF	
	Floating Roof and Pan Pressure/Vacuum Vents (Section 8-9.1.5)	FPPVV	
	Floating Roof and Pan Legs (Section 8-9.1.6)	FRPLG	
	Secondary Tank Bottoms (Section 8-9.2)	SNDTB	
	Tank Pressure/Vacuum Vents (Section 8-9.3)	TPVVT	
	Product Saver Tanks (Section 8-9.10)	PRDST	
	Fill Ports (Section 8-9.12)	FPRT	
	Point Sensor - Dry (Section 8-9.13.1)	PSDRY	
	Point Sensor - Wet (Section 8-9.13.2)	PSWET	
	Point Sensor - Pressure/Vacuum (Section 8-9.13.3)	PSPV	
	Visual Leak Detection (Section 8-9.13.4)	VSLLD	
	Floating Suction Lines (Section 8-9.14)	FLTSL	
	Stilling Wells (Section 8-9.17)	STGW	
	Deactivated Petroleum Fuel Tanks (Section 12-2)	DEACT	
Testing	Pressure Testing		
Underground Pits	Isolation Valve Pits (Section 6-11.1)	ISVLP	
	Hydrant Fuel Pits (Section 6-11.2)	HDFP	
	High Point Vent Pits (Section 6-11.3)	HPVP	
	Low Point Drain Pits (Section 6-11.4)	LPDP	
	Lateral Control Pits (Section 6-11.5)	LTCP	
Valves	General System Control Valves (Section 4-3.2.1)	GSCVL	
	Refuel Control Valves (Section 4-3.2.5)	RCVL	
	Pressure Relief Valves (Section 4-3.2.6)	PRCVL	
	Defuel Control Valve (Section 4-3.2.7)	DFCVL	
	Dual Rate-of-Flow Control Valves (Section 4-3.2.8)	DRFCVL	
	Combination Dual Rate-of-Flow Control and Solenoid Valves (Section 4-3.3.1)	CFSCVL	
	Dual Pressure Relief, Solenoid Shutoff, and Check Valves (Section 4-3.3.2)	DPSCVL	
	Non-Surge Check Valves (Section 4-4.2.1)	NSCKVL	
	Filter Separator Control Valves (Section 4-4.2.2)	FSCVL	
	Defuel/Flush Valves (Section 4-4.2.3)	DFFCVL	
	Issue Venturi (Section 4-4.2.4)	ISVTR	
	Return Venturi (Section 4-4.2.5)	RTVTR	
	Back Pressure Control Valves (Section 4-4.2.6)	BPCVL	
	Pressure Control Valves (Section 4-4.2.7)	PCVL	
	Hydrant Control Valves (Section 4-4.2.8)	HCVL	
	Emergency Shut-off Valves (Section 4-4.2.9)	ESOVL	
	Pantograph Control Valves (Section 4-5.2.12)	PTCVL	
	Pantograph Pressure Control Valves (Section 4-5.2.13)	PTPCVL	
	Overfill Valve for Product Recovery Tanks (Section 4-8.1)	OVLPR	
	Plug Valves - Lubricated (Section 6-6.2.1)	PLVL	
	Plug Valves - Non-lubricated (Section 6-6.2.2)	NPLVL	
	Gate Valves (Section 6-6.2.3)	GTVL	
	Ball Valves (Section 6-6.2.4)	BLVL	
	Double Block and Bleed Valves (Section 6-6.2.5)	DBBVL	
	Butterfly Valves (Section 6-6.2.6)	BFVL	
	Globe Valves (Section 6-6.2.7)	GLVL	
	Check Valves (Section 6-6.2.8)	CKVL	
	Line Blanks, Ring Spacers, and Spectacle Blinds (Section 6-6.2.9)	BLIND	
	Manual Valve Gear Operators (Section 6-6.2.10)	MVLGO	
	Fire Valves (Section 6-6.4.1)	FRVL	
	Fusible Link Butterfly Valves (Section 6-6.4.2)	FLBFVL	
		Truck Fill Valves (Section 6-6.5.1)	TFVL
		Motor Operators (Section 6-6.6)	MTROP
		External High Level Shutoff Valves (HLSO) (Section 8-9.6.1)	EHL SVL
		Internal HLSO Valves (Section 8-9.6.2)	IHL SVL
	Waste	Oil/Water Separators (Section 11-5)	OWS

APPENDIX G – MAINTENANCE TABLE						
The contractor must perform maintenance tasks in accordance with the most current version of UFC 3-460-03.						
Section and Appendices referred to in this maintenance table are referenced from UFC 3-460-03, 10 November 2017, Change 1, 29 April 2021						
Maintenance tasks are separated into Operator Maintenance (OM) and Systems Maintenance (SM).						
Tasks with responsibility identified as SM shall be performed with identified frequency as part of this contract unless otherwise noted.						
Tasks with responsibility identified as OM shall not be performed unless otherwise noted.						
UFC Change 1, 29 April 2021 are highlighted and in bold below.						
	Task Number	Section	Description	Frequency	Responsibility	Notes
SIGNAGE AND MARKINGS	1	Signage and Markings (Section 2-7)	A. Check permanent signs and markings for adequacy and readability. Repair or replace deteriorated or illegible signs and markings.	Monthly	OM	
	2		B. Inspect the location of Department of Transportation (DOT) regulated underground pipelines and ensure they are marked in accordance with 49 Code of Federal Regulations (CFR) 195.410.	Monthly	OM	
	3		C. Check that all non-DOT regulated pipelines, tanks, valves, pumps, meters, and other equipment are marked in accordance with UFC 3-460-01 Section 2-17. If markings are missing or insufficient, repair or add markings in accordance with UFC 3-460-01.	Monthly	OM	
	4		D. Ensure petroleum fuel system Emergency Fuel Shutoff (EFSO) push buttons are properly identified at each location. Ensure that signage is properly secured and that the lettering is legible from 25 feet (7.5 meters) away and not faded.	Monthly	OM	
	5		E. Verify enough movable or temporary signs are maintained in good condition to serve anticipated needs; for example: "DANGER," "CLOSED TO TRAFFIC," "KEEP FLAMES AWAY," "MEN WORKING," "NO SMOKING," "DANGER NO OPEN FLAME OR IGNITION SOURCE BEYOND THIS POINT." Use bilingual signs when appropriate.	Annually	OM	
FILTRATION	6	Pre-Filters (Section 3-6.1)	A. Open drains under flow conditions until clear fuel is observed from the drain valve.	Daily	OM	
	7		B. Monitor differential pressure in filter cartridges. Chart differential pressure measurements from readings taken during normal operations.	Daily	OM	
	8		C. Operate pre-filter isolation valves.	Quarterly	SM	
	9		D. Replace filter cartridges when the acceptable maximum differential pressure is reached, the maximum in-service duration has passed, or the fuel becomes visibly dirty or discolored. Acceptable maximum differential pressure for a specific pre-filter is dependent on the system flow rate. The Military Service-specific SCP may extend in-service duration filter cartridge replacement period based on differential pressure for high throughput systems. Check expiration date of replacement filter cartridges before installation.	When differential pressure has reached the lower of manufacturer's recommendation or 20 psid (140 kPa), filter cartridge in-service period of 24 months has expired, or when fuel becomes visibly dirty or discolored.	SM	Routine filter changes for sites that do not self perform shall be priced under CLIN 6 FFP maintenance activities. Existing maintenance schedules when provided will be located in Appendix J. If no existing schedules have been provided, assume filter changes in Base Year and thereafter following the required service period indicated in this section. Filter changes required due to a repair, out of sequence, or other circumstance beyond normal system operation shall be performed by service order. Filter cartridges will be purchased by the Government and supplied to the Contractor.
	10		E. Refer to Section 6-7.2 Differential Pressure Gauges for inspection and maintenance requirements of differential pressure gauges.	As required	SM	
	11		F. Refer to Section 3-10.2 Automatic Air Vents for inspection and maintenance requirements of automatic air vents.	As required	SM	
	12		G. Refer to Section 6-6.3 Thermal and Pressure Relief Valves for inspection and maintenance requirements of thermal and pressure relief valves.	As required	SM	
	13		H. Conduct inspections of code rated vessels that meet the requirements of UFC 3-430-07 Operations and Maintenance: Inspection and Certification of Boilers and Unfired Pressure Vessels.	As required by UFC 3-430-07	SM	This task shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.
	14	Filter Separators (Section 3-6.2)	A. Open drain under flow conditions until clear fuel is observed from the drain valve.	Daily	OM	
	15		B. Monitor differential pressure of coalescer cartridges. The acceptable maximum differential pressure for a specific filter/separator is dependent on the system flow rate. Monitor and chart differential pressure measurements of filter separators from readings taken during normal operations. Investigate sudden drops or spikes in differential pressure measurement readings.	Daily	OM	
	16		C. Operate filter separator isolation valves.	Quarterly	SM	
	17		D. Inspect components and check operation of water shutoff system.	Quarterly	SM	
	18		E. Change coalescer cartridges. Refer to Section 3-6.2.2 Replacement of Coalescer Cartridges for general instructions on replacement of coalescer cartridges. Military Service-specific SCP may extend the coalescer cartridge replacement frequency based on differential pressure if filters separators are used on high throughput systems. Check expiration date of replacement coalescer cartridges before installation.	Every 36 months or sooner if required by differential pressure.	SM	Routine coalescer changes for sites that do not self perform shall be priced under CLIN 6 maintenance activities. Existing maintenance schedules when provided will be located in Appendix J. If no existing schedules have been provided, assume coalescer changes in Base Year and thereafter following the required service period indicated in this section. Coalescer changes required due to a repair, out of sequence, or other circumstance beyond normal system operation shall be performed by service order. Coalescer cartridges will be purchased by the Government and supplied to the Contractor.
	19		F. Inspect and clean separator cartridges at time of coalescer cartridge change in accordance with Section 3-6.2.3 Separator Cleaning. Worn or damaged separator cartridges shall be replaced.	Every 36 months or sooner if required by differential pressure.	SM	Routine separator cartridge cleaning or replacement for sites that do not self perform shall be priced under CLIN 6 maintenance activities. Existing maintenance schedules when provided will be located in Appendix J. If no existing schedules have been provided, assume separator changes/cleaning in Base Year and thereafter following the required service period indicated in this section. Separator cleaning or changes required due to a repair, out of sequence, or other circumstance beyond normal system operation shall be performed by service order. Separator cartridges will be purchased by the Government and supplied to the Contractor.
	20		G. Refer to Section 6-7.2 Differential Pressure Gauges for inspection and maintenance requirements of differential pressure gauges.	As required	SM	
	21		H. Refer to Section 3-10.2 Automatic Air Vents for inspection and maintenance requirements of automatic air vents.	As required	SM	
	22		I. Refer to Section 6-6.3 Thermal and Pressure Relief Valves for inspection and maintenance requirements of thermal and pressure relief valves.	As required	SM	

	Task Number	Section	Description	Frequency	Responsibility	Notes
	23	Haypack Filters (Section 3-6.3)	J. Refer to Section 4-4.2.2 Filter Separator Control Valves for inspection and maintenance requirements of filter separator control valves.	As required	SM	This task shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.
	24		K. Conduct inspections of code rated vessels that meet the requirements of UFC 3-430-07 Operations and Maintenance: Inspection and Certification of Boilers and Unfired Pressure Vessels.	As required by UFC 3-430-07	SM	
	25		A. Refer to manufacturer's operation and maintenance manual for inspection and maintenance requirements of haypack filters.	Per manufacturer's specifications	SM	
	26		B. Refer to Section 2-6.4 Waste Disposal for disposal requirements.	As required	SM	
	27	Basket Strainers (Section 3-6.4)	A. Monitor and chart differential pressure measurements of basket strainers from readings taken during normal operations. Investigate sudden drops or spikes in differential pressure measurement reading.	Daily	OM	
	28		B. Clean and inspect basket and strainer screen. Basket strainer isolation valves shall be closed and the strainer body shall be drained before removing the cover. After cleaning, the strainer screen shall be inserted in the strainer body, and the head tightened and checked for leakage. If strainer is not equipped with means to measure differential pressure, unit shall be opened monthly and inspection.	Semi-annually if basket strainer is equipped with means to measure differential pressure; otherwise quarterly	OM	
	29		C. Refer to Section 6-7.2 Differential Pressure Gauges for inspection and maintenance requirements of differential pressure gauges.	As required	SM	
	30	Filter Separator Sump Heaters (Section 3-6.5)	A. Inspect filter separator sump and drain line heater elements for proper operation per manufacturer's operation and maintenance manual. Ensure heater elements meet manufacturer's requirements by measuring resistance of heater elements with an ohm meter.	Semi-annually	SM	
METERS	31	Positive Displacement Meters (Section 3-7.1)	A. Inspect counter head for unusual noises and smooth operation.	Monthly	OM	Calibration shall be done by SO if FMSR requests an out of cycle calibration due to circumstances beyond normal operation.
	32		B. Positive displacement meters shall be inspected and calibrated semi-annually or when improper performance is suspected; when unusual sounds or register actions develop; or after repairs have been made which may affect performance. Positive displacement meters are satisfactory when the measurement error in the normal flow direction is within ±0.3% of actual quantity delivered (e.g., ±1.8 gallons for a 600-gallon test (±6.8 liters for a 2275-liter test)). Adjustment of the meter's register will be in accordance with manufacturer's instructions. Identify the next calibration date on meters (example: Mar 14 for March 2014). Use weather resistant label that will remain legible and affixed for at least one year.	Semi-annually or as required	SM	
	33		C. Inspect temperature element operation of meters equipped with temperature compensation feature per manufacturer's operation and maintenance manual.	Semi-annually or as required	SM	
	34	Turbine Flow Meters (Section 3-7.2)	A. Turbine flow meters shall be inspected and calibrated semi-annually or when improper performance is suspected, register actions develop, or after repairs have been made which may affect performance. Turbine flow meters are satisfactory when the measurement error in the normal flow direction is within ±0.5% of actual quantity delivered (e.g., ±3 gallons for a 600-gallon test (±11 liters for a 2275-liter test)). Adjustment of the meter's register will be in accordance with the manufacturer's instructions. Identify the next calibration date on meters (example: Mar 14 for March 2014). Use weather resistant label that will remain legible and affixed for at least one year.	Semi-annually or as required	SM	Calibration shall be done by SO if FMSR requests an out of cycle calibration due to circumstances beyond normal operation.
	35		B. Inspect temperature element operation of meters equipped with temperature compensation feature per manufacturer's operation and maintenance manual.	Semi-annually or as required	SM	
	36	Orifice Flow Meters (Section 3-7.3)	A. Refer to Section 6-7.2 Differential Pressure Gauges for inspection and maintenance requirements of differential pressure gauges.	As required	SM	
	37		B. Refer to Section 6-7.4 Differential Pressure Transmitters for inspection and maintenance requirements of differential pressure transmitters.	As required	SM	
PUMPS	38	Centrifugal Pumps (Section 3-8.1)	A. Check for proper operations while pump is in use. Check suction and discharge pressure gauge for abnormal readings.	Quarterly	SM	
	39		B. Check for unusual noise, vibration, overheating of bearings or case.	Quarterly	SM	
	40		C. If equipped with lubricating oil charge, check oil level and adjust as necessary.	Quarterly	SM	
	41		D. Tighten or replace loose, missing or damaged nuts, bolts, or screws.	Quarterly	SM	
	42		E. Inspect suction and discharge isolation dampeners for misalignment and wear.	Quarterly	SM	
	43		F. Inspect mechanical seals, if possible, for proper operating temperature, drips, leaks and dirt.	Quarterly	SM	
	44		G. Check alignment, clearances, and rotation of shaft and coupler (requires removal of coupler shroud or cover).	Annually	SM	
	45		H. Lubricate pump bearings.	Annually	SM	
	46		I. If equipped with lubricating oil charge, drain old oil, and fill with new to full mark on sight indicator (also fill bulb).	Annually	SM	
	47		J. Refer to Section 9-1.7 Electric Motors for inspection and maintenance requirements of electric motors.	As required	SM	
	48	Vertical Inline Pumps (Section 3-8.2)	A. Check for proper operations while pump is in use. Check suction and discharge pressure gauges for abnormal readings.	Quarterly	SM	
	49		B. Check for unusual noise, vibration, overheating of bearings.	Quarterly	SM	
	50		C. Tighten or replace loose, missing or damaged nuts, bolts, or screws.	Quarterly	SM	
	51		D. Inspect suction and discharge isolation dampeners for misalignment and wear.	Quarterly	SM	
	52		E. Inspect mechanical seals, if possible, for proper operating temperature, drips, leaks and dirt.	Quarterly	SM	
	53		F. Check alignment, clearances, and rotation of shaft and coupler (requires removal of coupler shroud or cover).	Annually	SM	
	54		G. Lubricate pump bearings.	Annually	SM	
	55		H. Refer to Section 9-1.7 Electric Motors for inspection and maintenance requirements of electric motors.	As required	SM	
	56	Vertical Turbine/Submerged Turbine Pumps (Section 3-8.3)	A. Check for proper operations while pump is in use. Check discharge pressure gauge for abnormal readings.	Quarterly	SM	
	57		B. Check for unusual noise, vibration, overheating of bearings or case.	Quarterly	SM	
	58		C. If equipped with lubricating oil charge, check oil level and adjust as necessary.	Quarterly	SM	
	59		D. Tighten or replace loose, missing or damaged nuts, bolts, or screws.	Quarterly	SM	
	60		E. Inspect mechanical seals, if possible, for proper operating temperature, drips, leaks and dirt.	Quarterly	SM	
	61		F. Inspect anti-rotation device for proper operation.	Semi-annually	SM	
	62		G. Check alignment, clearances, and rotation of shaft and coupler (requires removal of coupler shroud or cover).	Annually	SM	
	63		H. Lubricate pump bearings.	Annually	SM	
	64		I. If equipped with lubricating oil charge, drain old oil, and fill with new oil to full mark on sight indicator (also fill bulb).	Annually	SM	
	65		J. Refer to Section 9-1.7 Electric Motors for inspection and maintenance requirements of electric motors.	As required	SM	
	66		A. Inspect pump for unusual noise, vibrations, and overheating of bearings and case.	Quarterly	SM	
	67		B. Inspect mechanical seals, if possible, for drips or leaks and dirt.	Quarterly	SM	
	68		C. Lubricate pump bearings.	Quarterly	SM	
	69		D. Inspect pump and motor coupling for proper alignment.	Annually	SM	

	Task Number	Section	Description	Frequency	Responsibility	Notes
	70	Sliding Vane Pumps (Section 3-8.5)	E. Refer to manufacturer's operation and maintenance manual for internal pressure relief testing and calibration procedures.	Annually	SM	
	71		F. Refer to Section 3-8.4 Gearboxes for inspection and maintenance of reduction gearboxes.	As required	SM	
	72		G. Refer to Section 9-1.7 Electric Motors for inspection and maintenance requirements of electric motors.	As required	SM	
	73	Gear Pumps (Section 3-8.6)	A. Inspect pump for unusual noise, vibrations, and overheating of bearings and case.	Quarterly	SM	
	74		B. Inspect mechanical seals, if possible, for drips or leaks and dirt.	Quarterly	SM	
	75		C. Lubricate pump bearings.	Quarterly	SM	
	76		D. Inspect pump and motor coupling for proper alignment.	Annually	SM	
	77		E. Refer to Section 3-8.4 Gearboxes for inspection and maintenance of reduction gearboxes.	As required	SM	
	78		F. Refer to Section 9-1.7 Electric Motors for inspection and maintenance requirements of electric motors.	As required	SM	
	79	Diaphragm Pumps (Section 3-8.7)	A. Inspect hose for cracks or dry rot.	Quarterly	SM	
	80		B. Inspect compressed air connections for signs of leaks.	Quarterly	SM	
	81		C. Inspect compressed air hose coupling safety pins or safety wires for wear and damage. Replace damaged components.	Quarterly	SM	
	82		D. Diaphragm pumps should have the internal diaphragm replaced if the pump shows decreased performance. Also check operation of actuator valve and ensure ball checks seat properly.	As required	SM	Repairs should be performed by service order.
	83	Internal Combustion Drives (Section 3-8.8)	A. Refer to manufacturer's operation and maintenance manual for specific maintenance procedures and schedules associated with a specific model of internal combustion drive. Follow all applicable general maintenance and safety requirements listed in the manufacturer's operation and maintenance manual.	As required by manufacturer's operation and maintenance requirements	SM	
	84	Gearboxes (Section 3-8.9)	A. Inspect gearboxes for signs of smoke near shaft connections or discoloration of the gearbox from overheating.	Quarterly	SM	
	85		B. Verify that the oil in the sight glass is not dark or appears to have foam. Adjust oil level if required.	Quarterly	SM	
	86		C. Lubricate bearings per manufacturer's recommendations.	Semi-annually	SM	
	87		D. Check motor and gear box and gear box and pump couplers for wear and alignment.	Semi-annually	SM	
	88		E. Inspect gear alignment within gearbox.	Annually	SM	
	89		F. Replace lubricant oil in accordance with manufacturer's specifications and recommendations.	Annually	SM	
HOSES	90	Loading Fuel Hoses (Section 3-9.1)	A. Visually inspect hoses for loose covers, cracks, brittle surface coatings, exposed wire braids, exposed reinforcement, flattening, kinks, and bulges or soft spots which might indicate broken or displaced reinforcement.	Weekly	OM	
	91		B. Pressurize hose to normal working pressure. Check flanged and threaded connections for leaks and inspect hose couplers for fluid seepage by pushing at the base of the coupling with your thumbs; a hose softened by fluid seepage must be replaced.	Monthly	OM	
	92		C. Check for coupling slippage. Replace hose that shows signs of coupling slippage.	Quarterly	SM	When a new hose is placed in service, stencil the date (MM/YYYY) installed and paint a 50 mm (2-inch) band at each coupling. This will aid in identifying if slippage occurs and when testing is due.
	93		D. Refer to Appendix D, Section D-2.1 Loading Hose Hydrostatic Test for loading hose hydrostatic testing requirements and procedures. Task deleted in UFC 3-460-03 Change 1.		N/A	This task has been deleted.
	94	Offloading Fuel Hoses (Sections 3-9.2)	E. Conduct test of fuel hose electrical resistivity using an electrostatic meter in accordance with NFPA 77 & API 2003.	Annually	SM	
	95		A. Visually inspect hoses for cracks brittle surface coatings, exposed wire braids, exposed reinforcement, flattening, kinks, and bulges or soft spots which might indicate broken or displaced reinforcement.	Weekly	OM	
	96		B. Check flanged and threaded connections for leaks and inspect hose couplers for fluid seepage by pushing at the base of the coupling with thumbs; a hose softened by petroleum fluid seepage must be replaced. Damaged or leaking hoses shall be replaced immediately or isolated and taken out of service.	Quarterly	SM	Repairs should be performed by service order unless otherwise covered in the PWS.
	97		C. Conduct test of offloading fuel hose electrical resistivity as directed in NFPA 77 and API 2003.	Annually	SM	
AUTOMATIC AIR VENTS	98	Air Eliminator Tanks (Section 3-10.1)	A. Inspect operation of fuel level probes. Ensure probes operate correctly when the level of fuel in the tank rises to the level of the probe sensing unit.	Annually	SM	
	99		B. Remove the float vent valve from the air eliminator tank. Clean and inspect the sealing surfaces of the float vent valve. Ensure the float is buoyant in fuel and test the valve to ensure it closes properly.	Annually	SM	
	100		C. Refer to Section 8-9.3 Tank Pressure/Vacuum Vents for inspection and maintenance requirements of pressure vacuum vents.	As required	SM	
	101	Automatic Air Vents (Section 3-10.2)	A. Check for proper operation of the automatic air vent. Ensure the vent opens to allow air to escape and ensure the float of the vent is buoyant in petroleum fuel and rises to close the vent when the float is suspended in petroleum fuel.	Annually	SM	
FUEL ADDITIVE	102	Fuel Additive Injectors (Section 3-11)	A. Inspect injectors to ensure they are operating properly.	When fuel system has flow through it, inspect weekly. When fuel system is sitting idle, inspect injectors monthly.	OM	
	103		B. Calibrate injector to ensure proper additive to fuel ratio.	Annually	SM	

ANT SYSTEM	104	General System Control Valves (Section 4-3.2.1)	A. Verify operating settings of valve. Valve adjustment shall be in accordance with manufacturer's operation and maintenance manuals and final start-up and commissioning set points. Use of DoD standard set points should only be used as a reference starting point as pipe size and other hydraulic factors influence final system settings.	Quarterly	SM	
	105		B. Remove and clean strainer installed in the petroleum fuel supply line to the pilot and main valve diaphragm. This strainer is provided to prevent clogging of the orifice in the supply line. Clogging of the screen will cause malfunctioning of the valve.	Annually for unfiltered systems and as required for filtered systems.	SM	
	106		C. Diaphragms shall be removed and inspected for deterioration and breaks at the flexing joint. Damage is often caused by pipe scale, pipe tape, and thread sealant compound that collect above the diaphragm and become lodged between the diaphragm and bonnet of the valve. Damage may also be caused by a change of operational petroleum fuel type or grade (such as a change from JP-4 to JP-8).	Every 10 years	SM	This task shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.
	107	Refuel Control Valves (Section 4-3.2.5)	A. Verify refuel control valve is set to maintain 100 psig (690 kPa) (typical operating pressure) as measured at the furthest hydrant outlet.	Quarterly	SM	
	108		B. Verify pressure-reducing control will open at 5 psig (35 kPa) above normal operating pressure (typically 105 psig (725 kPa) as measured at the farthest hydrant outlet).	Quarterly	SM	
	109		C. Verify refueling control valve opening rate is set between 15 and 20 seconds. The valve should open as quickly as possible without tripping the pressure differential control shut-off.	Quarterly	SM	
	110		D. Verify operation of the excess flow shut-off function.	Quarterly	SM	
	111		E. Verify operation of solenoid.	Quarterly	SM	
	112		F. Refer to Section 4-3.2.1 General System Control Valves for additional inspection and maintenance requirements.	As required	SM	

	Task Number	Section	Description	Frequency	Responsibility	Notes
CONTROL VALVES - TYPE II HYDR	113	Pressure Relief Valves (Section 4-3.2.6)	A. Verify pressure relief valve will open at 10 psig (69 kPa) above normal inlet pressure to the refuel control valve.	Semi-annually	SM	Maintenance procedure shall include process to verify that the valve has properly reset after all maintenance activities are performed on pressure relief valves or thermal and pressure relief valves.
	114		B. Refer to Section 4-3.2.1 General System Control Valves for additional inspection and maintenance requirements.	As required	SM	Maintenance procedure shall include process to verify that the valve has properly reset after all maintenance activities are performed on pressure relief valves or thermal and pressure relief valves.
	115	Defuel Control Valve (Section 4-3.2.7)	A. Verify the defuel control valve opens when the solenoid on the defuel control valve is energized.	Quarterly	SM	
	116		B. Refer to Section 4-3.2.1 General System Control Valves for additional inspection and maintenance requirements.	As required	SM	
	117	Dual Rate-of-Flow Control Valves (Section 4-3.2.8)	A. Verify dual rate-of-flow control valve is set to maintain a flow rate of 200 gpm (12.5 lps).	Quarterly	SM	
	118		B. Verify check valve feature is operational.	Quarterly	SM	
	119		C. Refer to Section 4-3.2.1 General System Control Valves for additional inspection and maintenance requirements.	As required	SM	
	120	Combination Dual Rate-of-Flow Control and Solenoid Valves (Section 4-3.3.1)	A. Verify valve is set to maintain a flow rate of 300 gpm (19 lps).	Quarterly	SM	
	121		B. Verify operation of check valve feature.	Quarterly	SM	
	122		C. Verify solenoid operation.	Quarterly	SM	
	123		D. Refer to Section 4-3.2.1 General System Control Valves for additional inspection and maintenance requirements.	As required	SM	
	124	Dual Pressure Relief, Solenoid Shutoff, and Check Valves (Section 4-3.3.2)	A. Verify high pressure relief control will open at 5 psig (35 kPa) above the refuel control valve pressure relief control set point (typically set at 110 psig (760 kPa)).	Quarterly	SM	
	125		B. Verify low pressure relief control will open at 5 psig (35 kPa) when refueling pumps are stopped.	Quarterly	SM	
	126		C. Verify closing speed provides a smooth, pulsation free operation.	Quarterly	SM	
	127		D. Verify operation of solenoid valve.	Quarterly	SM	
	128		E. Refer to Section 4-3.2.1 General System Control Valves for additional inspection and maintenance requirements.	As required	SM	
CONTROL VALVES - TYPE III HYDRANT SYSTEM	129	Non-Surge Check Valves (Section 4-4.2.1)	A. Verify main valve opening speed (typically 20 seconds). Adjust if required.	Semi-annually	SM	
	130		B. Verify valve maintains 650 gpm (41 lps) flow rate (some instances 950 gpm (60 lps) flow rate). Adjust if required.	Semi-annually	SM	
	131		C. Ensure the check valve function is operating properly.	Semi-annually	SM	
	132		D. Refer to Section 4-3.2.1 General System Control Valves for additional inspection and maintenance requirements.	As required	SM	
	133	Filter Separator Control Valves (Section 4-4.2.2)	A. Test FSCV emergency shut off solenoid under flow conditions and ensure that valve closes within 10 seconds of EFSO button activation. Coordinate with overall EFSO test listed in Section 9-1.2.1 Inspection and Maintenance - Electrical Equipment.	Quarterly	SM	
	134		B. Operate test button (if installed) to ensure the FSCV closes at high water level. Physically press the test button, while recirculating fuel, and ensure the FSCV closes. Note: closing speed is a function of the number of open filters separators and the number of pumps operating. With all filters open and only one pump operating, the valve will close very slowly.	Quarterly	SM	
	135		C. Verify valve maintains flow rate (typically 600 gpm (38 lps), operating range based on commissioning documentation). Adjust flow rate if required. Flow rate is determined by filter separator vessel gpm (lps) rating, or element flow rate, whichever is less. Use return venturi to measure and confirm flow rate during valve testing and adjustment.	Semi-annually	SM	
	136		D. Ensure check valve function is operating properly.	Semi-annually	SM	
	137		E. Test buoyancy of water level float. Remove the ball or float assembly and place it in a bucket of water. Correctly operating ball or float will float at the top of the water's surface.	When coalescer cartridges are changed.	SM	
	138		F. Refer to Section 4-3.2.1 General System Control Valves for additional inspection and maintenance requirements.	As required	SM	
	139		A. Ensure Solenoids A and B are de-energized with system in automatic mode and lead pump operating.	Quarterly	SM	
	140		B. Ensure Solenoid A is energized and Solenoid B is de-energized to allow main valve to open and drop system pressure to 80 psig (550 kPa) (typical set pressure) with system in automatic mode and lead pump off.	Quarterly	SM	
	141	Defuel/Flush Valves (Section 4-4.2.3)	C. Ensure Solenoid A is de-energized and Solenoid B is energized when system is in flush mode.	Quarterly	SM	
	142		D. Ensure Solenoids A and B are de-energized when system is in tightness test mode.	Quarterly	SM	
	143		E. Check opening and closing speed. Speed should be as fast as possible while still maintaining smooth operation.	Quarterly	SM	
	144		F. Refer to Section 4-3.2.1 General System Control Valves for additional inspection and maintenance requirements.	As required	SM	
	145		A. Ensure issue venturi DPTs are reading the same value within $\pm 2\%$ full scale.	Semi-annually	SM	
	146	Issue Venturi (Section 4-4.2.4)	B. Refer to Section 6-7.4 Differential Pressure Transmitters for inspection and maintenance requirements of DPTs.	As required	SM	
	147		A. Ensure return venturi DPTs are reading the same value within $\pm 2\%$ full scale.	Semi-annually	SM	
	148	Return Venturi (Section 4-4.2.5)	B. Refer to Section 6-7.4 Differential Pressure Transmitters for inspection and maintenance requirements of DPTs.	As required	SM	
	149		A. Verify constant upstream pressure is maintained at the setpoint established and listed in the system commissioning documents. Adjust setting of BPCV as necessary.	Quarterly	SM	
	150	Back Pressure Control Valves (Section 4-4.2.6)	B. Ensure Solenoid A is energized and Solenoid B is de-energized while lead pump is operating in automatic mode.	Quarterly	SM	
	151		C. Ensure Solenoids A and B are de-energized prior to lead pump shutdown and system going to stand-by.	Quarterly	SM	
	152		D. Ensure Solenoids A and B are de-energized while system is in flush mode.	Quarterly	SM	
	153		E. Ensure that Solenoid A is de-energized and Solenoid B is energized while system is in tightness test mode.	Quarterly	SM	
	154		F. Verify closing speed control. Valve should close as fast as possible while still maintaining smooth operation.	Quarterly	SM	
	155		G. Check solenoid EFSO feature when equipped. Coordinate test with overall EFSO test listed in Section 9-1.2.1 Inspection and Maintenance - Electrical Equipment.	Quarterly	SM	
	156		H. Refer to Section 4-4.2.1 General System Control Valves for additional inspection and maintenance requirements.	As required	SM	
	157	Pressure Control Valves (Section 4-4.2.7)	A. Ensure Solenoid A is energized and Solenoid B is de-energized while system is in automatic mode and lead pump is operating.	Quarterly	SM	
	158		B. Ensure Solenoids A and B are de-energized while system is in automatic mode and lead pump is off. Verify valve opens to maintain system pressure at 75 psig (515 kPa).	Quarterly	SM	
	159		C. Ensure Solenoid A is energized and Solenoid B is de-energized while system is in flush mode and lead pump is operating.	Quarterly	SM	
	160		D. Ensure Solenoids A and B are de-energized while system is in flush mode and pumps are off.	Quarterly	SM	
	161		E. Ensure Solenoids A and B are energized while system is in tightness test mode.	Quarterly	SM	

	Task Number	Section	Description	Frequency	Responsibility	Notes
	162	Hydrant Control Valves (Section 4-4.2.8)	F. Verify closing speed control. Valve should close as fast as possible while still maintaining smooth operation.	Quarterly	SM	
	163		G. Refer to Section 4-3.2.1 General System Control Valves for additional inspection and maintenance requirements.	As required	SM	
	164		A. Verify HCV maintains 45 psig (310 kPa) nozzle pressure at a flow of 50 to 600 gpm (3 to 38 lps).	Quarterly	SM	
	165		B. Verify HCV closes when nozzle pressure exceeds 50 psig (345 kPa).	Quarterly	SM	
	166		C. Verify HCV opening rate is set at a minimum of 20 seconds.	Quarterly	SM	
	167		D. Ensure HCV opens when the deadman control level is pressed.	Quarterly	SM	
	168		E. Verify HCV closes in five seconds maximum after the deadman lever is released.	Quarterly	SM	
	169		F. Refer to Section 4-3.2.1 General System Control Valves for additional inspection and maintenance requirements.	As required	SM	
	170	Emergency Shut-off Valves (Section 4-4.2.9)	A. Ensure Solenoids A and B are energized under normal operations.	Quarterly	SM	
	171		B. Ensure Solenoids A and B are de-energized during emergency stop conditions.	Quarterly	SM	
	172		C. Test emergency stop function of the valve under flow conditions. Ensure the valve closes within 10 seconds of EFSO button activation. Coordinate test with overall EFSO test listed in Section 9-1.2.1 Inspection and Maintenance - Electrical Equipment.	Quarterly	SM	
	173		D. Verify differential control maintains a constant seven psig (48 kPa) differential pressure between the inlet and outlet of the valve.	Quarterly	SM	
	174		E. Ensure thermal relief function (ball check valve) relieves excess pressure when cover chamber pressure exceeds inlet pressure.	Quarterly	SM	
	175		F. Refer to Section 4-3.2.1 General System Control Valves for additional inspection and maintenance requirements.	As required	SM	
CONTROL VALVES - TYPE IV AND V HYDRANT SYSTEM	176	Pantograph Control Valves (Section 4-5.2.12)	A. Verify PTCV maintains 55 psig (380 kPa) nozzle pressure at a flow of 50 to 600 gpm (3 to 38 lps).	Quarterly	SM	
	177		B. Verify PTCV opens when the deadman control lever is pressed.	Quarterly	SM	
	178		C. Verify PTCV closes in a maximum of 10 seconds after deadman lever is released.	Quarterly	SM	
	179		D. Refer to Section 4-3.2.1 General System Control Valves for additional inspection and maintenance requirements.	As required	SM	
	180	Pantograph Pressure Control Valves (Section 4-5.2.13)	A. Verify PPCV opens at 75 psig (515 kPa).	Quarterly	SM	
	181		B. Verify PPCV opening and closing speed are three seconds.	Quarterly	SM	
	182	Fixed Pantographs (Section 4-7.1.1)	A. Place entire pantograph under static pump head pressure and check for leaks, ease of movement, and damaged grounding or bonding wire.	Monthly	OM	
	183		B. Inspect wheels (if equipped) for warping, cracking, and uneven wear.	Quarterly	SM	
	184		C. Inspect exposed piping and components for corrosion.	Quarterly	SM	
	185		D. Refer to Section 4-7.3 Fueling Nozzles for inspection and maintenance requirements of fueling nozzle.	As required	SM	
	186	Detachable Pantographs (Section 4-7.1.2)	A. Place entire pantograph under static pump head pressure and check for leaks, ease of movement, and damaged grounding or bonding wire.	Monthly	OM	
	187		B. Inspect exposed piping and components for corrosion.	Quarterly	SM	
	188		C. Lubricate wheels.	Quarterly	SM	
	189		D. Inspect wheels for warping, cracking and uneven wear.	Quarterly	SM	
	190		E. Refer to Section 4-7.2 Hydrant Adapters for inspection and maintenance requirements of pantograph hydrant adapters.	As required	SM	
	191		F. Refer to Section 4-7.3 Fueling Nozzles for inspection and maintenance requirements of fueling nozzles.	As required	SM	
	192	Hydrant Adapters (Section 4-7.2)	A. Inspect hydrant adapter for proper operation, damage, and wear.	Quarterly	SM	
	193		B. Test operation of dry break system.	Quarterly	SM	
	194	Fueling Nozzles (Section 4-7.3)	A. Inspect the condition of the dust cap at the aircraft adapter end and ensure it is in good working order. Dust caps must be attached to nozzles when they are not in use.	Monthly	OM	
	195		B. Test leak resistance of poppet valve against full pump pressure. Unusual conditions found during this test indicate that repair is necessary and the nozzle shall be removed from service.	Monthly	OM	
	196		C. Inspect storage racks for moisture or dirt accumulation. Correct conditions that may be attributing to accumulation of moisture or dirt in the storage racks.	Monthly	OM	
	197		D. Remove nozzle for inspection of content impinged upon the mesh screen. Clean and dry screens before nozzles are returned to service. If a strainer ball valve is installed upstream of the nozzle only the strainer in the strainer ball valve needs to be checked. Nozzles should not be used while strainers are removed from upstream strainer ball valves.	Monthly	OM	
	198		E. Tests nozzle interlocks. Ensure interlocks prevent release of fuel when the fueling nozzle is not properly connected. Adjust the seating of the poppet valve if required.	Monthly	OM	
	199		F. Check the operation of the manual valve crank assembly for smooth and positive motion on a special test stand.	Monthly	OM	
	200	Surge Suppressors (Section 4-7.4)	A. Inspect for nitrogen leaks.	Quarterly	SM	
	201		B. Bladder pressure inside surge suppressors must be validated and recharged as needed with nitrogen. Some surge suppressors are also equipped with needle valves. Settings established in the startup and commissioning documents should be maintained. Adjust nitrogen charge per manufacturer's recommendations.	Quarterly	SM	
	202	Aircraft Fueling Hoses (Section 4-7.5)	A. Visually inspect hoses for loose covers, cracks, brittle surface coatings, exposed wire braids, exposed reinforcement, flattening, kinks, and bulges or soft spots which might indicate broken or displaced reinforcement.	Monthly	OM	
	203		B. Pressurize hose to normal working pressure. Check flanged and threaded connections for leaks and inspect hose couplers for fluid seepage by pushing at the base of the coupling with thumbs. A hose softened by petroleum fluid seepage must be replaced.	Monthly	OM	
	204		C. Check for coupling slippage. Replace hose that shows signs of coupling slippage.	Quarterly	SM	
	205		D. For hot pit refueling hoses only, refer to Appendix D, Section D-2.1 Loading Hose Hydrostatic Test for loading hose hydrostatic testing requirements and procedures.	Annually	SM	
	206		E. Conduct test of petroleum fuel hose electrical resistivity using an electrostatic meter in accordance with NFPA 77 and API 2003.	Annually	SM	
	207	Overfill Valve for Product Recovery Tanks (Section 4-8.1)	A. Verify that a green light is illuminated on the pump control panel graphic display when OV is open.	Semi-annually	SM	
	208		B. Ensure pressure reservoir bladder is charged with 13 to 15 psig (90 to 103 kPa) of nitrogen and that the reservoir holds fuel pressure.	Semi-annually	SM	
	209		C. Verify that the OV closes when the control float is lifted (normally 95% full). Use the manual tester to lift the float. NOTE: When the float in the product recovery tank rises and the OV closes, the pressure in the pressure reservoir tank will decrease.	Semi-annually	SM	
	210		D. Verify that a red light is illuminated and that an alarm is activated on the pump control panel graphic display when OV is closed. Alarm is activated by a limit switch installed on the OV.	Semi-annually	SM	
	211		E. Ensure the pressure reservoir tank holds FTP deadhead pressure when the pump is deactivated.	Semi-annually	SM	
	212		F. Open and clean reservoir inlet strainer.	Semi-annually	SM	

	Task Number	Section	Description	Frequency	Responsibility	Notes
HYDR	213		G. Refer to Section 6-6.3 Thermal and Pressure Relief Valves for inspection and maintenance requirements of thermal and pressure relief valves.	As required	SM	
MARINE RECEIVING AND DISPENSING EQUIPMENT	214	Piers and Wharves Fuel Containment Systems (5-1.2)	A. Hydrostatically test the secondary containment and associated drainage systems to include containment concrete/sealant, drain inlets, drain lines and containment drain valves to ensure containment is liquid tight. This test may use opportune rainfall by holding rainwater in the containment system for one hour. Where evaporation is a concern, conduct the testing when this concern would be minimized, such as at night/early morning or during a time of year when this would not be as much of an issue. Record the water level at the start of the 60-minute (minimum) hold period. If the water level drops by 1/8 inch or more, perform and record an investigation to determine the cause and any required repairs. Refer to Appendix B for testing procedures and to document the testing.	Every 3 Years	SM	Note: Hydrostatic Containment testing shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan. All other Pier and Wharf Fuel Containment Systems inspection and maintenance shall be in accordance with PWS requirements.
	215	Marine Receipt (Section 5-2)	A. Conduct a shore side inspection of the pier or wharf for signs of damage as soon as marine barge or tanker disembarks.	After each use	OM	
	216		B. Inspect the ground switch used between the marine barge or tanker and the petroleum fuel receipt piping.	Monthly	OM	
	217		C. Inspect mooring lines, cleats, bollards, bits, pulley blocks, steel wire ropes, and winches. Use UFC 4-150-08 Inspection of Mooring Hardware as a guide when conducting inspections. Repair or replace damaged components as required.	Monthly	OM	
	218		D. Refer to Section 6-1 Pipe Testing and Inspections for inspection and maintenance requirements of petroleum fuel pipelines installed above water surfaces. These pipelines are regulated under 33 CFR 154 and 156. Any additional requirements listed under 33 CFR 154 and 156 shall also be followed.	As required	SM	Pipeline pressure testing shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.
	219		E. Refer to Section 5-5.1 Marine Transfer Hoses for inspection and maintenance requirements of petroleum fuel marine hoses.	As required	SM	
	220		F. Refer to Section 5-4 Marine Loading Arms for inspection and maintenance requirements of petroleum fuel marine loading arms.	As required	SM	This task is being performed by another CMP and not required under this contract.
	221		G. Refer to Section 3-6.4 Basket Strainers for inspection and maintenance requirements of basket strainers.	As required	SM	
	222		H. Refer to Section 3-7 Meters for inspection and maintenance requirements of petroleum fuel meters.	As required	SM	
	223		I. Refer to Section 3-8.2 Positive Displacement Pumps for inspection and maintenance requirements of stripper pumps.	As required	SM	This task is being performed by another CMP and not required under this contract.
	224		J. Refer to Section 9-1.6 Grounding Systems for inspection and maintenance requirements of grounding systems.	As required	SM	
	225	Marine Issue (Section 5-3)	A. Inspect pier or wharf for signs of damage as soon as marine barge or tanker disembarks.	After each use	OM	
	226		B. Inspect the ground switch between the fueling tanker/barge and the fuel system.	Monthly	OM	
	227		C. Inspect mooring lines, cleats, bollards, bits, pulley blocks, steel wire ropes, and winches. Use UFC 4-150-08 Inspection of Mooring Hardware as a guide when conducting inspections. Repair or replace damaged components as required.	Monthly	OM	
	228		D. Refer to Section 6-1 Pipe Testing and Inspections for inspection and maintenance requirements of petroleum fuel pipelines installed above water surfaces. These pipelines are regulated under 33 CFR 154 and 156. Any additional requirements listed under 33 CFR 154 and 156 shall also be followed.	As required	SM	Pipeline pressure testing shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.
	229		E. Refer to Section 3-6.4 Basket Strainers for inspection and maintenance requirements of basket strainers.	As required	SM	
	230		F. Refer to Section 3-8 Pumps for inspection and maintenance requirements of marine loading and stripper pumps.	As required	SM	Stripper pump maintenance is being performed by another CMP and not required under this contract.
	231		G. Refer to Section 3-7 Meters for inspection and maintenance requirements of petroleum fuel meters.	As required	SM	
	232		H. Refer to Section 5-5.1 Marine Transfer Hoses for inspection and maintenance requirements of petroleum fuel marine hoses.	As required	SM	
	233		I. Refer to Section 5-4 Marine Loading Arms for inspection and maintenance requirements of petroleum fuel marine loading arms.	As required	SM	This task is being performed by another CMP and not required under this contract.
	234		J. Refer to Section 9-1.6 Grounding Systems for inspection and maintenance requirements of grounding systems.	As required	SM	
	235	Marine Loading Arms (Section 5-4)	A. Check swivel for smooth operation. Check seals for signs of wear and discoloration which may indicate a seal or ball bearing failure.	Quarterly	SM	This task is being performed by another CMP and not required under this contract.
	236		B. Inspect ball bearings when accessible. Rough and/or uneven wear on the surface are indications of swivel joint failure.	Annually	SM	This task is being performed by another CMP and not required under this contract.
	237		C. Conduct pressure test of marine loading arms in accordance with 33 CFR 156.170 Equipment Tests and Inspections, Section (f)(1).	Annually	SM	This task is being performed by another CMP and not required under this contract.
	238	Marine Transfer Hoses (Section 5-5.1)	A. Visually inspect transfer hoses. Transfer hoses shall have no loose covers, kinks, bulges, soft spots, and no gouges, cuts or slashes that penetrate the hose reinforcement. Hoses shall also have no external deterioration.	Before each use	OM	
	239		B. Visually survey petroleum fuel marine hoses. Observe the general condition and look for fluid puddles, fine mists, physical damage such as jacket abrasion or deformation, and deteriorated joints. Use sense of smell to detect petroleum vapor. Look for improper hose handling that may overstress the hose by stretching, relative movement, or kinking.	During each use	OM	
	240		C. Refer to Appendix D, Section D-2.2 Marine and Underwater Transfer Hose Hydrostatic Test for marine transfer hose hydrostatic testing requirements and procedures.	Annually or not less than 30 days prior to the first transfer conducted past one year from the date of the last test and inspection.	SM	This task shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.
	241	Underwater Hoses (Section 5-5.2)	A. Refer to Appendix D, Section D- 2.2 Marine and Underwater Transfer Hose Hydrostatic Test for underwater hose hydrostatic testing requirements and procedures.	Annually or not less than 30 days prior to the first transfer conducted past one year from the date of the last test and inspection.	SM	This task shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.
	242	Single Point Mooring Systems (Section 5-7.1)	A. Inspect and, if necessary, repair or replace all mooring hawsers or lines, deck hose, chain, chair stoppers, flange adaptors, gaskets or other gear used in mooring the marine tanker and in connecting hoses.	Monthly	OM	
	243		B. Inspect air-compressor for proper operation.	Annually	SM	
	244		C. Inspect navigation aids and mooring buoy, in accordance with NAVFAC MO-124 Mooring Maintenance Manual, for evidence of damage and possible movement or dragging by vessels, current or winds.	Annually	SM	This task shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.
	245		D. Divers shall conduct underwater inspections of mooring chains, shackles and anchors attaching buoys to bay/harbor floors.	Annually	SM	This task shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.

	Task Number	Section	Description	Frequency	Responsibility	Notes
	246	Multi Point Mooring Systems (Section 5-7.2)	E. Conduct overhaul of single point mooring buoys every 3 to 5 years. Single point mooring buoys must be brought ashore for repair in these instances.	Every 5 years	SM	This task shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.
	247		A. Inspect and, if necessary, repair or replace all mooring hawsers or lines, deck hose, chain, chair stoppers, flange adaptors, gaskets or other deck gear used in mooring the marine tanker and in connecting underwater hoses.	Monthly	OM	
	248		B. Inspect navigation aids and mooring buoys, in accordance with NAVFAC MO-124 Mooring Maintenance Manual, for evidence of damage and possible movement or dragging by vessels, current or winds.	Annually	SM	This task shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.
	249		C. Divers shall conduct underwater inspections of mooring chains, shackles and anchors attaching buoys to bay/harbor floors.	Annually	SM	This task shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.
SUBMERGED PIPING SYSTEMS	250	Submerged Piping Systems (Section 5-8)	A. Inspect water above submerged pipelines and their seaward end for tell-tale petroleum fuel slicks indicating leakage from pipes or underwater hoses.	Weekly	OM	
	251		B. If equipped, electrically check the cathodic protection rectifier for proper performance.	Six times each calendar year with intervals not exceeding 2½ months	SM	This task shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.
	252		C. Divers shall inspect submerged pipe and hoses for signs of incipient failure or indications of rapid wear of parts subject to wave motion or abrasion on the ocean floor.	Semi-annually	SM	This task shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.
	253		D. Conduct annual pipe test as specified in Appendix G - Petroleum Fuel Pipeline Pressure testing Guidelines and Criteria. Testing requirements of marine pipelines are regulated under 33 CFR 154 and 156, particularly 33 CFR 156 Section 170.	Annually	SM	This task shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.
	254		E. Conduct cathodic protection tests on the protected pipeline as specified in Section 9.2.1 Cathodic Protection at least once each calendar year with intervals not exceeding 15 months between tests from consecutive years.	Annually	SM	This task shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.
	255	Boom Reels (Section 5-9)	A. Visually inspect hydraulic drives and hose connections for leaks.	Quarterly	SM	
	256		B. Grease bearings.	Quarterly	SM	
	257		C. Inspected boom reel for signs of corrosion. Inspect breaking system and ensure it is in good working order.	Quarterly	SM	
	258		D. Inspect boom for wear, rips, and tears. Repair or replace as required to ensure containment of petroleum fuel in the event of a spill.	Annually	SM	Repairs shall be performed by SO.
ON-BASE PIPELINES	259	On-Base Pipelines (Section 6-1.1)	A. Conduct petroleum fuel pipeline visual inspection of aboveground piping in accordance with Section 6-1.5 Pipeline Visual Inspection.	Quarterly	SM	Repairs shall be performed by SO.
	260		B. Conduct line walk in areas of petroleum fuel piping in accordance with Section 6-1.6 Line Walk.	Conduct during transfer operations, or monthly, at a minimum	OM	
	261		C. Conduct annual test as specified in Appendix G - Petroleum Fuel Pipeline Pressure Testing Guidelines and Criteria.	Annually	SM	This task shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.
	262		D. Conduct cathodic protection tests as specified in Section 9.2.1 Cathodic Protection on protected petroleum fuel pipelines at least once each calendar year, but with intervals not exceeding 15 months.	Annually	SM	This task shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.
	263		E. Conduct five year test as specified in Appendix G - Petroleum Fuel Pipeline Pressure Testing Guidelines and Criteria.	Every five years	SM	This task shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.
	264		F. Conduct petroleum fuel pipeline API 570 inspection in accordance with Section 6-1.9 API 570 Inspections.	Every 5 or 10 years depending on API class piping or in accordance with Pipeline Integrity Management Plan (PIMP).	SM	This task shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.
	265		G. Conduct petroleum fuel pipeline cleaning in accordance with Section 6-2 General Pipeline Cleaning.	As required to ensure fuel quality.	SM	This task shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.
INTER-TERMINAL PIPELINES	266	Non-DOT Regulated (Section 6-1.2.1)	A. Conduct petroleum fuel pipeline volume check in accordance with Section 6-1.8 Volume Check.	Monthly	OM	This task shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.
	267		B. Conduct line patrol in areas of underground petroleum fuel pipeline in accordance with Section 6-1.7 Line Patrol.	Annually	OM	
	268		C. Government operated inter-terminal petroleum fuel pipelines shall follow the maintenance requirements listed in Section 6-1.1.1 for On-Base Pipelines.	As required	SM	This task shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.
	269	Aboveground Piping (Section 6-1.3)	A. Conduct petroleum fuel piping visual inspection in accordance with Section 6-1.5 Pipeline Visual Inspection.	Weekly	OM	
	270		B. Conduct petroleum fuel piping annual test as specified in Appendix G - Petroleum Fuel Pipeline Pressure Testing Guidelines and Criteria.	Annually	SM	This task shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.
	271		C. Conduct petroleum fuel piping API 570 inspection in accordance with Section 6-1.9 API 570 Inspections.	Every 5 or 10 years depending on API class piping or in accordance with Pipeline Integrity Management Plan (PIMP).	SM	This task shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.
	272		D. Conduct cleaning of petroleum fuel piping in accordance with Section 6-2 General Pipeline Cleaning.	As required to ensure fuel quality.	SM	This task shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.
	273	Double-Wall Piping (Section 6-1.4)	A. Conduct petroleum fuel pipeline visual inspection of aboveground piping in accordance with Section 6-1.5 Pipeline Visual Inspection.	Monthly	OM	
	274		B. Conduct annual carrier pipe test as specified in Appendix G - Petroleum Fuel Pipeline Pressure Testing Guidelines and Criteria.	Annually	SM	This task shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.
	275		C. Conduct cathodic protection tests as specified in Section 9.2.1 Cathodic Protection on protected petroleum fuel pipelines at least once each calendar year, but with intervals not exceeding 15 months.	Annually	SM	This task shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.
	276		D. Conduct containment pipe test as specified in Appendix G - Petroleum Fuel Pipeline Pressure Testing Guidelines and Criteria.	Every three years	SM	This task shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.
	277		E. Conduct petroleum fuel pipeline API 570 inspection in accordance with Section 6-1.9 API 570 Inspections.	Every 5 or 10 years depending on API class piping or in accordance with Pipeline Integrity Management Plan (PIMP).	SM	This task shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.

	Task Number	Section	Description	Frequency	Responsibility	Notes
	278		F. Conduct petroleum fuel pipeline cleaning in accordance with Section 6-2 General Pipeline Cleaning.	As required to ensure fuel quality.	SM	This task shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.
MANUAL VALVES	279	Plug Valves - Lubricated (Section 6-6.2.1)	A. Open and close valve to check for ease of operation.	Quarterly	SM	
	280		B. Lubricate valve operator stems and all grease fittings.	Semi-annually	SM	
	281		C. Inspect valve exterior for corrosion and tightness of bolts. Repaint/tighten as required.	Semi-annually	SM	Per PWS Touch-up Coating Repair
	282	Plug Valves - Non-lubricated (Section 6-6.2.2)	A. Open and close valve to check for ease of operation. Adjust or replace packing as needed.	Quarterly	SM	
	283		B. Inspect valve exterior for corrosion and tightness of bolts. Repaint and retighten as required.	Semi-annually	SM	
	284		A. Open and close valve to check for ease of operation. Adjust or replace packing as needed.	Quarterly	SM	
	285	Gate Valves (Section 6-6.2.3)	B. Lubricate valve operator stem.	Semi-annually	SM	
	286		C. Inspect valve exterior for corrosion and tightness of bolts. Repaint and retighten as required.	Semi-annually	SM	Per PWS Touch-up Coating Repair
	287		A. Open and close valve to check for ease of operation.	Quarterly	SM	
	288	Ball Valves (Section 6-6.2.4)	B. Lubricate overhead ball valve chain operator gears.	Quarterly	SM	
	289		C. Adjust packing per manufacturer's specifications.	Quarterly	SM	
	290		D. Inspect valve exterior for corrosion and tightness of bolts. Repaint/tighten as required.	Quarterly	SM	Per PWS Touch-up Coating Repair
	291		E. Refer to Section 6-6.2.10 Manual Valve Gear Operators for inspection and maintenance of gear operators if equipped.	As required	SM	
	292		A. Open and close valve to check for ease of operation.	Quarterly	SM	
	293		B. Lubricate overhead valve chain operator gears if equipped.	Quarterly	SM	
	294		C. Adjust packing per manufacturer's specifications.	Quarterly	SM	
	295	Double Block and Bleed Valves (Section 6-6.2.5)	D. Inspect valve exterior for corrosion and tightness of bolts. Repaint and tighten as required.	Quarterly	SM	Per PWS Touch-up Coating Repair
	296		E. Operate the body cavity drain when valve is in closed position to ensure that the valve is closing properly.	Quarterly	SM	
			F. Keep the valve operator housing full of lubricant to displace and prevent moisture from accumulating and freezing, in accordance with manufacturer's recommendations.	Semi-annually	SM	
	295		G. Remove bottom drain plug and drain valve.	Annually	SM	
	296		H. Refer to Section 6-6.2.10 Manual Valve Gear Operators for inspection and maintenance of gear operators if equipped.	As required	SM	
	297		I. Some double block and bleed valves are equipped with integrated pressure/thermal relief valves. Refer to Section 6-6.3 Thermal and Pressure Relief Valves for inspection and maintenance requirements of pressure/thermal relief valves.	As required	SM	
	298	Butterfly Valves (Section 6-6.2.6)	A. Open and close valve to check for ease of operation. Ensure that lever operators and locking mechanisms are in place and working properly.	Quarterly	SM	
	299		B. Adjust packing per manufacturer's specifications as needed. If butterfly valves are leaking or not shutting off flow, tightening the gland flange to tighten the stem packing or remove the valve from service and replace the seats as necessary.	Quarterly	SM	
	300		C. Inspect valve exterior for corrosion and tightness of bolts. Repaint and retighten as required.	Quarterly	SM	Per PWS Touch-up Coating Repair
	301		A. Open and close valve to check for ease of operation.	Quarterly	SM	
	302	Globe Valves (Section 6-6.2.7)	B. Adjust packing per manufacturer's specifications as needed.	Quarterly	SM	
	303		C. Inspect valve exterior for corrosion and tightness of bolts. Repaint/tighten as required.	Quarterly	SM	Per PWS Touch-up Coating Repair
	304	Check Valves (Section 6-6.2.8)	A. Use external test lever to make sure the valve is not sticking if equipped. If a check valve is suspected of not checking and cannot be serviced in place, it shall be removed from the piping system and serviced in a shop.	Quarterly	SM	Repairs that require servicing the valve in a shop should be performed through a service order.
	305		B. Inspect valve exterior for corrosion and tightness of bolts. Repaint and retighten as required.	Quarterly	SM	Per PWS Touch-up Coating Repair
	306	Line Blanks, Ring Spacers, and Spectacle Blinds (Section 6-6.2.9)	A. Inspect exposed side of spectacle blinds. The exposed side shall be kept clean and free of corrosion.	Quarterly	SM	
	307		B. Spectacle blinds should be inspected to ensure they are installed with the correct orientation for the desired flow or no-flow condition.	Quarterly	SM	
	308	Manual Valve Gear Operators (Section 6-6.2.10)	A. Lubricate gear driven operators and check for smooth operation.	Quarterly	SM	
RELIEF VALVES	309	Thermal and Pressure Relief Valves (Section 6-6.3)	A. Thermal and pressure relief valves shall be inspected for signs of leak-by. Inspect relief valves for leaks by visually inspecting downstream flow indicators (if installed) for flow. If no flow indicators are installed listen for possible leaks. If suspect: isolate and test the relief valve; check opening pressure; and verify re-sealing. Malfunctioning valves shall be repaired or replaced.	Monthly for Army, Navy, USMC; Quarterly for AF	OM for Army, Navy, USMC; SM for AF	Maintenance procedure shall include process to verify that the valve has properly resealed after all maintenance activities are performed on pressure relief valves or thermal and pressure relief valves.
	310		B. Ensure manual isolation valves installed upstream and downstream of thermal and pressure relief valves are open with valve handles are removed, wired open or locked.	Monthly for Army, Navy, USMC; Quarterly for AF	OM for Army, Navy, USMC; SM for AF	
	311		C. Inspect valve exterior of thermal and pressure relief valves for corrosion. Repaint as required. Information plates attached to thermal and pressure relief valves shall not be painted over.	Quarterly	SM	Per PWS Touch-up Coating Repair
	312		D. Verify thermal and pressure relief valve setting by consulting as-built and historical data.	Annually	SM	
	313		E. Thermal and pressure relief valves shall be validated for proper calibration by isolating the valve and using the test connection provided on the piping in conjunction with a hand pump and portable reservoir. The operating pressure shall be checked against the set pressure listed on the stamped information plate attached to the valve. The operating pressure shall be adjusted to the stamped set pressure if necessary. If there is no test connection provided, isolate the relief valve and remove the valve to test. If there is no valve isolation or test connection, consider adding these to simplify future testing.	Annually	SM	Maintenance procedure shall include process to verify that the valve has properly resealed after all maintenance activities are performed on pressure relief valves or thermal and pressure relief valves.
SEMI-AUTOMATIC VALVES	314	Fire Valves (Section 6-6.4.1)	A. Ensure the fusible link mechanism is attached properly to actuate in case of a fire and that it has not been by-passed, blocked, or damaged in any manner. Ensure the fusible link is not filled with debris or paint which could impact operation. Maintain fusible links per manufacturer's recommendation.	Quarterly	SM	
	315		B. Check the closing mechanism to ensure that it closes the valve properly.	Annually	SM	
	316	Fusible Link Butterfly Valves (Section 6-6.4.2)	A. Ensure the fusible link mechanism is attached properly to actuate in case of a fire and that it has not been by-passed, blocked, or damaged in any manner. Ensure the fusible link is not filled with debris or paint which could impact operation. Maintain fusible links per manufacturer's recommendation.	Quarterly	SM	
	317		B. Test the operation of spring closure unit. Ensure that the spring actuator closes the valve and that the valve closes securely against the seat.	Annually	SM	
	318		C. Refer to Section 6-6.2.6 Butterfly Valves for additional inspection and maintenance requirements of butterfly valves.	As required	SM	
	319		A. Verify TFV maintains 35 psig (240 kPa) nozzle pressure at a flow range of 50 to 600 gpm (3 to 38 lps).	Quarterly	SM	
	320		B. Verify TFV closes rapidly when outlet pressure exceeds control set point.	Quarterly	SM	

	Task Number	Section	Description	Frequency	Responsibility	Notes
AUTOMATIC VALVES	321	Truck Fill Valves (Section 6-6.5.1)	C. Verify TFV opens when the deadman control lever is pressed.	Quarterly	SM	
	322		D. Verify TFV closes after the deadman control lever is released.	Quarterly	SM	
	323		E. If equipped, verify operation of solenoid connected to grounding verification system. Ground verification system should energize solenoid when an acceptable ground is detected by the ground verification unit.	Quarterly	SM	
	324		F. Systems that have overflow protection systems shall be inspected and maintained concurrently with the inspection and maintenance of TFVs.	Quarterly	SM	
	325	Motor Operators (Section 6-6.6)	G. Refer to Section 4-3.2.1 General System Control Valves for additional inspection and maintenance requirements.	As required	SM	
	326		A. Visually inspect motor operators to ensure smooth movement during opening and closing operation and adjust, if necessary, to ensure that they are opening and closing fully. Listen for and investigate unusual noises during operation.	Quarterly	SM	
	327		B. Lubricate mechanical overrides (if equipped).	Quarterly	SM	
	328		C. Refer to Section 9-1.7 Electric Motors for inspection and maintenance requirements of electric motors.	As required	SM	
PRESSURE/VACUUM INSTRUMENTATION	329	Pressure and Pressure/Vacuum Gauges (Section 6-7.1)	A. Check operation of gauge. Ensure gauge is indicating pressure of the system.	Monthly	OM	
	330		B. Clean outside of gauge glass.	Quarterly	SM	
	331		C. Inspect liquid filled gauges for leakage, refill/replace as needed.	Semi-annually	SM	
	332		D. Conduct calibration check by comparing readings of the process gauge with the readings of a certified master calibration gauge which has been calibrated within the last year. The process gauge and the master calibration gauge shall be connected to the same pressure source for testing. Verify accuracy of gauge is within $\pm 2\%$ of full scale. Calibrate gauge if required.	Annually	SM	
	333	Differential Pressure Gauges (Section 6-7.2)	A. Verify proper operation of differential gauge in accordance with gauge manufacturer's procedures.	Quarterly	SM	
	334		B. Clean outside of gauge glass.	Quarterly	OM	
	335		C. Conduct calibration check by comparing readings of the differential process gauge with the readings of a certified differential master calibration gauge which has been calibrated within the last year. The differential process gauge and the differential master calibration gauge shall be connected to the same pressure source for testing. Verify accuracy of gauge is within $\pm 2\%$ of full scale. Calibrate if required.	Annually	SM	
	336		D. Some differential pressure gauges have a small gauge protection filter located at the high pressure inlet of the gauge that must be checked and replaced as needed. Filters need to be replaced if the indicator is moving slow or sluggishly inside the sight glass or if the sight glass is dirty. Refer to manufacturer's operation and maintenance manual for filter replacement procedure.	Annually for inspections and maximum 5 years of service between filter replacements.	SM	This task shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.
	337	Pressure Transmitters (Section 6-7.3)	A. Inspect the exterior of the transmitter enclosure for accumulated oil, dust, and dirt. Clean if required.	Quarterly	SM	
	338		B. Check that both enclosure caps are fully threaded onto the enclosure, compressing the O-ring between the cap and the enclosure. The O-ring must not be cracked, broken, or otherwise damaged.	Quarterly	SM	
	339		C. Inspect the display viewing glass for cleanliness and damage. Replace the enclosure cap assembly if the glass is damaged or missing. No accumulation of dust, dirt, or water (condensate) should be present inside the enclosure.	Quarterly	SM	
	340		D. Inspect transmitter and mounting bracket hardware for tightness. Tighten loose hardware as necessary.	Quarterly	SM	
	341		E. Inspect for loose, bent, or cracked sensing lines. Replace damaged sensing lines.	Quarterly	SM	Repairs shall be performed by SO.
	342		F. Check operation of transmitter. Ensure transmitter is indicating accurate pressure of the system.	Quarterly	SM	
	343		G. Bleed sensing lines between the transmitter and the main line to ensure they are clean and free of suspended solids and air.	Semi-annually	SM	
	344		H. Check that all wire connections inside enclosure are tight.	Annually	SM	
	345		I. Pressure Transmitters (PTs) and Pressure Indicating Transmitters (PITs) must be calibrated mechanically and electrically with test equipment and adjusted if applicable. The presence of air in the sensing line of a pressure transmitter is a common cause for failure. Conduct calibration check by comparing readings of the PT or PIT with the readings of a certified master calibration gauge which has been calibrated within the last year. The PT or PIT and the master calibration gauge shall be connected to the same pressure source for testing. Verify accuracy of PT or PIT gauge is within $\pm 2\%$ of full scale. Calibrate in accordance with manufacturer's operation and maintenance manual if required.	Annually	SM	
	346	Differential Pressure Transmitters (Section 6-7.4)	A. Inspect the exterior of the transmitter enclosure for accumulated oil, dust, and dirt. Clean as required.	Quarterly	SM	
	347		B. Check that both enclosure caps are fully threaded onto the enclosure, compressing the O-ring between the cap and the enclosure. The O-ring must not be cracked, broken, or otherwise damaged.	Quarterly	SM	
	348		C. Inspect the display viewing glass for cleanliness and damage. Replace the enclosure cap assembly if the glass is damaged or missing. No accumulation of dust, dirt, or water (condensate) should be present inside the enclosure.	Quarterly	SM	
	349		D. Inspect transmitter and mounting bracket hardware for tightness. Tighten loose hardware as necessary.	Quarterly	SM	
	350		E. Inspect for loose, bent, or cracked sensing lines. Replace damaged sensing lines.	Quarterly	SM	
	351		F. Check operation of transmitter. Ensure transmitter is indicating accurate pressure of the system.	Quarterly	SM	
	352		G. Bleed sensing lines between the transmitter and the main line to ensure they are clean and free of suspended solids and air.	Semi-annually	SM	
	353		H. Check that all wire connections inside enclosure are tight.	Annually	SM	
	354		I. DPTs must be calibrated mechanically and electrically with test equipment and adjusted, if applicable. The presence of air in sensing lines of differential pressure transmitters is a common cause for failure. Conduct calibration check by comparing readings of the DPT with the readings of a certified differential master calibration gauge which has been calibrated within the last year. The DPT and the differential master calibration gauge shall be connected to the same pressure source for testing. Verify accuracy of DPT is within $\pm 2\%$ of full scale. Calibrate in accordance with manufacturer's operation and maintenance manual if required.	Annually	SM	

	Task Number	Section	Description	Frequency	Responsibility	Notes
FLEXIBLE BALL JOINTS	355	Flexible Ball Joints (Section 6-8)	A. Lubricate ball joints and inspect for wear and stress.	Quarterly	SM	
THERMOMETERS	356	Dial Thermometer (Section 6-9.1)	A. Inspect thermometer for cracked face and proper operational condition. Replace if damaged.	Quarterly	SM	
	357		B. Check accuracy of thermometer against calibrated master thermometer. Ensure process and calibrated master thermometer are reading the same heat source. Verify accuracy of thermometer is within $\pm 2\%$ of full scale. Calibrate process thermometer if required.	Annually	SM	
PIPE COATINGS	358	Aboveground Piping and Equipment Coatings (Section 6-10.1)	A. Visually inspect coatings for signs of deterioration, corrosion or damage. Repair damaged or deteriorated coatings.	Quarterly	SM	
UNDERGROUND FUEL PITS	359	Isolation Valve Pits (Section 6-11.1)	A. Isolation valve pits should be inspected to ensure that the pits are dry and clean and that all components within the pit are clean and in good working order. Maintain seals and boot seals as appropriate. Obtain necessary confined space entry permits before entry. Inspect the pit for signs of fuel or water. Water or fuel should be removed from the pit as soon as possible and the source of water infiltration or fuel leak determined.	Monthly, or more often based on local conditions	OM	
	360		B. Check for cracks in concrete and check piping penetrations through pit wall or bottom to ensure that mechanical seals and boot seals are in good working condition and are allowing no seepage of water into the pits. Make note of cracks in concrete and schedule maintenance as necessary. Check for fuel leaks at all flanged and other piping connections. Check for rusted or deteriorated ladders or grating platforms that might make entry unsafe. Check pit lids for proper sealing. Check rolling pit covers for ease of operation and signs of deterioration, damage or corrosion. Make sure required locks are in place and locking mechanisms are not broken.	Monthly, or more often based on local conditions	OM	
	361	Hydrant Fuel Pits (Section 6-11.2)	A. Hydrant fuel pits shall be inspected to ensure that they are dry and clean and that all fueling components within the pit are clean and in good working order. Obtain necessary confined space entry permits before entry. Inspect the pit for fuel or water. Fuel or water found in the pit shall be sumped out as soon as possible.	Monthly, or more often based on local conditions	OM	
	362		B. Check pipe penetrations through pit walls or bottom to ensure that mechanical and boot seals are in good working condition and are allowing no water seepage into the pits.	Monthly, or more often based on local conditions	OM	
	363		C. Check for fuel leaks at all flanged and pipe connections.	Monthly, or more often based on local conditions	OM	
	364		D. Check pit lids to ensure that seals are in good working order and are preventing water entry into the pits.	Monthly, or more often based on local conditions	OM	
	365		E. Inspect hydrant fuel pit bonding cables for corrosion and ensure electrical continuity between bonded equipment.	Monthly, or more often based on local conditions	OM	
	366	High Point Vent Pits (Section 6-11.3)	A. Inspect high point vent pits to ensure they are dry and free of water and other debris and that pit and piping components are leak free and in good working condition. Inspect the pit for fuel or water. Fuel or water found in the pit shall be sumped out as soon as possible.	Monthly	OM	
	367		B. Check pipe penetrations through pit walls or bottom to ensure that mechanical and boot seals are in good working condition and are allowing no water seepage into the pits.	Monthly	OM	
	368		C. Check pit lid seals for deterioration and replace as necessary.	Monthly	OM	
	369		D. Ensure that high point vent valves, quick-disconnect couplings or pit lids are lockable and that locking mechanisms are in good working order.	Monthly	OM	
	370		E. Inspect high point vent pit bonding cables for corrosion and ensure electrical continuity between bonded equipment.	Monthly	OM	
	371	Low Point Drain Pits (Section 6-11.4)	A. Inspect low point drain pits to ensure they are dry and free of water and other debris and that all pit and piping components are leak free and in good working condition. Inspect the pit for fuel or water. Fuel or water found in the pit shall be sumped out as soon as possible.	Monthly	OM	
	372		B. Check pipe penetrations through pit wall or bottom to ensure that mechanical seals and boot seals are in good working condition and are allowing no water seepage into the pits.	Monthly	OM	
	373		C. Check pit lid seals for deterioration and replace as necessary.	Monthly	OM	
	374		D. Ensure that low point vent valves, quick-disconnect couplings or pit lids are lockable and that locking mechanisms are in good working order.	Monthly	OM	
	375		E. Inspect low point drain pit bonding cables for corrosion and ensure electrical continuity between bonded equipment.	Monthly	OM	
	376	Lateral Control Pits (Section 6-11.5)	A. Inspect lateral control pits to ensure they are dry and free of water and other debris and that all pit and piping components are leak free and in good working condition. Inspect the pit for fuel or water. Fuel or water found in the pit shall be sumped out as soon as possible.	Monthly	OM	
	377		B. Check pipe penetrations through pit wall or bottom to ensure that mechanical seals and boot seals are in good working condition and are allowing no water seepage into the pit.	Monthly	OM	
	378		C. Check pit lid seals for deterioration and replace as necessary.	Monthly	OM	
	379		D. Check for fuel leaks at all flanged and other piping connections.	Monthly	OM	
	380		E. Ensure that pit lids are lockable and that locking mechanisms are in good working order.	Monthly	OM	
	381		F. Inspect lateral control pit bonding cables for corrosion and ensure electrical continuity between bonded equipment.	Monthly	OM	
MINOR PIPING EQUIPMENT	382	Low Point Drains (Section 6-12.1)	A. Visually inspect low point drains. Ensure that quick-disconnect dust caps are in place and that valves are locked closed.	Weekly	OM	
	383		B. Operate low point drains when system is not under operating pressure. If there is an absence of sufficient line pressure close the low point drain and pressurize the system. Once adequate pressure is available, continue draining until the piping fuel sample is clear and bright with no visible water.	Monthly or as required by local conditions. Verify low point drains are closed after maintenance.	OM	
	384	High Point Vents (Section 6-12.2)	A. Inspect high point vents. If fuel leaks are observed they should be repaired as soon as possible. Ensure that quick-disconnect dust caps are in place and that high point vent valves are locked.	Weekly	OM	
	385	Sight Flow Indicators (Section 6-12.3)	A. Verify there are no leaks around pipe connection fittings and glass seals. Also check glass for indications of cracks.	Daily or at each use	OM	
MONIT	386		A. Ensure the monitoring panel associated with the rope sensor(s) is powered on and no alarms are present.	Daily	OM	

	Task Number	Section	Description	Frequency	Responsibility	Notes
ELECTRONIC RELEASE DETECTION	387	Rope Sensor Systems (Section 6-13.1.1)	B. Test rope sensor system and ensure it is functional.	Annually	SM	This task shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.
	388	Point Sensor - Dry (Section 6-13.1.2)	A. Ensure the monitoring panel associated with the point sensor(s) is powered on and no alarms are present.	Daily	OM	
	389		B. Ensure monitoring space is clear and free of debris and liquid.	Monthly	OM	
	390		C. Test sensor and ensure it is functional.	Annually	SM	This task shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.
	391	Visual Monitoring (Section 6-14.1)	A. Visually inspect ports for signs of leaks. Remove debris or foreign objects obstructing the view.	Weekly	OM	
FILLING STATION DISPENSERS	392	Dispenser Nozzles (Section 7-2)	A. Inspect dispenser nozzle spout. Ensure it is tight, round, has no cracks, or excessive wear. Inspect automatic shutoff hole. Ensure the hole is open and free of obstructions. Inspect nozzle hold-open latch. Ensure the latch is straight, moves freely, and the return spring operates correctly. Inspect body of nozzle. Ensure the body is in good condition and that the valve stem is clean and free of fuel. Inspect the nozzle to hose connection and ensure it is clean and free of fuel.	Daily	OM	
	393		B. Dispenser nozzle handles must be inspected for an expiration date established by the manufacturer. Nozzles must be replaced before the indicated expiration date. Task deleted in UFC 3-460-03 Change 1.		N/A	This task has been deleted.
	394		C. Test automatic shutoff feature and ensure it is operating properly. Test automatic shutoff at all nozzle hold-open latch positions.	Annually	SM	
	395	Dispenser Hoses (Section 7-3)	A. Inspect dispenser hoses and hose whips for gouges, cuts, blisters, or outside wear that may lead to rupture during use. Replace hose or hose whips that show signs of wear. Inspect connection points of hoses and hose whips to the dispenser, breakaways, swivels, and the nozzle and ensure the connection points are clean and free of fuel.	Daily	OM	
	396	Breakaways (Section 7-4)	A. Inspect breakaways for loose connections and signs of damage to poppets. Ensure breakaways are clean and free of fuel.	Daily	OM	
	397		B. Inspect breakaway for an expiration date established by the manufacturer. Breakaways must be replaced before the indicated expiration date.	Monthly	OM	
	398	Swivels (Section 7-5)	A. Inspect swivel for loose connections and signs of damage. Ensure swivel rotates easily and is clean and free of fuel.	Daily	OM	
	399		B. Inspect swivel for expiration date established by manufacturer. Swivels must be replaced before the indicated expiration date.	Monthly	OM	
	400	Hose Retriever (Section 7-6)	A. Test hose retriever and ensure it is operating correctly and supporting the hose.	Monthly	OM	
	401	Dispenser Cabinet (Section 7-7)	A. Inspect outside of cabinet and ensure it is free of damage. Inspect for fuel stains on the concrete island around the cabinet and on the outside of the cabinet. Ensure the cabinet is free of dirt and fuel.	Monthly	OM	
	402		B. Open both sides of the cabinet and inspect the inside of the cabinet. Ensure the inside of the cabinet and all of the components inside the cabinet are clean and free of fuel.	Monthly	OM	
	403		C. Ensure door panels and locks operate easily. Inspect anchor bolts of cabinet to dispenser island and ensure the bolts are in good condition.	Annually	SM	
	404	Dispenser Meters (Section 7-8)	A. Inspect meter and ensure meter is clean and free of fuel. Ensure calibration mechanism is sealed.	Monthly	OM	
	405		B. Since moving parts inside meters are subject to wear, periodic calibration is necessary. Meters shall be recalibrated utilizing a certified 5 gallon (20 liter) prover can or other approved method. Meters are considered satisfactory for further operation when the error does not exceed ±0.2% of actual quantity delivered.	Annually	SM	
	406	Dispenser Filters (Section 7-9)	A. Inspect filter and ensure filter is clean and free of fuel and that filter is labeled with a legible installation date.	Monthly	OM	
	407		B. Replace dispenser filters annually or when a change in flow rate is noted.	Annually or as needed	SM	Routine filter changes shall be performed as part of the maintenance activities. Filter changes required due to a repair or other circumstance beyond normal system operation shall be performed by service order.
	408	Dispenser Strainers (Section 7-10)	A. Inspect and clean strainers. Inspect strainer cover gasket for cracks, distortion, and dry rot. If breaks are detected in strainer mesh, replace the strainer.	Annually	SM	
GROUND FUEL PIPING	409	Ground Vehicle Fuel Piping (Section 7-11)	A. Visually inspect aboveground lines for leaks. Shut down systems that are found with leaks and repair. *	Daily	OM	*Recommend shut down of facility to FMSR.
	410		B. Visually inspect leak detection systems installed on underground piping. Inspections include line leak detectors and leak detection sensors installed in transition sumps and dispenser sumps. Perform leak testing on pressurized underground piping with installed leak detection equipment and record results.	Quarterly	SM	
	411		C. Test leak detection systems installed on underground piping used for ground vehicle petroleum fuel products. Underground leak detection systems include discrete detection sensors installed in transition and dispenser sumps, and line leak detectors installed at the outlet of pumps used to supply pressurized liquid petroleum fuel to underground lines. Repair faulty components. Execution of this work may require State certification or license.	Annually	SM	
	412		D. Conduct service station aboveground piping annual test as outlined in Appendix G - Petroleum Fuel Pipeline Pressure Testing Guidelines and Criteria. Execution of this work may require State certification or license.	Annually	SM	
	413		E. Conduct service station underground piping annual test outlined in Appendix G - Petroleum Fuel Pipeline Pressure Testing Guidelines and Criteria. Execution of this work may require State certification or license.	Annually	SM	
	414		F. Refer to Section 2.7 Signage and Markings for inspection and maintenance requirements of ground vehicle petroleum fuel pipe markings.	As required	SM	
	415		G. Refer to Section 6-10.1 Aboveground Piping and Equipment Coatings for inspection and maintenance requirements of ground vehicle petroleum fuel pipe coatings.	As required	SM	
	416	Emergency Shutoff Valves (Shear Valves) (Section 7-12)	A. Inspect stabilizer bar to ensure that it is securely mounted below the base of the dispenser. Inspect the mounting bolts that secure the emergency shutoff valve to the stabilizer bar.	Monthly	OM	
	417		B. Inspect fusible link and ensure it is not obstructed. Ensure valve body is clean and free of fuel.	Monthly	OM	
	418		C. Inspect mechanical links of the valve for correct operation. Conduct test of valve to ensure it operates correctly. Execution of this work may require State certification or license.	Annually	SM	
	419	Dispenser Sumps (Section 7-13)	A. Inspect for signs of water, fuel, trash, and debris inside sumps. Remove and properly dispose of collected water, fuel, trash, and debris. Visually inspect penetration fittings. If fuel or water is detected investigate the source and repair.	Monthly	OM	
	420		B. Inspect sump pipe transition fittings for tears, cracks, or other signs of deterioration. Check hose clamp seals to ensure they are securely tightened.	Quarterly	SM	
	421		C. Test dispenser sumps and ensure they are liquid tight by using vacuum, pressure, or liquid testing in accordance with 40 CFR 280, Section 43.	Every three years	SM	This task shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.

	Task Number	Section	Description	Frequency	Responsibility	Notes
	422	Transition Sumps (Section 7-14)	A. Inspect for signs of water, fuel, trash, and debris inside sumps. Remove and properly dispose of collected water, fuel, trash, and debris. Visually inspect penetration fittings. If fuel or water is detected investigate the source and repair.	Monthly	OM	
	423		B. Inspect sump pipe transition fittings for tears, cracks, or other signs of deterioration. Check hose clamp seals to ensure they are securely tightened.	Quarterly	SM	
	424		C. Test sumps and ensure they are liquid tight by using vacuum, pressure, or liquid testing in accordance with 40 CFR 280, Section 43.	Every three years	SM	This task shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.
	425	Remote Dispenser Pumps (Section 7-15.1)	A. Refer to Section 7-19.1.2 Automatic Line Leak Detector for maintenance and inspection requirements of automatic line leak detectors installed on submersible turbine pumps.	As required	SM	
	426		B. Refer to Section 3-8.1.3 Vertical Turbine/Submerged Turbine Pumps for inspection and maintenance requirements of remote dispenser pumps.	As required	SM	
	427	Self-Contained Dispenser Pumps (Section 7-15.2)	A. Inspect self-contained dispenser pump v-belt drives for proper tension and excess wear. Replace belt as recommended by manufacturer.	Quarterly	SM	
	428		B. Inspect pump body. Ensure pump body is clean and free of fuel. Inspect air eliminator. Ensure air eliminator is clean and free of fuel and that the vent tube is not obstructed.	Quarterly	SM	
EFSO SYSTEMS	429	EFSO Systems (Section 7-16)	A. Check the operation of the EFSO system by activating the fueling system and then pressing each of the EFSO buttons. Ensure that each button disables power to all of the dispensers and fuel pumps installed at the service station.	Quarterly	SM	
	430		B. Refer to Section 2-7 Signage and Markings for inspection and maintenance requirements of EFSO pushbutton signs.	As required	SM	
VAPOR RECOVERY	431	Stage I Vapor Recovery (Section 7-17.1)	A. Inspect vapor recovery hoses for gouges, cuts or outside wear that may result in vapor leaks.	Daily or before each use	OM	
	432		B. Inspect caps and camlock fittings for tightness and leaks.	Quarterly	SM	
	433		C. Refer to Section 7-11 Ground Vehicle Fuel Piping for inspection and maintenance requirements of Stage I vapor recovery piping.	As required	SM	
	434	Stage II Vapor Recovery (Section 7-17.2)	A. There are several approved vendors for Stage II Vapor Recovery systems. Consult the manufacturer's operation and maintenance manual that was provided with the system for periodic maintenance requirements.	Per manufacturer's specifications	SM	
	435	Vapor Burners (Section 7-17.3)	A. Inspect vapor burners to ensure that the pilot flame system is operating properly. Fans, duct work, and dampeners must also be inspected to ensure proper air to fuel vapor mixtures allow for complete burns.	Quarterly	SM	
	436		B. Inspect burner knock out pots for condensed fuel vapors and water if equipped.	Quarterly	SM	
	437		C. Inspect thermowells and gas detection monitors for operability.	Quarterly	SM	
ELECTRONIC RELEASE DETECTION MON	438	Point Sensor - Dry (Section 7-19.1.1)	A. Ensure the monitoring panel associated with the point sensor(s) is powered on and no alarms are present.	Quarterly	OM	
	439		B. Ensure monitoring space is clear and free of debris and liquid.	Monthly	OM	
	440		C. Test sensor and ensure it is functional.	Annually	SM	This task shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.
	441	Automatic Line Leak Detector (Section 7-19.1.2)	A. Ensure the monitoring panel associated with the detector(s) is powered on and no alarms are present.	Daily	OM	
	442		B. Simulate a 3 gallons per hour leak at 10 pounds per square inch; the automatic line leak detector must activate within one hour. A licensed and/or certified technician is required to, test, troubleshoot, or calibrate for operation.	Annually	SM	This task shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.
	443	Visual Monitoring (Section 7-20.1)	A. Visually inspect at inspection ports for signs of leaks. Remove debris or foreign objects obstructing the view.	Weekly	OM	
	444	Aboveground Field-Erected Tanks (Section 8-4)	A. Visually inspect for evidence of leaks; shell distortions; signs of settlement; corrosion, condition of tank foundation, condition of coating, insulation systems, and appurtenances. Inspection shall include all components and equipment located inside the containment area such as piping, pipe supports, containment valves, and product saver tanks. Items noted during the inspection will be documented for follow-up action by an authorized inspector. See Appendix F for the Field-Erected Tank Monthly Inspection Checklist.	Monthly	OM	
	445		B. Visually inspect bottom edge projection (chime) to ringwall sealant. Seal should be maintained in good working order to prevent corrosion of the underside of the tank bottom.	Monthly	OM	
	446		C. Visually inspect the exterior of the tank for leaks, corrosion, or irregularities such as tilting, settling, or out-of-roundness. Give special attention to seams and anchor bolts. Visual inspection shall include all components and equipment located inside the tank containment area such as piping, pipe supports, containment valves, and product saver tanks. Retain records of inspections reports for five years. See Appendix F for the Field-Erected Tank Annual Inspection Checklist.	Annually	OM	
	447		D. Perform a formal in-service external inspection of the tank in accordance with API 653 or STI SP001 to evaluate the tank for conditions which may affect the operational integrity of the storage tank, including minimum shell thickness measurements. This inspection must be performed by an applicable certified inspector. Inspection shall include all components and equipment located inside the tank containment area such as piping, pipe supports, containment valves, and product saver tanks.	Every five years or as required by an appropriately certified tank inspector in the previous API 653 or STI SP001 inspection report.	SM	This task shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.
	448		E. Perform an out-of-service API 653 or STI SP001 inspection to evaluate the tank for conditions which may affect the operational integrity of the tank floor, shell, roof and floating roof or pan. API 653 or STI SP001 provides a checklist to be used as part of the assessment. This inspection must be performed by an appropriately certified API 653 or STI SP001 inspector. Inspection shall include all components and equipment located inside the tank containment area such as piping, pipe supports, containment valves, and product saver tanks. The API 653 or STI SP001 inspector must recommend the date of the next inspection. The inspection interval must be based on the date the Suitability for Service Letter is issued immediately prior to when the tank is returned to service.	As recommended by the API 653 or STI SP001 inspector. If there is not a previous recommendation, the inspection must be performed within ten years after the tank was placed into operation.	SM	This task shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.
	449		A. Conduct external inspection of geodesic dome roofs, where accessible, for corrosion of tank-to-shell bolts, gasket connections, visible signs of corrosion, apparent roof leaks, clogging or deterioration of vent screens, and damage to the structure or panels.	Monthly	OM	
	450	Geodesic Dome Roofs (Section 8-4.2)	B. Conduct internal inspection of geodesic dome roofs from the floating roof, where accessible, for corrosion of tank-to-shell bolts, gasket connections, visible signs of corrosion, apparent roof leaks, clogging or deterioration of vent screens, and damage to the structure or panels.	Annually	OM	

	Task Number	Section	Description	Frequency	Responsibility	Notes
	451	Foundations (Section 8-4.3)	A. Inspect visible components of tank foundations for signs of erosion due to heavy rains, wash-down, etc. and repaired as necessary. Also inspect tank foundations for structural cracks, signs of settlement, spalling, or general deterioration. Remove vegetation found around the tank foundation.	Monthly	OM	
	452	Aboveground Shop Fabricated Tanks (Section 8-5.1)	A. Monthly External Inspection (Identified as P in STI SP001): Visually inspect for exterior signs of corrosion or coating deterioration. Visually inspect weld seams, tank-to-saddle connections, tank supports, tank anchors, foundation and anchor bolts, overfill valves and alarms, normal vents, emergency vents, leak detection probe or water/petroleum accumulation in the interstice on double-walled tanks, leaking valves, fittings, or components, spill containment systems and release prevention barriers. Leaking valves, fittings or components shall be repaired immediately or immediately removed from service and isolated to prevent further discharge. Any irregularities, (e.g., missing valve handles, bolts, nuts, screens) will be assessed for priority and repaired as soon as possible or as required depending on the nature of the defect (See Appendix E for an example of the STI SP001 Standard Monthly Inspection Checklist).	Monthly	OM	
	453		B. Annual External Inspection (Identified as P in STI SP001): A more detailed examination of the tank and appurtenances shall be performed on an annual basis (See Appendix E for an example of the STI SP001 Standard Annual Inspection Checklist).	Annually	OM	
	454		C. Formal External Inspection (Identified as E in STI SP001): A formal external inspection as defined in STI SP001 Standard for the Inspection of Aboveground Storage Tanks shall be conducted by certified STI SP001 inspector.	As established by SCP based on tank size and category as defined in STI SP001	SM	This task shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.
	455		D. Formal Internal Inspection (Identified as I in STI SP001): A formal internal inspection as defined in STI SP001 Standard for the Inspection of Aboveground Storage Tanks shall be performed by a certified STI SP001 inspector. The API 653 or STI SP001 inspector must recommend the date of the next inspection. The inspection interval must be based on the date the Suitability for Service Letter is issued immediately prior to when the tank is returned to service.	As established by SCP based on tank size and category as defined in STI SP001	SM	This task shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.
	456		E. Leak Test (Identified as L in STI SP001): A leak test as defined in STI SP001 Standard for the Inspection of Aboveground Storage Tanks shall be performed in accordance with STI SP001 Standard for the Inspection of Aboveground Storage Tanks.	As established by SCP based on tank size and category as defined in STI SP001	SM	This task shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.
	457	Self-Diking or Vaulted Tanks (Section 8-5.2)	A. Monthly External Inspection (Identified as P in STI SP001): Visually inspect for exterior signs of corrosion or coating deterioration. Visually inspect weld seams, tank-to-saddle connections, tank supports, tank anchors, foundation and anchor bolts, overfill valves and alarms, normal vents, emergency vents, leak detection probe or water/petroleum accumulation in the containment area, leaking valves, fittings, or components. Leaking valves, fittings or components shall be repaired immediately or immediately removed from service and isolated to prevent further discharge. Any irregularities, (e.g., missing valve handles, bolts, nuts, screens) will be assessed for priority and repaired as soon as possible or as required depending on the nature of the defect (See Appendix E for an example of the STI SP001 Standard Monthly Inspection Checklist).	Monthly	OM	
	458		B. Annual External Inspection (Identified as P in STI SP001): A more detailed examination of the tank and appurtenances shall be performed annually (See Appendix E for an example of the STI SP001 Standard Annual Inspection Checklist).	Annually	OM	
	459		C. Formal External Inspection (Identified as E in STI SP001): A formal external inspection as defined in STI SP001 Standard for the Inspection of Aboveground Storage Tanks shall be conducted by certified STI SP001 inspector.	As established by SCP based on tank size and category as defined in STI SP001	SM	This task shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.
	460		D. Formal Internal Inspection (Identified as I in STI SP001): A formal internal inspection as defined in STI SP001 Standard for the Inspection of Aboveground Storage Tanks shall be performed by a certified STI SP001 inspector.	As established by SCP based on tank size and category as defined in STI SP001	SM	This task shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.
	461		E. Leak Test (Identified as L in STI SP001): A leak test as defined in STI SP001 Standard for the Inspection of Aboveground Storage Tanks shall be performed in accordance with STI SP001 Standard for the Inspection of Aboveground Storage Tanks.	As established by SCP based on tank size and category as defined in STI SP001	SM	This task shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.
	462	Rectangular Concrete-Encased Tanks (Section 8-5.3)	A. Monthly External Inspection (Identified as P in STI SP001): Visually inspect tank supports, anchors and anchor bolts, overfill valve and alarms, normal vent, emergency vent, leaking valves, fittings or other components. In addition the exterior concrete shall be visually inspected for cracking, degradation, excessive calcareous deposits or signs of damage. Leaking valves, fittings or components shall be repaired immediately or isolated to prevent further discharge. Any other deficiencies or irregularities noted shall be repaired as soon as possible or as required depending on the nature of the defect (See Appendix E for an example of the STI SP001 Standard Monthly Inspection Checklist).	Monthly	OM	
	463		B. Annual External Inspection (Identified as P in STI SP001): A more detailed examination of the tank and appurtenances shall be performed on an annual basis (See Appendix E for an example of the STI SP001 Standard Annual Inspection Checklist).	Annually	OM	
	464		C. Formal External Inspection (Identified as E in STI SP001): A formal external inspection shall be conducted by certified STI SP001 inspector.	As established by SCP based on tank size and category as defined in STI SP001	SM	This task shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.
	465		D. Formal Interior Inspection (Identified as I in STI SP001): A modified formal internal inspection as defined in manufacturer's instructions or STI SP001 Standard for the Inspection of Aboveground Storage Tanks shall be performed on concrete-encased tanks by a certified STI SP001 inspector if the tank interior is accessible.	As established by SCP based on tank size and category as defined in STI SP001	SM	This task shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.
	466		A. Monthly External Inspection (Identified as P in Table 8-1): Ensure all tank port covers are present, are in good condition, and sealed firmly on the correct tank. Inspect tank stick gauge and ensure markings are legible and that the stick gauge is not warped or broken. Inspect tank for water using ATG or stick gauge with water-finding paste. Remove water found in tank. Open and inspect tank-top containment sumps and ensure no fuel or water is collected in the sumps. Check for and remove obstructions in tank fill pipe.	Monthly	OM	

	Task Number	Section	Description	Frequency	Responsibility	Notes
STORAGE TANKS	467	Single-Walled Underground Shop-Fabricated Tanks (Section 8-5.4.1)	B. Annual External Inspection (Identified as P in Table 8-1): Inspect electrical connections and junction boxes in underground sumps and access ports on tank. Ensure boxes are sealed, and that boxes, conduit, and electrical fittings are not corroded. Inspect submerged turbine pumps if present. Ensure pumps are in good condition and that pumps and fittings show no signs of leaking. Inspect tank top containment sumps for cracks, holes, and budes. Ensure tank top containment sump electrical and pipe penetrations are intact and secured. For double-walled piping systems that drain into the tank top containment sump, ensure interstitial space of piping is open and that sump sensor is properly mounted at the bottom of the sump. Ensure tank top containment sump lid gasket and seals are in good condition. Inspect road access covers. Ensure covers are in good condition, that all bolts are present and that handles and lift mechanism is in good condition as applicable. Inspect concrete installed over tank and ensure there is no significant cracking.	Annually	SM	This task shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.
	468		C. Tank Tightness Test (Identified as T in Table 8-1): Perform test in accordance with 40 CFR 280, Section 43.	As established by SCP based on tank size and release detection type listed in Table 8-1 .	SM	This task shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.
	469		D. Formal Internal Inspection (Identified as I in Table 8-1): A formal modified internal inspection in accordance with STI SP001 Standard for the Inspection of Aboveground Storage Tanks shall be conducted by a certified STI SP001 inspector if the interior is accessible. The inspector will need to supplement and/or adapt portions of STI SP001 to evaluate the specific concerns of an underground tank. Check the tank for settlement and ensure that the tank slopes towards the water drain.	As established by SCP based on tank size and release detection type listed in Table 8-1 or as recommended by an STI SP001 certified tank inspector in the previous inspection report.	SM	This task shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.
	470		E. Test tank-top containment sumps and ensure they are liquid tight by using vacuum, pressure, or liquid testing in accordance with 40 CFR 280, Section 43.	Every three years	SM	This task shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.
	471	Double-Walled Underground Shop-Fabricated Tanks (Section 8-5.4.1)	A. Monthly External Inspection (Identified as P in Table 8-2): Ensure all tank port covers are present, are in good condition, and seated firmly on the correct tank. Inspect tank stick gauge and ensure markings are legible and that the stick gauge is not warped or broken. Inspect tank for water using ATG or stick gauge with water-finding paste. Remove water found in tank. Open and inspect tank-top containment sumps and ensure no fuel or water is collected in the sumps. Check for and remove obstructions in tank fill pipe.	Monthly	OM	
	472		B. Annual External Inspection (Identified as P in Table 8-2): Inspect electrical connections and junction boxes in underground sumps and access ports on tank. Ensure boxes are sealed, and that boxes, conduit, and electrical fittings are not corroded. Inspect submerged turbine pumps if present. Ensure pumps are in good condition and that pumps and fittings show no signs of leaking. Inspect tank top containment sumps for cracks, holes, and budes. Ensure tank top containment sump electrical and pipe penetrations are intact and secured. For double-walled piping systems that drain into the tank top containment sump, ensure interstitial space of piping is open and that sump sensor is properly mounted at the bottom of the sump. Ensure tank top containment sump lid gasket and seals are in good condition. Inspect road access covers. Ensure covers are in good condition, that all bolts are present and that handles and lift mechanism is in good condition as applicable. Inspect concrete installed over tank and ensure there is no significant cracking.	Annually	SM	This task shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.
	473		C. Formal Internal Inspection (Identified as I in Table 8-2): A formal modified internal inspection in accordance with STI SP001 Standard for the Inspection of Aboveground Storage Tanks shall be conducted by a certified STI SP001 inspector if the interior is accessible. The inspector will need to supplement and/or adapt portions of STI SP001 to evaluate the specific concerns of an underground tank. Check the tank for settlement and ensure that the tank slopes towards the water drain.	As established by SCP based on tank size and release detection type listed in Table 8-2 or as recommended by an STI SP001 certified tank inspector in the previous inspection report.	SM	This task shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.
	474		D. Test tank-top containment sumps and ensure they are liquid tight by using vacuum, pressure, or liquid testing in accordance with 40 CFR 280, Section 43.	Every three years	SM	This task shall be performed by SO. The contractor shall identify when this task is required in the Facility Maintenance Plan.
	475	Underground Field-Constructed Tanks (Cut and Cover Tanks) (Section 8-6)	A. Check the level gauge records and interstitial monitoring ports to determine if the tank is leaking.	Daily	OM	
	476		B. Apply field-erected tank monthly external inspection to the maximum extent possible. Visually inspect tank and appurtenances for evidence of leaks, shell distortions, signs of corrosion, and settlement at accessible locations. Items noted during the inspection will be documented for follow-up action by an authorized inspector (See Appendix F for the Field-Erected Tank Monthly Inspection Checklist).	Monthly	OM	
	477		C. Check tank under static storage conditions for 24 hours using existing inventory management system to determine if petroleum losses are occurring. If leakage is noted, further investigation shall be conducted in accordance with Military Service-specific guidelines.	Monthly	OM	
	478		D. Apply field-erected tank annual external inspection to the maximum extent possible. Visually inspect tank and appurtenances for evidence of leaks, shell distortions, signs of corrosion, and settlement at accessible locations. Visually inspect pump/equipment vaults for leaks and cracking in concrete walls and floors. Retain records of inspections reports for five years (See Appendix F for the Field-Erected Tank Annual Inspection Checklist).	Annually	SM	This task shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.
	479		E. Perform a modified out-of-Service API 653 internal inspection to evaluate the tank for conditions which may affect the operational integrity of the tank floor, shell, columns and roof by certified API 653 inspector. API 653 provides a checklist to be used as part of the assessment; however the certified API 653 inspector must modify this checklist to incorporate specific needs of underground field-constructed tanks. The API 653 or STI SP001 inspector must recommend the date of the next inspection. The inspection interval must be based on the date the Suitability for Service Letter is issued immediately prior to when the tank is returned to service.	As recommended by the API 653 or STI SP001 inspector. If there is not a previous recommendation, the inspection must be performed within ten years after the tank was placed into operation.	SM	This task shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.

	Task Number	Section	Description	Frequency	Responsibility	Notes
	480	Tank Cleaning (Section 8-7)	A. Conduct Tank Cleaning: Unless otherwise mandated by operational concerns or Military Service directives, schedule and conduct tank cleaning based upon the frequency listed below. After cleaning tanks shall be stenciled in accordance with Section 8-8.1 Tank Stenciling Requirements.	a. Air Force - Tanks above 20,000 gallon (75,700 liters) in capacity - Every 10 years unless required more frequently due to fuel quality issues. Contact AFPET and AF Fuel SME for deviations on schedule. Schedule changes are typically accepted based on TO 42B1-1 requirements. b. Air Force - Tanks 20,000 gallon (75,700 liters) in capacity and under - During out of service inspection cycle unless required more frequently due to potential fuel quality issues. c. Army, Navy, U.S. Marine Corps - During out-of-service inspection cycle unless required more frequently due to potential fuel quality issues.	SM	This task shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.
	481	Aluminum Honeycomb Floating Pans (Section 8-9.1.1)	A. Visually inspect pan guide/anti-rotation cables and centering of pan.	Monthly	OM	
	482		B. Visually inspect pan grounding cables for proper attachment and wear or binding.	Monthly	OM	
	483		C. Visually inspect for buckling or damage to the pan.	Monthly	OM	
	484		D. Inspect grounding cables for proper attachment and wear or binding.	Annually	SM	
	485		E. Inspect all floating roof penetration seals, such as ladder seals, stilling well seals, and other seals to ensure that they are in good working condition.	Annually	SM	
	486		F. Clean and inspect perimeter tank/pan seals.	At time of out of service internal inspection	SM	This task shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.
	487		G. Refer to Section 8-9.1.5 Floating Roof and Pan Pressure/Vacuum Vents for inspection and maintenance requirements of floating pan pressure/vacuum vents.	As required	SM	
	488		H. Refer to Section 8-9.1.6 Floating Roof and Pan Legs for inspection and maintenance requirements of floating pan legs.	As required	SM	
	489		A. Visually inspect pan guide/anti-rotation cables and centering of pan.	Monthly	OM	
	490		B. Visually inspect pan grounding cables for proper attachment and wear or binding.	Monthly	OM	
	491	Steel Floating Pans (Section 8-9.1.2)	C. Visually inspect for buckling or damage to the pan.	Monthly	OM	
	492		D. Visually inspect for damage or deflection in the rolling ladder (if equipped).	Monthly	OM	
	493		E. Inspect grounding cables for proper attachment and wear or binding.	Annually	SM	
	494		F. Inspect all floating pan penetration seals, such as gauge well seals to ensure that they are in good working condition.	Annually	SM	
	495		G. Inspect gauge wells for abrasions that might indicate out of roundness, or improper centering.	Annually	SM	
	496		H. Inspect vertical ladder for abrasions that might indicate out of roundness, or improper centering (if equipped).	Annually	SM	
	497		I. Inspect for damage or deflection in the rolling ladder (if equipped).	Annually	SM	
	498		J. Clean and inspect perimeter tank/pan seals.	At time of out of service internal inspection	SM	This task shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.
	499		K. Refer to Section 8-9.1.5 Floating Roof and Pan Pressure/Vacuum Vents for inspection and maintenance requirements of floating pan pressure/vacuum vents.	As required	SM	
	500		L. Refer to Section 8-9.1.6 Floating Roof and Pan Legs for inspection and maintenance requirements of floating pan legs.	As required	SM	
	501	Pontoon Floating Pans (Section 8-9.1.3)	A. Visually inspect pan guide/anti-rotation cables or pipes and centering of pan.	Monthly	OM	
	502		B. Visually inspect pan grounding cables for proper attachment and wear or binding.	Monthly	OM	
	503		C. Visually inspect for buckling or damage to the pan.	Monthly	OM	
	504		D. Visually inspect for damage or deflection in the rolling ladder (if equipped).	Monthly	OM	
	505		E. Inspect pontoons for standing liquid and presence of strong vapors.	Annually	SM	
	506		F. Remove mechanical gauge float cover and ensure float is securely fastened to gauge tape. Check gauge tape for ease of movement.	Annually	SM	
	507		G. Inspect for damage or deflection in the rolling ladder (if equipped).	Annually	SM	
	508		H. Inspect vertical internal ladder and internal ladder/pan seals for abrasions that might indicate out of roundness, or improper centering (if equipped).	Annually	SM	
	509		I. Inspect gauge wells and gauge well/pan seals for abrasions that might indicate out of roundness, or improper centering.	Annually	SM	
	510		J. Inspect steel floating pan coatings for corrosion. Touch up with compatible coating if required (aluminum pans do not require coatings).	Annually	SM	
	511	Floating Roofs (Section 8-9.1.4)	K. Clean and inspect perimeter tank/pan seals.	At time of out of service internal inspection	SM	This task shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.
	512		L. Refer to Section 8-9.1.5 Floating Roof and Pan Pressure/Vacuum Vents for inspection and maintenance requirements of floating pan pressure/vacuum vents.	As required	SM	
	513		M. Refer to Section 8-9.1.6 Floating Roof and Pan Legs for inspection and maintenance requirements of floating pan legs.	As required	SM	
	514		A. Visually inspect the center primary roof drain system is water-free.	Monthly	OM	
	515		B. Visually inspect anti-rotation pipes/roof guides and centering of roof.	Monthly	OM	
	516		C. Visually inspect grounding cables for proper attachment and wear or binding.	Monthly	OM	
	517		D. Visually inspect for buckling or damage to the roof.	Monthly	OM	
	518		E. Visually inspect for standing water on roof deck.	Monthly	OM	
	519		F. Visually inspect for damage or deflection in the rolling ladder (if equipped).	Monthly	OM	
	520		G. Ensure that the drip-tight plug is placed in the roof drain opening.	Annually	SM	
	521		H. Ensure that the roof drain valve is closed. The drain valve is kept in the closed position except after each rain or snowfall when it is opened just long enough to drain the roofline. Tanks with retrofitted geodesic domes or metal roofs may have had the floating roof drain line removed, so before opening the roof drain valve ensure the roof drain line has not been removed.	Annually	SM	
	522		I. Inspect pontoons for standing liquid and presence of strong vapors.	Annually	SM	
	523		J. Remove mechanical gauge float cover and ensure float is securely fastened to gauge tape. Check gauge tape for ease of movement.	Annually	SM	
	524		K. Ensure emergency drain (if equipped) is not blocked with debris.	Annually	SM	
	525		L. Inspect for damage or deflection in the rolling ladder (if equipped).	Annually	SM	

	Task Number	Section	Description	Frequency	Responsibility	Notes
	526		M. Inspect vertical internal ladder and internal ladder/roof seals for abrasions that might indicate out of roundness, or improper centering (if equipped).	Annually	SM	
	527		N. Inspect gauge wells and gauge well/roof seals for abrasions that might indicate out of roundness, or improper centering.	Annually	SM	
	528		O. Inspect the floating roof coating for corrosion. Touch up with compatible coating if required.	Annually	SM	
	529		P. Clean and inspect perimeter tank/pan seals.	At time of out of service internal inspection	SM	This task shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.
	530		Q. Refer to Section 8-9.1.5 Floating Roof and Pan Pressure/Vacuum Vents for inspection and maintenance requirements of floating roof pressure/vacuum vents.	As required	SM	
	531		R. Refer to Section 8-9.1.6 Floating Roof and Pan Legs for inspection and maintenance requirements of floating roof legs.	As required	SM	
	532	Floating Roof and Pan Pressure/Vacuum Vents (Section 8-9.1.5)	A. Inspect the floating roof or pan pressure/vacuum vent to ensure that the seats and retaining straps or guides are in good working order and that the pressure/vacuum vent is not stuck to its seats, but instead lift easily off of its seats and reseats properly. Inspect gaskets for wear and replace as required. Refer to the manufacturer's operation and maintenance manual provided with the floating roof or pan for additional guidance on servicing the pressure/vacuum vent.	At time of out of service internal inspection	SM	This task shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.
	533	Floating Roof and Pan Legs (Section 8-9.1.6)	A. Inspect the floating roof or pan legs and tank bottom striker plates for wear; inspect the seals where the legs penetrate the floating roof or pan for leaks; inspect the low leg position stops to make sure they are securely fastened to the legs and will stop the floating roof or pan at the low position; inspect the leg keeper straps to make sure they are securely fastened to the legs to prevent the legs from falling off or through the floating roof or pan; inspect the threaded keeper caps or high position locking mechanisms to ensure they are in proper working order for securing the floating roof or pan in the high position. Refer to the maintenance manual provided with the floating roof or pan for additional guidance on floating roof or pan legs and associated hardware.	At time of out of service internal inspection	SM	This task shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.
	534	Secondary Tank Bottoms (Section 8-9.2)	A. Tanks designed with secondary tank bottoms should have tell-tale devices (leak detection ports) to allow for monitoring of the tank's floor integrity. The tell-tale devices are typically configured as valves or inspection ports to allow for visual monitoring of liquid that may be present between the foundation and the tank floor. The presence of water would indicate a breach in the foundation seals or flooring while the presence of petroleum would indicate integrity loss in the tank floor. Open and check tell-tale valves or inspection ports. Verify the absence of water or petroleum.	Monthly	OM	
	535	Tank Pressure/Vacuum Vents (Section 8-9.3)	A. On underground shop fabricated tanks, ensure tank pressure/vacuum vent is present and that the riser pipe is securely supported and vertical.	Annually	OM	
	536		B. Inspect vent settings. Pressure and vacuum settings for pressure/vacuum vents are usually specified on the vent nameplate or in the manufacturer's manual for the vent.	Annually	SM	
	537		C. Clean the pressure/vacuum vent. Information on the type of pressure/vacuum vent and procedures for the removal of covers, hoods and/or pallet removal and reinstallation should be found in the manufacturer's operation and maintenance manual. Before removing the pallets, brush all accumulations from the protecting screens, the pallets, and all surfaces of the valve. Brush the screens from inside the valve so that dirt and other objects fall to the outer sides. Remove heavy loading weights prior to removing the pallet assembly. Remove deposits or foreign matter using reasonable care not to damage diaphragms or seats.	Annually	SM	
	538		D. Inspect gaskets, seats, diaphragm, pallet stems and stem guides. Check all mating surfaces which must be free of nicks, cuts, cracks or deposits that might interfere with the proper seating or tightness of the valve. Test the pallets to ensure they move freely up and down over the full range of travel.	Annually	SM	
	539	Emergency Vents (Section 8-9.4)	A. Inspect emergency vents for external damage, such as dents, rusting, severe pitting or obstruction by other equipment, piping or conduits.	Annually	SM	
	540		B. Remove the vent, if possible, and inspect the seals and diaphragms for cracking or breakdown. Inspect retaining cables to ensure they are fastened to the vent and the manway or tank. Inspect guides to ensure emergency vents can function properly and re-seat.	Annually	SM	
	541		C. Verify that emergency vents have not been removed or modified. Emergency vents should not be replaced with ATGs, manual sample ports, level alarms, etc.	Annually	SM	
	542		D. Tanks that are equipped with manways for emergency vents shall be inspected for appropriate type, length, number of bolts, and lift clearance of the manway in accordance with UL 142 Standard for Steel Aboveground Tanks for Flammable and Combustible Liquids, Section 8 and 9.	Annually	SM	
	543	Flame Arrestors (Section 8-9.5)	A. The tube bank shall be removed and cleaned of foreign matter by immersing in an approved solvent solution, taking care not to damage the tube bundle. Gaskets shall be inspected and replaced as necessary.	Annually	SM	
	544	External High Level Shutoff Valves (HLSO) (Section 8-9.6.1)	A. Activate the tank high-high level alarm and ensure the solenoid valve (if equipped) activates on the HLSO valve. Ensure the HLSO valve closes when the solenoid valve is activated.	Quarterly	SM	
	545		B. Isolate, drain, and then vent the external float valve chamber (if equipped). Refill (either manually or via the storage tank product saver tank pump) the float chamber to test the float valve. Ensure the HLSO closes when the float is raised.	Annually	SM	
	546		C. Lift the manual test lever of internally mounted float valve (if equipped). Ensure that the HLSO closes when the float of the float valve is raised.	Annually	SM	
	547	Internal HLSO Valves (Section 8-9.6.2)	A. Inspect and test the high level shut-off valve and float mechanism, counter-weights, float rods, and floats to ensure the float mechanism is moving freely and functioning properly to close the high level shut-off valve. If valve is not equipped with a manual test mechanism the level of the tank must be raised to the high level shutoff valve set point in order to test the valve. Ensure valve is installed at a proper height.	Annually	SM	
	548	Mechanical Tape Gauges (Section 8-9.7)	A. Visually check that a liquid level is indicated and that the measurement appears to be accurate.	Daily	OM	
	549		B. Check the mechanical tape gauge against the automatic electronic tank gauge (if installed) or by manually gauging the tank for relative accuracy and proper working condition. Consult the manufacturer's operation and maintenance manual for additional maintenance and inspection requirements.	Quarterly	SM	
	550	Mechanically Operated Tape Gauge (Section 8-9.8.1)	A. Visually inspect the gauge to ensure the power is on, there are no warning alarms or lights and a liquid measurement is indicated and the tank level reading appears to be accurate.	Daily	OM	
	551		B. Inspect gauge head for buildup of sediment.	Quarterly	SM	
	552		C. Inspect tape conduit for deformations that would inhibit movement of tape up and down.	Quarterly	SM	
	553		D. Gauge level accuracy shall be performed against a hand dip measurement of the tank. Calibrate as required.	Semi-annually	SM	
	554		E. Inspect float and guide cable through an opened manway or access cover. Verify that the guide wire is taut and free of kinks. Verify that the float is buoyant and free of sludge or sediment build up.	Semi-annually	SM	

	Task Number	Section	Description	Frequency	Responsibility	Notes
AUTOMATIC TANK GAUGES	555		F. Inspect power and control wires for damage.	Semi-annually	SM	
	556		G. Inspect wire connection termination points for damage or loose connections.	Semi-annually	SM	
	557	Magnetostriuctive Probes (Section 8-9.8.2)	A. Visually inspect the gauge to ensure the power is on, there are no warning alarms or lights and a liquid measurement is indicated and the tank level reading appears to be accurate.	Daily	OM	
	558		B. Inspect probe assembly for buildup of sediment.	Quarterly	SM	
	559		C. Inspect probe assembly and probe shaft for deformations that would inhibit movement of probe.	Quarterly	SM	
	560		D. Level probe accuracy shall be performed against a hand dip measurement of the tank. Calibrate as required.	Semi-annually	SM	
	561		E. Verify that the probe float is buoyant and free of sludge or sediment build up.	Semi-annually	SM	
	562		F. Inspect power and control wires for damage.	Semi-annually	SM	
	563		G. Inspect wire connection termination points for damage or loose connections.	Semi-annually	SM	
	564	Servo Gauge (Section 8-9.8.3)	A. Visually inspect the gauge to ensure the power is on, there are no warning alarms or lights and a liquid measurement is indicated and the tank level reading appears to be accurate.	Daily	OM	
	565		B. Inspect gauge head for buildup of sediment.	Quarterly	SM	
	566		C. Gauge level accuracy shall be performed against a hand dip measurement of the tank. Calibrate as required.	Semi-annually	SM	
	567		D. Inspect float and guide cable through an opened manway or access cover. Verify that the guide wire is taut and free of kinks. Verify that the float is buoyant and free of sludge or sediment build up.	Semi-annually	SM	
	568		E. Inspect power and control wires for damage.	Semi-annually	SM	
	569		F. Inspect all wire connection termination points for damage or loose connections.	Semi-annually	SM	
	570		G. Inspect stilling well to be straight and vertical with no dents so that the float can move freely.	Annually	SM	
	571		H. Lubricate moving parts of the gauge head.	Annually	SM	
LEVEL ALARMS	572	Externally Mounted Level Alarms (Section 8-9.9.1)	A. Test level alarm switches by isolating the chambers from the tank using the sensing chamber isolation valves. Vent and drain the chambers. Slowly pour product into the chambers through a funnel on top of the chamber to test the level switch at the specified level setting.	Semi-annually	SM	
	573	Internally Mounted Level Alarms (Section 8-9.9.3)	A. Test level alarm switches by activating manual testing levers, if equipped. If alarms switches are not equipped with manual testing levers, adjust the level of fuel in the tank to the alarm points in order to test the alarm switches. If it is not feasible to adjust the level of the fuel in the tank to all of the alarm set points, remove the alarm switches from the tank and test the alarms externally. Reinstall alarm switches in the tank once testing is complete.	Annually	SM	
PRODUCT SAVER TANKS	574	Product Saver Tanks (Section 8-9.10)	A. Inspect the product saver tank to ensure all valves are working properly, sight level gauges with density balls are working properly and are not broken, and hand pumps or electric pumps are working properly and are not leaking.	Quarterly	SM	
SIDESTREAM FILTRATION SYSTEMS	575	Sidestream Filtration Systems (Section 8-9.11)	A. Check (typically 5 gallon (19 liters), if incorporated) filter separator vent tank and ensure it is empty.	Monthly	OM	
	576		B. Refer to Section 6-1 Pipe Testing and Inspections for inspection and maintenance requirements of piping.	As required	SM	
	577		C. Refer to Section 3-6.4 Basket Strainers for inspection and maintenance requirements of basket strainers.	As required	SM	
	578		D. Refer to Section 3-8 Pumps for inspection and maintenance requirements of fuel pumps.	As required	SM	
	579		E. Refer to Section 3-6.2 Filter Separators for inspection and maintenance requirements of filter separators.	As required	SM	
	580		F. Refer to Section 4-4.2.2 Filter Separator Control Valves for inspection and maintenance requirements of filter separator control valves.	As required	SM	
	581		G. Refer to Section 9-1.6 Grounding Systems for inspection and maintenance requirements of grounding systems.	As required	SM	
	582		H. Refer to Section 9-1.9 Electronic Equipment for inspection and maintenance requirements of control panels.	As required	SM	
FILL PORTS	583	Fill Ports (Section 8-9.12)	A. Ensure fill port covers are installed and are not damaged or broken. Ensure fill port covers are identified by fuel type and are installed on the correct tank. Visually inspect the fill port spill bucket to ensure there are no cracks, budes, or holes. Ensure the spill bucket is clean of dirt, trash, water, and fuel.	Daily	OM	
	584		B. Inspect drain valve in spill bucket and ensure it is in good condition. Ensure the caps installed on the receipt connection points are vapor tight and are not broken, cracked, or chipped. Ensure the poppet valve of the vapor recovery port seals tightly and no vapor is escaping from the tank when the valve is closed.	Quarterly	SM	
	585		C. Hydrostatically test fill-port to ensure containment is liquid-tight. Where evaporation is a concern, conduct the testing when this concern would be minimized, such as at night/early morning or during a time of year when this would not be as much of an issue. Record the water level at the start of the 60-minute (minimum) hold period. If the water level drops by 1/8 inch or more, perform and record an investigation to determine the cause and any required repairs. Once repairs are completed, a new test must be completed. Refer to Appendix B for testing procedures and to use to document the testing. Ensure secondary containment area of fill port is fuel tight. Ensure the manual transfer pump or drain valve is operational.	Every 3 Years	SM	Note: Hydrostatic Containment testing shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.
LEAK DETECTION	586	Point Sensor - Dry (Section 8-9.13.1)	A. Ensure the monitoring panel associated with the point sensor(s) is powered on and no alarms are present.	Daily	OM	
	587		B. Ensure monitoring space is clear and free of debris and liquid.	Quarterly	SM	
	588		C. Test sensor and ensure it is functional.	Annually	SM	
	589	Point Sensor - Wet (Section 8-9.13.2)	A. Ensure the monitoring panel associated to the wet point sensor(s) is powered on and no alarms are present.	Daily	OM	
	590		B. Ensure level of monitoring fluid is within normal range.	Quarterly	SM	
	591		C. Test sensor and ensure it is functional.	Annually	SM	
	592	Point Sensor - Pressure/Vacuum (Section 8-9.13.3)	A. Ensure the monitoring panel associated with the pressure/vacuum point sensor(s) is powered on and no alarms are present.	Daily	OM	
	593		B. Test vacuum sensor for proper operation.	Annually	SM	
	594	Visual Leak Detection (Section 8-9.13.4)	A. Visually inspect leak detection ports (tell-tales) for signs of leaks. If there are debris or objects obstructing the view, appropriate measures shall be taken to remove the debris or remedy the obstructions.	During routine inspection of other components or monthly, whichever comes first	OM	
	595		B. Visually inspect reinforcement plate tell-tale holes for signs of leaks. Ensure tell-tale holes have not been plugged by debris or a cap. Pack reinforcement plate tell-tales with white grease to prevent insect nesting and buildup of debris.	Quarterly	OM	

	Task Number	Section	Description	Frequency	Responsibility	Notes
FLOATING SUCTION LINES	596	Floating Suction Lines (Section 8-9.14)	A. Check external floating suction line position indicator to ensure floating suction line is moving freely as the level in the tank rises or falls.	Quarterly	SM	
	597		B. Inspect cables, floats, and swing joint. Ensure interior of floats have not collected fuel. Ensure cables are securely fastened to anchor points and are in good working order. Ensure the suction pipe flange used to support the swing joint is level and true and that swing joint moves freely up and down and does not bind.	When tank is taken out of service for internal cleaning or inspection	SM	This task shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.
HEATING COILS	598	Steam Type Heating Coils (Section 8-9.16.1)	A. Observe the regulating valve and check it against a thermometer to be sure that it controls the tank temperature within a safe range, usually not over 150 degrees F (65 degrees C) for No. 6 burner fuel oil. Steam traps shall be inspected for proper operation to ensure condensate is evacuated from the steam coil.	At each operation	OM	
	599		B. Pressure check heating coils to 10% above normal operating pressure.	Annually	SM	
	600		C. Steam coils shall be cleaned and inspected for visible signs of corrosion or wear when the tank is emptied and cleaned for inspection. All components of the steam heating coils, such as weld joints, support points, valves, temperature wells, control valves, and steam traps shall be inspected and checked for proper operation and visible wear or damage. The coil may be carefully pressurized with steam and visually checked for leaks if necessary. Leaks or damage found shall be repaired.	When the tank is taken down for formal internal inspection or sooner if steam heating coil damage is suspected.	SM	This task shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.
	601	Thermal Fluid Type Heating Coils (Section 8-9.16.2)	A. Observe the regulating valve and check it against a thermometer to be sure that it controls the tank temperature within a safe range, usually not over 150 degrees F (65 degrees C) for No. 6 burner fuel oil. All external valves, fittings, and other components shall be inspected for visible signs of leaks during operation.	At each operation	OM	
	602		B. Pressure check heating coils to 10% above normal operating pressure.	Annually	SM	
	603		C. When tanks are emptied and cleaned for inspection, the heating coils shall be cleaned and inspected for visible signs of corrosion, wear, or damage. The coils can be pressurized and checked for leaks at that time with the thermal heating fluid at normal operating pressure, but at ambient temperature to alleviate possible burns to personnel. Leaks shall be repaired.	When the tank is taken down for formal internal inspection or sooner if thermal heating coil damage is suspected.	SM	This task shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.
	604	Electric Rod Type Heating (Section 8-9.16.3)	A. Inspect heater to ensure no fluid leakage around the heater to tank connection and that the heater is performing properly.	At each operation	OM	
STILLING WELLS	605	Stilling Wells (Section 8-9.17)	A. Stilling wells shall be visually inspected to be vertically straight and free dents or indentations. Sometimes tank stilling wells are made of bare carbon steel pipe. In these instances the stilling wells shall be replaced with aluminum.	At time of out of service internal inspection	SM	This task shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.
	606		B. Inspect floating seals inside stilling wells to ensure they are not worn and are sealing the inside of the stilling well properly.	At time of out of service internal inspection	SM	This task shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.
CONTAINMENT SYSTEMS	607	Containment Systems (General) (Section 8-10.1)	A. Inspect containment systems for cleanliness, if accessible.	Daily	OM	
	608		B. Secondary containment systems degrade and will collect debris which can clog drainage inlets or prevent drain valves from seating properly. Hydrostatically test the drainage systems to include containment drain inlets, drain lines and containment drain valves to ensure the containment is liquid tight. This test may use opportune rainfall by holding rainwater in the containment system for one hour. Where evaporation is a concern, conduct the testing when this concern would be minimized, such as at night/early morning or during a time of year when this would not be as much of an issue. Record the water level at the start of the 60-minute (minimum) hold period. If the water level drops by 1/8 inch or more, perform and record an investigation to determine the cause and any required repairs. Record the water level at the start of the 60 minute (minimum) hold period. If the water level drops by 1/8 inch or more, perform and record an investigation to determine the cause and any required repairs. Refer to Appendix B for testing procedures and to use to document the testing. American Concrete International (ACI) Standards 224R "Control of Concrete Cracking" and ACI's Concrete Repair Manual are two standards that owners/operators can follow to maintain the integrity of the concrete secondary containment.	Every 3 years	SM	Note: Hydrostatic Containment testing shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.
	609	Concrete and Cement Brick Dike/Berm Walls (Section 8-10.2.1)	A. Inspect for vegetation that has taken root in seals or cracks. All vegetation shall be removed in all cases to prevent penetration of seals, joints or cracks in the concrete.	Daily	OM	
	610		B. Inspect walls constructed of bricks for signs of deterioration (e.g., spalling caused by freeze-thaw conditions, cracks, and joint cracks between bricks). Walls constructed of bricks shall be patched immediately to prevent further penetration of the wall structure.	Daily	OM	
	611		C. Inspect walls constructed of concrete for signs of deterioration (e.g., spalling caused by freeze-thaw conditions and cracks). Clean and seal cracks with a fuel resistant sealant.	Semi-annually	SM	Per PWS Joint Sealant and Crack Repair
	612		D. Inspect seals and joints in concrete walls. Joint sealant that has retracted from the joint or become unbonded with the joints shall be removed and replaced with fuel resistant sealant.	Semi-annually	SM	
	613	Dike/Berm Floors (Section 8-10.2.2)	A. Inspect for vegetation that has taken root in seals or cracks. All vegetation shall be removed in all cases to prevent penetration of seals, joints or cracks in the concrete.	Daily	OM	
	614		B. Inspect floors made of concrete for signs of deterioration (e.g., spalling caused by freeze-thaw conditions and cracks). Clean and seal cracks with a fuel resistant sealant.	Semi-annually	SM	Per PWS Joint Sealant and Crack Repair
	615		C. Inspect joints and seals. Joint sealant that has retracted from the joint or become unbonded with the joints shall be removed and replaced with a fuel resistant sealant.	Semi-annually	SM	Per PWS Joint Sealant and Crack Repair
	616	Earthen Dike Walls (Section 8-10.3)	A. Inspect for vegetation that has taken root. All vegetation shall be removed in all cases.	Daily	OM	
	617		B. Prevent the growth of vegetation inside the containment area. Use fireproof chemicals for sterilization. Only herbicides approved by the Installation Environmental Office shall be used.	Monthly	OM	
	618		C. Inspect for signs of erosion. Inspections should be performed particularly after heavy rains or storms. Repair areas that have deteriorated due to erosion.	Quarterly	SM	Repairs shall be performed by SO.
	619	Self-Diking or Vaulted Tank Containment (Section 8-10.4)	A. Secondary containment structures on self-diking or vaulted tanks shall be inspected visually for integrity breaches with special attention given to pipe penetrations and interstitial drain valves.	Daily	OM	
	620		A. Remove vegetation growing in the gravel and dirt, taking note if the roots have penetrated the FML.	Daily	OM	

	Task Number	Section	Description	Frequency	Responsibility	Notes
ELECTRICAL CONTROL SYSTEMS AND EQUIPMENT	621	Flexible Membrane Liners (Section 8-10.5)	B. Visibly inspect FMLs where attached to ringwalls, dike walls, concrete piers and other projections for deterioration due to weather or wear and repair as necessary.	Quarterly	SM	Repairs shall be performed by SO.
	622		C. Visually inspect FMLs covered with smooth rock or gravel for bare spots where the gravel has been washed away due to storms or heavy rains for tears. Replace gravel taking care not to puncture the liner.	Quarterly	SM	
	623		D. Visually inspect exposed FML for tears or punctures and repair.	Quarterly	SM	Repairs shall be performed by SO.
	624	Pipe Penetrations (Section 8-10.6)	A. Inspect boot seals and mechanical link-type seals for wear and cracking. Ensure the seals are in good working order to seal out water or retain the petroleum product as intended. Repair or replace defective boot and link-seals.	Quarterly	SM	Repairs shall be performed by SO.
	625		B. Inspect sealant between pipes and concrete walls, berms, and floors. Sealant that has retracted from the concrete or pipe surfaces shall be removed and replaced with new fuel resistant sealant.	Semi-annually	SM	Repairs shall be performed by SO.
	626	Electrical Equipment (Section 9-1.2)	A. Electrical control systems include: deadman control; ground verification systems; EFSO operation; control panels, motor control, and pump start/stop buttons. These systems shall be tested on a periodic basis to ensure proper operation and functionality. In addition, control system Uninterruptible Power Supplies (UPS) must be inspected and replaced as necessary.	Quarterly	SM	Repairs shall be performed by SO.
	627	Power Cables (Section 9-1.3)	A. Visual inspection: Verify that there are no sharp bends. Verify that the cable insulation is intact. Verify that cables are appropriately tagged or otherwise identified. Verify that all connections are tight and not corroded. Open manholes and handholes. Verify that they are not flooded, clogged with debris or infested by pests.	Quarterly	SM	
	628		B. Insulation resistance test: This test measures the resistance of the insulation with an Insulation Resistance Tester. During the test, the cable will be disconnected from both ends. Acceptable test values are 100 megaohms for cables rated between 120V to 1000V. Insulation resistance testing for voltages higher than 1000V are to be performed by specialized testing company.	As needed based on visual inspection	SM	Resistance test to be performed by service order.
	629	Motor Controls (Section 9-1.4)	A. Verify that the labeling is consistent with the drawings and specifications.	Semi-annually	SM	
	630		B. Verify that pushbuttons are easy to operate and are not stuck. Verify that there is no grease accumulation around the seating. Verify that indicating lights are functional and replace if required.	Semi-annually	SM	
	631		C. Verify that indicating lights are functional and replace as needed.	Semi-annually	SM	
	632		D. Verify that electrical and mechanical interlocks operate according to the design intent. In case of key interlocks, ensure that the number of keys corresponds to the interlock intent. Having more keys than required defeats the intent of the interlocking and poses danger to the service personnel and equipment. If extra keys are found, they should be removed from the equipment.	Semi-annually	SM	
	633		E. Inspect the enclosure for visible signs of corrosion.	Interior annually/exterior semi-annually	SM	
	634		F. Open the enclosure - be mindful of insects, rodents and reptiles, particularly if located outdoors. Look for signs of corrosion, dust accumulation, spider webs, etc. Clean the enclosure with compressed air and apply rust inhibitors and paint as needed.	Annually	SM	Per PWS Touch-up Coating Repair
	635		G. Inspect the overcurrent protective devices for proper seating. Verify that rating is appropriate for the motor. Look for signs of attached wire and device overheating.	Annually	SM	
	636		H. Inspect the arch shoots of contactors and clean as needed. Check that partitions are not burned.	Annually	SM	
	637		I. Inspect contactors for abnormal wear. Check contacts for pitting, roughness and oxidation. Verify that contact gap, alignment and pressure are in accordance with manufactures recommendations.	Annually	SM	
	638		J. When contactors are used, listen for the chatter of contacts or buzzing noise. These are indicative of a faulty contactor.	Annually	SM	
	639		K. Verify that relays and switches are firmly seated in their bases and there are no signs of overheating or vibration.	Annually	SM	
	640		L. Look for frayed or broken strands in the flexible control wiring and replace if such are found.	Annually	SM	
	641		M. Perform a functional test of protective devices if they are equipped with self-testing circuits or switches.	Annually	SM	
	642		N. Perform a functional test of all manual switches and verify proper operation against intended design logic. Replace switches and relays if operation is not satisfactory.	Annually	SM	Repairs shall be performed by SO.
	643		O. Perform insulation resistance test for the control wiring. (NOTE: Testing of the control wires may require substantial down time. Therefore, this should only be performed on a case by case basis if there are reasons to suspect that the insulation of the control wiring is deteriorating.)	As required	SM	This task shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.
	644	Panelboards (Section 9-1.5)	A. Verify that there are no physical obstructions blocking access to the panelboard. Remove physical obstructions.	Quarterly	OM	
	645		B. Inspect the enclosure and the surrounding area for water damage and corrosion.	Annually	SM	
	646		C. Verify that all breakers are either in the "On" or the "Off" position. If there are tripped breakers, investigate the cause of the trip.	Annually	SM	
	647		D. Verify that there is a breaker schedule. If there is no breaker schedule or the schedule is worn and out-of-date, create and post a new one.	Annually	SM	Breaker schedules shall be developed by SO.
	648		E. Verify that the breaker operation matches the description on the panel schedule.	Annually	SM	
	649		F. Observe breakers, wires and terminals for signs of overheating or short circuiting.	Annually	SM	
	650		G. Verify that all breakers are firmly seated and locked in place by slightly shaking them.	Annually	SM	
	651		H. Verify that all grounding wires are firmly connected to the grounding bar.	Annually	SM	
	652		I. If a breaker malfunction is identified, leave breaker in the open position and replace as soon as possible. If a breaker cannot disconnect its circuit, the entire panelboard shall be switched off using its main disconnecting means and locked out until the breaker is repaired.	Annually	SM	
	653	Power Grounding Systems (Section 9-1.6.1)	A. The connections to the grounding system shall be surveyed and verified for continuity. If a connection is suspected to be loose, perform further testing. In some occasions, it is more cost effective to replace the suspected connection instead of performing diagnostic tests.	Annually	SM	
	654		B. Measure the voltage between the equipment grounding conductor and the electrode grounding conductor (usually bare copper). Investigate test results above 3 VAC for a potential ground fault.	Annually	SM	
	655		C. Measure the voltage between the chassis of the equipment and the electrode grounding conductor. Investigate if the readings exceed 2 VAC.	Annually	SM	
	656		D. Facility ground resistance check: This type of testing is performed with a four lead, low resistance ohmmeter or digital ohmmeter. Recommended values are between 3 and 5 ohms. In no case should the grounding resistance be higher than 25 ohms.	Every five years	SM	This task shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.
	657		A. Inspect ground reels for corrosion. Ensure ground reels are securely mounted to a rigid base. Inspect clamps for serviceability. Replace clamp if jaws are deformed for corroded, spring is weak, or other defects are evident that would prevent a good connection. Inspect cable wires. Replace if more than one-third of the cable wires are broken.	Quarterly	SM	

	Task Number	Section	Description	Frequency	Responsibility	Notes
	658	Static Grounding Systems (Section 9-1.6.2)	B. The connections to the grounding system shall be surveyed and verified for continuity. If a connection is suspected to be loose, perform further testing. In some occasions it is more cost effective to replace the suspected connection instead of performing diagnostic tests.	Annually	SM	
	659		C. Resistance measurement on static grounds: Measure static ground resistance of new and damaged ground rods. Static ground with a resistance greater than 10,000 ohms will be removed or replaced. Static ground mechanically damaged will be repaired and retested.	When observed to be physically damaged.	SM	This task shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.
	660	Electric Motors (Section 9-1.7)	A. Lubricating motor bearings and inspect for vibration and overheating.	Quarterly	SM	
	661		B. Check for debris and other foreign material in the fan housing.	Semi-annually	SM	
	662		C. Check motor ground wires. Ensure they are firmly connected to the housing or the junction box.	Annually	SM	
	663		D. If the motor is installed in a hazardous location, verify that the seals of the connection boxes and conduits are intact.	Annually	SM	
	664	Lighting (Section 9-1.8)	A. Verify proper operation of light switch, lighting contactor, photocell or timer as appropriate. If a lighting contactor is used, listen for the chatter of contacts or buzzing noise. These are indicative of a faulty contactor. Replace if required.	Quarterly	SM	Repairs shall be performed through a service order.
	665		B. With the lights turned on, observe individual luminaries for flicker or lights turning on and off. The former is indicative of a faulty choke. The latter is indicative of a faulty starter. Replace the faulty components as required.	Quarterly	SM	
	666		C. When light fixtures are located in hazardous areas, verify that the seals are intact and the hazardous rating of the fixture is maintained.	Quarterly	SM	
	667		D. Thoroughly clean dust, bugs, and debris from the luminaire. Light solvents or cleaning agents may be used.	Annually	SM	
	668		E. Re-Lamping: With the lights turned off, replace the lamps. In order to prevent accidental turning on of the lights, it is mandatory to switch off and lockout the breaker of the lighting circuit. Ensure the replacement lamps are the same type as those they are replacing. Verify the proper operation of all light fixtures after the lamp replacement.	Annually or as required	SM	Re-lamping will be performed through a service order and should be executed in conjunction with an RM visit to avoid mobilization costs.
	669	Electronic Equipment (9-1.9)	A. Inspect the outside of equipment enclosures for dust and evidence of corrosion. Vacuum clean the dust to ensure unobstructed air circulation.	Annually	SM	
	670		B. Open the enclosure and vacuum clean the dust to ensure unobstructed air circulation. Pay particular attention to fans and air passages. If there is evidence of corrosion, verify that there is no water damage on printed circuit boards or contacts. If water or humidity damage is observed, the electronic components may not work properly and further testing is required.	Annually	SM	
	671		C. Verify proper operation of the space heater if one is installed.	Annually	SM	
	672		D. Check if fans for proper operations and rotation.	Annually	SM	
	673		E. Look for signs of overheating such as discoloration and charring.	Annually	SM	
	674		F. Replace air filters.	Annually	SM	Replacement will be performed through a service order and should be executed in conjunction with recurring maintenance to avoid additional mobilization costs.
	675		G. Verify connection tightness. Lightly pull wires on soldered and terminal screws and ensure the wires are not loose.	Annually	SM	
	676		H. Verify that circuit boards are properly seated. Ensure that board locking tabs are fully engaged. Do not unplug and plug connectors to verify seating. This will wear out the pins. Unplug only if connector malfunction is suspected.	Annually	SM	
	677		I. Observe wires for excessive strain, braiding, or wear due to vibration. Replace as required.	Annually	SM	Repairs shall be performed by SO.
	678	Cathodic Protection (Section 9-2.1)	A. Inspect rectifiers in in accordance with UFC 3-570-06 <i>Operation and Maintenance: Cathodic Protection Systems</i> .	Quarterly	SM	This task shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.
	679		B. Inspect cathodic protection systems in accordance with UFC 3-570-06 <i>Operation and Maintenance: Cathodic Protection Systems</i> .	Annually	SM	This task shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.
CATHODIC PROTECTION SYSTEMS	680	Lightning Surge Arresters (Section 9-2.2.1)	A. Newer lightning surge arresters are designed to withstand unlimited surges at 50,000 amperes; however, manufacturers of older surge arresters may provide a maximum number of surge events that can occur before it must be replaced. If surge arresters include a maximum number of surge events, a spare arrester shall be kept on hand. Refer to the surge arrester manufacturer's operation and maintenance manual for particular inspection instructions and parts. Inspect as part of an overall cathodic protection system inspection.	Annually	SM	This task shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.
	681	Card and Key Locks (Section 9-3)	A. Conduct operational check of card and key lock system and ensure that all features provided with the installed system are operational.	Annually	SM	
	682	Lightning Protection Systems (Section 9-4)	A. Inspect air terminals to make sure they are securely attached to the roof of the building, canopy, or the piece of equipment. Check all connections between the air terminals and the grounding loop or grounding rods. Repair damaged or loose connections and perform continuity check after repairs.	Annually	SM	Repairs which require wire replacement should be performed through a service order. Other repairs described in the item shall be performed under the firm fixed price.
	683	Ground Verification System (Section 9-5)	A. Conduct an operational check of the ground verification system and ensure that all features provided with the installed system are operational. Inspect the plug for corrosion, weakness, or loose nuts and replace if heavily dented or deformed.	Quarterly	SM	This task shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.
	684	Electronic Overfill Protection Systems (Section 9-6)	A. Conduct operational check of overfill prevention system and ensure that all features provided with the installed system are operational.	Quarterly	SM	
	685	Liquefied Petroleum Tanks (Section 10-1.1)	A. Inspect fuel tank for leaks. If a leak is occurring, the odorizing agent of the gas should be detectable. Use a soap and water solution to spray on areas suspected of leaks. Systems that are found with leaks shall be taken out of service.	Monthly	OM	
	686		B. Test operation of emergency shutoff valves. Ensure the fusible link mechanism is attached properly to actuate in case of a fire and that it has not been by-passed, blocked, or damaged in any manner. Ensure the fusible link is not filled with debris or paint which could impact operation.	Semi-annually	SM	
	687		C. Check settings of tank safety valves and calibrate if required.	Every 5 years	SM	This task shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.
	688	Liquefied Petroleum Pipelines (Section 10-1.2)	A. Conduct visual inspection of pipelines for potential damage and leak points. Use a soap and water solution to spray on areas suspected of leaks. Systems that are found with leaks shall be taken out of service and repaired.	Monthly	OM	
	689		B. Inspect coatings and markings on piping. Repair coating deterioration and replace labels that are fading and are difficult to read.	Semi-annually	SM	
	690	Liquefied Petroleum Vapor Lines (Section 10-1.3)	A. Inspect vapor lines for leaks. If leaks are occurring, the odorizing agent in the gas should be detectable. Use a soap and water solution to spray on areas suspected of leaks. Systems that are found with leaks shall be taken out of service and repaired.	Monthly	OM	
	691		B. Inspect coatings and markings on piping. Repair coating deterioration and replace labels that are fading and are difficult to read.	Semi-annually	SM	
	692	LPG Vaporizers (Section 10-1.4)	A. Inspect vaporizers for leaks. If leaks are occurring, the odorizing agent in the gas should be detectable. Use a soap and water solution to spray on areas suspected of leaks. Systems that are found with leaks shall be taken out of service and repaired.	Monthly	OM	

	Task Number	Section	Description	Frequency	Responsibility	Notes
ALTERNATE POL FACILITIES	693		B. The manufacturer's maintenance schedules and recommendations provided with the LPG vaporizer shall be followed.	As required by the manufacturer's operation and maintenance requirements.	SM	
	694	Petroleum Gas Regulators (Section 10-1.5)	A. Inspect petroleum gas regulators for leaks. If leaks are occurring, the odorizing agent in the gas should be detectable. Use a soap and water solution to spray on areas suspected of leaks. Systems that are found with leaks shall be taken out of service and repaired.	Monthly	OM	
	695	Liquefied Petroleum Gas Hoses (Section 10-1.6)	A. Inspect hoses for damage and leaks. If leaks are occurring, the odorizing agent in the gas should be detectable. Use a soap and water solution to spray on areas suspected of leaks. If leaks are detected from a hose discontinue use of the hose and remove it from service. Inspect for damage to outer cover that exposes reinforcement. Inspect for kinks or flattened areas, soft spots or bulges. Inspect couplings and ensure they have not slipped on the hose or been damaged.	Monthly	OM	
	696	CNG Piping (Section 10-2.1)	A. Inspect CNG lines for leaks. Inspection of high-pressure CNG lines and equipment shall be conducted using proper PPE including but not limited to safety glasses, a face shield, hard hat and fire resistant clothing. If leaks are occurring, the odorizing agent in the gas should be detectable. Use a soap and water solution to spray on areas suspected of leaks. Systems that are found with leaks shall be taken out of service and repaired.	Daily	OM	
	697		B. Inspect coatings and markings on piping. Repair coating deterioration and replace labels that are fading and becoming difficult to read.	Semi-annually	SM	Repairs required shall be performed by Service Order.
	698	CNG Compressors (Section 10-2.2)	A. Compressors will require maintenance based on the model included in the system. Consult the compressor manual for maintenance requirements.	As required by the manufacturer's operation and maintenance requirements.	SM	
	699	CNG Storage (Section 10-2.3)	A. Inspect CNG tubes and tanks for leaks. Inspection of high-pressure CNG lines and equipment shall be conducted using proper PPE including but not limited to safety glasses, a face shield, hard hat and fire resistant clothing. If leaks are occurring, the odorizing agent in the gas should be detectable. Use a soap and water solution to spray on areas suspected of leaks. Systems that are found with leaks shall be taken out of service and repaired.	Daily	OM	
	700		B. Inspect coatings and markings on storage tubes or tanks. Repair coating deterioration and replace labels that are fading and becoming difficult to read.	Semi-annually	SM	
	701		C. Check operation and calibration of safety valves on tubes or tanks.	Every 3 years	SM	This task shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.
	702	CNG Dispensers (Section 10-2.4)	A. Dispensers are listed for service with CNG and will vary by manufacturer. Consult the maintenance manual that was supplied with the system for manufacturer's maintenance required for the CNG dispenser.	As required by the manufacturer's operation and maintenance requirements.	SM	
	703	CNG Dispenser Hoses (Section 10-2.5)	A. Inspect hoses for damage, leaks, and cracks. If leaks are occurring, the odorizing agent in the gas should be detectable. Use a soap and water solution to spray on areas suspected of leaks. If leaks are detected from a hose, discontinue the use of the hose and remove it from service.	Monthly	OM	
	704		B. Test hoses for leaks following manufacturer recommended frequencies and procedures.	As required by the manufacturer's operation and maintenance requirements.	SM	
	705	Hydrazine Charging Units (Section 10-3)	A. Hydrazine charging units are self-contained factory fabricated systems. Refer to the manufacturer's maintenance manual that was provided with the system for required periodic maintenance.	As required by the manufacturer's operation and maintenance requirements.	SM	
	706	Fuel Truck and Rail Car Containment Areas (Section 11-1.1)	A. Remove debris from around security fence.	Monthly	OM	
	707		B. Inspect fence grounding points. Ensure connections are not loose or damage.	Monthly	OM	
	708		C. Inspect the parking area for cracks in the concrete containment paving and curbs. Remove vegetation that may have established roots in the buildup of dirt or from exposed earth under cracks. Thoroughly clean and seal cracks with a fuel resistant sealant.	Quarterly	SM	Per PWS Joint Sealant and Crack Repair
	709		D. Secondary containment systems degrade and will collect debris which can clog drainage inlets or prevent drain valves from sealing properly. Hydrostatically test secondary containment and associated drainage systems to include containment concrete/sealant, drain inlets, drain lines and containment drain valves to ensure containment is liquid tight. This test may use opportune rainfall by holding rainwater in the containment system for one hour. Where evaporation is a concern, conduct the testing when this concern would be minimized, such as at night/early morning or during a time of year when this would not be as much of an issue. Record the water level at the start of the 60-minute (minimum) hold period. If the water level drops by 1/8 inch or more, perform and record an investigation to determine the cause and any required repairs. Once repairs are completed, a new test must be completed. Refer Appendix B for testing procedures and to document the testing.	Every 3 years	SM	Note: Hydrostatic Containment testing shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.
	710		E. Verify continuity of vehicle grounding system connections. If a connection is suspected to be loose, perform further testing. In some occasions it is more cost effective to replace the suspected connection instead of performing diagnostic tests.	Annually	SM	
	711		F. Inspect pavement markings and vehicle movement lines for wear and fading. Repair faded or worn pavement markings.	Annually	SM	Repairs shall be performed through a service order.
	712		G. Inspect security fence for wear and rust. Inspect barbed wire and ensure it is adequately secured to outriggers. Repair loose fencing components and coatings at areas that show rust.	Annually	SM	Repairs shall be performed through a service order.
	713		H. Refer to Section 9-1.8 Lighting for inspection and maintenance requirements of area lighting.	As required	SM	
	714		A. Inspect the remote containment basin for cracks in the concrete containment paving, walls, and curbs. Remove vegetation that may have established roots in the buildup of dirt or from exposed earth under cracks. Thoroughly clean cracks with a water spray or air jet. Seal cracks with a fuel resistant sealant.	Quarterly	SM	Per PWS Joint Sealant and Crack Repair
	715		B. If equipped, inspect spill containment sump pump for proper operation.	Quarterly	SM	

	Task Number	Section	Description	Frequency	Responsibility	Notes
SUPPORT FACILITIES	716	Remote Spill Containment (Section 11-1.2)	C. Secondary containment systems degrade and will collect debris which can clog drainage inlets or prevent drain valves from sealing properly. Hydrostatically test secondary containment and associated drainage systems to include containment concrete/sealant, drain inlets, drain lines and containment drain valves to ensure containment is liquid tight. This test may use opportune rainfall by holding rainwater in the containment system for one hour. Where evaporation is a concern, conduct the testing when this concern would be minimized, such as at night/early morning or during a time of year when this would not be as much of an issue. Record the water level at the start of the 60-minute (minimum) hold period. If the water level drops by 1/8 inch or more, perform and record an investigation to determine the cause and any required repairs. Once repairs are completed, a new test must be completed. Refer Appendix B for testing procedures and to document the testing.	Every 3 years	OM	Note: Hydrostatic Containment testing shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.
	717	Pumphouse/Filter Buildings (Section 11-2.1)	A. Inspect the floor and containment curbs for cracks. Thoroughly clean cracks with a water spray or air jet. Seal cracks with a fuel resistant sealant.	Annually	SM	Per PWS Joint Sealant and Crack Repair
	718		B. Refer to UFC 3-110-03 for inspection and maintenance requirements of pumphouse and filter building roof systems.	As required	SM	This task shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.
	719	Canopies (Section 11-2.2)	A. Inspect and maintain canopies in accordance with UFC 3-110-03 .	As required	SM	This task shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.
	720	Emergency Eyewash/Showers (Section 11-3)	A. Test operation of the emergency eyewash/shower by pushing on the activation handles. Ensure the water is not brown in color, due to rust in the piping or dirt seeping in from a hole in the buried piping. For systems with tempered water, ensure that the water that is being supplied by the emergency eyewash/shower is between 60 and 100 degrees F (16 and 39 degrees C). For systems with a horn and strobe light, ensure that the horn and strobe light activate when the activation lever on the emergency eyewash/shower is pushed. For systems that interface with Installation or fire emergency systems, pre-coordinate before testing. At some Installations emergency eyewashes and showers act as EFSOs and are tied into the fire alarm systems.	Weekly	OM	
	721		B. Inspect portable/packaged safety showers and eyewash stations for proper operation. Check fluid levels. Where tap water is used, fluid shall be replaced monthly. Less frequent intervals of fluid change, as recommended by the manufacturer, are acceptable where a solution or water additive is used. Ensure packaged eyewash supplies are within the listed expiration date. Tags or labels shall be attached to the unit or adjacent to it, indicating the fluid change schedule.	Monthly	OM	
	722		C. Inspect the exterior coatings of permanently installed units and repair damaged coatings or rust.	Quarterly	SM	
	723		D. For systems with tempered water systems inspect components of the water heater for correct operation and temperature control. Ensure that the safety valve on the hot water heater tank is not leaking.	Semi-annually	SM	
	724		E. Inspect signage and labels on the emergency eyewash/shower. Replace missing labels or signage that has become loose. Signs that are faded shall be replaced.	Annually	SM	
	725		A. Inspect the operation of the doors. Ensure that they close and open smoothly.	Quarterly	SM	
	726		B. Inspect the lights inside of the hood to make sure they are operating properly. Replace light bulbs that are no longer working.	Semi-annually	SM	
	727	Ventilation Hoods (Section 11-4.1)	C. Verify that all electrical equipment is properly classified in accordance with NFPA 70 National Electrical Code .	Annually	SM	
	728		D. Inspect the ventilation system (ductwork, fans, etc.) for signs of disrepair and air leakage and ensure it is operational and pulling air through the hood. Inspect and assure that the lab hood air measuring device for assuring proper air flow is permanently attached and working properly. The ventilation hood shall be inspected and approved by a service specific industrial hygienist or bioenvironmental engineer in accordance with OSHA, 29 CFR 1910.1450 Occupational Exposure to Hazardous Chemicals in Laboratories, and ANSI/AIHA Laboratory Ventilation Z9.5.	Annually	SM	Note: General requirements in this section to be performed by RMMR. Approval by the service specific industrial hygienist or bioenvironmental engineer is the responsibility of the site.
	729		E. Verify negative pressure is present through the ventilation hood to the exhaust.	Annually	SM	
	730	Oil/Water Separators (Section 11-5)	A. Inspect the oil/water separator for the buildup of collected petroleum fuel or oil. Remove and properly dispose of accumulated petroleum fuel or oil.	Quarterly	SM	Remove and properly dispose of accumulated petroleum fuel or oil through a service order.
	731		B. Drain, clean, and inspect the interior of the oil/water separator. Ensure all divider plates and screens are in good working order. Replace or repair damaged components.	Annually	SM	Sampling, storage, disposal costs shall be submitted through a service order. Repairs shall be performed by SO.
	732	Cranes and Hoists (Section 11-6)	A. Inspect cranes and hoists for smooth operation. If the crane or hoist is equipped with electronic controls, check power supply and operational control cords for nicks or damage. A crane service technician shall correct binding that may prevent smooth operation and repair damage to power cords.	Before each use	OM	
	733		B. Apply lubricant or grease to areas that require periodic greasing.	Annually	SM	
	734		C. Military Services-specific, Host Nation, State, and/or Local regulations require cranes and hoists to be certified for operation. Follow the more stringent of Military Services-specific, Host Nation, State or Local regulations. Certify cranes and hoists annually.	Annually	SM	
N OR CLOSURE	735	Deactivated Petroleum Fuel Tanks (Section 12-2)	A. Inspect water or anti-corrosion level in tank. If level has dropped, investigate potential leak points such as blind flanges. Repair leaks that are detected and refill to appropriate level.	Quarterly	SM	Repairs shall be performed by SO.
	736		B. Check exterior coatings and labels. Repair peeling coatings and/or rusting areas and replace or repair labels which have become faded and difficult to read.	Quarterly	SM	Repairs shall be performed by SO.
	737		C. Inspect cathodic protection system for proper operation.	Annually	SM	This task shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.

	Task Number	Section	Description	Frequency	Responsibility	Notes
FUEL FACILITY TEMPORARY DEACTIVATION	738	Deactivated Petroleum Fuel Pipelines (Section 12-3)	A. Inspect the pressure of the nitrogen charge applied to the petroleum fuel pipeline with a pressure gauge. If the pressure of the charge has dropped investigate and repair leak points. Once leak points are repaired, recharge with nitrogen.	Quarterly	SM	Repairs shall be performed by SO.
	739		B. Check exterior coatings and labels. Repair peeling coatings and/or rusting areas and replace or repair labels which have become faded and are difficult to read.	Quarterly	SM	
	740		C. Inspect cathodic protection system for proper operation.	Annually	SM	This task shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.
	741	Deactivated Petroleum Fuel Pumps (Section 12-4)	A. Manually rotate pump through several rotations. Ensure that the pump turns freely.	Quarterly	SM	
	742		B. Check exterior coatings. Repair peeling coatings and/or rusting areas and replace or repair labels which have become faded and difficult to read.	Quarterly	SM	Repairs shall be performed by SO.
	743		C. Remove isolation flanges and recoat interior of pump with light corrosion-inhibiting oil.	Annually	SM	
	744	Miscellaneous Deactivated Components (Section 12-5)	A. Ensure that blind flanges are tight. Inspect exterior coatings and labels. Repair peeling coatings and/or rusting areas and replace or repair labels that have become faded and are difficult to read.	Annually	SM	Repairs shall be performed by SO.
MISC. REQUIREMENTS	745	Fire Protection Systems	Perform fire protection system maintenance in accordance with the PWS.	See PWS	SM	
	746	Back-Up Power Generators	Perform back-up power generator maintenance in accordance with the PWS.	See PWS	SM	
	747	Air Compressors	Perform air compressor maintenance in accordance with the PWS.	See PWS	SM	
	748	Pumps	Perform pump maintenance in accordance with the PWS and other requirements in Appendix G.	See PWS	SM	
	749	Fuel Piers and Wharves	Inspect and clean in accordance with PWS Section 3.	See PWS	SM	
	750	Coatings/Markings and Signage	Perform coatings, markings, and signage repairs and maintenance in accordance with the PWS.	See PWS	SM	
	751	API 510 Inspections	Perform API 510 inspections on all capitalized pressure vessels, filter separators, and associated pressure relieving devices in accordance with the PWS.	As required	SM	This task shall be performed by SO or another contract. The contractor shall identify when this task is required in the Facility Maintenance Plan.

APPENDIX I - CONTRACT SITE LIST AND SUPPORT LEVEL

# of Sites	Installation Name	Site Name	DLA Site Code	RPSUID	City	State	Postal Code	Branch of Service	Region	Anticipated-Service-Start-Date	Max-Frequency	Quarterly	Semi-Annual	Annual	Minor-Repair	Emergency Repairs
1	JACKSONVILLE IAP	Jacksonville IAP Site #1	JVL	2390	Jacksonville	FL	32218	Air Force	SAD-AF	14-Feb-2026	4	X 1	X 1	X 1	X	X
2	SI CAPE CANAVERAL	Cape Canaveral AFS Site #1	DBE	1555	Cape Canaveral	FL	32920	Air Force	SAD-AF	14-Feb-2026	4			X 1	X	X
3	SI PATRICK	Patrick AFB	PAT	3143	Cocoa Beach	FL	32925	Air Force	SAD-AF	14-Feb-2026	4			X 1	X	X
4	JB CHARLESTON	Charleston AFB (ID 26) - Joint Base	CAF	1579	Charleston	SC	29404	Air Force	SAD-AF	14-Feb-2026	4			X	X	X
5	JB CHARLESTON	DFSP Charleston	CHS	1580	Charleston	SC	29406	Air Force	SAD-AF	14-Feb-2026	4	X 1	X 1	X 1	X	X
6	CHARLOTTE IAP	Douglas MAP ANG (ID 146)	DGL	1661	Charlotte	NC	28208	Air Force	SAD-AF	14-Feb-2026	1+MC			X	X	X
7	DOBBINS ARB	Dobbins ARB (ID 192)	DOB	1660	Marietta	GA	30069	Air Force	SAD-AF	14-Feb-2026	1+MC			X 1	X	X
8	SAVANNAH HILTON HEAD IAP	Glynco ANG Station	JAS	2124	Brunswick	GA	31525	Air Force	SAD-AF	14-Feb-2026	4			X	X	X
9	JB CHARLESTON	Joint Base Charleston NWS	JBC	213	Charleston	SC	29404	Air Force	SAD-AF	14-Feb-2026	4	X 1	X 1	X 1	X	X
10	SI MOODY	Moody AFB	MDY	3020	Valdosta	GA	31699	Air Force	SAD-AF	14-Feb-2026	4	X 1	X 1	X	X	X
11	MCENTIRE JOINT NATIONAL GUARD BASE	McEntire ANG (ID 158)	MNT	2793	Eastover	SC	29044	Air Force	SAD-AF	14-Feb-2026	1+MC			X 1	X	X
12	ROBINS AFB	Robins Air Force Base Site 1	ROB	3219	Warner Robins	GA	31098	Air Force	SAD-AF	14-Feb-2026	4	X 1	X 1	X 1	X	X
13	SAVANNAH HILTON HEAD IAP	Savannah ANG (IAP ID 107)	SAG	171075	Savannah	GA	31408	Air Force	SAD-AF	14-Feb-2026	1+MC			X	X	X
14	SAVANNAH HILTON HEAD IAP	Savannah/Hilton Head IAP Site #3	SHH	3358	Savannah	GA	31408	Air Force	SAD-AF	14-Feb-2026	4			X	X	X
15	SHAW AFB	Shaw AFB (ID 55)	SHW	3269	Sumter	SC	29152	Air Force	SAD-AF	14-Feb-2026	4			X 1	X	X
16	SEYMOUR JOHNSON AFB	Seymour Johnson AFB (ID 56)	SMJ	3268	Goldsboro	NC	27531	Air Force	SAD-AF	14-Feb-2026	1+MC			X 1	X	X
17	CHARLOTTE IAP	Stanly County Airport	WEF	3312	New London	NC	28127	Air Force	SAD-AF	14-Feb-2026	4			X	X	X

Note 1: Sites under Installation Name ROBINS AFB previously separated in RBA and ROB have been combined to form one site ROB.

APPENDIX J - EXISTING MAINTENANCE SCHEDULES																				
#	Installation Name	Site Name	DLA Site Code	RPSUID	Location	City	ST	Existing Max Freq	<u>1st Quarter</u> <i>Contract PoP 14 Aug 20 -13 Aug 21</i>			<u>2nd Quarter</u>			<u>3rd Quarter</u>			<u>4th Quarter</u>		
									Aug-24	Sep-24	Oct-24	Nov-24	Dec-24	Jan-25	Feb-25	Mar-25	Apr-25	May-25	Jun-25	Jul-25
1	SI CAPE CANAVERAL	Cape Canaveral AFS Site #1	DBE	1555	Cape Canaveral AFS	Cape Canaveral	FL	1							Annual 2/24-2/25					
2	SI PATRICK	Patrick AFB	PAT	3143	Patrick AFB	Cocoa Beach	FL	4							Annual 2/17-2/21					
3	JACKSONVILLE IAP	Jacksonville IAP Site #1	JVL	2390	Jacksonville ANG	Jacksonville	FL	1			SA1/Q1 10/16-10/18			Q2 1/21-1/22			A/SA2/Q3 4/22-4/25		Q4 7/23-7/24	
4	DOBBINS ARB	Dobbins ARB (ID 192)	DOB	1660	Dobbins ARB, GA (ID 192)	Marietta	GA	1+MC			MC						Annual 4/7-4/10			
5	ROBINS AFB	Robins Air Force Base Site 1	ROB	3219	Robins ANG, GA	Warner Robins	GA	4	SA1/Q1 8/28-8/30			Q2 11/21-11/22				A/SA2/Q3 3/3-3/6			Q4 6/3-6/4	
6	SI MOODY	Moody AFB	MDY	3020	Moody AFB, GA	Valdosta	GA	4		Q1 9/16-9/18			A-SA1-Q2 12/02-12/11			Q3 3/24-3/26			SA2-Q4 6/17-6/20	
7	SAVANNAH HILTON HEAD IAP	Glynco ANG Station	JAS	2124	Glynco Air National Guard Station	Brunswick	GA	1					Annual 12/16							
8	SAVANNAH HILTON HEAD IAP	Savannah ANG (IAP ID 107)	SAG	171075	Savannah ANG, GA (IAP ID 107)	Savannah	GA	1+MC					Annual 12/17-12/19					MC		
9	SAVANNAH HILTON HEAD IAP	Savannah/Hilton Head IAP Site #3	SHH	3358	SAVANNAH/HILTON HEAD IAP SITE #5	Savannah	GA	4					Annual 12/20							
10	JB CHARLESTON	DFSP Charleston	CHS	1580	DFSP Charleston	Charleston	SC	1	SA1/Q1 8/19-8/23			Q2 11/13-11/15			A/SA2/Q3 2/3-2/21			Q4 5/06-5/08		
11	JB CHARLESTON	Charleston AFB (ID 26) - Joint Base	CAF	1579	Charleston AFB, SC (ID 26) - Joint Base	Charleston	SC	1				Annual 11/18-11/22								
12	JB CHARLESTON	Joint Base Charleston NWS	JBC	213	JOINT BASE CHARLESTON NAVAL WEAPONS STATION	Charleston	SC	4		Q1 9/10			SA1-Q2 12/10-12/11			Q3 3/11-3/12			A-SA2-Q4 6/18-6/20	
13	MCENTIRE JOINT NATIONAL GUARD BASE	McEntire ANG (ID 158)	MNT	2793	McEntire ANG, SC (ID 158)	Eastover	SC	1+MC			MC						Annual 4/14-4/16			
14	SHAW AFB	Shaw AFB (ID 55)	SHW	3269	Shaw AFB, SC (ID 55)	Sumter	SC	1									Annual 4/17-4/24			
15	CHARLOTTE IAP	Douglas MAP ANG (ID 146)	DGL	1661	Douglas MAP ANG, NC (ID 146)	Charlotte	NC	1+MC				Annual 11/04-11/06						MC		
16	CHARLOTTE IAP	Stanly County Airport	WEF	3312	Stanly County Airport	New London	NC	1				Annual 11/7								
17	SEYMOUR JOHNSON AFB	Seymour Johnson AFB (ID 56)	SMJ	3268	NC	Goldsboro	NC	1+MC						MC					Annual 6/09-6/17	
Note 1: Sites who receive Annual RM only shall also receive Meter Calibration in accordance with UFC 3-460-03 (twice per year). No other Semi-Annual RM shall be required. Refer to PWS paragraph 3.3.5.																				

APPENDIX K

REAL PROPERTY DATA
[PROVIDED IN EXCEL]

U.S. Army Engineering and Support Center
Huntsville, AL

APPENDIX L

EXISTING FACILITY MAINTENANCE PLANS [PROVIDED IN EXCEL]

**U.S. Army Engineering and Support Center
Huntsville, AL**

APPENDIX M

Essential Mission Criteria

**U. S. Army Engineering and Support Center
Huntsville, Alabama**

APPENDIX M – Essential Mission Criteria

1. Purpose

The tasks outlined within this document are hereby designated as essential to mission success in support of Department of Logistics Agency – Energy (DLA-E) capitalized fuel systems and will be prioritized for continuation of services in the event of an abnormal event, including but not limited to natural disasters, widespread health crises, or a declaration of war. All criteria contained herein are considered high priority and will be completed to the greatest extent possible during such events. However, the Contracting Officer (KO) reserves the right to reprioritize these criteria based on the specific nature and evolving circumstances of the qualifying event. The KO will provide formal notification to the contractor regarding the activation of this plan, as well as notification when normal operating conditions are resumed. Determination of a qualifying event triggering this plan rests solely with the KO. (Ref: PWS Sections 1.0, 1.1 and 1.2)

2. Scope

This document applies to all tasks and deliverables outlined in the Performance Work Statement (PWS) related to preventive maintenance (PM), corrective maintenance (CM), emergency repairs, and records management for petroleum facilities, systems, and supporting DLA capitalized facilities.

3. Mission Essential Criteria Table

Criterion	Description	PWS Reference(s)	Justification
Corrective Maintenance (CM) Execution	Provide CM to restore real property to its designated purpose by overhaul, reprocessing, or replacement of constituent parts.	1.1, Appendix A, Appendix H	<i>Essential</i> for restoring functionality after failures, ensuring continued operation.
Quality Control	Provide a Quality Control program.	1.1, 1.2, 1.25.2 B, 01 45 00.00 10	Ensures that all maintenance and repair activities are performed to the required standards and specifications.
Records Management	Provide a program of Records Management for petroleum facilities,	1.1, 1.11, 1.25.2 C	Critical for tracking maintenance

APPENDIX M – Essential Mission Criteria

Criterion	Description	PWS Reference(s)	Justification
	petroleum systems, and supporting DLA Capitalized facilities. Includes completed and updated Maintenance Records/Binders.		history, identifying trends, and ensuring accountability. Supports audits and inspections.
Transition Plan Execution	Execute the Transition Plan (including Phase-In) to meet PWS requirements without impacting the fueling mission.	1.25.1	Ensures a smooth handover from the previous contractor and avoids disruptions to fuel operations. Addressing carry-over deficiencies is <i>critical</i> .
Staff Qualifications and Management	Provide qualified personnel with appropriate training, certifications, and experience. Submit resumes and E-Verify information.	1.5, 1.5.1, 1.9.4, 1.25.1 C	Ensures that personnel have the skills and knowledge to perform the required work safely and effectively.
Communication	Maintain consistent and effective communication with the Government, including designated contacts, flow charts, and communication tools.	1.25.1 E	Facilitates coordination and ensures timely resolution of issues.
Subcontractor Management	Manage subcontractors effectively, including ensuring their qualifications and maintaining required certifications.	1.5.2	Extends the quality and compliance requirements to all subcontractors.
Reporting	Provide required reports, including Three Week Look Ahead Schedule,	Appendix B, 1.25.2 D	Provides the Government with visibility into

APPENDIX M – Essential Mission Criteria

Criterion	Description	PWS Reference(s)	Justification
	Monthly Report, Preventive Maintenance Report, and Service Order Tracker.		contractor performance and progress.
Antiterrorism/Operations Security Compliance	Comply with the requirements described in Appendix D Antiterrorism / Operations Security Compliance.	1.9.5, Appendix D	Ensures the security of the facilities and personnel.

4. Monitoring and Enforcement:

The Government will monitor the Contractor's performance against these mission-essential criteria through regular inspections, reviews of documentation, and feedback from stakeholders. Failure to meet these criteria may result in corrective action requests, cure notices, contract penalties, or termination of the contract.