

Annex A (Overarching Base Operations PWS) to OPORD 24-XXX

IMCOM Enterprise Base Operations (BASOPS) Performance Work Statement (PWS)
Templates (U)

Performance Work Statement (PWS)

Base Operations

15 January 2026

Annex A (Overarching Base Operations PWS) to OPORD 24-XXX: IMCOM Enterprise Base Operations (BASOPS) Performance Work Statement (PWS) Templates (U)

Table of Contents

1.0 INTRODUCTION	1
1.1 Background	1
1.2 Objectives	1
1.3 Climatic Conditions	1
1.4 Facility Access	2
1.5 Traffic Flow.....	2
1.6 Drainage.....	2
1.7 Restoration of Landscape Damage.....	2
1.8 Dust Suppression	2
1.9 Utility Location.....	2
1.10 Excavation Permits	2
1.11 Work Clearance	3
2.0 REQUIREMENTS.....	3
2.1 Description of Services	3
2.1.2 General Information.	3
2.1.3 Place of Performance and Hours of Operation.	4
2.1.4 Federal Holidays	4
2.1.5 Travel/Temporary Duty	6
2.1.6 Emergency Services	6
2.1.7 Contract Administration and Management.....	6
2.1.8 COR/ACOR Functions	8
2.1.9 Quality Control (QC).	8
2.1.10 Subcontract Management.....	8
2.1.11 Contractor Employees	8
2.1.12 Business Relations	10
2.2 Work Management.....	10
2.2.1 Coordination	11
2.3 As-Builts and Geospatial Information System (GIS).	Error! Bookmark not defined.
2.3.1 Maintain As-Builts	Error! Bookmark not defined.
2.3.2 Real Property Records Updates	Error! Bookmark not defined.
2.3.3 GIS.....	Error! Bookmark not defined.
2.3.4 GIS Support Services	Error! Bookmark not defined.

Annex A (Overarching Base Operations PWS) to OPORD 24-XXX: IMCOM Enterprise Base Operations (BASOPS) Performance Work Statement (PWS) Templates (U)

2.3.5 GIS Files	Error! Bookmark not defined.
2.3.6 Other Documents.....	Error! Bookmark not defined.
2.4 Historic Property or Archaeological Site.....	20
2.4.1 Repair and Replacement	20
2.5 Special Requirements	21
2.5.1 Security.....	21
2.5.2 Security Training.	23
2.5.3 Safety.....	24
2.5.4 Training, Physical Requirements, or other Expertise Required.....	24
2.5.5 Environmental Requirements.....	25
2.5.6 Contingency Plans.	25
3.0 PERFORMANCE REQUIREMENTS AND STANDARDS	26
3.1 Performance Task Requirements, Standards and Acceptable Quality Levels (AQLs).....	26
3.2 Quality Assurance	26
4.0 PERFORMANCE REQUIREMENTS SUMMARY (PRS) MATRIX.	1
5.0 COMMON LEVELS OF SERVICE (SERVICE).....	2
6.0 DELIVERABLES.....	3
7.0 RELATED DOCUMENTS.....	3
7.1 Definitions and Acronyms	3
7.1.1 Definitions	3
7.1.2 Acronyms.....	13
7.3 Applicable Directives, Publications.	15
7.3	Error! Bookmark not defined.
7.4 Government-Furnished Material (GFM)/Property (GFP)/Equipment (GFE).	24
7.4.1 Utilities	24
7.5 Contractor-Furnished Material (CFM)/Property (CFP)/Equipment (CFE)	24
7.5.1 Contractor-Furnished Material and Responsibilities	24
7.5.2 Contractor-Furnished Items	24
7.5.3. Contractor Facilities	25
7.6 U.S. Department of Labor (DOL) Wage Determination (WD)	25

Annex A (Overarching Base Operations PWS) to OPORD 24-XXX: IMCOM Enterprise Base Operations (BASOPS) Performance Work Statement (PWS) Templates (U)

1.0 Introduction. This is a non-personal services contract to provide Base Operation and Support Services for the United States Army Garrison (USAG) Fort Gordon GA. The Government will not exercise any supervision or control over the contract service providers. The Contractor shall perform to the standards specified in this Performance Work Statement (PWS). Contract service providers shall be accountable solely to the Contractor who, in turn is responsible to the Government. The Contractor shall provide all personnel, equipment, supplies, facilities, transportation, tools, materials, supervision, and other items and non-personal services necessary as defined in this PWS. The Contractor is responsible for providing all parts required for Preventive Maintenance Orders (PMOs) and all repair parts required for Demand Maintenance Orders (DMOs).

1.1 Background. Fort Gordon is a large, multi-mission, multi-service, military installation providing base services and support across a wide spectrum of training, operational, and Soldier sustainment needs. The Installation supports Department of Army (DA) and Department of Defense (DoD) organizations and activities performing regional and world-wide missions including communications training and operations, military intelligence, cyber operations, medical and dental care, force integration, and mobilization. Fort Gordon provides year-round training for more than 54,000 reservists as well as Army and Navy Reserve Officer Training Corps (ROTC) students.

1.2 Objectives. The Contractor shall ensure all work accomplished in the performance of this PWS meets all applicable Federal, State, and Local Laws, Regulations, and Directives to include, but not limited to, the publications in Section 7, Related Documents.

1.2.1 The Contractor shall ensure all work in support of mission requirements tendered to the Government for acceptance conforms to the measurable performance standards of quality, timeliness, and quantity specified in the PWS of this contract. Without additional expenses to the Government, the Contractor shall obtain/ensure subcontractors obtain all licenses and permits required to perform this work under this contract. The intent is to establish work requirements that are performance-based and results oriented. This approach is intended to allow the Contractor to determine the best and most cost-effective ways to fulfill base operations and their component needs, emphasizing innovation and commercial best practices.

1.3 The Fort Gordon, GA area average annual rainfall is 45 to 50 inches with the wettest months being June-August. The first killing frost may be expected in October and the last killing frost generally occurs in March. The average annual maximum and minimum temperatures are approximately 90.6 degrees and 34.4 degrees Fahrenheit, respectively. Monthly normal temperatures ranged from a low of 25 degrees in the month of January to a high of 89 degrees in the month of July. Summer temperatures often reach 100+ degrees Fahrenheit, while sub-freezing weather is common during the winter months.

Annex A (Overarching Base Operations PWS) to OPORD 24-XXX: IMCOM Enterprise Base Operations (BASOPS) Performance Work Statement (PWS) Templates (U)

1.4 Facility Access. The Contractor shall ensure access to all fire detection and suppression systems in case of emergencies or for other Fire Department purposes. The Contractor shall inform the Fire Department point-of-contact (POC), prior to outages that will impact the function of the system, special problems or circumstances, which require Fire Department inspection. The Fire Department will reset alarm systems to operational status.

1.5 Traffic Flow. The Contractor shall maintain the free flow of vehicular and pedestrian traffic while conducting maintenance and repair activities. **The Contractor shall notify the COR, in writing, a minimum of fourteen (14) business days in advance of any scheduled closure of lanes or streets.** Emergency lane and road closures shall be coordinated with the COR.

1.6 Drainage. Maintenance work performed under this PWS shall not impede drainage. The Contractor shall implement the Erosion Control and Wetland Plans as prescribed in the INRMP. Deliverable A1064, Erosion Control and Wetlands Plans. The Contractor shall take an active role in identifying any developing erosion areas not already identified in the plan. The Contractor shall perform grading and drainage requirements for damaged and disturbed areas as to return to pre-damaged conditions.

1.7 Restoration of Landscape Damage. Trees or other landscape features damaged by the Contractor's operations shall be restored to the original state at no additional cost to the Government.

1.8 Dust Suppression. The Contractor shall perform dust suppression when necessary, during maintenance and repair activities or as directed by the Contracting Officer or COR.

1.9 Utility Location. The Contractor shall perform utility cuts in pavements as required to repair existing Government owned utilities, referenced in the PWS, after obtaining a digging permit to do so. The Contractor shall locate and stake out underground utility pipes/cables prior to their digging operations. The Contractor shall be responsible for having the proper equipment to locate all underground utilities referenced in the PWS.

1.9.1 The Contractor shall locate all Government owned utilities, referenced in this PWS. This utility locates will be in support of ongoing base operations (BASOPS) activities and all other excavation, construction, and/or design locate activities on the Installation. The Contractor shall be responsible for obtaining excavation and utility clearances (dig permits) to perform work under all PWO/DMO/OWOs. The Contractor shall not proceed with the excavation of any kind until a dig permit has been initiated, issued and cleared. A dig permit is initiated when you call Georgia 811 by dialing 811 or 1-800-282-7411. Georgia 811 can also be contacted via the website address www.Georgia811.com.

1.10 All excavation permits shall be initiated in writing and processed through the local Installation operating procedures. **The Government requires up to five (5) business days**

Annex A (Overarching Base Operations PWS) to OPORD 24-XXX: IMCOM Enterprise Base Operations (BASOPS) Performance Work Statement (PWS) Templates (U)

to review and approve excavation permits and provide this approval to the Contractor so the permit can be finalized and returned to the requestor. The Contractor shall keep record of every permit, assign a unique number, provide locator and marking service, initiate marking with GA811 and provide status to the Government. The Contractor shall notify the requestor within twenty-four (24) hours of receiving a processed excavation permit package.

1.10.1 The Contractor shall use the GA811 utility locate form for tracking the current status and clearance of submitted utility locates. The GA811 locate form identifies all utilities, POCs, current status, issued, delinquent and expiration dates. A copy of the completed GA811 clearance form shall be provided to the KO/COR; a copy will be given to the excavation contractor and kept on the excavation site at all times and a copy of the excavation clearance form shall be filed in General Fund Enterprise Business System (GFEBS) available for inspection by the Government.

1.11 Work Clearance. For work involving digging/excavation operations, the Contractor shall obtain a properly approved diffing permit before ground disturbance.

2.0 Requirements.

2.1 Description of Services. See Section 5.0 for the specific Common Level of Support (CLS).

2.1.1 Non-Personal Services. The personnel rendering the services are not subject; either by the contract's terms or by the manner of its administration, to the supervision and control usually prevailing in relationships between the Government and its employees. Non-personal service contracts are authorized by the Government in accordance with (IAW) Federal Acquisition Regulation (FAR) Subpart 37.104, under general contracting authority, and do not require specific statutory authorization.

2.1.2 General Information.

2.1.2.1 Transition (Phase In/Phase Out). The Contractor shall prepare and submit within ten (10) business days after contract award, a Phase In/Phase Out Plan to be implemented by the Contractor; to include IT/Network accounts and access with the appropriate Government organizations. The Contractor shall provide sufficient experienced personnel during the phase-in and phase-out period to ensure that the services are maintained at the required level of proficiency. During the phase-in, the Contractor shall observe all operations pertinent to the requirements of the PWS, to include office functions, procedures, operations, repair/maintenance operations, and any other operations as deemed necessary by the Contractor that will enable Contractor personnel to become both knowledgeable in, and familiar with, their assigned areas of responsibility. The Contractor shall commence all operations required by this PWS as of the first day of the contract start period. Therefore, on the initial day of performance, the Contractor

Annex A (Overarching Base Operations PWS) to OPORD 24-XXX: IMCOM Enterprise Base Operations (BASOPS) Performance Work Statement (PWS) Templates (U)

shall provide a work force which is fully qualified and capable of performing all work required under this contract.

2.1.2.2 Transition (Phase-Out). During the sixty (60) calendar day transition period immediately prior to the end of the previous contract, the Contractor shall permit the successor Contractor (and the successor Contractor's employees) to observe and become familiar with all operations under the contract. The Contractor shall not defer any needed repairs or maintenance for the purpose of transferring responsibility to the successor Contractor. The Contractor shall fully cooperate with the successor Contractor and the Government so as not to interfere with their work or duties.

2.1.3 Place of Performance and Hours of Operation.

The work to be performed under this contract will be performed at Fort Gordon, GA, which lies approximately ten (10) miles west of Augusta, GA. The post is surrounded by the communities of Grovetown, Harlem, and Hephzibah. The post can be easily reached from Interstate 20 by following Jimmie Dyess Parkway. Additional work sites are the Pointes West Army Recreational Site, located on Thurmond Lake, approximately twenty (20) miles northwest of Fort Gordon, GA. and Gillem Enclave, located in Georgia, Clayton County, city of Forest Park.

2.1.3.2 Hours of Operation. The Contractor shall conduct business, between the hours of 0730 to 1600, Monday through Friday, excluding Federal holidays or when the Government facilities are closed due to local or national emergencies, administrative closings, or similar Government directed facility closings. The Contractor shall maintain an adequate workforce for the uninterrupted performance of all tasks defined within this PWS when the Government facility is not closed for the above reasons. The Contractor shall provide a staffed work reception section to be operated twenty-four (24) hours a day, seven (7) days a week and be capable of reception, processing and response to DMOs and/or customer requests during normal and outside of standard working hours.

2.1.4 Federal Holidays. The Contractor's performance shall not be required on the Federal public holidays listed below, unless there is a requirement to respond to a Priority 1, Emergency. Holidays occurring on weekends will be observed as directed by the Federal calendar (5 United States Code (U.S.C) § 6103, Government Organization and Employees, Holidays).

New Year's Day	1st day of January
Martin Luther King Jr.'s Birthday	3rd Monday of January
Presidents Day	3rd Monday of February
Memorial Day	Last Monday of May
Juneteenth	19th day of June
Independence Day	4th day of July
Labor Day	1st Monday of September

Annex A (Overarching Base Operations PWS) to OPORD 24-XXX: IMCOM Enterprise Base Operations (BASOPS) Performance Work Statement (PWS) Templates (U)

Columbus Day	2nd Monday of October
Veterans Day	11th day of November
Thanksgiving Day	4th Thursday of November
Christmas Day	25th day of December

NOTE: When a holiday falls on a Sunday, the following Monday will be observed as a holiday, and, when a holiday falls on a Friday or Saturday, the preceding Thursday is observed as a holiday by U.S. Government Agencies. Federal holidays also include any Presidential or Congressionally designated days off other than the holidays listed above.

2.1.4.1 The Contractor shall provide personnel support within (2) hours of notification outside the normal hours of operation as required, including holidays, to support the Directorate of Public Works (DPW) mission. Prior to the performance of services outside the locally established hours of operation, the Contractor shall request and obtain, in writing, approval from the KO. The Project Manager shall be available after normal hours to serve as the central point of contact for Contractor operations. Contractor personnel shall not be scheduled for overtime work.

2.1.4.2 Installation Closures.

When an unforeseen installation closure occurs on a regularly scheduled day of work, the Contractor shall reschedule the work to be performed the following day unless the following day is a Saturday, Sunday, a recognized Federal holiday, and when routine work is not scheduled for that day; or reschedule the work for the next business day following the closure.

2.1.4.3 Inclement Weather Delay. The Contractor will be notified via the Installation Thor-Guard system of any inclement weather conditions in the immediate area. The KO/COR will notify the Contractor when to curtail operations, IAW the Fort Gordon Severe Weather Emergency Action Plan, (SWEAP). Based on the SWEAP, the COR shall notify the Contractor when to resume operations.

2.1.4.4 Curtailment of Operations. When operations are curtailed due to manmade or natural conditions on a working day, it may be necessary for the KO/COR to interrupt that day's work under this contract. The Contractor shall reschedule the work on any day acceptable to the Government. If the KO agrees, the Contractor may continue the work as scheduled. The KO will provide verbal announcements of immediate curtailment of operations to the Contractor.

2.1.4.5 Days of No Scheduled Activities (DONSA). The Installation has historically granted Military personnel (Enlisted and Officers) DONSA, for example, the Friday after Thanksgiving, in addition to the listed Federal Holidays above.

- DONSA are not considered a day of excused absence for the Government civilian work force or Contractor employees.

Annex A (Overarching Base Operations PWS) to OPORD 24-XXX: IMCOM Enterprise Base Operations (BASOPS) Performance Work Statement (PWS) Templates (U)

- If a DONSA affects scheduled contract work or access to facilities, the work in affected facilities may be rescheduled to compensate for the DONSA.
- However, announced DONSA or exodus of Military personnel may provide the Contractor with an opportunity for unrestricted access to facilities and areas or uninterrupted performance of work (i.e., training facility and area maintenance and supply inventories).

The Contractor shall vary work schedules to take full advantage of such opportunities by planning maintenance that is better accomplished when personnel are not using facilities during those times.

2.1.5 Travel/Temporary Duty. N/A

2.1.6 Emergency Services.

2.1.6.1 Emergency Medical Treatment. The Contractor or their employees shall immediately notify their supervisor of any accident requiring emergency medical treatment. The Contractor shall notify the COR no later than (NLT) two (2) hours of the incident. The Contractor shall be responsible for the emergency medical treatment services for Contractor personnel. However, the Government will provide, on an emergency basis, medical services for injuries incurred while an employee is performing under the PWS. The Contractor shall reimburse the Government for emergency medical services provided, upon receipt of invoice from the medical facility. Reimbursement shall be made to the United States Government.

2.1.6.2 Accident Reporting. The Contractor shall comply with Operational Safety and Health Administration (OSHA) for record keeping and reporting of all accidents resulting in death, injury, occupational disease, or adverse environmental impact. The Contractor shall provide a verbal report to the COR within one (1) hour of each such occurrence. A completed typed original plus one (1) copy of ENG Form 3394 United States Army Corps of Engineers Accident Investigation Report (or equivalent reporting form) shall be delivered to the COR within five (5) business days of occurrence, whenever an accident involving personal injury or Government owned property occurs.

2.1.7 Contract Administration and Management.

2.1.7.1 The Contractor shall attend the post award conference convened by the Contracting Activity or Contract Administration Office as agreed upon and stated in the contract award document. The KO, COR and DPW Management will meet monthly with the Contractor to review the Contractor's performance. The written minutes of meetings will be recorded by the Contractor and signed by both the Project Manager (PM) and the KO. The written minutes will be distributed within two (2) business days after the meeting. If the Government does not concur with any portion of the minutes recorded by the Contractor, the non-concurrence shall be provided in writing by the COR within two (2) workdays following receipt of the minutes. Notwithstanding, the Contractor's responsibility for total management during the performance of this contract, the administration of

Annex A (Overarching Base Operations PWS) to OPORD 24-XXX: IMCOM Enterprise Base Operations (BASOPS) Performance Work Statement (PWS) Templates (U)

the contract requires maximum coordination and cooperation between the Government and the Contractor. Deliverable A0002, Meeting Minutes.

2.1.7.2 Notwithstanding the Contractor's responsibility for total management during the performance of this contract, the administration of the contract requires maximum coordination and cooperation between the Government and the Contractor.

2.1.7.3 The following provides the roles and their respective authority during the performance of the contract:

2.1.7.3.1 Contracting Officer (KO). The KO is the only person authorized to direct changes in any of the requirements under this contract, and, notwithstanding any provisions contained elsewhere in this contract, said authority remains solely with the KO. In the event the Contractor makes any change in the direction of any person other than the KO, the change shall be considered to have been made without authority and solely at the risk of the Contractor. All contract administration will be affected by KO. Communications pertaining to contractual administrative matters shall be addressed to the KO. No changes in or deviation from the terms and conditions shall be affected, without a written modification to the contract, executed by the KO authorizing such changes. The KO will approve all submittals and plans required in this PWS.

2.1.7.3.2 Contracting Officer's Representative (COR). The KO will appoint a COR during the performance of this contract. Additional Government personnel may be assigned to assist in contract oversight IAW AR 70-13, *Management and Oversight of Service Acquisitions*. Other surveillance personnel may be designated as COR or Alternate Contracting Officer's Representative (ACOR), and shall be trained and appointed IAW DoDI 5000.72, *DoD Standard for Contracting Officer's Representative (COR) Certification* and DFARS 201.602-2. The Alternate Contracting Officer Representative (ACOR) will serve as on-site representatives of the COR in the performance of actual contract surveillance, if they meet all COR training and experience requirements, and are appointed by the KO as an ACOR. The COR/ACOR will provide assistance in identification and resolution of problems, conflicts in priority, subtask requirement definitions, and other operations type problems. The COR/ACOR will perform IAW the responsibilities and duties identified in the appointment letter.

2.1.7.3.2.1 COR Authority. A letter of designation will be issued to the COR/ACOR by the KO. A copy of the letter will be sent to the Contractor. The letter of designation states the responsibilities and limitations of the COR/ACOR, especially regarding changes in cost, price estimates, or changes in delivery dates. The COR/ACOR is not authorized to change any of the terms and conditions regarding cost, quantity, or schedule of the resulting order.

Annex A (Overarching Base Operations PWS) to OPORD 24-XXX: IMCOM Enterprise Base Operations (BASOPS) Performance Work Statement (PWS) Templates (U)

2.1.7.3.3. The Contractor shall not in any way represent the United States (U.S.) Government, or that it has the authority to contract or procure supplies for the account of the United States of America (USA).

2.1.8 COR/ACOR Functions. The COR/ACOR monitors all technical aspects of the contract and assists in contract administration. The COR/ACOR is authorized to perform the following functions: assure the Contractor performs the technical requirements of the contract; perform inspections necessary in connection with contract performance; maintain written and oral communications with the Contractor concerning technical aspects of the contract; issue written interpretations of technical requirements; monitor, document, and report Contractor's performance and notify both the KO and Contractor of any deficiencies; coordinate availability of Government-Furnished Property, and coordinate site entry of Contractor personnel.

2.1.9 Quality Control (QC). Quality Control is the responsibility of the Contractor. The Contractor shall provide a Quality Control Plan (QCP) five (5) business days before contract start. The Contractor shall provide and maintain a QCP that is acceptable to the KO. Changes to the Contractor's QCP shall be submitted to the KO for review and approval within five (5) business days prior to implementation.

2.1.10 Subcontract Management. N/A

2.1.11 Contractor Employees.

2.1.11.1 Key Personnel.

2.1.11.1.1. Project Manager (PM). The Contractor shall provide a PM who is responsible for the performance of the work. The PM shall have full authority to act for the Contractor on all contract matters relating to daily operation of the contract. The PM shall have a baccalaureate degree from an accredited College or University and five (5) years of experience in base support management or a contract similar in scope and breadth to this solicitation. The name of the PM shall be provided by the Contractor to the KO. In the circumstances when the PM is not available, the Contractor shall designate an alternate who can perform the same duties during the absence of the Project Manager. The name of this person and an alternate who shall act for the Contractor when the manager is absent shall be designated in writing to the contracting officer at the start of the contract. The PM or alternate shall be available 24/7/365 including Federal holidays. The PM shall be available between 0700 - 1600 hours, Monday through Friday except Federal holidays or when the Government facility is closed for administrative reasons. The PM and any individuals designated as key personnel shall be able to understand, speak, read, and write the English language.

2.1.11.1.2 GFEBS PM Coordinator Lead. The GFEBS PM Coordinator Lead shall have demonstrated experience in successfully utilizing GFEBS on a Military Installation. The name of the GFEBS PM Coordinator Lead shall be provided by the Contractor to the COR/ACOR. The GFEBS PM Coordinator Lead shall be available between

Annex A (Overarching Base Operations PWS) to OPORD 24-XXX: IMCOM Enterprise Base Operations (BASOPS) Performance Work Statement (PWS) Templates (U)

0800 - 1600 hours, Monday through Friday, except Federal holidays or when the Government facility is closed for administrative reasons. The GFEBS PM Coordinator Lead shall have the following roles in GFEBS:

- A76 DPW Contractor PM Master Data Maintainer
- A76 DPW Contractor Preventative Maintenance Controller
- A76 DPW Contractor GR Processor
- A76 DPW Contractor Physical Inventory Maintainer
- A76 DPW Contractor PM Material Requirement Planning Maintainer
- A76 DPW Contractor PM Order Approver
- A76 DPW Contractor PM Order Maintainer
- A76 DPW Contractor PM Reporter

2.1.11.1.3 GFEBS Certification. The Contractor designated GFEBS Coordinator shall possess a working knowledge of GFEBS and shall complete GFEBS training modules provided by the Government within thirty (30) business days of contract award date. **The Contractor shall provide certificates of completion for all roles required to perform the requirements of the position upon Government request.** The Contractor/GFEBS Coordinator shall be responsible for GFEBS data entry and reporting.

2.1.11.1.3.1 General Fund Enterprise Business System, GFEBS, required Contractor roles and associated training is found in TE A-6.5, A76 Financial & Plant Maintenance Roles and Courses.

2.1.11.1.4 Common Access Card (CAC). Certain designated Contractor personnel will require a Common Access Card (CAC) to access Government systems. Each CAC badge shall be issued prior to any employees performing work under this contract IAW FAR 52.204-9, *Personal Identity Verification of Contractor Personnel*, Homeland Security Presidential Directive 12 (HSPD-12), and Federal Information Processing Standards Publication 210-2 (FIPS PUB 201). Contractor personnel with routine physical access to a Federally controlled facility shall be issued a common identifier with specific security registration and identity proofing objectives. Specifically, Fort Gordon meets this requirement by using the CAC for all such federal employees and contractors.

2.1.11.1.5 U.S. Residency. All Contractor employees shall be legal U.S. residents. The Contractor shall immediately remove any employee that is not a legal U.S. resident. The Contractor personnel shall be able to communicate clearly in the English language.

2.1.11.1.6 Qualification Standards. The Contractor shall inspect, repair, and maintain systems and components associated with facilities listed in real property records as required throughout this contract utilizing properly trained, skilled, and qualified employees or Sub-contractor personnel.

Annex A (Overarching Base Operations PWS) to OPORD 24-XXX: IMCOM Enterprise Base Operations (BASOPS) Performance Work Statement (PWS) Templates (U)

2.1.11.1.7 Contractor Identification. The Contractor shall ensure all personnel be identified as a Contractor to distinguish themselves (e.g., badge, company logo, or uniform) from Government employees. The Contractor shall ensure all correspondence and reports produced are marked as Contractor products or that Contractor participation is disclosed.

2.1.11.1.8 Standards of Conduct. Contractor personnel's conduct shall not reflect discredit upon the Government. The Contractor shall ensure all personnel present a professional appearance while working on the Government Installation. The Contractor's employees shall observe and comply with all local policies and procedures concerning fire, safety, environmental protection, sanitation, security, and possession of firearms or other lethal or illegal weapons or substance. The Contractor shall ensure all Contractor employees, providing services under this contract, conduct themselves and perform services in a professional, safe, and responsible manner. The Contractor shall remove, from the job site, any employee for reasons of misconduct or security. The Contractor shall ensure employee conduct complies with 41 USC 423, *Procurement Integrity*. The Contractor shall also ensure that no Contractor employees conduct political related activities or events on the Installation. The removal of such a person shall not relieve the Contractor of the requirement to provide personnel to perform adequate and timely service.

2.1.11.1.9 Contractor Hiring Restrictions. The Contractor shall not hire or sub-contract with off duty or former Government employees whose employment would result in a conflict with Joint Ethics Regulation (JER) DoD 5500.07-R.

2.1.12 Business Relations. The Contractor shall successfully integrate and coordinate all activity needed to execute the requirement of this PWS. The Contractor shall manage the timeliness, completeness, and quality of problem identification to a degree acceptable to the Government. The Contractor shall provide the KO corrective action plans, timely identification of issues, and effective management of subcontractors. The Contractor shall ensure customer satisfaction and professional and ethical behavior of all Contractor personnel.

2.1.13 Manual Operations. The Contractor shall establish a contingency plan for manual operations in the event of a loss of power or other utilities that disables the Contractor's ability to computer process the DMO/OWO/PMO and PWO related work documentation. **The plan shall be delivered to the KO within fifteen (15) business days after the contract award date.** Provisions should also be made for providing work related data to the DPW Work Management (WK MGMT) to update data into the Government system (GFEBS) on a delayed basis in case the network or system is down. The contingency plan shall include coordination with DPW WK MGMT and its operations. Deliverable A1082, Manual Operations Plan.

2.2 Work Management. Applicable to all CLS. All coordination requirements in this section and inherent to this Contract shall take into consideration the DPW WK MGMT and

Annex A (Overarching Base Operations PWS) to OPORD 24-XXX: IMCOM Enterprise Base Operations (BASOPS) Performance Work Statement (PWS) Templates (U)

their operations. Work requirements, timelines, and execution shall include coordination with the DPW WK MGMT.

2.2.1 Coordination. As a part of the work scheduling process, the Contractor shall coordinate all work with the Building/Facility Manager in charge of the facility where the work is to be scheduled and accomplished.

2.2.2 General Fund Enterprise Business System (GFEBS).

GFEBS is the web-based asset and accounting system of record for the Government. The Government will use GFEBS as a production scheduling and monitoring system for determining the status of work, maintenance, and repair expenditures against individual facilities. GFEBS is the official system of record for all Real Property Maintenance Activity (RPMA). The Contractor shall utilize GFEBS, in establishing the receipt, scheduling, and tracking procedures for the handling of DMOs (formerly known as Service Calls/Service Orders) received from the customer, for Operations Work Orders (OWOs) [formerly known as Standing Operations Orders (SOOs)], Preventive Maintenance Orders (PMOs) and PWOs received from the Government. A crosswalk of terms (GFEBS term to Government term) can be found at <https://www.gfebs.army.mil>. When PWOs are received from the Government, the Contractor will also utilize Fort Gordon's official project management system [i.e., GFEBS c-Projects] for tracking purposes. Work management system input shall include but is not limited to recording of receipt, status and data reporting, and filing. Deliverable A0001, Monthly Functional Workload Update in GFEBS.

The submission of specific labor rates for each labor category, included in the Contractor's offer, will be required to calculate a shop rate to be utilized within the GFEBS system.

2.2.2.1 Army Maintenance Application (ArMA): A web service available for customers to request maintenance services by use of computer or mobile devices (smart phone) and receive status updates on requests or orders. Current IMCOM ArMA Business Rules can be found at Main_ArMA_Overview (deps.mil). Requests received through ArMA will follow the same classification and priority of services needed as in Annex B.

2.2.2.1.1 Contingency Plan: The Contractor shall include in the Contingency plan the continuing Service Order Desk operations to cover the ArMA system. The Plan shall include coordination with the DPW Contractors during the events, the entry of ArMA requests backlog and work-related documentation once the system is available.

2.2.2.2 Transition (Phase-in) Plan: The Contractor shall include in the Transition (Phase-in) Plan in the transition of the operations to include the ArMA website.

2.2.2.1.3 ArMA and GFEBS: DMOs and OWOs assigned to any facility shall be primarily processed in the ArMA followed by GFEBS processing, or as required by the Government. The Contractor shall monitor ArMA in real-time, create requests, process requests, respond and communicate with customers, and close orders. In the event when

Annex A (Overarching Base Operations PWS) to OPORD 24-XXX: IMCOM Enterprise Base Operations (BASOPS) Performance Work Statement (PWS) Templates (U)

ArMA and GFEBS do not interface; the Contractor shall manually update both systems when required. The Contractor shall ensure ArMA and GFEBS information are identical for all applicable fields. The Contractor shall process unassigned requests immediately upon receipt.

Notifications created by the ArMA website in GFEBS, the Contractor shall be updated and processed in GFEBS.

2.2.2.1.4 Duplicate Orders. The Contractor shall monitor for duplicate orders. If more than one (1) service order is submitted for work, similar in nature, associated with the same building and room number (if applicable), the orders shall be treated as a single order and documented as one (1) in ArMA. The Contractor shall reconcile duplicate orders with the customers on the ArMA website and cancel duplicate orders in ArMA.

NOTE: Government systems and database of records are subject to updates, modifications, end of service life preparation and migration to new systems will occur at the discretion of the Army.

2.2.3 Demand Maintenance Orders (DMOs). Contractor oversees the DMO Desk or Work Control.

2.2.3.1 DMO Work Control. The Contractor shall establish a DMO help desk, commonly referred as Work Control for the initiation and execution of all DMOs. Contractor will monitor ArMA 24/7/365. The Contractor shall provide ArMA/GFEBS DMO Dispatcher(s) to input all DMO data into GFEBS on a daily basis. This individual(s) shall be on duty onsite Monday through Friday from **0700 hours to 1600 hours**. The Contractor shall also produce upon request by the COR/ACOR the following reports: Installation Status Reports (ISR), Strategic Management System (SMS), Project Status, and Unfunded Requirements lists. The Contractor shall receive notification of work from authorized customers by means of telephone call, in person customer request, via ArMA, email, or directly from the KO/COR. The Contractor shall establish a dedicated telephone number to be used exclusively for receipt of DMOs. The line shall be available to receive calls twenty-four (24) hours a day, seven (7) days a week, throughout the entire calendar year. During normal duty hours, the service call desk shall be manned. The person(s) performing work reception shall be fully familiar with the Contractor's organization and procedures as well as the terms and response factors specified herein. During non-duty hours, the DMO Work Control may be operated remotely. The Contractor is authorized to execute DMOs that do not exceed thirty-two (32) work hours in labor. The work control team shall have at least one (1) year of experience entering maintenance orders into GFEBS, charging time and materials on the orders, and running/analyzing maintenance order reports.

2.2.3.2 DMO Call Receipt and Entry. The Contractor shall process all DMOs in ArMA and GFEBS IAW the priority timelines listed below. As part of the receipt process the Contractor shall ensure all required customer information is provided: work/problem na-

Annex A (Overarching Base Operations PWS) to OPORD 24-XXX: IMCOM Enterprise Base Operations (BASOPS) Performance Work Statement (PWS) Templates (U)

ture; location of service work requirement, including the facility number; name and telephone number of requestor, and priority level and enter it into GFEBS (TE A-6.1 DMO Task Codes). Based on the customer provided information and the criteria established in TE A-6.1, the Contractor shall establish the priority and assign it to the appropriate shop. For life threatening emergencies (DMO priority 1), the service call desk shall notify the appropriate shop within five (5) minutes and complete the work in one (1) calendar day. Once the DMO has been completed by the appropriate technician, the Contractor will charge hours and time for the order in GFEBS. The customer will request maintenance orders through ArMA. All DMOs shall be entered into GFEBS within the following timelines:

- Priority 1 (Emergency) DMOs received via ArMA or directly to the DMO Desk shall be entered within thirty (30) minutes of receipt of service call into GFEBS by the Contractor. DMOs are classified as Emergency (Priority 1) when immediate action is required to eliminate life threatening or serious injury hazards to personnel. These DMOs are responded to as soon as possible and no later than one (1) hour after the request. Emergency/Critical DMOs are completed within twenty-four (24) hours of request unless the urgency of the work has been reduced to a Priority 2 or 3.
- Priority 2 (Urgent) DMOs received via ArMA or directly to the DMO Desk shall be entered within thirty (30) minutes into GFEBS by the Contractor and completed within seven (7) calendar days from receipt, unless reduced to a Priority 3 by the COR. Mold related priority 2 (urgent) DMOs must be responded to within 24 hours when received during normal business days.
- Priority 3 (Routine) DMOs received via ArMA or directly to the DMO Desk shall be entered within thirty (30) minutes into GFEBS by the Contractor and completed within thirty (30) calendar days of receipt.

2.2.3.3 GFEBS and/or ArMA Case Number. ArMA case number are auto generated after a customer submits the case. This ArMA Case number shall function as a reference number for customer inquiries and Government surveillance purposes.

2.2.3.4 Completed Work. The Contractor, certifying the work was satisfactorily performed, shall sign completed work authorizations. After completion of each work order, the Contractor shall identify (using GFEBS T-CODE IW38) the total labor hours the technician worked and the fully burdened rate based on shop (e.g., carpentry, electrical, plumbing, etc.). Within seven (7) days of DMO issuance, the Contractor shall TECO the DMO to close out the order.

2.2.4 Preventive Maintenance Orders (PMOs). The Contractor shall perform all PMOs for the facilities and equipment listed in TE A-6.2, TE A-6.3 and TE H-001. The Contractor technicians shall complete scheduled PM work within five (5) days for monthly PM's, fourteen days for quarterly PMs, and thirty (30) days for semi-annual and annual PMs. Until the PMO program as described in paragraph 2.2.5 below is complete, the Contractor shall execute PMOs IAW historical PM data provided in **TE XX**. Within seven (7) days of PMO completion, the Contractor shall TECO the PMO in GFEBS.

Annex A (Overarching Base Operations PWS) to OPORD 24-XXX: IMCOM Enterprise Base Operations (BASOPS) Performance Work Statement (PWS) Templates (U)

2.2.4.1 PMO Program. The Contractor shall develop and execute a PMO program. The Contractor shall first verify and update the equipment listed in TE H-001 for the buildings listed in TE A-6.2 and TE A-6.3. During the equipment inventory assessment, the Contractor shall, at a minimum, collect the equipment Maintenance Control Designation (MCD), serial number, equipment description, work center (shop), building number, frequency basis for that equipment (e.g., monthly, quarterly, annually, etc.), maintenance plan and task list. Upon completion of the equipment verification, the PMO program shall be developed and entered into GFEBS. The PMO program shall be completed and fully operational in GFEBS no later than ninety (90) days after contract start date. The Contractor shall be responsible for maintaining the accuracy and currency of the equipment list and associated PM Schedules in GFEBS throughout the life of the contract.

2.2.4.2 PMO Schedules. Once the PMO Program is established in GFEBS, the Contractor shall create a PM scheduler. The Contractor shall continually update the list as required with the DPW Operations and Maintenance Division. The PM scheduler should be Microsoft Excel based and includes work center, maintenance plan, equipment number, equipment description, building number, frequency, task list, date called/scheduled, and any additional notes pertinent to the PM (e.g., date added, new building, etc.). Additionally, by close of business each week, the Contractor shall provide the COR in Microsoft Excel, a project PM planning schedule of work to be accomplished in the following week.

2.2.4.3 Approved PM Schedule. The Contractor shall strictly adhere to the scheduled PM dates to facilitate verification of work by the COR/ACOR in GFEBS. If the Contractor finds it necessary to reschedule a PM, a written request shall be made to the COR/ACOR detailing the reasons for the proposed change at least five (5) working days prior to the originally scheduled PM date. No scheduled PM dates shall be changed without the prior written approval of COR/ACOR.

2.2.4.4 PMO Stickers/Log. Upon completion of the PM inspection, the Contractor shall attach a sticker to the equipment item (or in the immediate vicinity thereof) indicating the equipment MCD number, the date of maintenance, and the initials and identification number of the Contractor employee who performed the work. PM will not be considered performed unless the sticker is current and affixed, and a Labor & Equipment (L&E) Utilization Preventive Maintenance (EHSC Form 4288-2) line entry is made to document the PM action. The PM sticker information which includes the MCD number, date of maintenance and warranty information will be added into GFEBS-by-GFEBS T- code "IE01." In instances where a PMO sticker is not practicable, then the Contractor may elect to maintain a current PMO log in lieu of a sticker.

2.2.4.5 Warranty Program. The Contractor shall establish and maintain a Warranty Program to warrant all equipment, parts, components, where the manufacturers provide a warranty and shall be exercised for the duration of this contract. The Contractor shall input the warranty information into GFEBS and provide the COR/ACOR & PM Coordinator with a copy of the warranty and manual for all equipment in an excel sheet format.

Annex A (Overarching Base Operations PWS) to OPORD 24-XXX: IMCOM Enterprise Base Operations (BASOPS) Performance Work Statement (PWS) Templates (U)

The warranty excel sheet should be updated as warranty information changes for the equipment. The warranty information in the excel sheet should match exactly what is in GFEBS. The Contractor shall provide a plan for managing warranties with the technical proposal. All warranty data shall be returned to the Government at contract completion.

When Contractor personnel determine that a warranted item not installed by the Contractor requires service, the Contractor shall notify the COR in writing no later than 0900 the next working day or give telephone notification within fifteen (15) minutes of detection if the deficiency threatens damage to personnel or property. The COR/ACOR will direct the Contractor to: (1) repair the deficiency if potential damage may result from deferring repairs; or (2) clean the work area and stop work. The Contractor shall not receive payment for work not authorized by the COR/ACOR which is performed on warranted equipment, unless the COR/ACOR concurs that such work was a legitimate response to a true emergency condition.

2.2.4.6 Operation and Maintenance (O&M) Manual Digital Library. The Contractor shall create and maintain a current electronic repository of all O&M Manuals from the manufacturer or supplier for all facilities and equipment delineated in the Contractor's PMO program. The repository shall be organized by a shop/work center.

2.2.5 Operations Work Orders (OWOs). The Contractor shall respond to, and complete individual tasks related to OWOs. An OWO is recurring maintenance, cyclical in nature, outside of GFEBS scheduled PM, requested demand maintenance, or projects. Support for recurring OWOs is referenced in TE A-2.3. If a new OWO is required in addition to those identified in TE A-2.3, then a DA Form 4283, *Facilities Engineering Work Requests*, will be issued and shall serve as the authorization document for the initiation and execution of the OWO. In addition to performing OWOs on TE A-2.3, The Contractor shall perform duties including but not limited to maintaining and updating the TE's referenced in the TE Index as needed. The Contractor shall provide TE updates and TE Index updates electronically to the COR/ACOR as needed throughout the life of the Contract.

2.2.6 Project Work Orders (PWOs).

2.2.6.1 DA Form 4283, *Facilities Engineering Work Requests*, shall serve as the authorization document for the initiation and execution of PWOs. The DA Form 4283 shall be submitted to the BOID for processing and approval. The Contractor will be tasked with approximately 300 PWOs per year for execution. For DMO generated PWOs, a DA Form 4283 is not required. These PWOs are included in the fixed price CLIN for maintenance services. TE A-2.2 provides historical data on the number of PWOs generated from DMOs. The PWO (4283 form) should cover the following parameters:

- a. Actual labor hours, materials, and costs for items other than pre-expended bin materials expended.
- b. Government representative signature indicating work has been performed and date.
If representative is not available, the Contractor shall so note on the DMO document.
- c. MCD number of equipment items and/or facility worked on under the DMO.

Annex A (Overarching Base Operations PWS) to OPORD 24-XXX: IMCOM Enterprise Base Operations (BASOPS) Performance Work Statement (PWS) Templates (U)

- d. As-built information for any utility infrastructure changes made during the work, or operation and maintenance manuals for any installed equipment (as applicable).
- e. sketch-indicating the area where work was performed and schematic of activities (as applicable).
- f. Digital photos before and after work performance (as applicable).

2.2.6.1.1 Conversion of DMO to PWO. The Contractor shall not at any time exceed thirty-two (32) hours and /or \$15,000 material cost during the performance of a DMO without approval by the KO/COR. The Contractor may determine that a DMO, as requested, will exceed the hour threshold during execution or prior to execution. The procedures for each circumstance are detailed below.

2.2.6.1.2 Conversion during Execution. The Contractor shall stop work immediately upon determining that a DMO will exceed the thirty-two (32) hours \$15,000 material cost threshold. The Contractor shall immediately notify the KO/COR of the status of the DMO and complete the following tasks:

- The Contractor shall notify the KO/COR in writing of the reason for expecting the DMO to exceed the cost threshold.
- The Government may initiate a PWO or cancel the DMO.
- If the Government initiates a PWO, the Contractor shall proceed as described in Section 2.2.6.
- If the Government cancels the DMO, the Contractor shall cease work and leave the work site in a safe and stable condition.

2.2.6.1.3 Conversion Prior to Execution. The Contractor shall immediately notify the KO/COR of the expectation that a DMO will exceed the cost threshold and conduct no work. The Contractor shall then complete the following tasks:

- The Contractor shall notify the KO/COR in writing of the reason for expecting the DMO to exceed the cost threshold and a preliminary cost estimate.
- The Government may initiate a PWO, cancel the DMO or adjust the DMO scope.
- If the Government initiates a PWO and determines the requirement urgently then the Contractor shall proceed as described in Section 2.2.6.
- If the Government initiates a PWO and does not determine the requirement urgently then the Contractor shall proceed as if receiving a normal PWO request.

2.2.6.2 Cost Estimates for PWOs. The Contractor will provide the Government with a DA Form 4283 that delineates the scope of the project. PWOs that exceed \$150,000 shall be accomplished through a separate contractual vehicle.

The OWO/PWO will be negotiated as follows:

Annex A (Overarching Base Operations PWS) to OPORD 24-XXX: IMCOM Enterprise Base Operations (BASOPS) Performance Work Statement (PWS) Templates (U)

- a. The Contractor shall provide the preliminary desktop (scoping), design as required, and cost estimate based on the DA Form 4283 to the COR within five (5) working days of receipt.
- b. When requested in writing by the COR, the Contractor will provide detailed scoping, design, and cost estimates within ten (10) working days of receipt of the request.
- c. All other OWO/PWO detailed scoping, design, and cost estimates shall be submitted within thirty (30) business days of receipt of the request.
- d. Negotiate the terms and conditions of the OWO/PWO, to include a scheduled completion date.
- e. KO will issue a notice to proceed with a memorandum to the Contractor to perform the OWO/PWO effort agreed upon.
- f. The Contractor shall bill for all approved OWOs/PWOs consistent with the direction provided at FAR 52.232-5, Payments under Fixed-Price Construction Contracts.

It is estimated that the number of detailed estimates required under this contract will be approximately 200 per year.

2.2.6.3 Preparation of Detailed Estimates. The Contractor shall prepare detailed estimates of the labor, equipment and materials required to complete PWO work using industry accepted estimating procedures and data from RSMeans, Building Construction Cost Data, or other appropriate estimating sources approved by the COR. All estimates, supporting information, documentation, and calculations shall be submitted to the COR.

2.2.6.4 Subcontract Work. PWOs subcontracted IAW with the Contractor's purchasing system where three (3) independent offers are obtained, and the low offer is accepted will not require a detailed cost estimate. Work, which the Contractor proposes to subcontract, shall be identified in the estimate. Information, documentation, and calculation required for subcontract work is the same as that required for work to be performed by the Contractor's work force.

2.2.6.5 Specialty Subcontracting Work. For specialized services where estimating software or other estimating standards are not applicable, the Contractor shall prepare a proposal that shall include a minimum of three (3) Subcontractor quotes. Quotes shall include all labor, material, and equipment necessary for Subcontractor to complete the work to be performed on the work request. If the work is of such a type that only one (1) Subcontractor can be found to perform the work, then a proposal, including breakout of costs, shall be provided sufficient for the KO to determine that the price is reasonable. If only one (1) Subcontractor is solicited the Contractor shall provide information to the KO sufficient to justify the sole source procurement.

2.2.6.6 Execution of PWO Work. The Contractor shall provide proposals for all PWO Work addressing the scope, performance schedule and proposed price. The proposal shall provide supporting data presented including labor, and other direct costs such as equipment, material, and subcontract estimates. The COR will evaluate the Contractor's estimate to determine if: (1) the scope has been clearly and accurately identified,

Annex A (Overarching Base Operations PWS) to OPORD 24-XXX: IMCOM Enterprise Base Operations (BASOPS) Performance Work Statement (PWS) Templates (U)

(2) the task hours have been properly estimated with supporting data presented, and (3) equipment, material, and subcontract estimates are reasonable and properly documented and provide recommendations to KO. After the estimate has been reviewed, the KO will determine whether to approve or negotiate elements of the PWO. Upon KO acceptance or negotiation of the proposed PWO, KO will execute a delivery order.

2.2.6.7 Wage Rates for PWOs. Specific work shall be subject to wage rates under the Construction Wage Rates as identified in Section J of the contract.

2.2.6.8 PWO Bi-weekly Meetings. The Contractor shall attend a biweekly meeting with DPW personnel to provide schedule updates for all current PWOs. Schedules shall include as a minimum for each work order: (a) Change Order Number (if applicable), (b) Facility Designation, (c) Priority, (d) Initials of Quality Assurance Specialist assigned to the work order, (e) Total person hours as issued by ACO, (f) Level of work (II or III, as applicable), (g) Description of Scope of Work, (h) Date Contractor received request for proposal, (i) Date Contractor submitted proposal to Government, (j) Date work order received by Contractor, (k) Date work order will start and required completion date, (l) Percentage complete, and (m) Pertinent comments (i.e., phase of work currently in process, delivery date for materials, reason for stoppage or delay (if applicable), etc.). **The Contractor will take meeting minutes during the meeting and will send to the COR and BOID PM Coordinator within two (2) business days.**

2.2.6.9 PWO Records. **The Contractor shall maintain a record of all PWOs executed under the contract. All records related to PWOs shall be made available to the COR/ACOR upon request.** All records are the property of the Government and shall be turned over to the Government upon completion or termination of the contract.

2.2.6.10 PWO Reporting Requirements. **The Contractor shall provide a monthly report on PWO's no later than the fifth (5th) day of every month to the COR. The report will be in the format approved by the COR. Format changes can be implemented and/or approved by the COR as needed.**

2.2.7 Warranty Program. The DPW PM Plan within GFEBS identifies warranty of all equipment, parts, components, where the manufacturers provide a warranty and shall be exercised for the duration of this contract. GFEBS Records identify the item, the nature and expiration date of the warranty, and the name and location of the firm to contact about entitlement under the warranty. The Contractor shall update within GFEBS warranty records on any items of equipment or repair items to which the Government will take title, which shall be installed on Government property.

2.2.7.1 Warranty Enforcement Manager. The Contractor shall designate a Warranty Manager or Point of Contact (POC) to monitor and track all Government-owned equipment as identified by the Government as having a warranty.

Annex A (Overarching Base Operations PWS) to OPORD 24-XXX: IMCOM Enterprise Base Operations (BASOPS) Performance Work Statement (PWS) Templates (U)

2.2.7.2 Warranty Management. The Warranty Manager shall receive a daily listing of all DMOs from the DPW Work Control and review all DMOs (including DMOs assigned to other service providers) in facilities under warranty for possible warranty items.

2.2.7.3 Routing of Warranty DMOs. The Contractor personnel shall be familiar with all facilities and equipment under warranty to notify the Warranty Manager of DMOs requests impacting warranties. For DMOs assigned to other service providers, the Warranty Manager shall notify the service provider, who shall then determine if the problem is a valid warranty item. If the item is a valid warranty request, the service provider shall route the DMO back to the Warranty Manager and the DMO shall be routed to the warranty provider for repair. If the repair requirement item is not covered by the warranty, the DMO shall be completed by the service provider. Warranty items that may have been overlooked by the DMO review may be flagged by technicians or workmen as warranty items. In such cases, the DMO shall be routed back to the Warranty Manager and the DMO shall be routed to the warranty provider for repair. The contractor shall place warranty calls and track status until warranty repair has been completed.

2.2.7.4 Warranty Records. The Contractor shall comply with standard Army execution and warranty claim action reporting programs as defined in AR 700-139.

2.2.7.5 Exceptions. The existence of a warranty does not alleviate the Contractor of his responsibility to perform work needed to prevent potential damage to personnel and property or to prevent unnecessary shutdown of facilities and functions.

2.2.7.6 Technical Document Library Operation. The Contractor shall store, maintain, and make technical documents available to all Government personnel and others approved by DPW upon request. If electronic versions are available, the Contractor shall provide these via e-mail or other electronic media. If no electronic copy is available, the hardcopies will be scanned and sent to the Government personnel and others approved by DPW. Contractor shall obtain and record adequate contact information from the borrower, and the documents will be checked out for no longer than five (5) days. In the case where only one hardcopy exists, and the document cannot be scanned; the documents shall be made available for reference or for copies. The Contractor shall maintain all warranty documents in an electronic data base.

2.3 As-Builts. Applicable only for SERVICE 411, 414 and 420

2.3.1 Maintain As-Builts. The Contractor shall maintain as-built drawings. The Contractor shall be provided one (1) hard copy for the detailed Installation maps in **TE A-1.01**. The maps to be provided are the following: Heating & Cooling System, Installation Grounds, and Nature Trails System. Utility repairs, component replacements, modifications, alterations, and additions to all systems and components shall be electronically redlined as well as on the hard copy maps upon completion of work. The Contractor shall redline annotate all components replaced during the period of the contract and annotate all items removed from service.

Annex A (Overarching Base Operations PWS) to OPORD 24-XXX: IMCOM Enterprise Base Operations (BASOPS) Performance Work Statement (PWS) Templates (U)

2.3.1.1 Support. Hard copy markups and electronic redlines shall be delivered to the COR/ACOR at the completion of each major project as identified by the COR/ACOR or, at a minimum, at the end of each contract-year quarterly cycle. The Contractor shall validate all maps for accuracy and content.

2.3.2 Real Property Records Updates. When the Contractor is provided plans or drawings as part of a DMO or PWO, the Contractor shall be responsible for providing two (2) copies of marked up red lines drawings reflecting the changes, to the COR/ACOR. The Contractor shall submit these drawings prior to closing out the DMO or PWO. All electronic data and hard copy maps remain the property of the DPW and shall be turned over to the COR/ACOR upon completion of the contract.

2.3.3 Historic Property or Archaeological Site. Historic properties and archaeological sites are subject to the provisions of the *National Historic Preservation Act* (NHPA). The Contractor shall maintain the historic properties on the Installation IAW the NHPA, 54 United States Code (U.S.C) § 300101, *National Preservation*; 36 Code of Federal Regulations (CFR) Part 800, *Advisory Council on Historic Preservation*; and United Facilities Guide Specifications (UFGS). The Contractor shall comply with all applicable Federal Historical Structure and Archeological Laws. Location maps can be found at the local DPW.

2.3.4 Repair and Replacement. The Contractor shall report damages to the COR/ACOR within one (1) hour. The Contractor shall repair or replace parts with products similar in appearance to the original. Repairs, renovation, or replacement to historic buildings must be approved by the KO. The Contractor shall coordinate work through the Cultural Resources Manager. The Contractor shall comply with the appropriate provisions and stipulations of the Secretary of Interior's "*Standards for Rehabilitation and Guidelines for Rehabilitating Historic Buildings*" (Revised 1983) and the Integrated Cultural Resources Management Plan (TE A-6.6). Location maps are available at the DPW.

2.4 Historic Property or Archaeological Site. Historic properties and archaeological sites are subject to the provisions of the *National Historic Preservation Act* (NHPA). The Contractor shall maintain the historic properties on the Installation IAW the FNHPA, 54 United States Code (U.S.C) § 300101, *National Preservation*; 36 Code of Federal Regulations (CFR) Part 800, *Advisory Council on Historic Preservation*; and United Facilities Guide Specifications (UFGS). The Contractor shall comply with all applicable Federal Historical Structure and Archeological Laws. TE A-6.3 provides more detail on historic family housing properties at Fort Gordon. Location maps can be found at the local DPW.

2.4.1 Repair and Replacement. The Contractor shall report damages to the COR/ACOR within one (1) hour. The Contractor shall repair or replace parts with products similar in appearance to the original. Repairs, renovation, or replacement to historic buildings must be approved by the KO. The Contractor shall coordinate work

Annex A (Overarching Base Operations PWS) to OPORD 24-XXX: IMCOM Enterprise Base Operations (BASOPS) Performance Work Statement (PWS) Templates (U)

through the Cultural Resources Manager. The Contractor shall comply with the appropriate provisions and stipulations of the Secretary of Interior's "*Standards for Rehabilitation and Guidelines for Rehabilitating Historic Buildings*" (Revised 1983) and the Integrated Cultural Resources Management Plan (TE A-6.6). Location maps are available at the DPW.

2.4.2 Salvage. The Government retains all salvage rights to replaced property of value. The Government will determine the value of the property. Items of no value shall be disposed of at the Contractor's expense. For items of value, and for all Government equipment regardless of value, the Contractor shall prepare DD Form 1348-1 for property disposal.

2.5 Special Requirements.

2.5.1 Security.

2.5.1.1 Access and General Protection/Security Policy and Procedures. The Contractor and all associated Subcontractors' employees shall comply with applicable Installation, facility, and local security policies and procedures. The Contractor workforce shall comply with all personal identity verification (PIV) requirements as directed by Department of Defense (DoD), Headquarters Department of the Army (HQDA), and local policy. The COR/ACOR will request changes in Contractor security matters or processes if the Force Protection Condition (FPCON) at any individual facility or Installation changes.

2.5.1.2 Motor Vehicle Operators. Contractor's personnel, whose tasks require operation of any vehicles, shall possess a valid driver's license, certificates, and permits applicable for the type and class of vehicle being operated.

2.5.1.3 Contractor Vehicle Registration. Currently there is no requirement to register Contractor owned vehicles with the Provost Marshal or DES. However, all vehicles must be registered IAW current state requirements. In addition, the Contractor shall maintain a list of all Contractor-owned or operated vehicles and trailers always operating on the Installation. The list may be used in case of emergency and/or another contingency. Evidence of vehicle ownership and vehicle liability insurance must be presented upon request.

2.5.1.3.1 Contractor and Vendor Access. All privately-owned vehicles or motorcycles or Contractor or vendor-furnished vehicles and equipment must enter the Installation through the designated secure access control points (ACP). Under the present Installation FPCON, vehicle and equipment operators and passengers must possess identification documents as required by Fort Gordon DES to access the Installation. Vehicle and equipment operators must also possess and be ready to show a valid state and/or commercial driver's license, current vehicle registration, and proof of state required minimum liability insurance. As determined by the Installation FPCON, an elevated FPCON may

Annex A (Overarching Base Operations PWS) to OPORD 24-XXX: IMCOM Enterprise Base Operations (BASOPS) Performance Work Statement (PWS) Templates (U)

require additional security screening and/or limited Installation access. All vehicles must be registered IAW current state requirements in which they are registered.

2.5.1.3.2 All Contractor personnel, not possessing a Common Access Card (CAC), requesting access to Fort Gordon will enter through the designated Visitor Control Center (VCC) located by Gate Six. All Contractor personnel will be required to present a United States National or State issued identification that is capable of being scanned for valid entry. Contractor personnel will receive a visitor's badge at the VCC with the length of access allowed. The maximum access length for visitor badging is one year. Once issued a valid visitor's badge Contractor personnel may enter any Manned Access Control Point/Gate. All Contractor personnel and their vehicles, equipment, and packages are subject to inspection or examination (search) at entry/exit of the Fort Gordon.

2.5.1.4 Physical Security. The Contractor shall safeguard all Government equipment, information, and property provided for Contractor use IAW AR 190-13, The Army Physical Security Program. The Contractor shall maintain a physical security checklist or log (e.g., Standard Form (SF) 701, Activity Security Checklist), which will be forwarded to the KO and COR, NLT the 10th of each month, following the month of surveillance. The Contractor shall secure Government facilities, equipment, and materials at the close of each work period.

The Contractor will be provided Government furnished on-site staging area for necessary equipment and materials. The Contractor shall secure the area at the close of each work period. The Contractor shall be solely responsible for any loss or damage of equipment and material. The Contractor shall ensure debris of any type will be disposed of according to local policies and directives.

2.5.1.5 Secure Area Access. Portions of the work under the contract are performed in secure areas and all persons requiring access to a secure area will be escorted by the activity or Government personnel. In the case of escort, forty-eight (48) hours advance notice to the activity shall be required except in emergency or urgent work. Contractor employees requiring access to secure areas shall be free of felony convictions, and prior Military Service Members shall have an honorable discharge (See DD Form 254, *Department of Defense Contract Security Classification Specification*).

2.5.1.6 Employee Terminations. When an employee is terminated from employment on the contract for any reason, the Contractor shall have an out-processing checklist that identifies the Government issued CAC card and Installation Access Badge/Pass has been turned in to the COR and property items accounted for and back in proper custody. A signature shall be required on the checklist from the appropriate person acknowledging receipt of the items. Checklists shall be retained for the duration of the contract.

2.5.1.7 Departing Employees. The Contractor shall ensure Contractor employees return security photographic identification cards, permits, CAC, GFP, keys, photo passes,

Annex A (Overarching Base Operations PWS) to OPORD 24-XXX: IMCOM Enterprise Base Operations (BASOPS) Performance Work Statement (PWS) Templates (U)

range passes, sensor access (slide) cards and that access to the LAN email has been canceled. All out-processing Contractor employee CACs must be returned to the COR no later than close of business on the last workday. A formal termination or departing memo must be submitted to the COR and security office with the requested items stating they have been collected.

2.5.1.8 Key Control. The Contractor shall establish a control system to ensure no keys issued to the Contractor by the Government are lost, misplaced, or used by unauthorized persons. Government keys shall not be duplicated by the Contractor without the COR's/ACOR's authorization. Procedures developed to control Government keys shall be included in the Contractor's QCP. The Contractor shall comply with AR 190-13 *The Army Physical Security Program* and AR 190-51 *Security of Unclassified Army Property (Sensitive and Non-sensitive, applicable to key and lock)*.

2.5.2 Security Training.

2.5.2.1 iWATCH Training. The Contractor shall brief the local iWATCH program (training standards provided by the RA's Anti-Terrorism Officer (ATO)) to all of the Contractor's employees and associated Subcontractors. This training is used to inform employees of the types of behavior to watch for and instruct employees to report suspicious activity to the COR/ACOR. The Contractor shall complete the training within thirty (30) calendar days of contract award and within five (5) calendar days of new employees commencing performance with the results reported to the COR/ACOR NLT thirty (30) calendar days after contract award.

2.5.2.2 Anti-Terrorism (AT) Level 1 Awareness Training. All Contractor employees, to include Subcontractor employees, requiring access to Fort Gordon Installation, facilities and controlled access areas shall complete AT Level I awareness training within thirty (30) calendar days of contract start date and within five (5) calendar days of new employees commencing performance and send to the COR via both electronic and paper copy. The Contractor shall complete the training within thirty (30) calendar days of contract award AT level I awareness training is available at the following website: <http://jko.jten.mil>.

2.5.2.3 Operational Security (OPSEC) Awareness Training. IAW AR 530-1, Operations Security, Contractor employees shall complete Level I OPSEC Awareness training within thirty (30) calendar days of contract award and send to the COR via both electronic and paper copies. All Contractor personnel shall complete Level I OPSEC Awareness training annually. Level I OPSEC training is available at the following website: <https://securityawareness.usalearning.gov/opsec/index.html>.

2.5.2.3.1 All Contractor employees must complete the DoD Cybersecurity Awareness Training before issuance of network access and annually thereafter (Deliverable A1013,

Annex A (Overarching Base Operations PWS) to OPORD 24-XXX: IMCOM Enterprise Base Operations (BASOPS) Performance Work Statement (PWS) Templates (U)

IA Awareness Training). Upon completion of training, the Contractor shall submit training certificates to the COR.

2.5.3 Safety. The Contractor shall safeguard and maintain all Government and Contractor property, as well as provide for the safety and well-being of personnel employed under this contract. The Contractor shall comply with AR 385-10, *The Army Safety Program*. All Contractor employees shall wear a reflective vest or suitable substitute while working during darkness hours. Contractor shall be responsible for any injury to any Contractor's representative, or others, as well as for any damage to any personal or public property that occurs during the performance of this contract that is caused by the Contractor's fault or negligence.

2.5.3.1 Safety Plan. The Contractor shall develop and implement a safety program for its employees. The Contractor shall submit the Safety Plan to the KO for review and acceptance within ten (10) days of commencement of work. Revisions shall be submitted five (5) calendar days prior to the effective date of change.

2.5.3.2 Occupational Safety and Health Administration (OSHA). The Contractor shall comply with the OSHA standards. The Contractor shall comply with all applicable Federal, State, and Local Laws, Regulations, and Directives. If the Contractor fails or refuses to comply promptly with safety requirements, the Government may issue an order stopping all or part of the work until satisfactory corrective action has been taken. No part of the time lost due to any such order shall be made the subject of claim for extension of time or for excess costs or damages to/by the Contractor. The Contractor shall be responsible for enforcement of all safety requirements by the Contractor and his Subcontractors/teaming partners and/or joint venture partners.

2.5.3.3 Hot Work Permit.

A Hot Work Permit is required any time heat producing devices are used and shall be issued by the Fire Department prior to ANY work being started.

- Example, welding, grinding, cutting, brazing, etc.
- Hot Work Permits will be closed by the Fire Department, after hot-work is completed, and before personnel responsible for the work clears the job site.

2.5.4 Training, Physical Requirements, or other Expertise Required.

2.5.4.1 Certification and Licensure. The Contractor shall ensure all Contractor's employees and associated Subcontractors are certified or licensed in the specific areas required by the State of Georgia. The Contractor shall ensure employees are certified or licensed in the appropriate Environmental Protection Agency (EPA) areas required. The Contractor shall ensure all required documentation of certification or licensure for Contractor personnel are filed with the COR/ACOR within twenty-four (24) hours prior to employees commencing performance.

Annex A (Overarching Base Operations PWS) to OPORD 24-XXX: IMCOM Enterprise Base Operations (BASOPS) Performance Work Statement (PWS) Templates (U)

2.5.5 Environmental Requirements.

2.5.5.1 Green Procurement. Section 6002 of the *Resource Conservation and Recovery Act of 1976* (RCRA) requires the use of recycled and recovered products identified in the EPA's Comprehensive Procurement Guidelines.

2.5.5.2 The Contractor shall use these recycled or recovered products unless they cannot be procured within a reasonable period of time not to exceed seven (7) calendar days; at prices not to exceed five (5) percent of prevailing rates; or the product(s) does not meet technical or performance standards. EPA Guidelines are the minimum requirement. The Contractor shall use materials and products commonly used in industry. The Contractor shall maintain records and submit an annual report to the COR/ACOR, along with the annual certification required by FAR 52.223-9 (*Certification and Estimate of Percentage of Recovered Material Content for EPA Designated Items*), upon completion of the base year and each option year.

2.5.5.3 Environmental Compliance. The Contractor shall comply with all Federal, State, Local, and Installation Environmental Laws, Rules, Plans, and Policies. The Contractor shall use and store all materials, chemicals, and equipment used in the performance of services on the Installation IAW with Industry Standards, Local, State and Federal Laws. The Contractor shall be financially responsible for all fines and associated costs for hazardous waste management, transportation, and disposal of waste due to the Contractor's non-compliance. The Contractor shall submit Safety Data Sheets (SDS) for approval on all materials, five (5) days before delivery of the material, to the COR/ACOR. The Contractor shall provide upon request from the COR/ACOR all required data to meet environmental-mandated reporting requirements (e.g., air emission data, hazardous material storage/usage, herbicide/pesticide usage, solid/hazardous waste generation). The Contractor shall provide data to meet reporting deadlines and during compliance inspections upon request from the COR/ACOR.

2.5.5.4 Spill Plan. The Contractor shall notify the COR/ACOR within one (1) hour, if the Contractor spills or releases any hazardous substances, *i.e.*, substances listed in 40 CFR 302, *Designation, Reportable Quantities, and Notification*. The Contractor shall submit a Spill Plan to the KO for approval within thirty (30) days of contract award IAW Spill Prevention Control and Countermeasure Plan.

2.5.6 Contingency Plans.

2.5.6.1 General. The Contractor shall establish, maintain, and implement contingency plans for mobilization, disaster, and labor dispute contingencies. The plans shall assume no Government support to the Contractor workforce. The Contractor shall, within thirty (30) days of contract award, designate in writing a single contact Designated Contingency Coordinator (DCC) within the Contractor's organization. The DCC shall participate and coordinate with the Installation contingency and mobilization planning activities. The DCC shall participate in the Installation mobilization planning and execution conferences; and shall modify and maintain appropriate Contractor contingency plans to

Annex A (Overarching Base Operations PWS) to OPORD 24-XXX: IMCOM Enterprise Base Operations (BASOPS) Performance Work Statement (PWS) Templates (U)

compliment or enhance corresponding Installation plans. The Contractor shall submit all plans to the KO for approval.

2.5.6.2 Mobilization Contingency Plan. This plan shall establish procedures, personnel, and means of maintaining or expanding performance of all PWS requirements in the event of rapid deployment or sudden build-up of Military Forces. The Contractor shall submit a Mobilization Contingency Plan within (30) days of contract award. The Plan shall be approved by the KO/COR prior to the start of work.

2.5.6.3 Disaster Contingency Plan. This plan shall establish procedures, identify personnel, document essential PWS disaster services, conduct comprehensive damage assessment if the impacted installation(s) after a weather event or disaster and identify the means of maintaining essential PWS services during disasters. Disaster means natural disaster (e.g., earthquake, major storm, flash flood, or hurricane), utility outage, terrorist attack or other special circumstances identified by the Government. The Contractor shall submit a Disaster Contingency Plan within thirty (30) days of contract award.

2.5.6.4 Labor Dispute Contingency Plan. This plan shall establish procedures and identify responsible personnel to provide the services below, with no interruption in the event of a labor dispute:

- a. Identify and address critical Preventive Maintenance and inspection tasks,
- b. Maintain electrical emergency generators, and
- c. Process and execute emergency and urgent service and work orders.

The plan shall establish procedures and time frame to secure replacement personnel in the event of a strike; and shall also record the Contractor's experience with and establish Contractor procedures for collective bargaining. The Contractor shall submit a Labor Contingency Plan NLT contract start date.

2.5.6.5 Plan Updates. The Contractor shall update these plans as changes occur and shall submit a copy of the proposed plan to the KO for approval at least thirty (30) days prior to the proposed effective date of the updated plan.

3.0 Performance Requirements and Standards.

3.1 Performance Task Requirements, Standards and Acceptable Quality Levels (AQLs).

3.2 Quality Assurance (QA). The Government will evaluate the Contractor's performance under the contract IAW the Government's Quality Assurance Surveillance Plan (QASP). QASPs are considered to be "living documents," dynamic, adaptable, and subject to modification based on Contractor performance surveillance results. The QASP is not part of the PWS and will not be issued with the solicitation. The QASP focuses on the procedures and processes the Government will implement to assure the Contractor is performing IAW the performance standards within the PWS. The Government plan

Annex A (Overarching Base Operations PWS) to OPORD 24-XXX: IMCOM Enterprise Base Operations (BASOPS) Performance Work Statement (PWS) Templates (U)

defines the criteria of how the Contractor's performance will be evaluated, the frequency of surveillance, and the items to be inspected. Although the Government will develop a QASP, Government surveillance of Contractor performance is not limited to the QASP, or the performance objectives, outlined in the Performance Requirements Summary (PRS). The Government retains the right to evaluate all services required by the contract. The Government will perform inspections and tests in a manner that will not unduly delay the work. If any of the services performed do not conform to contract requirements, the Contractor shall perform the services again at no additional cost to the Government.

3.3 Quality Control Plan (QCP). Quality control is the responsibility of the Contractor. The Contractor shall develop, implement, and maintain an effective quality control program which shall be documented in a QCP to ensure services are performed IAW this PWS. The Contractor shall develop and implement procedures to identify and prevent the recurrence of defective services. The Contractor's QCP is the means by which they assure themselves that the work conforms to contract requirements. The basic principle of the plan is that the Contractor is responsible for quality control. The QCP shall be constructed in such a manner that each SERVICE can be extracted and used for that function only and not contain extraneous information. The Contractor's QCP shall include a separate section, which addresses the Contractor's method of managing quality of work. The QCP shall include a description of the inspection system to address services listed in this PWS, and a description of the methods to be used for identifying and preventing defects in the quality of services performed. The plan shall include a description of the Contractor's inspection system to include specifics as to areas to be inspected on a scheduled and unscheduled basis, frequency of inspections, and the title and organizational placement of the Contractor's inspectors. No lead person or first line supervisor shall be considered a Quality Control Inspector. The Contractor shall develop, maintain, and submit a QCP to the KO for acceptance within thirty (30) calendar days after the contract is awarded. The Contractor shall submit any proposed changes in the QCP to the KO for written approval five (5) working days prior to implementation.

3.4 Quality Control Files. The Contractor shall maintain files of all inspections or tests conducted by the Contractor, to include any corrective actions taken. These files shall be subject to Government review at the COR's discretion during the contract term, to include any extensions of contract term. The Quality Control Files will be the property of the Government and shall be turned over to the Government upon completion or termination of the contract.

3.5 Customer Feedback Program. The Contractor shall establish and operate a customer feedback program as part of the QCP. Performance Requirements Summary (PRS) Matrix.

Annex A (Overarching Base Operations PWS) to OPORD 24-XXX: IMCOM Enterprise Base Operations (BASOPS) Performance Work Statement (PWS) Templates (U)

4.0 Performance Requirements Summary (PRS) Matrix.

Required Services/ Performance Object	PWS Paragraph Number	Performance Standard	Maximum Allowable Degree of Deviation from Requirement (AQL Level)	Method Of Surveillance	Deduct Schedule
DMO (Service Order) Receipt and Entry	2.2.3	Assigns appropriate priority level	No more than one (1) defect per month allowed.	Random sample	\$500 per defect above AQL
Priority 1 DMO	2.2.3.2	Complete 100% of Emergency DMOs within twenty-four (24) hours	No more than zero (0) defects per month.	100% Inspection	\$1,500 per defect above AQL
Priority 2 DMO	2.2.3.2	Complete all Priority 2 DMOs within seven (7) calendar days	No more than two (2) defects per month allowed	Random Sample	\$1,000 per defect above AQL
Priority 3 DMO	2.2.3.2	Complete all Priority 3 DMOs within thirty (30) calendar days	No more than eight percent (8%) defects per month allowed	Random Sample	\$100 per defect above AQL

Annex A (Overarching Base Operations PWS) to OPORD 24-XXX: IMCOM Enterprise Base Operations (BASOPS) Performance Work Statement (PWS) Templates (U)

PMO tasks	2.2.4	Execute all PMO tasks scheduled for the month	No more than zero (0) defects per month allowed	Random Sample	\$1,000 per defect above AQL
PWO's	2.2.6	Complete PWO's within the scheduled delivery date	No more than one (1) defect allowed per month	100% Inspection	\$500 per defect above AQL
Workload Management in GFEBS	2.2.3.3. for DMOs 2.2.4 for PMOs	TECO DMOs and PMOs in GFEBS within seven (7) calendar days of completion	No more than five (5) defects allowed per month	Random Sample	\$500 per defect above AQL
GFEBS PMO Program	2.2.4.1	Develop and complete PMO Program in GFEBS	NLT ninety (90) days from contract start date	100% Inspection	\$250 per day above AQL

5.0 Common Levels of Service (SERVICE).

The Contractor shall provide overall management, supervision, personnel, labor, generalized or specialized equipment necessary to maintain, repair, operate, and perform all the SERVICE functions of the Base Operations specified below. This shall be done IAW all the Terms, Conditions, General and Special Provisions, Specifications, Drawings, Attachments, and Exhibits contained herein or incorporated by reference.

The Contractor shall ensure that all work meets or exceeds the specifications for the listed SERVICE.

Annex A (Overarching Base Operations PWS) to OPORD 24-XXX: IMCOM Enterprise Base Operations (BASOPS) Performance Work Statement (PWS) Templates (U)

SERVICE	Service Title	Annex No.
200	Unaccompanied Housing	Annex C
403	Solid Waste Management	Annex E
404	Grounds Maintenance	Annex F
408	Pavement Clearance	Annex G
411	Facility Maintenance - Vertical	Annex H
414	Facility Maintenance - Army Family Housing (AFH)	Annex I
420	Facility Maintenance - Horizontal	Annex J
501	Heating and Cooling Services	Annex K
510	Pest Management Services	Annex M
N/A	Army Cemetery	Annex O
N/A	Gillem Enclave	Annex P

6.0 Deliverables. Reference TE A-6.13

7.0 Related Documents.

7.1 Definitions and Acronyms.

7.1.1 Definitions.

7.1.1.1 Acceptable Quality Level (AQL). The AQL is the maximum percent defective (or the number of defects per hundred units) for the purposes of sampling inspection can be considered satisfactory.

7.1.1.2 Alternate Contracting Officer's Representative (ACOR). An employee of the U.S. Government provided by the RA and appointed by the KO to provide support to CORs in monitoring and documenting the Contractor's performance. These alternate surveillance support personnel will serve as on-site representatives of the COR in performance of actual contract surveillance if they meet all COR training, experience requirements, and are appointed by the KO as an ACOR.

7.1.1.3 Ashes. The residue from burned wood, coal, coke, and other combustible material.

7.1.1.4 Bulk Waste. Large items of solid waste such as household appliances, furniture, auto parts, pallets, shelving, piping, stone, concrete rubble, brick, lumber, toys, and other wastes; the size or weight of which, precludes or complicates the handling by normal collection, processing, or disposal methods.

7.1.1.5 Bulky Waste. The waste placed at the collection point or curbside that doesn't fit or is too heavy to be placed in the routine collection container. These wastes include but are not limited to: lumber, scrap metals, bricks, blocks, concrete rubble, stones, toys, furniture, appliances, logs, limbs, televisions, cabinets, automotive components,

Annex A (Overarching Base Operations PWS) to OPORD 24-XXX: IMCOM Enterprise Base Operations (BASOPS) Performance Work Statement (PWS) Templates (U)

power equipment, crates, wheels, de-rimmed tires, electronics and their components, etc.

7.1.1.6 Cannibalize. Remove parts from Government property for use or for Installation on other Government property.

7.1.1.7 Carpet Care. Cleaning and maintenance to keep carpet reasonably free of all stains, soil, and dirt. Methods used for carpet care are vacuum cleaners and carpet shampoos.

7.1.1.8 Child, Youth and School Services (CYS). Overarching naming convention for Child Development Center (CDC), Youth Activity Center, and School Age Services (SAS). CYS is used when referencing all programs.

7.1.1.9 Cleaning. Removing stains, soil, and dirt; accomplished by chemical or mechanical means.

7.1.1.10 Collection. The pickup of accumulated recyclable material, solid waste, including bulky waste, from any collection point, regardless of quantity.

7.1.1.11 Collection Frequency. The number of times collection is performed during a specific time frame.

7.1.1.12 Collection Point. The location designated on the drawings or maps or described in this performance work statement where solid waste, including bulky materials, will be temporarily stored for collection by the Contractor.

7.1.1.13 Commercial Solid Waste. All types of solid waste generated by stores, offices, restaurants, warehouses, and other non-manufacturing activities, excluding residential and industrial waste.

7.1.1.14 Construction and Demolition (C&D) Waste. The waste building materials, packaging and rubble resulting from construction, remodeling, repair, and demolition operation on pavement, housing, commercial buildings, and other structures.

7.1.1.15 Contract Administrator (CA). The official Government representative delegated authority by the KO to administer a contract. This individual, normally working in an appropriate contracting or procurement career field, advises on all technical contractual matters.

7.1.1.16 Contract Discrepancy. A failure of the Contractor to perform IAW contract requirements and specifications, e.g., a failure of the Contractor to provide, or provide on time, the required contract products, or services; or it may result because delivered products or services do not meet specific contract requirements.

Annex A (Overarching Base Operations PWS) to OPORD 24-XXX: IMCOM Enterprise Base Operations (BASOPS) Performance Work Statement (PWS) Templates (U)

7.1.1.17 **Contract Discrepancy Report (CDR).** A report used to document other than satisfactory Contractor performance. The CDR requires the Contractor to explain, in writing, why performance is other than satisfactory; how performance shall be returned to satisfactory levels; and how recurrence of the problem shall be prevented in the future.

7.1.1.18 **Contractor.** A supplier or vendor awarded a contract to provide specific supplies or service to the Government. The term used in this contract refers to the prime.

7.1.1.19 **Contractor Acquired Property (CAP).** Property acquired, fabricated, or otherwise provided by the Contractor for performing a contract. Contractor retains title.

7.1.1.20 **Contractor Manpower Reporting Application (CMRA).** N/A

7.1.1.21 **Contracting Officer (KO).** A person with authority to enter into, administer, and or terminate contracts, and make related determinations and findings on behalf of the Government. Note: The only individual who can legally bind the Government.

7.1.1.22 **Contracting Officer's Representative (COR).** An employee of the U.S. Government appointed by the KO to help administer the contract. Such appointment shall be in writing and shall state the scope of authority and limitations. This individual has authority to provide technical direction to the Contractor as long as that direction is within the scope of the contract, does not constitute a change, and has no funding implications. This individual does NOT have authority to change the terms and conditions of the contract.

7.1.1.23 **Corrosion.** Corrosion shall be classified in accordance with AR 420-1 and UFC 3-701-01. Actions taken to prevent, slow, or arrest deterioration, including inspection, cleaning, surface preparation, removal of minor surface corrosion without material loss, and application of protective coatings or sealants, shall be classified as preventive maintenance. Corrosion that results in material loss, structural degradation, component failure, or reduced operational capability shall be classified as repair, and may include removal and replacement of corroded materials or components and restoration of systems to their original intended condition, capacity, and function. Corrosion preventive maintenance shall not include replacement or restoration of lost material, and corrosion repair shall not increase system capacity, alter configuration, or introduce improvements beyond the original design intent.

7.1.1.24 **Curb Side Pick-Up.** Collection of solid waste or recyclable materials (to include bulky waste) that is placed next to curb, doorway or alley by the supported activity. This refers to locations that are not serviced by bulk containers (dumpsters or compactors).

7.1.1.25 **Damage Caused by Contractor.** Damages caused by Contractor employees shall be repaired at no cost to the Government. The Contractor shall notify the COR/ACOR and return the damaged area to its previous condition. The Contractor

Annex A (Overarching Base Operations PWS) to OPORD 24-XXX: IMCOM Enterprise Base Operations (BASOPS) Performance Work Statement (PWS) Templates (U)

shall furnish all labor, materials, and equipment to perform the repair work including cultivating and applying seed, sprigging, or placing sod. The Contractor shall maintain all turf repair work to ensure successful growth.

7.1.1.26 **Damage Report.** The Contractor shall submit a monthly damage report to the COR/ACOR that annotates the damage, corrective action, and date corrected.

7.1.1.27 **Debris.** Includes, but is not limited to, paper, cans, bottles, cigarette butts, cardboard, plastic, limbs and branches, pine straw and pine cones, leaves, rocks, and other similar items.

7.1.1.28 **Defective Service.** A service output that does not meet the standard of performance associated with the PWS.

7.1.1.29 **Deliverable.** Anything that can be delivered; can include non-manufactured things, such as meeting minutes or reports.

7.1.1.30 **Equipment.** A tangible item that is functionally complete for its intended purpose, durable, nonexpendable, and needed for the performance of a contract. Equipment is not intended for sale and does not ordinarily lose its identity or become a component part of another article, when put into use. Equipment does not include material, real property, special test equipment or special tooling.

7.1.1.31 **Fertilization.** Fertilization is the process of applying nutrient elements to the soil where the soil has become deficient in nutrients essential for proper plant growth.

7.1.1.32 **Food Waste.** Organic residue generated by the handling, storage, sale, preparation, cooking and serving of foods.

7.1.1.33 **Garbage.** Animal and vegetable waste resulting from the handling, preparation, cooking, and consumption of foods.

7.1.1.34 **General Fund Enterprise Business System (GFEBS).** GFEBS is the U.S. Army's web-based enabled financial, asset, and accounting management system that standardizes, streamlines, and shares critical financial data across the Active Army, the Army National Guard, and the Army Reserves. GFEBS is the work management system that the Directorate of Public Works uses for all order types and projects.

7.1.1.35 **Generation.** The act or process of producing refuse (solid waste) or recyclable materials.

7.1.1.36 **Government-Furnished Property (GFP).** Property in the possession of, or directly acquired by, the Government and subsequently furnished to the Contractor for performance of a contract. Government-furnished property includes, but is not limited to, spares and property furnished for repair, maintenance, overhaul, or modification.

Annex A (Overarching Base Operations PWS) to OPORD 24-XXX: IMCOM Enterprise Base Operations (BASOPS) Performance Work Statement (PWS) Templates (U)

Government-furnished property also includes Contractor-acquired property if the Contractor-acquired property is a deliverable under a cost contract when accepted by the Government for continued use under the contract.

7.1.1.37 Government Property. All property owned or leased by the Government. Government property includes both Government-furnished property and Government purchased Contractor-acquired property. Government property includes material, equipment, special tooling, special test equipment, and real property. Government property does not include intellectual property and software.

7.1.1.38 Grass Cutting. Grass cutting includes cutting and trimming, within the designated area, all grasses, weeds, and other vegetation which is one (1) inch or less in diameter (at ground level).

7.1.1.39 Hard Surface Floor Care. Hard surface floor care includes, but is not limited to tile, vinyl, rubber tile, mosaic tile, quarry tile, ceramic tile, marble, concrete, terrazzo, and linoleum. Floor care includes, but is not limited to dust mopping, wet mopping, scrubbing, stripping, waxing, re-finishing, or sealing.

7.1.1.40 Hazardous Material. Any item or chemical, which is a “health hazard”, or “physical hazard”, as reflected in Federal Standard (FED-STD) 313 *Material Safety Data and Disposal Data for Hazardous Materials Furnished to Government Activities*, defined in OSHA 29 CFR 1910, and pursuant to FAR 23.301 (Hazardous Materials) Definition. It also includes any other material designated by a Government COR/technical representative as potentially hazardous and requiring safety controls (e.g., pesticides, fertilizers).

7.1.1.41 Installation Design Guide (IDG). IDGs provide standards for site planning, buildings, vehicular and pedestrian circulation, landscaping, site elements (e.g., signage, utilities), force protection, and sustainable design. The IDGs are specific to each Army Installation.

7.1.1.42 Institutional Solid Waste. Waste that is generated by educational, health care, correctional and other institutional facilities.

7.1.1.43 Key Personnel. Contractor personnel evaluated in a source selection process and are used in the performance of a contract. When key personnel are used as an evaluation factor in best value procurement, an offer can be rejected if it does not have a firm commitment from the persons who are listed in the proposal. The prime Contractor is responsible for performance of all Subcontractors.

7.1.1.44 Lavatories, Latrines, or Bathrooms. Commodes, urinals, wash basins, bathtubs, shower stalls, sinks, and shower curtains.

Annex A (Overarching Base Operations PWS) to OPORD 24-XXX: IMCOM Enterprise Base Operations (BASOPS) Performance Work Statement (PWS) Templates (U)

7.1.1.45 **Loss of Government Property.** Unintended, unforeseen, or accidental loss, damage, or destruction of Government property that reduces the Government's expected economic benefits of the property. Loss of Government property does not include occurrences such as purposeful destructive testing, obsolescence, normal wear and tear, or manufacturing defects. Loss of Government property includes, but is not limited to:

- a. Items that cannot be found after a reasonable search,
- b. Theft,
- c. Damage resulting in unexpected harm to property requiring repair to restore the item to usable condition, or
- d. Destruction resulting from incidents that render the item useless for its intended purpose or beyond economical repair.

7.1.1.46 **Lot.** A collection of service outputs from which a sample is to be drawn and inspected to determine conformance with the standard. This definition applies to the Performance Requirements Summary (PRS), not the word "lot" in Section B of the contract.

7.1.1.47 **Lot Size.** The number of service outputs in a lot. This definition applies to the PRS, not the words "lot size" in Section B of the contract.

7.1.1.48 **Material.** Property that is consumed or expended during the performance of a contract, component parts of a higher assembly, or items that lose their individual identity through incorporation into an end-item. Material does not include equipment, special tooling, and special test equipment or real property.

7.1.1.49 **Material Handling Area.** The material handling area is used for the accumulation and preparation of bulk solid waste or recyclable materials for transportation to a solid waste management facility.

7.1.1.50 **Non-Combustible Material.** Material that doesn't burn at ordinary temperatures.

7.1.1.51 **Non-Personal Services.** The personnel rendering the services are not subject, either by the contract's terms or by the manner of its administration, to the supervision and control usually prevailing in relationships between the Government and its employees. Non-personal service contracts are authorized by the Government IAW FAR 37.104, under general contracting authority, and do not require specific statutory authorization.

7.1.1.52 **Organic Storage Site.** Area of accumulation for organic materials (e.g., leaves, logs, limbs, and grass clippings).

7.1.1.53 **Performance Indicator.** The characteristic of an output of a work process that can be measured.

Annex A (Overarching Base Operations PWS) to OPORD 24-XXX: IMCOM Enterprise Base Operations (BASOPS) Performance Work Statement (PWS) Templates (U)

7.1.1.54 Performance Requirements Summary (PRS). Identifies the key service outputs of the contract that will be evaluated by the Government to ensure contract performance standards are met by the Contractor (other services may also be inspected under the authority of the Inspection of Service Clause).

7.1.1.55 Physical Security. Actions that prevent the loss or damage of Government property.

7.1.1.56 Plant. A living organism, of the kind exemplified by trees, shrubs, herbs, grasses, ferns, and mosses, typically growing in a permanent site, absorbing water, and inorganic substances through its roots.

7.1.1.57 Property. All tangible property, both real and personal.

7.1.1.58 Property Administrator (PA). An authorized representative of the KO, appointed IAW agency procedures, responsible for administering the contract requirements and obligations relating to Government property in the possession of a Contractor.

7.1.1.59 Property Records. Records created and maintained by the Contractor in support of its stewardship responsibilities for the management of Government property.

7.1.1.60 Provide. To furnish, as in Government-furnished property, or to acquire, as in Contractor-acquired property.

7.1.1.61 Pruning. Pruning is selectively removing unwanted growth to make a plant or tree grow or respond in a desired manner. Pruning differs from "shearing". Pruning involves selection and judgment. "Shearing" means clipping all growth on a plant at a uniform distance and shape.

7.1.1.62 Public Traffic Areas. Lobbies, hallways, corridors, stairwells, meeting rooms, and lavatories.

7.1.1.63 Quality Assurance (QA). Verification that services being performed by the Contractor are IAW acceptable standards.

7.1.1.64 Quality Assurance Evaluator (QAE). A Government representative responsible for performing surveillance and inspection of Contractor performance.

7.1.1.65 Quality Assurance Surveillance Plan (QASP). An organized document written by the Government specifying the surveillance methodology used for surveillance of Contractor performance.

7.1.1.66 Quality Control. All necessary measures taken by the Contractor to assure that the quality of an end product or service shall meet contract requirements.

Annex A (Overarching Base Operations PWS) to OPORD 24-XXX: IMCOM Enterprise Base Operations (BASOPS) Performance Work Statement (PWS) Templates (U)

7.1.1.67 **Raise.** Selective pruning of limbs, identified by the COR, or limbs that pose a public safety hazard with a minimum clearance of 14 feet over streets, parking lots, and driveways; eight (8) feet over walk areas; four (4) feet over buildings and three (3) feet from buildings and streetlights, IAW established industry standards.

7.1.1.68 **Random Number Table.** A table of numbers arranged in random fashion; a table used to select random samples.

7.1.1.69 **Random Sample.** A sampling method whereby each service output in a lot has an equal chance of being selected.

7.1.1.70 **Random Sampling.** A method for looking at a few individual items in a lot to measure the quality of that lot against a standard.

7.1.1.71 **Real Property.** DoD Lands, buildings, structures, utility systems, improvements, and appurtenances, thereto that includes equipment attached to and made part of buildings and structures, but not movable equipment. See Federal Management Regulation 102-71.20 (41 CFR 102-71.20).

7.1.1.72 **Recycling.** The act of recovering materials from the solid waste stream, separating them by commodity, and returned to the economic mainstream as raw material.

7.1.1.73 **Recycling Materials.** Commodities include corrugated cardboard, wood, and plastic pallets.

7.1.1.74 **Recycling Facility.** Any facility employed, beyond the initial collection processes and managing recycling which include, but not limited to electronics, organics, plastics, metals, paper, and cardboard.

7.1.1.75 **Regulated Medical Waste.** Waste not specifically excluded from the restrictions of Federal regulations, and which meets the criteria listed in 40 CFR 259.

7.1.1.76 **Refuse.** All garbage, ashes, debris, trash, rubbish and items intended for disposal that are generated in conjunction with the activities in the areas covered in this contract. Items excluded are explosives, incendiary waste, hazardous waste, and pathological waste resulting from medical and radiological processes.

7.1.1.77 **Refuse Collection.** A system of collecting and transporting solid waste from pick-up stations to points of disposal.

7.1.1.78 **Refuse/Recycling Storage Containers.** Cans, drums, bins, bags, boxes, crates, sidewalk litter containers, dumpsters, roll-off containers, or similar receptacles which are used for the temporary storage of solid waste while awaiting collection. The term "container" used in this document shall have the same meaning as solid waste storage container.

Annex A (Overarching Base Operations PWS) to OPORD 24-XXX: IMCOM Enterprise Base Operations (BASOPS) Performance Work Statement (PWS) Templates (U)

7.1.1.79 Reporting Labor Hours. N/A.

7.1.1.80 Residential Solid Waste. Waste generated by the normal activities of households, including, but not limited to: food waste, rubbish, ashes and bulky waste.

7.1.1.81 Sample Size. The number of outputs in the sample; a group of one or more tasks drawn from the specified performance.

7.1.1.82 Sampling. A sample consists of one (1) or more service outputs drawn from a lot IAW random sampling procedures to be evaluated by Government personnel.

7.1.1.83 Scavenging. The uncontrolled and unauthorized removal of materials at any point of the solid waste management stream.

7.1.1.84 Sensitive Property. Property potentially dangerous to the public safety or security if stolen, lost, or misplaced, or that shall be subject to exceptional physical security, protection, control, and accountability. Examples include weapons, ammunition, explosives, controlled substances, radioactive materials, hazardous materials or wastes, or precious metals.

7.1.1.85 Service/Maintain. These words are interchangeable.

7.1.1.86 Shrub. A woody plant with several perennial stems. It will usually have a height less of than thirteen (13) feet and stems no more than about three (3) inches in diameter.

7.1.1.87 Soil. Includes, but is not limited to dust, dirt, stains, grease, smudges, streaks, spots, lint, or odors. Soil can be removed chemically, mechanically, or by a combination of both. Mechanical soil removal is removing soil with a machine such as a vacuum cleaner. Chemical soil removal is removing soil with a liquid that contains cleaning agents such as detergents, surfactants, and emulsifiers. The combination of chemical and mechanical methods such as an automatic floor scrubbing machine, uses the chemical method to breakdown and loosen soil which then the mechanical method picks up and carries the soil away. Which soil removal method is used depends on the cleaning objectives and on size, location, and type of surface to be cleaned and is the prerogative of the Contractor.

7.1.1.88 Solid Waste. Garbage, refuse, sludge, and other waste materials not excluded by Federal regulations. Solid waste is any solid, liquid, semi-solid, or contained gaseous material resulting from institutional, industrial, commercial, mining, agricultural, or community operations and activities. Solid wastes are accumulated, stored, or treated before being discarded. A material is discarded if abandoned and not used, re-used, reclaimed, or recycled by being disposed of, burned, or treated. Regulated medical wastes are not included in this category.

Annex A (Overarching Base Operations PWS) to OPORD 24-XXX: IMCOM Enterprise Base Operations (BASOPS) Performance Work Statement (PWS) Templates (U)

7.1.1.89 Solid Waste Management Facility (SWMF). Any facility employed, beyond the initial collection processes and managing solid waste including, but not limited to: storage areas or facilities, transfer stations, rail haul or barge haul facilities, landfills, disposal facilities, solid waste facilities, surface impoundment and waste oil storage, repossessing, refining facilities, recyclable handling, recovery facilities and waste tire storage facilities.

7.1.1.90 Source Separation. Source separation is the act of separating recyclable materials at their point of generation by the waste generator.

7.1.1.91 Spray Buffing. Procedure to apply a light coat of wax to maintain the waxed floor after removing minor scratches and scuff marks.

7.1.1.92 Spot Cleaning. Cleaning small areas of carpet by vacuuming, hot water extraction, or shampooing due to accumulation of dirt or soil on heavy traffic patterns or due to leaks or spillage on small areas of floor surface. Spot cleaning is also removal of spots from walls, ceilings, floors, and furniture surfaces.

7.1.1.93 Standard. A measure of comparison; an acceptability criterion; a benchmark or yardstick against which a service will be measured.

7.1.1.94 Stairwell Cleaning. Cleaning of all stairwells in any building. This process includes steps, landing, walls, and handrails.

7.1.1.95 Street Wastes. Materials picked up by manual or mechanical sweepings of alleys, streets, and sidewalks. Waste from solid waste receptacles and catch basins.

7.1.1.96 Stripping. The removal of floor finishes down to the flooring material. Stripping of a floor means floor surfaces are free of dirt, stains, deposits, cleaning solutions, standing water, and have a uniform appearance when dry. Stripping of floor surfaces includes utilizing procedures and equipment to prevent safety hazards.

7.1.1.97 Subcontractor. One that enters into a contract with a prime Contractor. The Government does not have privity of contract with the Subcontractor.

7.1.1.98 Tonnage. Weight measured in tons (not imperial).

7.1.1.99 Transfer Station. A transfer station is a facility which processes collected solid waste in a particular area for transportation to a solid waste management facility.

7.1.1.100 Trash Removal. Trash removal includes the pickup and removal of all papers and other debris in buildings. This includes but is not limited to wastebaskets, boxes, or any substance used for refuse.

Annex A (Overarching Base Operations PWS) to OPORD 24-XXX: IMCOM Enterprise Base Operations (BASOPS) Performance Work Statement (PWS) Templates (U)

7.1.1.101 Tree. A woody plant having one erect perennial stem (trunk), at least three inches in diameter, at a point 4-1/2 feet above the ground, a definitely formed crown of foliage, and mature height of at least 13 feet.

7.1.1.102 Trimming. Cutting of grass and other vegetation around grounds obstacles that prevent mowing.

7.1.1.103 Unit Acquisition Cost.

- a. For Government-furnished property, the dollar value assigned by the Government and identified in the contract; and
- b. For Contractor-acquired property, the cost derived from the Contractor's records that reflect consistently applied generally accepted accounting principles.

7.1.1.104 Vector. A carrier, usually an arthropod, which can transmit a pathogen from one organism to another.

7.1.1.105 Wash. The act of cleansing using water and soap or detergent.

7.1.1.106 Wide Area Workflow (WAWF). A secure web-based system for electronic invoicing, receipt, and acceptance. WAWF allows Government vendors to submit and track invoices and receipt or acceptance documents over the web allowing Government personnel to process those invoices in a real-time, paperless environment.

7.1.1.107 Work Day. The number of hours per day the Contractor provides services IAW the contract.

7.1.1.108 Work Week. Monday through Friday, unless specified otherwise.

7.1.1.109 Yard Wastes. Materials such as: tree and shrub branches, trimmings, brush, grass clippings, leaves, Christmas trees, weeds, etc.

7.2 Acronyms.

ACC	Army Contracting Command
ACOR	Alternate Contracting Officer's Representative
AFARS	Army Federal Acquisition Regulation Supplement
AMC	Army Materiel Command
ANSI	American National Standards Institute
AQL	Acceptable Quality Level
ArMA	Army Maintenance Application
AR	Army Regulation
ARC	Army Resource Center
ATO	Anti-Terrorism Officer
CAP	Contractor Acquired Property
CDC	Child Development Center

Annex A (Overarching Base Operations PWS) to OPORD 24-XXX: IMCOM Enterprise Base Operations (BASOPS) Performance Work Statement (PWS) Templates (U)

CDRL	Contract Data Requirements List
CFE	Contractor Furnished Equipment
CFM	Contractor Furnished Material
CFP	Contractor Furnished Property
CFR	Code of Federal Regulations
CLIN	Contract Line Item Number
CMRA	Contractor Manpower Reporting Application
CONUS	Continental United States (excludes Alaska and Hawaii)
COR	Contracting Officer's Representative
CORT	Contracting Officer's Representative Tool
CPARS	Contractor Performance Assessment Reporting System
DA	Department of the Army
DCMA	Defense Contract Management Agency
DES	Directorate of Emergency Services
DFARS	Defense Federal Acquisition Regulation Supplement
DID	Data Item Description
DoD	Department of Defense
DOL	Department of Labor
DOT	Department of Transportation
DPW	Directorate of Public Works
ECO	Environmental Compliance Officer
EM	Engineering Manual, U.S. Army Corps of Engineers (USACE)
EO	Executive Order
EPA	Environmental Protection Agency
ERDC	Engineering Research Development Center
FAR	Federal Acquisition Regulation
FIPS	Federal Information Processing Standards
FPCON	Force Protection Condition
GFE	Government-Furnished Equipment
GFEBS	General Fund Enterprise Business System
GFM	Government-Furnished Material
GFP	Government-Furnished Property
HLO	High Level Objective
HQDA	Headquarters Department of the Army
HSPD	Homeland Security Presidential Directive
IAW	In Accordance With
IMCOM	Installation Management Command
IPM	Integrated Pest Management
IPMC	Integrated Pest Management Coordinator
IPMP	Integrated Pest Management Plan
IT	Information Technology
KO	Contracting Officer
N/A	Not Applicable
NGB	National Guard Bureau
NLT	Not Later Than
OCI	Organizational Conflict of Interest

Annex A (Overarching Base Operations PWS) to OPORD 24-XXX: IMCOM Enterprise Base Operations (BASOPS) Performance Work Statement (PWS) Templates (U)

OCONUS	Outside Continental United States (includes Alaska and Hawaii)
OMB	Office of Management and Budget
OSHA	Occupational Safety and Health Administration
PAM	Pamphlet
PM	Preventive Maintenance
POC	Point of Contact
PoP	Period of Performance
PPIRS	Past Performance Information Retrieval System
PRS	Performance Requirements Summary
PUB	Publication
PWS	Performance Work Statement
QA	Quality Assurance
QAP	Quality Assurance Program
QASP	Quality Assurance Surveillance Plan
QC	Quality Control
QCP	Quality Control Plan
RCRA	Resource Conservation and Recovery Act
SDS	Safety Data Sheets
SF	Standard Form
TE	Technical Exhibit
USARC	U.S. Army Reserve Command
U.S.C.	United States Code
VCE	Virtual Contracting Enterprise
VIP	Very Important Person
WAWF	Wide Area Workflow
WD	Wage Determination

7.3 Applicable Directives, Publications.

ACC PAM 70-1	Interim Army Contracting Command – Contracting Officer's Representative Policy Guide
AASHTO-T11	Standard Method of Test for Materials Finer Than 75-µm (No. 200) Sieve in Mineral Aggregates by Washing
ANSI A300	Standard Practices for Tree Care Operations
ANSI Z60.1	American Standards for Nursery Stock
ANSI Z87.1-2003	Practice for Occupational and Educational Personal Eye and Face Protection Devices
ANSI Z133.1	Safety Requirements for Tree Care Operations
ANSI/ASQC-Z1.4	National American Standard

Annex A (Overarching Base Operations PWS) to OPORD 24-XXX: IMCOM Enterprise Base Operations (BASOPS) Performance Work Statement (PWS) Templates (U)

ANSI Z245.1	Mobile Refuse Collection and Compaction Equipment – Safety Requirements
AR 11-27	Army Energy Program
AR 40-5	Preventive-Medicine (Child Development Centers)
AR 40-400	Medical Services Patient Administration
AR 70-13	Management and Oversight of Service Acquisitions
AR 190-5	Motor Vehicles Traffic Supervision
AR 200-1	Environmental Protection and Enhancement
AR 200-3	Natural Resources; Land, Forest, and Wildlife Management
AR 200-4	Cultural Resources Management
AR 200-5	Pest Management
AR 385-10	Army Safety Program
AR 385-40	Army Accident Investigation and Reporting
AR 420-1	Army Facilities Management
AR 420-70	Facilities Engineering (Transportation Infrastructure and Dams)
AR 420-90	Fire Emergency Services
AR 530-1	Operations Security
AR 600-50	Standards of Conduct for Department of Army Personnel
AR 600-63	Army Health Promotion
AR 608-10	Child Development Services
AR Directive 2014-23	Conduct of Screening and Background Checks for Individuals Who Have Regular Contact with Children in Army Programs
29 CFR Part 1910	Occupational Safety and Health Standards

Annex A (Overarching Base Operations PWS) to OPORD 24-XXX: IMCOM Enterprise Base Operations (BASOPS) Performance Work Statement (PWS) Templates (U)

40 CFR	Protection of the Environment
40 CFR Subchapter I	Solid Wastes
40 CFR 202	Motor Carriers Engaged in Interstate Commerce
40 CFR 257	Criteria for Classification of Solid Waste Disposal Facilities and Practices
40 CFR Part 302	Protection of Environment, Designation, Reportable Quantities and Notification
49 CFR 390-396	Motor Carrier Safety Standards
49 CFR 571	Federal Motor Vehicle Safety Standards
Clean Air Act (CAA)	
Clean Water Act (CWA)	
Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA)	
DA PAM 385-40	Army Accident Investigations and Reporting
DA PAM 420-1-1	Housing Management*
DoD 4160.21-M	Defense Materiel Disposition Manual
DoD Directive 5500.7-R	Joint Ethics Regulation
DoDI 1402.5	Criminal History Background Checks On Individuals in Child Care Services
DoDI 4150.07	DoD Pest Management Program
DoDI 5000.72	DoD Standard for Contracting Officer's Representative (COR) Certification
EM-385-1-1	Safety and Health Requirements Manual
EO 13423	Strengthening Federal Environmental, Energy, and Transportation Management
EO 13693	Planning for Federal Sustainability in the Next Decade

Annex A (Overarching Base Operations PWS) to OPORD 24-XXX: IMCOM Enterprise Base Operations (BASOPS) Performance Work Statement (PWS) Templates (U)

EPA, Method 9095	Paint Liquids Filter Test
EPA, SW-846	Test Methods for Evaluating Solid Wastes, Physical/Chemical Methods
FC 3-260-06F	Air Force Design, Construction, Maintenance, and Evaluation of Snow and Ice Airfields in Antarctica 06-01-2015
Federal Standard #313	Material Safety Data and Disposal Data for Hazardous Materials Furnished to Government Activities
Federal Standard #595	Colors
FIFRA	Federal Insecticide, Fungicide, and Rodenticide Act
FIPS PUB 201-2	Personal Identity Verification (PIV) of Federal Employees and Contractors
Garrison's Snow, Ice, and Sand Removal Control Plan	
HSPD 12 Common	Homeland Security Presidential Directive 12 Policy for a Identification Standard for Federal Employees and Contractor
IDG	Installation Design Guide
NFPA 1.12-2	Combustible Fibers
OMB M-05-24	Office of Management and Budget (OMB) Guidance Implementation of Homeland Security Presidential Directive (HSPD) 12 – Policy for a Common Identification Standard for Federal Employees and Contractors
OPORD 13-153	Enterprise Municipal Services Performance Standards
SF 95	Position of Public Trust
TB MED 530 5-28(h)(i)	Tri-Service Food Code
TM 5-623	Pavement Maintenance Management
TM 5-624	Maintenance and Repair of Surface Areas
TM 5-634	Solid Waste Management

Annex A (Overarching Base Operations PWS) to OPORD 24-XXX: IMCOM Enterprise Base Operations (BASOPS) Performance Work Statement (PWS) Templates (U)

TM 5-683	Electrical Interior Facilities
TM 5-820-4	Drainage for Areas other than Airfields
TM 9-6150-226-13	Electrical Feeder System
UFC 1-200-01	DoD Building Code (General Building Requirements)
UFC 4-010-1	DoD Minimum Antiterrorism Standards for buildings (Change 1)
UFC 4-021-01	Design and O&M for Mass Notification Systems
UFC 4-021-02NF	Security Engineering Electronic Security Systems
UFC 3-101-01	Architecture 11-28-2011
UFC 3-110-03	Roofing, with Change 1 05-01-2012
UFC 3-110-04	Roofing Maintenance and Repair 01-11-2007
UFC 3-120-01	Design: Sign Standards, with Change 2 03-01-2014
UFC 3-120-10	Interior Design, with Change 1 06-15-2006
UFC 3-190-06	Protective Coatings and Paints 01-16-2004
UFC 3-201-01	Civil Engineering 06-01-2013
UFC 3-201-02	Landscape Architecture, with Change 1 02-23-2009
UFC 3-210-10	Low Impact Development 07-01-2015
UFC 3-220-01	Geotechnical Engineering 11-01-2012
UFC 3-220-04	Backfill for Subsurface Structures 01-16-2004
UFC 3-220-05	Dewatering and Groundwater Control 01-16-2004
UFC 3-220-06	Grouting Methods and Equipment 01-16-2004
UFC 3-220-08	Engineering Use of Geotextiles 01-16-2004
UFC 3-220-10N	Soil Mechanics 06-08-2005

Annex A (Overarching Base Operations PWS) to OPORD 24-XXX: IMCOM Enterprise Base Operations (BASOPS) Performance Work Statement (PWS) Templates (U)

UFC 3-230-01	Water Storage, Distribution, and Transmission, with Change 2 11-01-2012
UFC 3-230-02	O&M: Water Supply Systems 07-10-2001
UFC 3-230-03	Water Treatment 11-01-2012
UFC 3-230-06A	Subsurface Drainage, with Changes 1-2 01-16-2004
UFC 3-240-01	Wastewater Collection, with Change 1 11-01-2012
UFC 3-240-02	Domestic Wastewater Treatment 11-01-2012
UFC 3-240-03N	Wastewater Treatment System Augmenting Handbook Operation and Maintenance 01-16-2004
UFC 3-240-05A	Solid Waste Incineration 01-16-2004
UFC 3-240-10A	Sanitary Landfill 01-16-2004
UFC 3-240-13FN	Industrial Water Treatment Operation and Maintenance 05-25-2005
UFC 3-250-01FA	Pavement Design for Roads, Streets, Walks, and Open Storage Areas 01-16-2004
UFC 3-250-03 2001	Standard Practice Manual for Flexible Pavements 05-15-2001
UFC 3-250-04	Standard Practice for Concrete Pavements, with Change 2 01-16-2004
UFC 3-250-06	Repair of Rigid Pavements Using Epoxy Resin Grouts, Mortars and Concretes 01-16-2004
UFC 3-250-07	Standard Practice for Pavement Recycling 01-16-2004
UFC 3-250-08FA	Standard Practice for Sealing Joints and Cracks in Rigid and Flexible Pavements 01-16-2004
UFC 3-250-09FA	Aggregate Surfaced Roads and Airfields Areas 01-16-2004
UFC 3-250-11	Soil Stabilization for Pavements 01-16-2004
UFC 3-260-01	Airfield and Heliport Planning and Design 11-17-2008

Annex A (Overarching Base Operations PWS) to OPORD 24-XXX: IMCOM Enterprise Base Operations (BASOPS) Performance Work Statement (PWS) Templates (U)

UFC 3-260-02	Pavement Design for Airfields 06-30-2001
UFC 3-260-03	Airfield Pavement Evaluation 04-15-2001
UFC 3-260-05A	Marking of Army Airfield Heliport Operational and Maintenance Facilities, with Change 1 01-16-2004
UFC 3-260-11 FA	Model Design-Build (D-B) Request for Proposal (RFP) For Airfield Contracts 05-25-2005
UFC 3-260-16 FA	FA Airfield Pavement Condition Survey Procedures Pavements 01-16-2004
UFC 3-260-17	Dust Control for Roads, Airfields and Adjacent Areas 01-16-2004
UFC 3-270-01	Asphalt Maintenance and Repair 03-15-2001
UFC 3-270-02	Asphalt Crack Repair 03-15-2001
UFC 3-270-03	Concrete Crack and Partial-Depth Spall Repair 03-15-2001
UFC 3-270-04	Concrete Repair 03-15-2001
UFC 3-270-05	Paver Concrete Surfaced Airfields Pavement Condition Index (PCI) 03-15-2001
UFC 3-270-06	Paver Asphalt Surfaced Airfields Pavement Condition Index (PCI) 03-15-2001
UFC 3-270-07	O&M: Airfield Damage Repair 08-12-2002
UFC 3-270-08	Pavement Maintenance Management 01-16-2004
UFC 3-280-01A	Guidance for Ground Water/Fuel Extraction and Ground Water Injection Systems 01-16-2004
UFC 3-280-04	Army Filtration of Liquids 12-17-2003
UFC 3-301-01	Structural Engineering, with Change 1 06-01-2013
UFC 3-310-04	Seismic Design for Buildings 06-01-2013
UFC 3-310-08	Non-Expeditionary Bridge Inspection, Maintenance and Repair, with Change 1 08-16-2010

Annex A (Overarching Base Operations PWS) to OPORD 24-XXX: IMCOM Enterprise Base Operations (BASOPS) Performance Work Statement (PWS) Templates (U)

UFC 3-320-06A	Concrete Floor Slabs on Grade Subjected to Heavy Loads 03-01-2005
UFC 3-340-01	Design and Analysis of Hardened Structures to Conventional Weapons Effects (FOUO) 06-30-2002
UFC 3-340-02	Structures to Resist the Effects of Accidental Explosions, with Change 2 12-05-2008
UFC 3-400-02	Design: Engineering Weather Data 02-28-2003
UFC 3-401-01	Mechanical Engineering 07-01-2013
UFC 3-410-01	Heating, Ventilating, and Air Conditioning Systems, with Change 1 07-01-2013
UFC 3-410-02	Lon works (R) Direct Digital Control for HVAC and Other Local Building Systems, with Change 1 05-01-2012
UFC 3-410-04N	Industrial Ventilation 10-25-2004
UFC 3-420-01	Plumbing Systems, with Change 9 10-25-2004
UFC 3-420-02FA	Compressed Air, with Change 1 05-15-2003
UFC 3-430-01FA	Heating and Cooling Distribution Systems 07-25-2003
UFC 3-430-02FA	Central Steam Boiler Plants, with Change 1 05-15-2003
UFC 3-430-07	Operations and Maintenance: Inspection and Certification of Boilers and Unfired Pressure Vessels, with Change 4 07-24-2003
UFC 3-430-08N	Central Heating Plants 01-16-2004
UFC 3-430-09	Exterior Mechanical Utility Distribution, with Change 1 01-16-2004
UFC 3-430-11	Boiler Control Systems 02-14-2001
UFC 3-440-01	Facility-Scale Renewable Energy Systems 07-01-2015
UFC 3-440-05N	Tropical Engineering, with Changes 1-2 01-16-2004
UFC 3-450-01	Noise and Vibration Control 05-15-2003

Annex A (Overarching Base Operations PWS) to OPORD 24-XXX: IMCOM Enterprise Base Operations (BASOPS) Performance Work Statement (PWS) Templates (U)

UFC 3-470-01	Lon works (R) Utility Monitoring and Control System (UMCS) 05-01-2012
UFC 3-460-01	Design: Petroleum Fuel Facilities, with Change 2 08-16-2010
UFC 3-460-03	O&M: Maintenance of Petroleum Systems 01-21-2003
UFC 3-501-01	Electrical Engineering, with Change 3 02-03-2010
UFC 3-510-01	Foreign Voltages and Frequencies Guide, with Change 2 03-01-2005
UFC 3-520-01	Interior Electrical Systems, with Change 3 02-03-2010
UFC 3-520-05	Stationary Battery Areas, with Change 1 05-01-2015
UFC 3-530-01	Interior and Exterior Lighting Systems and Controls 04-01-2015
UFC 3-535-01	Visual Air Navigation Facilities 11-17-2005
UFC 3-540-01	Engine-Driven Generator Systems for Backup Power Applications 08-01-2014
UFC 3-550-01	Exterior Electrical Power Distribution with Change 1 02-03-2010
UFC 3-555-01N	400 Hertz Medium Voltage Conversion/Distribution and Low Voltage Utilization Systems 01-16-2004
UFC 3-560-01	Electrical Safety, O&M, with Change 5 12-06-2006
UFC 3-570-02A	Cathodic Protection 03-01-2005
UFC 3-570-02N	Electrical Engineering Cathodic Protection 01-16-2004
UFC 3-570-06	O&M: Cathodic Protection Systems 01-31-2003
UFC 3-575-01	Lightning and Static Electricity Protection Systems 07-01-2012
UFC 3-580-01	Telecommunications Building Cabling Systems Planning and Design 06-22-2007
UFC 3-580-10	Navy and Marine Corps Intranet (NMCI) Standard Construction Practices, with Changes 1-3 07-14-2004

Annex A (Overarching Base Operations PWS) to OPORD 24-XXX: IMCOM Enterprise Base Operations (BASOPS) Performance Work Statement (PWS) Templates (U)

UFC 3-600-01	Fire Protection Engineering for Facilities, with Change 3 09-26-2006
UFC 3-601-02	Operations and Maintenance: Inspection, Testing, and Maintenance of Fire Protection Systems; 09-08-2010
42 U.S.C. 6901	Resource Conservation and Recovery Act (RCRA), Solid Waste Disposal Act (SWDA) of 1976, as amended, including Subtitle D

7.3 Technical Exhibit (TE). Reference the TE Index for a list of all TEs in this Contract.

REMOVE THE BELOW TE references if not applicable

7.4 Government-Furnished Material (GFM)/Property (GFP)/Equipment (GFE).

7.4.1 Utilities. The Government will provide all utilities in the facility will be available for the Contractor's use in performance of tasks outlined in this PWS, and access to water and electrical services. The Contractor shall obtain written approval from DPW prior to installing connections and meters. The Contractor shall instruct employees in utilities conservation practices. The Contractor shall be responsible for operating under conditions that preclude the waste of utilities, which include turning off the water faucets or valves after using the required amount to accomplish cleaning vehicles and equipment.

7.5 Contractor-Furnished Material (CFM)/Property (CFP)/Equipment (CFE). All Contractor furnished, material, property and equipment shall meet applicable Federal, State, Local, DoD and Army Laws, Codes, and Regulations. Examples are provided below:

7.5.1 Contractor-Furnished Material and Responsibilities. The Contractor shall furnish all supplies, equipment, facilities, and services required to perform work under this contract.

7.5.2 Contractor-Furnished Items. The Contractor shall provide all facilities, vehicles, equipment, parts, tools, fuel, oil, materials, and any other items required to perform all Contract requirements. The Contractor's property shall be operational as intended by the manufacturer, and be safe, clean, and suitable for use at a Military Installation. All Contractor furnished property and equipment are subject to KO inspection at all times.

7.5.2.1 Identification of Contractor Vehicles and Trailers. The company name shall be displayed on each of the Contractor's vehicles and trailers in a manner and size that is clearly visible. All vehicles and trailers shall display a valid State license plate and meet current local and State vehicle registration requirements.

7.5.2.2 The Contractor's equipment and other slow-moving equipment shall be equipped with the slow-moving vehicle sign.

Annex A (Overarching Base Operations PWS) to OPORD 24-XXX: IMCOM Enterprise Base Operations (BASOPS) Performance Work Statement (PWS) Templates (U)

7.5.3. Contractor Facilities. The Contractor shall occupy Government furnished facilities assigned by DPW.

7.5.4 Damage Caused by Contractor. Damages caused by Contractor employees shall be repaired at no cost to the Government. In all instances where Contractor's employees damage Government property or equipment, the Contractor shall provide a verbal report to the KO within four (4) hours of occurrence. The Contractor shall notify the COR/ACOR and return the damaged area to its previous condition. All damage done by the Contractor and/or his sub-Contractor/s shall become the Contractor's responsibility. The Contractor shall furnish all labor, materials and equipment to perform the repair work including cultivating and applying seed, sprigging, or placing sod. All turf repair work shall be maintained to ensure successful growth.

7.5.5 Third Party Repair Damaged Areas. In the event the Contractor discovers damage caused by another party, the Contractor shall notify the KO and COR of the extent of the damage and proposed corrective action. The Contractor shall make no repairs until authorized by the KO.

7.5.6 Equipment Replacement (Government Property). If an item of Government property is determined by the Contractor to be beyond economical repair, the Contractor shall recommend to the KO and COR in writing that such equipment be replaced. Substantiating data to support the recommended replacement shall be included. If the Government decides that such equipment should be replaced or repaired, and replacement or repair is authorized, the Contractor shall accomplish the work IAW the appropriate work level criteria. Disposal instructions will be provided by the KO and COR.

7.5.7 Permits. The Contractor shall obtain all appointments, licenses, and permits required for performance of work and for complying with all applicable Federal, State, and Local Laws. Permits and licenses shall be provided to the COR/ACOR before work commences.

7.6 U.S. Department of Labor (DOL) Wage Determination (WD). The Contractor shall refer to <https://www.wdol.gov/dba.aspx> for U.S. Department of Labor Wage Determinations (DOL WD).