

**SITE Domestic Water Valve Replacements Phase 2
at the NIST Boulder, CO Campus
SOURCES SOUGHT**

Original Set Aside: N/A, TBD

Set Aside: N/A, TBD

Classification Code: Z1JZ – Maintenance of Miscellaneous Buildings

NAICS Code: 237 – Heavy and Civil Engineering Construction/237110 – Water and Sewer Line Related Structures Construction

Synopsis: ***PLEASE OPEN ATTACHMENTS FOR COMPLETE SOURCES SOUGHT ANNOUNCEMENT INFORMATION***

In accordance with (IAW) FAR RFO 15.101(c)(3) this is a SOURCES SOUGHT FOR MARKET RESEARCH. THIS

SOURCES SOUGHT IS NOT A REQUEST FOR PROPOSALS, QUOTATIONS OR BIDS. This announcement constitutes a Sources Sought (market survey). This notice is a request for information to provide data for planning purposes only and does not constitute an Invitation for Bids, a Request for Proposals, a Solicitation, a Request for Quotes, or an indication the Government will contract for the services contained in this Sources Sought. A solicitation is not currently available. This Sources Sought is a market research tool used by the acquisition team to determine potential and eligible businesses that have the capability and interest in providing the required commercial services described herein, prior to determining the method of acquisition. This also serves as a Request for Comments on the draft statement of work (SOW) for the planned project.

The U.S. Department of Commerce, National Institute of Standards & Technology (NIST), Acquisition Management Division (AMD), is seeking information from potential sources that are capable and interested in performing the work on a commercial contract at the NIST Boulder, Colorado Campus Site.

This request is not to be construed as a commitment on the part of the Government to award a contract, nor does the Government intend to pay for any information submitted as a result of this notice. The Government does not reimburse respondents for any cost associated with this source sought or reimburse expenses incurred to interested parties for preparing a response as a result of this posting. The Government is not obligated to and will not pay for any information or comments received from potential sources as a result of this Sources Sought and Request for Comments announcement. Any responses received will not be used as a proposal. Respondents will not be notified of the Sources Sought evaluation results, nor will questions be addressed by the Government.

The results of this Sources Sought will be utilized to assess the amount of interest and capability in the current market, and to determine if any Small Business Set-aside opportunities exist for

this potential requirement. All Small Business Set-aside categories will be considered. This market research tool will be used to identify potential and eligible service contractors, of all sizes, prior to determining the method of acquisition and level of announcement for issuance of a solicitation.

The Request for Comments portion of this Sources Sought provides contractors the opportunity to make any comments, including recommendations, regarding the draft SOW for the potential project. Comments will be used for consideration in the development of the SOW. The Government will not provide responses to any questions or Requests for Information regarding this project as a part of this Sources Sought and Request for Comments.

Project Description:

NIST, OFPM, the purpose of this project is to remove and replace domestic water piping and valves. Remove approximately 350 linear feet of existing 6-inch cast iron domestic water piping and replace it with PVC piping. Work includes the removal and replacement of one 6-inch fire hydrant valve, one 6-inch water main valve and one 6-inch branch valve. Work location is the NIST Boulder Campus, Daycare center lawn, Building 26 to the front of Building 3 main entrance sidewalk.

Sources Sought: Interested and capable sources are requested to electronically submit a Capabilities Statement with supporting supplemental data supporting the exact product that is recommended. The submission shall be no more than twenty (20) pages in length inclusive of the following information:

1. Company name and address. The name, position title, telephone number and email address of a company point of contact (POC).
2. UEI/CAGE code registered in the system for Award Management (SAM) at www.sam.gov.
3. Indicate whether your company is a large business or a small business under the NAICS code specified in this announcement or the suggested NAICS code with rationale as to why the recommendation is a better choice, versus the previously listed project NAICS.
4. Company Profile description.
5. Statement of Capability stating your company's skills, experience, knowledge, and supplemental data of the organizations proposed equipment to the work requirement. Additionally, address the percentage of this work requirement that will be self-performed, and what portions and to who/whom will not be self-performed.
6. Recent experience is experience performed within the last five (5) years. If none then please state, there is none.
7. Any other relevant information that is not listed above which the Government may consider in developing the service requirement and market research.

Request for Comments: All comments provided in response to the Sources Sought shall be submitted electronically on the attached Request for Comments sheet. Comments will be used for consideration in the development of the SOW. The Government will not provide responses to any questions, Requests for Information, regarding this project as a part of this Sources Sought and Request for Comments.

Submittal Instructions: All responses to this Sources Sought shall be submitted via email by the required Response Date to Primary Point of Contact with a courtesy copy to the Alternate Point of Contact in this announcement.

-----[CONTINUE TO NEXT PAGE FOR THE WORK REQUIREMENT]-----

DRAFT STATEMENT OF WORK
SITE Domestic Water Valve Replacements Phase 2

I. BACKGROUND INFORMATION

The Facilities Maintenance Division (FMD) 194 is responsible for the maintenance and repair of physical infrastructure across the National Institute of Standards and Technology (NIST) campus in Boulder, Colorado. The purpose of this project is to remove and replace domestic water piping and valves.

II. PURPOSE

Remove approximately 350 linear feet of existing 6-inch cast iron domestic water piping and replace it with PVC piping. Work includes the removal and replacement of one 6-inch fire hydrant valve, one 6-inch water main valve and one 6-inch branch valve.

PLACE OF PERFORMANCE

Work location is the NIST Boulder Campus, Daycare center lawn, Building 26 to the front of Building 3 main entrance sidewalk.

Regular Business Hours

Regular business hours are Monday through Friday, 7am to 6pm Mountain Time, excluding Federal holidays and NIST closures.

PERIOD OF PERFORMANCE

Period of Performance for this work is 180 Calendar days from Notice to Proceed (NTP).

III. SPECIFIC REQUIREMENTS

TASKS

Location: See attached map for exact locations.

1. General Requirements

The Contractor shall provide all labor, materials, equipment, supervision, and transportation necessary to perform demolition, installation, testing, and restoration associated with the replacement of an existing water main and associated components. Work shall include removal of existing piping and valves, installation of new piping and valves, testing and disinfection, and restoration of all disturbed areas.

The work area includes sections of property located within a daycare yard and adjacent areas containing asphalt pavement, sidewalks, and landscaping. The Contractor shall coordinate construction activities to minimize disruption to facility operations and ensure public safety.

The Contractor shall verify all existing site conditions and utility locations prior to beginning excavation activities.

2. Demolition

The Contractor shall perform demolition and removal work necessary to facilitate the installation of the new water main.

2.1 Utility Location and Protection

- a. Identify and isolate existing water system valves as shown on the attached site map.
- b. Perform thorough utility locates prior to excavation activities.
- c. Utilize hydro-vacuum excavation (potholing) to expose existing water lines and electrical utilities before trenching.
- d. Exercise extreme caution when working near electrical lines serving transfer switches.

2.2 Removal of Existing Infrastructure

- a. Remove approximately **350 linear feet of existing 6-inch cast iron water piping**.
- b. Abandon the existing water service entrance piping and eliminate the existing tee connection.
- c. Remove existing water valves associated with the removed piping.
- d. Remove asphalt pavement and concrete sidewalks as necessary to facilitate excavation and installation activities.
- e. Remove and temporarily modify or remove daycare fencing and adjacent concrete as necessary to allow construction access.

2.3 Disposal

All demolished materials, including piping, valves, asphalt, and concrete debris, shall be removed from the site and disposed of at an approved off-site disposal facility in accordance with all applicable regulations.

3. Installation

The Contractor shall install new water system infrastructure in accordance with the specifications listed below.

3.1 Water Main Installation

The Contractor shall install approximately **350 linear feet of new 6-inch water main** meeting the following requirements:

- Pipe shall be **Blue Brute C900 PVC pipe or approved equivalent**.
- Install **#12 AWG HS-CCS tracer wire** continuously along the entire water line to facilitate future utility locating.

- Valves for Isolation to facilitate water pipe removal and replacement – MV 92-48 and MV 94-38. Coordinate with COR to verify isolation with Fire Hydrant flow.

3.2 Valve Installation

The Contractor shall furnish and install the following valves:

1. One (1) **6-inch water main valve MV 94-38**
2. One (1) **6-inch branch valve MV 92-53**
3. One (1) **6-inch fire hydrant valve FHV ?? (depicted on map)**

Isolation for valve replacements MV 92-48, MV 92-30 and MV 92-29. This work must take place on a weekend. Three-week minimum notice prior to work.

Valve requirements:

- Valves shall be **Mueller Resilient Wedge Gate Valves or approved equivalent.**
- All water valves shall be configured to **open counterclockwise.**
- Provide **cathodic or corrosion protection** for installed valves and associated metallic components.

3.3 Pipe Bedding and Backfill

Select backfill and pipe bedding materials shall be used at all pipe replacement locations.

- From **4 inches below the pipe to 12 inches above the pipe**, install granular embedment material.
- Embedment material shall consist of **washed angular aggregate ranging from 3/8 inch to 3/4 inch in size.**

4. Testing and Disinfection

Prior to final backfilling operations, the Contractor shall perform the following:

- a. Disinfect the water line in accordance with the pipe manufacturer's instructions and applicable water system standards.
 - b. Perform pressure testing of the installed water line.
 - c. Submit written testing and disinfection reports to the **Contracting Officer's Representative (COR)** for review and approval prior to proceeding with final backfill.
-

5. Site Restoration

All areas disturbed during construction shall be restored to original or better condition.

5.1 Asphalt Restoration

The Contractor shall patch and restore all asphalt pavement removed during construction operations.

5.2 Sidewalk Replacement

Concrete sidewalk replacement shall meet the following requirements:

- Minimum **6-inch thickness**
- Reinforced with **6-inch by 6-inch welded wire fabric**
- Contraction joints shall match existing sidewalk joint spacing
- Provide **½-inch expansion joints** between new and existing sidewalks
- Concrete shall have a **minimum compressive strength of 5,000 PSI**
- Concrete shall be **air-entrained at 6% ± 1.5%**
- Provide **broom finish surface**
- Concrete shall be **membrane cured**
- Consolidate concrete by vibration during placement

5.3 Sod Replacement

Replacement sod shall be Colorado grown, 100% certified Merion Kentucky Bluegrass blend of a mixture of 4 or more of the following improved varieties: Baron Artista, Parade, Midnight, Ram I Flying, America, A-34, Pennstarr, Columbia, Victa Touchdown, Adelphi.

5.4 Irrigation Systems

The Contractor shall repair any irrigation piping damaged during construction activities. Coordination shall occur with the **COR and facility grounds personnel** when irrigation damage is identified.

6. Operational Coordination and Safety

6.1 Daycare Coordination

The water line passes through the daycare yard area. The Contractor shall:

- Provide a **minimum of three (3) weeks advance notice** prior to closure of the daycare playground.
- Coordinate the duration and timing of the closure with the COR.

6.2 Fire Hydrant Service Interruption

The Contractor shall submit and obtain approval for an **impairment permit** when the fire hydrant is taken out of service.

6.3 Traffic and Pedestrian Control

The Contractor shall provide all traffic control and pedestrian safety measures necessary to protect workers and the public.

All **traffic control and pedestrian control plans** shall be submitted to the **COR for review and approval prior to implementation**.

Task 07 Safety on the NIST Campus

NIST is committed to maintaining a work environment that safeguards the public and the environment, as well as personnel and property.

If the award requires construction, demolition, excavation, renovation, or other work for which the contractor directs and oversees contractor personnel (including subcontractors) at NIST-owned and operated sites, the contractor shall:

Provide a detailed, site-specific Safety Plan to the contracting officer within 10 days after award that describes how the contractor will maintain a safe work environment and comply with applicable Occupational Safety and Health Administration (OSHA) standards, as well as with applicable state and local laws, standards, and codes.

The Safety Plan shall specify how the company's policies and practices will comply with each of the applicable standards, laws, and codes.

The contracting officers representative (COR) will provide written comments regarding the plan to the contractor within ten (10) days of receipt and will require the contractor to submit a revised safety plan within ten (10) days after that to the contracting officer for their review. This cycle may be repeated, if necessary, until the contracting officer determines the safety plan to be acceptable.

Reference:

See NIST's Contractor Safety Program for required elements of Contractor Safety Plans.

Task 07 Safety-Related Equipment

The Contractor shall:

Provide all safety-related equipment required to perform the work under this award, including personal protective equipment (PPE) and other equipment that is required or appropriate to protect contractor personnel and other personnel on the NIST campus. Contractor-provided personal protective equipment shall include, at a minimum, hard hats, safety shoes, safety glasses (prescription or standard), respiratory protection (powered air purifying respirator or full-face mask respirator), high visibility clothing and gloves that meet applicable OSHA standards for PPE.

Task 08 Training

The Contractor shall:

Provide safety-related training required by applicable OSHA, state and local regulations or standards to affected contractor personnel (including subcontractor personnel) that perform work under this award. Such training may include, for example, training for proper use of PPE, respirator use, fall protection, crane operation, forklift operation; electrical safety, or other safety-related topics.

Maintain records of safety training provided to contractor personnel (including subcontractor personnel) that perform work on this award. The contractor shall make those records available to the contracting officer, contracting officer's representative for the award, or other authorized personnel within 7 days of receipt of their written request, and annually thereafter or upon request.

Require contractor personnel (including subcontractors) to attend required NIST-specific health or safety training that is required by the award.

Task 09 Health Hazard Assessments and Medical Evaluations

The Contractor shall:

Provide required health hazard exposure assessments, medical evaluations and screenings, and exposure monitoring required by applicable OSHA requirements. Ensure PII information is protected.

Task 10 Homeland Security Presidential Directive (HSPD)-12

The Contractor (and/or any subcontractor) and its employees who require physical access to NIST facilities or logical access to NIST IT networks or systems must comply with Homeland Security Presidential Directive (HSPD)-12, *Policy for a Common Identification Standard for Federal Employees and Contractors*; OMB M-05-24; OMB M-19-17; FIPS 201, *Personal Identity Verification (PIV) of Federal Employees and Contractors*; NIST HSPD-12 policy; and *Executive Order 13467, Part 1 §1.2*.

5. Roster

IV. GENERAL REQUIREMENTS

See attached "NIST Boulder General Contractor Requirements"

Inspection & Acceptance

In addition to the inspection and acceptance terms articulated in the specific FAR clause that allows the Government reserves the right to perform such performance tests and evaluations as

defined below to verify specified system performance. Such tests and evaluations, if performed, shall be conducted within the environment that the system is to be operated. The Contractor has the right to be present during the tests and evaluations, if performed, at the Contractor's expense.

REQUIREMENTS FOR CONTRACTOR PERSONNEL

Identify all qualifications that the Contractor and/or their personnel working on this contract must possess.

Safety: The Contractor employee must be responsible for knowing and complying with all installation safety prevention regulations. Such regulations include, but are not limited to, general safety, fire prevention, and waste disposal.

Security: NIST is a restricted campus. An identification badge is required for access for entry into buildings and is shown to the armed Security Police when entering the campus.

Identification Badges: Contractor employees must comply with NIST identification and access requirements. Each Contractor employee must wear a visible identification badge provided by the NIST Security Office.

V. SCHEDULE OF DELIVERABLES

<i>Deliverable Number</i>	<i>Description</i>	<i>Format</i>	<i>Due Date</i>	<i>Quantity</i>
1	Site Specific Safety plan	PDF	Within 10 days prior to NTP	Email
2	Project Schedule	PDF	Within 10 days prior to NTP	Email
3	Piping Material	PDF	Within 10 days after NTP	Email
4	Valve Cutsheets	PDF	Within 10 days after NTP	Email
5	Select Bedding and Backfill Material.	PDF	Within 10 days after NTP	Email
6	Concrete Mix Design	PDF	Within 10 days after NTP	Email
7	Testing and Disinfection Reports	PDF	Prior to backfilling operations	Email

Standards of Acceptance: The NIST POC or COR shall review all the above deliverables and respond with an acceptance or request for revision email to the Contractor Point of Contact (POC) within 10 days of receipt of deliverable. This section applies to deliverables which must be reviewed and approved for acceptance (e.g., draft plans, drawings, etc.)