

PERFORMANCE WORK STATEMENT (PWS)
FOR
INTEGRATED SOLID WASTE MANAGEMENT
(ISWM)

ROBINSON Digitally signed by
.ANNA.M.1 ROBINSON.ANNA.
284501647 M.1284501647
Date: 2026.04.28
09:18:00 -06'00'

Hill AFB
28 April 2026

PERFORMANCE WORK STATEMENT
TABLE OF CONTENTS

<u>SECTION</u>	<u>PAGE</u>
1. DESCRIPTION OF SERVICES	3-14
2. SERVICE SUMMARY	14-17
3. GOVERNMENT FURNISHED PROPERTY AND SERVICES	17-18
4. GENERAL INFORMATION	18-29
5. APPENDICES	29-79

1. DESCRIPTION OF SERVICES: The Contractor shall provide all personnel, equipment, tools, transportation, materials, vehicles, supervision, and other items and services necessary to perform Integrated Solid Waste Management (ISWM), municipal solid waste (MSW) collection and recycling services at Hill Air Force Base (HAFB) and Little Mountain Test Annex, Utah (LM). The Contractor shall perform these services in this PWS for the Basic Year and each executed Option Year plus any extension of services as required per FAR Clause 52.217-8 Option to Extend Services. The Contractor shall perform to the standards in the contract as well as all local, state, federal regulations, international agreements, Status of Forces Agreements (SOFA), and appropriate Final Governing Standards (FGS), or in their absence, the Overseas Environmental Baseline Guidance Document (OEBGD), with a focus on safety, sanitation and customer service. The Contractor is encouraged and expected to use innovative approaches to efficiently and effectively accomplish PWS requirements in a timely manner, at a reasonable cost and in a way that fosters pride and ownership in the work performed. Estimated Workload Factors (Tables A1 and A2) and Collection Areas (Tables A3, A4, and A5) are in Appendix A, Maps and/or Site Plans are in Appendix B, Government Furnished Property and Services are in Appendix C, CLINS (Bid Schedule Basic Year) is in Appendix D, Container Marking Instructions are in Appendix E, and Safety Requirements are in Appendix F.

1.1. COLLECTION REQUIREMENTS.

1.1.1 Main Base

1.1.1.1. Municipal Solid Waste. The Contractor shall empty refuse containers (Contractor provided MSW containers **with lid closer backstops**) based on historical data in Appendix A, Tables A1 and A2 (Estimated workload and refuse tonnage) for the first 30 days of performance, by the schedule and frequencies identified in Appendix A, Tables A3-A5 (refuse, roll off, and recycle sizes, positions, and frequencies). **The Contractor shall provide lock bars on all trash containers east of the runway both inside and outside the airfield fence, west of the runway inside the airfield fence (especially Bldg 8), and at eating facilities where food debris is present, locations designated with lock bar (LB) in Appendix A-3.** The Contractor shall establish initial vehicle routes and collection schedules upon contract award and if collection dates fall on a federal holiday, the schedule shall reflect this as a non-collection day and adjust accordingly. Details on size, routes, and frequencies shall be submitted to the Contracting Officer (CO) within five (5) calendar days prior to the start of contract performance. The Contractor may propose adjustments to the schedule at any time but as a minimum the CO's designated Representative (COR) (Quality Assurance Personnel) and contractor shall monitor fill capacities during the first 30 days of performance and during one other period to be agreed upon during the same performance period, in order to determine if adjustments to container size, routes, or frequencies should be made to provide the minimum number of pickups necessary to maintain a healthy, vector free environment, and prevent waste container overflow. At the discretion of the CO, sensors may be installed on waste collection containers to study waste generation trends and optimize collection routes. No changes are allowed to the schedule or haul route without CO or COR coordination. Collections as a result of any delays shall be performed by the next workday. Historical frequency tables are located at Appendix A, Table A3. When the contractor completes service at a location there shall be no litter, waste, or recyclable material on the ground within a 10-foot radius of the container.

1.1.1.2. Food Waste. Empty containers used to dispose of food waste daily or at least as necessary to maintain a healthy, vector free environment (on days when the serviced facility is in operation) whether the container is full or not. Food Waste containers and pickup days are identified in Appendix A, Tables A3-A5. Cleaning and deodorizing shall be accomplished IAW paragraph 1.4.2. The government reserves the right to add hauling of food waste to the food digester in Salt Lake City as an option to CLINs 0002, 1002, 2002, 3002, 4002, and 5002.

1.1.1.3. Recycling. The Contractor shall empty recycling containers (both Government and contractor provided **with lid closer backstops**) based on historical data in Appendix A, Tables A1 and A2 (Estimated workload and refuse tonnage) or at least by the schedule and frequencies identified in Appendix A, Tables A3-A5 (refuse, roll off, and recycle sizes, positions, and frequencies) in the first 30 days of performance. **The Contractor shall provide lock bars on all lids of recycling containers east of the runway, both inside and outside the airfield fence, and on the lids of all other recycling containers inside the airfield fence west of the runway to reduce the FOD risk from debris blowing around near and onto the runway, locations designated with lock bar (LB) in Appendix A-5.** The Contractor shall establish initial vehicle routes and collection schedules upon contract award and if collection dates fall on a federal holiday, the schedule shall reflect this as a non-collection day and adjust accordingly. Container size, routes, and frequencies should be established to provide the minimum number of pickups necessary to maintain a healthy, vector free environment and prevent waste container overflow. The initial vehicle routes and collection schedules shall be submitted to the Contracting Officer (CO) within five (5) calendar days prior to the start of contract performance. The Contractor may propose adjustments to the schedule at any time but as a minimum the CO's designated Representative (COR) (Quality Assurance Personnel) and contractor shall monitor fill capacities during the first 30 days of performance and during one other period to be agreed upon during the same performance period, in order to determine if adjustments to container size, routes, or frequencies should be made and provide the minimum number of pickups necessary to maintain a healthy, vector free environment and prevent waste container overflow. At the discretion of the CO, sensors may be installed on waste collection containers to study waste generation trends and optimize collection routes. No changes are allowed to the schedule or haul route without CO or COR coordination. Historical frequency tables are located at Appendix A, Table A5. Collections as a result of any delays shall be performed by the next workday. When the Contractor completes service at a location there shall be no litter, waste, or recyclable material on the ground within a 10-foot radius of the container.

1.1.2. Military Family Housing (MFH) (Non-Privatized). "Reserved" Not applicable to this contract.

1.1.3. Over and Above Requirements (paragraphs 1.1.3.1 through 1.1.3.9 are all Over and Above requirements). The following services shall be priced separately IAW the cost contained in blocks 19 through 24 on the SF 1449 and Section B. The contractor shall be compensated IAW the price specified on the SF 1449 for that service. The contractor shall be compensated IAW the unit price when these services are requested. Zero (0) deficiencies permitted while performing unscheduled collections IAW 1.1.3. – 1.1.3.7. Services designated over and above (estimated quantities based on historical data) shall be compensated IAW the unit price when these services are requested, when additional funding and services are necessary a modification will be issued by the CO.

1.1.3.1. Unscheduled Pickup and Special Events. In addition to the scheduled solid waste collections, the CO or COR may request the contractor make unscheduled collections and disposals. For unscheduled events, the contractor shall respond within one business day of notification from the CO or COR. For special events, the contractor shall also perform additional work and provide additional (or reposition as directed) solid waste containers. These containers shall be placed in locations for a length of time designated by the CO or COR. The CO shall notify the contractor in writing at least 7 business days in advance of the special event date. Special events/projects include, but are not limited to, Operational Readiness Exercises (ORE), Unit Compliance Inspections (UCI), Operational Readiness Inspections (ORI), Environmental Compliance Assessment Management Program (ECAMP), Air Shows, Change of Command ceremonies, and Government functions. These special events may be located at geographically separated locations that do not normally receive service. [The COR will notify the Contractor when special remote service is required and discuss particulars of the needed service]. The Contractor shall perform all work within the agreed timeframe. Additional work required for special events shall not relieve the Contractor of the responsibility to perform existing scheduled required services. See Appendix A for estimated workload data and task and frequency tables.

1.1.3.2. Construction and Demolition Debris (C&D). When requested by the CO or COR, the contractor shall provide roll-off containers for collection of C&D as detailed below and in Appendix A, Table A4. The contractor shall place container(s) at the designated site within one business day of notification by the CO or COR. Container(s) placed in Industrial or Flight Line areas shall have a fitted cover (or cover provided to the facility manager). Each container service includes pickup, recycling or disposal, and return to original location IAW paragraphs 1.1.5 and 4.5 and will be billed as one collection on the monthly invoice. The contractor shall recycle or dispose of all C&D at a recycling facility or permitted landfill. The contractor shall provide weight tickets of all roll-off containers to the COR. Contractor shall be on an “on call” basis within one business day of notification by the CO or COR. The Government may require the contractor to perform this service other than normal duty hours. See Appendix A for estimated workload data and locations.

1.1.3.2.1 Permanent Roll off Containers. The Contractor shall provide containers to collect scrap wood, construction debris, and miscellaneous refuse or recyclable materials. The location of delivery is listed in Appendix A. The Contractor shall service the containers as listed in Appendix A Table A4. The COR or CO shall notify the contractor when the roll off is ready to be serviced if frequency differs from that listed in Appendix A. The contractor shall immediately notify the CO or COR of any overloaded or blocked containers. See Appendix A for task and frequency.

1.1.3.2.2 Roaming Roll off Containers. The contractor shall provide containers to collect scrap wood, construction debris, and miscellaneous refuse or recyclable materials. The COR or CO shall notify the contractor the date and location of delivery and the point of contact including telephone number. The COR or CO shall notify the contractor when the roll off is ready to be serviced or picked up. Each delivery and pick up or service will be billed as one collection on the monthly invoice. The contractor shall immediately notify the CO or COR of any overloaded or blocked containers. See Appendix A for task and frequency.

1.1.3.2.3 Roll off Load & Go's. The contractor shall provide containers to collect scrap wood, construction debris, and miscellaneous refuse or recyclable materials as a load & go collection. The COR or CO shall notify the contractor of the date and location of collection and the point of contact including telephone number at least 24 hours prior to scheduled delivery time. The contractor shall contact each load & go customer no later than 0730 the morning of delivery to notify them of the arrival time so the customer can arrange for personnel and equipment to begin working as soon as the roll off container arrives. The contractor must notify the customer no later than 1 hour prior to arrival time. If the contractor needs to reschedule, the contractor shall notify the customer. The contractor shall notify the COR of any rescheduling no later than 1500 the same day. The contractor shall wait while the roll off container is filled by the customer. If the customer is unable to start filling the container within 10 minutes of arrival, the contractor shall notify the COR or CO immediately and leave the area. The customer will reschedule with the COR. The contractor shall immediately notify the CO or COR of any overloaded or blocked containers. See Appendix A for estimated workload data.

1.1.3.3. Public/Common Use MSW Receptacles. “Reserved” Not applicable to this contract.

1.1.3.4. Public/Common Use Recycling Receptacles. “Reserved” Not applicable to this contract.

1.1.3.5. Ash Collection. “Reserved” Not applicable to this contract.

1.1.3.6. Additional Pickups. In the event unusual conditions cause a container to require pickup before the scheduled time, the CO or COR may request in writing (email sufficient) pickup within 24 hours and the contractor will be compensated at a unit rate based on the container size per contract line item IAW Schedule B.

1.1.3.7. Container Relocations. The Government may request relocation of containers. The request will be made in writing, and the container shall be relocated within 72 hours, unless an emergency request is made. The contractor shall provide emergency container relocations during real-world higher Force Protection Conditions (FPCON's). The contractor shall move all specified containers to the locations identified by the CO or the COR for the purpose of relocating containers at least 83 feet (25 meters) from the facilities. The contractor shall be on-call 24 hours a day, 7 days a week, including weekends and holidays. Emergency container relocations are expected to be initiated when the base reaches real-world FPCON Alpha plus or higher. The contractor shall supply the name of their designated representative for contractual actions. The contractor shall notify the CO within 24 hours of any change affecting the designated representative. Initiation to relocate the identified containers shall be completed by the CO or the COR notifying the contractor's designated representative by phone or other means of communication. The CO or the COR shall direct the contractor to execute relocation of containers to FPCON locations. The contractor shall begin container relocations within 2 hours of notification. All moves must be completed in a quick and safe manner. The contractor shall contact the CO or the COR if there are any problems, difficulties, or resistance associated with container relocations. If problems with routine collection occur, contractor shall coordinate with the COR to adjust routine collection schedules during FPCON. The contractor shall notify the CO immediately upon completion of dumpster relocations. Dumpsters shall remain at designated FPCON locations until directed by the COR. At this time, the contractor shall move

all dumpsters back to the original locations during regular refuse collection schedule; these moves shall be completed within seven (7) working days.

1.1.4. Inclement Weather Schedule. The contractor shall collect MSW and recyclable material during periods of inclement weather. In cases of severe weather, the CO or COR may authorize exceptions, in writing. When exceptions are granted, all missed collections shall be performed within 24 hours after the severe weather has terminated, unless the CO authorizes additional time.

1.1.5. Route Parameters. The contractor shall submit proposed routes from their facility to Hill AFB using the New North Gate as the only entrance/exit point to the CO at least five (5) calendar days prior to contract award. Collection shall be made between the hours of 0600 – 1500 hours, Monday through Friday for all containers. Collection outside these hours shall require prior coordination of the CO or COR.

1.1.5.1 The contractor shall establish routes so that all containers within restricted or secured areas are serviced during normal working hours (0700 – 1430). The contractor shall identify in writing the employees performing service to any containers located in restricted or secured areas. As a minimum, the names, social security number, type of vehicle and start date of employment shall be provided. The contractor shall update list as changes occur.

1.1.5.2 The contractor shall immediately notify the CO or Government COR of any conditions that may interrupt the schedule of performance such as accidents, disposal sites backed up, delays due to security measures, exercises, vehicle breakdowns, blocked containers, etc. Commercial vehicles going through the New North Gate inspection area have had far fewer delays than the previous Roy Gate had, which was up to 4 hours on a single day. Previous contracts had issues in the 1200's area with vehicles blocking access to containers even when parked legally, but this has been better since people started teleworking during the pandemic.

1.1.5.3 The contractor shall comply with all security procedures to ensure restricted/secure areas are not compromised. This may include but is not limited to ensuring that access gates into secure areas close behind the drivers as well as opening and securing privacy fence gates and/or dumpster enclosure doors.

1.1.6. Points of Collection. Collection stations for MSW and recyclable materials are shown in Appendix B. The contractor shall position bulk containers for customer ease in depositing MSW and recycling material. The contractor shall also position containers to minimize interference with adjacent parking areas, sidewalks, roadways, overhead utilities, trees, storm drains, fire hydrants, and other potential obstructions. The COR may request the Contractor to relocate or reposition dumpsters when required. The Contractor shall perform these relocations within 72 hours after notification. Notify the COR immediately if any hazardous waste is found at a collection point. The contractor shall accomplish service for all containers on days and frequency stated in their collection schedule IAW requirements in paragraph 1.1.5. **The government reserves the right to add up to a total of 60 rented front loader containers sized 6 CY of type MSW and up to a total of 60 rented front loader containers sized 8 CY of type recycle, in addition to those locations listed in Appendix A, throughout the life of this contract at no**

additional charge.

1.1.6.1. Missed Collections. The Contractor shall not miss collections; in the event that they are missed, the Contractor shall prioritize missed pick-ups at no additional cost to the Government. If the Contractor is notified by the CO or COR because of a missed collection, such collections shall be performed within 24 hours after notification and will be documented as a customer complaint.

1.1.7. Cubic Yard Capacity. Proposed capacity of containers is indicated in Appendix A. The contractor is encouraged to identify changes to the capacity of containers and/or pickup frequency to improve the overall efficiency of MSW and recycling removal, and to submit these changes to the CO or COR. No changes shall be made until the proposed change is coordinated with the CO or COR. The Government reserves the right to change the cubic yard capacity at any collection station or change the number of collection stations as long as it does not increase the overall total cubic yard capacity of this PWS. The Government may also reduce the frequency of collections.

1.1.8. Government-Approved Containers. Collection of MSW and recyclable materials in all areas except **Boyer Hill** residential area shall be from contractor-provided, CO or COR accepted, additional **MSW and** recyclable materials containers, and Government furnished recyclable materials containers. All containers shall meet the base architectural/appearance standards. The Government will provide approximately 210 recycling containers (cardboard/paper) at select buildings. The contractor shall furnish **seventy-two (72)** recycling containers (cardboard/paper) to be located at additional selected existing and new buildings after placing government furnished recycle bins. **Placement of containers shall be documented on the container placement spreadsheet to include building number nearest the container location, date delivered, and signed by the contractor representative and the CO or COR.**

1.1.8.1. Containers. The contractor shall furnish all bulk refuse dumpsters (including up to 60 additional refuse containers) **with lid closer backstops, all recycling containers (including up to 60 additional refuse containers) with lid closer backstops, self-contained compactor units, and roll off containers.** All containers must be delivered and kept in good working condition. All bulk refuse dumpsters shall be cathedral type with durable plastic lids for most areas on base. Dumpsters placed along loading docks shall be convenient for customers to throw refuse away from the dock. The contractor shall collect and dispose of refuse and recyclable materials such that refuse and recycling containers are emptied before reaching full capacity. **The Contractor shall provide lock bars on all trash containers east of the runway both inside and outside the airfield fence, west of the runway inside the airfield fence (especially Bldg 8), and at eating facilities where food debris is present. The Contractor shall provide lock bars on all lids of recycling containers east of the runway, both inside and outside the airfield fence, and on the lids of all other recycling containers inside the airfield fence west of the runway to reduce the FOD risk from debris blowing around near and onto the runway, locations designated with lock bar (LB) in Appendices A-3 and A-5.**

1.1.8.2. Painting of collection containers. The contractor shall wash and paint all containers including government-provided recycling containers (cardboard/paper) at least

once annually, repair as needed, and document on the *container condition checklist*. All contractor-provided MSW containers shall be Dakota Brown Federal paint number 30099 (Sherwin-Williams # 2056), and contractor-provided recycling containers (cardboard/paper) shall be Greystone Federal paint number 23617 (Glidden # 78-50). The contractor shall also paint all Government-provided recycling containers (cardboard/paper) Greystone Federal paint number 23617 (Glidden # 78-50).

1.1.8.3. Sawdust collection containers. The contractor shall furnish containers to capture sawdust at locations listed in Appendix A under Refuse Collection Stations & Frequency.

1.1.8.4. Container Storage. All contractor storage shall be off base, including government provided recycling containers. The contractor is responsible for any damaged or stolen government containers; the contractor shall ensure before the containers are brought to the base, they are freshly emptied, cleaned, and painted.

1.1.8.5. Compactor Units. The contractor shall provide three self-contained food compactor units to be positioned on the Northwest corner of building 849, on the West side of building 400 (Commissary), and on the South side of building 412 (BX). If the contractor should replace the compacting unit with a different type or model than the existing units, the contractor shall furnish training to government personnel employees at no cost to the government. See Appendix A for historical data.

1.1.9. Maintaining Containers and Collection Area. The Contractor shall return all MSW and recycling containers to their original location after servicing, in an upright position with the lids securely in place (closed and locked where applicable) and accessible to both customers and the contractor. The Contractor is responsible for cleaning up any spills, debris, etc., on the ground within ten (10) feet of the container when servicing a location. The contractor shall collect debris placed at collection stations; for example, tree branches, sacks, cartons, boxes, cans, tied bundles, or other containers as applicable. It is intended that the majority of debris will be placed in containers. The Contractor shall notify the COR of locations where debris is frequently placed outside of containers so the COR may notify facility managers and, if necessary, the Contractor can adjust the container size or pickup frequency with CO or COR approval. The contractor shall be responsible for keeping collection areas free of solid waste and debris. The contractor shall also notify the COR if it is discovered that a particular receptacle is being utilized for the wrong material.

1.1.10. Vehicle Weighing. All vehicles used to collect MSW, C&D, organics, and recyclable commodities shall be weighed on state-certified public vehicle scales / weigh station, either on- or off-base. When use of off-base scales is the only option, a predetermined public state-certified scale/weight station will be identified for use. The COR may be present at the public scale for empty and loaded weighing with no notice to the Contractor. All weight discrepancies shall be resolved prior to departing the scale site. The Contractor and COR (if present) shall sign all weight tickets. The Contractor shall submit a monthly report (paragraph 1.5) that includes weight tickets that reflect the disposed tonnage figures, disposal date, vehicle type, and landfill tipping fee cost. The Contractor shall be reimbursed for tipping fees according to submitted invoices with original valid weight tickets.

1.2. RECYCLABLE MATERIALS PROCESSING. The contractor needs to take recycling material off base to be sorted at a Municipal Recycle Facility (MRF). The base operates a Qualified Recycling Program (QRP) to reduce the volume of non-hazardous solid waste generated. It is the intent of the base to conduct direct sales of recyclable commodities through a QRP. The contractor shall provide a detailed accounting of recyclable commodities sold (type / weight / price) to the QRP along with 100 percent of the sales proceeds. The contractor shall be aware of the DoD and USAF waste diversion goals and notify the base QRP manager of potential waste diversion opportunities in the local area. The Air Force waste diversion goals can be found in the most current USAF Strategic Sustainability Performance Plan (SSPP). The USAF SSPP can be found at <http://www.safie.hq.af.mil/esoh/>.

1.2.1. Materials. The following items shall be recycled: office paper, newspaper, clean corrugated fiberboard/cardboard/paperboard, colored paper, packing paper, paper bags, magazines, and books. Contractor may recycle materials not listed above with prior coordination of the CO or COR, if collection and transportation costs do not exceed cost of disposal as MSW. All recyclable items shall be stored, shipped and disposed of IAW federal and local environmental regulations.

1.2.2. Pickup Points. Contractor shall provide recycling containers at the locations specified in Appendix A, Tables A3-A5. Containers shall be emptied as specified in section 1.1.1.3.

1.2.3. Base Recycling Center / Material Recovery Facility. The government will provide the contractor use of the base recycling area as shown in Appendix B. Alternatively, the contractor may transport mixed recyclables to a contractor-owned or third party off-base facility for separation and resale so long as government recyclable materials are sorted and weighed prior to commingling with other customers' recyclables. Recyclable recovery is detailed below.

1.2.3.1. Contractor Responsibilities. Separate and process recyclables IAW buyers specifications. The contractor shall prepare for transport/resale all recyclable materials. Perform daily general maintenance, such as cleaning and replacing light bulbs, and perform recommended maintenance on government furnished equipment. Provide appropriate personal protective equipment for employees. Notify Base Civil Engineer customer service for facility maintenance or repair requirements. Return government furnished equipment listed in Appendix C to the government upon conclusion of contract. With the approval of the CO, contractor may procure and install additional equipment as required to more efficiently process recyclable materials. Contractor-purchased equipment shall be procured at the contractor's expense, owned by the contractor and may be removed upon contract termination.

1.2.3.1.1. Organic materials. The contractor shall collect co-mingled cardboard and paper from government and contractor provided recycling containers. Collected co-mingled clean corrugated cardboard, white ledger, colored paper, newspaper, packing paper, paper bags, paperboard, magazines, books, etc. shall be taken to an off-base vendor that accepts these items. The contractor shall also collect wood waste that shall be preferentially taken to a recycle or compost facility if available.

1.2.4. Marketing. The contractor shall, with CO approval, market recyclable commodities, which may include transporting commodities to buyers. The Contractor shall, with CO approval,

educate all residential and base facility occupants on the benefits of recycling and encourage the widest possible participation. If approved by the CO, written publications such as original published pamphlets, brochures, or other informative media, may be used to inform users.

1.2.5. Sales Receipts. The contractor shall provide a Commodity Sales Summary to the COR, no later than the fourth working day of the month following the sale month, consisting of commodity type sold, sale proceeds achieved by commodity, and weights of commodity sold. Documentation to accompany the Commodity Sales Summary includes original commodity sales receipts for recyclable materials, commodity sold weight tickets, and reimbursement check for commodity sales proceeds to the COR. The sales receipts shall contain the weight, type, and price of the commodity recycled. The contractor shall also submit an invoice for reimbursement for costs associated with conducting sales transactions, collection, processing, transporting, and sale of recyclable commodities to commodity buyers.

1.2.6. Composting. “Reserved” Not applicable to this contract. Composting performed under current Grounds Maintenance Contract.

1.3. DISPOSAL.

1.3.1. Off-Base Disposal. The contractor shall transport and dispose of all MSW at a permitted off-base disposal site. A copy of the landfill(s) operating permit that material is transported to shall be provided to the CO. The contractor shall transport recyclable commodities to an off-base material recovery facility. The contractor is responsible for disposal being IAW existing local, state, and federal regulations such as FGS, OBEGD, etc. The contractor shall be responsible for any permit or fees associated with the use of off-base disposal locations and invoice to CLIN 0018 for reimbursement.

1.3.2. Disposal of Non-marketable Materials. Any commodity rejected by a predetermined commodity buyer must be reclaimed by the Contractor for commodity rework or disposal. Commodity rejection explanation must be provided to the CO or COR within 24 hours of buyer rejection along with remedy of the reject and plans to prevent same future rejections. Disposal of non-marketable materials from processing recyclable materials at contractor’s off-base facility include plastic bags, pizza boxes, other soiled boxes, Styrofoam, household items, toys, automotive parts, tires, mattresses, refrigerators, TV’s, etc.

1.4. EQUIPMENT MAINTENANCE. Contractor furnished containers and Government furnished containers shall match the color scheme of the base. Additional re-painting shall match the approved color scheme. The Contractor shall maintain all Contractor and Government provided containers ensuring they are free of unpleasant odors, dirt, debris, and pests. All containers shall remain in good, workable condition, with no leaks. They shall remain easily accessible to both customers and the Contractor while always maintaining traffic safety. Containers no longer serviceable or repairable shall be replaced from the Contractor’s back-up stock at no additional cost to the Government. **The Contractor shall perform all cleaning and painting tasks off base at least once annually and document on the *container condition checklist*. The Contractor shall perform all repair and other maintenance tasks off base as needed and document on the *container condition checklist*.** Trucks and trailers used for hauling and collecting shall be free of odor, dirt, debris, and pests. Contractor vehicles and

equipment shall not have any waste or equipment leaks such as oil or hydraulic fluid. Should any Contractor vehicles or equipment have any leaks, the Contractor is responsible for cleanup.

1.4.1. Vehicles. All vehicles shall be contractor-furnished. All contractor vehicles shall have their company logo clearly visible on both sides of the vehicle and be maintained clean to present a neat, professional appearance. The contractor shall provide an adequate number of vehicles and equipment to fulfill the scope of this contract. In addition, the contractor shall maintain or have backup capability to provide continued service in the event primary vehicles or equipment is down for extended maintenance or repairs. Vehicle and/or equipment failure shall not alleviate the contractor from performing any requirement contained in this contract.

1.4.1.1. Vehicle Maintenance. All vehicles and equipment used in the performance of this contract shall be in good operable condition and meet the current and future local, state, and federal safety requirements if updated during this contract period. Vehicles and equipment found to be unsafe and unable to function as designed shall be removed from the installation and replaced at the contractor's expense. Vehicular repairs shall be done off base including all routine maintenance such as fluid changes or top offs. The CO or COR may inspect the contractor's vehicles and equipment at any time and direct the removal of any unsafe or unusable vehicle or equipment from the installation. Broken down vehicles shall be removed from the base within 2 hours. Any vehicle leaks on base property must be reported to the COR or CO immediately. Contractor shall provide absorbent material, a flat nosed shovel and broom, and a container to recover spilled liquids from emergency situations such as broken hydraulic lines (spill kit on each vehicle should be maintained to contain enough for 110% of the maximum volume of chemicals carried on that vehicle). Clean up shall be performed immediately, and disposal of recovered materials shall be done off Base in compliance with applicable laws. Contractor shall also carry materials to prevent spilled fluids from entering a drain. Contractor is liable for the spill or release into soil/water/drains. Contractor is responsible for all costs associated with clean-up and restoration including any applicable fines and/or penalties.

1.4.2. Container Maintenance. All containers must remain in good, workable condition, with no rust, dents, broken parts, inoperable parts, or leaks. Major repairs or maintenance, as determined by the CO, shall require replacement of the container. This applies to all refuse, recycling, compactor units, and roll-off containers. **Missing or defective container lids within the flight line area shall be replaced within 48 hours after notification of defect; container lids in all other areas shall be replaced within seven working days.**

1.4.2.1 Painting and Signage Requirements. All refuse, compactor units, and roll off dumpsters shall be numbered, have signs, and painted a uniform brown, Dakota Brown Federal paint number 30099 (Sherwin-Williams # 2056). Government furnished and contractor furnished cardboard/paper containers shall be numbered, have signs, and painted a uniform beige, Grey Stone Federal paint number 23617 (Glidden # 78-50). The contractor shall provide all container signage and numbering, see Appendix E for specific requirements. Signage and numbering shall be approved by the CO before placing on containers. The contractor shall paint and apply new signage and numbering to all refuse, recycling, compacting units, and roll off containers within the first 90 days after the start of the contract and at a minimum of once every two years. Any painting shall be performed IAW standard commercial industry practice, performing proper pre-

paint preparation practices, etc.

1.4.2.1.1 Cardboard Recycling Containers. Except where previously stated, cardboard containers shall be eight (8) cubic yard containers, with self-closing lids and slot cut in top front for insertion of flattened cardboard. Location and frequency of collection are specified in Appendix A-5. The contractor shall provide all container signage and numbering, see Appendix E for specific requirements.

1.4.2.1.2 Sawdust Collection Containers. The contractor shall provide containers for the collection of sawdust as required. The container shall be modified to fit the collection system. The contractor shall provide all container signage and numbering, see Appendix E for specific requirements.

1.4.2.2 Cleaning Requirements. At a minimum all containers shall be cleaned annually to clean any food and/or refuse left on the inside and outside of the container and reduce odor. Containers located at a dining or similar facility shall be cleaned annually during warm months to clean food waste and reduce odors. All bulk containers shall have lids and doors that are easily operable and that prevent rodents from entering. The contractor shall be responsible for insuring container drain plugs are in place and functional throughout the period of the contract. The contractor shall furnish replacement bulk containers for all bulk containers removed for more than two hours for cleaning, painting, and/or repair. The term “all containers” refers to all contractor furnished property such as dumpsters, compactors, roll-offs, sawdust containers, recycle bins, etc. and to all government furnished property such as recycle bins.

1.4.3. Container Condition Logs. Truck drivers shall keep a monthly log that lists the following information: date, location of container, structural repair needed (as applicable), repair plan, estimated repair completion date, actual repair completion date. Contractor shall submit a monthly *container condition checklist* report to the COR concurrent with the monthly invoice. Report shall be submitted in tabular format, such as an Excel spread sheet.

1.5. REPORTS AND RECORDS. The contractor shall provide a monthly report (invoice), by the third working day of the month, detailing the previous month’s total contract costs incurred, cumulative weight tickets for total tonnage of solid waste collected (MSW, C&D, organics, recycling, roll-off, compactors, and load & go’s), landfill tipping fees, weight tickets, weights diverted by recyclable commodity, cost to divert by recyclable commodity, sales proceeds reimbursed in sufficient detail to support Defense Environmental Programs Management requirements. These monthly reports shall be furnished in both pdf file and Excel format file(s). The monthly invoice shall be submitted to the Government COR no later than three (3) workdays following the month of service using electronic means of submission, i.e. Wide Area Work Flow (WAWF). The government will inform the contractor if changes to the submittal process are required. The contractor shall provide monthly landfill or transfer station report listing all transactions for the month. Report shall contain the load/ticket number, date, and time, and total weight. Original refuse weight tickets and recycling sales receipts from the recyclables must accompany the report, as well as gross proceeds from recyclable sales. Reports and weigh tickets shall be provided no later than the third working day of each month in order to meet billing requirements.

1.6. Contractor Manpower Reporting. The contractor shall report ALL contractor labor hours (including subcontractor labor hours) required for performance of services provided under this contract for ISWM via a secure data collection site. The contractor is required to completely fill in all required data fields at <https://sam.gov/content/entity-reporting> within the general website of <https://www.sam.gov>. Reporting inputs will be for the labor executed during the period of performance for each Government fiscal year (FY), which runs from 1 October through 30 September. While inputs may be reported any time during the FY, all data shall be reported no later than 31 October* of each calendar year. Contractors may direct questions to the CMRA help desk.”

***Reporting Period:** Contractors are required to input data by 31 October of each year.

Variation in Workload: The monthly invoice and weight tickets shall be submitted to the Government COR no later than three (3) workdays following the month of service using electronic and physical means of submission, i.e. Wide Area Work Flow (WAWF). The government will inform the contractor if changes to the submittal process are required. The contractor shall provide monthly landfill or transfer station report listing all transactions for the month. Report shall contain the load/ticket number, date, and time, and total weight.

Uses and Safeguarding of Information: Information from the secure web site is considered to be proprietary in nature when the contract number and contractor identity are associated with the direct labor hours and direct labor dollars. At no time will any data be released to the public with the contractor name and contract number associated with the data.

User Manuals: Data for Air Force service requirements must be input at the Air Force CMRA link. However, user manuals for government personnel and contractors are available at the Army CMRA link at

<https://acc.army.mil/contractingcenters/acc-nj/COR/Contractor%20CMRA.pdf>.

2. SERVICE SUMMARY. The contract service requirements are summarized in performance objectives that relate directly to mission essential items. **Unless indicated elsewhere, these performance objectives will be measured monthly.** The performance threshold briefly describes the minimally acceptable levels of service required for each requirement. The Services Summary (SS) and the Contractor’s Quality Control Plan (QCP) provide information on contract requirements, the expected level of contractor performance, the expected method of Government validation/surveillance, and confirmation of services provided. These thresholds are critical to mission success. Procedures as set forth in the FAR 52.212-4 (a), Contract Terms and Conditions - Commercial Items, Inspection/Acceptance, will be used to remedy all deficiencies. During the first initial 30 days of the contract, two additional errors on each Performance Objective shall be allowed in an effort to identify normal phase-in problems.

Performance Objective	PWS para.	Performance Threshold
Collect MSW IAW the established schedule.	1.1	No more than 2 valid customer complaints per month.
Perform Recyclable Materials Processing IAW QRP and USAF SSPP.	1.2	0 Deficiencies permitted.
Dispose of MSW IAW the established governing directives.	1.3	0 Deficiencies permitted.
Performance Objective	PWS para.	Performance Threshold
Perform Recyclable Materials Processing IAW QRP and USAF SSPP.	1.2	0 Deficiencies permitted.
Dispose of MSW IAW the established governing directives.	1.3	0 Deficiencies permitted.
Maintain contractor owned and government owned equipment in good workable condition, free of defects. Perform painting and cleaning requirements. Trucks and solid waste containers washed and free of odors.	1.1.8, 1.1.9, 1.4, 1.4.1, 1.4.2, and 3.2	No more than 2 valid Customer Complaints per month.
Perform unscheduled collections required by the contracting officer IAW paragraph 1.1.	1.1.3.1	0 Deficiencies permitted. (Delivery order will not be accepted until all deficiencies are corrected.)
Produce/maintain reports and records by third working day of the month.	1.1.10, 1.2.3, 1.2.5, 1.3, 1.4.3, and 1.5	0 Deficiencies permitted.
Collect and dispose of scrap wood, construction debris, and miscellaneous refuse from roll off containers IAW the established schedule.	1.1.3.2 and 1.1.8.5	No more than 2 valid customer complaints per month.
Comply with Environmental rules, regulations, and security and safety requirements.	1.4, 1.4.1.1, 1.4.2.2, 4.9, and 4.10	No deficiency permitted

2.1. Quality Control. The contractor shall develop and maintain a quality control program to ensure ISWM, MSW collection, and recycling collection services are performed IAW commonly accepted commercial practices and services identified in this PWS. The contractor shall develop and implement procedures to identify, prevent, and ensure non-recurrence of defective services. As a minimum, the contractor shall develop quality control procedures addressing the areas identified in paragraph 2, Service Summary.

2.1.1. Quality Control Program. In compliance with the clause **FAR 52.246-4** entitled “Inspection of Services – Fixed-Price”, the contractor shall establish a complete Quality Control Program to ensure the requirements of this contract are provided as specified. The CO will notify the contractor of acceptance or required modifications to the plan before the contract start date. The contractor shall make appropriate modifications (at no additional costs to the government) and obtain acceptance of the plan by the CO before the start of the first operational performance period. The contractor shall have a person on staff that is qualified as the project Quality Control (QC) Manager. That person shall conduct random on-site inspections, ensure daily operations are on schedule and completed within specified timelines, have full authority to act on all contract matters relating to the daily operation of the contract, and be responsible for compliance with the quality control plan.

2.2. Quality Assurance. The Government will inspect and evaluate the Contractor’s performance to ensure services are received IAW requirements set forth in this PWS. The contractor shall provide work schedules to the COR IAW paragraph 4.3 of this PWS. The COR will inspect by validating actual work performance, physically checking an attribute of the completed task, checking a management information report, investigating customer complaints, conferring with facility managers, or otherwise inspecting the task or its results to determine whether or not performance meets the standards contained in this PWS. The COR will use the Contractor’s work schedule or modified version thereof, to record validation results. Results of the validation then become the official Air Force record of the Contractor’s performance. Missed collections and unacceptable services shall be corrected within 24 hours of CO/COR notification at no additional cost as the preferred course of action when appropriate. When a performance threshold has not been met or Contractor performance has not been accomplished, the COR will initiate and provide the CO a Contract Discrepancy Report (CDR) DD Form 2772 for issuance to the Contractor. The Contractor shall respond to the CDR IAW instructions provided and return it to the CO within 10 calendar days of receipt. Performance of a corrected service shall be evaluated to determine whether or not it meets the performance requirements of this contract.

2.2.1. Government Remedies. The CO shall follow FAR 52.212-4 Contract Terms and Conditions-Commercial Items, for contractor’s failure to perform satisfactory services or failure to correct non-conforming services.

2.3. Performance Assessment.

2.3.1. Periodic Validation. This method requires the COR to employ a “spot check” style of evaluation based on the contractor’s schedule. Periodic validation will be conducted on a

scheduled basis (i.e. daily, weekly, monthly, quarterly, semi-annual or annually) and may be adjusted, based on quality trends.

2.3.2. Unsatisfactory Performance. Any unsatisfactory inspection (defect) result will be recorded, and the Contractor shall re-perform the service after notification by the COR. Failing to meet the performance threshold as outlined in the Services Summary for any performance objective in any one month period will result in a warning or letter of concern from the CO. Failing to meet the performance threshold as outlined in the Services Summary of these performance objectives in any combination for any two, or more, consecutive or non-consecutive months during a contract period will constitute an immediate Progress Meeting with the Multi-Functional Team. All remedies will be IAW the FAR 52.212-4 (a), Contract Terms and Conditions – Commercial Items, Inspection/Acceptance.

2.3.3. Customer Complaints. The COR will receive and investigate complaints. The COR will be responsible for initially validating customer complaints. The CO will make final determination of the validity of customer complaint(s) in cases of disagreement with the COR and the Contractor. Validated customer complaints shall be re-performed after notification by the CO or COR. Exceeding the performance threshold as outlined in the Services Summary for performance objective in any one month period will result in a warning or letter of concern from the CO. Exceeding the performance threshold as outlined in the Services Summary for performance objectives for any two (2), or more consecutive or non-consecutive months during a contract period will constitute an immediate Progress Meeting with the Multi-Functional Team. All remedies will be IAW the FAR 52.212-4 (a), Contract Terms and Conditions – Commercial Items, Inspection/Acceptance.

2.4. PERIODIC PROGRESS MEETINGS.

2.4.1. Meetings. The CO, Functional Commander, COR, QRP Manager and/or Solid Waste Manager, other government personnel as appropriate, and the Contractor shall periodically meet to discuss the Contractor's performance. The following issues shall be discussed: opportunities to improve the contract, required contract modification(s), unsatisfactory inspections and trends against each performance objective observed, positive performance, and steps taken by the Contractor to prevent unsatisfactory occurrences in the future. The Contractor shall provide a summation of unsatisfactory inspections and customer complaints and provide insight into any identified trends.

2.4.2. Meeting Minutes. The minutes of these meetings will be reduced to writing, signed by the CO, and any other signatures as deemed appropriate, distributed to the functional area and the Contractor, and a copy placed in the official contract file. Should the Contractor not concur with the minutes, the Contractor shall provide a written notification to the CO identifying areas of non-concurrence for resolution.

3. GOVERNMENT FURNISHED PROPERTY AND SERVICES. The Government will not provide any facilities or storage space for the Contractor's use under this contract. The Government will provide most recycling containers and all snow removal, police, fire, and

rescue services IAW Appendix E. The Contractor shall reimburse the Government for emergency medical treatment and transportation if these services are required.

3.1. Recycling Center/Material Recovery Facility. Currently there is a centrally managed recycling center at Bldg. 801 near Balmer Ave and 6th Street, see Appendix B. There are recycle containers for cardboard/paper located east of the facility, to the north of Bldg. 805 (Outdoor Recreation). Provide utility service to the recycling center/material recovery facility and perform facility maintenance and repairs. Provide use of equipment listed in Appendix C.

3.2. Recycle Containers. The Government is providing most recyclable containers “as is” for Contractor use and will give the opportunity for the Contractor to inspect the property before it is provided. Any repairs and/or refurbishment shall be at the contractor’s expense IAW FAR 52.245-1 and 52.245-2. The Contractor shall have a property management plan (PMP) that shall be a contractually binding document that is to be approved by the CO, it shall discuss the voluntary consensus standards (VCS) or industry leading practices (ILPs) the contractor intends to follow. Contractors shall use ILPs and VCSs to manage Government property in their possession. Recycle containers are on a rent-free basis.

4. GENERAL INFORMATION.

4.1. MISSION.

The overall Civil Engineer mission at Hill AFB and Little Mountain Test Annex is to plan, maintain, operate, and protect the infrastructure, facilities, and environment for assigned Airmen, families, and civilian employees.

4.2. BACKGROUND.

In the past there have been issues with vehicles blocking dumpsters causing issues with servicing the cans during normal business hours. Also, in the past there have been issues with gate delays increasing wait times during a service day. Due to many employees teleworking, there are fewer issues with vehicles blocking dumpsters in the 1200’s area than previously. Gate delays still happen, but only occasionally now.

4.3. HOURS OF OPERATION. Perform integrated solid waste management services during normal duty hours and be available (by phone, pager, cell phone, text message, or fax/email) during the Government Program Office’s hours (6:00 a.m. to 3:00 p.m., Monday through Friday) and for after-hours response to refuse/recycling problems or emergencies. This excludes federal holidays, unless otherwise required in the contract or approved by the CO. There may be situations that require the Contractor to work at times other than normal duty hours. Collection outside these hours shall require prior approval of the CO. When the Contractor’s work schedule conflicts with an Air Force mission requirement, advise the CO and reschedule the work to minimize disruption.

4.4. HOLIDAYS & CLOSURES

4.4.1 Recognized Federal Holidays. There may be federal holidays when the Contractor is not required to perform service, except in emergency situations or to support specific mission needs. The holidays are:

New Year's Day - 1 January
Martin Luther King Day - 3rd Monday in January
Washington's Birthday - 3rd Monday in February
Memorial Day - last Monday in May
Juneteenth - 19 June
Independence Day - 4 July
Labor Day - 1st Monday in September
Columbus Day - 2nd Monday in October
Veteran's Day - 11 November
Thanksgiving Day - 4th Thursday in November
Christmas Day - 25 December

If a holiday falls on a Saturday, the preceding Friday will be observed. If a holiday falls on Sunday, the following Monday will be observed. If a holiday falls on a scheduled service day, the Contractor shall be responsible for rescheduling services for the first day after the holiday observance.

4.4.2. Other Base Closures. Work scheduled but not accomplished because of base closure due to exercises or real-world events shall be accomplished as soon as possible after base reopening.

4.5. PERFORMANCE OF SERVICE DURING CRISIS OR HEIGHTENED SECURITY.

The services under this contract are not essential for performance during crisis. The CO will determine circumstances which constitute a crisis based on direction from Security Forces and base leadership. IAW DFARS 252.237-7023 (continuation of Essential DoD Contractor Services during a Crisis) and/or DFARS 252.237-7024 (notice of continuation of Essential DoD Contractor Services during a Crisis),

(a) Contractors providing services designated as essential contractor services by a requiring activity shall be prepared to continue providing such services, IAW the terms and conditions of their contracts, during periods of crisis. As a general rule, this will apply only to those services functions that have been specifically identified as essential contractor services by the functional commander or civilian equivalent.

(B) Contractors who provide Government determined essential contractor services shall provide a written plan to be incorporated in the contract to ensure the continuation of these services in crisis situations. COs will consult with a functional manager to assess the sufficiency of the contractor-provided written plan. Contractors shall activate such plans only during periods of crisis, as authorized by the CO, who does so at the direction of the appropriate functional command or civilian equivalent. And aforementioned Air Force implementation, unless otherwise directed by an authorized Government representative, it is determined that Refuse collection requirements under this Performance-Based Work Statement are essential to be

performed during a crisis. The CO will notify the contractor of any changes to the hours of operation or procedures. The contractor shall only be permitted to bring empty trucks on base.

4.6. CONTRACTOR WORK SCHEDULE

4.6.1. Schedule Submission and Approval. The Contractor shall submit a schedule for all services described in this PWS and Appendices to the CO for approval at the post-award conference. The schedule shall include routes, pickup points, times, and days that pickups will occur. The Contractor shall not deviate from the approved schedule without prior approval from the CO or COR. Permanent changes to the schedule shall be submitted 10 days before implementation and receive CO approval before the Government will allow the proposed changes. The schedule shall be submitted electronically using a file format compatible with Government software.

4.6.2. Schedule Changes. Occurrence based (non-permanent) schedule changes due to customer requests or base exercises shall be submitted to the COR and do not require CO approval.

4.7. CONTRACT PERSONNEL

4.7.1. Contract Manager. The contractor shall establish and maintain an office through which the contract manager or alternate(s) can be contacted during work hours. The contract manager or alternate shall be available during normal duty hours to meet on the installation within 1 hour with the government personnel designated by the CO to discuss problem areas. The contractor shall provide the CO telephone number(s) where validation results and complaints can be reported. The contractor shall also provide to the CO the names and phone numbers of contractor POCs for after business hours including nights, weekends, and holidays. This information shall be kept updated by the contractor whenever personnel changes occur. The contract manager or alternate shall have full authority to act for the contractor on all contract matters relating to the daily operation of this contract.

4.7.2. Personnel. Contractor personnel shall present a neat appearance. Contractor personnel shall be easily recognizable while on the installation in conjunction with this contract. This shall be accomplished through the wear of distinctive clothing, overcoats, or hats, bearing the company name or logo. The coloring or design of the items selected should be such that identifies personnel easily and quickly for reasons of safety and personal protection.

4.7.2.1. The contractor shall provide a contract manager who shall be responsible for the performance of the work. The contract manager and alternate(s) shall be able to read, write, speak, and understand English. The name of the manager and alternate(s), who shall act for the contractor when the manager is absent, shall be designated in writing to the CO prior to the contract start date. These persons may be contacted outside of normal duty hours. Changes to personnel shall be submitted to the Government at least five (5) workdays before the changes.

4.7.2.2. The contract manager shall have full authority to act for the contractor on the installation. The contract manager shall meet as necessary with government personnel designated by the CO to discuss problem areas. The contract manager or alternate shall be on

site during normal duty hours and contingencies requiring work beyond normal duty hours. The contractor's phone shall be monitored during normal duty hours. After normal duty hours, the manager or designated alternate shall be available within one hour.

4.7.2.3. The contractor manager and alternate(s) shall be required to have a cell phone with local phone numbers and supply the phone numbers to the government at the start of the contract and when any changes occur. Contractor shall have computers with internet service and local and head office email addresses. The contractor shall arrange and pay for all telephone, fax and email services.

4.7.2.3.1. Radio equipped vehicles or equipment shall comply with base frequency regulations. Radio frequencies used by the contractor shall not interfere with any base function communications.

4.7.3. Employee Restrictions. The government is authorized to restrict employment under the contract of any contractor employee or prospective contractor employee who is identified as a potential threat to the health, safety, security, general well-being, or operational mission of the installation and its population.

4.7.3.1 Contractor Employees. The selection, assignment, and management of contractor employees is the responsibility of the contractor; however, the contractor shall not employ any individual who is identified as a potential threat to the health, safety, security, and general well-being, or operation of the installation's mission or personnel. The contractor is fully responsible for all contractor employee performance and conduct at all times. The contractor shall not allow any employee to perform work under this contract while under the influence of alcohol, drugs, or any other incapacitating agent. Contractor personnel shall present a neat appearance and be easily recognized as contractor employees. This shall be accomplished by the wearing of distinctive clothing bearing the name of the company or by possessing the appropriate badges containing the company's name and employee picture.

4.8. Contractor Manpower Reporting Application (eCMRA). The Contractor shall report ALL contractor labor hours (including subcontractor labor hours) required for performance of services provided under this contract for "U.S. Air Force" via the secure data collection site (i.e. Contract Manpower Reporting Application). The contractor is required to completely fill in all required data fields using the following web address <http://www.ecmra.mil>. Reporting inputs shall be for the labor executed during the period of performance of October 1 through September 30, the Government fiscal year (FY). While inputs may be reported any time during the FY, all data shall be reported no later than October 31 of each calendar year. Contractors may direct questions to the electronic Contractor Manpower Reporting Application (eCMRA) help desk.

4.9. SECURITY REQUIREMENTS. Contractor employees shall comply with all Hill AFB and Little Mountain Test Annex security requirements imposed by the Installation Commander at all times while on Hill AFB and Little Mountain Test Annex premises. The Contractor shall obtain all necessary passes, decals, badges, or other items required for access to perform contract services at Hill AFB and Little Mountain Test Annex. The Contractor is responsible for accountability of all such media, which shall be surrendered to the Security Forces Squadron Pass and Registration Section upon completion or termination of the contract or upon

termination of an individual's employment for the Contractor. The Contractor shall comply with all Hill AFB and Little Mountain Test Annex policies regarding entry to the installation, rules of the road, contingency operations compliance, and photography prohibitions. Contractor employees are authorized entry to the installation for the purpose of work under this contract only and are not authorized in other facilities or areas without prior government authorization. Due to safety/security requirements, Contractor personnel shall be required to *fluently* speak, comprehend, read, and write English.

4.9.1. Base Access. *The Contractor must be aware that entry requirements are subject to change due to installation and world situations. All employees may be subject to a background check through the FBI for base access.*

4.9.2. Main Base Access. Current security access restrictions at Hill AFB North Gate require all contractor vehicles (which are the size of a standard bread delivery truck or larger), such as front loader and roll off vehicles, to enter through the North Gate only. Contractor vehicles may be subject to search prior to gaining base entry. The Contractor should plan and allow for delays as a result of increased and ever-changing security procedures.

4.9.3. Security Manager. Upon contract award, the Contractor shall designate, in writing to the CO, a Security Manager who shall be the Contractor's point of contact for all security matters. Within 5 working days of contract award, the Contractor's Security Manager shall contact the Civil Engineer Squadron (CES) Security Manager for assistance on accomplishing Contractor personnel security requirements.

4.9.3.1. Security Training. Contractor personnel are required to attend security and OPSEC orientation under Homeland Security Presidential Directive (HSPD) Title 12. The Contractor shall schedule initial and annual refresher training (for all assigned contractor personnel) through the CES Security Manager. All contractor personnel shall be thoroughly briefed by the CES Security Manager on established security requirements and procedures as stipulated in Air Force Policy Directive (AFPD 31-1, Integrated Defense).

4.9.3.2. Security Authority. The Contractor shall brief all employees that they shall *immediately leave any area* upon notification by the CO, COR, constituted authority, Security Forces, or when directed as occasional operational requirements, real world activities, or emergencies dictate.

4.9.4. Restricted/Controlled Areas. Contractor performance within restricted/controlled areas shall require Contractor compliance with various levels of security and established personnel security entry control procedures. The Contractor shall ensure all contractor employees performing services in secured areas are processed for a controlled area, limited access, or visitor badge by the Entry Controller of the restricted/controlled area.

4.9.4.1. Access Coordination. The facility manager/user/occupant/requester will be responsible for *providing* access, escorts, or temporary visitor access badges for contractor personnel while performing ISWM duties. The Contractor shall be responsible for *scheduling* access/escorts/badges by contacting the facility manager/requester at the Entry Control Point of the restricted/controlled area.

4.9.4.2. Escorts. At all times while in restricted/controlled areas, contractor employees shall be under direct surveillance of a person from that facility who is cleared to wear a controlled area badge and perform escort duties. Visitor badges shall be returned to the Entry Controller each time the employee completes the duties and leaves the area. This requirement is waived for contractor personnel who have unescorted access privileges and display a controlled area badge for the restricted/controlled areas.

4.9.5. Employee Background Checks. All Contractor employees who do not have a current security investigation acceptable to the Security Forces, and who require a National Agency Check (NAC) for the performance of their duties, shall complete an Electronic Personnel Security Questionnaire (EPSQ), SF 85P, Questionnaire for Public Trust Positions, in three copies (original and two photocopies); and an AF Form 2583, Request for Personnel Security Action. For all employees requiring local area network (LAN) access (if applicable), the Contractor shall submit the following information: full name, date and place of birth, social security account number, affirmation of United States citizenship, and any current security investigation data. Information shall be in writing, on company letterhead, and submitted to Security Forces through the CES Security Manager.

4.9.5.1. Pre-approval Coordination. The CES Security Manager is the source for the necessary forms and will provide instructions for receiving, preparing, and processing these forms. The Contractor shall coordinate with all required facilities to process all necessary paperwork. After forms have been properly completed, the CES Security Manager will provide information to make an appointment for contractor employee(s) to go to the Security Forces for submittal of paperwork and fingerprinting. Appointments will be scheduled within two weeks of request.

4.9.5.2. Badge Issuance. A minimum of 180 days is required to process contractor employee NACs. Additional time will be required if the NAC is unfavorable and may result in denial of entry to restricted/controlled areas or denial of base LAN access. The CES Security Manager will notify the Contractor of any NAC results. After completion of a favorable NAC, each eligible employee shall report to the CES Security Manager for processing of AF Form 2586, Unescorted Entry Authorization Certificate. The CES Security Manager will schedule appointments for issuance of badges.

4.9.5.3. Access Revocation. The Hill AFB and Little Mountain Test Annex Installation Commander reserves the right to deny restricted area entry to any contractor employee whose NAC is unfavorable, and the right to terminate the entry of any employee upon disclosure of information indicating the individual's continued entry to a secure area is not in the best interest of national security.

4.9.5.4. Badge Validity. Controlled area badges will be valid only for the actual period of employment or the term of the contract, whichever occurs first. Contractor employees shall display the controlled area badge on their outer garment above waist level, and shall, upon request, surrender the badge to any DoD member for identification verification. Violations or deviations from established security procedures by contractor employees may result in confiscation of controlled area badges and denial of future entry to restricted areas.

4.9.5.5. Contract Personnel Requirements. The Contractor shall not employ persons for work on this contract who are identified to the Contractor by the CO as a potential threat to the health, safety, security, general well-being, or operational mission of the installation and its population.

4.9.6. Contractor Vehicles. Contractor vehicles shall be maintained in a safe and operational condition at all times while on Hill AFB and Little Mountain Test Annex.

4.9.7. For Official Use Only (FOUO). The contractor shall comply with DoD 5400-7-R, DoD Freedom of Information Act (FOIA) Program requirements. This regulation sets policy and procedures for the disclosure of records to the public and for marking, handling, transmitting, and safeguarding FOUO material.

4.9.8. Reporting Requirements. Contractor personnel shall report to an appropriate authority any information or circumstances of which they are aware may pose a threat to the security or well-being of DoD personnel, contractor personnel, resources, and classified or unclassified defense information.

4.9.9. Physical Security. The contractor shall be responsible for safeguarding all government property and controlled forms provided for contractor use. At the end of each work period, all government facilities, equipment, and materials shall be secured. All contractor vehicles are required to enter the base through the North Gate located on the North West side of the base. Time to enter the base may be longer during higher traffic hours or higher FPCON's. Security Forces may require all contractor vehicles exit the base through the North gate.

4.9.10. Key/Access Card Control. The contractor shall establish and implement methods of making sure all keys/combinations/access cards issued to the contractor by the government are not lost, misplaced, duplicated, or used by unauthorized persons, and are secured when not in use. The contractor shall not duplicate any keys issued by the government. The contractor shall immediately report to the COR or CO any occurrences of lost, misplaced, or duplicated keys. In the event keys other than master keys are lost, misplaced, or duplicated, the contractor may be required, upon written direction of the CO, to re-key or replace the affected lock or locks without cost to the government. The government may, however, at its option, replace the affected lock or locks or perform re-keying and deduct the cost of such from the monthly payment due the contractor. In the event a master key is lost, misplaced, or duplicated, the government will replace all locks and keys for that system, and the total cost will be deducted from the monthly payment due the contractor.

4.10. SAFETY REQUIREMENTS AND REPORTS. The contractor shall perform work in a safe manner as required by OSHA, Safety and Health Requirements. Provide a verbal report to the CO as soon as possible of each occurrence of damage to Government property or an accident resulting in death, injury, occupational disease, or adverse environmental impact. Provide a completed copy of required Accident Investigation Reports to the CO within five calendar days of each occurrence. Additionally, it is the intent of this Installation to implement Voluntary Protection Program (VPP). Detailed information on VPP is available on the OSHA website at

<http://www.osha.gov/dcsp/vpp/index.html>. Additional safety requirements shall be performed IAW Appendix F.

4.10.1 Voluntary Protection Plan (VPP) Hill AFB and Little Mountain Test Annex is in the process of pursuing VPP recognition and/or has already been recognized under the Occupational Safety and Health Act (OSHA) Voluntary Protection Plan (VPP) impacting all “applicable contractors” meaning they are working on Hill AFB and Little Mountain Test Annex for a minimum of one thousand hours in three months under the same contract. It is the contractor’s responsibility to ensure its employees and managers have a comprehensive understanding of VPP as well as full compliance with OSHA requirements. The contractor shall follow all safety and health rules of the installation. Detailed information on VPP is available on the OSHA website at <http://www.osha.gov/dcsp/vpp/index.html>.

All requirements as specified in Appendix F shall apply to the contractor and any and all subcontractors performing work under this contract. The contractor shall provide a verbal report to the CO/COR within four (4) hours for each occurrence of damage to Government property or an accident resulting in death, injury, occupational disease, or adverse environmental impact. Provide a completed copy of required Accident Investigation Reports to the CO within three (3) calendar days of each occurrence.

The Contractor shall provide their Total Case Incidence Rate (TCIR), their Days Away Restricted and/or Transfer case incident rate (DART) rates and their OSHA form 300 A annually to the CO and the COR for consolidation and submission as part of the installation’s annual VPP Safety and Health management report. TCIR and DART rates are due by the **15th of January of each year.**

The Contractor is responsible for compliance with the OSHA Public law 91-596. The Contractor shall submit a Safety and Health Plan and corresponding site safety checklist to the CO ten (10) work days after contract award date. The Contractor’s Health and Safety plan shall include appropriate measures to ensure the Contractor reacts promptly to investigate, correct and track alleged safety and health violations and uncontrolled hazards in the Contractor work area.

4.10.2. Contractor’s Safety and Health Plan. The Contractor’s Safety and Health Plan shall demonstrate a management commitment to employee and health.

4.10.2.1 In performing work under this contract on Hill AFB and Little Mountain Test Annex the Contractor shall provide a Safety and Health Plan with corresponding checklists to the CO and the COR which shall:

- (a) Identify the roles and responsibilities of the following individuals: management, supervisors, employees and safety coordinator.
- (b) Identify all applicable safety and health laws, rules and regulations listed in this PWS and the contract. When applicable laws, rules and regulations change during the term of this contract, the Contractor shall comply as the changes come into effect if it does not impact cost or delivery schedules or if a conflict does not arise in implementation of the new procedures. If any of these conditions occur, a written evaluation along with specific

backup data and estimated cost data for these changes which impact the Contractor's performance shall be provided to the Contracting Office *(CO) or the Administrative Contracting Office (ACO). The Contractor shall not incorporate these publication changes until approved by CO or ACO. In the event there is a conflict between two or more publications, the Contractor shall provide written evaluation along with specific backup data to the CO or ACO and the COR within ten (10) calendar days of knowledge of conflict. Resolution of the conflict will be provided by the CO or ACO to the Contractor.

- (c) Provide worksite hazard analysis to include base-line hazard identification and required control measures.
- (d) Provide job site analysis to include hazard of tasks required to control measures, identify employee safety and health training requirements, the documentation and documentation process.
- (e) Workplace inspection frequency to include identifying the individual conducting the inspections and shall include employee hazard reporting procedures.
- (f) Identify individual(s) responsible for corrective hazards, and shall identify first aid and injury procedures, procedures for accident investigation and reporting, identify emergency response procedures, and identify the process for tracking controlled hazards in Contractor work area.

4.10.2.2 The primary Contractor is responsible for establishing these requirements for all subcontractors who qualify as applicable contractors (see paragraph 4.10.1)

4.10.3. HEALTH AND SAFETY ON GOVERNMENT INSTALLATIONS

4.10.3.1. In performing work under this contract on a government installation, the Contractor shall:

- (a) Comply with the specific health and safety requirements established by this contract;
- (b) Comply with the health and safety rules of the government installation that concern related activities not directly addressed in this contract;
- (c) Take all reasonable steps and precautions to prevent accidents and preserve the health and safety of Contractor and government personnel in any way performing or meeting the performance of this contract; and
- (d) Take such additional immediate precautions as the CO may reasonably require for health and safety purposes.

4.10.3.2. Any violation of these health and safety rules and requirements, unless promptly corrected as directed by the CO, will be grounds for termination of this contract in accordance with the Default clause of this contract. Include a clause in all subcontracts to require subcontractors to comply with the safety provisions of this contract to include cooperation and assistance in accident/mishap reporting and investigation.

4.10.4. Emergency Evacuation Procedures. Contractor employees shall follow the direction of the government employees relating to emergency evacuation procedures, i.e. fire, tornado, bomb threats, etc. It is the responsibility of the Contractor to provide guidance and establish

procedures for responding to emergencies to their employees. It is the Contractor responsibility to account for their employees following an emergency evacuation.

4.11. SPECIAL QUALIFICATIONS.

4.11.1. Contractor/Employee Base Pass and Identification, Special Clearances and Vehicle Passes. The Contractor shall also comply with all requirements and procedures IAW FAR 5352.242-9000, Contractor Access to Air Force Installations. All documentation shall be submitted at the pre-performance conference. The contractor shall also comply with all requirements and procedures IAW EAFBI 31-101, Installation Access. The contractor shall ensure all employees requiring access to the installation to include all sites have completed all requirements and obtained authorization from the contracting office. All vehicles shall be operated IAW Base traffic rules and regulations. The Government reserves the right to limit or deny access to the installation as required. Base passes, identifications and vehicle passes shall be returned to the Hill AFB South Gate Visitors Center at the end of the last contract period (period of performance) and receive receipt of return.

4.11.1.1. With adequate notice, not less than 48 hours, escorts will be arranged and provided until controlled or restricted area badges are obtained and initial flight line driving training is completed (for new employees only).

4.11.1.2. The contractor shall ensure all contractor employees receive initial and recurring training IAW Hill Instruction 13-213 paragraph 1.1.2. All employees (including backup drivers) required to drive in the flight line area shall be familiar with local flight line rules, are required to complete all flight line driving training and testing requirements and shall possess a current AF Form 483 authorizing flight line driving. ***This requirement shall be completed prior to driving in the flight line area.***

4.11.1.3. At the start of the contract, and when otherwise directed, an Entry Authorization Letter (EAL) request with the names of each contractor personnel and their social security numbers will be provided to each restricted area for their approval.

4.11.2. Force Protection Requirements. In addition to the requirements of clause FAR 5352.242-9000 Contractor Access to Air Force Installations (Nov 2012), during performance of this contract the contractor is responsible for:

4.11.2.1. Complying with all applicable security conditions. At the post award conference, the government will provide the contractor guidance and appropriate instructions for force protection conditions (FPCON's).

4.11.2.2. Contractor shall adhere to local Force Protection requirements. Restricted access to the installation or to areas of the base may occur for a non-specific, limited amount of time without warning for physical security of the base. Vehicles are subject to inspection by the COR, Base Safety Office, and Security Forces.

4.11.3. Restricted Areas. Throughout the contract, certain areas/sites may be restricted or closed to contractor personnel. The contractor shall comply with requirements for entry to include signing in or securing an entry badge.

4.11.4. MSA Requirements. All visitors to a Munitions Storage Area (MSA) including those on a Visitor Access List (VAL) must have an Explosive Safety Certificate. The certificate is obtained by attending the Explosive Safety Awareness Training, which is conducted by the Weapons Safety Office in Bldg 180 Room 226 on Mondays at 1430 hours (On Tuesday if Monday is a holiday).

4.11.5. HERO Program Requirement. The 75 ABW Weapons Safety Office is the Office of Primary Responsibility for the Hazards of Electromagnetic Radiation to Ordnance (HERO) program. Modern Mobile Emitters (MMEs) are hazardous and degrade the integrity of Air Force Munitions. These devices include electronics that emit cellular and Wi-Fi antennas such as radios, smart watches, and computers. MMEs that are planned to be introduced into the Munitions Storage Area (fixed or mobile) must have a HERO Analysis conducted by the 75 ABW Weapons Safety Office IAW DAFI 91-208 Paragraph 5.5.5. Please contact the 75 ABW Weapons Safety Office at 777-7185 with any HERO requests.

4.11.6. Government and Personal Property. The contractor shall be responsible for safeguarding all Government property. The contractor shall conduct work so that property, personnel, and work areas shall be protected at all times from inconvenience, damage, or injury. In the event of damage of any nature, caused by contractor operations or employees, due to improper protection, precaution, or safety measures, such damages shall be repaired or replaced by the contractor at his expense.

4.12. Contracting Officer (CO) And Contracting Officer Representative (COR). (Quality Assurance Personnel - QAP)

The Contracting Officer will appoint a primary and alternate representative for management of the day-to-day activities of the contract. The identity, title, and authority of this representative will be provided in writing to the contractor after contract award. The following are the responsibilities of the CO and COR:

4.12.1. The COR is a representative for the CO and may be asked for assistance during the administration of this contract. Upon contract award, the identity of the COR(s), with a brief resume of their duties and authority will be promptly furnished to the successful bidder/offeree.

4.12.2. The COR(s) or alternate(s) will inform the contract manager when discrepancies occur and will request corrective action. The COR(s) or alternate(s) will make a notation of the discrepancy on their checklist with the date and time the discrepancy was noted and will request the contract manager (or authorized representative) to initial the entry on the checklist.

4.12.3. Any matter concerning a change to the scope, prices, terms or conditions of this contract shall be referred to the CO and not to the COR(s).

4.12.4. The services to be performed by the contractor during the period of this contract shall, at all times and places, be subject to review by the CO or authorized representative(s).

4.12.5. The COR and personnel from Base safety, fire department, flight line operations, security police and environmental management are empowered to issue a stop work order to the contractor in the event of an extreme emergency. If a stop work order causes a delay in work that permits an equitable adjustment, the CO shall be notified.

4.13. Multi-Functional Team. The Senior Leadership may require a multi-functional team to be established between the government and the contractor to ensure joint cooperation and a sound customer focus of all parties involved in the execution of this contract after contract award.

4.14. PARTNERING AGREEMENT

The CO may require a partnering agreement, or multi-functional team, between the Government and Contractor to facilitate joint cooperation and a sound partnership of all parties involved in the execution of this contract. Partnering is the creation of a Government-Contractor relationship that promotes achievement of mutually beneficial goals. It involves an agreement in principle to share the risk involved in completing the project and establishing and promoting a nurturing partnership environment. Representatives from each organization are encouraged to participate in developing a partnering agreement. The partnering agreement that results may be formal or informal. If formal, it should be reduced to writing and signed by the parties involved.

4.15. DAMAGES TO GOVERNMENT BUILDINGS, EQUIPMENT, OR VEGETATION

Damages to government buildings, equipment, or vegetation are addressed in FAR 52.237-2, Protection of Government Buildings, Equipment, and Vegetation.

4.16. TRANSITION PHASE. The new contractor will be allowed access to the facilities from the notification of contract award through 30 September 2026 to become completely familiar with the refuse removal requirements at Hill AFB and Little Mountain Test Annex. This is to familiarize supervisors and key personnel with work scheduling, procedures and to prepare the equipment. All necessary visits shall be coordinated through the COR. The contractor shall take all actions necessary for a smooth transition of the contracted operations. Contractor shall not interfere with ongoing performance of services. This phase shall be performed at no charge to the Government.

5. APPENDICES.

A. Estimated Workload Data

B. Tasks and Frequency Tables

C. Container Marking Instructions

D. Maps and/or Site Plans

E. Government Furnished Property/Services/Equipment

F. Safety, Fire Protection and Health Specification Industrial Safety Requirements

APPENDIX A

ESTIMATED WORKLOAD DATA

TABLE A-1

Estimated Data Refuse

ITEM/ CLIN REF	NAME	ANNUAL ESTIMATED QUANTITY	
X001	Municipal Solid Waste	<u>2697</u>	Tons
X002	Food Waste	<u>485</u>	Tons
X003	Recyclable Commodity – Paper	<u>0</u>	Tons
X003	Recyclable Commodity – Glass	<u>0</u>	Tons
X003	Recyclable Commodity – Plastic	<u>0</u>	Tons
X003	Recyclable Commodity – Cardboard	<u>435</u>	Tons
X008	Unscheduled Pickups	<u>50</u>	Each
X008	Special Event Container Placements	<u>40</u>	Each
X009	Construction and Demolition (C&D) Container Placements	<u>0</u>	Each
X009	Construction and Demolition (C&D) Debris	<u>0</u>	Tons
X010	Public / Common Use MSW Receptacles	<u>0</u>	Each
X011	Public / Common Use Recycling Receptacles	<u>0</u>	Each
X012	Ash	<u>0</u>	Tons
X013	Additional Pickups	<u>10</u>	Each
X014	Container Relocations	<u>30</u>	Each
X016	Compostable Organics (Yard and Wood Waste)	<u>550</u>	Tons
X017	Container Maintenance	<u>714</u>	Each
X017	Compactor Maintenance	<u>3</u>	Each
X017	Baler Maintenance	<u>0</u>	Each
		ONE WAY	
	Distance To Disposal / Incinerator Site	<u>12</u>	Miles
	Distance To Recyclable Processing Center	<u>12</u>	Miles

TABLE A-2

Historical Data FY22 – FY25

Refuse
(Listed in tons)

	OCT	NOV	DEC	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	TOTAL
Commercial													
FY22	182.14	163.91	180.20	165.86	162.24	138.87	190.46	194.72	198.64	169.56	207.95	197.99	2,152.54
FY23	192.87	185.74	199.58	193.85	178.07	226.00	202.31	211.26	201.76	180.15	215.99	201.30	2,388.88
FY24	193.27	184.35	183.47	188.91	181.77	196.05	198.05	224.30	177.89	201.83	209.26	181.90	2,321.05
FY25	206.10	188.54	202.34	172.79	199.51	221.86	214.76	232.28	199.30	202.60	211.98	192.99	2,445.05
Roll-off													
FY22	84.46	119.23	78.11	115.63	108.93	148.75	154.67	145.28	122.70	154.17	131.18	93.86	1,456.97
FY23	105.60	115.43	74.90	83.24	69.03	106.61	99.86	114.51	105.58	120.88	150.74	112.58	1,258.96
FY24	109.10	108.54	75.33	80.81	81.06	88.70	100.36	119.78	98.63	90.62	121.32	90.17	1,164.42
FY25	97.34	65.63	92.49	89.44	100.38	125.70	100.24	90.97	83.20	86.56	114.16	135.71	1,181.82
Compactor													
FY22	8.25	13.84	11.94	7.84	7.84	6.91	6.77	8.41	10.95	8.16	20.86	9.76	121.53
FY23	7.75	16.20	8.56	13.16	9.64	14.02	19.54	9.21	9.21	7.94	10.80	13.87	139.90
FY24	14.47	12.17	9.58	11.85	8.73	13.84	8.95	12.16	9.33	11.82	10.03	18.94	141.87
FY25	18.50	10.39	15.32	14.19	11.79	14.09	12.32	13.85	9.48	15.50	9.14	9.94	154.51
Recycle													
FY22	40.34	33.70	38.89	36.93	28.52	24.78	36.82	36.80	34.97	34.88	37.83	33.88	418.34
FY23	34.31	29.17	38.49	44.53	34.33	47.42	40.65	40.11	33.83	37.60	40.44	37.58	458.46
FY24	38.67	32.91	38.58	47.13	38.75	41.19	35.18	37.38	30.94	30.84	34.32	29.73	435.62
FY25	35.09	32.16	35.45	46.29	32.76	45.96	30.53	36.10	30.58	31.85	38.02	37.07	431.86

TABLE A-3

TASKS & ESTIMATED FREQUENCY

REFUSE COLLECTION STATIONS & FREQUENCY

Note: ALL containers are 6 Cubic Yards unless otherwise designated in the “nomenclature-description” below. Additionally, food waste and sawdust containers will be designated. The nomenclature listed may be added to or subtracted from based on the needs of the Government. NOTE: LB = lock bar, new dumpsters highlighted.

Note: The government recommends that the contractor maintain at least 2% additional inventory of refuse containers for special events.

Bldg. #	Nomenclature-Description	Location	SIZE	Frequency	Can #	Monday	Tuesday	Wednesday	Thursday	Friday
1		S.E. corner	6	2 x wk	400	6		6		
1		S.E. corner	6	2 x wk	401	6		6		
1 LB	Flight line	1A	6	2 x wk	402		6			6
5		Bay A/B, NE Corner	6	2 x wk	403	6		6		
5		Bay C, East side	6	2 x wk	404	6		6		
5		Bay H/U, North Side	6	2 x wk	405	6		6		
5		Bay K, West Side	6	2 x wk	406	6		6		
5		Bays M/N/P, SW Corner	6	2 x wk	407	6		6		
8 LB	Flight line	NW Corner	6	1 x wk	408					6
12		NW corner	6	2 x wk	409	6		6		
21		South Side	6	2 x wk	410	6		6		
23	New Fire Dept	South Side	6	2 x wk	411		6			6
30	Metal Shop	NW corner	6	2 x wk	412	6		6		
37 LB	Flight line	East side	6	2 x wk	413		6			6
37 LB	Flight line	East side	6	2 x wk	414		6			6
37 LB	Flight line	East side	6	2 x wk	415		6			6

39 LB	Flight line	West side	6	2 x wk	416		6			6
39 LB	Flight line	West side	6	2 x wk	417		6			6
39 LB	Flight line	East side	6	2 x wk	418		6			6
48 LB	Flight line	West side	6	2 x wk	419		6			6
50 LB	Flight line	West side	6	2 x wk	420		6			6
50 LB	Flight line	West side	6	2 x wk	421		6			6
50 LB	Flight line	West side	6	2 x wk	422		6			6
50 LB	Flight line	West side	6	2 x wk	423		6			6
100		North Side	6	2 x wk	424	6		6		
100		North Side	6	2 x wk	425	6		6		
100		Bay O, SW Corner	6	2 x wk	426	6		6		
100		Bay O, SW Corner	6	2 x wk	427	6		6		
100		Bay F, SE Corner	6	2 x wk	428	6		6		
100		Across street, SE Corner	6	2 x wk	429	6		6		
118/119		SE Corner	6	2 x wk	430	6		6		
150		North side	6	2 x wk	431	6		6		
150		North side	6	2 x wk	432	6		6		
150		West Side	6	2 x wk	433	6		6		
180		SE Corner pk lot	6	2 x wk	434	6		6		
204 LB		SE Corner	6	2 x wk	435		6			6
205		SE Corner	6	2 x wk	436	6		6		
220 LB		NW Corner	6	2 x wk	437		6			6
220 LB		SW side	6	2 x wk	438		6			6
220 LB		South Side	6	2 x wk	439		6			6
225 LB		North side	6	2 x wk	440		6			6
225 LB		North side	6	2 x wk	441		6			6
225 LB		North side	6	2 x wk	442		6			6
225 LB		North side	6	2 x wk	443		6			6

225 LB		Inside	6	2 x wk	444		6			6
225 LB		Inside	6	2 x wk	445		6			6
225 LB		Inside	6	2 x wk	446		6			6
225 LB		Inside	6	2 x wk	447		6			6
225 LB		East side	6	2 x wk	448		6			6
225 LB		SE side	6	2 x wk	449		6			6
TAMS LB		Southwest Corner	6	2 x wk	450		6			6
230	Dunkin Donuts	SW Corner	6	2 x wk	451	6		6		
230		SW Corner pk lot	6	2 x wk	452	6		6		
233 LB		North side	6	2 x wk	453		6			6
233 LB		West side	6	2 x wk	454		6			6
238		NW Corner	6	2 x wk	455	6		6		
238		NW Corner	6	2 x wk	456	6		6		
238		North Side	6	2 x wk	457	6		6		
238		North Side	6	2 x wk	458	6		6		
243/245		SE Corner	6	2 x wk	459	6		6		
249	OCC Medicine SVC	NW Corner	6	2 x wk	460	6		6		
250	Tech TNG Lab/SHP	SW Corner	6	2 x wk	461	6		6		
250	Tech TNG Lab/SHP	SW Corner	6	2 x wk	462	6		6		
256/257 LB	Hazard Disp Facility	Between Buildings	6	2 x wk	463		6			6
256/257 LB	Hazard Disp Facility	Between Buildings	6	2 x wk	464		6			6
257 SW LB	Hazard Disp Facility		6	2 x wk	465		6			6
257 SE LB	Hazard Disp Facility	Behind fence	6	ON CALL	466					6
260 LB	HTG Facility Bldg	West side	6	2 x wk	467		6			6
260 LB	HTG Facility Bldg	West side	6	2 x wk	468		6			6
265 LB	Sheet Metal	South East	6	2 x wk	469		6			6
265 LB	Sheet Metal	South East	6	2 x wk	470		6			6
265 LB	Sheet Metal	North West	6	2 x wk	471		6			6
265 LB	Sheet Metal	North West	6	2 x wk	472		6			6

269 LB		North	6	2 x wk	473		6			6
269 LB		North West	6	2 x wk	474		6			6
269 LB		South East	6	2 x wk	475		6			6
270 LB	HG, Maint. Dept	NW Corner	6	2 x wk	476		6			6
279 LB	Mat Process, Dep	West side	6	2 x wk	477		6			6
295 LB		West	6	2 x wk	478		6			6
341	Dorm	North Side	6	3 x wk	479	6		6		6
344	Postal and SC	East	6	2 x wk	480	6		6		
345	Dorm AM PP/PCS-STD	NE corner	6	3 x wk	481	6		6		6
346	Dorm	South Side	6	3 x wk	482	6		6		6
350	Dorm VAQ	East Side	6	3 x wk	483	6		6		6
351	Dorm VAQ - OVER HEAD	North Side	6	3 x wk	484	6		6		6
358	Lounge, Dayroom	North Side	6	3 x wk	485	6		6		6
358	Lounge, Dayroom	North Side	6	3 x wk	486	6		6		6
361	Lounge, Dayroom	North Side	6	3 x wk	487	6		6		6
364	Lounge, Dayroom	South Side	6	3 x wk	488	6		6		6
365	Dorm	North Side	6	3 x wk	489	6		6		6
366	Army Corps Engr	South Side	6	2 x wk	490	6		6		
366	Army Corps Engr	South Side	6	2 x wk	491	6		6		
400	Commissary	East Side	6	2 x wk	492		6			6
401	Veterinary clinic	East Side	6	2 x wk	493	6		6		
402		SW Corner	6	2 x wk	494	6		6		

408	Security Forces	NE Corner	6	2 x wk	495	6		6		
412	BX	North Side	6	2 x wk	496	6		6		
412	BX	North Side	6	2 x wk	497	6		6		
412	BX	North Side	6	2 x wk	498	6		6		
414	Base Supply Store	NW Corner	6	2 x wk	499	6		6		
416	POV Wash Shack	NW End	6	2 x wk	500	6		6		
418 LB	Burger King	East Side	6	3 x wk	501	6		6		6
420	Mini Mall	NE Corner	6	2 x wk	502	6		6		
420	Mini Mall	NW Corner	6	2 x wk	503	6		6		
430		NE Corner	6	2 x wk	504	6		6		
431/441	Theater	NW Corner	6	2 x wk	505	6		6		
445	Chapel	West Side	6	2 x wk	506	6		6		
445	Chapel	West Side	6	2 x wk	507	6		6		
450	Club Hill	North Side	6	2 x wk	508	6		6		
450	Club Hill	North Side	6	2 x wk	509	6		6		
460		Southwest	6	2 x wk	510	6		6		
464	Child Development Center	North Side	6	3 x wk	511	6		6		6
472	TLF	NW Corner	6	3 x wk	512	6		6		6
480	VOQ	South Side	6	3 x wk	513	6		6		6
503 LB	Whse Sup Equip Dep	NW Corner	6	2 x wk	514		6			6
503 LB	Whse Sup Equip Dep	NE Corner	6	2 x wk	515		6			6
503 LB	Whse Sup Equip Dep	East Side	6	2 x wk	516		6			6
505 LB	Ship ACFT	NE Corner	6	2 x wk	517		6			6
505 LB	Ship ACFT	SE Corner	6	2 x wk	518		6			6

505 LB	Ship ACFT	SE Corner	6	2 x wk	519		6			6
507 LB	E-C Land Gear	NW Corner	6	2 x wk	520		6			6
507 LB	E-C Land Gear	West Side	6	2 x wk	521		6			6
507 LB	E-C Land Gear	West Side	6	2 x wk	522		6			6
507 LB	E-C Land	SW Middle	6	2 x wk	523		6			6
507 LB	E-C Land Gear (Door 5)	SW Corner	6	2 x wk	524		6			6
507 LB	E-C Land Gear (Door 8WC)	SW Corner	6	2 x wk	525		6			6
507 LB	E-C Land Gear (Door 8WC)	SW Corner	6	2 x wk	526		6			6
507 LB	E-C Land Gear	SE Side	6	2 x wk	527		6			6
507 LB	E-C Land Gear	East Side	6	2 x wk	528		6			6
508	Civilian Personnel	West Side	6	2 x wk	529	6		6		
510 LB	Aircraft & Engine	North Side	6	2 x wk	530		6			6
510 LB	Aircraft & Engine	SE Corner	6	2 x wk	531		6			6
511 LB	Aircraft & Engine	SW Corner	6	2 x wk	532		6			6
513	419 FW	SE Corner	6	2 x wk	533	6		6		
513	419 FW	NW Corner	6	2 x wk	534	6		6		
514 LB	Refuel Vehicle	South Side	6	2 x wk	535		6			6
515/516 LB	Aero Engineering	NW Corner	6	2 x wk	536		6			6
518		South Side	6	2 x wk	537	6		6		
519 LB	Dining Hall (Food Waste)	South Side	8	2 x wk	538	8		8		8
519 LB	Dining Hall (Food Waste)	South Side	8	2 x wk	539	8		8		8
520	Gymnasium	NW Corner	6	2 x wk	540	6		6		
520/533	Gymnasium	NE Corner	6	2 x wk	541	6		6		
521		West	6	2 x wk	542	6		6		
524	JR. enlisted advisory council	NW Corner	6	2 x wk	543	6		6		
525	Bowling Alley	North Side	6	2 x wk	544	6		6		

534	Hobby Shop	North Side	6	2 x wk	545	6		6		
542	So. Gate Visitors center	South Side	6	2 x wk	546	6		6		
544	FAM Camp Latr/Laundry	SW Corner	6	3 x wk	547	6		6		6
545	Includes 546 & 547	South Side	6	2 x wk	548	6		6		
558 LB	75 CEG/IWTP	South Side	6	2 x wk	549		6			6
562		Southeast	6	3 x wk	550	6		6		6
562		Southeast	6	3 x wk	551	6		6		6
564	Centennial Park (seasonal)	NE Corner	6	3 x wk	552	6		6		6
564	Centennial Park (seasonal)	NE Corner	6	3 x wk	553	6		6		6
567 LB		NW corner	6	2 x wk	554		6			6
567 LB		NW corner	6	2 x wk	555		6			6
570	Hospital	SW Corner	6	2 x wk	556	6		6		
570	Hospital	SW Corner	6	2 x wk	557	6		6		
570	Hospital (they pull out)	SW Corner	6	2 x wk	558	6		6		
583		SW corner	6	2 x wk	559	6		6		
586		NE Corner	6	2 x wk	560	6		6		
589		East (across street)	6	2 x wk	561	6		6		
590 LB		SW Corner	6	2 x wk	562		6			6
590 LB		SW Corner	6	2 x wk	563		6			6
592 LB		NW Side	6	2 x wk	564		6			6
593		SW Corner	6	2 x wk	565	6		6		
597		SE Corner	6	2 x wk	566	6		6		
640 LB		West Side	6	2 x wk	567		6			6

674 LB		North Side	6	2 x wk	568		6			6
674 LB		North Side	6	2 x wk	569		6			6
674 LB		North Side	6	2 x wk	570		6			6
680 LB	309 AMXG	North	6	2 x wk	571		6			6
680 LB	309 AMXG	West Side	6	2 x wk	572		6			6
680 LB	309 AMXG	West Side	6	2 x wk	573		6			6
688 LB	F-22	SW	6	2 x wk	574	6		6		
688 LB	F-22	SW	6	2 x wk	575	6		6		
694 LB	Fire Department	South	6	2 x wk	576	6		6		
708 LB	Golf Midway House	South Side	6	2 x wk	577	6		6		
710 LB	Golf Maintenance	SW Corner	6	2 x wk	578	6		6		
721 LB	Golf Clubhouse/Equip	East Side	6	2 x wk	579	6		6		
721 LB	Golf Clubhouse/Equip	East Side	6	2 x wk	580	6		6		
732 LB		West Side	6	2 x wk	581	6		6		
735 LB	Borta - Combat Training	West Side	6	2 x wk	582	6		6		
735 LB	Borta - Combat Training	West Side	6	2 x wk	583	6		6		
735 LB	Borta - Combat Training	West Side	6	2 x wk	584	6		6		
741 LB	SFS Outdoor Range	NW Corner	6	2 x wk	585	6		6		
746 LB	They Bring Out	South	6	2 x wk	586	6		6		
748 LB	649 CLSS	West Side	6	2 x wk	587	6		6		
748 LB	649 CLSS	West Side	6	2 x wk	588	6		6		
748 LB	649 CLSS	West Side	6	2 x wk	589	6		6		
749 LB	CEV	SW Corner	6	2 x wk	590	6		6		
751 LB	SHP INSTM OVHL Dept.	SE Corner	6	2 x wk	591	6		6		

754 LB	Bldg WTR SUP	SE Corner	6	2 x wk	592	6		6		
762 LB	Bldg WTR SUP	NE Side	6	2 x wk	593	6		6		
772 LB	Park Ranger	SE Corner	6	2 x wk	594	6		6		
777 LB	Readiness, CRW	East Side	6	2 x wk	595	6		6		
798 LB	AFCS Maint FCLTY	West Side	6	2 x wk	596	6		6		
801	Recycle Center	East Side	6	3 x wk	597	6		6		6
802		East Side	6	2 x wk	598	6		6		
804	Log Cabin	North Side	6	2 x wk	599	6		6		
805	MWR Outdoor Storage	NE Corner	6	2 x wk	600	6		6		
822		SE Corner	6	2 x wk	601	6		6		
841	Thrift Store	SW Corner	6	2 x wk	602	6		6		
843	Whse Sup Equip Dep - Prk lot	NW Corner	6	2 x wk	603	6		6		
843	Whse Sup Equip Dep - Prk lot	NW Corner	6	2 x wk	604	6		6		
843	Whse Sup Equip Dep - Bay G/H	North Side	6	2 x wk	605	6		6		
843	Whse Sup Equip Dep - Bay G/H	NE Corner	6	2 x wk	606	6		6		
843		SE Corner	6	2 x wk	607	6		6		
845	Bay A (Prk lot)	NE Side	6	2 x wk	608	6		6		
845	Bay B (Prk lot)	NE Side	6	2 x wk	609	6		6		
845	Bay D (Prk lot)	North Side	6	2 x wk	610	6		6		
845	Bay D (Prk lot)	North Side	6	2 x wk	611	6		6		
845	Bay D (Prk lot)	North Side	6	2 x wk	612	6		6		
845	Bay G (Prk lot)	NW Side	6	2 x wk	613	6		6		
845	Inside	North Side	6	2 x wk	614	6		6		
845	Inside	North Side	6	2 x wk	615	6		6		
845	Bay G (Dock)	South Side	6	2 x wk	616	6		6		
845	Bay H (Prk lot)	NW Side	6	2 x wk	617	6		6		

847	Prod, GM	SW Corner	6	2 x wk	618		6		6
847	Prod, GM	SW Corner	6	2 x wk	619		6		6
847	Prod, GM	SE Corner	6	2 x wk	620		6		6
847	Prod, GM	SE Corner	6	2 x wk	621		6		6
847	Prod, GM	South Side (Inside)	6	2 x wk	622		6		6
849	Mat Process, Dept.	North Side	6	2 x wk	623	6		6	
849	Mat Process, Dept.	SE Corner	6	2 x wk	624	6		6	
849	Mat Process, Dept.	SE Corner	6	2 x wk	625	6		6	
849	Mat Process, Dept. (prk Lot)	South Side	6	2 x wk	626	6		6	
849	Mat Process, Dept. (prk Lot)	South Side	6	2 x wk	627	6		6	
849	Mat Process, Dept. (prk Lot)	South Side	6	2 x wk	628	6		6	
849	Mat Process, Dept. (prk Lot)	South Side	6	2 x wk	629	6		6	
850	Bay A	East	6	2 x wk	630	6		6	
850	Bay A	South	6	2 x wk	631	6		6	
850	Bay D	SW Corner	6	2 x wk	632	6		6	
850	Bay D	SW Corner	6	2 x wk	633	6		6	
850	Bay D	SW Corner	6	2 x wk	634	6		6	
850	Bay D	SW Corner	6	2 x wk	635	6		6	
850	Bay E	South	6	2 x wk	636	6		6	
850	Bay F	South	6	2 x wk	637	6		6	
850	Bay G	South	6	2 x wk	638	6		6	
850	Bay G	SW Corner	6	2 x wk	639	6		6	
850	Bay C	Inside	6	2 x wk	640	6		6	
850	Bay D	Inside	6	2 x wk	641	6		6	
850	Bay D	Inside	6	2 x wk	642	6		6	
850	Bay E	Inside	6	2 x wk	643	6		6	
850	Bay E	Inside	6	2 x wk	644	6		6	
850	Bay E	Inside	6	2 x wk	645	6		6	
860	CE Maint. Shop	SE Corner	6	2 x wk	646	6		6	
883	Youth Center	North Side	6	2 x wk	647	6		6	
883	Youth Center	North Side	6	2 x wk	648	6		6	
891	DPI	SW Corner	6	2 x wk	649		6		6
891	DPI	SW Corner	6	2 x wk	650		6		6
891	DPI	SE Corner	6	2 x wk	651		6		6

891	DPI	SE Corner	6	2 x wk	652		6			6
893		NE Corner	6	2 x wk	653	6		6		
896		NE Corner	6	2 x wk	654	6		6		
900	TRML, Air Frt (Prk Lot)	SE Side	6	2 x wk	655	6		6		
900	TRML, Air Frt (bldg 903)	SW Side	6	2 x wk	656	6		6		
906 LB	388th	West Side	6	2 x wk	657		6			6
911	Shp, Refl Veh	NE Corner	6	2 x wk	658		6			6
915	Fuel Lab	NE Corner	6	2 x wk	659	6		6		
916	Snow Barn (Prk Lot)	West Side	6	2 x wk	660	6		6		
919	Composting Yard	North Side	6	2 x wk	661	6		6		
924	Gov Veh FL Stn	East Side	6	2 x wk	662	6		6		
927	Chenault St (Lot 3)	North Side	6	2 x wk	663	6		6		
928		NE Corner	6	2 x wk	664	6		6		
935	MSA-1	North Side	6	2 x wk	665		6			6
935	MSA-1	North Side	6	2 x wk	666		6			6
939	MSA-1	North Side	6	2 x wk	667		6			6
940	MSA-1	North Side	6	2 x wk	668		6			6
945	MSA-1	North Side	6	2 x wk	669		6			6
950	MSA-1	North Side	6	2 x wk	670		6			6
965	MSA-1	North Side	6	2 x wk	671		6			6
970	MSA-1	North Side	6	2 x wk	672		6			6

975	MSA-1	North Side	6	2 x wk	673		6			6
980	MSA-1	North Side	6	2 x wk	674		6			6
984	MSA-1	North side	6	2 x wk	675		6			6
985	MSA-1	West Side	6	2 x wk	676		6			6
988	MSA-1	North Side	6	2 x wk	677		6			6
991	MSA-1	South Side	6	2 x wk	678	6		6		
1102	OO-ALC Headqtrs (prk Lot)	Southeast	6	2 x wk	679	6		6		
1129		NE Parking	6	2 x wk	680	6		6		
1133	Vehicle Maint.	North Side	6	2 x wk	681	6		6		
1135	Vehicle Maint.	NE Corner	6	2 x wk	682	6		6		
1142	368 RSG	East Side	6	2 x wk	683	6		6		
1151	Fire Station 2	North Side	6	2 x wk	684	6		6		
1160	Med Supply Warehouse (DLA)	South East	6	2 x wk	685	6		6		
1160	Med Supply Warehouse (DLA)	West Side	6	2 x wk	686	6		6		
1160	Med Supply Warehouse (DLA)	SW Corner	6	2 x wk	687	6		6		
1160	Med Supply Wrhse (usamma)	NW Corner	6	2 x wk	688	6		6		
1201	Logistics Facility	NW Corner	6	2 x wk	689	6		6		
1206	Logistics Facility	SW Corner	6	2 x wk	690	6		6		
1207	Logistics Facility	NW Corner	6	2 x wk	691	6		6		
1208	Avionics/ Security can	SW Corner	6	2 x wk	692	6		6		
1210	West Gas Station	NW Corner	6	2 x wk	693	6		6		

1212	Logistics Facility	SE Corner	6	2 x wk	694	6		6		
1213	Logistics Facility	NE Corner	6	2 x wk	695	6		6		
1214	Logistics Facility	South Side	6	2 x wk	696	6		6		
1215	Logistics Facility	NE Corner	6	2 x wk	697	6		6		
1221	Logistics Facility	SE Corner	6	2 x wk	698	6		6		
1223	Logistics Facility	SW Corner	6	2 x wk	699	6		6		
1224	Logistics Facility	SW Corner	6	2 x wk	700	6		6		
1225	Logistics Facility	NW Corner	6	2 x wk	701	6		6		
1226	Logistics Facility	North Side	6	2 x wk	702	6		6		
1227	Logistics Facility	SW Corner	6	2 x wk	703	6		6		
1227	Logistics Facility	NE Corner	6	2 x wk	704	6		6		
1228	Logistics Facility	North Side	6	2 x wk	705	6		6		
1230		East Side	6	2 x wk	706	6		6		
1231	Logistics Facility	SW Corner	6	2 x wk	707	6		6		
1232	Logistics Facility	NW Corner	6	2 x wk	708	6		6		
1233	Logistics Facility	SW Corner	6	2 x wk	709	6		6		
1234	Logistics Facility	West Side	6	2 x wk	710	6		6		
1236	Logistics Facility	NW Corner	6	2 x wk	711	6		6		
1237	Logistics Facility	NW Corner	6	2 x wk	712	6		6		
1238		NW Corner	6	2 x wk	713	6		6		
1238		SE Corner	6	2 x wk	714	6		6		

1243	Vehicle Maint. Shed	East Side	6	2 x wk	715	6		6		
1244	Personnel	SE Corner	6	2 x wk	716	6		6		
1245	Personnel	SW Corner	6	2 x wk	717	6		6		
1246	Logistics Facility (across st.)	SE Corner	6	2 x wk	718	6		6		
1248	Control Center	NW Corner	6	2 x wk	719	6		6		
1248	Control Center	East Side	6	2 x wk	720	6		6		
1251	Vehicle Maint. Shop	SW Corner	6	2 x wk	721	6		6		
1253	Vehicle Maint. Shop	SW Corner	6	2 x wk	722	6		6		
1254	Logistics Facility	SW Corner	6	2 x wk	723	6		6		
1257	Logistics Facility Dep Ops	NE Corner	6	2 x wk	724	6		6		
1258	Logistics Facility (North)	SW Corner	6	2 x wk	725	6		6		
1258	Logistics Facility (North)	SW Corner	6	2 x wk	726	6		6		
1265	Shop MSL SVC	NE Corner	6	2 x wk	727	6		6		
1266	Shop MSL SVC	NE Corner	6	2 x wk	728	6		6		
1267	Photo Lab, BSE	NE Corner	6	2 x wk	729	6		6		
1268		NW Corner	6	2 x wk	730	6		6		
1269	TV Prod Fclty	NW Corner	6	2 x wk	731	6		6		
1274	Elct RSCH Eng	West Side	6	2 x wk	732	6		6		
1277	HQ Group	NW Corner	6	2 x wk	733	6		6		
1278	Law Center	SE Corner	6	2 x wk	734	6		6		
1279		SE Corner	6	2 x wk	735	6		6		

1283	SQ Ops	SE Corner	6	2 x wk	736	6		6		
1284		NW Corner	6	2 x wk	737	6		6		
1289		South Side	6	2 x wk	738	6		6		
1289		East Parking Lot	6	2 x wk	739	6		6		
1289	Horse Shoe Parking Lot	North Side	6	2 x wk	740	6		6		
1295	Logistics Facility	NE Corner	6	2 x wk	741	6		6		
1295	Logistics Facility	SE Corner	6	2 x wk	742	6		6		
1377	MSA-1	NE Corner	6	2 x wk	743		6			6
1377	MSA-1	NE Corner	6	2 x wk	744		6			6
1424	MSA-1	East Side	6	2 x wk	745		6			6
1424	MSA-1	East Side	6	2 x wk	746		6			6
1438	MSA-1	East Side	6	2 x wk	747		6			6
1477	MSA-1, 388 FW	West Side	6	2 x wk	748		6			6
1478	MSA-1	NE Corner	6	2 x wk	749		6			6
1511		NW Corner	6	2 x wk	750	6		6		
1513		SE Corner	6	2 x wk	751		6			6
1513		SE Corner	6	2 x wk	752		6			6
1515	Integr SPT Fclty	NE Corner	6	2 x wk	753		6			6
1515	Integr SPT Fclty	NE Corner	6	2 x wk	754		6			6
1515	Integr SPT Fclty	SE Corner	6	2 x wk	755		6			6
1515	Integr SPT Fclty	SE Corner	6	2 x wk	756		6			6
1530		SE Corner (Parking Lot)	6	2 x wk	757	6		6		
1531		NE Corner	6	2 x wk	758	6		6		
1538		East Side	6	2 x wk	759	6		6		

1540	Prod, GM	SE Corner	6	2 x wk	760	6		6		
1552	Russia House	West Side	6	2 x wk	761	6		6		
1590	Heat Operation Section	SW Corner	6	2 x wk	762	6		6		
1621	Log Fclty Dep Ops	SE Corner	6	2 x wk	763	6		6		
1621	Log Fclty Dep Ops	SE Corner	6	2 x wk	764	6		6		
1622	Log Fclty Dep Ops	SE Corner	6	2 x wk	765	6		6		
1627	Log Fclty Dep Ops	NE Corner	6	2 x wk	766	6		6		
1642	They bring out to 1621	East	6	2 x wk	767	6		6		
1780	SP Kennel, Canine	SW Corner	6	2 x wk	768	6		6		
1781	EOD	South Side	6	2 x wk	769	6		6		
1910	729 Squadron	NE Corner (parking lot)	6	2 x wk	770	6		6		
1913	729 Squadron	NE Corner	6	2 x wk	771	6		6		
1938	729 Air Control SQ.	SE Corner (parking lot)	6	2 x wk	772	6		6		
1938	729 Air Control SQ.	SE Corner (parking lot)	6	2 x wk	773	6		6		
1954	Air Force Museum	North Side	6	2 x wk	774	6		6		
1955	Air Force Museum	NW Corner	6	2 x wk	775	6		6		
2013	MSA-2	SW Corner	6	2 x wk	776		6			6
2013	MSA-2	SW Corner	6	2 x wk	777		6			6
2014	MSA-2	SW Corner	6	2 x wk	778		6			6
2016	MSA-2	South Side	6	2 x wk	779		6			6
2021	MSA-2	SW Corner	6	2 x wk	780		6			6

2026	MSA-2	SW Corner	6	2 x wk	781		6			6
2104	MSA-2	West Side	6	2 x wk	782		6			6
2113	MSA-2	NE Corner	6	2 x wk	783		6			6
2149	MSA-2	SE Corner	6	2 x wk	784		6			6
2193	MSA-2	SE side	6	2 x wk	785		6			6
2213	MSA-2	SE Corner	6	2 x wk	786		6			6
2403	MSA-1, 309 MMXG	West Side	6	2 x wk	787		6			6
2404	MSA-1	SW Corner	6	2 x wk	788		6			6
2405	MSA-1	NW Corner	6	2 x wk	789		6			6
2408	MSA-1	NE Corner	6	2 x wk	790		6			6
2409	MSA-1	NW Corner	6	2 x wk	791		6			6
2695	MSA-1	SE Corner	6	2 x wk	792		6			6
2720	Trailer next to Bldg. 1515	SE Corner	6	2 x wk	793	6		6		
2720	Trailer next to Bldg. 1515	NE Corner	6	2 x wk	794	6		6		
2721	Trailer next to Bldg. 1513	NE Corner	6	2 x wk	795	6		6		
2728	New Trailer between Bldg. 1552 and 1540	SE Corner	6	2 x wk	796	6		6		
2731	Archery	South Side	6	2 x wk	797	6		6		
5077	Outside Fence by Gate	NE Corner	6	2 x wk	798	6		6		
10740	Fireman Training Facility (Airplane)	3021 combo, South Side	6	2 x wk	799		6			6
10746	Tower, Special	North Side	6	2 x wk	800		6			6
10746	Tower, Special	South Side	6	2 x wk	801		6			6

10758	Radar Dome	East Side	6	2 x wk	802	6		6		
402	Little Mountain	North Side	6	1 x wk	803				6	
402	Little Mountain	North Side	6	1 x wk	804				6	
501	Little Mountain	West Side	6	1 x wk	805				6	
1701	Little Mountain	Northwest Side	6	1 x wk	806				6	
4301	Little Mountain	South Side (across street)	6	1 x wk	807				6	
	New Bldg	Two Dumpsters	12	2 x wk	808, 809	12		12		
	New Bldg	Two Dumpsters	12	2 x wk	810, 811	12		12		
	New Bldg	Two Dumpsters	12	2 x wk	812, 813	12		12		
	New Bldg	Two Dumpsters	12	2 x wk	814, 815	12		12		
	New Bldg	Two Dumpsters	12	2 x wk	816, 817	12		12		
	New Bldg	Two Dumpsters	12	2 x wk	818, 819	12		12		
	New Bldg	Two Dumpsters	12	2 x wk	820, 821	12		12		
	New Bldg	Two Dumpsters	12	2 x wk	822, 823	12		12		
	New Bldg	Two Dumpsters	12	2 x wk	824, 825	12		12		
	New Bldg	Two Dumpsters	12	2 x wk	826, 827	12		12		
	New Bldg	Two Dumpsters	12	2 x wk	828, 829	12		12		
	New Bldg	Two Dumpsters	12	2 x wk	830, 831	12		12		
	New Bldg	Two Dumpsters	12	2 x wk	832, 833	12		12		
	New Bldg	Two Dumpsters	12	2 x wk	834, 835	12		12		
	New Bldg	Two Dumpsters	12	2 x wk	836, 837	12		12		
	New Bldg	Two Dumpsters	12	2 x wk	838, 839	12		12		
	New Bldg	Two Dumpsters	12	2 x wk	840, 841	12		12		
	New Bldg	Two Dumpsters	12	2 x wk	842, 843	12		12		
	New Bldg	Two Dumpsters	12	2 x wk	844, 845	12		12		
	New Bldg	Two Dumpsters	12	2 x wk	846, 847	12		12		
	New Bldg	Two Dumpsters	12	2 x wk	848, 849	12		12		
	New Bldg	Two Dumpsters	12	2 x wk	850, 851	12		12		
	New Bldg	Two Dumpsters	12	2 x wk	852, 853	12		12		
	New Bldg	Two Dumpsters	12	2 x wk	854, 855	12		12		
	New Bldg	Two Dumpsters	12	2 x wk	856, 857	12		12		
	New Bldg	Two Dumpsters	12	2 x wk	858, 859	12		12		
	New Bldg	Two Dumpsters	12	2 x wk	860, 861	12		12		
	New Bldg	Two Dumpsters	12	2 x wk	862, 863	12		12		
	New Bldg	Two Dumpsters	12	2 x wk	864, 865	12		12		
	New Bldg	Two Dumpsters	12	2 x wk	866, 867	12		12		

				Yards		1948	822	1948	30	970
		Total Cans	468	Lifts		324	137	324	5	161

TABLE A-4**TASKS & ESTIMATED FREQUENCY****ROLL OFF & COMPACTOR
COLLECTION STATIONS & FREQUENCY**

* Roll off container shall be multi-use and constructed with dividers so that each inorganic recyclable material will have its own compartment. The container shall be labeled according to Appendix E.

Extra roll off containers will be needed as requested.

Scheduled Permanent Roll Offs (23)		
Building and Location	Number of Roll Offs	Est. Collection Frequency
Alley Between Bldgs. 50 and 58, Wood	1 - 40yd roll-off	Bi - Weekly
Bldg. 225 Southeast, Fuel Foamer	1 - 40yd roll-off	Daily
Bldg. 257, Wood	1 - 40yd roll-off	Daily
Bldg. 400 (Commissary), Trash	1 - 40yd roll-off	Bi - Weekly
Bldg. 412 (BX), Trash	1 - 40yd roll-off	Bi - Weekly
Bldg. 503 North Side (Air Field), Wood	1 - 40yd roll-off	Daily
Bldg. 503 North Side (Air Field), Wood	1 - 40yd roll-off	Daily
Bldg. 508 West Side (Loading Dock), Trash	1 - 40yd roll-off	Bi - Weekly
Bldg. 509 East Side, Wood	1 - 40yd roll-off	1 X Weekly
Bldg. 590 South Side, Fuel Foamer	1 - 40yd roll-off	Bi - Weekly
Bldg. 680 Southwest, Fuel Foamer	1 - 40yd roll-off	Daily
Bldg. 843 Northwest, Trash	1 - 40yd roll-off	Daily
Bldg. 847 Southwest (Behind Gate), Trash	1 - 40yd roll-off	1 X Weekly
Bldg. 849 South, Trash	1 - 40yd roll-off	2 X Daily
Bldg. 850 Bay D South Side, Trash	1 - 40yd roll-off	Daily
Bldg. 850 Bay F North Side, Trash	1 - 40yd roll-off	Bi - Weekly
Bldg. 860 East Side, Trash	1 - 40yd roll-off	1 X Weekly
Bldg. 935 (MSA 1), Trash	1 - 40yd roll-off	1 X Weekly
Bldg. 1158 West Side, Wood	1 - 40yd roll-off	1 X Weekly
Bldg. 1377 (MSA 1), Wood	1 - 40yd roll-off	1 X Weekly
Bldg. 1438 (MSA 1), Wood	1 - 40yd roll-off	Daily
Bldg. 1438 (MSA 1), Wood/Trash	1 - 40yd roll-off	1 X Weekly
Bldg. LM 4301 (Little Mountain), Trash	1 - 40yd roll-off	Bi - Weekly

Scheduled Permanent Compactors (3)		
Building and Location	Number of Compactors	Est. Collection Frequency
Bldg. 400 (Commissary)	1 - 40yd Compactor	1 X Weekly
Bldg. 412 (BX)	1 - 40yd Compactor	1 X Weekly
Bldg. 849 West Door 1	1 - 40yd Compactor	1 X Weekly
Scheduled Roamer/Load & Go Roll Offs (8)		
Building/Location Per COR Request	Number of Roll Offs	Est. Collection Frequency
Temporary Use Roamer Roll-Offs	1 - 40yd roll-off	Daily
Temporary Use Roamer Roll-Offs	1 - 40yd roll-off	Daily
Temporary Use Roamer Roll-Offs	1 - 40yd roll-off	Daily
Temporary Use Roamer Roll-Offs	1 - 40yd roll-off	Daily
Temporary Use Roamer Roll-Offs	1 - 40yd roll-off	Daily
Temporary Use Roamer Roll-Offs	1 - 40yd roll-off	Daily
Temporary Use Roamer Roll-Offs	1 - 40yd roll-off	Daily
Temporary Use Roamer Roll-Offs	1 - 40yd roll-off	Daily

*** All of the above are under **CLIN XX01**. These are not considered Over and Above requirements even those placed in various locations.

TABLE A-5**TASKS & ESTIMATED FREQUENCY****ORGANIC RECYCLE
COLLECTION STATIONS & FREQUENCY****NOTE: LB = lock bar**

Bldg #	Location	SIZE	Frequency	Can	Monday	Tuesday	Wednesday	Thursday	Friday
1	SE Corner	8	2 x wk	001	8		8		
1A LB	West, Flight Line	8	2 x wk	002		8			8
5	NE Side, Bay A/B	8	2 x wk	003	8		8		
5	East Side, Bay C	8	2 x wk	004	8		8		
5	West Side, Bay K	8	2 x wk	005	8		8		
5	SW, Bay M/N/P	8	2 x wk	006	8		8		
12	NW Corner	8	2 x wk	007	8		8		
21	South Side	8	2 x wk	008	8		8		
23	South Side	8	2 x wk	009		8			8
37 LB	East Side	8	2 x wk	010		8			8
37 LB	East Side	8	2 x wk	011		8			8
39 LB	West Side	8	2 x wk	012		8			8
39 LB	West Side	8	2 x wk	013		8			8
48 LB	West Side	8	2 x wk	014		8			8
50 LB	West Side	8	2 x wk	015		8			8
50 LB	West Side	8	2 x wk	016		8			8
100	North Side	8	2 x wk	017	8		8		
100	North Side	8	2 x wk	018	8		8		
100	SW Side, Bay O	8	2 x wk	019	8		8		
100	SE (across by 225)	8	2 x wk	020	8		8		

118	SE Corner	8	2 x wk	021	8		8		
150	West Side	8	2 x wk	022	8		8		
180	SE Corner pk lot	8	2 x wk	023	8		8		
204 LB	SE Corner	8	2 x wk	024		8			8
205	SE Corner	8	2 x wk	025	8		8		
220 LB	SW Side	8	2 x wk	026		8			8
225 LB	North Side	8	2 x wk	027		8			8
225 LB	North Side	8	2 x wk	028		8			8
225 LB	North Side	8	2 x wk	029		8			8
225 LB	Inside	8	2 x wk	030		8			8
225 LB	Inside	8	2 x wk	031		8			8
225 LB	Inside	8	2 x wk	032		8			8
225 LB	Southeast Side	8	2 x wk	033		8			8
TAMS LB	Southwest	8	2 x wk	034		8			8
230	Southwest	8	2 x wk	035	8		8		
233 LB	West	8	2 x wk	036		8			8
238	Northwest	8	2 x wk	037	8		8		
238	Northwest	8	2 x wk	038	8		8		
238	North Side	8	2 x wk	039	8		8		
238	North Side	8	2 x wk	040	8		8		
249	Northwest	8	2 x wk	041	8		8		
250	Southwest	8	2 x wk	042	8		8		
250	Southwest	8	2 x wk	043	8		8		
256/257 LB	Between Bldgs	8	2 x wk	044		8			8
260 LB	West Side	8	2 x wk	045		8			8
265 LB	Southeast	8	2 x wk	046		8			8

269 LB	Northwest	8	2 x wk	047		8			8
269 LB	East Side	8	2 x wk	048		8			8
270 LB	Northwest	8	2 x wk	049		8			8
279 LB	Southwest	8	2 x wk	050		8			8
344	East Side	8	2 x wk	051	8		8		
361	North Side	8	3 x wk	052	8		8		8
364	South Side	8	3 x wk	053	8		8		8
365	North Side	8	3 x wk	054	8		8		8
366	South Side	8	2 x wk	055	8		8		
401	North (400 south)	8	2 x wk	056	8		8		
408	Northeast	8	2 x wk	057	8		8		
412	North Side	8	2 x wk	058	8		8		
412	North Side	8	2 x wk	059	8		8		
414	North Side	8	2 x wk	060	8		8		
416	Northwest	8	2 x wk	061	8		8		
418	East Side	8	3 x wk	062	8		8		8
420	Northwest	8	2 x wk	063	8		8		
420	Northeast	8	2 x wk	064	8		8		
430	Northeast	8	2 x wk	065	8		8		
445	West Side	8	2 x wk	066	8		8		
450	North Side	8	2 x wk	067	8		8		
460	Southwest	8	2 x wk	068	8		8		
464	North Side	8	3 x wk	069	8		8		8

472	Northwest	8	3 x wk	070	8		8		8
480	South Side	8	3 x wk	071	8		8		8
503 LB	NE Corner	8	2 x wk	072		8			8
503 LB	East Side	8	2 x wk	073		8			8
505 LB	North Side	8	2 x wk	074		8			8
505 LB	Southeast	8	2 x wk	075		8			8
505 LB	Southeast	8	2 x wk	076		8			8
507 LB	Northwest	8	2 x wk	077		8			8
507 LB	Northwest	8	2 x wk	078		8			8
507 LB	West Side	8	2 x wk	079		8			8
507 LB	Southwest	8	2 x wk	080		8			8
507 LB	Southwest	8	2 x wk	081		8			8
507 LB	East Side	8	2 x wk	082		8			8
508	West Side	8	2 x wk	083	8		8		
510 LB	North Side	8	2 x wk	084		8			8
511 LB	Southwest	8	2 x wk	085		8			8
511 LB	Southeast	8	2 x wk	086		8			8
513	Northwest	8	2 x wk	087	8		8		
519	South Side	8	3 x wk	088	8		8		8
520	Northwest	8	2 x wk	089	8		8		
525	North Side	8	2 x wk	090	8		8		
564	Northeast	8	3 x wk	091	8		8		8
567 LB	North Side	8	2 x wk	092		8			8
570	Southwest	8	2 x wk	093	8		8		
570	Southwest	8	2 x wk	094	8		8		
570	Southwest	8	2 x wk	095	8		8		

586	Northeast	8	2 x wk	096	8		8		
589	East Side	8	2 x wk	097	8		8		
590 LB	Southwest	8	2 x wk	098		8			8
590 LB	Southwest	8	2 x wk	099		8			8
592 LB	Northwest	8	2 x wk	100		8			8
593	Southwest	8	2 x wk	101	8		8		
597	Southeast	8	2 x wk	102	8		8		
640 LB	West Side	8	2 x wk	103		8			8
674 LB	North Side	8	2 x wk	104		8			8
674 LB	North Side	8	2 x wk	105		8			8
674 LB	North Side	8	2 x wk	106		8			8
680 LB	NW Corner	8	2 x wk	107		8			8
680 LB	NW Corner	8	2 x wk	108		8			8
694 LB	South Side	8	2 x wk	109		8			8
708 LB	South Side	8	2 x wk	110	8		8		
721 LB	East Side	8	2 x wk	111	8		8		
732 LB	West Side	8	2 x wk	112	8		8		
741 LB	North Side	8	2 x wk	113	8		8		
746 LB	South Side	8	2 x wk	114	8		8		
802	East Side	8	2 x wk	115	8		8		
841	SW Corner	8	2 x wk	116	8		8		
843	NW Corner	8	2 x wk	117	8		8		
843	North Side	8	2 x wk	118	8		8		
843	North Side	8	2 x wk	119	8		8		
843	SE Corner	8	2 x wk	120	8		8		

845	NW Corner	8	2 x wk	121	8		8		
845	North Side	8	2 x wk	122	8		8		
845	NE Corner	8	2 x wk	123	8		8		
845	South Side (Dock)	8	2 x wk	124	8		8		
845	Bay B	8	2 x wk	125	8		8		
845	Bay D	8	2 x wk	126	8		8		
847	SW Corner	8	2 x wk	127		8			8
847	SE Corner	8	2 x wk	128		8			8
849	North Side	8	2 x wk	129	8		8		
849	East Side	8	2 x wk	130	8		8		
849	East Side	8	2 x wk	131	8		8		
849	West Side	8	2 x wk	132	8		8		
849	West Side	8	2 x wk	133	8		8		
849	West Side	8	2 x wk	134	8		8		
849	West Side	8	2 x wk	135	8		8		
849	South Side	8	2 x wk	136	8		8		
849	South Side	8	2 x wk	137	8		8		
849	South Side	8	2 x wk	138	8		8		
850	East Side, Bay A	8	2 x wk	139	8		8		
850	South Side, Bay A	8	2 x wk	140	8		8		
850	South Side, Bay B	8	2 x wk	141	8		8		
850	South Side, Bay C	8	2 x wk	142	8		8		
850	South Side, Bay D	8	2 x wk	143	8		8		
850	South Side, Bay D	8	2 x wk	144	8		8		
850	South Side, Bay D	8	2 x wk	145	8		8		
850	South Side, Bay D	8	2 x wk	146	8		8		
850	South Side, Bay E	8	2 x wk	147	8		8		
850	South Side, Bay E	8	2 x wk	148	8		8		
850	South Side, Bay F	8	2 x wk	149	8		8		
850	South Side, Bay G	8	2 x wk	150	8		8		
850	Southwest, Bay G	8	2 x wk	151	8		8		
883	North Side	8	2 x wk	152	8		8		
883	North Side	8	2 x wk	153	8		8		
891	SW Corner	8	2 x wk	154		8			8
891	SW Corner	8	2 x wk	155		8			8
891	SE Corner	8	2 x wk	156		8			8

891	SE Corner	8	2 x wk	157		8			8
896	NE Corner	8	2 x wk	158	8		8		
900	East Side	8	2 x wk	159	8		8		
906	West Side	8	2 x wk	160		8			8
915	NE Corner	8	2 x wk	161	8		8		
916	West Side	8	2 x wk	162	8		8		
935	North Side	8	2 x wk	163		8			8
935	North Side	8	2 x wk	164		8			8
945	North Side	8	2 x wk	165		8			8
980	North Side	8	2 x wk	166		8			8
1102	Southeast	8	2 x wk	167	8		8		
1135	NW Corner	8	2 x wk	168	8		8		
1142	East Side	8	2 x wk	169	8		8		
1151	North Side	8	2 x wk	170	8		8		
1158	South End	8	2 x wk	171	8		8		
1160	West Side	8	2 x wk	172	8		8		
1160	West Side	8	2 x wk	173	8		8		
1160	West Side	8	2 x wk	174	8		8		
1160	West Side	8	2 x wk	175	8		8		
1160	West Side	8	2 x wk	176	8		8		
1160	West Side	8	2 x wk	177	8		8		
1160	West Side	8	2 x wk	178	8		8		
1160	West Side	8	2 x wk	179	8		8		
1160	West Side	8	2 x wk	180	8		8		
1160	Inside (Dock)	8	2 x wk	181	8		8		
1201	Northwest	8	2 x wk	182	8		8		

1206	Southwest	8	2 x wk	183	8		8		
1208	Southwest	8	2 x wk	184	8		8		
1210	Northeast	8	2 x wk	185	8		8		
1213	Northeast	8	2 x wk	186	8		8		
1214	Southeast	8	2 x wk	187	8		8		
1215	Southeast	8	2 x wk	188	8		8		
1221	Southeast	8	2 x wk	189	8		8		
1223	Southwest	8	2 x wk	190	8		8		
1225	Northwest	8	2 x wk	191	8		8		
1226	Southeast	8	2 x wk	192	8		8		
1228	Northeast	8	2 x wk	193	8		8		
1231	Southwest	8	2 x wk	194	8		8		
1234	West Side	8	2 x wk	195	8		8		
1236	Northwest	8	2 x wk	196	8		8		
1237	Northwest	8	2 x wk	197	8		8		
1237	Southwest	8	2 x wk	198	8		8		
1243	East Side	8	2 x wk	199	8		8		
1244	Southeast	8	2 x wk	200	8		8		
1248	Northwest	8	2 x wk	201	8		8		
1248	East Side	8	2 x wk	202	8		8		
1251	Southwest	8	2 x wk	203	8		8		
1253	Southwest	8	2 x wk	204	8		8		

1258	Southwest	8	2 x wk	205	8		8		
1264	Southeast	8	2 x wk	206	8		8		
1266	Northwest	8	2 x wk	207	8		8		
1267	Northeast	8	2 x wk	208	8		8		
1268	Northwest	8	2 x wk	209	8		8		
1269	Northwest	8	2 x wk	210	8		8		
1284	Northwest	8	2 x wk	211	8		8		
1289	South Side	8	2 x wk	212	8		8		
1289	East Side (pkg lot)	8	2 x wk	213	8		8		
1295	Northeast	8	2 x wk	214	8		8		
1295	Southeast	8	2 x wk	215	8		8		
1377	NE Corner	8	2 x wk	216		8			8
1377	Northeast	8	2 x wk	217		8			8
1377	Northeast	8	2 x wk	218		8			8
1424	East Side	8	2 x wk	219		8			8
1438	North Side	8	2 x wk	220		8			8
1477	Northwest	8	2 x wk	221		8			8
1478	Northeast	8	2 x wk	222		8			8
1511	Northwest	8	2 x wk	223	8		8		
1513	Southeast	8	2 x wk	224		8			8
1515	Northeast	8	2 x wk	225		8			8
1515	Northeast	8	2 x wk	226		8			8
1515	Southeast	8	2 x wk	227		8			8
1515	Southeast	8	2 x wk	228		8			8
1530	SE Corner (Pk Lot)	8	2 x wk	229	8		8		

1531	NE (behind gate)	8	2 x wk	230		8			8
1540	Southeast	8	2 x wk	231	8		8		
1573	East Side	8	2 x wk	232	8		8		
1621	Southeast	8	2 x wk	233	8		8		
1621	Southeast	8	2 x wk	234	8		8		
1622	Southeast	8	2 x wk	235	8		8		
1781	South (across st)	8	2 x wk	236	8		8		
1913	Northeast	8	2 x wk	237	8		8		
1938	Southeast	8	2 x wk	238	8		8		
1938	Southeast	8	2 x wk	239	8		8		
1955	Northwest	8	2 x wk	240	8		8		
2013	Southwest	8	2 x wk	241		8			8
2016	South Side	8	2 x wk	242		8			8
2021	Southwest	8	2 x wk	243		8			8
2026	Southwest	8	2 x wk	244		8			8
2104	West Side	8	2 x wk	245		8			8
2149	Southeast	8	2 x wk	246		8			8
2193	Southeast	8	2 x wk	247		8			8
2213	Southeast	8	2 x wk	248		8			8
2404	Southwest	8	2 x wk	249		8			8
2405	Northwest	8	2 x wk	250		8			8
2409	Northwest	8	2 x wk	251		8			8

2695	Southeast	8	2 x wk	252		8			8
2720	East Side	8	2 x wk	253	8		8		
2728	East Side	8	2 x wk	254	8		8		
2731	South Side	8	2 x wk	255	8		8		
10758	East Side	8	2 x wk	256	8		8		
1800 N Gate	Southeast	8	2 x wk	257	8		8		
Little Mtn 402	North Side	8	1 x wk	258				8	
Little Mtn 501	West Side	8	1 x wk	259				8	
Little Mtn 1701	Northwest	8	1 x wk	260				8	
Little Mtn 4301	South Side	8	1 x wk	261				8	

RECYCLE COLLECTION AREA

Hill AFB Recycle collection area is located at bldg. 801, just north of bldg. 805. The area is monitored for hazardous materials. If the contractor sees hazardous materials at the site, contact the COR immediately at (801) 775-6779.

801	Recycle Lot/ Glass and Cans	6	2 x wk	262		6			6
801	Recycle Lot/ Glass and Cans	6	2 x wk	263		6			6
801	Recycle Lot/CB	8	2 x wk	264		8			8
801	Recycle Lot/CB	8	2 x wk	265		8			8
801	Recycle Lot/CB	8	2 x wk	266		8			8
801	Recycle Lot/CB	8	2 x wk	267		8			8
801	Recycle Lot/CB	8	2 x wk	268		8			8
801	Recycle Lot/CB	8	2 x wk	269		8			8
801	Recycle Lot/CB	8	2 x wk	270		8			8
801	Recycle Lot/CB	8	2 x wk	271		8			8
801	Recycle Lot/CB	8	2 x wk	272		8			8
801	Recycle Lot/CB	8	2 x wk	273		8			8
801	Recycle Lot/CB	8	2 x wk	274		8			8
801	Recycle Lot/CB	8	2 x wk	275		8			8
801	Recycle Lot/CB	8	2 x wk	276		8			8
801	Recycle Lot/ Aluminum	8	2 x wk	277		8			8
801	Recycle Lot/ Aluminum	8	2 x wk	278		8			8

801	Recycle Lot/ Plastic	8	2 x wk	279		8			8
801	Recycle Lot/ Plastic	8	2 x wk	280		8			8
New Bldg	Two Dumpsters	16	2 x wk	281,282	16		16		
New Bldg	Two Dumpsters	16	2 x wk	283,284	16		16		
New Bldg	Two Dumpsters	16	2 x wk	285,286	16		16		
New Bldg	Two Dumpsters	16	2 x wk	287,288	16		16		
New Bldg	Two Dumpsters	16	2 x wk	289,290	16		16		
New Bldg	Two Dumpsters	16	2 x wk	291,292	16		16		
New Bldg	Two Dumpsters	16	2 x wk	293,294	16		16		
New Bldg	Two Dumpsters	16	2 x wk	295,296	16		16		
New Bldg	Two Dumpsters	16	2 x wk	297,298	16		16		
New Bldg	Two Dumpsters	16	2 x wk	299,300	16		16		
New Bldg	Two Dumpsters	16	2 x wk	301,302	16		16		
New Bldg	Two Dumpsters	16	2 x wk	303,304	16		16		
New Bldg	Two Dumpsters	16	2 x wk	305,306	16		16		
New Bldg	Two Dumpsters	16	2 x wk	307,308	16		16		
New Bldg	Two Dumpsters	16	2 x wk	309,310	16		16		
New Bldg	Two Dumpsters	16	2 x wk	311,312	16		16		
New Bldg	Two Dumpsters	16	2 x wk	313,314	16		16		
New Bldg	Two Dumpsters	16	2 x wk	315,316	16		16		
New Bldg	Two Dumpsters	16	2 x wk	317,318	16		16		
New Bldg	Two Dumpsters	16	2 x wk	319,320	16		16		
New Bldg	Two Dumpsters	16	2 x wk	321,322	16		16		
New Bldg	Two Dumpsters	16	2 x wk	323,324	16		16		
New Bldg	Two Dumpsters	16	2 x wk	325,326	16		16		
New Bldg	Two Dumpsters	16	2 x wk	327,328	16		16		
New Bldg	Two Dumpsters	16	2 x wk	329,330	16		16		
New Bldg	Two Dumpsters	16	2 x wk	331,332	16		16		
New Bldg	Two Dumpsters	16	2 x wk	333,334	16		16		
New Bldg	Two Dumpsters	16	2 x wk	335,336	16		16		
New Bldg	Two Dumpsters	16	2 x wk	337,338	16		16		
New Bldg	Two Dumpsters	16	2 x wk	339,340	16		16		
			Yards		1832	852	1832	32	924
	Total Cans	340	Lifts		229	107	229	4	116

*** All of the above are under CLIN XX03. These are not considered Over and Above requirements even those placed in various locations.

APPENDIX B

MAPS AND/OR SITE PLANS

BASE STREET MAP – provided via request from CO.

APPENDIX C

GOVERNMENT FURNISHED PROPERTY/SERVICES/EQUIPMENT

GOVERNMENT FURNISHED ITEMS:

RECYCLE CONTAINERS- Approx. 210 8 yd. containers

RECYCLING AREA – Located near Balmer Street, 6th Street, and F Avenue

SNOW REMOVAL SERVICES

POLICE SERVICES

FIRE SERVICES

RESCUE SERVICES

APPENDIX D

CLINS

BID SCHEDULE BASIC YEAR

CONTRACT LINE ITEM NO. (CLIN)	SUPPLIES/SERVICE	QTY	UNIT	UNIT PRICE	AMOUNT
	NON-PERSONAL SERVICES: Provide all supervision, personnel, tools, vehicles, equipment, transportation, materials, and other items and services necessary to perform Integrated Solid Waste Management services at Hill AFB and Little Mountain for the IDIQ contract period 1 Oct 2026 to 30 Sep 2031 IAW the Performance-based Work Statement (PWS) dated: 22 Feb 2025. This CLIN is not separately priced; the requirement of this CLIN applies to all subsequent CLINS (0001-0018)				
0001	Municipal Solid Waste Collection – Base (PWS 1.1.1.1)	12	MO		
0002	Food Waste Collection - Base (PWS 1.1.1.2)	12	MO		
0003	Recyclable Collection – Base (PWS 1.1.1.3)	12	MO		
0004	Municipal Solid Waste Collection – MFH (Non-privatized) (PWS 1.1.2.1)	12	MO		
0005	Recyclable Collection – MFH (Non-privatized) (PWS 1.1.2.2)	12	MO		
0006	Compostable Organics – MFH (Non-privatized) (PWS 1.1.2.3)	12	MO		
0007	Bulk Item Pickup – MFH (Non- privatized) (PWS 1.1.2.4)	8	EA		
0008	Unscheduled Items Pick-up and Special Events (PWS 1.1.3.1)	Xx	EA		
0009	Construction and Demolition Debris Placement / Pick-up (PWS 1.1.3.2) [NOT FOR CONSTRUCTION CONTRACT (SRM) DEBRIS]	Xx	EA		
0010	Public / Common Use MSW Receptacle Collection (PWS 1.1.3.3)	12	MO		

CONTRACT LINE ITEM NO. (CLIN)	SUPPLIES/SERVICE	QTY	UNIT	UNIT PRICE	AMOUNT
0011	Public / Common Use Recycling Receptacle Collection (PWS 1.1.3.4)	12	MO		
0012	Ash Collection (PWS 1.1.3.5)	12	MO		
0013	Additional Pickups (PWS 1.1.3.6.)	Xx	EA		
0014	Container Relocations (PWS 1.1.3.7)	Xx	EA		
0015	Operate Base Recycling Center / Material Recovery Facility (PWS 1.2)	12	MO		
0016	Operate Composting Facility (PWS 1.2.6)	12	MO		
0017	Equipment Maintenance (PWS 1.4)	Xx	EA		
0018	Landfill Tipping Fees (PWS 1.5)	Xx	Tons		
TOTAL CLINS: 0001-0018					

NOTE: CONTRACTING OFFICERS SHALL NOT DEVIATE FROM THIS SCHEDULE WITHOUT AFIMSC APPROVAL. A STANDARDIZED CLIN STRUCTURE IS CRITICAL FOR AF ACTIVITY MANAGEMENT PLANS IN ORDER TO PROVIDE FULL COST VISIBILITY.

INSERT THE FOLLOWING ON SF 1449 CONTINUATION SHEET PRICING SCHEDULE (BLOCKS 19 THROUGH 24)

APPENDIX E

CONTAINER MARKING INSTRUCTIONS

All Front Load Containers: (All signage shall be at least 6x9 inches or larger, legible and readable as listed below, and missing or damaged signage replaced within two (2) workdays of notification of Government COR or immediately upon discovery by contractor personnel)

1) *THIS DUMPSTER IS FOR REFUSE GENERATED ON HILL AFB ONLY*

VIOLATORS WILL BE PROSECUTED

2) *NO PARKING WITHIN 10 FEET*

3) *NO HAZARDOUS WASTE*

4) *KEEP LIDS AND DOORS CLOSED*

5) *DO NOT FILL PAST THIS LINE*

6) *LEAVE MESSAGE AT (801) 775-6779*

(Other specific signage detailed per type below)

Refuse Containers: (Place Number in Right-Hand Corner, starting with number 400)

(See specific signage listed above)

Recycling Containers: (Place Number in Right-Hand Corner, starting with number 001)

SINGLE STREAM RECYCLING ONLY, NO GLASS

(PAPER, CARDBOARD, PLASTICS, ALUMINUM, STEEL)

(See specific signage listed above)

Glass Container:

GLASS ONLY

ABSOLUTELY NO FLUORESCENT LIGHTS

(See specific signage listed above)

Sawdust Collection Container:

SAWDUST ONLY

(See specific signage listed above)

All Roll Offs and Compactors:

1) *THIS DUMPSTER IS FOR REFUSE GENERATED ON HILL AFB ONLY*

VIOLATORS WILL BE PROSECUTED

2) *NO PARKING WITHIN 10 FEET*

3) *NO HAZARDOUS WASTE*

4) *DO NOT FILL PAST THIS LINE*

5) *LEAVE MESSAGE AT (801) 775-6779*

The Quality Assurance Personnel must approve all container markings prior to placing them on the containers.

NOTE: Actual markings may vary depending on which recycling materials vendors are willing to accept.

APPENDIX “F”

OGDEN AIR LOGISTICS CENTER

UNITED STATES AIR FORCE

HILL AIR FORCE BASE, UTAH 84056

SAFETY, FIRE PROTECTION AND HEALTH SPECIFICATION

INDUSTRIAL SAFETY REQUIREMENTS

INTEGRATED SOLID WASTE MANAGEMENT

UNITED STATES AIR FORCE
HILL AIR FORCE BASE, UTAH 84056

Contractor's Guide

Safety Appendix

**OCCUPATIONAL SAFETY AND HEALTH
REQUIREMENTS FOR CONTRACT OPERATIONS**

DATE: 01 Sep 19

75 ABW Safety Office	777-7233
OO-ALC Safety Office	586-6038
Command Post	777-3007
Security Forces	777-3056
Fire Services	777-3021

INDEX

Pre-Brief

General Requirements

Safety Plan Specific Requirements

PRE-BRIEF

Project Title: _____

Location: _____

Brief description of work: _____

Project Number: _____

Contract number _____

Estimated Start Date: _____

Estimated Completion Date: _____

Safety plan was reviewed by _____ Date _____

Contractor: _____ Number: _____

Contracting Officer: _____ Number: _____

Contracting Officer Representative: _____ Number: _____

Sub-Contractor _____ Number: _____

Site Supervisor: _____ Number: _____

75 ABW Safety: _____ Number: 777-7233 (SAFE)

OO-ALC Safety: _____ Number: 586-6038

**This completed page will be provided to the safety offices
for historical purposes**

**** Construction and manufacturing only**

Safety Office Use Only Control number if used (YYYYMMDD-XX)

GENERAL SAFETY REQUIREMENTS

This handout is to familiarize you with some of the safety requirements that you may encounter while working on Hill AFB.

The Safety Office sincerely hopes your work here will be mishap free. If you require emergency medical attention, be aware there are no emergency services available at Hill AFB. Emergency service are only available by calling 911.

If you encounter problems with vehicle registration, traffic, parking, or area security you should contact the Security Forces Law Enforcement Desk at 777-3056.

Air Force Materiel Command (AFMC) Acquisition Reform initiatives focus on risk management rather than traditional methods of providing specific government guidance for risk elimination. With “performance-based” language, the government will provide the contractor with areas requiring specific information and the contractor will be free to meet those objectives using corporate standards.

Contractors and their subcontractors are responsible to follow all applicable federal, state, and local laws, Occupational Safety and Health Act, (OSHA) Public Law 91-596, and Air Force guidance called out in this document. Written safety plans will be available to all employees. All work areas will be maintained in a manner that protects all employees, and safeguards the general public, and government personnel, equipment and property.

All employees will be properly trained and qualified and be able to demonstrate knowledge of their duties. All contractors and subcontractors will be knowledgeable of all hazards and potential hazards associated with the duties and the work area they are assigned to. All employees will have the right to stop all work if at any time they deem the duties or area may be hazardous. All hazards will be mitigated prior to work being resumed.

Contractors and subcontractors are responsible for providing any necessary barricades, signs, lights, fencing, and any additional protective measures the Contracting Office determines is necessary for the purposes of protecting all employees, the general public, government personnel, equipment and property.

Crosswalks: All personnel are required to use the closest crosswalk, or traffic controlled intersection when crossing the road if possible.

****Cranes:** If cranes are used, prior to raising the boom above facility roof lines, you must contact 75 OSS Airfield Management at 777-3592.

****Dig permits (red stakes):** Any digging will require a dig permit from CEG at 777-0540. It may take up to 21 days to get approval, plan accordingly.

Explosive Safety (AFI 91-201) If duties require entry into an explosive clear zone, employees must receive Explosive Safety Awareness Training. Contact your respective Safety Office to schedule a class and receive additional guidance.

Hazardous energy control (LOTO): If lock out tag out procedures are required, a meeting with the area supervisor(s) must take place to coordinate differences in procedures.

****Hot work permits:** Any hot work (welding, cutting, grinding...) will require a hot work permit (AF Form 592). Contact the Fire Department at 777-0236.

Motor vehicles: Seatbelts are required while vehicles are in operation. Cell phone use by a driver is prohibited while the vehicle is in motion.

****Permit required confined space entries:** If entry into a confined space is required contact the area supervisor and or the installation safety office. All known hazards will be discussed prior to entry. 777-SAFE (7233)

Photography: If photographs will be required, permission to use a camera must be obtained from the unit security manager. Photographs in a secured area will normally not be allowed.

****Trenching/excavations:** See dig permits and environmental issues

X-ray approvals: If X-ray equipment will be used contact Bioenvironmental at 777-1053.

Environmental Issues

Air quality: If emission producing equipment is brought on base you must contact Civil Engineering Air Quality Flight at 777-0888. If your process will produce vapors, fumes, or dust you must contact Bioenvironmental at 777-1053.

Cultural resources: If artifacts of any kind are discovered you must contact Civil Engineering Cultural Resources Flight at 586-2464.

Hazardous materials: If any hazardous materials are brought on to the base you must coordinate with Civil Engineering Hazardous Materials Flight at 586-2718.

Hazardous waste: Contact Civil Engineering Hazardous Waste Flight at 586-8537.

Landfill use: If the base landfill will be used you will need to apply for a permit. Contact Civil Engineering Hazardous Solid Waste Flight at 777-5788.

Storm water: Contact Civil Engineering Water Quality Flight at 777-0493.

Flight line

Flight line operations: If you are required to drive on the flight line contact 75 OSS Airfield Management at 777-3592.

SAFETY PLAN SPECIFIC REQUIREMENTS

NOTE

The government shall assume no liability or responsibility for the contractor's compliance or non-compliance with safety requirements.

The contractor must also protect personnel from hazards generated by the work. If the contractor employs bilingual speaking employees, they must post bilingual signs and have written procedures for specific tasks in applicable languages.

Safety program requirements. Contractors will implement a written safety plan, provide it to subcontractors, and have it available upon request at the job site. The plan will consist of the following items if they apply to your work on Hill AFB or any government owned property:

NOTE

If safety programs are modified after the initial review, the contractor shall submit the proposed modification, in writing, to the Contract Administration Office.

a. Hazard Assessments. Prior to any work, a hazard assessment must be conducted, and documented. The assessment will be certified and briefed to all affected employees.

****b. Contractor Safety Board (construction projects).** Contractors and subcontractors will display and maintain a safety and health bulletin board in a commonly accessed area in clear view of the on-site workers. The location should be protected against the elements and unauthorized removal. It shall contain, at minimum, the following safety and health information:

*If this information is not posted on the safety board, a placard must indicate its location.

1. A map with route to the nearest Emergency Care Facility.
2. Emergency phone numbers; (911, Police, Fire, Environmental, others as applicable)
3. A copy of the most up-to-date Safety Plan shall be mounted on or adjacent to the bulletin board, or a notice on the bulletin board shall state the location of the APP. The location of the APP shall be accessible to all employees.
4. A copy of the current Hazard Analysis/analyses shall be mounted on or adjacent to the bulletin board, or a notice on the bulletin board should state the location of the Hazard Analysis. The location of the Hazard Analysis shall be accessible to all employees.
5. The Occupational Safety and Health Administration (OSHA) Form 300A, Summary of Work Related Injuries and Illnesses, shall be posted, in accordance with OSHA requirements, from February 1 to April 30. It shall be mounted on or adjacent to the bulletin board, which will be accessible to all employees.

6. A copy of the Safety and Occupational Health deficiency tracking log shall be mounted on or be adjacent to the bulletin board or a notice on the bulletin board shall state the location where it may be accessed by all workers upon request.
7. Safety and Health promotional posters.
8. Date of last lost workday injury.
9. OSHA Safety and Health Poster.
10. A copy of the hazardous material inventory, identification of use, approximate quantities and site map detailing location.
11. Mishap reporting forms and hazard reporting forms.
12. Contract Information (Section 1 of this document).

c. Site-specific training. The contractor will ensure all employees and subcontractor employees are properly trained and qualified to conduct their work safely. Detailed training plans will be developed and available to all employees. Training plans will include, at a minimum, all required information contained in all applicable federal, state, and local laws, Occupational Safety and Health Act, (OSHA) Public Law 91-596, and Air Force guidance called out in this document. The training plans will be available for review upon request from the Contracting or Safety Office.

d. Mishap Reporting (29 CFR 1904) In the event of injury or damage to government equipment or property:

- ✓ Contact your supervisor and safety representative.
- ✓ Contact your designated Government Representative.
- ✓ After hours contact the Hill AFB Command Post at 777-3007.
- ✓ Contact your Safety Office representative (75 ABW/SEG or OO-ALC/SEG).
- ✓ Secure the mishap scene, do not move anything until released by the Safety Office.
- ✓ Obtain witness statements, do not release witnesses until instructed by the Safety Office. Separate witnesses while they are writing statements.

POC: _____ Number: _____
 POC: _____ Number: _____
 POC: _____ Number: _____

Mishap report shall contain, as a minimum, the following information:

1. Contractor Name, Contract Number, Name and Title of Person(s) Reporting.
2. Date, Time, and exact location of mishap.
3. Narrative of mishap (Events leading to mishap/incident).
4. Cause of mishap, if known.
5. Estimated cost of mishap (material and labor to repair/replace).
6. Nomenclature of equipment and personnel involved in mishap/incident.
7. Corrective actions (taken or proposed).
8. Other pertinent information.

The contractor will provide copies of contractor data related to mishaps, such as contractor analyses, test reports, summaries of investigations, etc. as necessary to support the government investigation.

Send a copy of the written mishap/incident report NO LATER THAN 3 work days to the Government Representative, and the Safety Office at 75ABW.SE.Workflow@us.af.mil;

e. Hazardous Communication (HAZCOM, 29 CFR 1910.1200) All materials will have a current Safety Data Sheets available to all employees. Employees will be trained on all aspects of a HAZCOM program.

f. Routine job site inspections. Supervisors are responsible to conduct and document routine safety inspections at intervals established based on potential hazards to the work being conducted. At a minimum a daily area inspection should be conducted.

g. Routine safety briefs. Daily safety briefs will be conducted and documented explaining any new or existing hazardous conditions.

h. On-site competent person. Every worksite will have an assigned competent person to ensure employees and subcontractors are working in a safe manner.

i. Subcontractor Clause. All subcontractors are responsible for following all applicable federal, state, and local laws, Occupational Safety and Health Act, (OSHA) Public Law 91-596, and Air Force guidance called out in this document. Prime contractors will routinely ensure subcontractors following safety guidance.

j. Identification of segregated work site locations. List any locations or operations that cannot be co-mingled with general industrial operations. Requires Contracting Officer approval of operations and changes at these specific sites.

k. Emergency Action Plans (29 CFR 1926.35, 29 CFR 1910.38) Detailed emergency action plans will be developed and briefed for each site as required. Ensure emergency services are available for extremely hazardous work, examples include but are not limited to permit required confined space entry and fall protection rescue. Ensure this plan is coordinated with Hill AFB Fire Services.

l. Fire Prevention Plans (29 CFR 1926.24, 29 CFR 1910.39) Detailed fire prevention plans will be developed for each work site and briefed to all employees. Ensure this plan is coordinated with Hill AFB Fire Services.

****Safety and Occupational Health Plan**

The Contractor shall provide a stand-alone Project Health and Safety Plan. The Project Health and Safety Plan shall be kept on-site at the construction management location at all times. All Contractor personnel, subcontractor personnel, Government, and visitors entering the construction site shall be briefed on the health and safety plan and required to sign an endorsement of strict adherence to the plan: USACE EM 385-1-1 *Safety and Health Requirements Manual*, sets forth the specific Contractor's Safety Program requirements. The following comprises Health and Safety Plan topics.

- a. Background (Site location and history and planned activities).
- b. Safety Program Organization (identification of safety program members, roles and responsibilities, contact [normal and emergency] information).
- c. Site Map (site delineation, points of entrance and egress, staging areas, alarms and emergency equipment, site evacuation map, and communication devices).
- d. Site Hazards (personal safety and environmental).
- e. Site Worker Training Requirements.
- f. Accident Prevention Plan (APP).
- g. Personnel Protection Equipment (PPE) Requirements.
- h. Activity Hazard Analysis (AHA).
- i. Medical Surveillance.
- j. Monitoring (frequency, equipment and calibration, action levels).
- k. Site Control Areas (requiring PPE, confined spaces).
- l. Emergency Response Actions.