

60kW Diesel Generator Upgrade and Installation for Hemp Shelter

STATEMENT OF WORK (SOW)

April 22, 2026

1. Requirement: The activity required is the MacDill 6th Communication Squadron. We require the replacement of the existing power generation system for the Hemp Shelter. The current system, consisting of two 30kw microturbines, needs to be upgraded to a new 60kw diesel generator to ensure a reliable and adequate power supply for operations.

2. Description of Services: The contractor shall provide all necessary labor, materials, and equipment to perform the following services:

- Remove the two existing 30kw Capstone microturbines (SN:003085, and 003086) and the associated automatic transfer switch from the Hemp Shelter (Bldg. 578).
- Remove the existing diesel fuel tank located outside of the shelter and the existing diesel day tank located inside (Bldg. 578) the shelter.
- Install one (1) new 60kw diesel generator in place of the two existing microturbines.
- Install one (1) new 200-amp, 480-volt, three-phase automatic transfer switch.
- Install a new (408-gallon) diesel fuel tank and day tank, including all necessary fuel piping and connections.
- Provide all required engineering and drawings for the project.
- Secure all necessary electrical and fuel permits and manage all related inspections.

3. Services Summary: The contractor shall deliver a complete and operational power generation system. Acceptability will be determined by the successful installation, testing, and commissioning of the following deliverables:

- Deliverables:
 - One (1) new Caterpillar Diesel Generator (Model D60 GC), rated at 60KW standby, 277/480 Volts, 3 Phase, with a weatherproof, sound-attenuated enclosure and a 408-gallon UL142 listed fuel tank.
 - One (1) new ASCO 300 Series Automatic Transfer Switch, rated at 200-Amp, 480 volts, 3 Phase, in a NEMA 3R enclosure.
 - Completion of a pre-start inspection and system startup.
 - A successful 4-hour on-site resistive load test.
 - All necessary project drawings, permits, and inspection approvals.
 - 2-Year / 1000-hour Caterpillar Extended Service Coverage.
 - Asco Two-Year Limited Warranty.
- Frequencies:
 - The removal and installation work is a one-time event.
 - Preventive maintenance service for the generator to include every 6 months for fluid and filter changing. As well as the major inspection every year for load bank testing, replacing belts, filters and fluids.

4. Work Schedule: The maintenance will be coordinated between the contractor and the 6CS/SCP flight two weeks prior to the completion date. Contractors will conduct maintenance Monday-Friday between 0800-1600 (L). This excludes federal holidays and family wing days. Contractors will be required to conduct emergency Maintenance 24/7 on a as needed basis.

5. Place of Performance: Work will be performed at the following location:

- MacDill 6th Communication Squadron
- USCENTCOM
- Hemp Shelter (Bldg. 578)
- 7121 S Boundary Blvd
- Tampa, FL 33621 US