

## STATEMENT OF WORK FOR G STREET SIDEWALK AND VAULT REPAIR

---

### 1 BACKGROUND

---

The U.S Government Printing Office (GPO) provides publishing and dissemination services for the official and authentic government publications to Congress, Federal agencies, Federal depository libraries, and the American public. GPO has four buildings and some of these buildings date back to 1903. An extensive structural evaluation has been conducted of deteriorated concrete areas in the vehicular maintenance garage and G-Street vaulted sidewalk. The primary focus of this statement of work shall be the repair of vehicular maintenance garage. The extensive study of vehicular maintenance garage has recommended to some extend replace portion of the vehicular maintenance garage slab and to repair the slab & vaults underneath. A copy of the extensive report and a set of design and repair drawings will be provided to assist the construction contractor to implement the recommended construction work.

### 2 OBJECTIVES

---

The contractor shall provide the labor, material, equipment, and supervision to demolish and install the sidewalk slab and to repair and renovate the vaults beams, concrete slab, waterproofing membrane, and columns and other related structures to eliminate the water migration into the basement. All the work shall be in accordance with the design drawings and specifications prepared and submitted along with this statement of work. The contractor is required to obtain permits, traffic control plans, safety, and security approval prior to construction starting.

### 3 SCOPE

---

The concrete sidewalk and the vault structure beneath the G Street Sidewalk are showing signs of moderate to severe deterioration of the concrete and the encased structural framing. Over time and a failure of the waterproofing membrane, salt water, and other liquids constantly migrate into the reinforced slab and cause deterioration substantial damages.

Contractor shall furnish all labor, materials, tools, supervision, equipment, and perform all operations necessary to accomplish all work as specified herein. The attached construction documents, including drawings and specifications, provide more details for the work to be performed.

## 4 TASKS

---

The contractor shall complete the following tasks as part of the project at the **GPO G Street Sidewalk Repair**:

### **Pre-Construction Tasks**

- Obtain all required permits and approvals.
- Submit project schedule, safety plan, and traffic control plan.
- Coordinate with GPO project management and stakeholders.
- Conduct pre-construction meetings and site walkthrough.

### **Site Preparation & Demolition**

- Install temporary barriers, signage, and traffic control measures.
- Set up designated staging and material storage areas.
- Perform selective demolition of existing structures as required.
- Ensure safe removal and disposal of construction debris.

### **Material Delivery & Logistics**

- Coordinate material deliveries in compliance with schedule.
- Inspect and verify all materials upon arrival.
- Store materials in designated secure areas.

### **Construction & Installation**

- Perform site grading and preparation, if applicable.
- Install structural components, framing, and support systems.
- Complete mechanical, electrical, and plumbing (MEP) installations.
- Install architectural finishes, including flooring, ceilings, and walls.
- Implement weatherproofing and insulation systems as required.
- Conduct equipment and systems testing to ensure functionality.

### **Safety & Compliance**

- Maintain compliance with OSHA and other regulatory standards.
- Implement and monitor safety protocols for workers and pedestrians.
- Address any environmental concerns, including hazardous material handling.

### **Quality Control & Inspections**

- Conduct periodic quality control checks.
- Submit required inspection and testing reports.
- Address any deficiencies noted in inspections.

### Project Closeout

- Complete all final construction activities and finishing work.
  - Conduct a final walkthrough with the GPO project team.
  - Prepare and submit as-built drawings and O&M manuals.
  - Resolve punch list items and obtain final acceptance.
  - Restore site and remove temporary facilities.
  - Submit final project documentation, including warranties and certifications
- 

## 5 DELIVERY

---

The contractor shall be responsible for ensuring the timely and organized delivery of all materials, equipment, and supplies necessary for the completion of the project. The following requirements shall apply:

- **Delivery Coordination**
  - All deliveries must be coordinated in advance with the GPO project representative to minimize disruptions to ongoing operations.
  - The contractor shall submit a delivery schedule for approval, detailing expected dates, times, and types of materials being delivered.
  - Any changes to the delivery schedule must be made at least **48 hours in advance**.
- **Delivery Hours**
  - Deliveries shall be made during **GPO-approved working hours**, typically between **7:00 AM and 2:00 PM**, Monday through Friday, unless otherwise authorized.
  - Weekend or after-hours deliveries require prior written approval from GPO.
- **Loading and Unloading**
  - All unloading shall take place at designated areas specified by GPO.
  - The contractor is responsible for providing the necessary personnel and equipment (e.g., forklifts, pallet jacks) to unload materials efficiently.

- No materials shall be left in unauthorized areas or obstruct emergency exits, pedestrian pathways, or active work zones.
- **Traffic and Site Access**
  - The contractor shall comply with all GPO security and access requirements, including any vehicle inspections before entering the site.
  - Delivery vehicles must follow designated routes to avoid interference with facility operations and public roadways.
  - If necessary, the contractor shall provide traffic control personnel to assist with vehicle movement and ensure pedestrian safety.
- **Material Handling and Storage**
  - All delivered materials must be inspected for damage upon arrival and rejected if found to be defective or non-compliant with specifications.
  - The contractor shall store materials in designated areas to prevent safety hazards and weather exposure.
  - Secure storage shall be provided for high-value items to prevent theft or vandalism.
- **Waste and Packaging Disposal**
  - The contractor is responsible for removing all packaging materials, pallets, and waste generated from deliveries.
  - All disposals shall comply with local environmental regulations and GPO waste management policies.
- **Compliance and Penalties**
  - Any failure to comply with delivery requirements, including unauthorized deliveries, improper storage, or obstruction of operations, may result in penalties, delays, or removal from the site.

## 6 SECURITY

---

- **Entry Requirements:**
  - The contractor shall exchange his/her valid federal or state identification for a GPO Visitor's Badge for entry to GPO
  - Expired identification shall not be acceptable forms of ID
  - Under no circumstances shall a visitor be granted access to GPO without proper identification
  - The Visitor's Badge shall always be visible as safety allows
- Contractors shall be always escorted and/or in line of sight of the escort in the construction area while inside of GPO.
- The contractor is required to set up fencing at work site.
- The contractor is required to secure all openings of basement at the end of each workday.

---

7 OTHER UNIQUE REQUIREMENTS

---

- Offerors are strongly encouraged to attend the site visit outlined in the solicitation.
- Normal working hours of GPO employees are from 06:00AM - 04:00PM
- Weekend and after-hours work is permitted with 48 hours advance notice and approval.
- The contractor may be asked to perform this work out of normal business hours at their own cost.
- Contractor must coordinate with DCDOT.
- The contractor shall be responsible for ensuring the safe and efficient movement of **vehicle and pedestrian traffic** throughout the duration of the project at the **GPO G Street Facility**. This includes implementing necessary **traffic control measures, closures, and rerouting** to minimize disruptions while maintaining access for employees, visitors, and emergency personnel. Any road or sidewalk closures must be **coordinated in advance** with the GPO project manager and local authorities, with proper signage, barricades, and detour routes clearly established. The contractor shall provide **flaggers, temporary barriers, and warning signs** as needed to ensure public safety. Additionally, all traffic control measures must comply with **local transportation regulations, OSHA standards, and the Manual on Uniform Traffic Control Devices (MUTCD)**. The contractor is responsible for restoring normal traffic flow as soon as work allows and ensuring that no construction activities pose a hazard to pedestrians or vehicles in adjacent areas.
- Contractor is required to provide the information included in the bid sheet included in the specifications.
- Project Schedule – A detailed construction schedule, including milestones, phasing, and completion dates, submitted within 10 days of the Notice to Proceed (NTP).
- Material Submittals & Certifications – All required product data, material samples, and certifications to ensure compliance with project specifications, including but not limited to:
  - Manufacturer specifications
  - Safety data sheets (SDS)
  - Compliance with Buy American Act (if applicable)
- Traffic Control Plan – A comprehensive plan outlining vehicular and pedestrian safety measures, including signage, rerouting, barriers, and flagger locations, submitted prior to the start of work.

- **Delivery & Logistics Plan** – A strategy for material delivery, handling, and storage, detailing coordination efforts to avoid disruptions to GPO operations.
- **Site Safety Plan** – A documented plan outlining safety procedures, including OSHA compliance, hazard mitigation, and emergency response protocols.
- **Daily & Weekly Progress Reports** – Updates summarizing work completed, challenges encountered, and any deviations from the schedule.
- **Quality Control Reports** – Regular inspection and testing reports demonstrating compliance with project specifications, including any corrective actions taken.
- **Waste Management & Disposal Records** – Documentation of proper disposal methods for construction debris, hazardous materials, and recyclables, ensuring compliance with environmental regulations.
- **Punch List & Closeout Documentation** – A final list of outstanding work items, corrective actions, warranties, as-built drawings, and operation & maintenance (O&M) manuals for installed systems.
- **Final Inspection & Acceptance Report** – A signed report verifying project completion, including certification that all work has been performed per contract requirements and specifications.
- **Performance Bond**  
The contractor shall furnish a Performance Bond in an amount equal to 100% of the contract value to ensure the satisfactory completion of the work in accordance with contract requirements. The bond must be issued by a surety company licensed to operate in the jurisdiction of the project and must comply with all applicable federal, state, and local regulations.

The Performance Bond shall remain in full force and effect for the duration of the contract, including any approved extensions, until the project has been successfully completed and accepted by the Government Publishing Office (GPO). If the contractor fails to perform in accordance with contract terms, the surety shall be responsible for completing the work or compensating GPO for any losses incurred.

The contractor shall submit the Performance Bond within 10 days of contract award. Failure to provide the required bond within this timeframe may result in contract termination and forfeiture of any initial payments or deposits.

## 8 EVALUATION FACTORS

AWARD WILL BE BASED ON THE LOWEST EVALUATED PRICE OF PROPOSALS MEETING OR EXCEEDING THE ACCEPTABILITY STANDARDS FOR NON-COST FACTORS – LOWEST PRICE TECHNICALLY ACCEPTABLE (LPTA). THE GOVERNMENT WILL ASSIGN AN OVERALL TECHNICAL RATING BASED ON THE COMBINED ASSESSMENT OF THESE FACTORS. THE FOLLOWING FACTORS WILL BE USED TO EVALUATE AND RATE OFFERS USING THE DEFINITIONS PROVIDED BELOW:

---

1. Technical Capabilities (including Schedule)
2. Key Personnel
3. Past Performance

### I. Technical Capabilities (including Schedule)

The Government will evaluate the offeror's technical approach to completing the scope of work, including methods for coordination, execution, quality assurance, safety, and compliance with applicable standards. A clear understanding of site constraints, stakeholder coordination, and construction challenges must be demonstrated.

The **project schedule** will be reviewed as part of this factor to assess the offeror's ability to complete the project within the required period of performance. The schedule must include all critical activities, major milestones, procurement, mobilization, construction phases, and final closeout. It should reflect a realistic, achievable, and logically sequenced plan. Known constraints and risk mitigation strategies should be addressed.

### II. Key Personnel

Key personnel are critical to the successful execution of the work under this contract. Their education, experience, and capabilities will be evaluated to determine their qualifications for their proposed roles. Offerors must provide documentation demonstrating that all proposed key personnel meet or exceed the minimum requirements. This includes clearly outlining responsibilities, technical competencies, experience, and education.

Experience in the construction of similar size and scope is required. The Government also values disciplinary diversity among key personnel, particularly in architecture, mechanical engineering, and electrical engineering.

The Government will evaluate all proposed key personnel and require the following key personnel for this project:

#### **Project Manager**

- *Responsibilities:* Provides overall leadership and direction. Ensure schedule, budget, and contract compliance. Acts as primary liaison with the Government.
- *Minimum Experience:* 10 years
- *Minimum Education:* Bachelors in Engineering, Architecture, Construction Management, or related field (can be waived for 15 years of experience).

### **Quality Control & Site Superintendent**

- *Responsibilities:* Leads quality control and provides on-site construction supervision. Coordinates with the COR and manages daily field operations.
- *Minimum Experience:* 7 years
- *Minimum Education:* Bachelors in relevant field (can be waived for 12 years of experience).

### **Safety Lead**

- *Responsibilities:* Conducts inspections, ensures compliance with safety regulations, and implements site-specific safety protocols.
- *Minimum Experience:* 5 years
- *Minimum Education:* Bachelors in Occupational Health and Safety or related field (can be waived for 10 years of experience).

## **III. Past Performance**

Past performance will be evaluated to assess the offeror's ability to successfully perform work of similar size, scope, and complexity. Offerors should submit information on relevant projects completed within the last five (5) years, including:

- Timeliness of performance
- Quality of work
- Responsiveness
- Contract and budget compliance
- Client satisfaction

The Government may consider information from references, past contract records, CPARS, or other third-party sources. Failure to provide relevant and recent past performance information may result in a lower rating.

## **IV. Price**

Price evaluation will be conducted under the expectation of adequate price competition, relying primarily on market forces to determine price reasonableness. Comparative analysis of proposed prices in response to this



solicitation will be the preferred method. The Government Publishing Office may also compare proposed prices to:

- Historical prices for similar work; and
- The Independent Government Cost Estimate (IGCE).

Additional techniques and procedures outlined in MMAR 15.404-1(b) may be employed, if necessary, to ensure prices are fair and reasonable.

### **Responsiveness**

No price evaluation will be performed on proposals determined to be non-responsive or technically unacceptable.

## **9 PLACE OF PERFORMANCE**

---

The project is located at the U.S. Government Publishing Office (GPO) Headquarters, situated at 732 North Capitol Street NW, Washington, D.C. 20401. The site extends along G Street NW, beginning at the corner of North Capitol Street NW and continuing westward. This central location places the project within the Capitol Hill district, adjacent to key government facilities and major transportation routes. Given its proximity to high-traffic areas, careful coordination will be required to minimize disruptions to daily GPO operations, pedestrian flow, and vehicular traffic.

## **10 PERIOD OF PERFORMANCE**

---

The construction and repair work need to be completed within 18 months after the issuance of the Purchase Order / Notice To Proceed (NTP). This included preconstruction requirements, construction completion.