

D

C

B

A

MECHANICAL, PLUMBING, AND MISCELLANEOUS EQUIPMENT WIRING SCHEDULE										
EQUIPMENT	SHEET #	VOLTS	PHASE	WATTS/ HP	FLA	SERVING PANELBOARD	WIRE AND CONDUIT SIZE	DISCONNECT	FUSE	NOTES
CU-4	EP104	480	3	-	36.8A	MSB	3#6, 1#10G, 3/4"C	60A, WP	60A	-
AHU-1	EP104	480	3	10	67A	MSB	3#2, 1#8G, 1-1/4"C	100A, WP	-	-
DOAS-1	EP104	480	3	-	16.36A	MH1	3#10, 1#10G, 3/4"C	30A	20A	-
DOAS-1, LIGHTS	EP104	120	1	-	2.61A	ML1	2#12, 1#12G, 3/4"C	-	-	-
DOAS-1, RECEPTACLE	EP104	120	1	-	8A	ML1	2#12, 1#12G, 3/4"C	-	-	-
CU-1	EP105	480	3	-	7.5A	MH1	3#12, 1#12G, 3/4"C	30A, WP	-	-
CU-2	EP104	480	3	-	6.7A	PH1	3#12, 1#12G, 3/4"C	30A, WP	-	-
CU-3	EP104	480	3	-	7.5A	PH1	3#12, 1#12G, 3/4"C	30A, WP	-	-
EF-1	EP104	120	1	1/4HP	5.8A	PL2	2#12, 1#12G, 3/4"C	30A	-	-
IU-1	EP102	208	1	-	-		PER MANUFACTURERS REQUIREMENTS	30A	-	1
IU-2	EP102	208	1	-	-		PER MANUFACTURERS REQUIREMENTS	30A	-	1
IU-3	EP105	208	1	-	-		PER MANUFACTURERS REQUIREMENTS	30A	-	1
IU-4	EP102	208	1	-	-		PER MANUFACTURERS REQUIREMENTS	30A	-	1
OU-1	EP105	208	1	-	12A	PL6	2#10, 1#10G, 3/4"C	30A, WP	-	-
OU-2	EP105	208	1	-	12A	TPP1	2#10, 1#10G, 3/4"C	30A, WP	-	-
OU-3	EP104	208	1	-	12A	TPP2	2#10, 1#10G, 3/4"C	30A, WP	-	-
OU-4	EP105	208	1	-	16A	PL6	2#10, 1#10G, 3/4"C	30A, WP	-	-
BCU-1	EP104	480	3	-	3.3A	MH1	3#12, 1#12G, 3/4"C	30A	-	-
BCU-2	EP106	480	3	-	2.5A	PH1	3#12, 1#12G, 3/4"C	30A	-	-
BCU-3	EP106	480	3	-	2.5A	PH1	3#12, 1#12G, 3/4"C	30A	-	-
P-1A	EP102	480	3	7.5 HP	11A	MSB	3#12, 1#12G, 3/4"C	30A	-	-
P-1B	EP102	480	3	7.5 HP	11A	MSB	3#12, 1#12G, 3/4"C	30A	-	-
CR-1 (A)	EP102	480	3	3 HP	4.8A	MSB	3#12, 1#12G, 3/4"C	30A	-	-
CR-1 (B)	EP102	480	3	3 HP	4.8A	MSB	3#12, 1#12G, 3/4"C	30A	-	-
UH 1-1	EP103	120	1	1/12	3.2A	AL1	2#12, 1#12G, 3/4"C	-	-	2
UH 1-2	EP103	120	1	1/12	3.2A	AL1	2#12, 1#12G, 3/4"C	-	-	2
UH 1-3	EP103	120	1	1/12	3.2A	AL1	2#12, 1#12G, 3/4"C	-	-	2
UH 1-4	EP103	120	1	1/12	3.2A	AL1	2#12, 1#12G, 3/4"C	-	-	2
UH 1-5	EP103	120	1	1/12	3.2A	AL1	2#12, 1#12G, 3/4"C	-	-	2
UH 1-6	EP103	120	1	25W	0.2A	AL1	2#12, 1#12G, 3/4"C	-	-	2
UH 1-7	EP102	120	1	1/20	2.2A	PL4	2#12, 1#12G, 3/4"C	-	-	2
UH 1-8	EP102	120	1	25W	0.2A	PL4	2#12, 1#12G, 3/4"C	-	-	2
UH 1-9	EP102	120	1	25W	0.2A	PL1	2#12, 1#12G, 3/4"C	-	-	2
UH 1-10	EP102	120	1	25W	0.2A	PL2	2#12, 1#12G, 3/4"C	-	-	2
UH 1-11	EP104	120	1	1/8	4A	ML2	2#12, 1#12G, 3/4"C	-	-	2
UH 1-12	EP104	120	1	25W	0.2A	ML2	2#12, 1#12G, 3/4"C	-	-	2
UH 1-13	EP104	120	1	25W	0.2A	ML2	2#12, 1#12G, 3/4"C	-	-	2
UH 1-14	EP104	120	1	25W	0.2A	ML1	2#12, 1#12G, 3/4"C	-	-	2
UH 1-15	EP104	120	1	25W	0.2A	ML1	2#12, 1#12G, 3/4"C	-	-	2
UH 1-16	EP104	120	1	25W	0.2A	ML2	2#12, 1#12G, 3/4"C	-	-	2
UH 1-17	EP104	120	1	1/20	2.2A	ML1	2#12, 1#12G, 3/4"C	-	-	2
UH 1-18	EP104	120	1	25W	0.2A	ML2	2#12, 1#12G, 3/4"C	-	-	2
UH 1-19	EP103	120	1	1/20	2.2A	AL1	2#12, 1#12G, 3/4"C	-	-	2
UH 2-1	EP105	120	1	25W	0.2A	PL10	2#12, 1#12G, 3/4"C	-	-	2
UH 2-2	EP105	120	1	25W	0.2A	PL10	2#12, 1#12G, 3/4"C	-	-	2
UH 2-3	EP105	120	1	25W	0.2A	PL10	2#12, 1#12G, 3/4"C	-	-	2
UH 2-4	EP105	120	1	1/20	2.2A	PL9	2#12, 1#12G, 3/4"C	-	-	2
UH 2-5	EP105	120	1	1/20	2.2A	PL9	2#12, 1#12G, 3/4"C	-	-	2
UH 2-6	EP105	120	1	1/20	2.2A	PL8	2#12, 1#12G, 3/4"C	-	-	2
UH 2-7	EP105	120	1	1/20	2.2A	PL8	2#12, 1#12G, 3/4"C	-	-	2
UH 2-8	EP105	120	1	1/20	2.2A	PL8	2#12, 1#12G, 3/4"C	-	-	2
UH 2-9	EP105	120	1	1/20	2.2A	PL8	2#12, 1#12G, 3/4"C	-	-	2
UH 2-10	EP106	120	1	25W	0.2A	PL7	2#12, 1#12G, 3/4"C	-	-	2
UH 2-11	EP106	120	1	25W	0.2A	PL7	2#12, 1#12G, 3/4"C	-	-	2
UH 3-1	EP107	120	1	1/20	2.2A	PL10	2#12, 1#12G, 3/4"C	-	-	2
UH 3-2	EP107	120	1	1/20	2.2A	PL8	2#12, 1#12G, 3/4"C	-	-	2
UH 3-3	EP107	120	1	1/20	2.2A	PL8	2#12, 1#12G, 3/4"C	-	-	2
UH 3-4	EP107	120	1	1/20	2.2A	PL7	2#12, 1#12G, 3/4"C	-	-	2
TF-1	EP102	120	1	-	4A	MDP	2#12, 1#12G, 3/4"C	30A	-	2

(SCHEDULE CONTINUED ON SHEET EP504)

- MECHANICAL, PLUMBING, AND MISCELLANEOUS EQUIPMENT WIRING SCHEDULE NOTES:
- INDOOR UNIT IS POWERED BY THE OUTDOOR UNIT.
 - PROVIDE MOTOR RATED TOGGLE DISCONNECT SWITCH.
 - [OPTION 3] PROVIDE.

GENERAL NOTES

- PROVIDE DISCONNECT AND STARTERS AS INDICATED IN THE SCHEDULE AND ON THE PLANS.
- COORDINATE DISCONNECT AND STARTER LOCATIONS IN THE FIELD TO PROVIDE CLEARANCES REQUIRED BY NEC. PROVIDE MIN 30 INCHES WIDE, 36 INCHES DEEP (120/208V) OR 42 INCHES DEEP (480V), AND 6 FOOT-7 INCHES HIGH WORKER CLEARANCE. REFER TO NEC 110.26.
- PROVIDE STARTERS, CONTACTORS, WIRING, AND ACCESSORIES AS REQUIRED TO ACHIEVE OPERATION AND SEQUENCE OF OPERATION PER THE CONTRACT DOCUMENTS.
- PROVIDE BRANCH CIRCUITS INDICATED IN THE SCHEDULES AND ON THE PLANS.
- PROVIDE FUSES. COORDINATE FINAL SIZES WITH EQUIPMENT PROVIDED.
- COORDINATE WITH THE HVAC CONTROLS INSTALLER AND PROVIDE CONDUIT FOR CONTROLS WIRING.
- PROVIDE FULL SIZE LIQUID TIGHT METAL FLEXIBLE CONDUIT ONLY FOR FINAL CONNECTION FROM STARTERS AND VFD'S TO MOTORS AND FROM DISCONNECTS TO VIBRATING EQUIPMENT AND MOTORS. MAXIMUM LENGTH OF LIQUID TIGHT METAL FLEXIBLE CONDUIT TO BE 6'.



APPROVED	
FOR COMMANDER NAVFAC	
ACTIVITY	
SATISFACTORY TO DATE	
DESIGNER	HRM
DRAWN BY	BPD
CHECKED BY	DCL
DESIGN MANAGER	T. CARLETON
PROJECT MANAGER	L. LYONS
FEADNAME	
FIRE PROTECTION	S. RUCINSKI
DEPARTMENT OF THE NAVY NAVAL FACILITIES ENGINEERING SYSTEMS COMMAND - MID-ATLANTIC ROCC-ME PORTSMOUTH NAVAL SHIPYARD KITTEERY, ME	
B60 REPAIRS	
MECHANICAL, PLUMBING, AND MISCELLANEOUS EQUIPMENT WIRING SCHEDULE	
PROJECT NO.: 1740579	
NAVFAC DRAWING NO.	
SHEET	257 OF 282
EP503	