

WebAIM Short Form TASK GROUP INSTRUCTION

21-JAN-2026 1550

20.15.6.0.9333 (July 2025)

ICN: 38K6112316 KeyOp: A01

TGI NO:	COMPONENT NAME: #3 GTG INTK & UPTK	TYPE: AY	PHASE: A	REPEAT: 0	CHG/VER: 0/0
SHIP/HULL NO: DDG-115	SHIP/HULL NAME: USS RAFAEL PERALTA	PROJECT: K61	SYSTEM:	PLANT ID:	CASREP CAT:
CU PHASE TITLE: F/O - PRESERVE NO. 3 SSGTG INTAKE AND EXHAUST TRUNK					
PREPARING ACTIVITY:		STATUS: APP		WORKING STATUS:	
PREPARED BY: HAYASHI, MOTONORI		CODE: 231B	PHONE: 3152436145	DATE: 24-NOV-2025	
APPROVED BY: TAKAGI, RYOUTA		CODE: 231B	PHONE: 3152434502	DATE: 24-NOV-2025	
CONCURRED BY:		CODE:	PHONE:	DATE:	
REASON FOR WORK/NEED FOR CHANGE: EM02L037 * EM04L038 * EM04L039					
JCN: EM02-L037 * EM04-L038 * EM04-L039					
SPECIAL REQUIREMENTS: TGI Short Form					
CU PHASE DESCRIPTION: 1 SCOPE/PURPOSE: 1.1 Title: No. 3 Ship's Service Gas Turbine Generator (SSGTG) Intake and Exhaust Trunk; preserve 1.2 Location of Work: 1.2.1 SSGTG Exhaust Trunk (1-370-2-Q) (Main Deck) (01 Level) 1.2.2 SSGTG Intake Trunk (1-388-2-Q) (Main Deck) (01 Level) 1.2.3 Passage (1-377-0-L) 1.2.4 Aviation Repair Shop (1-381-0-Q) 1.2.5 Generator Room (3-370-0-E) 1.3 Identification:					
ZONE MANAGER: SAITO, KAZUNOBU		ZONE:	COMPARTMENT:	LEVEL:	FRAME: SIDE:
JOB SUMMARY ID: 123A2116	TOT MAN HR.:	TOT DUR:	TOT JML COST:	PLANNING ACCEPTANCE:	

WORK CERTIFICATION SIGNATURES:	DLs												
COMPLETION OF WORK REVIEW:				BADGE NO:	SHOP/CODE:	PHONE:	DATE:						
RECORDS REVIEW:				BADGE NO:	SHOP/CODE:	PHONE:	DATE:						



WebAIM Short Form TASK GROUP INSTRUCTION

21-JAN-2026 1550

20.15.6.0.9333 (July 2025)

(Continued)

ICN: 38K6112316

KeyOp: A01

TGI NO:	COMPONENT NAME: #3 GTG INTK & UPTK	TYPE: AY	PHASE: A	REPEAT: 0	CHG/VER: 0/0
SHIP/HULL NO: DDG-115	SHIP/HULL NAME: USS RAFAEL PERALTA	PROJECT: K61	SYSTEM:	PLANT ID:	CASREP CAT:
CU PHASE TITLE: F/O - PRESERVE NO. 3 SSGTG INTAKE AND EXHAUST TRUNK					

CU PHASE DESCRIPTION (Cont.)

1.3.1 Quantity (1,100 SF), Entire Interior Structural Surface in 1-370-2-Q (Main Deck) (01 Level)

1.3.2 Quantity (1,370 SF), Entire Interior Structural Surface in 1-388-2-Q (Main Deck) (01 Level)

Remarks: The area excluding behind the bolts and nuts that secure the moisture separator.
The area excluding louver.

1.4 Security Classification: None.

1.5 Initial Condition:

1.5.1 Critical Coated Area: CCNY-DDG115-002-26 for the areas listed in 1.3.1 and 1.3.2

1.5.2 Potential Asbestos Hazard

1.6 Contractor Work start date: 7/27/2026

1.7 Contractor Work completion date: 9/4/2026

2 PROCEDURE:

2.1 Accomplish the requirements of Ref. No. 3. See 2.4.3 and 2.4.4

(V)(G) "GAS TURBINE MAINTENANCE PROCEDURE"

2.2 Accomplish the requirements of 009-032 of Ref. No. One, including Table 3, Line(s) 22A, for each area listed in 1.3.1, and Table 3, Line(s) 18A, for each area listed in 1.3.2.

2.3 Confirm that all personnel have exited the space prior to closure of the space listed in 1.2.1. Designate one person to account for all personnel who may have entered the space.

2.4 Notes:

2.4.1 Planner: Code 231B M. Hayashi, 243-6145
Planner: Code 232 Y. Watanabe, 243-2375
Planner: Code 233 S. Suzuki, 070-3769-2799
Planner: Code 234 Y. Yajima, 243-0977
Planner: Code 234 T. Nagashima, 243-4527

2.4.2 Work Integration Manager (WIM): Code 333 T. Yaginuma, 080-6522-9560

2.4.3 Step D.1 and D.2 of Ref. No. 3 is accomplished by SRF-JRMC (TGI No. 38K6112316R01).

2.4.4 Step F.2 of Ref. No. 3 is accomplished by SRF-JRMC (TGI No. 38K6112316U01).

2.4.5 JCNs EM02-L037, EM04-L038, and EM04-L039 are related to this TGI.

2.5 Government Furnished Material (GFM):

WebAIM Short Form TASK GROUP INSTRUCTION

21-JAN-2026 1550

20.15.6.0.9333 (July 2025)

(Continued)

ICN: 38K6112316

KeyOp: A01

TGI NO:	COMPONENT NAME: #3 GTG INTK & UPTK	TYPE: AY	PHASE: A	REPEAT: 0	CHG/VER: 0/0
SHIP/HULL NO: DDG-115	SHIP/HULL NAME: USS RAFAEL PERALTA	PROJECT: K61	SYSTEM:	PLANT ID:	CASREP CAT:
CU PHASE TITLE: F/O - PRESERVE NO. 3 SSGTG INTAKE AND EXHAUST TRUNK					

CU PHASE DESCRIPTION (Cont.)

- 2.5.1 SRF-JRMC will provide GFM listed in the Material List.
- 2.6 SRF-JRMC will provide the following service work: (TGI No. 38K6112316S02)
 - 2.6.1 [C740] Crane and crane rigger service.
 - 2.6.2 [X99E] Utility service, electrical.
 - 2.6.3 [X99M] Utility service, including water supply, and steam supply.
 - 2.6.4 [C106.1] Safety inspection for SRF-JRMC employees.
 - 2.6.5 [C106.2] Gas free inspection for SRF-JRMC employees.
 - 2.6.6 [C133] QA inspection for (G) symbol(s) and review of coating application data.
 - 2.6.7 [C285] Inspection for (G) symbol(s).

Ref. No.	Document/Drawing Number	DOCUMENT/DRAWING TITLE	REV	CHG NO.	CPY REQ	PARAGRAPH	SECT	PG	CHPT
----------	-------------------------	------------------------	-----	---------	---------	-----------	------	----	------

WebAIM Short Form TASK GROUP INSTRUCTION

21-JAN-2026 1550

20.15.6.0.9333 (July 2025)

(Continued)

ICN: 38K6112316

KeyOp: A01

TGI NO:	COMPONENT NAME: #3 GTG INTK & UPTK	TYPE: AY	PHASE: A	REPEAT: 0	CHG/VER: 0/0
SHIP/HULL NO: DDG-115	SHIP/HULL NAME: USS RAFAEL PERALTA	PROJECT: K61	SYSTEM:	PLANT ID:	CASREP CAT:
CU PHASE TITLE: F/O - PRESERVE NO. 3 SSGTG INTAKE AND EXHAUST TRUNK					

Ref. No.	Document/Drawing Number	DOCUMENT/DRAWING TITLE	REV	CHG NO.	CPY REQ	PARAGRAPH	SECT	PG	CHPT
1	NSI FY-26	NAVSEA Standard Items	-	1	N				
2	LI FY-26	Local Standard Items	-	ORG	N				
3	MP AL14-K6112316-EM04L039	No.3 SSGTG INTK FOD PROTN FOR PSV THE INTK TRK CMPT 1-388-2-Q/01-388-2-Q	-		Y			ALL	

TASK NAME / TASK DESCRIPTION	SHOP/ TSD	TS	SF WC	CREW #	MHRS	RWRK

MATERIAL REFERENCES			
REF NO.	DOCUMENT/DRAWING NUMBER	DOCUMENT/DRAWING TITLE	REV
1	MISC		

ICN: 38K6112316	KEY OP: A01
-----------------	-------------

MATERIAL LIST												
ITEM NO.	PC NO.	REF NO.	M / C	DESCRIPTION	STOCK NUMBER	GENERIC MATL TYPE	LVL	QA	HAZ MAT	DOC NO.	QTY REQD/ UNIT	QTY USED/ UNIT

WebAIM Short Form TASK GROUP INSTRUCTION

21-JAN-2026 1550

20.15.6.0.9333 (July 2025)

(Continued)

ICN: 38K6112316

KeyOp: A01

TGI NO:	COMPONENT NAME: #3 GTG INTK & UPTK	TYPE: AY	PHASE: A	REPEAT: 0	CHG/VER: 0/0
SHIP/HULL NO: DDG-115	SHIP/HULL NAME: USS RAFAEL PERALTA	PROJECT: K61	SYSTEM:	PLANT ID:	CASREP CAT:
CU PHASE TITLE: F/O - PRESERVE NO. 3 SSGTG INTAKE AND EXHAUST TRUNK					

MATERIAL LIST												
ITEM NO.	PC NO.	REF NO.	M / C	DESCRIPTION	STOCK NUMBER	GENERIC MATL TYPE	LVL	QA	HAZ MAT	DOC NO.	QTY REQD/ UNIT	QTY USED/ UNIT
001			M	INSULATI, INSULATION, ACOUSTIC, 24" X 36" X 2"THK, FIBER GLASS, FACED THERMAL AND SOUND ABSORBING FELT TYPE, MIL-DTL-32585 TYPE II FORM 2 FACING D (FORMER SPEC MIL-I-22023 TY-III), CLAREMONT MARINE INSULATION - TUFFSKIN 1613. DO NOT CROSS NSN 5640-01-509-0809 SMIC X3.	9Q 5640 LL4808709		NA	4	N	53297580	110/SH	
002			M	INSULATI, INSULATION, ACOUSTIC, 24" X 36" X 1"THK, FIBER GLASS, FACED THERMAL AND SOUND ABSORBING FELT TYPE, MIL-DTL-32585 TYPE II FORM 2 FACING D (FORMER SPEC MIL-I-22023 TY-III), TUFFSKIN 1613. ORIG: C-231B M.HAYASHI 243-6145 ORDERED FOR KTR	9Q 5640 LL4808710		NA	4	N	53287469	50/SH	
003			M	STUD,CAP, ORIG: C-231B M. HAYASHI 243-6145 ORDERED FOR KTR	9Z 5340 LL4945008		NA	4	N	53287477	800/EA	
004			M	TAPE,TEX, ORIG: C-231B M.HAYASHI 243-6145 ORDERED FOR KTR	9B 8315 002671632		NA	4	N	53285107	30/RO	
005			M	TAPE,TEX, ORIG: C-231B M.HAYASHI 243-6145 ORDERED FOR KTR	9B 8315 002671633		NA	4	N	53285151	10/RO	
006			M	ADHESIVE, ORIG: C-231B M.HAYASHI 243-6145 ORDERED FOR KTR	9B 8040 002738708		NA	4	Y	53285111	5/GL	
300			M	BACKSHELL KIT ASSY, BACKSHELL KIT ASSEMBLY, STRAIGHT COLD SHRINK, BIW CATALOG NO. 26266-815, ORDER FOR KTR ORIG: C226 K.YAMAMI, 080-9350-1447			NA	4	N		3/EA	
301			M	CONNECTOR,PLUG,ELEC, ORDER FOR KTR ORIG: C226 K.YAMAMI, 080-9350-1447	9B 5935 006222929		NA	4	N	53285146	1/EA	
302			M	CONNECTOR,PLUG,ELEC, ORDER FOR KTR ORIG: C226 K.YAMAMI, 080-9350-1447	9B 5935 011113576		NA	4	N	53285148	1/EA	
303			M	CONNECTOR,PLUG,ELEC, ORDER FOR KTR ORIG: C226 K.YAMAMI, 080-9350-1447	9B 5935 012594852		NA	4	N	53285152	1/EA	

WebAIM Short Form TASK GROUP INSTRUCTION

21-JAN-2026 1550

20.15.6.0.9333 (July 2025)

(Continued)

ICN: 38K6112316

KeyOp: A01

TGI NO:	COMPONENT NAME: #3 GTG INTK & UPTK	TYPE: AY	PHASE: A	REPEAT: 0	CHG/VER: 0/0
SHIP/HULL NO: DDG-115	SHIP/HULL NAME: USS RAFAEL PERALTA	PROJECT: K61	SYSTEM:	PLANT ID:	CASREP CAT:
CU PHASE TITLE: F/O - PRESERVE NO. 3 SSGTG INTAKE AND EXHAUST TRUNK					

MATERIAL LIST												
ITEM NO.	PC NO.	REF NO.	M / C	DESCRIPTION	STOCK NUMBER	GENERIC MATL TYPE	LVL	QA	HAZ MAT	DOC NO.	QTY REQD/ UNIT	QTY USED/ UNIT
304			M	CONNECTOR, PLUG, ELEC, ORDER FOR KTR ORIG: C226 K.YAMAMI, 080-9350-1447	9B 5935 012594853		NA	4	N	53285154	1/EA	
305			M	ADAPTER, ADAPTER STRAIGHT, COLD SHRINK BOOT TERMINATION, BIW CATALOG NO. 26296-501, ORDER FOR KTR ORIG: C226 K.YAMAMI, 080-9350-1447			NA	4	N		1/EA	
400			M	RUBBER S, ORIG: C234 Y.YAJIMA, 243-0977 ORDERED FOR KTR	9B 9320 002449277		NA	4	N	53285153	1/SY	
401			M	SHEET, P, SHEET, PERFORATED, 4FT X 8FT X 0.063"THK, CRES 316L, ASTM-A240, 3/16"DIA, PITCH: 3/8" ON STAGGERED CENTERS ORDERD FOR KTR C234 Y.YAJIMA, 243-0977	9B 9515 LL9603130		NA	4	N	53287478	20/SH	
402			M	INSULATI, INSULATION, ACOUSTIC, 24" X 36" X 2"THK, FIBER GLASS, FACED THERMAL AND SOUND ABSORBING FELT TYPE, MIL-DTL-32585 TYPE II FORM 2 FACING D (FORMER SPEC MIL-I-22023 TY-III), CLAREMONT MARINE INSULATION - TUFFSKIN 1613. DO NOT CROSS NSN 5640-01-509-0809 SMIC X3. ORDERED FOR KTR C234 Y.YAJIMA, 243-0977	9Q 5640 LL4808709		NA	4	N	53297581	135/SH	
403			M	INSULATI, INSULATION, THERMAL FELT, 2FT X 3FT X 2"THK, 1.5LB/QFT DENSITY, FIBROUS GLASS, MIL-DTL-32585 TYPE I FORM 2 FACING A (FORMER SPEC MIL-I-22023 TY-I CL-4), 10 SHEETS PER BOX. ORDERED FOR KTR C234 Y.YAJIMA, 243-0977	9Q 5640 LL9005023		NA	4	N	53297582	14/BX	
404			M	TAPE, PRESSURE SENSI, ORDERED FOR KTR C234 Y.YAJIMA, 243-0977	9Q 7510 015406777		NA	4	N	53285098	14/RO	
405			M	ADHESIVE, ORDERED FOR KTR C234 Y.YAJIMA, 243-0977	9B 8040 002738708		NA	4	Y	53285113	14/GL	
406		1	M	RUBBER SHEET, FLAT, 3/16"THK X 42"WIDE X 48"LG, MIL-PRF-2765, OIL RESISTANT, RUBBER, ORDER FOR KTR C234 Y.YAJIMA, 243-0977	9B 5330 LL9005091		NA	4	N		1/SH	

WebAIM Short Form TASK GROUP INSTRUCTION

21-JAN-2026 1550

20.15.6.0.9333 (July 2025)

(Continued)

ICN: 38K6112316

KeyOp: A01

TGI NO:	COMPONENT NAME: #3 GTG INTK & UPTK	TYPE: AY	PHASE: A	REPEAT: 0	CHG/VER: 0/0
SHIP/HULL NO: DDG-115	SHIP/HULL NAME: USS RAFAEL PERALTA	PROJECT: K61	SYSTEM:	PLANT ID:	CASREP CAT:
CU PHASE TITLE: F/O - PRESERVE NO. 3 SSGTG INTAKE AND EXHAUST TRUNK					