

3/10/2026 4:42:13 PM Q-601 C:\Users\mdonovan\Documents\22103_25_BLDG60_ARCHITECTURAL-V23_mdonovan\BVPXR.rvt

A

B

C

D

1

2

3 UNCLASSIFIED

4

5

BUILDING 60 EQUIPMENT SCHEDULE

BUILDING 60 EQUIPMENT SCHEDULE																					
EQUIPMENT TAG NO.	ALPHA NO. (SHIPYARD TAG)	QTY	DESCRIPTION	EXISTING LOCATION	UTILITIES												STATUS	MANUFACTURER	MODEL NUMBER	REMARKS	
					ELECTRICAL (SEE ELECTRICAL SHEETS)	SY AIR PSI	GAS	EXHAUST	EXHAUST TYPE	CFM	DUST COLLECTION	WATER	FIRE PROTECTION	DRAIN	STEAM	NRTL					FND
102D	-	16	CABLE PROTECTOR RAMP	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	NEW	ATLAS	CP9896	F
EQ100A	-	4	MEDIUM WEIGHT SEWING MACHINE	N/A	YES	65-75	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	NEW	JUKI	LU-1510N-7	A,B,H
EQ100C	-	1	LIGHT WEIGHT SEWING MACHINE	N/A	YES	65-75	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	NEW	JUKI	DDL 5550N	A,B,H
EQ100D	NDD, ENR, EWY, EXA, EXB, EYH, EYP, EQY, EYS, FAJ, OR FAS	8	LONG ARM SEWING MACHINE	OFF SITE	YES	65-75	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	EXIST	JUKI	LU-2216N-7	A,B,C
EQ100D	-	4	LONG ARM SEWING MACHINE	N/A	YES	65-75	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	NEW	JUKI	LU-2216N-7	A,B,H
EQ100E	NDD, ENR, EWY, EXA, EXB, EYH, EYP, EQY, EYS, FAJ, OR FAS	2	LONG ARM SEWING MACHINE - LG158	OFF SITE	YES	65-75	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	EXIST	JUKI	LG158	A,B,C
EQ101A	FPT, FPS, OR EXC	1	BOX STITCHER	OFF SITE	YES	65-75	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	EXIST	JUKI	AMS-210EN	A,B,C
EQ101A	-	1	BOX STITCHER	N/A	YES	65-75	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	NEW	JUKI	AMS-210EN	A,B,H
EQ102A	FFF	2	HEAT SEALER	OFF SITE	YES	100	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	CONC/PVMT	EXIST	THERMEX THERMATRON	F15-30	A,B,C
EQ102A	-	8	HEAT SEALER	N/A	YES	100	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	CONC/PVMT	NEW	THERMEX THERMATRON	F15-30	A,B,G
EQ102B	-	2	RF HEAT SEALER PEDESTAL	OFF SITE	N/A	N/A	N/A	YES	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	EXIST	THERMEX THERMATRON	M23933	A,B,C
EQ102B	-	8	RF HEAT SEALER PEDESTAL	N/A	N/A	N/A	N/A	YES	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	NEW	THERMEX THERMATRON	M23933	A,B,G
EQ104A	MVY, FHN, EPH, OR MXD	1	GROMMET MACHINE	OFF SITE	YES	80	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	LEVEL FLOOR	EXIST	EDWARD SEGAL	92GW	A,B,C
EQ104A	-	1	GROMMET MACHINE	N/A	YES	80	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	LEVEL FLOOR	NEW	EDWARD SEGAL	92GW	A,B
EQ105A	FPX	1	CNC FABRIC CUTTER	OFF SITE	YES	100	N/A	N/A	N/A	1500	N/A	N/A	N/A	N/A	N/A	N/A	LEVEL FLOOR	EXIST	GERBER INDUSTRIAL	Z1	A,B,C
EQ105A	-	1	CNC FABRIC CUTTER	N/A	YES	100	N/A	N/A	N/A	1500	N/A	N/A	N/A	N/A	N/A	N/A	LEVEL FLOOR	NEW	GERBER INDUSTRIAL	Z1	A,B,G
EQ105B	-	1	CNC BLOWER	OFF SITE	YES	N/A	N/A	YES	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	EXIST	GERBER INDUSTRIAL	Z1-15HP	A,B,C,E
EQ105B	-	1	CNC BLOWER	N/A	YES	N/A	N/A	YES	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	NEW	GERBER INDUSTRIAL	Z1-15HP	A,B,E,G
FSR	-	1	EMBROIDERY MACHINE	OFF SITE	YES	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	EXIST	MELCO	EMT16	A,B,C
GQU	ASJ	1	POLY BAG SEALER	OFF SITE	YES	80	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	EXIST	PAC MACHINERY	48PS-KN	A,B,C
GQU	-	1	POLY BAG SEALER	N/A	YES	80	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	NEW	PAC MACHINERY	48PS-KN	A,B
MC100B		20	SHOP BUILT TABLE - 8x3	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	SHIPYARD	CUSTOM	CUSTOM	D
MC100J		1	SHOP BUILT TABLE - 8X6	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	SHIPYARD	CUSTOM	CUSTOM	D
MC100K		2	SHOP BUILT TABLE - GERBER	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	SHIPYARD	CUSTOM	CUSTOM	D
MC102D		1	SHOP BUILT STORAGE - 10X4	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	SHIPYARD	CUSTOM	CUSTOM	D
MC103A		7	SEWING TABLE LARGE	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	SHIPYARD	CUSTOM	CUSTOM	D,B
MC103B		2	SEWING TABLE MEDIUM	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	SHIPYARD	CUSTOM	CUSTOM	D,B
MC103C		4	SEWING TABLE - MEDIUM LONG	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	SHIPYARD	CUSTOM	CUSTOM	D,B
MC103D		2	SEWING TABLE - SMALL	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	SHIPYARD	CUSTOM	CUSTOM	D,B
MC104A		1	LAYOUT TABLE 24'x8'	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	SHIPYARD	CUSTOM	CUSTOM	D
MC104C		1	LAYOUT TABLE - 24'X5'	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	SHIPYARD	CUSTOM	CUSTOM	D
MC105A		6	SHOP BUILT DIE RACK - 5X3	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	SHIPYARD	CUSTOM	CUSTOM	D
MS104G		22	HEAVY DUTY RACK - 6'X24"	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	NEW	GRAINGER	35UR59	A
MS104H		1	HEAVY DUTY RACK - 6'X36"	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	NEW	GRAINGER	35UR60	A
MS104K		7	HEAVY DUTY RACK - 8'X36"	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	NEW	GRAINGER	35UT09	A
MS106A		7	CABINET - SHELVES - 6'X24"X78"	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	NEW	GLOBAL INDUSTRIES	WBB495262	A
MS106I		2	CABINET - DRAWERS 30"X28"X59"	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	NEW	GLOBAL INDUSTRIES	WBB527756	A
MS107C		69	TOOL BOX - ROLLING BASE - 34"	OFF SITE	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	EXIST	GRAINGER	48VA11	A,C
MS107C		10	TOOL BOX - ROLLING BASE - 34"	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	NEW	GRAINGER	48VA11	A
MS108A		2	HAZARDOUS MATERIAL CABINET - SMALL	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	NEW	GRAINGER	55EA93	A
MS109A		6	CANTELEVER RACK	OFF SITE	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	EXIST	GLOBAL INDUSTRIES	WB248383L	A,C
MS109A		2	CANTELEVER RACK	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	NEW	GLOBAL INDUSTRIES	WB248383L	A
MS112A		4	CLOTH UNWINDING TRUCK - 102 INCHES	OFF SITE	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	EXIST	Southwest Sewing Machine LLC	125G	A,C
MS113A		2	PLASTIC WASTE CONTAINER	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	NEW	MCMASTER CARR	4052T11	A
MS119B		2	SHELVING - CLOSED - 36"x24"	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	NEW	MCMASTER CARR	4829T325	A
MVF		1	ROLL SLITTER	OFF SITE	YES	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	EXIST	COLLINS CRAFT	76-24AR	A,B,C
SP102A		12	EXTENSION CORD REEL (25' LENGTH)	N/A	YES	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	NEW	KH INDUSTRIES	RTBB3LB-1DD520-J12F	A,B
SP102B		9	EXTENSION CORD REEL (50' LENGTH)	N/A	YES	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	NEW	KH INDUSTRIES	RTBB3LB-1GB520-J12K	A,B
SP102C		9	COMPRESSED AIR REEL (50' LENGTH)	N/A	N/A	65-75	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	NEW	REELCRAFT	RS7650 OPL	A,B
SP103C		1	COMPUTER - STANDALONE	N/A	YES	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	SHIPYARD	N/A	N/A	B,D
SP103D		2	CNC - CONTROLLER	N/A	YES	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	GERBER INDUSTRIAL	N/A	A,B,I
WT103A		1	WORKBENCH - HARDWOOD TOP - 4'	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	NEW	GRAINGER	35UX04	A
WT103C		2	WORKBENCH - HARDWOOD TOP - 6'	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	NEW	GRAINGER	35UX07	A
WT103G		2	WORKBENCH - HARDWOOD TOP - 8'	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	NEW	GLOBAL INDUSTRIAL	WB183170	A

EQUIPMENT SCHEDULE GENERAL NOTES

1.

SEE SHEET G-007 FOR CONSTRUCTION SEQUENCING INFORMATION.
2.

SEE SHEETS QD101 THRU QD602 FOR EXISTING EQUIPMENT TO BE DISCONNECTED AND REMOVED.
3.

PATCH ANCHORAGE HOLES IN THE SLAB WITH NON-SHRINK GROUT ONCE THE EQUIPMENT IS REMOVED.
4.

COORDINATE EQUIPMENT LAYOUT WITH MECHANICAL, PLUMBING, FIRE PROTECTION, AND ELECTRICAL PLANS AND EQUIPMENT SCHEDULE.
5.

EQUIPMENT LOCATIONS ARE FOR PLANNING AND COORDINATION PURPOSES. THE CONTRACTOR IS RESPONSIBLE FOR INSTALLING THE INDUSTRIAL EQUIPMENT AS INDICATED AND IS RESPONSIBLE FOR COORDINATING THE RELOCATION OF EXISTING EQUIPMENT BY THE GOVERNMENT. COORDINATE SEQUENCING AND CONNECTION OF UTILITIES TO THE EQUIPMENT WITH THE CONTRACTING OFFICER.
6.

COORDINATE TESTING OF EXISTING EQUIPMENT TO BE RELOCATED TO CONFIRM WORKING CONDITION BEFORE AND AFTER RELOCATION. TESTS MUST BE WITNESSED BY SHOP REPRESENTATIVE AND COORDINATED WITH THE CONTRACTING OFFICER.
6.

SEE CIVIL, STRUCTURAL, ARCHITECTURAL, MECHANICAL, PLUMBING, ELECTRICAL, AND SPRINKLER SHEETS FOR EQUIPMENT UTILITY CONNECTIONS.
7.

PROCURE AND INSTALL EQUIPMENT STATUS MARKED "NEW" (EQUIPMENT TO BE PURCHASED BY THE CONTRACTOR).
8.

INSTALL EQUIPMENT STATUS MARKED "EXIST" (EQUIPMENT TO BE RELOCATED BY THE GOVERNMENT).
9.

COORDINATE AND PERFORM NEW EQUIPMENT MANUFACTURER'S STANDARD TESTING PROCEDURES.
10.

SCHEDULE INFORMATION IS BASED ON AVAILABLE INFORMATION AT THE TIME OF CONTRACT DOCUMENT PREPARATION. COORDINATE WITH CONTRACTING OFFICER FOR ADDITIONAL INFORMATION.

EQUIP SCHEDULE REMARKS NOTES

- A.

INSTALL EQUIPMENT AT FINAL LOCATION IN BUILDING 60.
- B.

PROVIDE INDUSTRIAL EQUIPMENT UTILITIES INDICATED. COORDINATE WITH MECHANICAL, PLUMBING, FIRE PROTECTION, AND ELECTRICAL SHEETS.
- C.

COORDINATE THE EQUIPMENT DISCONNECTION AND RELOCATION BY THE GOVERNMENT.
- D.

COORDINATE EQUIPMENT INSTALLATION BY GOVERNMENT.
- E.

EXHAUST TO SPACE. PROVIDE MANUFACTURER'S DUCT SILENCER AND COORDINATE WITH MECHANICAL SHEETS.
- F.

TURN EQUIPMENT OVER TO THE GOVERNMENT FOR STORAGE. COORDINATE STORAGE LOCATION WITHIN BUILDING 60 WITH THE CONTRACTING OFFICER.
- G.

THIS ITEM REQUIRES SOLE SOURCING AND IS NOT SUBJECT TO FULL AND OPEN COMPETITION. THIS ITEM IS NOT COMMERCIALY AVAILABLE "OFF THE SHELF", AND REQUIRES CUSTOMIZED MODIFICATION. SEE ATTACHED SPECIFICATION AND/OR MANUFACTURER'S QUOTE INDICATING EQUIPMENT OPTIONS AT THE END OF THIS PACKAGE.
- H.

THIS ITEM REQUIRES SOLE SOURCING AND IS NOT SUBJECT TO FULL AND OPEN COMPETITION. PROVIDE SPECIFIC MAKE, MODEL, AND CONFIGURATION INDICATED.

I. PROVIDED WITH CNC CUTTER - EQ105A

SCHEDULE KEY

B60 BUILDING 60
NEW CONTRACTOR PURCHASED AND INSTALLED EQUIPMENT
EXIST GOVERNMENT RELOCATED EQUIPMENT, CONTRACTOR INSTALLED
SHIPYARD SHIPYARD PROVIDED AND INSTALLED EQUIPMENT

PROJECT NO.: 1740579

NAVFAC DRAWINGS NO.

SHEET 161 OF 282

Q-601

DRAWING REVISION: 14 SEP 2023

DEPARTMENT OF THE NAVY
NAVAL FACILITIES ENGINEERING SYSTEMS COMMAND - MID-ATLANTIC
ROCK-CRME
PORTSMOUTH NAVAL SHIPYARD
KITTERY, ME

B60 REPAIRS

EQUIPMENT SCHEDULE (OPTION 2)



APPROVED
FOR COMMANDER NAVFAC
ACTIVITY
SATISFACTORY TO DATE
DESIGNER JMR
DRAWN BY MJD
CHECKED BY RSH
DESIGN MANAGER T. CARLETON
PROJECT MANAGER L. LYONS
HEADLINE
FIRE PROTECTION S. RUCINSKI



SEAL

APPROVED

FOR COMMANDER NAVFAC

ACTIVITY

SATISFACTORY TO DATE

DESIGNER JMR

DRAWN BY MJD

CHECKED BY RSH

DESIGN MANAGER T. CARLETON

PROJECT MANAGER L. LYONS

HEADLINE

FIRE PROTECTION S. RUCINSKI

NAVAL FACILITIES ENGINEERING SYSTEMS COMMAND - MID-ATLANTIC
ROCK-CRME
PORTSMOUTH NAVAL SHIPYARD
KITTERY, ME

B60 REPAIRS

EQUIPMENT SCHEDULE (OPTION 2)

PROJECT NO.: 1740579

NAVFAC DRAWINGS NO.

SHEET 161 OF 282

Q-601

DRAWING REVISION: 14 SEP 2023