

GENERAL CONSTRUCTION NOTES

1. FURNITURE, FIXTURES, AND EQUIPMENT (FF&E)
2. INDUSTRIAL EQUIPMENT
3. RADON FANS
4. SECURITY DEVICES
5. ADDITIONAL WINDOW RESTORATIONS
6. NOT APPLICABLE
7. ADDITIONAL ANNEX REPAIRS
8. ADDITIONAL FINISHES
9. ELECTRICAL SERVICE INFRASTRUCTURE
10. RESINOUS FLOORING
11. COMMUNICATION SERVICE ROUTING

ROOM NAME


ROOM 222

ROOM NUMBER

ROOM IDENTIFIER

SEE SHEET G-100.

1. COMPLY WITH STATE, FEDERAL, NATIONAL, AND OTHER CODES AND ORDINANCES THAT APPLY TO THIS PROJECT.
2. COMPLETE WORK IN ACCORDANCE WITH INDUSTRY STANDARDS AND PERFORM WORK IN A WORKMANLIKE AND PROFESSIONAL MANNER.
3. WHERE CONFLICTS EXIST WITHIN THE DOCUMENTS OR BETWEEN THE DOCUMENTS AND APPLICABLE CODES, ORDINANCES, OR INDUSTRY STANDARDS, THE MORE STRINGENT, AS DETERMINED BY THE CONTRACTING OFFICER, MUST BE PROVIDED AT NO ADDITIONAL COST TO THE GOVERNMENT.
4. MAINTAIN BUILDING EGRESS PATHS DURING THE ENTIRE CONTRACT PERIOD. PROVIDE TEMPORARY PATHS TO MAINTAIN BUILDING EGRESS. COMPLY WITH NFPA 241, STANDARD FOR SAFEGUARDING CONSTRUCTION, ALTERATIONS, AND DEMOLITION OPERATIONS.
5. MAINTAIN THE CONSTRUCTION SITE IN A SECURE, NEAT, WATER TIGHT, CLEAN, AND SAFE CONDITION DURING THE ENTIRE CONTRACT PERIOD. EXTERIOR ENVELOPE WORK MUST BE PERFORMED IN A MANNER TO MAINTAIN WEATHER TIGHTNESS.
6. PROVIDE ITEMS AND COMPONENTS SHOWN ON THE DRAWINGS UNLESS NOTED AS "EXISTING" (EXIST).
7. WORK FROM GIVEN DIMENSIONS AND LARGE SCALE DETAILS. DO NOT SCALE DRAWINGS.
8. DIMENSIONING SYSTEM: UNLESS OTHERWISE NOTED, PLAN DIMENSIONS ARE TO/FROM FINISHED FACE OF EXISTING WALLS, TO/FROM FACE OF FRAMING FOR STUD FRAMED WALLS, AND TO/FROM THE FACE OF MASONRY FOR MASONRY WALLS. DIMENSIONS INDICATED AS "CLEAR" (CLR) MUST BE MAINTAINED AND ARE MEASURED FROM THE FACE OF FINISH. CENTERLINE DIMENSIONS ARE INDICATED BY CENTERLINE SYMBOL (C).
9. LOCATE DOOR OPENINGS 6 INCHES FROM ADJACENT WALL (FACE OF FRAMING TO ROUGH OPENING), UNLESS OTHERWISE DIMENSIONED.
10. VERIFY EXISTING CONDITIONS AND DIMENSIONS AND REPORT DISCREPANCIES TO THE CONTRACTING OFFICER. PROCEED WITH THE WORK AFTER THE DISCREPANCIES HAVE BEEN RESOLVED BY THE GOVERNMENT.
11. DO NOT PENETRATE JOISTS, BEAMS, OR OTHER STRUCTURAL MEMBERS. OBTAIN WRITTEN APPROVAL FROM THE ENGINEER OF RECORD FOR UNAVOIDABLE PENETRATIONS OF STRUCTURAL MEMBERS.
12. PROVIDE SOLID BLOCKING BEHIND SURFACE APPLIED FIXTURES, TRIM, GRAB BARS, SHELVES, WOOD WALL BASE, BASE AND WALL CABINETS, MARKER BOARDS, TELEVISIONS, AND OTHER ACCESSORIES AND EQUIPMENT INCLUDING GOVERNMENT SUPPLIED ITEMS WHEN MOUNTED TO STUD WALLS.
13. DISPOSE OF AND/OR RECYCLE CONSTRUCTION DEBRIS FROM THE PROJECT SITE AS REQUIRED BY THE STATE OF MAINE AND AS REQUIRED BY THE CONTRACT. OBTAIN REQUIRED DISPOSAL PERMITS.
14. PROTECT EXISTING SYSTEMS AND SURFACES TO REMAIN. REPAIR OR REPLACE DAMAGE RESULTING FROM PROJECT OPERATIONS, AS APPROVED BY THE CONTRACTING OFFICER AT NO ADDITIONAL COST TO THE GOVERNMENT.
15. OBTAIN APPROVAL FROM THE CONTRACTING OFFICER FOR THE SEQUENCE AND TIMING OF OPERATIONS PRIOR TO COMMENCING WORK AND PER OUTAGE REQUIREMENTS DETAILED IN THE SPECIFICATIONS.
16. FIRESTOP CONDUIT/PIPE/DUCT PENETRATIONS THROUGH FIRE-RATED WALLS, CEILINGS, AND FLOORS. PROVIDE SMOKE BARRIER SEALANT AT FLOOR PENETRATIONS AND PENETRATIONS THROUGH SMOKE PARTITIONS.
17. DO NOT INTERRUPT UTILITY SERVICES WITHOUT AN APPROVED OUTAGE REQUEST. DO NOT RESTORE UTILITIES WITHOUT AN APPROVED 'ONAGE' REQUEST. REFER TO SPECIFICATION SECTION 01 14 00.00 22 WORK RESTRICTIONS (PWD ME) AND SHEETS G-008 AND G-009.
18. BUILDING 60 IS A HISTORIC FACILITY. PERFORM WORK IN COMPLIANCE WITH THE US DEPARTMENT OF THE INTERIOR "SECRETARY OF THE INTERIOR'S STANDARDS FOR THE TREATMENT OF HISTORIC PROPERTIES." HISTORIC ITEMS INDICATED OR SPECIFIED TO BE SALVAGED FOR REINSTALLATION OR TO REMAIN IN PLACE MUST BE PROTECTED DURING CONSTRUCTION.
19. WHEN ATTACHING FASTENERS, BLOCKING, OR ACCESSORIES TO EXISTING HISTORIC BRICK OR STONE, PLACE FASTENERS IN MORTAR JOINTS. EXCEPTION: LIGHTNING PROTECTION.
20. SYSTEMS AND THEIR ASSOCIATED CONDUIT MUST NOT PENETRATE HISTORIC FEATURES OF THE BUILDING (WINDOW AND DOOR SURROUNDS, STAIRWELLS, WOOD BASE, CRANE RAILS, ETC.). MAXIMIZE THE PLACEMENT OF CONDUIT IN SECONDARY SPACES WHERE PRACTICABLE.
21. PRIOR TO INSTALLING FIRE PROTECTION PIPING, MECHANICAL DUCTWORK, PIPING, ELECTRICAL CONDUIT, AND OTHER ASSOCIATED SYSTEM ELEMENTS, SUBMIT COORDINATION DRAWINGS AND OBTAIN APPROVAL BY THE CONTRACTING OFFICER AND THE PWD ME CULTURAL RESOURCES MANAGER. REFER TO SPECIFICATION SECTION 01 30 10.00 22 COORDINATION PROCEDURES AND COORDINATION DRAWINGS (PWD ME).
22. PROVIDE LIGHTNING PROTECTION SYSTEM TYPICAL. SEE ELECTRICAL SHEETS FOR INFORMATION.
23. ACCESS TO THE INTERIOR OF BUILDING 60 MUST BE VIA EXISTING OPENINGS IN EXTERIOR FACADE. UNDER NO CIRCUMSTANCES WILL NEW TEMPORARY OPENINGS BE ENTERTAINED AND MUST NOT BE INCLUDED AS BASIS OF BID.
24. CONTRACTOR MUST PROVIDE PAVEMENT AND ASSOCIATED SELECT SUB BASE FOR AREAS BEYOND THOSE IDENTIFIED ON THE CONTRACT DOCUMENTS THAT ARE IMPACTED AS A RESULT OF THE CONTRACTORS MEANS AND METHODS AS REQUIRED TO PERFORM THE CONTRACT SCOPE OF WORK.

																																																																																																																																																																																																							
---	--	---	--	---	--	---	--	---	--	---	--	---	--	---	--	---	--	---	--	---	--	---	--	---	--	---	--	---	--	---	--	---	--	---	--	---	--	---	--	---	--	---	--	---	--	---	--	---	--	---	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--