

SUMMARY OF ACM TO BE REMOVED

SUMMARY OF ACM TO BE REMOVED				
BUILDING MATERIAL	LOCATION	APPROXIMATE QUANTITY	EPA CATEGORY	ASBESTOS RESULTS
TAN FLOOR TILE WITH NON-ACM MASTIC LOCATED UNDER OTHER NON-ACM FLOORING	SECOND FLOOR, SOUTH CORRIDOR, TRAINING COORDINATOR CODE 970T OFFICE, CODE 970 TRAINING LEADERS OFFICE, KITCHEN/TRAINING ROOM, AND SHOP 76 OFFICES	3,300 SQUARE FEET	CATEGORY I NONFRIABLE	3% CHRYSOTILE
BROWN DUCT SEALANT	MEZZANINE, OVER PRODUCTION, STORAGE AND CHEM STORAGE ROOMS, AT SEAMS OF SQUARE DUCT	30 LINEAR FEET	CATEGORY II NONFRIABLE	6% CHRYSOTILE
TEXTURED SURFACING	THROUGHOUT FIRST FLOOR ON CEILINGS AND BEAM SURFACES, TO BE REMOVED WHERE NECESSARY FOR FASTENER/HANGER INSTALLATION AND OTHER NEW CONSTRUCTION	400 SQUARE FEET, COORDINATE WITH REMOVALS AND NEW WORK	FRIABLE ACM	3% CHRYSOTILE
PIPE INSULATION AND PIPE FITTING INSULATION	THROUGHOUT FIRST FLOOR MAIN ROOM TRENCHES, FIRST FLOOR MAIN ROOM ANNEX, AND MEZZANINE LOCKER ROOM	1,000 LINEAR FEET	FRIABLE ACM	5%-10% AMOSITE 10% CHRYSOTILE
PLASTER	FIRST FLOOR MEN'S BATHROOM SOUTHEAST WALL, WOMEN'S BATHROOM NORTHEAST WALL, MEZZANINE SOUTH CORRIDOR/OPEN OFFICE WALL, MEZZANINE NORTHEAST STAIR MID-LANDING SOUTH WALL, MEZZANINE NORTHEAST STAIR LANDING TO LOCKER ROOM EAST AND SOUTH WALLS, MEZZANINE LOCKER ROOM NORTHEAST WALL	2,500 SQUARE FEET	FRIABLE ACM	5% CHRYSOTILE
UNUSED CONTROL CIRCUIT WIRE	SECOND FLOOR PRODUCTION SHOP	100 LINEAR FEET		
ACM DEBRIS	THROUGHOUT FIRST FLOOR TRENCHES	1,400 SQUARE FEET	CATEGORY II NONFRIABLE AND FRIABLE ACM	1% CROCIDOLITE 1-20% AMOSITE 10-60% CHRYSOTILE
ACM & HEAVY METALS CONTAINING PAINT	ANNEX EXTERIOR ON BUTTRESSES	780 SQUARE FEET	CATEGORY II NONFRIABLE	0.46-0.56% ANTHOPHYLLITE
GRAY SEALANT	ANNEX EXTERIOR ON SIDING	50 SQUARE FEET	CATEGORY II NONFRIABLE	2.1% CHRYSOTILE
BLACK SEALANT	ANNEX EXTERIOR AT VERTICAL JOINT BETWEEN ANNEX AND BRICK	60 LINEAR FEET	CATEGORY II NONFRIABLE	5.5% CHRYSOTILE

1. ABATEMENT OF PAINT CONTAINING HEAVY METALS FROM BUILDING SURFACES: 200 SF (10 UNITS OF 20 SF)	8. ABATEMENT OF DUST/DEBRIS CONTAINING HEAVY METALS: 100 SF (5 UNITS OF 20 SF)
2. ABATEMENT OF ACM PIPE INSULATION: 50 LF (5 UNITS OF 10 LF)	9. PLM ANALYSIS SAMPLING: 10 EA (10 UNITS OF 1 EA)
3. ABATEMENT OF ACM PIPE FITTINGS: 10 EA (10 UNITS OF 1 EA)	10. TEM ANALYSIS SAMPLING: 10 EA (10 UNITS OF 1 EA)
4. ABATEMENT OF ACM JOINT COMPOUND: 50 LF (5 UNITS OF 10 LF)	11. RCRA 8 PAINT SAMPLING: 15 EA (15 UNITS OF 1 EA)
5. ABATEMENT OF ACM SEALANT: 50 LF (5 UNITS OF 10 LF)	12. RCRA 8 DUST SAMPLING: 10 EA (10 UNITS OF 1 EA)
6. ABATEMENT OF ACM FLOOR TILE AND MASTIC: 50 SF (5 UNITS OF 10 SF)	13. PCB SAMPLING: 10 EA (10 UNITS OF 1 EA)
7. ABATEMENT OF ACM DEBRIS IN TRENCHES: 50 LF (5 UNITS OF 10 LF)	

ACM SAMPLES COLLECTED

ACM SAMPLES COLLECTED						
SAMPLE ID	DESCRIPTION	ORGANIC (WT. %)	ACID SOLUBLE (WT. %)	ASBESTOS (WT. %)		OTHER NON-ASBESTOS (WT. %)
HG61C	DUCT SEALANT, GREY, INTERIOR, MEZZANINE OVER CARBON BLACK	58.76%	0	NONE DETECTED		41.24%
HG62C	DUCT SEALANT, GREY, INTERIOR, MEZZANINE OVER CARBON BLACK	73.32%	0	1.60%	CHRYSOTILE	25.07%
HG62B	DUCT SEALANT, GREY, INTERIOR, MEZZANINE OVER CARBON BLACK	-	-	NOT ANALYZED		-
HG62C	DUCT SEALANT, GREY, INTERIOR, MEZZANINE OVER CARBON BLACK	-	-	NOT ANALYZED		-
HG55A-A	ROOF CORE, ROLLED ASPHALT AND ISO, EXTERIOR, ROOF, EAST	64.13%	0%	NOT DETECTED		35.87%
HG55A-B	ROOF CORE, ROLLED ASPHALT AND ISO, EXTERIOR, ROOF, EAST	94.12%	0%	NOT DETECTED		5.88%
HG55B-A	ROOF CORE, ROLLED ASPHALT AND ISO, EXTERIOR, ROOF, CENTER	61.80%	0%	NOT DETECTED		38.20%
HG55B-B	ROOF CORE, ROLLED ASPHALT AND ISO, EXTERIOR, ROOF, CENTER	98.04%	0%	NOT DETECTED		1.96%
HG55C-A	ROOF CORE, ROLLED ASPHALT AND ISO, EXTERIOR, ROOF, ON LOWER ROOF	56.94%	0%	NOT DETECTED		43.06%
HG56A	ROOF CORE, ROLLED ASPHALT AND ISO, EXTERIOR, ROOF, AHU PITCH-POCKET, EAST	64.90%	0%	NOT DETECTED		35.10%
HG56B	ROOF CORE, ROLLED ASPHALT AND ISO, EXTERIOR, ROOF, AHU PITCH-POCKET, CENTER	68.54%	0%	NOT DETECTED		31.46%
HG56C	ROOF CORE, ROLLED ASPHALT AND ISO, EXTERIOR, ROOF, AHU PITCH-POCKET, WEST	66.75%	0%	NOT DETECTED		33.25%
HG57A	CAULKING, WHITE, EXTERIOR, ROOF, FLASHING, EAST	69.42%	0%	NOT DETECTED		30.58%
HG57B	CAULKING, WHITE, EXTERIOR, ROOF, FLASHING, WEST	68.07%	0%	NOT DETECTED		31.93%
HG57C	CAULKING, WHITE, EXTERIOR, ROOF, FLASHING, SOUTH	69.89%	0%	NOT DETECTED		30.11%
HG59A	DUCT CAULK, GREY, INTERIOR, MEZZANINE OVER CARBON BLACK	19.12%	0%	NOT DETECTED		80.88%
HG59B	DUCT CAULK, GREY, INTERIOR, MEZZANINE OVER CARBON BLACK	19.12%	0%	NOT DETECTED		80.88%
HG59C	DUCT CAULK, GREY, INTERIOR, MEZZANINE OVER CARBON BLACK	18.89%	0%	NOT DETECTED		81.11%
HG61	DUCT SEALANT, GREY, INTERIOR, MEZZANINE OVER CARBON BLACK	59.28%	0%	NOT DETECTED		40.72%
HG61B	DUCT SEALANT, GREY, INTERIOR, MEZZANINE OVER CARBON BLACK	58.42%	0%	NOT DETECTED		41.58%



		
		
		

OAK POINT
ASSOCIATES

APPROVED	
FOR COMMANDER NAIFAC	
ACTIVITY	
SATISFACTORY TO DATE	
DESIGNER	MJR
DRAWN BY	MJD
CHECKED BY	RSH
DESIGN MANAGER	T. CARLETON
PROJECT MANAGER	L. LYONS
FEAD/PM&E	
FIRE PROTECTION	S. RUCINSKI

DEPARTMENT OF THE NAVY NAVAL FACILITIES ENGINEERING SYSTEMS COMMAND - MID-ATLANTIC ROICC-ME	NAVAL FACILITIES ENGINEERING SYSTEMS COMMAND PORTSMOUTH NAVAL SHIPYARD - KITTERY, ME KITTERY, ME
PORTSMOUTH NAVAL SHIPYARD B60 REPAIRS	HAZARDOUS MATERIALS SCHEDULES 2

EPROJECT NO.:	1740579
NAVFAC DRAWING NO.	

SHEET 27 OF 282