



1. SEE SHEET AE101 FOR GENERAL NOTES.
2. B59 WILL BE OCCUPIED DURING CONTRACTING. COORDINATE WORK PLAN AND ACCESS WITH CONSTRUCTION OFFICER.
3. IN ADDITION TO THE AREAS INDICATED, PROVIDE 200 SF OF PATCH AND REPAIR WOOD FLOOR WORK FOR WORK NOT OTHERWISE INDICATED IN THE DRAWINGS. LOCATIONS TO BE COORDINATED WITH THE CONTRACTING OFFICER.

- 1 MEZZANINE PLATFORM AND STAIRS, SEE STRUCTURAL SHEETS.
- 2 PERIMETER EXPANSION JOINT, SEE DETAILS C1 AND C3 ON SHEET AE530.
- 3 INSTALL SALVAGED HISTORIC BORROWED LIGHTS.
- 4 REPAIR HISTORIC WOOD WINDOW/DOOR, SEE RESTORATION SCHEDULE ON SHEET AE622.
- 5 MECHANICAL DUCT WINDOW PENETRATION, SEE DETAIL C3/AE621 AND COORDINATE WITH MECHANICAL SHEETS.
- 6 3/4" PLYWOOD FLOORING OVER METAL DECKING.
- 7 PROVIDE BLOCKING IN STUD WALL FOR MECHANICAL EQUIPMENT AND SUPPORT BRACKETS, COORDINATE LOCATIONS WITH MECHANICAL SHEETS.
- 8 GUARDRAIL SYSTEM, SEE DETAIL A4/AE626.
- 9 GUARDRAIL SYSTEM, SEE DETAIL D1/AE445.
- 10 PROVIDE REMOVABLE SECTION OF GUARDRAIL.

1/8" = 1' - 0"



A horizontal graphic scale bar with a black and white checkered pattern. It is marked with the values 0, 5', 10', 15', and 30'.