

PPI #	PPI	Government Answer
01	Ref. Solicitation Document: Page 1 gives 548 days to complete where schedule section on Page 15 only gives 414 days. Page 9 of Attachment T shows 1080 calendar days. Please clarify the duration for the seed project at B60.	Refer to Amendment 0002 0004 and revised Attachment T
02	Ref. Solicitation Document: Page 9 stipulates 40% Small Business participation where Page 16 only requires 20%. Please clarify the Small Business participation percentage for the seed project at B60.	There is no discrepancy. 40% is a component of the NAVFAC command-wide target for small business subcontracting. These targets are based on a percentage of total planned subcontract dollars. The 20% in Factor 3 applies to the total contract value.
03	Factor 1, Corporate Experience, requires that projects submitted were completed within (7) years of the proposal due date. Larger projects, particularly those with a final construction cost in excess of \$50M and those involving complex waterfront work span several years (3-4) thereby making the 7-year window short for a contractor involved in this work to have applicable projects. We request that this window be extended to 15-years to capture recent and relevant Corporate Experience.	Propose in accordance with the Solicitation
04	Factor 1, Corporate Experience, requires that projects submitted are complete. We request that projects at least 75% complete be accepted.	Propose in accordance with the Solicitation
05	Factor 1B calls for the submission of design firm experience. Please identify all design firms that NAVFAC deems ineligible to participate on the proposing contractors' teams, due to their direct contracting with NAVFAC.	The Government will not provide guidance in the development of proposals. Any concern of potential organizational conflicts of interest should be explained in offeror's proposals.
06	Ref. Solicitation Document Page 7 #3. Proposal Submission and Pre-proposal Inquiries. Section ends with 'Contractors should ensure that...' Please finish this sentence.	Refer to Amendment 0002
07	Ref. Solicitation Document Page 7 #3. Proposal Submission and Pre-proposal Inquiries. PPI are due by January 30, 2026 however proposals are due almost 5 weeks later. Please extend the due date for PPI to February to give bidders reasonable time to submit questions.	Refer to Amendment 0002
08	Ref. Solicitation Document Page 1. Proposals are due March 07, this is a Saturday. Please confirm this is correct.	Refer to Amendment 0002
09	Ref. Solicitation Document Page 32. Includes DFARS 252.7012, .7019, .7020 however none of the documents are labeled CUI or indicated to be controlled. Please confirm none of the contract is considered CUI.	Confirmed. The contract is not CUI.
10	Ref. 01 11 00.00 22 Par. 1.3.1 Indicates commencement of this contract is contingent on other ongoing projects. Please confirm what date the Government expects these contract(s)	Delete second sentence under paragraph 1.3 Period performance starting with "The mobilization date..". Replace paragraph 1.3.1 with the following: Contractor to mobilize no

	will be completing for material and labor pricing and schedule development for this proposal.	sooner than 45 calendar days after award and start construction activities no sooner than 90 calendar days after award. Pricing and schedule shall be developed accordingly.
11	Ref. 01 11 00.00 22 Par. 1.3.1 Describes a Post Award Meeting to review timelines and review proposed path forward. How does this meeting differ from the Preconstruction Meeting shown in 01 30 00.00 22?	Revise paragraph 1.3.1 as noted in response to PPI 10 (removes reference/requirement for Post Award Meeting). Also Delete "Post Award Kickoff (PAK)" from section 01 31 23.13 20 paragraph 1.6.8. Provide Preconstruction Meeting as indicated in specifications.
12	Ref. 01 33 29.00 22 Par. 1.5.3.2.a Prelim Sustainability eNotebook. Submit...at the first post award meeting in accordance with Section 01 30 00.00 22 ADMINISTRATIVE REQUIREMENTS (PWD ME). The Post Award Meeting is not detailed in 01 30 00.00 22. Please provide more information about this meeting.	Post Award Meeting is not required. Refer to responses to PPI 10 and 11. Prelim Sustainability eNotebook must be submitted at Preconstruction Meeting.
13	Ref 01 14 00.00 22 Par 1.2.a Tier 1 Infrastructure. Please provide the list of facilities that require additional work restrictions and procedures to be worked on or in the vicinity of. Please provide the restrictions and procedures. Please provide what constitutes in the vicinity of a Tier 1 Infrastructure.	a) Tier 1 Infrastructure includes: EW(12") Water line under building from Water Tower. Refer to revised sheets SB101 and SB102. b) Restrictions & procedures: Refer to spec 01 14 00.00 22 Paragraph 1.10 c) What constitutes 'within the vicinity of Tier 1 Infrastructure': Refer to spec 01 14 00.00 22 Paragraph 1.10 and see item 'a' above.
14	Ref 01 14 00.00 22 Par 1.4 Special Scheduling Requirements. It is unclear what is expected of the contractor in sub-paragraphs a & b. Par. b requires outages to be submitted 30 days prior to interruption where paragraph a only requires submission 15 days prior. Please clarify these requirements.	See revised specification section 01 14 00.00 22 for clarification.
15	Ref 01 14 00.00 22 Par 1.4.c Special Scheduling Requirements. ...See the Scope of Work to determine if the project limits include any security Island in or adjacent to the work area. Please confirm where this information is located in the contract documents.	See revised specification section 01 14 00.00 22 for clarification. Secure areas include work within Buildings 59, 13, and 86.
16	Ref 01 14 00.00 22 Par 1.4.d Special Scheduling Requirements. Coordinate the work with the sequencing/phasing requirements outlined in the Scope of Work Memo and as outline in the Construction Drawings. Please confirm where the Scope of Work Memo is located.	See revised specification section 01 14 00.00 22 for clarification. Section has been updated to reference construction drawings and specifications. See also <i>general sequencing info on Sheet G-007</i> .

17	Ref 01 14 00.00 22 Par 1.5.5.a Outage Requirements ...Outages involving Tier 1 Shipyard Infrastructure require a specific Risk Analysis and Risk Mitigation Plan as outlined in Paragraph herein entitled TIER 1 SHIPYARD INFRASTRUCTURE REQUIREMENTS. Please confirm where this paragraph is in the specifications.	Outages involving Tier 1 Infrastructure require a specific Risk Analysis and Risk Mitigation Plan as outlined in Section 01 35 26, paragraph 3.9.4, titled Excavating with Hazardous or Tier 1 Utilities Within the Excavation Area and under Section 01 14 00.00 22 paragraph 1.10 titled TIER 1 INFRASTRUCTURE RISK ANALYSIS (RA) AND RISK MITIGATION PLAN (RMP). Refer to revised specification section 01 14 00.00 22 for additional information
18	Ref 01 14 00.00 22 Par 1.5.5.a Outage Requirements ...Any Outage requests denied due to incomplete stakeholder alignment or information required to support the requested outages, will not be justification for a delay claim. The denial of an outage for alignment of stakeholders is not in the control of the contractor. Please confirm if the contractor submits the (9) items listed lower in the paragraph in advance of the outage it will satisfy the requirements for outages.	Confirmed. See revised specification section 01 14 00.00 22 for clarification. Text has been updated to reflect that if the required items contain "incomplete information" denial will not be justification for a delay claim.
19	Ref 01 14 00.00 22 Par 1.8.9 and 1.8.10 None of the contract documents have been labeled or designated CUI. These paragraphs limit the information to the Contractor's organization only but dissemination to subcontractors and vendors is necessary for this proposal. Please confirm the contract documents can be shared with other entities to support this proposal.	Refer to PPI 9 response - The contract is not CUI and documents can be distributed accordingly.
20	Factor 1, Corporate Experience, notes that projects submitted for the Offeror shall have been completed within the previous (7) years of the proposal due date for this RFP. The RFP seems to indicate that projects of large scale may be contemplated. Large projects generally have durations of 4 – 8 years. As such, very few large projects would qualify with a only a 7 year reach-back period. For such large project solicitations, it is common for the Government to allow a reach-back period of 15 years. In order to show a company's true capabilities, we request that the 7 year completion requirement be revised to 15 years.	Propose in accordance with the Solicitation
21	Factor 1 also requires projects be completed to qualify as relevant. Please consider allowing completed projects or projects that are at least 75% complete; or consider allowing projects in which the associated relevant portion of the work has been complete if the project is still ongoing.	Propose in accordance with the Solicitation
22	The RFP is silent on whether or not any Design Firms would be prohibited in participating on a team due to a conflict of interest. If the Government foresees any Designers not being	The Government will not provide guidance in the development of proposals. Any concern of potential organizational conflicts of interest

	eligible for participation on a team in response to the RFP, please provide the names of those conflicted out.	should be explained in offeror's proposals
23	Page 1 and page 30 of the RFP solicitation calls for a 548 day contract duration where Schedule section on page 15 calls for 414 days. Please clarify which duration applies to the overall contract period.	Refer to the changes included in Amendment 0004.
24	Factor 1 (1B) Design Experience instructs the offeror to use the "Construction & Design Experience Project Data Sheet (Attachment A)" for design experience. However, the Attachment A provided with the solicitation "Construction Experience Project Data Sheet" is only for construction projects, does not identify DES 1 to DES 5 at the top row, and does not include Block 8 that is usually reserved for design project information. a) Please clarify and provide the relevant Construction & Design Experience Project Data Sheet (Attachment A) that is mandatory to be used for both the design and the construction projects.	Please refer to the revised Attachment A provided with Amendment 0004.
25	The page limitation for each construction project is defined as 4 pages, whereas the page limitation for each design project is defined as 2 pages. Please confirm the page limitation for each Construction Project and each Design Project presented in Factor 1.	Confirmed. The page limitations are as stated in the Solicitation.
26	RFP page 8 states "information is not required to be completed under Section 00 10 00 - Solicitation Contract Form in SF 1442." a) Shall the offeror still include the Section 00 10 00 - Solicitation Contract Forms in the proposal, but enter "Not Applicable" in the cells for Unit Rate and Amount of the Base and Option periods? b) Alternatively, shall the offeror only provide the completed Attachment T Price Schedule form in this section?	Propose in accordance with the Solicitation
27	Item (vii) of the Price submission requirements identifies the Small Business Subcontracting Plan is required, but refers to details under the "ADDITIONAL INFORMATION TO BE SUBMITTED WITH PRICE PROPOSAL PACKAGE." Please confirm the Small Business Subcontracting Plan shall be presented under "Additional Information for Responsibility Determination" and not under item (vii)	Confirmed.
28	Factor 1, RFP page 11, Para 5 states "Offerors proposing as a JV shall submit a signed JV agreement." a) In which Factor and section shall the executed JV agreement be provided? b) Please confirm the JV agreement is not page counted.	Offerors should submit the executed JV agreement with the non-price proposal. It will not count towards the page limitations.
29	Para 1 states "... Offeror is required to identify the design firm (Architect/Engineering firm) to be utilized as Designer of Record (DOR) on anticipated future projects. Provide the full name of the firm, address, Unique Entity Identifier (UEI), and	a) Factor 1 b) Factor 1

	CAGE code. The Offeror must provide supporting documentation (such as a signed joint venture agreement, partnership agreement, teaming agreement, or letter of commitment on the proposed DOR's letterhead) demonstrating agreement by the proposed design firm to perform as DOR for the duration of this MACC." a) In which Factor and section shall the offeror place the executed agreement or letter of commitment for its proposed DOR? b) In which Factor and section shall the DOR's name, address, UEI, and CAGE code be presented? c) Please confirm the DOR agreement and the DOR company information are not page counted.	c) Confirmed.
30	The primary solicitation PDF and each Amendment 0001 and 0002 PDFs issued so far are of a secured nature such that they do not allow the offeror to find key words or to copy information, potentially impacting proposal compliance. Since the contract is not CUI, as clarified in Amendment 02, will the Government remove the security setting for any future amendment files?	Propose in accordance with the Solicitation.
31	when the original sources sought attached to this solicitation was issued in June 2025 under N6247024R0057rev1 the qualifying \$ amount for a single project was \$20mil. Would the Government entertain lowering the new single project requirement of \$50mil to \$25mil to allow those whom showed interest in this MACC originally to qualify? Although there appears to be a strong SB % requirement it does appear that this solicitation is favoring large business due to this new threshold.	Propose in accordance with the Solicitation.
32	Will NAVFAC consider providing a design stipend at 1% of the estimated construction cost, to offset proposal development burdens and encourage robust industry competition. Currently the US Army Corps of Engineers, and the Baltimore District in particular, are offering a 1% design stipend for design build type solicitations.	Propose in accordance with the Solicitation.
33	Please provide solicitation documents with text searchable content for ease of solicitation review and proposal development.	Propose in accordance with the Solicitation.
34	Please confirm that two PDF documents should be submitted as part of this proposal and named accordingly as listed below: 1.) Price Proposal 2.) Non-Price Technical Proposal	Propose in accordance with the Solicitation.
35	Paragraph 2 is missing from section 5.	Please refer to the changes included in Amendment 0004.
36	Please clarify what specific data should be included for projects listed in the Price Proposal under "Other offeror's work presently under contract".	Offerors shall provide a list of ongoing projects, to include the final value, duration, and geographical location of each project.
37	Please consider allowing projects substantially completed at 90% or greater to be included in past performance experience	Propose in accordance with the Solicitation.

	submissions to provide the Government with the most recent project experience that is relevant to the solicitation.	
38	Please identify what Factor or section an Offeror's JV agreement should be provided in the proposal.	An offeror's JV agreement should be provided with the non-price proposal.
39	(1A) Construction Experience states Attachment A is limited to two (2) double-sided pages (or four (4) single-sided pages) (1B) Design Experience states Attachment A is limited to one (1) double-sided pages (or two (2) single-sided pages) The page limitations for Attachment A differ as listed above. Please clarify the correct page limitations for Attachment A is two (2) double-sided pages (or four (4) single-sided pages) for Construction and Design experience.	Please refer to the revised Attachment A provided with Amendment 0004.
40	Please clarify the TRC rate calculation should be Number of TCR Incidents x 200,000 / Total Number of Employee Labor Hours Worked. The division operation appears to have been left out of the calculation equation.	Confirmed. Please refer to the revisions included in Amendment 0004.
41	Please increase the Factor 3 Management Approach page limitations to 10 single-sided pages to allow offerors the capability to fully describe our understanding of the requirements and management approach.	Please refer to the revisions included in Amendment 0004.
42	Will NAVFAC consider allowing offerors to only submit a PDF of the P6 schedule and remove the requirement for the native .xer file?	Please refer to the revisions included in Amendment 0004.
43	"The solicitation states ""the Offeror may receive a deficiency if firm commitments with subcontractors are not provided..."" Please clarify if Offerors required to include a copy of the commitment letter within Factor 5 for each subcontractor company listed in the SBPCD in order to demonstrate firm commitments?"	Offerors are not required to provide copies of their firm written commitment documents for each of the small business subcontractors identified on Attachment E, Small Business Participation Commitment Document (SBPCD). Please refer to the revised Attachment E provided with Amendment 0004.
44	Attachment A, Box 7 & 8 The instructions above Box 7 indicate that box 7 is to be completed for construction projects and box 8 is completed for design projects. Please clarify that Box 7 and 8 is required for both Construction and Design projects.	Please refer to the revised Attachment A provided with Amendment 0004.
45	Attachment A, Project No. Box: This section only provides boxes for Construction projects and does not provide a way to identify Design projects #1-#5.	Please refer to the revised Attachment A provided with Amendment 0004.
46	Please identify the anticipated total contract value offerors should utilize in the Small Business Subcontracting Plan for the Base Period, Option Period 1 and Option Period 2.	The value of the base and option periods should reflect the associated percentage of the total contract value.

47	Please clarify that there is no Option Period 3 or Option Period 4 on this MACC which is listed on page 13 of Attachment E.	Please refer to the revised Attachment F provided with Amendment 0003.
48	On page 7 of the RFP, it states that "proposals are to be submitted via the PIEE Solicitation Module." We are not able to locate this solicitation on PIEE. Will the Government please provide the PIEE link to the solicitation?	The PIEE link is now available and will remain available for proposal submission within the PIEE Solicitation Module
49	"Factor 5 - Small Business Participation and Utilization under item 1 states, ""Each project submitted under Factor 1, Corporate Experience, shall be included on Attachment D."" Typically such subcontracting information is only requested for the Construction Experience portion of the factor (not Design) since the Construction Experience represents the Offeror responsible for the management of the subcontracting program. Please confirm that Attachment D is only required for Construction Experience projects."	Please refer to the changes included in Amendment 0004 and to the revised Attachment D provided with Amendment 0004.
50	If an Offeror files VETS 4212 reports for multiple hiring regions, please confirm if all report confirmations should be included in the proposal, or only the report confirmation which corresponds to the region of the project.	Propose in accordance with the Solicitation.
51	On page 12 of the RFP, it states that Attachment A is required for response to Factor 1. Within Attachment A it states, "Complete Box 8 for Design Projects." Box 8 contains the detailed description of the project and the relevancy to the project requirements for both construction and design experience. Please clarify if there is a box missing.	Please refer to the revised Attachment A provided with Amendment 0004.
52	Attachment D instructions at the top of page one states <i>"supporting information for the evaluation of Factor 3"</i> . Factor 3 is Management Approach. Please clarify that Att D supports the evaluation of Factor 6, Small Business Utilization and Participation.	Please see the revised Attachment D included in Amendment 0004. Attachment D supports the evaluation of Factor 5, Small Business Utilization and Participation
53	The period of performance listed in the specifications is 608 calendar days. However the Amendment 2 solicitation, under Factor 4, states the POP is 548 calendar days. Please clarify.	Please refer to the changes included in Amendment 0004.
54	Factor 3, Management Approach (ii) Basis of Evaluation states <i>"An Offeror's <u>narrative work plan</u> that identifies risks for the seed project and provide potential mitigation solutions may be considered more favorably than those that do not."</i> Factor 3 instructions do not ask for Offeror's to provide a narrative work plan. Please clarify that this sentence applies to Factor 4, Schedule where risks and mitigations are discussed.	Please refer to the changes included in Amendment 0004.
55	Page 1 of the Solicitation - Section 13 states "Sealed offers in original and 1 copies to perform the work required are due at the place specified in Item 8....." Item 8 is currently left blank.	Item 8 is intentionally blank, as offers will be received electronically. Confirmed. Hard copy submissions will not be accepted. Please submit proposals in accordance with the

	Page 7 of the Solicitation 00 21 00 - Section 3 states "Proposals are to be submitted via the PIEE Solicitation Module. Hard Copy Delivery or facsimile submission will not be accepted." Please confirm hard copy of originals/ copies are not required and response shall be submitted electronically.	Solicitation revisions included in Amendment 0004.
56	Please advise if a date/ time for site visit been established?	Refer to Amendment 0003.
57	Factor 1B - Please confirm that we are allowed to have more than one Designer of Record on our team for this very large, very diverse MACC pursuit.	Confirmed. Please refer to the changes included in Amendment 0004.
58	Specification states: "Base Bid: the Government has estimated that the onsite contract work contingent upon the completion of current ongoing projects which have an estimated completion time of late summer 2026. Please confirm this specification section is intended to state 548 in accordance with the updates made in Amendment 0002.	See response to PPI #1
59	Specification states to provide coating inspector and protective coatings specialists for 09 97 13. 16 Interior coating of welded steel water tanks and 09 97 13.27 High performance coating for steel structures. The referenced specifications are not included for this project. Please confirm coating inspector and protective coating specialists are not required as it is not applicable for this project.	Confirmed. Protective costing specialists indicated for sections 09 97 13.16 and 09 97 13.27 are not applicable to this project.
60	Specification section 01 14 00.00 22 states "a. Do not release to anyone outside the Contractor's organization any unclassified information, regardless of medium (e.g., hard copies, computer files, film, tape, document), pertaining to any part of this Contract or any program related to this Contract, unless the Contracting Officer has given prior written approval. b. Requests for approval under paragraph (a) must identify the specific information to be released, the medium to be used, and the purpose for the release. Submit the request to the Contracting Officer at least 10 business days before the proposed date for release. c. The Contractor agrees to include a similar requirement, including this paragraph (c), in each subcontract under this Contract. Subcontractors must submit requests for authorization to release through the Prime Contractor to the Contracting Officer." Please confirm it is acceptable that all documents publicly available can be shared outside of Contractors organization for bidding purposes. Please also confirm all subcontractors can	Confirmed. The contract is not CUI.

	release publicly available information to sub-tier vendors and suppliers for bidding purposes.	
61	Specification states "Identify all activities in the Baseline NAS with its respective Drawing Code. The Drawing Code is the Sheet Number on the primary project drawing which indicates work to be performed. If an activity does not have an applicable Drawing Code (e.g., Mobilize), the code must be "0000"." Please advise if drawing codes are required for the schedule which will be submitted with the solicitation response.	Drawing codes are not required for the schedule which will be submitted with the solicitation response.
62	The documents included within the solicitation do not seem to provide order of precedence for the documents in the event of a conflict. Please provide an order of precedence.	Propose in accordance with the Solicitation.
63	Drawings do not indicate spray foam. Specifications not "stud work, attic, and eave as indicated." Please confirm where spray polyurethane foam work will take place.	Spray foam insulation will be limited to ancillary work for sealing openings, penetrations, etc. as part of insulated metal panel work.
64	• On sheet SP101 it shows the columns, and beams rated for 1HR of protection. • In the 07 81 00 spec section 1.4.2 it says 2HR rating. • On sheet G-100 it lists the building as a Type IIIB building which doesn't require fireproofing. Please clarify the fireproofing scope of work.	Provide fireproofing as indicated on sheet SP101. This includes 1-HR fireproofing at the new columns and beams supporting the fire pump room and existing steel beams and portion of wood joists at the existing northeast stair. Revise specification 07 81 00 Fire Rating Schedule to indicate 1-Hr rating. Note: Provide fireproofing, sealing, and firestopping as required at fire rated partitions that are indicated in contract drawings and specifications.
65	This specification section notes the requirement for complex systems. It also provided examples of equipment meeting and not meeting the Complex System Definition. Packaged Terminal Air-Conditioners are noted as not being complex systems. Are we to assume Split System Air conditioner is not a complex system, and thus would not need to be commissioned?	The ductless split system does need to be commissioned, being part of the HVAC systems.
66	On Sheet P-102, it shows Sanitary Vent piping being installed inside Elevator Machine (001A) that does not serve Elevator Machine (001A) or Elev (001). Please confirm this piping is allowed per Maine Elevator Code.	Sanitary line is to be installed within the stud wall cavity and not within the Elevator Machine Room. Applicable elevator code is ASME A17.1 as referenced in Specification 14 24 23.
67	Under (1B) Design Experience on page 12 of 63 of the solicitation, it is indicated that the DOR is to use the Attachment A for their Previous Experience however Attachment A is only for the Construction Experience. Please provide another attachment for the Designers Previous Experiences. thank you	Please refer to the revised Attachment A provided with Amendment 0004.

68	Please confirm if copies of the written, firm commitments with the small businesses are to be included with our proposal and in Factor 5. thank you	Offerors are not required to provide copies of their firm written commitment documents for each of the small business subcontractors identified on Attachment E, Small Business Participation Commitment Document (SBPCD). Please refer to the revised Attachment E provided with Amendment 0004.
69	Under Factor 1, Corporate Experience, Construction Experience it reads that projects submitted "shall have been completed within the previous seven (7) years of the proposal due date for this RFP. If discussions are required, the initial proposal submission date will be the date used to determine if projects were completed within the previous seven (7) years of the proposal due date of this RFP. and not any revised proposal due date." Please confirm that even if the proposal due date moves via Amendment, the original proposal due date listed on the RFP is the date used.	The due date of initial proposals, subject to any extensions issued via amendment, is the relevant date.
70	Factor 1, Corporate Experience requires the Construction Experience projects to be completed in the previous seven (7) years of the proposal due date for this RFP while the Design Experience requires design to be completed within the previous eight (8) years. Please confirm that the Construction Experience and Design Experience have different recency requirements versus both being 7 or 8 years.	Confirmed. Propose in accordance with the Solicitation.
71	Factor 1 Corporate Experience for Construction Experience reads that Construction Experience Project Data Sheets are not to exceed 4 single-sided pages, and the Design Experience Project Data Sheets are not to exceed 2 single-sided pages. Please confirm that the Construction and Design Project Data Sheet page limits are different and remain 4 single-sided pages for construction and 2 single-sided pages for design.	Confirmed. Propose in accordance with the Solicitation.
72	Factor 4, Schedule requires submission of the native (.xer) files with the proposal. These cannot be submitted via PIEE. Please confirm that we are to email this file to the contracting officer.	Please refer to the changes included in Amendment 0004.
73	Factor 5, Small Business Utilization reads to submit Attachment D for each project submitted under Factor 1. Please confirm that this is for only the projects submitted under Construction Experience only.	Please refer to the changes included in Amendment 0004 and to the revised Attachment D provided with Amendment 0004.
74	Factor 6, Past Performance reads that if no completed CPARS is available a PPQ is to be submitted. Please confirm that a "completed" CPARS can be an Interim CPARS if the project is completed and used for its final intended purpose but a final CPARS is not yet available.	Confirmed. Interim CPARS are acceptable if the final is not yet available
75	The latest three complete fiscal year financial statements are required in the Price Volume. It reads "Offerors are not required to submit financial information as detailed in the price submission instructions via PIEE. However, if this is the case, the submitted copies in the hard copy proposal must be received	Confirmed. Please refer to the changes included in Amendment 0004.

	no later than the established due date and time". Please confirm that hard copies are the Price and Non-Price proposals are not required.	
76	Section 00 21 00 says that "Proposals are to be submitted via the PEE Solicitation Module." When this solicitation is searched within PEE, it returns no results. Please confirm that this Solicitation is to be submitted via PEE and that the project page will be active at time of submittal.	The PEE link is now available and will remain available for proposal submission within the PEE Solicitation Module
77	For Design Experience it reads "Projects submitted for the DOR shall have had design completed within the previous eight (8) years of the proposal due date for this RFP. Please confirm that for Design Experience, only Design needs to be fully complete, and that construction can still be in progress.	Confirmed. Regarding projects submitted for design experience, only design needs to be fully complete, and construction can still be in progress.
78	In the Solicitation under [00 70 00] both FAR 52.225-9 - Buy American-Construction Materials and 52.225-11 Buy American-Construction Materials under Trade Agreements are incorporated by Full Text, but these are alternate clauses. Please confirm FAR 52.225-11 applies to the SEED Project Contract.	FAR 52.225-11 is incorporated and applies to the Seed Project.
79	Would you consider lowering th mininun of 1 project final; condtruction cost from \$50,000,000 to \$35,000,000 Our largest completed project to date had a final cost of \$34,194,441 this was N4008520C0025, DBB BQ 488, NAVALSUBMARINE BASE, NEW LONDON, CT which was awarded to us in May 15, 2020 we feel counting for the high increase costs in construction this same project if bid today would have a cost of way over \$50,000,000. This Building was 109,442 Gross SF this would be roughly \$330 per SF We are currently performing another Navy awarded in August 17, 2023 for \$36,246,142 this building is only 78,000 gross sf or roughly \$465 per SF these buildings are similar to each other. This would be an increase in SF costs of \$45 per sf for each of the 3 years between awards. So if I was to follow the \$45 increase per sf cost for 6 years it would be \$270 or a total of \$600 per sf so or 2020 project if bid today would be roughly \$65,000,000 We ask you to consider this as we would not be eligible to bid on this program without some consideration, we are currently working at PNSY and have finished other projects on that base and believe we are well liked by that construction office	Propose in accordance with the Solicitation.
80	The solicitation indicates that proposals are to be submitted via the PEE Solicitation Module. The solicitation cannot be found in PEE. Please confirm when the solicitation will be posted to PEE and if future amendments will be posted to PEE and/or SAM.gov.	The PEE link is now available and will remain available for proposal submission within the PEE Solicitation Module. All updates / amendments to the solicitation will be posted to SAM.gov.

81	An organized site visit is projected to be scheduled for the seed project and <i>"to be provided via amendment"</i> per the solicitation. Given the uncertainty of the site visit date and pending amendment, please consider extending the RFI closing period to be 3 business days following the date of the site visit to allow post site visit questions to be submitted.	Refer to Amendment 0003
82	Ref. Solicitation PPI Due Date: With the sitewalk scheduled for February 5, bidders and participating small businesses will need at least two weeks after the site visit to submit effective PPI. Currently the due date is February 6. Please extend the due date for PPI to accommodate the questions generated from the site visit.	Please refer to the changes included in Amendment 0004.
83	Ref. Solicitation Proposal Due Date: Due to the complexity of the seed project and the vastly differing corporate experience and past performance requirements, bidders must balance the complicated estimates with minor small business participation to date all with formulating the non-pricing factors. Also, there are important PPI still not answered that will change the pricing and schedule narrative. Please extend the proposal due date to April 7 to afford bidders the opportunity to gain more small business participation, assemble corporate experience and receive outstanding PPI responses to incorporate into the bid pricing.	Propose in accordance with the Solicitation.
84	Factor 3 Management Approach narrative is limited to only 4 pages. More space is warranted for the offeror to fully and effectively address the required four elements defined in item (i) and meet item (ii) basis of evaluation to demonstrate best value. As a reference, NAVFAC Solicitation N4008525R2507 (DB/DBB MACC MCI East AOR) allocates ten pages to address just three of the four elements required in this RFP, which affords ample space to fulfill each item. Will the Government follow the same approach by increasing the page count for the Factor 3 narrative from four pages to ten pages, allowing the offeror to effectively feature its management approach for this solicitation?	Please refer to the changes included in Amendment 0004.
85	(ii) Basis of Evaluation, para 2 states "An Offeror's narrative work plan that identifies risks for the seed project and provides potential mitigation solutions may be considered more favorably than those that do not." Should this statement be moved to the basis of evaluation for Factor 4, Schedule, where this topic applies? Please clarify.	Please refer to the changes included in Amendment 0004.
86	Box 1. in Attachment A requests the offeror to provide its DUNS Number for each Experience. The DUNS Number is no longer used. Other parts of the proposal require the offeror's Unique Entity Identifier (UEI), including the Executed SF1442. a) Will the Government replace "DUNS number" to "UEI" on	Please refer to the changes included in Amendment 0004.

	Attachment A? b) Shall the offeror enter the UEI instead of DUNS on Attachment A?	
87	RFP page 16 of 63, item 2., 3rd para/bullet states "To demonstrate maximum practicable participation of small businesses, identify (in terms of dollar value and percentage of the total contract value) the offeror's proposed small business participation." a) Please confirm that all dollars values and percentages detailed in Attachment E SBPCD, including Item 3.a) and Table on page 2 are based on a Total contract value (TCV)(including options) of \$4,000,000,000, which is the TCV of this solicitation. b) If the Attachment E SBPCD is required to be completed for the Seed Project value, then the contractor will only be able to provide accurate values if the Attachment E if it is due several days after the proposal is submitted. This practice is consistent with a variety of NAVFAC MACC and SIOP solicitations, such as NAVFAC Northwest N4425525RF014, RM25-4869 Seismic Repair Dry Dock 4, B704 PSNS, WA. Will the Government revise the due date such that the Factor 5 Attachment E SBPCD may be submitted within three business days after the main proposal due date?	a) Confirmed. b) Propose in accordance with the Solicitation.
88	a) Please confirm that all dollars values and percentages detailed in Attachment F Individual Small Business Subcontracting Plan, including Item 1.a) [Page 4 and Page 13] are based on a Total contract value (TCV)(including options) of \$4,000,000,000, which is the TCV of this solicitation. b) RFP Section 00 10 00 table indicates the MACC consists of a Three-Year Base Period (CLIN 0001) and two one-year Option Periods (Option Line Item 0002 and 0003). Please confirm the first five columns on Page 13 of Attachment F should be revised to Base Period 1 - Base Period 3, Option Period 1 - Option Period 2.	a.) Confirmed. b.) Please refer to the revised Attachment F included in Amendment 0004.
89	The deadline for submitting questions (6 February 2026) is only one day after the site visit. To provide offers to fully evaluate the site walk information for developing the technical solution and best value pricing, will the Government extend the deadline for pre-proposal inquiries to 20 February 2026, which leaves 14 days prior to the proposal due date?	Please refer to the changes included in Amendment 0004.
90	Will offerors be required to propose on every MACC Task Order?	No. Please refer to the changes included in Amendment 0004.
91	Congress recognized the unique financial risks faced by contractors working in locations with aged infrastructure and many unknown and unforeseen challenges when it included Section 2816 in the recently passed National Defense Authorization Act for Fiscal Year 2026. This section authorizes the use of Cost-Plus-Incentive-Fee (CPIF) contracts for certain	Propose in accordance with the Solicitation.

	military construction projects at all four public shipyards. This update has the effect of expanding the number of contractors allowed by their shareholders to bid on SIOP military construction projects, increasing competition and benefiting the Navy. Question: Would NAVFAC be amenable to including a CLIN allowing for CPIF contracts to be awarded under this MACC?	
92	Attachment A - Construction & Design Experience Project Data Sheets provided with the solicitation only include check boxes for Construction projects 1-5. Can the Government provide a revised Attachment A form that includes corresponding check boxes for projects submitted for Factor 1B – Design Experience?	Please refer to the revised Attachment A included with Amendment 0004.
93	Page 13 of the solicitation states that five years of safety data must be submitted: 2020, 2021, 2022, 2023, 2024. Should 2025 data also be submitted?	Propose in accordance with the Solicitation.
94	Line Item 3A on the pricing schedule shows a Government Estimated price of \$1,695,370. Please confirm this estimated price only accounts for procurement and installation of the new industrial equipment.	Confirmed. See PPI 119 response and see amended Price Schedule.
95	Amendment 0002 extended the Pre-Proposal Inquiry (PPI) deadline to 06 February 2026. We respectfully request that the PPI deadline be extended to 15 business days prior to the submission date for a revised date of 13 February 2026 to ensure that both the prime and subcontracting community has sufficient time to submit technical PPI's related to the Seed Project.	Please refer to the changes included in Amendment 0004.
96	Amendment 0003 included Site Walk Information instructing visitors needing passes to make an appointment at Pass & ID through the QLESS app. As many prime and subcontractors who plan to attend the Site Walk will not be local to Kittery and will be traveling in for the Site Walk and as there is extremely limited appointment availability on 4 February 2026 and the morning of 5 February 2026, please confirm there will be sufficient walk-in access to support the visitor pass needs of the Site Walk contractors the morning of 5 February 2026.	Offerors are responsible for compliance with the requirements detailed within Amendment 0003.
97	Will the Government please allow the use of an 11x17 size page for the presentation of the Factor 3 Organizational Chart?	Yes. Please refer to the changes included within Amendment 0007.
98	Please confirm that the Government is not expecting a full project schedule with the submission of Factor 4, and that a milestone schedule containing items A through E (on page 15) is sufficient.	Propose in accordance with the Solicitation.
99	FX400, note 11 states 8" incoming from underground supply but the drawing does not indicate how much of this piping is existing for reuse. Please confirm we are to cut at the nearest flange at the wall and start from that location.	The 8" pipe entering the building will be new. See sheet G-100 for approximate location of the start of the new pipe and refer to the exterior utility work outlined on CS101.

100	Please provide as-built drawings of the current fire protection system that requires removal.	There are no as-built drawings available. Entire existing sprinkler system will be demolished throughout the building under this contract per Fire Sprinkler Note 3 on FX001. Sheet FX001 is hereby amended, see continuation sheet.
101	Keynote 8 on Drawing AE102 states to refinish wood plank flooring per Option 8 but the limits of this keynote are unclear. Please provide a quantity for this work or clearly define the extent of the keynote.	Refer to amended sheet AE102 with dimensions.
102	Sign Type K Detail on AE131 calls for 12 signs associated with 12 Fire extinguishers on the project, but there are 14 fire extinguishers in the FFE plans. Please confirm the GC is to provide 14 fire extinguishers and 14 Type K signs.	Provide 15 fire extinguishers and associated type K signs. See amended FF&E Package and Sheet AE804.
103	Specification 104416 calls for surface mounted fire extinguisher cabinets where shown, but all fire extinguishers on the FFE plans are bracket mounted. Please confirm no Fire extinguisher cabinets are required.	Confirmed that fire extinguisher cabinets are not required. Section 10 44 16 is hereby amended to delete the requirement.
104	MD102: Under Keynotes, "CLIN002" is referenced. Per the new Price Schedule this is Option 1: FF&E. Please verify all work on this drawing sheet should fall under CLIN 01D. Please also see sheet MD106 where CLIN 002 is referenced.	Items indicated on MD102 and MD106 with CLIN 002 tags pertain to the existing industrial equipment removals included in CLIN 002. Items identified in construction documents as "CLIN 002" must be priced under item 1H in the Price Schedule. Refer to amended Price Schedule and amended sheets MD103, MD106, MD108, and MD109.
105	MP101: Keynote 1 appears under the Keynotes section with no text. Please provide the description for this keynote or confirm it is not used.	Sheet MP101 is hereby amended at Keynote 1 to read "LOCATE THERMOSTAT 48" ABOVE FINISHED FLOOR" and add appropriate keynote tags.
106	MP102: Keynote 7 appears under the Keynotes section with no text. Please provide the description for this keynote or confirm it is not used.	Sheet MP102 is hereby amended at keynote 7 to read "NOT USED".

107	MP107: Keynote 2 states that HWS/R piping is to be on stanchions secured to continuous structural channel rails running from HWS/R risers to Attic Unit Heater 3-1. The structural channel rail does not appear on the mechanical or structural sheets. Please provide a detail of this and show the structural channel on the plan.	Refer to amended drawings MP107, SF105, and SF506 for support detail information.
108	23 05 93-1.6 requires a Workmanship and performance warranty for the DALT and TAB system Work for 2 years and a Contractor installation warranty of 2 years. Please confirm "Contractor" in this case refers to the installing mechanical contractor.	The required 2-year installation Warranty is to be provided by the General Contractor.
109	The Schedule of Fire Protection Systems Inspections by FPQC Specialist after Specification 014500.0022 does not have boxes checked showing which tasks to perform. Please indicate which of these tasks are required inspections that the FPQC must provide.	Specification Section 01 45 00.00 22 is hereby amended for the checklist attachment to reflect the required actions.
110	Keynote 3 on SF102 says to reference notes on sheet G-003. Please confirm the correct reference is to sheet G-004A.	On Sheet SF102, Keynote 3 is hereby amended, deleting reference to "G-003". Replace to read "G-004A"
111	Keynote 3 on SF102 says "base bid on 60 lf of total crack repair between all (3) locations". However, there are 5 different locations where keynote 3 comes up on SF102. Please confirm that 60lf is still the correct qty to include in the base bid.	Bid per solicitation. There are only three locations tagged for "Keynotes" (3) showing new work, which is different from Existing Keynotes number (3) showing existing conditions.
112	Please confirm if quantities provided under "Approximate Masonry Restoration Quantities (Project Totals)" section on AE202 are the only items we are to include pricing on for exterior masonry repairs. Please confirm quantities provided on AE202 also include any patch/repair work required that are shown on AD201-AD203 as well.	Sheet AE202 is hereby amended to clarify that the quantities indicated under Approximate Masonry Restoration Quantities (Project Totals)" include masonry repairs on Sheets AE202-AE204. Additional quantities for work associated with removals per Removals Keynotes on sheets AD201 through AD203 are not included in the Approximate Masonry Restoration Quantities but must also be included in Base Bid pricing.
113	Rooms 201 and 206 show an existing beadboard ceiling but the Finish Schedule does not list any paint requirements. Please advise if we are to provide a P4 finish in these rooms similar to other rooms with existing beadboard ceiling.	Bid per solicitation. Per Keynote 5, Sheet AE704, " IN AREAS WHERE BEADBOARD CEILING HAS TRANSPARENT, CLEAR COAT FINISH, REMOVE DUST, DIRT OIL, AND GREASE, RINSE THOROUGHLY. [OPTION 8]" Most of the existing beadboard ceiling has

		been painted, but in areas where it hasn't (rooms 201 and 206) the original unpainted finish is to be preserved.
114	Section 014500.0022 Part 1.6 states that the FPQC cannot serve as the Special Inspector for fireproofing or firestopping which is not typical for NAVFAC projects. Please revise this section to allow the FPQC to serve these roles if they meet the qualifications for those inspections.	Bid per solicitation, Section 1.6.7.2 does not prohibit the FPQC from being the fire stopping inspector.
115	The Offeror has a strong history performing Department of Defense federal construction work, with primary experience in vertical construction projects. The Offeror is currently engaged in active DoD work within the region and is highly interested in competing for the referenced Multiple Award Construction Contract (MACC). The RFP solicitation includes resume and past performance requirements that reference work types such as wharf and dry dock construction, which are not services typically performed by all general contractors pursuing vertical construction work under this MACC. Please clarify whether an Offeror that does not meet the specific resume requirements associated with wharf and dry dock work would be eliminated from consideration for award under this MACC. The Offeror intends to pursue this MACC for vertical construction task orders and requests clarification to confirm eligibility and proposal expectations.	Propose in accordance with the Solicitation
116	Can additional geotechnical and boring information be provided? Based on the specification sections referenced, it seems additional information is available at it states: "The data are available for examination by prospective bidders in the office of the Contracting Officer." Additional information regarding the top of rock elevation is needed in order to understand the full scope of the micropiling requirements.	Drawings include the available Geotech and boring information. Specification 00 01 15 is hereby amended to delete paragraphs 1.3 BORING LOGS and 1.4 SUBSURFACE DATA.
117	Please see page SB401 Details A1, A2, B2, and C3. The steel pipe micropiles are called out to be galvanized but there is no reference to this in the specifications. What exactly is to be galvanized? Please provide clarification.	Sheet SB401 is hereby amended to delete the requirement to galvanize the steel casings since they are required to be designed with an extra 1/16-inch wall thickness to account for corrosion loss.
118	The price schedule (attachment T - Item 1AA) is indicating micropiles to be bid at 60 LF for 36 piles meaning each pile is less than 2ft in length. Is this correct?	The linear foot quantity of micropiles must be determined from the contract drawings based on the information provided (embedment length into ledge, height from the indicated ledge elevation to bottom of pile cap elevation, and embedment length into

		the pile cap). This total would be the base bid quantity to be carried in line item 1B. Line Item 1AA is no longer applicable. See updated Price Schedule.
119	Attachment T - Please advise if option 3A and 3B are flipped, and that the Government estimated price is for "...including installation of government procured and provided equipment and associated utilities.." and that the contractor is to provide an estimate for "...procurement/installation of new equipment..."	Item 3A must include provisions for the procurement and installation of new industrial equipment. Item 3B must include provisions for installation of government procured and existing industrial equipment as well as utilities associated with new and existing industrial equipment.
120	Please clarify if the roof being removed at the annex is ACM?	The Government's Hazardous Materials Survey Report, dated November 21, 2024, is included with the RFP documents and details the inspection, sampling, and testing of the Annex roof, which was conducted in accordance with MEDEP Chapter 425. Laboratory analysis of collected samples did not identify the presence of asbestos. For bidding purposes, the Annex roof shall be considered non-asbestos containing material. The Contractor remains responsible for all environmental sampling and work practices as required by the contract documents and all applicable regulations.
121	Sheet FA001 Note 9 notes that existing fire alarm system shall be maintained until the new fire alarm system has been installed, tested and accepted by NAVFAC Fire Protection Engineer and Engineer of Record. Since the building will be unoccupied during the course of the renovation, can this note be removed?	Sheet FA001 is hereby amended, revising Note 9 to read: "Provide NFPA 241 plan for fire alarm and fire protection measures during construction prior to the removal of existing systems"
122	Please confirm if this project is tax-exempt in the State of Maine?	Propose in accordance with the Solicitation. Offerors are responsible for their own compliance with any applicable taxes.
123	On the Equipment Removal Schedule 2 Sheet equipment tags Number 555 and 556 are listed as "Composite Pallets". Please	Items 556 and 557 on Sheet QD602 are identified as Composite Pallets. For bidding purposes assume removal

	list any materials or equipment on these pallets that will need to be removed and disposed of .	of pallets without additional equipment or materials.
124	Cold Formed Metal Framing is not specified as delegated design but requires specific drawing requirements. Will the CFMF shop drawings be required to be stamped by a PE and complete as a delegated design?	Requested information is within the documents. Price per solicitation. The cold-formed metal framing is not a delegated design. Shop drawings are required to be submitted to reflect the 05 40 00 structural cold-formed metal framing shown on the contract drawings but are not required to be stamped.
125	Metal panels are to be attached to existing structure. Please confirm all imposed loads by the metal panels onto the existing structure have been reviewed by the EOR and no further structural reinforcement of the existing structure is required.	Requested information is within the documents. Price per solicitation. The existing structure can support the imposed wind loads. No reinforcement of the existing steel framing is required, beyond the structural work shown in the documents for other purposes.
126	Please see key note #5 on HM102. Abatement and removal based on this directive is not quantifiable to an abatement contractor. In order for a complete bid a fixed quantity should be assumed. Can a quantity be provided to be included within the bid?	Requested information is within the documents. Price per solicitation. On sheet HM604 refer to schedule "SUMMARY OF ACM TO BE REMOVED" for quantities.
127	Drawing CS101 key note 22 identifies ductbank connection to AC801. Detail B4 - C502 depicts a general connection into the manhole. Has the existing conditions within the manhole been investigated? Can the new ductbank penetrations fit within this manhole. Is there existing infrastructure or racking that requires relocation to support the new infrastructure?	Requested information is within the documents. Price per solicitation. Existing manhole AC801 was investigated, and record documentation was reviewed to generate the elevations on Detail B4/C502. There is nothing on this manhole face that requires relocation.
128	Please clarify/ locate what exterior elements that contribute to base security, supervision, and access which must remain active.	Requested information is within the documents. Price per solicitation. Maintain access routes as indicated on Sheet G-006 as well as exterior site lighting unless otherwise provided by temporary security lighting that meets the requirements of the construction documents.

129	Pricing schedule items 1K, 1L, 1M, 1N, 1O, 1P, 1Q, 1R, 1S, 1T, 1X, 1Y, 1AA, 1BB, 1CC, 1DD, 1EE, 1FF, 1GG, identifies varies lines items with assigned quantities: 1) Will these items will be tracked as unit prices to the assigned quantities. 2) Shall the bid only include the quantities listed within the pricing schedule, or are these additional quantities, beyond what is identified in the documents? Please clarify the intention of the quantities and unit prices within the pricing sheet.	1. Yes, items 1K through 1GG will be tracked as unit prices. 2. These quantities as noted on updated drawings are for additional scope not otherwise indicated in the plans, specifications or reports provided with the solicitation. See revised Price Schedule and revised sheets HM604, CS101, SD101, SD102, SF502, AE105, and AE704.
130	Please confirm if B-1 of the boring log located on B-001 represents the conditions where the micropiles are to be installed.	Refer to specification 31 63 29, paragraph 1.6, borings are representative of the area in which the boring was conducted and is not representative of other areas. Refer to the response to PPI 116 for additional rock/ledge information.
131	Att. S FFE Package and the Building 60 Equipment Schedule found on Q-601 do not align with each other. There are 27 “contractor purchased and installed equipment” but 25 are listed in Att. S. Items are missing on the equipment schedule that are in the Att. S file and vice versa. Please advise which list to follow when bidding out the contractor purchased and installed equipment.	•Provide (16) Cable Protector ramps as indicated in updated FF&E attachment. See updated Equipment Schedule Sheet Q601. •Provide (2) Haz Mat cabinets (MS108A) as indicated in updated Equipment schedule Q-601. See updated FF&E attachment. •Delete Equipment item SP103D as it is included with the purchase of the CNC Cutter (EQ105A). See updated Equipment schedule sheet Q-601. •Delete Equipment item WT100A. See updated FF&E attachment.
132	Drawing G004A - list CLIN's 001 - 004 and 11 option line items (1-11). Pricing schedule Attachment T does not seem to include CLIN 002-003. Please clarify and update the documents accordingly.	Sheets G-004A and G-004B are hereby amended. Refer to continuation sheet and updated Price Schedule.
133	Solicitation Amendment 0004, Section 00 21 00, Para 2.(a)(1) Price Submittal Requirements; Section 00 10 00 - CLIN Schedule; Attachment T - Price Schedule AMD 0004 Amendment 0004 states the offeror is required to submit a complete Price Proposal Form that includes completion of all	No pricing is required in section 00 10 00.

	contract line-item numbers (CLINs), and that pricing information is not required to be completed under Section 00 10 00. Amendment 0004 revised the descriptions for CLIN 0001 (Base Period), Option Line Item 0002 (Option Period One), and Option Line Item 0003 (Option Period Two) to identical language but removed the associated period dates. Attachment T (Price Schedule AMD 0004) only includes CLINs for the B60 seed project. Please clarify what pricing, if any, is required to be submitted for CLIN 0001, Option Line Item 0002, and Option Line Item 0003 under Section 00 10 00, given that Attachment T addresses only the seed project.	
134	Solicitation Amendment 0004; Attachment F - Individual Small Business Subcontracting Plan AMD 0004, Attachment 1. Attachment 1 of the Small Business Subcontracting Plan (Attachment F) requires a breakdown of subcontracting goals by Base Period, Option Period 1, and Option Period 2. Since this is an IDIQ contract with no guaranteed dollar values per period beyond the \$10,000 minimum guarantee, please clarify how offerors should complete the dollar values and percentage goals in Attachment 1 for each contract period. Should offerors estimate projected contract values per period, use the B60 seed project value for the Base Period and leave option periods blank, or apply another methodology?	Refer to PPI #46
135	Can the Government please provide a Geotechnical report for this project?	See PPI 116 response.
136	The solicitation states: Responsibility Determination Information - In order to be eligible for award, the offeror must be determined responsible in accordance with FAR Part 9, specifically 9.104-1, General Standards. FAR Part 9, 9.104-1 General Standards includes: To be determined responsible, a prospective contractor must- (a) Have adequate financial resources to perform the contract, or the ability to obtain them (see 9.104-3(a)); (b) Be able to comply with the required or proposed delivery or performance schedule, taking into consideration all existing commercial and governmental business commitments; (c) Have a satisfactory performance record (see 9.104-3 (b) and subpart 42.15). A prospective contractor shall not be determined responsible or nonresponsible solely on the basis of a lack of relevant performance history, except as provided in 9.104-2; (d) Have a satisfactory record of integrity and business ethics (for example, see subpart 42.15); (e) Have the necessary organization, experience, accounting and operational controls, and technical skills, or the ability to obtain them (including, as appropriate, such elements as production control procedures, property control systems, quality assurance measures, and safety programs applicable to materials to be produced or services to be performed by the prospective contractor and subcontractors). (See 9.104-3(a).) (f) Have the necessary production, construction, and technical equipment and facilities, or the ability to obtain them (see 9.104-3(a)); and	Confirmed.

	(g) Be otherwise qualified and eligible to receive an award under applicable laws and regulations (see also inverted domestic corporation prohibition at 9.108). Please confirm that a response to all items in FAR Part 9, 9.104-1 (a) - (g) are not required and that the Government only requires Offerors to provide items 1-5 listed in the solicitation.	
137	Factor 3, Management Approach, the solicitation submittal requirements include the Organizational Structure in both narrative and chart form. It is understood that Offeror shall detail the Organizational Structure for the overall MACC program. However, it is unclear if the Organizational Structure for the Seed project shall also be included. Please confirm the intent is for the Offeror to provide details on the Organizational Structure for the overall MACC program and not the Seed project.	Confirmed. See Amendment 0004.
138	The paragraph states that a bid bond is required to be submitted equal to 20% of the total price or \$3 million dollars, whichever is less. Please confirm that the bid bond is for the Seed project only and that no other security is required for the overall MACC program. Also, please confirm the intent is for a bid bond to be supplied as part of each individual task order of the program.	The bid bond is for the Seed project only. If required, the requirement for bid bonds will be delineated in the RFP for individual task orders.
139	The RFP specifies a 10-point font minimum for Factor 3, Management Approach, and Factor 4, Schedule. Will NAVFAC permit a smaller font size for graphics including the organizational structure chart, tables, and other graphic figures?	Offerors may use a smaller font size for graphics, including the organizational structure chart, tables, and other graphic features.
140	For Factor 2, the RFP specifies a limit of two single-sided pages for the Technical Approach to Safety Narrative. Please confirm whether the DART and TCR rates do not count toward the two page limit for Safety Technical Approach and can be provided on a separate sheet.	Confirmed.
141	Bid documents and Seed project do not provide any indication that PLA's are anticipated on any of the task orders for this MACC. Please confirm that is the intent for this project. Project approach, interest, and teaming are all predicated on status of PLA's for various pursuits, and the assumption would be that the requirements would be consistent on the entire MACC based on the indication in the RFP and the associated Seed project.	The inclusion of PLAs will be determined on a task order basis.
142	We request a follow up pre-bid meeting focused on what projects and task orders are anticipated under this MACC. This would help inform our approach to teaming, the seed project, and the overall program as a whole.	The Government does not intend to hold a pre-bid meeting. Propose in accordance with the Solicitation.
143	The Specification Table of Contents indicates that sections 23 23 00 and 23 81 29 are "(Under Development)". Section 23 23 00 was included in Att J, but Section 23 81 29 was not included. Please confirm that the provided version of Section 23 23 00 is the final version for this solicitation. Please provide the missing Section 23 81 29 or remove from the table of contents.	The specification section 23 23 00 included in the documents is the final version (and not "under development"). Specification Section 23 81 29 is not applicable and is hereby deleted. Refer to revisions to Specification Table of Contents.

144	In Attachment T of AMD 04, General Bid Note B states that Line Items 6 through 12 (Options 5 through 11) can be awarded up to 365 calendar days after contract award. Please confirm when Line Items 2 to 5 (Options 1 to 4) will be awarded relative to contract award.	Please refer to the revised attachment T included with Amendment 0009.
145	If the Government elects to exercise any options to this contract, will it be done at one time or will they be exercised individually prior to the 365 calendar days after contract award deadline.	Please refer to the revised attachment T included with Amendment 0009.
146	The current proposal due date aligns with other NAVFAC solicitations, which is hindering subcontractors and small business's ability to properly respond to each solicitation. We request a four week extension to the proposal due date to allow adequate time to respond to this solicitation.	Please refer to the revised proposal due date included in Amendment 0006.
147	Please provide additional site visit(s) to allow access to boring logs and subsurface data referenced as only available at the station in the office of the Contracting Officer. Please define a date and time, along with procedures to offer firms enough time to resurvey and regain site access.	See response to PPI 116.
148	Please define how the Government distinguishes "maximum practicable opportunity" in small business Factor 5 to clarify the basis of evaluation for Offeror's to potentially be rated higher.	The Government will evaluate proposals in accordance with the criteria established in the solicitation for Factor 5.
149	Under Small Business Factor 5, does exceeding the minimum small business participation requirement—when supported by a reasonable demonstration and commitment—constitute providing "maximum practicable opportunity" defined in the evaluation criteria?	The Government will evaluate proposals in accordance with the criteria established in the solicitation for Factor 5.
150	Will the Government provide current, approved photographs of the project (interior and exterior) to assist Offerors in accurately pricing the seed project?	No, propose based on documents provided with the Solicitation.
151	Given the complexity and magnitude of the seed project, will the Government adjust the proposal due date to ensure at least three weeks between the release of responses to RFIs and the proposal submission deadline, allowing Offerors sufficient time to incorporate clarifications into their proposals?	Please refer to the revised proposal due date included in Amendment 0006.
152	Given the extensive amount of equipment within the facility, will the Government provide current, approved photographs and a comprehensive list of all industrial equipment that contractors are required to remove for bidding purposes?	No. Photographs are not available. Price per solicitation.
153	Drawing FA001 Notes ask us for a complete new fire alarm/mass notification system but fire alarm floor plan drawings only show sprinkler supervision monitoring devices. Please advise us of the complete scope of work for the fire alarm/mass notification system. Are we to provide only what is shown on the floor plans? Are there existing-to-remain system components? Or is this a design-build project with	The scope of the fire alarm / mass notification includes all devices shown on the drawing and all devices required by the specification. The specification is a performance specification that requires the contractor to provide shop drawings

	respect to the fire alarm system? If design-build, does the contractor have to engage the services of a registered Fire Protection Engineer (FPE) to do the design work?	to be prepared by the fire alarm designer (NICET III or IV) and reviewed and stamped by the QFPE, who is required to be a licensed FPE. The entire existing fire alarm system is required to be removed as part of this project, however, portions of the fire alarm may be required to remain temporarily as part of an NFPA 241 plan for construction period fire safety. This plan is required to be developed by the contractor to address all fire safety concerns during the construction including the periods of time without a fully functioning fire alarm or sprinkler system.
154	Will building be occupied during the renovation?	No.
155	Request photos of the interior and exterior of the building.	Photographs will not be provided.
156	3) Will equipment, tools, work benches, and machinery be removed from the renovation project work areas as work progresses?	Requested information is within the documents. Any items shown or described in the drawings and specifications are the responsibility of the contractor. Other than what is shown in the drawings and specifications, items such as tools, work benches, and contents that are not permanently installed in the building will be removed by the Government prior to mobilization of the contractor. Price per solicitation.
157	Drawing FA001 Notes ask us for a complete new fire alarm/mass notification system but fire alarm floor plan drawings only show sprinkler supervision monitoring devices. Please advise us of the complete scope of work for the fire alarm/mass notification system. Are we to provide only what is shown on the floor plans? Are there existing-to-remain system components?	See response to PPI 153.

158	Please provide domestic water and compressed air riser diagrams.	Riser diagrams for domestic water and the Compressed air piping are not available.
159	Specification 102113 includes Urinal Screens but none are shown on the plans. Please confirm no urinal screens are required on the project.	Confirmed, there are no urinal screens in the project.
160	No Exterior signage specifications were provided and none is shown on the plans. Please confirm no exterior signage is required on the project.	Confirmed, there is no exterior signage included in this project.
161	Custodial Closets 107 and 202 are shown on AE401 and AE402 to receive mop and broom holders but there is no such designation for Custodial M104. Please confirm M104 also receives a mop and broom holder.	Confirmed, provide mop and broom holder for Custodial M104. Sheet AE104 is hereby amended, see continuation sheet.
162	The Toilet Room Accessory Schedule on AE401 lists Solid Plastic Locker Benches but none are shown in enlarged bathroom plans or locker room. Please confirm locker benches are not required on the project.	Confirmed, locker benches are not required on this project.
163	Specification 102813 includes Industrial Soap Dispensers but none are shown on the plans. Please indicate where these go or confirm they are not required on the project.	Industrial soap dispensers are not required on this project. Note: Also see Continuation Sheet for two soap dispensers being added at the wash sink outside of the breakroom.
164	Specification 142423 Part 2.1.1.1.a calls for in-ground direct plunger type elevator. This design is no longer standard industry practice. Please confirm a holeless elevator type is an acceptable alternative.	A telescoping plunger is not permitted per UFC 3-490-06. Therefore given the travel distance and limited pit depth, a hole-less elevator would not work for B60.
165	Drawing Q-601 notes that equipment marked "NEW" is to be contractor purchased and installed. CLIN 3A on the Price Schedule shows a description of "procurement/installation of new equipment." Please confirm the equipment tagged "NEW" on Q-601 is included in this CLIN 3A item.	Confirmed. Refer to PPI response 119.
166	Drawing Q-601 notes that equipment marked "EXIST" is government relocated equipment to be contractor installed. Please confirm this work should be priced under CLIN 3B on the Price Schedule.	Confirmed. Refer to PPI response 119.

167	Please indicate the location where the contractor will take possession of the government relocated equipment that requires contractor installation.	Government provided/relocated industrial equipment will be delivered to Building 60 outside of overhead door 101A.
168	Please confirm if the Government will allow for the 2025 filling cycle of Veterans' Employment and Training (VETS-4212), rather than the 2023/2024 filing cycle as stated in the RFP.	Confirmed. Please refer to the changes included in Amendment 0007.
169	Specifications Volume 1, Section 01 91 00.15 22 Total Building Commissioning, sub-section 1.1 states the the Government has hired an independent Commissioning Firm for this project. Could the Government please confirm that all commissioning elements as described in the 01 91 00.15 22 Total Building Commissioning as well as the 23 08 00 Commissioning of Mechanical and Plumbing Systems will be executed by the Government hired Commissioning Firm?	Commissioning is a process that must be accomplished as a Team. Commissioning activities required of each member of the Cx Team (including the KTR, the Government hired Cx provider, the DOR and the Government's technical representatives) are assigned in UFGS 01 91 00.15 22 Total Building Commissioning. The Contractor, and relevant subcontractors, are required to actively participate, support, and coordinate with the Government Cx provider to execute the Commissioning process.
170	Sheet MD101 General Note #2 notes due to limited information of existing conditions to assume 1200' feet of 4" metal steam and heating water type of pipe to be removed from the trenches. Please clarify if this steam and water pipe removal is to be included in the bid form breakdown 1D for the Mechanical/Plumbing Breakdown, or bid form breakdown 1G for Building Demolition?	Include removals in line item 1G.
171	Specifications Volume 2, Section 07 84 00.00 Firestopping, sub section 1.5.1 states that a single qualified installer/subcontractor is to be used for the entire project in regards to the firestopping work. For clarification, please confirm this single subcontractor requirement will be on all firestopping scope of work for all trades and their systems including but not limited to mechanical, electrical, plumbings, and drywall.	Confirmed. One company will do all fire stopping for the entire project.
172	On sheet P-104, keynote 4 shows the locations of the 3/8" Compressed Air Hose and Electrical Power Extension Chords from the Retractable Reels which will be supplied by equipment packages per keynote 3 on sheet P-106 at 9	On sheet P-104, Keynote 4 is used to identify a total of nine (9) sets of compressed air hose reel / electrical power cord reel drops. Each pair of

	locations. The drawings on sheet P-104 show two locations for the compressed air service/electrical power extension chords at multiple locations in shop 111. Could the Government confirm that a total of 9 drops are required for this associated equipment with a single air service and single electrical power extension at each piece of equipment, and that the intent is not to have a double compressed air service at each piece of equipment?	small circles with leaders from a keynote 4 tag represents one air service drop and one electrical service drop.
173	Detail B1/P-501 shows an expansion tank EXT-P1 for the electric water heater EWH-1. The expansion tank schedule located on sheet P-601 only shows EXT-P1 which is located in room Mech M106. The detail A3/P-601 doesn't show any expansion tank for EWH-2. Will EWH-2 and EWH-3 require expansion tanks?	Expansion tank is required for electric water heater EWH-2. Sheets P-401 and P-601 are hereby amended. Refer to continuation sheet.
174	Offerors are told to assume removal of 1,000 linear feet of copper cable between load center 4 vault and building 60 for bidding purposes. If a quantity of cable larger than the amount stated is determined to be removed, please confirm this will be considered as an unforeseen condition and treated as a change.	Propose in accordance with the solicitation.
175	Please confirm that Offerors are responsible for all costs associated with the delegated design of the lightning protection system.	Confirmed.
176	Keynote 14 states that the Government will be responsible to locate and mark the underground utilities. Keynote 20 states that Offerors are to provide the services of an independent, private utility locating company. Please clarify who is responsible for providing utility locating on the project.	Bid in accordance with solicitation. Refer to specification 01 35 26.00 22 for utility locating requirements
177	Will the Government be responsible for maintaining the utility markings throughout the contract period?	Requested information is within the documents. Price per solicitation. Refer to specification 01 35 26.00 22 for utility locating requirements
178	On the DDC architecture drawing, AHU-1 is shown as having a BACnet interface for a controller. Should it be assumed that the instrumentation is included with the AHU and the I&C contractor should exclude from their bid for procurement?	Requested information is within the documents. Price per solicitation.
179	DDC System architecture shows "Control Unit-xx" on the drawing. It is assumed that these are the control panels that are required on-site. Control Unit-02 thru Control Unit-04 indicate that the equipment that should be included is BCU-x/CH-x. There are no chillers on the control drawings so it is unclear	See updated drawing M-701 for typographical corrections for blower coil unit/condensing unit pairs.

	what equipment should be tied to which control panel. Please clarify which equipment is to be tied the control panel.	
180	Will the Government be open to other ground improvement methods if the design parameters are met?	Propose in accordance with the solicitation.
181	(Att. P. 01 45 35a) The document states: "< Designated Seismic Systems APPLY to this project." However, all DSS tables (Electrical, Mechanical/Plumbing, and Other) are marked "N/A," and the Final Walk Down Inspection section states: "< Does not apply – no Designated Seismic Systems." (1) Please confirm whether Designated Seismic Systems do or don't apply to this project. (2) If they do not apply, please revise the document to remove the contradictory "APPLY" statement for consistency.	The document referenced in this PPI does not state that Designated Seismic Systems APPLY to this project. As stated at the bottom of Page 2 of this document, Designated Seismic Systems does NOT apply. No changes to this document will be issued.
182	Please clarify whether the ductwork is to be lined per the General Note #2 or externally insulated per Keynote #9.	For ductwork that is indicated as lined and includes Keynote 9, provide lined insulation (see General Note 2) inside the ductwork for acoustic sound dampening, and provide insulation on the exterior of the ductwork for thermal isolation.
183	Please confirm that Line Item 1DD "Replace damaged wood strip flooring (2nd floor)" on the Price Schedule is pertaining to Note 10 on sheet AE105 for 300SF.	Refer to updated sheet AE105. Unit Price Item 1DD is for scope not otherwise indicated in the plans, specifications or reports provided with the solicitation. Scope associated with Note 10 on Sheet AE105 is to be included in Line Item 1B for architectural work.
184	Option Item 8 states "Price for providing work associated with Additional Finishes". Note 8 on sheet AE102 states to Refinish Wood Plank Flooring on the First Floor. Please clarify how much of Corridor 103 should be Refinished.	Refer to PPI 101 response
185	Please provide a Manufacturer Model/Type for the Wood Strip Flooring.	Wood strip flooring is existing to be refinished. See Room Finish Schedule Note 6.

186	Please clarify if one of the existing panels can be used for temp power during the construction phase.	Yes, provided the existing panel is in safe, operational condition, it may be used for temp power during the construction phase.
187	Drawing SB401 shows the locations where to install the micropiles. The Price Schedule Line Item 1AA is for 60 LF of micropiles. It is unclear if Line Item 1AA is to include the micropiles shown on SB401 or if Line Item 1AA is additional micropiles above and beyond SB401. Please clarify if the micropiles shown on SB401 are to be included within Line Item 1AA or Line Item 1B (Structural/Architectural) on the Price Schedule.	Please refer to response provided for PPI 118.
188	Drawing SB401 shows the locations of where to install the micropiles. The Price Schedule Line Item 1CC is for 4 CY of drilling spoils generated with micropile installation. It is unclear if Line Item 1CC is to include the drilling spoils of micropiles shown on SB401 or if Line Item 1CC is additional drilling spoils of micropiles above and beyond SB401. Please clarify if the drilling spoils of micropiles shown on SB401 are to be included within Line Item 1CC or Line Item 1B (Structural/Architectural) on the Price Schedule.	The cubic yard quantity of drilling spoils must be determined from the contract drawings based on the information provided. This total must be the quantity included in Line Item 1B. The unit price (Line Item 1CC) is no longer applicable. Refer to updated Price Schedule.
189	Line Item 1Z on the Price Schedule Form is to provide a price for 1 Day of the Industrial Hygienist. Please clarify if Line Item 1Z is for Industrial Hygienist costs in addition to what is required in other Base Bid Line Items 1H & 1I.	Unit Price Item 1Z is no longer applicable. Refer to updated Price Schedule.
190	Please confirm that Line Item 1H on the Price Schedule is to include all scope identified as CLIN 002 on the drawings.	Confirmed. Refer to revised Price Schedule
191	Please confirm that Line Item 1I on the Price Schedule is to include all scope identified as CLIN 003 on the drawings.	Confirmed. Refer to revised Price Schedule
192	Please confirm that Line Item 1J on the Price Schedule is to include all scope identified as CLIN 004 on the drawings.	Confirmed. Refer to revised Price Schedule
193	Drawing AE622 states Bid Option 6 for the Window and Door Restoration. However, the Price Schedule states that Bid Option 6 is not applicable. Please confirm that all references to Bid Option 6 on AE622 should state Bid Option 5.	Confirmed. Sheet AE622 is hereby amended to reflect that the work is in "Bid Option 5".

194	Drawing AE704 identifies areas of existing wood bead board ceilings to be replaced on the 2nd Floor. On the Price Schedule form, Line Item 1EE is to provide a price to replace 120 SF of damaged wood bead board ceiling (2nd Floor). Please clarify if the wood bead board ceilings to be replaced on AE704 are to be included within Line Item 1EE or Line Item 1B (Structural/Architectural) on the Price Schedule.	The quantity indicated on drawings must be included in Line Item 1B. Unit Price Item 1EE is no longer applicable. See updated Price Schedule and sheet AE704.
195	Specification Section 01 11 00.00 22 1.3 states that the performance period is 608 days. However, the Amendment 0004 Price Schedule states the duration is 622 calendar days plus 40 days if Option 3 is exercised bringing a total duration to 662 calendar days. Please confirm that 662 days is the correct period of performance if all Options are exercised.	Performance Period is 622 Calendar days. If Option 3 is executed then the performance period would extend 40 calendar days, for a total of 662 calendar days. See amended Price Schedule. Confirmed. 662 calendar days is the correct period of performance if all Options are exercised.
196	On Drawing Q-601 Building 60 Equipment Schedule, it specifies many items as "NEW" to be Contractor Purchased and Installed Equipment. Please clarify that all equipment items listed as "NEW" are included within Line Item 3A (Option 2) Industrial Equipment FF&E.	Confirmed. See also response to PPI 119.
197	On Drawing Q-601 Building 60 Equipment Schedule, it specifies many items as "EXIST" to be Government Relocated Equipment, Contractor Installed. Please clarify that all equipment items listed as "EXIST" are included within Line Item 3B (Option 2) Industrial Equipment.	Confirmed. See also response to PPI 119.
198	Drawing Q-601 states that the Existing Equipment is located Off Site. Please clarify the current location of this Existing Equipment and the distance from Building 60.	Government provided/relocated industrial equipment will be delivered to Building 60 outside of overhead door.
199	Line Item 1FF on the Price Schedule Form is to provide a price for 50 LF of Masonry Crack Repair. However, Drawing AE202 states to assume 30 LF of Crack Repair. (1) Please clarify the assumed quantity of Masonry Crack Repair to be included. (2) Please confirm that all Masonry Crack Repair is to be included in Line Item 1FF.	1. The quantity indicated on AE202 (30 LF) must be included in line item 1B. 2. Item 1FF quantities are indicated on updated sheet SF502 and are for scope not otherwise indicated in the plans, specifications or reports provided with the solicitation. Note that the repairs in 1FF should be for work similar to repairs indicated in detail C1/SF502.

200	Specification Section 01 30 00.00 22 1.6 states that the Environmental Manager may be combined with the QC Manager. However, Section 01 57 19.00 22 1.5.4 states the Environmental Manager cannot perform the duties of the Quality Control Manager. Please confirm that the QC Manager can also be the Environmental Manager.	Environmental manager cannot perform the duties of the Quality Control Manager. Specification section 01 30 00.00 22 section 1.6 is hereby amended: Delete "May be combined with the QC Manager" from the Environmental Manager Responsibility/Restrictions column.
201	Specification Section 01 78 00.00 22 3.2 makes reference to Record Drawings and Record Model deliverables. As customary on a Design-Bid-Build delivery model, please confirm the DOR will be producing the record drawings and record BIM model, utilizing Contractor's as-built drawings. Since the DOR owns the complete set of electronic drawings required to produce the record drawings/model (including all backgrounds and "add-ons" which are often proprietary information), having the DOR produce these documents would be the most practical and efficient method. Please confirm the DOR will be providing the record drawings and record model for this Design-Bid-Build project.	Contractor is responsible for producing the Record Drawings in accordance with Specification 01 78 00.00 22.
202	Please confirm that all construction activities on this project must be performed by U.S. citizens.	Confirmed
203	Line Item 1I on the Price Schedule Form states to provide the management/abatement and removal of hazardous materials (identified as 003). However, the drawings do not identify 003 scope. Please confirm if all abatement and removal of hazardous materials within the drawings is to be included within Line Item 1I.	Abatement and removal of hazardous material is to be included under line item 1I unless noted otherwise (refer to industrial equipment related hazardous material which will be included in line item 1H). Refer to revised Price Schedule.
204	Specification Section 23 05 48.00 40 1.2 states that within ten working days of Contract Award, submit equipment and performance data for vibration isolator systems. This timeframe of ten working days after Contract Award is extremely quick to provide this information. Please confirm that the vibrator isolator systems equipment and performance data do not need to be submitted within ten working days of Contract Award.	In Specification Section 23 05 48.00 40, Part 1.2, first sentence; Delete "Within ten working days of Contract Award," and capitalize "submit" to read as follows: "Submit equipment and performance data for vibration isolation systems..."
205	Multiple items throughout the drawings indicate to be removed, salvaged, and stored for reinstallation. Please clarify if the Offeror is required to provide an onsite storage location for the	On-site storage is required. Refer to specification 01 11 00.00 22 for additional information and salvage plan requirements.

	items to be salvaged and reinstalled, or if the Government will provide a storage location.	
206	Drawing HM604 identifies the removal of 3,300 SF of ACM Floor Tile. However, Line Item 1R on the Price Schedule Form provides a removal quantity of 50 SF of ACM floor tile and mastic. (1) Please clarify what quantity is to be included within the project scope. (2) Is the Line Item 1R quantity in addition to what is shown on the drawings?	1. The quantity indicated on drawings must be included under line item 1I. 2. Item 1R quantities are indicated on updated sheet HM604 and are for scope not otherwise indicated in the plans, specifications or reports provided with the solicitation.
207	Drawing HM604 identifies the removal of ACM Brown Duct Sealant, Gray Sealant, and Black Sealant for a total of 140 LF. However, Line Item 1Q on the Price Schedule Form provides a removal quantity of 50 LF of ACM Sealants. (1) Please clarify what quantity is to be included within the project scope. (2) Is the Line Item 1Q quantity in addition to what is shown on the drawings?	1. The quantity indicated on drawings must be included under line item 1I. 2. Item 1Q quantities are indicated on updated sheet HM604 and are for scope not otherwise indicated in the plans, specifications or reports provided with the solicitation.
208	Drawing HM604 identifies the removal of 1,000 LF of ACM Pipe Insulation. However, Line Item 1N on the Price Schedule Form provides a removal quantity of 50 LF of ACM Pipe Insulation. (1) Please clarify what quantity is to be included within the project scope. (2) Is the Line Item 1N quantity in addition to what is shown on the drawings?	1. The quantity indicated on drawings must be included under line item 1I. 2. Item 1N quantities are indicated on updated sheet HM604 and are for scope not otherwise indicated in the plans, specifications or reports provided with the solicitation.
209	Drawing HM604 identifies the removal of ACM Unused Control Circuit Wiring. However, no quantities are provided. For bidding purposes, please provide a quantity of ACM unused Control Circuit Wiring that is to be removed.	On Sheet HM604 SUMMARY OF ACM TO BE REMOVED schedule, revise quantity for UNUSED CONTROL CIRCUIT WIRE to be 100LF.
210	Drawing HM604 identifies the removal of 1,400 SF of ACM Debris. However, Line Item 1S on the Price Schedule Form provides a removal quantity of 50 LF of ACM Debris. (1) Please clarify what quantity is to be included within the project scope. (2) Is the Line Item 1S quantity in addition to what is shown on the drawings?	1. The quantity indicated on drawings must be included under line item 1I. 2. Item 1S quantities are indicated on updated sheet HM604 and are for scope not otherwise indicated in the plans, specifications or reports provided with the solicitation.
211	Please confirm this project is not located within the Controlled Industrial Area (CIA).	Building 60 is not located within the CIA. Some communication routing work is located within the CIA.

212	Please confirm that all privately owned vehicles must park at the Jamaica Island Parking lot.	Confirmed per Specification 01 50 00.00 22, paragraph 1.7 EMPLOYEE PARKING PLAN.
213	Building 60 currently has a considerable amount of tools, material office supplies, FF&E, etc to support current operations. Since pictures were not allowed at the site visit, please confirm the Government will remove all items not shown on the drawings prior to construction starting.	See response to PPI 156
214	Please clarify what days and times heavy equipment delivery will be allowed to the project site.	Deliveries are to be scheduled during regular working hours except when approved by the Contracting Officer in accordance with Specification 01 14 00.00 22, paragraph 1.5 CONTRACTOR ACCESS AND USE OF PREMISES (PNSY) and paragraph 1.6 WORKING HOURS (PNSY).
215	Drawing G-006 identifies areas for Contractor construction staging and storage. Please clarify if there is another location for the Contractor's temporary construction office trailer.	No. Location of construction trailer/office must be coordinated with staging areas indicated or set up within Building 60.
216	(HM001; Drawings; 1. Haz. Survey) Can the collection of the additional samples A - E be done during two consecutive days or one mobilization, or will they need to be sequenced?	The Contractor is solely responsible for the sequencing and duration of all sampling activities. All sampling must be conducted in strict accordance with UFGS Sections 01 57 19, 02 82 00.00 22, and 02 83 00.00 22, as well as all applicable local, state, federal, and PNSY-specific instructions. The Contractor is responsible for submitting a sampling plan for approval that includes coordination with the government's representative/COR and to schedule the required government witnessing for each sampling event. Performing the sampling during two consecutive days or one mobilization will be dependent on the Contractor's approved plan and coordination efforts
217	(HM001; Drawings; 4. Haz. Survey) Can the collection of the additional 30 - 40 dust wipe samples A - E be done during two consecutive days or one mobilization, or will they need to be sequenced?	The Contractor is solely responsible for the sequencing and duration of all sampling activities. All sampling must be conducted in strict accordance with UFGS Sections 01 57 19 and 02 83 00.00 22, as well as all applicable local, state, federal, and PNSY-specific instructions. The Contractor is responsible for submitting a sampling plan for approval that includes coordination with the government's representative/COR and to schedule the required government witnessing

		for each sampling event. Performing the sampling during two consecutive days or one mobilization will be dependent on the Contractor's approved plan and coordination efforts.
218	Will the abatement of the loose and peeling paint require full containment?	The Government cannot dictate the contractor's means and methods. The specific level of containment and engineering controls is dependent on the paint mitigation activities proposed by the contractor. However, any chosen method must prevent the release of lead-containing dust, debris, and fumes from the immediate work area and comply with the strict performance requirements of UFGS Section 02 83 00.00 22, EM 385-1-1, and all applicable OSHA regulations (e.g., 29 CFR 1926.62, 1926.1126, & 1926.1127). The contractor is required to submit a detailed, site-specific LCC Compliance Plan outlining their proposed means, methods, and the engineering controls they will use to meet these performance standards. This plan requires review and approval by the Government's representative/COR before work can commence.
219	Will the abatement of the loose and peeling paint require post LCC dust wipe sampling?	The requirement for post-mitigation clearance, including the conditions under which dust wipe sampling is mandatory, is governed by the performance criteria detailed in UFGS Section 02 83 00.00 22. The Contractor is responsible for including a detailed, site-specific clearance plan within their overall Lead Abatement Plan. This clearance plan must describe the methodology the contractor will use to demonstrate that the work area meets the cleanliness criteria outlined in the UFGS specification for the chosen abatement strategy. This plan is subject to Government approval before work begins.
220	Will the abatement of the loose and peeling asbestos containing paint require post air sampling?	Requirements for air sampling for work on asbestos-containing materials (ACM) are governed by UFGS Section 02 82 00.00 22 and MEDEP Chapter 425. If the contractor's chosen means and

		methods have the potential to render the ACM friable, then post-abatement final clearance air sampling is mandatory per MEDEP Chapter 425 before containment can be dismantled. The contractor's site-specific Work Plan, submitted for Government approval, must detail the full air sampling strategy (personal, area, and clearance) to ensure compliance
221	Will heavy metals dust cleaning on equipment require dust wipe verification sampling prior to removal and disposal?	Dust wipe sampling for industrial equipment is not generally needed as long as a visual inspection of the cleaned equipment shows no accumulation of dust or debris. There are no clearance standards applicable in this situation. The litmus test is a visual inspection to ensure that the equipment can be taken out of the building without disseminating contaminated dust or debris in the process.
222	Will brush/scrape paint removal on walls and architectural features require full negative pressure enclosures?	Post-mitigation dust wipe sampling is not required for equipment designated for disposal. The Contractor's approved LCC Compliance Plan must detail the decontamination procedure, which shall include a final visual inspection to ensure equipment is free of all visible dust and debris before being removed from the work area.
223	Will brush/scrape paint removal on wood flooring require full negative pressure enclosures?	See response to PPI Question 218.
224	The Specification Section 02 83 00 Management of Lead, Cadmium, and Chromium (VI) is dated 10/23 and is not the latest version of this section. Is this version the applicable version to be utilized for this project?	No. Section 02 83 00 hereby amended, see continuation sheet.
225	Will the Government consider modifying the frequency of area air sampling for Chromium (IV) for large or long duration tasks and what needs to be submitted for review, consideration and approval?	Propose in accordance with the solicitation.
226	This seed project has considerable interest as demonstrated by the high turnout at the site walk. We are receiving a significant number of questions from subcontractors and vendors. There is a large volume of detailed information required to submit at the prime level. There are also several other Federal projects bidding in early March that are spreading resources thin at multiple levels of the supply chain. As the Government requires time to prepare detailed responses to all RFIs, adequate time is also needed for the contractors to integrate the RFI responses	Refer to Amendment 0006.

	issued into our proposals and pricing to ensure best value compliant proposals with ample competition. As such, will the Government please extend the proposal due date by 4 weeks to April 3, 2026?	
227	To effectively and clearly present the offeror's organization for the broad range of the scope of this solicitation, will the Government please allow the organization chart to be placed on an 11x17 size sheet?	Refer to PPI #97.
228	Please confirm the elevator does not have a stop at the second floor mezzanine.	Confirmed. Elevator has three stops (first floor, first floor mezzanine, and second floor)
229	Detail A1 and A2 on sheet AE111 conflict; Detail A1 appears to show elevator opening slotted to the right side, while A2 shows a left side opening. Please confirm which detail to follow.	Both plan and section show door opening in same direction. Section A2 is looking back at interior of door.
230	Please confirm space above proposed elevator shaft is clear to top of roof deck.	Provide 1-HR shaft ceiling at top of elevator shaft, refer to keynote 9 on AE411.
231	Please confirm warranty is required for providing periodic maintenance of elevator systems in addition to monthly and yearly inspections, per specification 14 24 23, for only a period of 1 year past Government acceptance.	Confirmed.
232	Can Site Quality Control Manager dual hat as Environmental Manager?	No. Propose in accordance with the solicitation.
233	The RFP states the Contractor's Interior Designer must have "completed a program accredited by the Council for Interior Design Accreditation (CIDA) or equal accreditation program of academic training in Interior Design," in addition to attaining NCIDQ certification and applicable state licensure, certification, or registration. To ensure compliance and consistent evaluation of qualifications, what academic programs or accreditation bodies does the Government consider acceptable as an "equal accreditation program" to CIDA? Specifically, please confirm the below programs are considered acceptable, provided the Interior Designer has attained NCIDQ certification and state licensure, certification, or registration: * Interior Design or Interior Architecture degrees from institutions accredited by the National Association of Schools of Art and Design (NASAD); * Interior Design or Interior Architecture degrees from regionally accredited colleges or universities whose programs meet NCIDQ eligibility requirements; and/or * Other nationally or regionally accredited academic programs that support eligibility for NCIDQ certification.	Provided that the Designer has passed the NCIDQ, programs listed are acceptable.

234	Is it permissible for the FF&E scope to be performed by a team of Interior Designers? One with the CIDA Design Accreditation and one with the NCIDQ certification.	Refer to Response for PPI #233
235	Specialty CEQ Package Requirements: The RFP states that the project “may also include a Specialty CEQ Package” and that, if required, the same requirements identified for the FF&E Package would apply, or as outlined by project-specific UFC or the requiring Agency. Please confirm there is no Specialty CEQ Package scope, and that there is no pricing, design, procurement, or installation of a Specialty CEQ Package associated with this solicitation. Otherwise, please identify the locations in the RFP or Price Schedule where it is defined and shall be incorporated.	Confirmed. There is no Specialty CEQ Package in the project.
236	Att. I) Specifications_Volume_2, Section 12 00 01.00 20 - Furniture, Fixtures and Equipment (FF&E) Package, Page 514 of 543, ¶3.1.1 states: The Contractor must hire a different Interior Designer to validate the FF&E Concept Design Package requirements with the Activity or End User and NAVFAC Interior Designer and make any necessary revisions. The Price Schedule does not appear to have a discrete line item for Interior Design services associated with this requirement. Under which line item on the Price Schedule shall the costs for engaging this separate Interior Designer (including validation, coordination meetings, and any required revisions) be included? Please clarify.	No separate line item is needed for the labor of the Contractor's Interior Designer. The Government Estimate reflects the cost of the FF&E and the Base Contract Estimate includes the labor of the Designer. Bidders are required to add the HAR and subtotals.
237	Att. I) Specifications_Volume_2, Section 12 00 01.00 20 - Furniture, Fixtures and Equipment (FF&E) Package, Page 514 of 543, ¶3.1.1 states: The FF&E or CEQ Concept Design Package submittal (approximately 35 percent), as prepared by the A/E's Interior Designer, was sufficiently developed to fully integrate with the building systems (e.g., electrical, mechanical) to include product sizes and communications, data, and electrical requirements. Given the seed project is defined as a Design-Bid-Build (DBB) procurement, and the AE 800-Series (FF&E) drawings, the Q-Series (Equipment) drawings and Att. S) FFE Package are stamped and sealed and identified as “FINAL SUBMISSION.” please confirm the referenced “approximately 35 percent” FF&E / CEQ Concept Design reflects the current and complete level of design for bidding purposes, such that no further design development by the Contractor is anticipated beyond standard coordination and submittal review.	Contractor is responsible for providing Interior Design services and completing the FF&E package design, procurement, installation, and related requirements in accordance with the specifications. See Spec section 12 00 01.00 20, Part 3 Execution, Paragraph 3.1.1 System Description: Contractor's Interior Design Services.

238	Please confirm the stamped and sealed AE 800-Series and Q-Series drawings represent the final contract documents for FF&E and equipment scope, including all required sizes, utilities, communications, data, and electrical requirements necessary for procurement and installation.	The stamped and sealed AE800-Series and Q-Series drawings are not the final design. The Contractor must hire a different Interior Designer to validate the FF&E Concept Design Package requirements with the Activity or End User and NAVFAC Interior Designer and make any necessary revisions. Refer to project documents and bid per solicitation.
239	Please advise if any additional FF&E or CEQ design development beyond what is shown in the final drawings is required of the Contractor.	Yes, additional FF&E design development beyond what is shown in the final drawings is required of the Contractor. Refer to project specifications and bid per solicitation. Refer to Response for PPI #238.
240	Att. I)_ Specifications_ Volume_2, Section 12 00 01.00 20 - Furniture, Fixtures and Equipment (FF&E) Package, Page 507 of 543. Is Section 12 00 01.00 20, Furniture, Fixtures, and Equipment (FF&E) intended to apply to the Option 2 Industrial Equipment scope of work as well? If not, please identify the specification section(s) that govern the Industrial Equipment requirements for Option 2.	Section 12 00 01.00 20, Furniture, Fixtures, and Equipment (FF&E) applies to the Option 2 Industrial Equipment scope of work as well
241	For Line Item 2, Option Item No. 1. Please confirm the Contractor is only required to provide the HAR percentage (%) and to calculate the corresponding HAR Subtotal and Total based on the Government Estimated Price for the FF&E scope.	Confirmed. Contractor must input HAR Subtotal and Total.
242	For Line Item 3A, Option Item No. 2. Please confirm the Contractor is only required to provide the HAR percentage (%) and to calculate the corresponding HAR Subtotal and Total based on the Government Estimated Price for the FF&E scope.	Confirmed. Contractor must input HAR Subtotal and Total.
243	Line Item 3B Option Item 2 states: ...for the entire work associated with industrial equipment, including installation of government procured and provided equipment and associated utilities... It is unclear what specific equipment should be included in pricing for Line Item 3B as the same nomenclature, i.e. 'government procured and provided equipment' is not utilized in the provided drawings. Drawing Q-601, Equipment Schedule (Option 2), identifies the status of equipment as: NEW,	See response to PPI 119

	EXIST, SHIPYARD. What Government procured and provided equipment is associated with Line Item 3B?	
244	Line Item 3B Option Item 2 states: ...for the entire work associated with industrial equipment, including installation of government procured and provided equipment and associated utilities... It is unclear what scope or 'entire work' is to be included for the installation of government procured and provided equipment in the pricing for Line Item 3B. Which of the following specific scope elements (or add others) shall be included in the pricing for the installation of Government-procured and provided equipment under Line Item 3B? *Equipment handling, off-loading, staging, and setting *Final placement, anchorage, and alignment *Electrical, mechanical, plumbing, controls, data, and other utility connections *Modifications to building systems or infrastructure required for installation *Testing, start-up, and coordination support *Any demolition, removals, or temporary work associated with installation	See response to PPI 119. The list indicated in the question is an accurate general scope related to 3B work. Note 3A will only include the procurement and installation of "NEW" industrial equipment. See response to PPIs 119 and 254. List indicated is accurate general scope related to 3B work. Note 3A will only include the procurement and installation of "NEW" industrial equipment.
245	For Line Item 1G it states: Subtotal of Base Price for the entire Building Removals/Demolition work complete, in accordance with the drawings and specifications. Shall the scope associated with the QD "Equipment Removal Plans" be included in the pricing for Line Item 1G? If not, under which line item it should be priced?	Industrial equipment removal (work indicated as CLIN 002) must be included in line item 1H. See revised Price Schedule.
246	Please confirm all infrastructure and utility systems required to support the FF&E have been fully designed by the Designer of Record (DOR) for this Design-Bid-Build (DBB) seed project, including but not limited to: *Structural support and anchorage *Electrical power, grounding, and communications *Mechanical systems (HVAC, exhaust, process piping, etc.) *DDC/BAS/controls and related integration *Fire protection and life safety interfaces	Contractor design requirements are outlined in specification 12 00 01.00 20. Price per solicitation.
247	Please confirm the Contractor's responsibility is limited to installation and coordination in accordance with the contract documents, and that no additional design development or engineering coordination effort is required beyond standard construction coordination.	See response to PPI 246

248	Key Note 8. states: 8. PROVIDE FOR REMOVAL OF (3)-20 CY DUMPSTERS WORTH OF MISCELLANEOUS MATERIALS/ EQUIPMENT LEFT IN SPACE BEYOND THE EQUIPMENT INDICATED. Under which Line Item # shall this pricing be included?	Line item 1H
249	Key Note 1. states: PROVIDE UTILITIES FOR AND INSTALLATION OF INDUSTRIAL EQUIPMENT. SEE EQUIPMENT SCHEDULE ON SHEET Q-601. For this Design-Bid-Build (DBB) seed project, please confirm all infrastructure and utility systems required to support the industrial equipment have been fully designed by the Designer of Record (DOR), including but not limited to: *Structural support and anchorage *Electrical power, grounding, and communications *Mechanical systems (HVAC, exhaust, process piping, etc.) *DDC/BAS/controls and related integration *Fire protection and life safety interfaces Please also confirm that the Contractor's responsibility is limited to installation and coordination in accordance with the contract documents, and that no additional design development or engineering coordination effort beyond standard construction coordination is required of the Contractor.	Requested information is within the documents. Price per solicitation. See response to PPI 246
250	Key Note 1. states: PROVIDE UTILITIES FOR AND INSTALLATION OF INDUSTRIAL EQUIPMENT. SEE EQUIPMENT SCHEDULE ON SHEET Q-601. Please confirm the Contractor's responsibility is limited to installation and coordination in accordance with the contract documents, and that no additional design development or engineering coordination effort beyond standard construction coordination is required of the Contractor.	See response to PPI 249.
251	(Att. M) This states: THE CONTRACTOR IS RESPONSIBLE FOR INSTALLING THE INDUSTRIAL EQUIPMENT AS INDICATED AND IS RESPONSIBLE FOR COORDINATING THE RELOCATION OF EXISTING EQUIPMENT BY THE GOVERNMENT. Note 8. states: INSTALL EQUIPMENT STATUS MARKED "EXIST" (EQUIPMENT TO BE RELOCATED BY THE GOVERNMENT). Equip Schedule Remarks Notes, Note A. states: INSTALL EQUIPMENT AT FINAL LOCATION IN BUILDING 60.	Government provided/relocated industrial equipment will be delivered to Building 60 outside of the west side overhead door. Contractor must coordinate the scheduling of this effort with the Contracting Officer. The Contractor will be responsible for

	What is the intended extent of the Government-performed relocation of existing equipment? Please confirm the division of responsibility between the Government and the Contractor so that pricing and logistics assumptions may be aligned.	final placement, installation, and coordination of testing.
252	(Att. M) Does the Government's relocation responsibility include moving the equipment to the final installed location shown on the drawings, or only to a temporary or intermediate location (e.g., building entrance, loading area)?	No. Refer to response to PPI 251
253	Will any equipment handling, rigging, internal movement, positioning, or setting in place be required to be performed by the Contractor following Government relocation?	Yes. Refer to response to PPI 251
254	Att. M)_Drawings_Volume_2a, Q-601, Equipment Schedule General Notes, Note 6. states: COORDINATE TESTING OF EXISTING EQUIPMENT TO BE RELOCATED TO CONFIRM WORKING CONDITION BEFORE AND AFTER RELOCATION. TESTS MUST BE WITNESSED BY SHOP REPRESENTATIVE AND COORDINATED WITH THE CONTRACTING OFFICER. The clarification is needed to assist the offeror appropriately allocate scope, schedule, and pricing assumptions. Testing Responsibility: Who is responsible for performing the testing of the existing equipment before and after relocation (i.e., Government personnel, shop representative, equipment manufacturer/vendor, or the Contractor)? If the Contractor is expected to perform or subcontract the testing, please confirm the extent of this responsibility.	Government personnel will be responsible for the testing of the existing equipment before and after relocation. Contractor is responsible for coordinating and witnessing the testing.
255	Witnessing vs. Performing: Please confirm the Contractor is responsible for coordination and witnessing of testing, but not for executing the tests.	Confirmed. See response to PPI 254.
256	Maintenance Records: Please provide any existing equipment maintenance, service, or testing records available for review to establish baseline operating condition prior to relocation.	Past maintenance records are not available. Also see response to PPI 254.
257	Att. M)_Drawings_Volume_2a, Q-601, Equipment Schedule General Notes, Note 6. states: COORDINATE TESTING OF EXISTING EQUIPMENT TO BE RELOCATED TO CONFIRM WORKING CONDITION BEFORE AND AFTER RELOCATION. TESTS MUST BE WITNESSED BY SHOP REPRESENTATIVE AND COORDINATED WITH THE	See response to PPI 254.

	CONTRACTING OFFICER The clarification is needed to assist the offeror in appropriately allocating scope, schedule, and pricing assumptions. Testing Responsibility: Who is responsible for performing the testing of the existing equipment before and after relocation (i.e., Government personnel, shop representative, equipment manufacturer/vendor, or the Contractor)? If the Contractor is expected to perform or subcontract the testing, please confirm the extent of this responsibility.	
258	Witnessing vs. Performing: Please confirm the Contractor's role is limited to coordination and witnessing of testing, and not for executing the tests.	See response to PPI 255
259	Maintenance Records: Please provide any existing equipment maintenance, service, or testing records available for review to establish baseline operating condition prior to relocation.	See response to PPI 226.
260	Paragraph 1.3.1.c. states that the FF&E Option Item must be awarded a minimum of six (6) months prior to the contract completion date to avoid schedule impacts, while Section 1.3b. identifies Option 2 – Industrial Equipment as having a 365-calendar-day onsite performance period, concurrent with the Base Bid. The clarification is requested to ensure consistent schedule logic and pricing assumptions. How does the six-month minimum award timing requirement in paragraph c. apply to Option 2, given its defined 365-day concurrent performance period? Specifically, please confirm whether: 1. The six-month award timing requirement applies only to the FF&E option and not to Option 2 – Industrial Equipment; or 2. Option 2 is also subject to the six-month minimum award requirement; and 3. How proposers should align scheduling and pricing assumptions for Option 2 in the event the option is awarded later in the Base Bid period.	1) Correct 2) No 3) Provide per solicitation
261	The QD drawings are identified as "Equipment Removals." However, the extent of the Contractor's responsibility related to removal, disposal, and potential salvage is not clearly defined. The clarification is requested to ensure proper allocation of scope, logistics, and pricing assumptions.	Yes.

	Is the Contractor responsible for the disposal of removed equipment?	
262	Will any removed equipment be salvaged; if so, will the salvage be performed by the Contractor?	No. Unless noted otherwise existing equipment is to be removed and disposed of.
263	Ownership of salvaged materials. Will the salvage value or proceeds accrue to the Government or the Contractor?	Any salvage value of materials noted to be removed and disposed of by the Contractor is to be accounted for in the Contractor's lump sum price proposal.
264	If salvage is required, will a specific location (onsite or offsite) be designated for delivery or storage of salvaged items?	No industrial equipment salvage is anticipated.
265	Will any removed equipment remain Government-owned and be protected, stored, or relocated rather than disposed of?	No.
266	It is our understanding the Government plans to relocate the existing bridge crane(s) within the building to allow Contractor to preform necessary repairs and that the Government will reinstall/relocate bridge crane following such repairs. Please confirm.	The Government will relocate the bridge cranes one time only, from their current locations to their final locations. The Contractor must work around the existing bridge cranes regardless of their locations. Crane will be moved within 45 days of Contractor making request to GOV.
267	During the site visit, it was observed that the existing bridge crane on first floor level was obstructed by miscellaneous electrical conduits and piping. Will the Government remove obstacles in the path of bridge crane for contractor to gain access? Or is the contractor responsible for removing these items?	The contractor is responsible for removing these items.
268	Please confirm the contractor is not responsible for testing and certifying the bridge crane since the contractor is reusing the existing bridge crane provided with building.	Confirmed. Contractor will not be certifying or operating bridge cranes. Contractor must coordinate with the Contracting Officer to schedule the Government to relocate cranes.
269	Will electric and water utilities consumption cost for course of construction usage be provided at no cost to the General Contractor?	Refer to Amendment 0009.
270	Detail A4 presents a Fire Alarm riser diagram with FA devices shown. There are no plans that show device locations within the building. Will fire alarm device layout drawings be provided?	See PPI 153 response.
271	As this project will require participation from several trades and designated parking is very limited will there be available	Refer to specifications for parking requirements. Price per solicitation.

	parking on base (and for how many vehicles) for this project; if so, please specify the physical location of this parking.	
272	How many phases or areas of the building will require a CIH work plan?	The number of phases or containment areas is not specified by the Government. This will be determined by the Contractor's proposed sequence of operations, means, and methods, proposed phasing and containment design, and based upon requirements identified in the RFP drawings, contract specifications, applicable regulations, and safety requirements. Price per solicitation.
273	Specification 02 82 00.00 is not clear what quantity of samples is required. In order to accurately estimate scope for Industrial Hygienist, please address the baseline sampling density for airborne asbestos and heavy metals (dust and air).	The Government does not specify the quantity or density of baseline sampling. The Contractor is responsible for determining the appropriate baseline sampling strategy, according to means and methods, proposed phasing and containment design, and based upon requirements identified in the RFP drawings, contract specifications, applicable regulations, and safety requirements. Price per solicitation.
274	Can the Contractor arrange the collection of the additional samples A. - E. during two consecutive days or one mobilization; or will they need to be sequenced ?	See response to PPI 216
275	Can the Contractor arrange the collection of the additional 30 - 40 dust wipe samples A. - E. during two consecutive days or one mobilization; or will they need to be sequenced?	See response to PPI 217
276	Are the pipes covered with asbestos insulation scheduled to be removed or stay?	Pipes covered with asbestos insulation are scheduled to be removed.
277	Will the abatement of the loose and peeling paint require full containment?	See response to PPI 218.
278	Will the abatement of the loose and peeling paint require post LCC dust wipe sampling?	See response to PPI 219.
279	Will the abatement of the loose and peeling asbestos containing paint require post air sampling?	See response to 220.

280	Will heavy metals dust cleaning on equipment require dust wipe verification sampling prior to removal and disposal?	See response to PPI 221.
281	Will brush/scrape paint removal on walls and architectural features require full negative pressure enclosures	See response to PPI 222.
282	Will brush/scrape paint removal on wood flooring require full negative pressure enclosures?	See response to PPI 223.
283	The specification section 02 83 00 Management of Lead, Cadmium, and Chromium (VI) is dated 10/23 and are not the latest version of this section. Is this latest version applicable for this project ?	See response to PPI 224.
284	Will NAVFAC consider modifying the frequency of area air sampling for Chromium (IV) for large or long duration tasks and what documentation/plans need to be submitted for review and approval?	See response to PPI 225
285	Note 4 directs the contractor to remove the existing exterior receptacle servicing trailer #2 and salvage it. The “existing keynotes” instructs this receptacle is to remain and be reused. Which is the correct direction?	The existing receptacle is to be removed, salvaged, and reinstalled in a new location. Refer to Keynote 4, Sheet ED101 and Keynote 1, Sheet EP101. The existing duraline connection/cable is existing to remain and must be disconnected from the receptacle at its existing location and plugged back into the receptacle at its new location. Refer to Existing Keynote 2, Sheet ED101 and Keynote 4, EP501.
286	Shows the power feed to trailer #2 and there are notes that indicate we need to temporarily feed trailer #2 and trailer #1. Can you tell us where the existing feed to trailer #1 is shown on the drawings?	Refer to Keynote 2, Sheet ED102. Refer to transformer in Storage 104, Sheet ED102. Refer to Keynote 12, Sheet EP501.
287	Can the existing building service be utilized for temporary power to trailers 1 and 2?	Refer to Keynote 6, Sheet ES101 and Sheet G-008, Electrical
288	Can the existing building service be utilized for construction power?	Refer to Keynote 6, Sheet ES101 and Sheet G-008, Electrical
289	The electrical demolition drawings indicate that the equipment will be removed and only disconnect switches will be left behind for removal under this scope of work. Is this a correct understanding?	No. Refer to the General Sheet Notes on the electrical demolition sheets for a description of what needs to be removed, in addition to the disconnect switches.
290	Do the existing emergency lights contain lead acid batteries that will require special disposal?	Refer to General Hazardous Materials Notes 6 on G-004A.

291	Existing network connection and telephone punchdown blocks are located in a different room from the future networking room. Do the existing data and telephone connections enter through the new network room or will these connection points need to be modified?	Existing telephone enters through the new network room. [Base Bid] Network N does not enter through the new network room. Refer to Keynote 7, Sheet ET501. One fiber optic cable serving Network P does not enter through the new network room. Refer to Keynote 9, Sheet ET501. The new Network P cable, indicated via Keynote 13, Sheet ET501, will enter the new network room. [Option 11] The new Network N and Network P outside plant fiber optic cables will enter the new network room. Refer to Keynotes 16 & 17, Sheet ET501. For reference, the ductbank indicated at Keynote 8, Sheet ES101, between B59 & B60, enters the new network room.
292	On drawing ED105 Note 4 indicates we are to disconnect power to existing attic exhaust fans. There are 4 locations where we see this indicated. Is it a correct understanding that there are only four attic exhaust fans?	There are 4 fans indicated with Keynote 4, Sheet ED105 and 2 additional fans called out on Sheet ED105 as "EF-E" and "EF60-2", with the "remove line type" that must be removed, as well.
293	Note 3 indicates we are to perform fusion splices to a 6mm network P cable. How many fibers are involved and will require splicing? Can the owner provide a length of cable necessary to perform this splicing as the location within building 59 is not indicated on the plans?	Refer to Keynote 2, Sheet ET106, this is the room within Building 59 that contains the existing fiber that must be spliced. This sheet also indicates the proposed pathway through Building 59. Provide splice to all 6-strands of fiber. Additionally, refer to Keynote 13, Sheet ET501.
294	ES101 note 5 indicates network cables for network P and network N are rooted to building 59 from building 60. This note is connected to a duck bank that connects 2 manholes and does not appear to enter building 59 or 60. How do these network cables connect to the two buildings and what length of cable will be required to make this connection?	This ductbank enters both Building 59 and Building 60 via pits located within each building. The location of the pit within Building 59 is indicated by Existing Keynote 1, Sheet ET106. The location of the pit within Building 60 is indicated by Keynote 7, Sheet ET102. Between these two sheets, and Sheet ES101 the cable lengths can be determined.
295	Note #8 indicates to seal conduits. Can the government clarify what they are asking for at this location?	Refer to General Note 17, Sheet E-001. The interior of the existing ducts entering into the pits within Building

		59 and 60 must be sealed after new cables are installed. The interior of conduits entering into Building 60 must also be sealed. Additionally, refer to Specification 33 71 02, 2.1.4 & 3.4.8.
296	Keynotes #1 indicate we are to remove 1000 feet of copper cable. Can the government provide a size of this cable? Are any of the cables to be removed lead covered?	For bidding purposes, assume three of the ducts contain a #2/0 bare, cut off, copper ground wire. Assume one of the ducts contains 3-1/C#2 cut off, wires. Assume the remaining cables are a 60A DC feeder. The cables are not anticipated to be lead covered.
297	Indicates a vertical fire rated chase will be required around the fire pump feeder. What rating should this chase have? Will the fire pump feeder be required to be fireproofed the length of its run back to the service?	The chase must be rated for 2-hours. Refer to Detail A4/AE501. Refer to Keynote 1, Sheet EP501 and Keynote 15, Sheet EP102. The concrete encased ductbank provides the required fire rating between the fire pump room and the service.
298	Indicates to provide a copper ground bar the length of the exterior wall as shown in detail A4 on drawing EP 502. The detail on drawing EP 502 shows individual ground bars but does not indicate a length or size. Is it the intent of the drawings that this should be a continuous copper ground bar or will individual ground bars at each piece of equipment with cable connections be acceptable?	Individual ground bars for each piece of equipment must be provided. A separate ground wire run from each ground bus must be provided back to the service ground ("star pattern"). Refer to amended sheet EP102
299	Must a separate ground wire be run from each ground buss back to the service ground or can the ground buss on each wall be chained together and a cable run back to the service ground?	A separate ground wire run from each ground bus must be provided back to the service ground ("star pattern").
300	Will the existing building radio master box be reused to provide connection to the fire station? If yes where is this master box located on the exterior of the building?	The existing masterbox will not be reused. However, it may be required to be maintained until the new masterbox is installed depending on the NFPA 241 plan developed by the KTR. The existing Radio Masterbox is located adjacent to the existing fire alarm control panel.
301	Indicates we are to reuse one set of existing conductors to provide temporary power for trailers. Will the government be adjusting the trip setting on the circuit breaker feeding these conductors?	The contractor must coordinate with the Government and the contractor must adjust the trip settings.
302	Shows a floor box with both power and data contained within it. Will the government permit both power and data within the same enclosure or will separate boxes be required?	Refer to Detail A1/EP505, Note 12. Divided compartments for power and

		communications are permitted within one poke through enclosure.
303	In corridor 102 there are two motion sensors shown. Do these motion sensors control all of the lights in the space or just the lights in the general area of the motion sensor?	The two motion sensors control all of the lights in the space: the (6) Type D1 fixtures in Corridor 102 located between columns J and N.
304	In vestibule 101 there are two motion sensors do these control the individual lights adjacent to them or do they operate the entire space? If a single motion sensor in this space will covered the area can the number of motion sensors be reduced?	"The two motion sensors operate the entire space. Yes, if a single motion sensor can be shown to provide complete coverage of the space, one sensor is acceptable. Ceiling height and potential obstructions from coiling doors must be considered.
305	On the security and technology plans there are RFID device stations indicated. There does not appear to be a coordinating power outlet at this location. Will power be required for the RFID equipment? If so how will this equipment be powered?	No, power is not required. The RFID are POE (power over ethernet) devices.
306	At what height will the RFID device stations be located?	Refer to Detail B4/ET502, Detail Note 7.
307	At what height will the TV outlets for the data system be located?	Refer to Detail C1/ET502.
308	Is it a correct understanding according to detail C1 on drawing EY 501 that security is only provided on exterior doors and there are no interior security islands?	No, that is not correct. Refer to the second floor of Detail C1/EY501 and associated Sheet ET105.
309	Please identify the NAVFAC Interior Design Representative and the NAVFAC Industrial Design Representative (if applicable) who will be responsible for review, coordination, and approval of the FF&E and/or Industrial Equipment scope.	Contractor to price their scope of work in accordance with the solicitation inclusive of Government review where required by the specifications.
310	The RFP provides general equipment information; however, key data necessary for means-and-methods planning, rigging design, structural verification, and safe installation appear to be undefined and subject to interpretation.If this information is not available, please advise whether the Contractor is expected to obtain this information directly from the OEM and whether any assumptions may be used for bidding purposes.F89 To ensure accurate pricing, logistics planning, and coordination, please provide the following for all applicable industrial equipment: 1. Confirmed equipment weights (including operational and shipping weights, if applicable). 2. Center of gravity (CG) locations. 3. OEM lifting points and rigging requirements, including manufacturer installation manuals or approved lifting diagrams.	The requested information will not be provided. Propose in accordance with the solicitation.

311	The RFP documents do not clearly identify responsibility or prescribed methodology for determining certain structural and site loading criteria necessary for equipment removal, delivery and installation planning. This clarification is requested to properly allocate responsibility and align pricing and logistical assumptions. Allowable slab loading limits – Please confirm whether allowable slab capacities have been determined by the Designer of Record (DOR) and where they are identified in the contract documents. If not identified, please confirm whether the Contractor is responsible for evaluating and verifying slab capacity.	The contractor is responsible for evaluating the existing slab capacity to support equipment and activities during construction. The existing slab thicknesses are indicated on sheets SD101 and SD102.
312	Slab thickness along heavy travel paths – Please identify where slab thicknesses are documented for areas anticipated to support heavy equipment transport. If not shown, please confirm responsibility for investigation and verification.	See response to PPI 311.
313	Known subsurface restrictions – Please confirm whether there are known subsurface constraints (e.g., utilities, voids, unsuitable soils) that would impact heavy equipment movement or crane operations and identify where such information is documented.	The existing known subsurface conditions are depicted on the contract drawings (civil and structural).
314	Crane outrigger loading limitations – Please confirm whether allowable ground bearing pressures or outrigger loading limitations have been established by the DOR, and where they are identified in the contract documents.	Establishing the allowable ground bearing pressures and/or outrigger loading limitations is considered Contractor means and methods, provided they comply with requirements defined in the project documents. The Contractor must coordinate to prevent damage to the site. Also, see responses to PPI 311 and 313.
315	Please identify whether the RFP prescribes a specific methodology for determining these criteria and clarify whether such evaluations are considered part of the Contractor's means and methods or are design parameters to be provided by the Government.	Note that Rigging and placement of equipment is considered Contractor means and methods, provided they comply with requirements defined in the project documents. See response to PPI 313.
316	"The contract documents do not appear to provide sufficient specificity regarding demolition and restoration requirements associated with equipment removal and reinstallation. This clarification is requested to ensure proper scope allocation and alignment of pricing assumptions. Housekeeping Pad Demolition – Is demolition of existing housekeeping pads required as part of the equipment removal scope? If so, please identify the applicable locations and extent of demolition."	Pad/slab removals are indicated on structural drawings.

317	Slab Restoration Standard – Following equipment removal and/or pad demolition, what is the required slab restoration standard (e.g., flush patch repair, structural repair, finish restoration to match adjacent slab, or full-depth structural replacement)? Please identify the governing specification section, if applicable.	Refer to General note 7 on QD101 for treatment at anchorage locations.
318	“Reinstallation Materials and Criteria – For equipment reinstallation, please confirm responsibility for providing anchors, epoxy, grout, and required torque values. Additionally, please confirm whether anchorage details and torque specifications are to be provided by the Designer of Record (DOR), the OEM, or determined by the Contractor.”	Unless noted otherwise, anchorage is to be provided by the contractor in coordination with OEM requirements.
319	The contract documents reference equipment installation and coordination activities that may require engineered lift planning; however, the specific requirements and approval process are not clearly defined. This clarification is requested to properly allocate engineering scope, schedule duration, and pricing assumptions. Critical Lift Determination – Which lifts are considered “critical” and require engineered lift plans? Is there a prescribed definition or criteria within the RFP (e.g., weight threshold, multi-crane lifts, proximity to structures, percentage of crane capacity, etc.)?	See response to PPI 313.
320	Professional Engineer (PE) Stamping – Are engineered lift plans required to be prepared and stamped by a third-party Professional Engineer? If so, please confirm the required discipline and state of licensure.	See response to PPI 313.
321	Government Review Duration – What is the anticipated Government review and approval duration for engineered lift plans?	See Specification Section 01 33 00.00 22, paragraph 1.11 for Government submittal review period.
322	Hold Points / Work Restrictions – Are there contractual hold points that prevent mobilization, lifting operations, or related work activities until lift plans are reviewed and formally approved?	See response to PPI 313.
323	Can the collection of the additional samples A. - E. be done during two consecutive days or one mobilization or will they need to be sequenced	See response to PPI 216.
324	Can the collection of the additional 30 - 40 dust wipe samples A. - E. be done during two consecutive days or one mobilization or will they need to be sequenced?	See response to PPI 217.
325	Are the pipes covered with asbestos insulation scheduled to be removed or stay?	See response to PPI 276
326	Will the abatement of the loose and peeling paint require full containment?	See response to PPI 218.
327	Will the abatement of the loose and peeling paint require post LCC dust wipe sampling?	See response to PPI 219.

328	Will the abatement of the loose and peeling asbestos containing paint require post air sampling?	See response to PPI 220.
329	Will heavy metals dust cleaning on equipment require dust wipe verification sampling prior to removal and disposal?	See response to PPI 221.
330	Will brush/scrape paint removal on walls and architectural features require full negative pressure enclosures?	See response to PPI 222.
331	Will brush/scrape paint removal on wood flooring require full negative pressure enclosures?	See response to PPI 223.
332	The specification section 02 83 00 Management of Lead, Cadmium, and Chromium (VI) is dated 10/23 and are not the latest version of this section. Is this version the applicable version to be utilized for this project?	See response to PPI 224.
333	Page 5 of section 01 11 00.00 22 states Contractor must provide commissioning specialist from a 3rd party. However, Part 1 General 1.1 Summary states "The Government has hired an independent Commissioning Firm." Please advise on if the contractor should price commissioning.	Building Envelope Commissioning is a process that is conducted by the Commissioning Team, which includes the government's CxB as well as the KTR's testing and verification company. Specification 01 91 19 describes the KTR's requirements. 01 11 00.00 22 is hereby amended.
334	Section 01 57 19 22 1.5.4 - Does the Environmental Manager need to be on-site 100% of the time?	The Environmental Manager must provide the required oversight of applicable programs as dictated in the project specifications. The presence of the Environmental Manager on-site would depend on the construction activities on that particular workday/week.
335	Section 01 57 19 22 3.1.2 – Understood that Environmental plans (SWPPP, etc.) need stamped by a Maine PE, however, do inspections need carried out by a PE or can they be done by a qualified inspector?	Inspections should be completed by a qualified inspector per State - Maine Certification in Erosion Control Practices (01 57 19.00 22)
336	Can excavation, foundation and pipe spoils remain on site?	Refer to specification Section 31 00 00.00 22 paragraph 1.4. Reuse of excavated soil as backfill is allowed given project specifications are met. Excess soils need to be disposed of in accordance with project specifications.
337	Is the contractor required to have a cultural resource manager or will this be provided by the Government?	Cultural Resources Manager is a Government entity that the Contractor must coordinate with where indicated.

338	Is the contractor required to provide the services of a historical architectural firm for concerns about the treatment of historic properties and adherence to the standard for historic buildings? Or will this be provided by the government (or has been provided via drawings) and an archeological and historical monitor are the only services required by the contractor?	Refer to requirements in 01 44 00.00 22, 04 01 00.91 22, and 01 11 00.00 22 which states that "Building 60 is an historic facility and requires special coordination to have limited impact on the historic facility and character defining features of the structure. Work must comply with the Secretary of the Interior's Standards for the Treatment of Historic Properties." Refer to the requirements in the specifications for technical qualifications and coordination procedures. Price per solicitation.
339	There is no requirement for the contractor to have a geotechnical engineer for the job however there is a requirement for the geotechnical engineer to be at the excavation meeting on site in specification section 01 30 00 – is a geotechnical engineer required of the contractor or is a testing agency enough?	Geotechnical engineer is required. Refer to specification Section 31 00 00.00 22 paragraph 1.6 for Quality Control requirements.
340	Specification 01 30 00.00 22 1.19.1 part f. Can follow-on partnering sessions be virtual?	No.
341	Will Contractor be required to provide a trailer for the government near the jobsite?	No.
342	Specification Section 01 91 00.15 3.1.3 refers to Design phase Commissioning Plan – this project is Design-Bid-Build and there is no design phase, please confirm.	Design Phase Commissioning is not the responsibility of the KTR. Specification 01 91 00.15 22 is hereby amended.
343	Would the government consider reducing the government review period to 7 days to facilitate full use of the period of performance?	No.
344	Should the contractor price commission separately for all options?	Contractor price each Line Item individually as applicable.
345	"Please provide latest geotechnical report for the project (boring logs previously provided in drawings)	Bid per solicitation. See response to PPI 116. Refer to unit price line items in the Price Schedule.
346	Will the government provide the radios for communicating with the fire department or will the contractor need to coordinate? If the contractor provides the radio for fire department and emergency services, who will program the radio?	The radio transmitter must be provided by the KTR. KTR to install and program the radio with GOV guidance.

347	For shop drawings that need approval from 3rd party sources (Emergency services etc.) who should submit the shop drawings for approval?	Section 01 30 00.00 22 does not refer to shop drawings and 3rd party approving services.
348	Is there any additional laydown space that can be provided to the contractor for trailers?	No.
349	For option 7 – has quantities been established for this asbestos and heavy metals for this work? If the quantity goes over contractor estimated amount how will this be paid?	1 Yes, refer to drawings. 2 Additional amounts will be handled via modification. Refer to Price Schedule.
350	Option 06 is listed as not applicable in the specifications however, option 06 is listed on drawing AE622 Window and Door Restoration Schedule. This seems to be option 05. Please clarify	See response to PPI 193
351	Please clarify what industrial equipment needs replaced in base bid versus option 2	Industrial Equipment must be included is Option 2. Note that the "(OPTION 2)" tag in Sheet titles indicates entire sheet is considered part of that option unless noted otherwise.
352	Please clarify if the ½" compressed air branch service with isolation valve as seen on P-106 is part of the base bid or option 2	Compressed air branch connection requirements are part of the base bid.
353	P109 – Key Note 1 – is the government to assume this is not needed if Option 3 is not awarded?	P109 Keynote 1 identifies base bid requirements, regardless of whether the government awards Option 3 (radon exhaust fans).
354	Who is responsible for testing for elevated Radon levels?	The Contractor
355	Please indicate what mechanical equipment needs removed by the contractor and what will be removed by the government.	Unless noted otherwise all mechanical equipment indicated for removal must be removed by the Contractor.
356	Please confirm anything that cannot be lifted by 2 people will be removed by the government.	Unless noted otherwise all mechanical equipment indicated for removal must be removed by the Contractor.
357	Please send approved pictures of mechanical equipment to be moved so the contractors can properly price removals	Pictures are not available.
358	Will the Jamaica Island parking be available for the contractors to use during construction?	See response to PPI 271.

359	Are their fencing requirements for the laydown area?	Requested information is within the documents. Price per solicitation.
360	Is the bridge crane to be removed from the building or just the jib crane?	Jib crane removal is part of the scope of work. The bridge cranes will remain and the Contractor must coordinate with the Government to relocate them as noted. Price per solicitation.
361	Can the 45 day notice to move the bridge crane be shortened if just moving the bridge crane from one end of the building to another? This will cause serious impacts to schedule	See PPI 266.
362	Note 8 shows an Overhead Door that is assumed to be the main access point to the building there are currently dumpsters and many other storage items in this area. Will these be moved by the government?	Yes.
363	Will the dumpsters be removed from the firelane?	If dumpsters are in the firelane, yes they would be moved.
364	Can the far north side of Turner St be used as additional laydown (where dumpster are now)?	Available laydown area is as defined on Sheet G-006 and will not be modified for additional laydown. If there is a dumpster(s) within laydown areas defined on this drawing, the Government will relocate prior to mobilization. Dumpsters outside of the defined laydown areas would not be moved.
365	The old ceiling has free space full of old asbestos insulation and ceiling panels - is it the responsibility of the contractor to abate all this asbestos even if ceiling is not being disturbed? Is there a quantity for this asbestos?	Bidders shall refer to the drawings for the exact scope and quantities required. The scope of this contract does not require the abatement of all existing asbestos on the first-floor ceiling. The assumption that the ceiling contains 'free space full of old asbestos insulation and ceiling panels' is incorrect. The material is an asbestos-containing textured surfacing and select transite panels. Requested information is within the documents. Price per solicitation.
366	Is the purple area described as "area available for contractor long term storage" the preferred location for contractor trailers?	No. It is not a preferred location for contractor trailers.

367	Are government trailers required on this project? If so, what are the contractor requirements?	No.
368	Are Office trailer 1 and Office trailer 2 currently occupied by NAVFAC, or can contractor use office trailers as field offices?	No. No.
369	The current submission timeline presents challenges in coordinating with specialty subcontractors and suppliers necessary to develop accurate and competitive pricing, Will the Government consider extending the proposal submission deadline by twenty-one (21) calendar days from current due date. We believe a modest extension would benefit the Government by increasing the quality and number of competitive proposals received, ultimately supporting best value to the Government.	Refer to Amendment 0006.
370	Does this note extend to Shop 119 and 120, or is it limited exclusively to 118?	Keynote extends to Shop 119. Add keynote 2 in room 119.
371	Where do the bridge crane wheel stop get relocated? What is the scope?	Existing Keynote 6 shows its existing location on the bridge crane. Keynote 6 with the text "(REVISED LOCATION)" is the new proposed location from the wheel stop. The Contractor must disconnect the crane wheel stop at its current location and re-attach it to the bridge crane rail in its new location. Price per solicitation.
372	Reference to "off-site equipment to building 60: 60 days". Coordinate construction schedule and sequence with the contracting officer for scheduling industrial equipment relocations. Duration is 60 days. What is being moved? Where is it being moved from? And, when will the equipment be ready to be relocated?	Contractor must inform Government when equipment delivery is desired and Government will deliver equipment indicated as EXIST from current locations to the overhead door at B60 within 60 days of request. Price per solicitation.
373	Par.1.3 states 608 calendar days. Solicitation Amd 0004 Factor 4 identifies 622 calendar days. Please identify the governing contract duration - 608 or 622 calendar days - and confirm whether a specification revision will be issued.	Refer to Amendment 0008. The correct duration is 622 days.
374	Tier 1 Infrastructure list referenced but not provided in bid documents. Provide the Tier 1 Shipyard Infrastructure list for the B60 project scope per Par.1.2(a), including all utilities, structures, and systems classified as Tier 1.	Refer to Amendment 004 documents.
375	Confirm whether finalized versions of Sections 23 23 00 and 23 81 29 will be issued by addendum prior to proposal due date, or whether bidders should price based on drawings only.	See response to PPI 143
376	Par.1.9.3.13 requires PCB Plan per Sections 02 84 33 and 02 61 23. Section 02 84 33 exists. Section 02 61 23 (PCB Contaminated Soils) not in TOC or spec volumes. Confirm whether PCB contaminated soil removal is within scope. If so, provide Section 02 61 23 or governing specification with anticipated quantities and locations.	There is no removal of PCB-contaminated soil within the scope of this project. The reference to UFGS Section 02 61 23 within UFGS 01 35 26.00 22 is not applicable to this project.

377	GFE per Equipment (Q) sheets with 45 CD advance notification only. No Government delivery commitment or schedule provided. Cannot establish delivery dates for P6 schedule. Provide anticipated delivery dates or windows for all GFE industrial equipment identified on Equipment (Q) sheets.	See response to PPI 372
378	Option 9: Government may exercise within 365 days of award. 186 CD concurrent with base bid. Cannot schedule, procure materials, or reserve subcontractors without exercise date. Provide anticipated timeline for Option 9 exercise decision, and confirm whether late exercise extends base contract duration.	Refer to amended Price Schedule and amended specification 01 11 00.00 22. Government will exercise Option 9 within 90 days of award. Date of exercise does not extend base contract duration.
379	Par.1.9.3.12 requires Site Safety and Health Plan per Section 01 35 29.13. This section not in table of contents or spec volumes. Reference suggests site may be contaminated. Confirm whether B60 site is classified as contaminated requiring Section 01 35 29.13. If so, provide the spec. If not, confirm reference is not applicable.	With reference to Specification Section 01 35 29.13, the site at B60 is NOT classified as contaminated. Refer to Continuation Sheet. The boundaries of the IR Site are specific to the footprint of Building 62A and the shoreline area behind Building 62. The limits of work for the B60 project do not extend into either of those areas. However, with some of the Contractor's laydown space being on the other side of the IR Site, note that the Contractor must avoid driving heavy equipment in the IR Site area. Note that soil samples were taken in vacuum excavation test pits at exterior of Building 60, and one boring inside Building 60. The results can be found on sheet B-005.
380	"SF105 General Note #1 states ""DO NOT STORE/STAGE MATERIAL ON ATTIC FLOOR FRAMING. PROVIDE TEMPORARY SHORING (WITH APPROVED ENGINEERED DESIGN) IF STORING/STAGING MATERIALS ON ATTIC FLOOR IS NECESSARY."" Based on the MEP work identified on P109, MH105, MP107, FX105, EP107, EL107, there will be permanent loads added to the attic. Please confirm no additional structural reinforcement is required for the new additional MEP loads and please confirm shoring is not required to install the permanent systems."	Requested information is within the documents. Price per solicitation.

381	Can you please provide the existing door hardware manufacturer?	Requested information is within the documents. Price per solicitation.
382	Section 01 91 00.15, paragraph 3.2.3.1.f requires the commissioning activities to include "Perform inspections, measurements, and testing of building envelope and roofing systems specified in Sections 07 42 13 METAL WALL PANELS and 07 42 63 METAL WALL PANEL ASSEMBLIES. In both of the referenced Sections the testing is specified as follows: "Leakage Tests: Finished application of metal wall panels are to be subject to inspection and test for leakage by request of the Contracting Officer, Architect/Engineer. Conduct inspection and tests at no cost to the Government." No test standard is included, and no scope of testing is identified. Please provide clarification.	Specification 01 91 00.15 22 is hereby amended. Refer to continuation sheet.
383	Section 01 91 19, paragraph 3.6.1 calls for tests in accordance with ASTM E783 and E1105. These two tests are typically run in tandem on installed windows. Section 08 51 70 "Steel Windows – Repair and Rehabilitation" does not require testing of any installed windows. Please verify whether any ASTM E783/E1105 testing will be required on the project.	Envelope tests are not always listed in item specific specifications because of all the specifications that might be involved at the junction, in this case, between the window and the rest of the assembly. Tests indicated in commissioning specifications are the responsibility of the KTR.
384	For Section 07 81 00 Sprayed Applied Fireproofing Page 4 section 1.6.2 Inspector Qualifications. Is an AMPP (Formerly NACE /SSPC) Certified Intumescent Coatings Inspector Level 2 is acceptable.	Yes, this is acceptable. See continuation sheet.
385	"Specification states ""Provide complete manufacturer's standard vision panels assembly consisting of clear acrylic glazing panels or fire-rated glass as required for the type door."" Drawing AE 601 - Door tags 101A and 101B for the overhead doors denotes ""N"" in the glazing column. Please confirm vision lites are not required for the overhead doors."	Confirmed - vision lites are not required
386	Drawing AE640 notes "CONC" for sealed concrete and references Division 3 for specification. It does not seem this specification is included within the	New concrete slab work is to be sealed, refer to Specification Section 03 30 00, paragraphs 2.4.3.1 (material) and 3.10.1.4 (installation). Existing concrete is not intended to receive a finish unless indicated. See

	Contract Documents. Please provide sealed concrete requirements and specifications.	Continuation Sheet, updated sheet AE640 and Specification Revisions for 09 67 23.13.
387	On drawing AD102, between grid lines K & J/ e4 & e6, it notes 1 - existing wood planks on concrete floor. The new finish plans (AE640), identify corridor 103 to have concrete floor. Please confirm the existing wood plank floor shall be removed in this location based on the proposed finish plans.	There is an area of existing strip wood flooring, original to the building, which is to remain. Under option 8, it is to be refinished. It's location and quantity is delineated on revised sheet AE102. Refer to amendment 008.
388	For the resinous flooring (option 10), the specification states to proceed with installation only after substrates have a maximum 75% percent relative humidity. Based on AE 640, finish plans, the resinous flooring will be installed in with new concrete slabs or concrete slab infills and existing slabs. Therefore the 75% maximum RH requirement will most likely not be met at the new locations based on cure time. The existing slabs may not have low RH depending on the existing underslab vapor barrier conditions. The specification does not provide any requirements for moisture mitigation. Please advise if moisture mitigation at resinous floor locations should be included within the bid for the option.	The Relative Humidity requirement can be adjusted to 85% from 75% with a 28 day cure time. Testing is required as per spec 09 67 23.13 Part 3.1 Provide moisture mitigation. Refer to Continuation Sheet.
389	For option 10, resinous flooring, please confirm resinous integral base is not required. Wall base would remain as indicated with the base bid option.	Integral resinous base is not required with resinous flooring. See finish schedule for specified wall base.
390	Details throughout this page identify "expansion joints". Do any of these conditions require firestopping and/ or be a fire rated assembly? Currently only detail A1 references firestopping.	Expansion joints must be smoke rated. Provide fire rated at locations indicated in details. Refer to updated sheets AE530 and AE531 and specification 07 95 00.
391	Specifications indicate wood siding, but not shown on drawings. Please indicate location.	Wood siding is not required on this project.
392	Can the collection of the additional samples A. - E. be done during two consecutive days or one mobilization or will they need to be sequenced	Refer to PPI 216.
293	Can the collection of the additional 30 - 40 dust wipe samples A. - E. be done during two consecutive days or one mobilization or will they need to be sequenced	Refer to PPI 217.
394	Are the pipes covered with asbestos insulation scheduled to be removed or stay	Refer to PPI 276.
395	Will the abatement of the loose and peeling paint require full containment	Refer to PPI 218.

396	Will the abatement of the loose and peeling paint require post LCC dust wipe sampling	Refer to PPI 219.
397	Will the abatement of the loose and peeling asbestos containing paint require post air sampling	Refer to PPI 220.
398	Will heavy metals dust cleaning on equipment require dust wipe verification sampling prior to removal and disposal	Refer to PPI 221.
399	Will brush/scrape paint removal on walls and architectural features require full negative pressure enclosures	Refer to PPI 222.
400	Will brush/scrape paint removal on wood flooring require full negative pressure enclosures	Refer to PPI 223.
401	The specification section 02 83 00 Management of Lead, Cadmium, and Chromium (VI) is dated 10/23 and are not the latest version of this section. Is this version the applicable version to be utilized for this project	Refer to PPI 224.
402	Will NAVFAC consider modifying the frequency of area air sampling for Chromium (IV) for large or long duration tasks and what needs to be submitted for review, consideration and approval	Refer to PPI 225.
403	The price schedule states for line item 3A - "Subtotal of Option Item 2 for the entire work associated with Industrial Equipment: procurement/installation of new equipment (identified as Option Item 2), but excluding work provided described in Line Item 1 – 2, 3B and 4 - 12. " There is Government estimated price for this line item. For clarification, please confirm this estimated value is for all items listed as "New" on drawing Q-601.	Confirmed. See also response to PPI 119 and 244
404	The price schedule states for line item 3A - "Subtotal of Option Item 2 for the entire work associated with Industrial Equipment: procurement/installation of new equipment (identified as Option Item 2), but excluding work provided described in Line Item 1 – 2, 3B and 4 - 12. " There is Government estimated price for this line item. For clarification, clarify if this includes the final MEP connections to the equipment..	See response to PPIs 119 and 244

405	The price schedule states for line item 3B - "Subtotal of Option Item 2 for the entire work associated with industrial equipment, including installation of government procured and provided equipment and associated utilities (identified as Option Item 2), but excluding work provided described in Line Item 1 – 2, 3A and 4 - 12." There is no Government estimated price for this line item. For clarification, please clarify if this line item is to include all items listed as "EXIST" on drawing Q601.	See response to PPIs 119 and 244
406	Schedule Key notes "EXIST" GOVERNMENT RELOCATED EQUIPMENT, CONTRACTOR INSTALLED. Please clarify the hand off between government and contractor requirements for these items. For example, will government move equipment into final location or will contractor be required to pick up equipment stored offsite and rig into place. Please clarify.	Government will deliver equipment to B60 at the west side exterior overhead door and the Contractor must place and install. Q-601 is hereby amended, refer to continuation sheet. See also response to PPI 167. Price per solicitation.
407	For example, in terms of cleaning new and ferrous surfaces, the specifications list " Where shop coat is missing or damaged, clean according to SSPC SP 2, SSPC SP 3, SSPC SP 6/NACE No.3, or SSPC SP 10/NACE No. 2." These are all different standards / methods to clean / prepare and is left ambiguous as to which one to follow. This happens multiple times in terms of surface preparation and cleaning for future paint / work. Please advise if in these situations the most stringent requirement shall be followed or it is left to subcontractor discrepancy since all are valid choices.	SSPC surface preparation must be performed in accordance with the paint manufacturer's printed instructions for the material to be painted. The choice for hand tool, power tool, or commercial blast with regards to metal substrate prep, is left to subcontractor's discretion. Also see responses to PPI 524 and PPI 535 where applicable.
408	Please confirm Option 5 in the price schedule / option is the same as Option 6 found on drawing page AE622.	See response to PPI 193
409	"Note 10 states ""ALL PIPING IN AREAS WITH SUSPENDED CEILINGS MUST BE CONCEALED ABOVE CEILINGS. ALL EXPOSED PIPE MUST BE PAINTED AND/OR LABELED IN ACCORDANCE WITH THE SPECIFICATION. ALL EXISTING PIPING THAT IS EXPOSED AND CURRENTLY NOT PAINTED, MUST BE PAINTED. ANY PIPING OBSERVED TO BE CORRODED THAT IS	All existing pipe will be removed. Revise note 10 to read: "ALL PIPING IN AREAS WITH SUSPENDED CEILINGS MUST BE CONCEALED ABOVE CEILINGS. ALL EXPOSED PIPE MUST BE PAINTED AND/OR LABELED IN ACCORDANCE WITH THE SPECIFICATION."

	NOT IDENTIFIED FOR REPLACEMENT MUST BE BROUGHT TO THE ATTENTION OF THE CONTRACTING OFFICER. "" Please provide locations of existing piping that requires to be painted."	
410	Sheet FA001 Note 9 notes that existing fire alarm system shall be maintained until the new fire alarm system has been installed, tested and accepted by NAVFAC Fire Protection Engineer and Engineer of Record. Can the existing FA as-builts be provided?	The as-builts for the existing fire alarm system are not available. NFPA 241 requires KTR personnel to be notified during an emergency. This can be accomplished with a temporary FA system or using the existing FA system. The plan developed per NFPA 241 is required to be approved by the GOV. Also see response to PPI 121.
411	Specification 01 45 00.00 22 requires Fire Protection Quality Control Specialist (QFPE) to "perform construction surveillance in accordance with the Schedule of Fire Protection System Inspections." The schedule included at the end of this specification section does not appear to have been edited for this project (all boxes unchecked). Please clarify scope of QFPE responsibility.	See response to PPI 109
412	The Statement of Special Inspections included at the end of Specification 01 45 35.00 22 identifies project seismic design category (SDC) as C, for which ASCE 7 typically specifies seismic design for architectural, mechanical, and electrical components (including fire sprinkler systems). Bid drawing S-002 identifies SDC as B. Please verify SDC and confirm whether seismic design requirements apply.	Sheet S-002 incorrectly identifies the building Seismic Design Category. The correct Seismic Design Category (SDC) is "C".
413	Bid drawing FA001, General Note #9, requires existing fire alarm system to remain operational until new system is installed, tested, and accepted. G-007, Construction Sequence Strategy, indicates existing fire alarm system will be removed before installation of new system. Please clarify extent to which existing fire alarm and fire sprinkler systems must remain operational during construction.	See response to PPI 121
414	FA-series bid drawings appear to generally omit fire alarm/mass notification system (FAMNS) notification appliance and initiating device layouts. FC 1-300-09N §7-11 requires design drawings to include this information. Please provide FAMNS device layouts to facilitate bidder cost estimates.	See response to PPI 153

415	Bid drawings FX001 and FX101 require fire sprinkler branch lines in “the annex” to be provided with threaded outlets for future ESFR sprinklers. Please specify maximum protection area and spacing of outlets (as determined by NFPA 13 Chapter 14) throughout annex.	10x10 spacing of 1-inch outlets.
416	Bid drawing FX103 appears to omit sprinkler design criteria for Stair 004 and adjacent utility space at First Floor Mezzanine level. Please clarify sprinkler design criteria for this space.	There is no utility space on the Mezzanine level. The stairs are only required to have sprinklers at the top and bottom since the stairs are noncombustible construction. Light hazard for stair sprinklers.
417	Please identify all concealed spaces where fire sprinkler protection is required. For example, section A1 on bid drawing AE221 appears to depict an interstitial space between ACT system in rooms 209, 210, and 211, and combustible mezzanine structure above.	All combustible concealed spaces are required to be provided with upright sprinklers.
418	Bid drawing FA102 appears to reference sprinkler system isolation valves for elevator pit and machine room; these valves aren’t referenced on FX102. Please clarify sprinkler and fire alarm requirements for elevator machine room, pit, and top of hoistway. For hydraulic elevators, UFC 3-600-01 generally requires separate isolation valves for pit and machine room sprinklers.	Isolation valves are required for elevator machine room and pit. In addition, waterflow device is required for the elevator machine room.
419	Fire pump layout on bid drawing FX400 doesn’t show a jockey pump. Please clarify whether jockey pump is required.	A jockey pump is required in accordance with 21 30 00.
420	Bid drawing FX400 shows the 8-inch fire service main entering the building through an exterior wall then changing direction to the backflow preventer suction. Please confirm whether fire service main must be restrained against movement at this location, and provide details of restraint.	Backflow preventor will be relocated. Refer to attached FX400 drawing modification.
421	Specification 21 30 00 §2.4.4.5 requires a “suction pressure regulating valve” in the fire pump assembly. This valve doesn’t appear to be shown on bid drawings; please confirm requirement.	Not all valves are shown on the drawings. Suction pressure regulating valve is required.
422	Specification 21 30 00 §2.13 requires fire pump assembly “to permit flow meter to discharge to pump suction and to discharge through test header.” Bid drawing FX400 shows flow meter discharging to pump suction but not directly to test header. Please confirm whether any modifications are required to the flow meter and test header configurations shown on FX400.	The discharge from the flow meter must connect to the test header. Refer to revised sheet FX400.

423	Specification 28 31 76 §2.13.3 requires mass notification text signs to display “EVACUATE” or “ANNOUNCEMENT”; this paragraph also refers to “scrolling text displays”. Please confirm whether mass notification signs limited to “EVACUATE” and “ANNOUNCEMENT” displays are sufficient, or whether scrolling text displays are required.	28 31 76 §2.13.3.g requires the date and time to be displayed when in non-emergency status.
424	Option Item 4 states to provide Video Surveillance Systems. However, the drawings do not show locations of video surveillance cameras. Please confirm if video surveillance cameras are required and where they are to be located.	Video surveillance system is not required.
425	Factor 1, Corporate Experience, requires that projects submitted were completed within (7) years of the proposal date for construction experience. We request that the 7 year completion requirement be revised to 10 years.	Propose in accordance with the Solicitation.
426	In Attachment T issued with Amendment 0004, bid line item 3 (“Option Item No. 2...”) appears to function as an offset to the Government’s estimate for FF&E associated with bid line item 2 (“Option Item No. 1...”). For clarity and consistency, should bid line item 2 be renumbered as “2A” and bid line item 3 as “2B,” and should the description currently labeled “Option Item No. 2” be revised to “Option Item No. 1”? Please confirm whether NAVFAC intends a numbering correction or whether the line items should remain as issued.	Price per solicitation. Bid line item 2 should not be renumbered. Bid line item 3 should not be renumbered.
427	Will the Government permit offerors to include a separate Assumptions and Clarifications document as part of the proposal submission? Box 2 of the SF-1442 identifies this procurement as “Negotiated,” and paragraph 3.2 states that the Government reserves the right to conduct discussions “except clarifications as described in FAR 15.306(a).” We believe that providing a concise Assumptions and Clarifications document would assist the Government in its evaluation and bid-conditioning process. Please confirm whether submitting such a document would be acceptable and not render the proposal unacceptable.	Propose in accordance with the Solicitation.
428	Referring to Attachment T issued with Amendment 0004, the Government has populated certain cells with its own estimated values. Please confirm that offerors should enter the same values in those cells, and that the brackets are not intended to indicate that offerors should provide negative dollar amounts.	Offerors should use the Government estimates where provided. Brackets do not indicate negative dollar amounts.
429	Please confirm that Attachments E and F are intended to reflect projected SBE participation for the MACC scope, and that Attachment D is to document historical SBE performance. Accordingly, please verify that no SBE exhibit or attachment is required with the bid for the Seed project.	Propose in accordance with the Solicitation, Attachment instructions, and PPI response #46.
430	Please confirm the Seed project price is subject to federal, state, and local taxes pursuant to the cited FAR clause 52.229-3 Federal, State, and Local Taxes and it is NOT tax exempt.	Propose in accordance with the Solicitation. Offerors are responsible for their own compliance with any applicable taxes.

431	Please provide the geotechnical report.	See response to PPI 116
432	"Quantities discrepancy between the ""Summary of ACM identified"" and ""Summary ACM to be removed"". Please clarify & confirm the removal quantities for the items below: a. Ceiling textured surfacing: 13,500 sqft identified / 400 sqft to be removed b. Transite Panels: 160 sqft identified / 0 sqft to be removed"	Items will remain in place unless indicated or required to be removed by project scope. Bidder to account for removal of quantities indicated "to be removed". Refer also to additional quantities indicated in the Price Schedule for unit prices.
433	Please provide the tables/summary of LCM (Paint), carbon black and PCB contained materials that required to remove from site.	A consolidated summary table of all materials for removal, in the format requested, is not provided. The comprehensive testing results were included in the RFP, and the definitive scope of work is detailed in the contract drawings and specifications.
434	Please identify/provide the location/area that require seeding & landscape construction maintenance.	Construction staging and storage areas may require repairs if disturbed by Contractor operations. See sheets G-006.
435	Under Factor 1B - Design Experience, the solicitation states, "For the purpose of evaluating Design Experience, a project is defined as a complete design effort performed under a single task order or stand-alone contract or subcontract." Will the Government accept projects involving multiple phases (i.e., Preliminary Design Authority [PDA]/preliminary or conceptual design, final design, Post Construction Award Services [PCAS]) of the same project awarded across different task orders, as a single project?	No. Propose in accordance with the Solicitation.
436	The Door Schedule indicates no glazing for doors 101A and 101B. Part 2.2.1.4 indicates that Coiling Overhead Doors are to be provided with the manufacturer's standard vision panels consisting of clear acrylic glazing panels or fire-rated glass. This conflicts with the Door Schedule notes. Are doors 101A and 101B to be supplied with vision panels and/or fire rated glass?	See response to PPI 385
437	General notes no. 7. Window Sash Replacement/Repair (20 nos) - please provide the details/size of the existing windows that stored in attic - existing sashes are painted & heavy metals containing paint..... what types of the hazardous materials need to abate? ACM, LCM or PCBs if contractor chooses to use for repair work - please confirm the cost for the additional existing windows sash remove, abate, repair/restore shall be price in Line item 6 - Option item no. 5.	For bidding purposes do not assume the use of the additional sashes in the attic for the repairs and restoration work indicated. Existing sashes can be evaluated during construction to determine if Contractor would like to propose incorporation of their use.
438	Please provide photographs typical of flooring areas to be repaired per Key Notes 4 & 7 on drawing AE105.	Photographs are not available. Keynote 4 indicates an area where there is existing racquetball court flooring over an existing wood strip flooring. The racquetball court flooring is scheduled to be removed. The wood strip flooring is not intended for refinishing but needs to

		be prepared to receive carpet tile. Keynote 7 indicates areas where plywood has been fastened to existing wood strip flooring. The plywood is scheduled to be removed and wood strip flooring to be refinished.
439	For the window noted to be salvaged and turned over the Government; is any restoration work required prior to turnover or is the window to be removed, salvaged, and turned over post restoration?	No. Restoration work is not required for window to be removed, salvaged and turned over to the Government. Price per solicitation.
440	There does not appear to be a waste receptacle included for the Expressing Rm 205. Please confirm this is correct.	A smaller waste receptacle is scheduled for that room in the FF&E package. See AE804.
441	Please confirm that there is no solid plastic locker bench item (J) included in the locker room or restrooms.	See response to PPI 162
442	For the historic borrowed lites to be reinstalled per KN7 - are these to be re-installed "as-is" after salvage or are they to be cleaned, painted, or restored in any fashion?	Scope for historic borrowed lites includes preparation and painting. Refer to drawings and specifications and price per solicitation.
443	Can the collection of the additional samples A. - E. be done during two consecutive days or one mobilization or will they need to be sequenced	See response to PPI 216
444	Can the collection of the additional 30 - 40 dust wipe samples A. - E. be done during two consecutive days or one mobilization or will they need to be sequenced	See response to PPI 217
445	Are the pipes covered with asbestos insulation scheduled to be removed or stay	See response to PPI 276
446	Will the abatement of the loose and peeling paint require full containment	See response to PPI 218
447	Will the abatement of the loose and peeling paint require post LCC dust wipe sampling	See response to PPI 219
448	Will the abatement of the loose and peeling asbestos containing paint require post air sampling	See response to PPI 220.
449	Will heavy metals dust cleaning on equipment require dust wipe verification sampling prior to removal and disposal	See response to PPI 221.
450	Will brush/scrape paint removal on walls and architectural features require full negative pressure enclosures	See response to PPI 222.
451	Will brush/scrape paint removal on wood flooring require full negative pressure enclosures	See response to PPI 223
452	The specification section 02 83 00 Management of Lead, Cadmium, and Chromium (VI) is dated 10/23 and are not the latest version of this section. Is this version the applicable version to be utilized for this project	See response to PPI 224.

453	Will NAVFAC consider modifying the frequency of area air sampling for Chromium (IV) for large or long duration tasks and what needs to be submitted for review, consideration and approval	See response to PPI 225.
454	What area will be made available for material laydown outside the building? If possible, it would be convenient if the parking lot on the west side of the building could be used for storage.	Refer to sheet G-006 - SITE CONSTRAINTS AND REQUIREMENTS PLAN
455	Please confirm whether there is a domestic steel requirement for micropiles.	Offerors are responsible for their own compliance with applicable clauses/regulations.
456	There is a gantry crane inside the building running above the proposed micropiles. Will this crane be made available to move materials within the building?	No. Contractor will not be able to use bridge cranes.
457	Prior to mobilization for the drilled micropiles, will the entire slab within the working area be removed or will there only be localized removals at proposed footing locations?	The Contractor must determine the means and methods of installing the piles. The Contractor must coordinate this work with their subcontractors.
458	A minimum of 15' of headroom is required for low headroom micropiles. Please confirm this will be the case throughout the working area.	Yes, upon completion of the demolition of the existing north mezzanine.
459	Please confirm that a water supply at hydrant pressure is available within 100' of the working area.	Refer to sheet G-100 for hydrant locations.
460	Will photos be permitted during construction for record keeping purposes?	Refer to 01 14 00.00 22
461	The Contractor must determine the means and methods of installing the piles. The method of installation must not damage GOV property, including but not limited to the existing building and its components.	The Contractor must determine the means and methods of installing the piles. The method of installation must not damage government property, including but not limited to the existing building and its components.
462	Is there a plan for ventilation of equipment exhaust?	Equipment exhausting must comply with EM 385-1-1.
463	Due to the significant size and complexity of reference projects anticipated to be submitted under Factor 1B – Design Experience, can the Government increase the total allowable page count for each design project data sheet to no more than two (2) double-sided pages (or four (4) single-sided pages)? This will enable offerors to provide more details about relevant features, which will help reduce ambiguity during the review process.	Propose in accordance with the Solicitation.
464	The contract drawings and Division 02 specifications identify removal of specific building components and systems; however, they do not appear to address removal of existing stored materials, inventory, furniture, or other loose contents currently located within B60 that are not shown. Please confirm that removal and disposal of these items will be performed by the Government and prior to Contractor receiving NTP.	For bidding purposes the Bidders are to include removals shown in the documents. Please note additional material removal requirements noted in General Note 8 on QD101. Also see response to PPI 156.

465	The contract documents indicate rehabilitation of existing windows, doors, and masonry at B60; however, the contractor was prohibited from taking photographs during the site walk due to shipyard security restrictions. Please provide Government-approved photo documentation of existing conditions sufficient to evaluate and price the rehabilitation scope.	Pictures are not available. Provide repairs and restorations indicated on AE622 and window survey per Window and Door Repair and Restoration General Notes 5.
466	Specification section 14 24 23 part 2.4.4 indicates an "in-ground direct plunger type hydraulic elevator" is to be provided. Please confirm that a plunger type elevator is required	See response to PPI 164
467	Per section 2.3 Glass and Glazing of the wood windows and doors spec, we are to "reuse existing intact original glass" and any "new glass and glazing materials must conform to Section 08 81 00 GLAZING". Please confirm the glass thickness, tempering, and fire rating on the new glazing units.	Revise paragraph 2.3 to read: "Reuse existing intact original glass. Reuse removed lights in their original frame and positions. New glass and glazing materials must conform to Section 08 81 00 GLAZING for Tempered Glass or must otherwise match existing glazing"
468	The contract details indicate the existing metal framing runs horizontally; however, the specified metal panel system requires vertical framing to achieve the required 16" O.C. fastener spacing and proper attachment of the corrugated panels, making the current detail unworkable. Please confirm if the panels may be installed vertically with horizontal corrugation or if additional vertical framing/sub-framing should be provided to accommodate the design intent.	Back-up metal wall panels will run vertical to attach to the existing horizontal framing. Outbound of that will be horizontal subframing to support the vertical corrugated siding. Refer to amended sheet AE511.
469	General Note 5 on AE622 references a window evaluation in Specification 080152/3.1. How will survey results alter the stated window repair conditions listed in base bid schedule on AE622	Survey results will be evaluated during construction. Price work per solicitation.
470	General Note 12 on AE622 references 20 sashes stored in the attic. Are these sashes from B60 mechanical intrusions and can they be used to infill the same locations in 60W1C, 60W1F, 60W1G, 601SA, and 60PN1A that currently are missing sashes?	It is unclear where the window sashes were removed from and may not match sizes of missing sashes.
471	Removal keynote 3 on AD203 references Window grills to be removed referencing historic restoration requirements. Are these grills to be retained and restored for future use?	No. Metal grills are to be removed and disposed of.
472	Removal keynote 3 on AD203 references Window grills. Do the window sashes exist currently behind the metal grills?	Yes, unless noted otherwise
473	There seems to be a contradiction in the window repair schedule on AE622 where repairs listed require NPS 2 restoration but the remark "F" states just to clean and paint. (i.e. 60E1B, 602NA). Please clarify repair scope.	Note F is associated with the Repairs which are included in the base scope. Restoration work is included in Option 5 - refer to Window and Door Restoration Schedule. See also response to PPI 193.
474	Are exterior window frames to be repaired or restored other than where metal grills have been attached?	Refer to Window and Door Repair Schedule on AE622 and elevation drawings and removal sheets. Note that per General Note 6 on the elevation drawings, the KTR is to "patch holes left by fasteners at

		removed utilites, window grates/grilles, etc. Coordinate with removals sheets." Price per solicitation.
475	Are the lower wooden panels in windows 8,9,10,11 to be scraped and painted in place in base bid and removed in the entirety off site for restoration in Option 6?	Yes, panels should be scraped and painted under base scope. Removal of sashes and frames to perform restoration/repair work is Contractor's means and methods. See also response to PPI 193
476	Do BL1, BL2 and BL3 that are being relocated require any repairs or restoration in Base Bid or Option 6?	Borrowed lights are to be prepared and painted under base scope, refer to details on AE621. Also see response to PPI 442. Price per solicitation.
477	Please clarify Key Note 7 (PATCH AND REPAIR WOOD FLOOR WHERE PLYWOOD WAS REMOVED. REFINISH WOOD FLOOR.) on Drawing AE105. Does the wood floor refinishing extend beyond the limits of the plywood is removed? If so, please define.	There are currently sheets of plywood (see AD104 for locations) fastened to wood strip flooring (which is throughout the majority of the 2nd floor). Once the plywood is removed, the entirety of the wood strip flooring (including areas that had no plywood over it) is scheduled to be refinished.
478	Amendment 0004 revises Factor 3 – Management Approach and removes the statement regarding consideration of seed project risks and mitigation. Please confirm that Factor 3 is intended to address the offeror's management approach for execution of the MACC overall, and not the seed project specifically.	Confirmed.
479	Spec Section 01 11 00.00 22 – Summary of Work identifies the Period of Performance for the Base Bid and Options; however, it does not provide detailed scope definitions or descriptions for each option. Additionally, the drawings highlighting the options do not provide sufficient information to accurately define or price the optional work. Please provide detailed scope descriptions and limits for Options 1 through 11 to support proper pricing.	Specification section 01 11 00.00 22 is hereby amended to add descriptions of the Options. See continuation sheet.
480	Can a press system be used for the domestic water system?	No.
481	Can a copper press system be used for the compressed air system?	No.
482	Can a press system be used for the heating hot water heating system?	No.
483	Can type L copper piping be used for hot water heating system?	Yes.

484	Detail C1 on Drawing C-502 shows the bituminous concrete pavement detail and the limits are defined on CR-101 and CS-101. Please confirm the intent is to only remove the existing wear and binder courses in these areas, leaving the base course intact.	See detail C1/C-502 Note 1 for related requirements. Note that if the gravel beneath the pavement is disturbed or quality degraded due to construction activities 18" base course shall be installed. Also, see General Sheet Note 8 on sheets CR101 and CS101 for other related requirements. Price per solicitation.
485	Spec 01 45 35.00 22 Quality Control - Para 2.1 indicates that work performed in the fabricators shop is to be inspected in accordance with the Schedule for Special Inspections if the fabricator is not AISC certified. Please confirm that the Schedule for Special Inspections for Structural Steel and Cold Form (Metal Decking), Sections A thru F, apply to both field and shop work. We ask this to be clear on inspection activities that must be provided for with a 3rd party agency if fabricator is not AISC certified.	As an AISC certified fabricator is required per specification section 05 12 00, paragraph 1.3, shop inspections are not required.
486	KEYNOTE 2/SF104 - Option 7: Regarding recoating previously coated existing steel with (ASTM) A780 Cold Applied Galv Paint as indicated, the note indicates to remove loose and flaking paint. Is the intention to scrape loose paint from surface with hand tools or will power tool cleaning to SP11 or abrasive blast be required. Note: many of the high zinc coating manufacturers are likely to require there be no residual coatings and to provide abrasive blast surface prep, although a power tool clean to SP11 may be sufficient. Other products may be more surface tolerant than zincs and could be considered.	The SSPC surface preparation method must be in accordance with the cold-applied galvanizing paint manufacturer's requirements. Price per solicitation.
487	Spec 05 12 00 with regard to GC steel design responsibilities: a. Para 2.1 – SYSTEM DESCRIPTION notes "...including design...". Please confirm that no structural steel design is to be provided by the GC on the seed project?	Structural steel design is not required except for the items specified to be a delegated design (i.e. stair framing and railings). Price per solicitation.
488	Spec 05 12 00 with regard to GC steel design responsibilities: b. Para 3.2 – CONNECTIONS notes "Except as modified....design connections...". Connections appear to be designed in the contract drawings. Please confirm that no structural steel connection design is to be provided by the GC on the seed project?	Structural steel connection design is not required except for the items specified to be a delegated design (i.e. stair framing and railings connections).
489	Keynote 12/SF101 indicates metal pan stairs, landings, and rails to be delegated design. Keynotes on SF101 are indicated "(this sheet only)" so would apply to Stair 002 and M110. Please clarify if stair 005 is also delegated design.	Stair 005 is a delegated design. The "THIS SHEET ONLY" reference is indicating the keynotes on the sheet apply to the corresponding sheet and do not otherwise refer or restrict design requirements elsewhere throughout the documents.
490	Stair in C4/AE440 is identified as M110. In C1/AE442 this stair is identified as M107. Please clarify correct stair number.	Stair is for M110. Revise detail C1/AE422 title to read: "STAIR M110 SECTION"
491	Keynote 12/SF102 indicates stringers for Stair 002 and Stair M110 are to be C12s. Please provide stringer weight/LF, or member size to selected by designer?	The stringer size must be 12-inches deep, but the final stringer channel

		size will be determined by the delegated designer.
492	Stair 005 as shown in C3/SF101 and C1/SF504 indicates (2) stringers to be MC12x10.6. Does this stringer size apply to the others in Stair 005, or is member size to be selected by designer?	The stairs inside Fire Pump room M107 are not part of Stair 005. Stair 005 is outside of the Fire Pump room and is a delgated design. The stairs within the Fire Pump room have been designed as part of this project. Detail C1/SF504 is only applicable to the stair within the Fire Pump room.
493	Regarding Stair 004, structural and architectural drawings indicate there are no removals and only the addition of a guardrail/handrail to existing stringer along the wall side from first level to the intermediate landing. Please confirm/clarify that this is the requirement.	Provide railing as indicated as well as repairs at first floor and guardrail at second floor adjacent to window. Refer to amended sheet AE441.
494	Regarding Stair 004, Keynote 1/AE441 indicates to replace riser and patch hole in stringer. Please provide details for these repairs.	Detailing to match existing stair and is similar to A3/AE444.
495	Keynote 8/AE105 indicates to provide guardrails at existing windows. We noted that the (4) northmost windows along Grid e4 and the (1) eastmost window along Grid p appear to have guardrails drawn, but do not have a Keynote 8 note. Please clarify if these windows require guardrails.	Windows 60E2I, 60E2H, 60E2G, and 60E2F do not require the guardrails.
496	From AE104, section A1/AE223 is cut (near e6 from p to f). In that section where the MECH MEZZ (M110) is shown, it appears the guardrail (small amount shown behind equipment) is 4-line fall protection rail per D1/AE445. Please confirm that is the type of rail required around the unprotected edges of this mezzanine.	Confirmed. Refer to detail D1/AE445. Confirmed, railing is to be provided at unprotected edges. Refer to updated sheet AE104 for locations.
497	Are the guardrails provided for window protection (A4/AE626) and fall protection at Mechanical Mezzanines (D1/AE445) to be included as part the delegated design responsibility/scope for pans stairs, guardrail, handrail, etc.? If not, please provide missing details for rail fabrication and installation (material, welds, fasteners, etc.).	Yes, railings at mech mezz and window protection railings are to be included in delegated design.
498	Is there a specific wage determination general decision applicable to the project?	Refer to Amendment 0007.
499	Please provide clarification on the scope of the Government's Independent Commissioning firm. The specification states that "The Government has hired an independent Commissioning Firm. This Section specifies the scope of work for the entire Commissioning Team which includes the scope of work for the Lead Commissioning Specialist, Commissioning Specialists, Designers of Record, Installing Contractors, and Equipment Suppliers." Are the CxC, CXS-M and CXS-E provided by the Government?	Lead Commissioning Specialist (CxC) and Technical Commissioning Specialists (CxM-H (HVAC), CxM-P (Plumbing), Cx-B (Building Envelope), and Cx-E (Electrical)) are hired by the government.
500	Please extend PPI deadline by 2-weeks to allow bidders sufficient time to address scope needing clarification. Again, the current proposal due date aligns with other NAVFAC solicitations, which is hindering subcontractors and small business's ability to properly respond to each solicitation.	Propose in accordance with the Solicitation. Please refer to Amendment 0006 for the revised proposal due date.

501	The base contract duration was updated in several documents in Amendment 0004, however there are still some conflicting dates within the documents. The updated Price Schedule from Amendment 0004 (Att. T), General Note B states that the contract completion date of 622 calendar days does not change with the award of Line Items 6 through 12. Specification 01 11 00.00 22 Paragraph 1.3 has an estimated period of performance of 608 calendar days. It is understood from prior responses the base bid duration is to be 548 calendar days, however please confirm the period of performance for each of the options.	See response to PPI 195. Please refer to Amendment 0008.
502	The specification states groundwater is estimated at "mean high water level" but subsequently mandates dewatering be planned for the "elevation of the highest tide." Drawing general notes indicate the highest observed tide is El. 8.1' while Mean Higher High Water is El. 4.2'. There is a 4-foot difference in hydraulic head between these two standards. Please clarify if the dewatering system design must account for continuous operations at Elevation 8.1' (Highest Tide) or if the system can be designed for Mean High Water with temporary suspension protocols during extreme tide events.	The elevations provided on the drawings are data points. The work may be phased with the tide cycles. Provide necessary controls required to manage dewatering activities required to complete the work within the specified contract time. Submit dewatering work plan prepared by a Professional Geotechnical Engineer licensed in the State of Maine.
503	Will rock removal be paid via a Unit Price schedule, or is the Contractor responsible for all rock removal as incidental to the Base Bid regardless of actual quantity encountered?	Contractor is responsible for calculating required rock removal based on information provided in documents and must be included in this quantity in the base bid CLIN 001 work. Item 1K quantities are for scope not otherwise indicated in the plans, specifications or reports provided with the solicitation.
504	Section 31 00 00.00 22 states "Testing results used for geotechnical analysis cannot also be used for waste characterization." Since the Government-provided environmental test results (Sheet B-005) identify contaminants (Arsenic, Lead, PAHs), can the Contractor rely on this data for bidding disposal costs, or must the Contractor carry the cost to re-sample and characterize 100% of the soil for off-site disposal prior to excavation?	Criteria for bidding is in specification section 31 00 00.00 22 paragraph 1.4. The tests provided are for bidding purposes. The Contractor is also required to provide testing of soils as indicated in specifications.
505	The specification states "Activity cost loading must be without front-end loading." Does the Government define mobilization, bonding, and insurance costs as "front-end loading," or can these be paid as distinct line items upon proof of payment/incurrence?	Mobilization should not be a line item on the SOV unless it is a large activity (i.e. dredging). It is a direct cost to the project. However, it should be included in OH cost. The same applies for insurance. That again, is a direct cost to the project, but should be included in OH cost. Bonding is allowed to be a line item on the SOV, is allowed to be invoiced, and paid prior to approval of the SOV. Note that the Solicitation will result in a Firm Fixed Price Contract. Propose in accordance with the Solicitation.

506	The specification lists conflicting floor flatness/levelness requirements: "Floor Flatness (Ff) 35 24 minimum and Floor Levelness (FL) 25 17 minimum." Please clarify which tolerance applies. Ff 35/FL 25 (Industrial/Flat) requires different finishing techniques and costs than Ff 24/FL 17 (Commercial/Moderately Flat).	The floor flatness and floor levelness values listed in the specifications show the "Specified Overall Value" (the first number) and the "Minimum Local Value" (the second number). These numbers are meant to be used in conjunction with one another.
507	Drawing AD121 indicates removal of roofing in the West sector. Please confirm if the existing roof insulation is to be removed down to the deck or if the intent is to recover the existing insulation. The demolition scope implies full removal, but sustainability specs often encourage reuse.	Roof system/Insulation should be removed down to existing deck.
508	Drawing G-004A, Note 7 states "Existing industrial equipment/processes have produced heavy metals residue." CLIN 002 covers the removal. The "residue" cleaning standard is undefined. "Decontamination" could mean a simple wipe down or a rigorous process requiring confirmatory lab testing (wipe sampling) to meet unrestricted release standards. Question: For the removal of industrial equipment under CLIN 002, what is the required clearance standard for "heavy metals residue"? Is a "visual clean" standard sufficient for disposal/recycling, or is the Contractor required to perform confirmatory wipe sampling to verify residue levels are below a specific threshold (e.g., HUD standards) prior to removal?	The required clearance standards are explicitly defined in UFGS 02 83 00.00 22, included in the contract documents. The standard is dependent on the location of the work. The Contractor is responsible for reviewing the drawings to identify the type of space where work is occurring and applying the corresponding clearance standard from UFGS 02 83 00.00 22. A 'visual clean' standard alone is not sufficient for all areas of the project.
509	The specifications mention limited parking and a requirement for an "Employee Parking Plan," hinting that POV parking on Jamaica Island is not guaranteed. Please confirm if the Government will provide sufficient on-base parking for the Contractor's entire workforce. If on-base parking is full, is the Contractor required to provide off-base parking and shuttle services at their own expense?	The Government is not obligated to provide sufficient parking. See response to PPI 271.
510	The spec states: "Testing results used for geotechnical analysis cannot also be used for waste characterization." However, Sheet B-005 provides environmental test results showing Arsenic and Lead contamination. Can the Contractor rely on the data in Sheet B-005 to profile soil for disposal pricing during the bid phase? If not, does the Government expect the Contractor to carry the risk of assuming all excavated soil is hazardous until proven otherwise by post-award sampling?	See response to PPI 504.
511	Solicitation Excerpt; Clause: "Prohibition on Contracting for Certain Telecommunications... (Huawei/ZTE)". - Issue: The solicitation enforces FAR 52.204-24/25/26, strictly prohibiting equipment from Huawei, ZTE, Hytera, Hikvision, and Dahua. This project includes Option 4: Electronic Security Systems (ESS) and Option 11: Communication Service Routing. - Inquiry: Given the ubiquity of chipset components from these manufacturers in "off-the-shelf" security cameras and communication devices, does the Government require the Contractor to provide "Representation" (proof of non-use) down to the internal chip/board level for all ESS and Comm equipment, or only for the end-unit manufacturer? This impacts the selection of the ESS integrator and equipment lead times.	Offerors are responsible for their own compliance with applicable clauses.

512	Clause: "The Contractor shall begin performance within 10 calendar days". ◦ Issue: The requirement to start performance within 10 days of award conflicts with the practical reality of obtaining DBIDS (Defense Biometric Identification System) passes and security clearances for a new workforce at Portsmouth Naval Shipyard (PNSY), which often takes weeks. ◦ Inquiry: Does the Government define "begin performance" as administrative tasks (e.g., bonds, insurance, APP submission) or physical onsite mobilization? If physical presence is required in 10 days, will the Government expedite security badging for the Superintendent and SSHO?	The requirement is to start performance within 10 days from the notice to proceed.
513	The specification states: "All other containers of waste hazardous materials... must be turned in to Building 357 by the end of the shift generated." Risk: This requirement prohibits the standard practice of maintaining a secured 90-day accumulation area at the job site. Transporting waste to Building 357 at the end of every shift creates a severe logistical burden, reduces labor efficiency, and increases handling costs. Question: Will the Government permit the Contractor to establish a secured, compliant 90-day Hazardous Waste Accumulation Area within the project limits to consolidate waste before transport, or is the requirement to transport waste to Bldg. 357 at the end of every single shift mandatory?	The requirement to transport all hazardous waste to the Building 357 Hazardous Waste Storage Facility by the end of the shift in which it was generated is mandatory and is the baseline requirement for this contract. Bidders shall base their proposals on adhering to this requirement.
514	The specification requires the Contractor to hire a "third party, qualified independent utility locating company" and explicitly states this "Cannot be the Government's Utility Locating Firm." Risk: If "The Government's Utility Locating Firm" refers to the specific contractor currently holding the base-wide utility maintenance contract, they often possess the most accurate institutional knowledge of the site. Excluding them increases the risk of utility strikes and forces the Prime to hire a firm less familiar with the Shipyard's complex infrastructure. Question: Please clarify the restriction on using "the Government's Utility Locating Firm." Does this exclude specific local vendors who may have the best knowledge of the Shipyard's infrastructure? If so, please identify the excluded firm(s) by name to ensure we do not inadvertently solicit bids from prohibited vendors.	Exclude the Government's Utility Locating Firm: Pro Mark Locating Services
515	The specifications list "QC Specialist - Mechanical" and "QC Specialist - Fire Protection" as required personnel. While the QC Manager, Superintendent, and SSHO are explicitly listed as "Sole Role" (dedicated) positions, the restrictions for QC Specialists are ambiguous regarding whether they can also serve as the trade foreman. Question: Can the required QC Specialists (Mechanical, Electrical, Fire Protection, etc.) be the Trade Foreman or Superintendent for that specific discipline, or does the Government require these to be dedicated Quality Control personnel with no production responsibilities?	FPQC/QFPE is required to be a 3rd party who is independent of the design team. The roles and responsibilities are clearly defined in Section 1.6.7 of Section 01 45 00.00 22. Price per solicitation.
516	Temporary Water Source Restriction Reference: Section 01 50 00.00 22, Paragraph 3.2.2 (Temporary Facilities). Issue: The specification states "Under no circumstances will taps to Shipyard fire hydrants be allowed for obtaining domestic water." Question: Since hydrant use is prohibited, please identify the approved point of connection for construction water.	For construction water, a temporary water connection to a fire hydrant may be requested by the Contractor. Note that Contractor must meet all related requirements in the Construction Documents, including but not limited to providing certified backflow preventing device(s), and

		obtaining review & approval by all Government reviewers and AHJ's involved. See Section 01 50 00.00 22 for additional information. Note that connecting to an adjacent building spigot would also be allowed if meeting all of the same requirements described for a fire hydrant. Refer to Continuation Sheet.
517	The specification states: "Work which will breach CIA fencing is prohibited unless... a Portsmouth Naval Shipyard Police representative is at the worksite during the period that the fence has been breached." Question: Paragraph 1.6 requires a Portsmouth Naval Shipyard Police representative to be present during work that breaches the CIA fence. Is the cost for this Police detail a Government-furnished service provided at no cost to the project, or must the Contractor include costs to reimburse the Shipyard for these security personnel?	Police are Government furnished.
518	The definition of "Tier 1 Infrastructure" states: "Coordinate with the Contracting Officer for a list of Tier 1 Infrastructure... This includes a 12-inch water line running under Building 60." The phrase "This includes" implies the list is not exhaustive. Question: Section 01 14 00 identifies the 12-inch water line under Building 60 as Tier 1 Infrastructure. Please confirm that this water line is the only Tier 1 Infrastructure element within the project limits. If other utilities are classified as Tier 1, please provide the full list to ensure accurate pricing of the required Risk Mitigation Plans.	Confirmed
519	Drawing HM-001, General Hazardous Materials Note 1 requires the Contractor to inspect for "unidentified" materials and includes a requirement to collect and analyze a specific quantity of new samples (30 Asbestos, 10 PCB, 15 Heavy Metals, 10 TCLP). Question: General Hazardous Materials Note 1 on HM-001 requires the Contractor to perform a survey and include costs for additional sampling (30 Asbestos, 10 PCB, etc.). If this post-award survey identifies hazardous materials not currently shown on the HM drawings, how will the abatement of those newly discovered materials be paid? Should the Contractor carry a unit price allowance for abatement of unknown materials?	Results of post-award survey will be evaluated based on findings at that time. Unit Prices are included in the pricing sheet for anticipated hazardous materials. Price per solicitation.
520	Please clarify the Contractors responsibility for the Building Envelope Commissioning Specialist (CxB). It is unclear from the documents whether this individual is part of the Government or Contractor's commissioning teams.	Refer to response for PPI 499. Contractor must support commissioning efforts as specified in documents.
521	Section 01 45 00 requires a "QC Specialist - Fire Protection (FPQC)" who "Cannot serve as Special Inspector." Section 21 13 13 requires a "Qualified Fire Protection Engineer (QFPE)" who must be a Registered P.E. to witness testing. Question: Can	Yes. The QFPE can be the FPQC.

	the "Qualified Fire Protection Engineer" (QFPE) required in Section 21 13 13 also serve as the "QC Specialist - Fire Protection" required in Section 01 45 00, provided they meet the on-site presence requirements?	
522	The specification requires the Contractor to submit a Progress FDW at 50% completion and "Field verify a portion of the eOMSI information." Question: Regarding the Facility Data Workbook (FDW) Progress Submittal, Paragraph 1.3.1 requires the Contractor to "field verify a portion of the eOMSI information." Please define the specific percentage or sample size (e.g., 10% of assets) required for this field verification to allow for accurate labor estimating.	Refer to Section 01 78 24.00 22 para 3.1 where the number of subsystems and related criteria are defined for the portion required.
523	Section 02 82 00 (Asbestos) states: "The Portsmouth Naval Shipyard Hazardous Waste Facility takes title and is responsible for all asbestos waste disposal." Section 02 83 00 (Lead/Heavy Metals) states: "All hazardous wastes generated... will be considered Government-generated, and disposed of by the Government." However, Price Schedule CLIN 003 requires pricing for "management/abatement and removal." Question: Sections 02 82 00 and 02 83 00 explicitly state that the Government takes title to and responsibility for the disposal of Asbestos and Heavy Metal hazardous wastes. Please confirm that the Contractor's pricing for CLIN 003 should exclude off-site disposal facility tipping fees and should only cover abatement, packaging, and transport to the PNSY Hazardous Waste Facility (Bldg. 357).	Confirmed.
524	Section 02 83 00 states: "The use of abrasive removal equipment is prohibited unless expressly approved by the NAVFAC Cultural Resources (CR) Managers." Conversely, Section 09 90 00 typically requires SSPC-SP 6 (Commercial Blast Cleaning) for existing structural steel preparation, and Drawing S-001 confirms existing steel is coated with lead-containing paint. Question: Section 02 83 00 prohibits abrasive blasting on lead-containing surfaces without specific approval, while Section 09 90 00 and standard industry practice require abrasive blasting (SSPC-SP 6) for structural steel surface preparation. Will the Government grant blanket approval for abrasive blasting of structural steel provided containment measures (Class 1A) are met, or must the Contractor bid the significantly higher labor cost of Power Tool Cleaning (SSPC-SP 3) for all existing steel?	02 83 00 is limited to the management of lead, cadmium, and chromium during renovation, demolition, removal, and abatement. The note about "prohibited unless expressly approved" is to prevent bricks from being damaged by abrasive blasting to remove paint. Abrasive blasting to prepare structural steel as specified in 09 90 00 is acceptable for this project except for conditions where otherwise noted. Note that abrasive blasting is prohibited for surface prep work on the exterior steel buttress frame and other structural beams coated with asbestos containing paint on the exterior south side of the Annex.

525	Amendment 0004 identifies that work within Buildings 13, 59, and 86 requires continuous Government escorts. Please clarify if a separate escort is required for each trade, person or group of people. Can we be guaranteed escort availability to prevent delays to monitoring related scopes of work?	One Government escort is required per three people. Escorts must have visual and physical control of people they are escorting. Escorts must be requested per the specifications.
526	Spec states the Archaeologist must identify a repository and pay initial curation fees. Does the Navy have a standing agreement with a preferred repository (e.g., a state-approved facility), and if so, can the Government provide a fixed fee schedule for bidding purposes to ensure price consistency among offerors?"	The Navy does not have a standing agreement with a preferred repository.
527	If a potentially significant resource is encountered, the Archaeologist must formalize an Archaeological Resource Report within 2 business days. Once submitted, what is the maximum Government turnaround time for a determination of significance and authorization to resume work in that area?	Propose in accordance with the solicitation.
528	Section 02 41 00 states "Scrap metal is the Contractor's property." However, Section 02 83 00 states all hazardous waste is Government property. Much of the scrap metal is coated in lead paint. Section 01 57 19 clarifies that scrap with PCBs >50ppm is hazardous waste. Question: Please clarify the ownership and disposal path for structural steel coated with lead-based paint (but <50ppm PCBs). Does the Contractor take title to this material for off-site recycling as scrap metal (standard industry practice), or must this material be treated as Government-generated hazardous waste and turned into Building 357?	Structural steel and other scrap metal coated with heavy metals containing paint shall be considered the Contractor's property, provided it is destined for recycling. Per Federal regulation 40 CFR § 261.6(a)(3)(ii), scrap metal being reclaimed is generally excluded from RCRA hazardous waste regulation. Therefore, the Contractor shall take title to this material and is responsible for its management and transport to an appropriate recycling facility. Pricing for this work shall be inclusive of all costs to prepare, handle, and transport the material for recycling. This material shall not be turned in to Building 357. Price per solicitation.
529	Drawing Volume 2a, plan sheet FX001 indicates three Keynotes for Detail A2. There are no Keynotes on plan sheet FX001. Please clarify.	The keynotes shown are hydraulic data points, not keynotes.
530	The specification requires the Contractor to remove the elevator plunger and fluid, and then: "The existing in-ground casing must be completely filled with flowable concrete." Question: Regarding the abandonment of the elevator casing, if the casing is compromised and cannot contain the flowable concrete, at what point does the Contractor's obligation to fill the casing	There is no existing elevator. Delete paragraph 3.1.14 in specification section 02 41 00.

	cease? Will the Government accept a cap/plug at the top if the casing bottom is "bottomless"?	
531	Please clarify the frequency for the QC specialists to be on site, whether it is on the construction site or a fabrication facility, as seen on 01 45 00.00. Is the intent that the QC specialist be working one day or multiple days for each week they are required?	Frequency of QC visits is outlined in "Experience Matrix" under paragraph 1.6.6
532	The specification states: "If there are less than 1600 "No PCB" labeled lighting ballasts, dispose of them as normal demolition debris." This sentence appears to be a typo or logically inverted. Usually, "No PCB" ballasts are always non-hazardous, or unlabeled ballasts are assumed PCB. The threshold of 1600 seems arbitrary and high for a "less than" condition regarding labeled non-PCB items. Question: Paragraph 3.3.1 states that if there are less than 1600 "No PCB" labeled ballasts, they may be disposed of as normal debris. Please clarify the intent of this quantity threshold. Are "No PCB" labeled ballasts considered regulated waste if the quantity exceeds 1600?	Ballasts labeled as "No PCB" may be treated as non-hazardous. The 1600 count threshold for Non-PCB Ballasts stated in UFGS 02 84 16.00 22 is significant as it acts as a trigger for notification to the National Resource Center of the disposal of greater than 100 pounds of DEHP, the Reportable Quantity for DEHP under CERCLA. For the purposes of this project it is irrelevant as there are not 1600 ballasts to be removed from the building.
533	The specification requires the Contractor to "Locate area of unsound concrete using hammer sounding method" and "Denote and mark perimeter boundaries." It does not quantify the amount of unsound concrete anticipated. Without a baseline quantity (e.g., square footage or cubic yards) of spall repair or delamination repair provided in the bid documents, the Contractor is exposed to undefined scope. "Unsound concrete" is a latent condition. If 20% of the existing slab is unsound, the cost is massive compared to 2%. Question: Section 03 01 00 requires the Contractor to sound the concrete and identify areas for repair but does not provide an estimated quantity of repairs. To allow for equitable bidding, please provide a baseline quantity (e.g., square feet of spall repair/delamination) to be included in the Base Bid, or establish a Unit Price schedule for concrete rehabilitation beyond a defined threshold.	Specification Section 03 01 00 only applies to the work shown in OPTION 7, which are local areas identified on sheet SB101 by Keynotes 9, 10, and 12. The scope of work area are defined in details A3/SB502, B2/SB502, and A5/SB503. The "soundings" shall be performed at these areas to define the final limits of the repairs shown.
534	Division 03 does not explicitly specify a maximum moisture vapor emission rate (MVER) or relative humidity (RH) limit for the new concrete, nor does it specify a topical moisture mitigation system. Most resinous flooring (Div 09) requires strict moisture limits (e.g., 5 lbs./1000sf or 75% RH). New concrete slabs often fail to meet the stringent moisture requirements of resinous flooring within the construction schedule constraints. Given the extensive use of Resinous Flooring (Section 09 67 23.13), does the Government require a topical liquid-applied moisture mitigation system to be included	Moisture mitigation must be included at new slabs for Bid Option No. 10, Resinous Flooring. Note that the Resinous Flooring is not included in the Base Bid. Also, see response to PPI 388.

	in the Base Bid for all new slabs receiving resinous flooring, or will moisture mitigation be treated as a unforeseen condition if the slab fails to reach required dryness levels within the scheduled curing period?	
535	The spec states: "Exposed areas must not exceed 2 percent of surface area in each linear foot of each bar." In a rehabilitation project, existing rebar often has significant corrosion or coating loss. This clause implies that if damage >2%, the bar might need replacement or extensive repair, but it doesn't explicitly state the remedy (splice new bar? sandblast and full recoat?). Question: Section 03 01 00 limits rebar coating damage/exposure to 2% per linear foot. If existing reinforcing encountered during demolition exhibits coating loss or corrosion exceeding this limit, is the Contractor required to replace the reinforcing steel, or will field application of a zinc-rich repair coating be acceptable?	Corrosion of the existing reinforcement, if found, must be cleaned to bare metal and coated with a zinc-rich repair coating.
536	Specification 04 01 00.91 22, Paragraph 3.4.k requires "complete cleaning of all exterior masonry surfaces." Please confirm if the Contractor is required to clean 100% of the building's exterior masonry facade as part of the Base Bid, or if cleaning is limited only to the specific areas receiving restoration/repainting work.	Provide cleaning only at the repairs indicated on drawings. Refer to Continuation Sheet.
537	Structural Note 8 states: "Do not make holes or penetrations through CMU bond beams or lintels." However, new MEP services are shown routed through existing and new masonry walls at elevations that will inevitably conflict with continuous bond beams (typically at 4'-0" or 8'-0" lifts). If penetrations through bond beams are strictly prohibited, the Contractor must route utilities over/under bond beams (creating offsets and chases) or install expensive steel headers/lintels at every conflict. Question: Structural Note 8 on Sheet S-001 prohibits penetrations through CMU bond beams. Given that continuous bond beams are required, please provide a standard detail or approved method for routing MEP services through masonry walls where elevation conflicts with bond beams occur, or confirm that coring bond beams is permissible if reinforcing steel is avoided/located.	The new cmu walls are limited to the construction of the elevator hoistway. The only penetrations through these cmu walls are for utilities that strictly serve the elevator. The Contractor must route these utilities in such a manner that they do not penetrate the cmu bond beams depicted on sheet SF201.
538	Drawings HM-101 to 106 requires the Contractor to "Abate and remove (brush/scrape) loose and flaking heavy metals containing paint from interior face of historic masonry walls." Please confirm whether painting of these surfaces are required after abatement.	Confirmed. Refer to Architectural sheets and finish schedule on AE640
539	The specification requires replacement brick to be "salvaged from existing structure... or new brick sourced to match in color, shape, size, texture, and appearance." The availability of	The government does not maintain a stockpile of salvage brick. Contractor

	matching historic brick (size and color) is often a critical path procurement delay. If no salvage brick is generated from demolition, custom fabrication may be required. Question: Paragraph 2.2.2.1 requires matching historic brick. Does the Government have a stockpile of salvage brick available for use, or must the Contractor assume full responsibility for sourcing and potentially custom-fabricating new brick to match the existing historic dimensions and color?	must assume responsibility for sourcing.
540	This specification requires that "expansion result... determined in accordance with ASTM C1293 must not exceed 0.04 percent at one year." It also allows ASTM C1567 (16-day test) for aggregate/cement combinations. ASTM C1293 takes one year to complete. If the local concrete plants do not have current C1293 data on file for their standard mixes, the Contractor cannot submit a compliant mix design without a 1-year delay or relying on the accelerated C1567 test which some Government reviewers reject in favor of the C1293 history. Question: Regarding Aggregate Reactivity (Paragraph 2.3.3), will the Government strictly require ASTM C1293 (1-year test) data, or will ASTM C1293 historical data from the aggregate supplier combined with current ASTM C1567 (16-day accelerated test) results be accepted for mix design approval to avoid schedule impacts?	The ASTM C1293 historic data along with the ASTM C1567 (accelerated test) is acceptable.
541	Section 05 50 13 requires all steel floor gratings to be galvanized. Please confirm if hot-dip galvanizing is the required finish for gratings located within the steam pit, or if stainless steel is required for this specific corrosive/high-heat environment?	Provide hot-dip galvanized steel gratings as indicated. Price per solicitation.
542	The scope involves attaching new structural steel to the existing building columns/girders that support an active bridge crane. Is the Contractor responsible for surveying and re-aligning the existing crane rails to meet CMAA/AISC tolerances, or is the new steel to be installed relative to the existing conditions regardless of current rail alignment?	There is no new structural steel being attached to the existing bridge crane rails.
543	Are there available Matterport surveys and/or drone footage available to bidders? This will help define on-site conditions for all since photography was not allowed at the site visit.	No.
544	Where new structural steel connects to existing steel columns/beams, is the Contractor required to apply fireproofing only to the new steel members, or must the existing supporting members also be abated of lead paint and fireproofed to meet the fire rating assembly requirements?	Refer to details on SP101 and provide surface preparation per specifications. Price per solicitation.

545	Section 01 91 19 requires Building Envelope Commissioning (BECx). Please confirm a quantitative "Whole Building Air Leakage Test" (ASTM E779) is required for this renovation project. If yes, what is the pass/fail leakage rate criterion (e.g., 0.40 cfm/sf) for this existing historic structure?	Where Building Envelope Commissioning (BECx) is required per the documents (Annex portion of building), the air leakage rate that must be met is as stated in 07 27 10 BUILDING AIR BARRIER SYSTEM. Refer to specification provided with amendment 009. Price per solicitation.
546	Do the new aluminum storm windows specified in Section 08 51 13 require blast-resistant glazing and anchorage to meet ATFP requirements for the facility, or are they solely for thermal performance?	Storm windows are existing to be reused. Provide repairs/installation as indicated in documents.
547	Paragraph 3.4.3.b requires full removal of existing coatings if "more than 20 percent peeling area" exists. Does this determination apply per wall/plane or per room?	The "20 percent peeling" text refers to a wall/plane.
548	For rooms with exposed overhead structure (e.g., Shops 110, 111), is the Contractor required to clean and paint the existing overhead steel, deck, and MEP utilities, or is the intent to leave the existing overhead structure unpainted/as-is?	The reflected ceiling plans and room finish schedule indicate which ceilings will be painted under base bid and which will be painted under an option. For instance on sheet AE702, room 110 is scheduled to be painted under base bid (Keynote 1,) and room 111 is schedule to be painted under Option 8 (keynote 5). Price per solicitation.
549	Section 09 01 90.60 covers preparation of wood strip flooring. Please specify the required finish system for the restored floors (e.g., type of stain, number of sealer/finish coats, sheen).	Paragraph 3.6 of spec section 09 01 90.60, refers to the Section 09 90 00 PAINTS AND COATINGS which has a paragraph (3.11 c) specific to wood floor finish. See Continuation Sheet.
550	Ref: Attachment S and Drawing Q-102/Q-601: Attachment S (FF&E Package - Option 1) includes industrial-style items such as MS series racks/cabinets and WT series workbenches. However, these items are missing from the FF&E schedules on drawings AE801–AE804. Instead, tags for these items are shown on the Option 2 Industrial Equipment plans (Q-series). Please clarify if these items are to be procured and installed under Option 1 (FF&E) or Option 2 (Industrial Equipment).	Items on sheets AE801-AE804 and pages 2-8 of the FF&E package are under Option 1. Items on sheets Q101-Q601 and on pages 16-25 of the FF&E package are under option 2.
551	Drawing Q-102 (Option 2) contains tags for items MS106A and MS107C and directs the contractor to the Q-601 schedule. However, these items are also specified in the Attachment S RFQ (Option 1). Please confirm which schedule governs these	See response to PPI 550.

	items and clarify which contract option is responsible for their cost and coordination.	
552	Note 1 on the architectural FF&E plans states that only items tagged and listed in the provided schedules are in the contract. Several items listed in the Attachment S RFQ are not listed in these schedules but appear on the Q-series drawings. Should the schedules on AE801–AE804 be updated to include all items in Attachment S, or are these industrial items intended to be part of the Q-601 Equipment Schedule? Confirm whether these items are to be included in Option 1 or 2?	Items indicated on Q-series equipment sheets are to be included in Option 2 - Industrial Equipment. Also see response to PPI 550.
553	Ref: Drawing AE401 and Spec 10 28 13: Item J in the Toilet Room Accessory Schedule is "Solid Plastic Locker Bench," but this item is not defined in the project specifications. Please provide a specification and basis-of-design for the locker benches.	See response to PPI 162.
554	Ref: Spec 10 28 13, Para 2.2.10 and Drawing AE401: The specifications require "Under Lavatory Guards," but these are missing from the Accessory Schedule. Please confirm if these guards are required for all wall-hung and countertop lavatories and update the schedule accordingly.	All exposed hot water supply lines and drainpipes under sinks are to be insulated. Lavatory exposed pipe insulation is called out in the Plumbing spec section 22 00 00. Price per solicitation.
555	The specifications provide requirements for both standard and industrial soap dispensers. The schedule only lists "Soap Dispenser (Item B)." Please clarify if the industrial dispensers are intended for shop areas (e.g., Room 111) and the standard dispensers for office/toilet areas.	See response to PPI 163.
556	Ref: Spec 10 28 13, Para 2.2.11 and Drawing AE001: The waste receptacle (Item M) is specified as semi-recessed. Please confirm that the 3-5/8" stud walls (Type 1C) have sufficient depth to accommodate these units without interfering with plumbing vents or electrical conduits.	A 3-5/8" metal stud wall with 5/8" gypsum board is sufficient depth to accommodate the waste receptacle.
557	Ref: Drawing AE401, Accessory Schedule: Item K is listed as "Not Used" in the schedule. Tag K is used on AE402 in details A3, A4 and D3. Please confirm what accessories Tag K represents.	Tag K indicates underlavatory pipe insulation. See response to PPI #554. Sheet AE401 is hereby amended to add "Underlavatory Pipe Insulation" to Accessory Schedule for Item K. See revised sheet AE401.
558	General Note 5 on AE622 references a window evaluation in Specification 080152/3.1. How will survey results alter the stated window repair conditions listed in base bid schedule on AE622?	See response to PPI 469.

559	Referring to A3/SP101, there are diagonally hatch zones on the plan view that according to the legend would contain steel beams/columns requiring intumescent fireproofing to be applied. These areas are existing structure. Please provide drawings or other information that clarifies what the steel types/sizes are to be fireproofed, as well as information on accessibility to the steel surfaces.	Refer to updated SP101 for additional information. Refer to structural framing plans for framing information. The existing structure to be fireproofed within stair will be exposed after building removals.
560	General Note 12 on AE622 references 20 sashes stored in the attic. Are these sashes from B60 mechanical intrusions and can they be used to infill the same locations in 60W1C, 60W1F, 60W1G, 601SA, and 60PN1A that currently are missing sashes?	See response to PPI 470.
561	Removal keynote 3 on AD203 references Window grills to be removed referencing historic restoration requirements. Are these grills to be retained and restored for future use?	No. Historic restoration requirements are for patching required at fasteners. See response to PPI 471. Price per solicitation.
562	Removal keynote 3 on AD203 references Window grills. Do the window sashes exist currently behind the metal grills?	Yes.
563	There seems to be a contradiction in the window repair schedule on AE622 where repairs listed require NPS 2 restoration but the remark "F" states just to clean and paint. (i.e. 60E1B, 602NA). Please clarify repair scope.	See response to PPI 473.
564	Are exterior window frames to be repaired or restored other than where metal grills have been attached?	Refer to schedules on AE622. Also see general notes on elevation drawings which require that repairs related to conduit/other penetrations must be patched. Price per solicitation.
565	- Per notes 9 & 10, on HM001 The government is providing a dumpster for hazardous materials, and drums of lead waste, with instructions to deliver to the PSNY Haz Waste Facility in Building 357 for disposal. Pertaining to the Removal and disposal of Hazardous materials who is responsible for the following: - o Chain of custody. - o Health permits - o Environmental engineering. - o Environmental Management Plan - How far way is Building 357 from the work site?	The Government will provide certain containers (e.g., dumpsters, drums) for the collection of waste, which will be turned over to the Portsmouth Naval Shipyard (PNSY) Hazardous Waste Storage Facility (HWSF) in Building 357. The Contractor is responsible for all hazardous material and waste management from the point of generation up to the point of formal acceptance by the HWSF. The following entities are responsible for specific items listed in the question: - Chain of Custody: The Contractor

		- Health Permits / Health & Safety: The Contractor - Environmental Engineering: The Contractor - Environmental Management Plan: The Contractor Building 357 is located 0.9 miles from Building 60.
566	Sewer Sequence Note 2 links the Building 62/62A sewer outage to the duration of the Building 60 water service reconstruction. Since this duration may extend beyond a single shift, is the Contractor required to provide a temporary sewer bypass system (pumping/piping) to maintain Building 62/62A sewer service during this period?	No, the contractor is not required to provide a temporary sewer bypass system for Buildings 62, 62A. The sewer for B60 is separate and will not impact sewer service at these other buildings.
567	Outage Schedule Note 8 states that listed durations are "for bidding purposes only" and subject to change by the Contracting Officer. Note 11 requires the Contractor to provide temporary services if work cannot be completed within the duration. If the Government reduces the allowable outage duration post-award (e.g., reducing an 8-hour window to 4 hours), will the costs for resulting temporary utility services (generators, bypass pumping) be considered a compensable change?	Propose in accordance with the solicitation.
568	For Fire Protection outages that render the building sprinkler system inoperable, is the Contractor responsible for providing and paying for a dedicated "Fire Watch" patrol during the downtime, or is this service provided by Government personnel (PNSY Fire Department)?	For Fire Protection outages that render the building sprinkler system inoperable, a dedicated "Fire Watch" is not required because the building will not be occupied during construction.
569	The Life Safety Plans identify various existing walls as rated Fire Barriers. Please confirm if the Base Bid scope includes the requirement to survey and repair all pre-existing deficiencies (e.g., unsealed penetrations, voids above ceilings, non-rated doors) in these existing assemblies to restore the rating, or if the scope is limited to firestopping new penetrations and repairing damage caused by construction activities?	Provide firestopping at existing locations (refer to AE441) as well as new penetrations and damage caused by construction.
570	Hazardous Materials General Note 5 requires management of heavy metals paint "separate from the substrate." Does this strictly mandate that all lead/heavy metal-containing paint must be stripped/removed from building components (e.g., drywall, wood, steel) prior to demolition, or is the Contractor permitted to dispose of the entire component (substrate plus coating) as	The intent of Hazardous Materials General Note 5 is not to require the stripping of all paint from every substrate prior to demolition. The phrase "separate from the substrate" applies specifically to waste streams generated during abatement activities where paint is intentionally removed

	appropriate hazardous/controlled waste without field separation?	from a surface that will remain (e.g., loose paint chips).
571	General Note 4 on HM001 indicates the presence of carbon black and heavy metal debris from industrial processes. Does the Base Bid (CLIN 0001) include a requirement to decontaminate/clean all existing building shell surfaces (e.g., overhead trusses, walls, existing utilities to remain) of this heavy metal dust prior to starting architectural renovations, or is this scope limited to the specific equipment identified in CLIN 002?	No. CLIN 0001 (Base Bid): The Base Bid does not include a separate, building-wide cleaning effort. However, all renovation work performed under the Base Bid <u>that will impact heavy metals containing paint or dust</u> shall be conducted in accordance with UFGS 02 83 00.00 22. The Contractor is responsible for managing any dust and debris generated during their architectural renovation activities (e.g., cutting, demolition, surface preparation). This includes performing all necessary cleaning and engineering controls required to protect workers and the environment in the immediate vicinity of their work.
572	Ref: Spec 01 11 00.00 22 and Dwg AE622: The Summary of Work identifies Option 5 as "Additional Window Restorations," while drawing AE622 refers to this scope as "Bid Option 6." Please clarify the correct Option number for the window restorations to ensure consistency in the price proposal.	See response to PPI 193
573	Are the lower wooden panels in windows 8,9,10,11 to be scraped and painted in place in base bid and removed in the entirety off site for restoration in Option 5?	See response to PPI 475
574	Do BL1, BL2 and BL3 that are being relocated require any repairs or restoration in Base Bid or Option 5?	Borrowed lites are to be reinstalled under base bid. Scope includes preparation of windows and painting. Refer to specifications, drawings, and details. Price per solicitation.
575	Ref: Dwg AE105, Dwg AE223, and Spec 08 51 13/08 51 70: Drawing AE105 mentions salvaged "aluminum" storm windows, while Drawing AE223 references "steel" windows. Please clarify the material of the existing interior storm windows and confirm which technical specification (08 51 13 or 08 51 70) governs their restoration.	08 51 13 is for the existing storm windows and 08 51 70 is for the existing steel windows at the annex.
576	Ref: Dwg AE622 Remark J and Dwg AE621 Detail C3: Remark J calls for opaque window film, but Detail C3/AE621 shows 1" insulated aluminum wall panels for mechanical penetrations. Please clarify if the film is required for windows that are not	Window film is only required at glazing panels and is not required at aluminum panels

	receiving mechanical penetrations, or if it is an additional requirement for the aluminum panels.	
577	Ref: Dwg AE622 Note 5 and Spec 08 01 52: Note 5 suggests using salvaged sashes and attic stock for repairs. If this stock is insufficient to complete all "Class III" restorations, is the contractor required to fabricate new wood sashes to match the original profiles?	Yes
578	Is there a list and corresponding inventory for "Attic Stock" noted to be utilized in the project?	Attic stock is not required. Note extra/spare parts are required where indicated. Specification sections 09 51 00, 09 68 00, and 09 90 00 are hereby amended, see continuation sheet.
579	Ref: Dwg AE626 Detail A4: Detail A4 shows a "Window Railing Detail" to be painted black. There appears to be no technical specification for these railings in the Division 05 or 08 specifications. Please provide a specification and basis-of-design for these window guardrails.	Railings are delegated design - please refer to 05 52 00
580	Ref: Spec 09 65 00, Para 2.1 and Dwg AE640: The specification requires SVT tiles to be 18" x 36", while the Room Finish Schedule lists them as 18" x 24". Please clarify the required tile size.	The Solid vinyl tile size is 18"x36". See Continuation Sheet.
581	Ref: Dwg AE105, Keynote 4 and Dwg AE640, Note 6: Drawing AE105 indicates wood flooring is to be prepped for carpet tile, while the Finish Schedule and Spec 09 01 90.60 call for the wood floor to be refinished. Please confirm if the wood floors are to receive a natural refinished surface or if they are to be used as a substrate for carpet tile.	Note 6, indicating the existing wood strip floor be refinished, is not in the notes column for rooms 208 and 210. The existing wood strip flooring in these two spaces is to be "prepped" i.e., old adhesive is removed, clean, dry, etc., but does not need to be refinished as carpet tile is being installed on top. The wood strip flooring is to remain as it is historic.
582	Ref: Dwg AE640, Note 9 and Spec 01 11 00.00 22: Is all resinous flooring (RF 1) scheduled on Drawing AE640 intended to be part of Bid Option 10, or is there a base bid quantity of resinous flooring? Please clarify.	All Resinous flooring is scheduled as Option 10. Base bid finishes are indicated in the schedule.
583	Ref: Dwg SB101, Note 15 and Spec 09 65 00, Para 3.2: The structural drawings specify F-number tolerances (Ff 35 / FL 25), while the resilient flooring specification uses a 3/16" in 10' straightedge requirement. Please clarify which tolerance standard governs for floor areas receiving SVT and CPTT.	New concrete slab finish tolerance is governed by the floor flatness and floor levelness values indicated on sheet S-001. Existing concrete slab finish tolerance is governed by Specification Section 09 65 00. The SVT is applied on the new concrete

		slab. The carpet tile is going over existing wood strip flooring, so no slab tolerance requirement in that instance.
584	Ref: Dwg AE640 and AE402: Please provide additional floor transition details for intersections between Resinous Flooring (RF 1) and Concrete (CONC), and between Carpet Tile (CPTT) and SVT.	Typically the slab is sawcut and the material is "chased" into the concrete, requiring no transition strip. See revised Sheet AE640 for detail. There is no transition between SVT and CPTT in the project.
585	Ref: Spec 09 65 00/09 68 00 and 01 45 00.00 22: The flooring specifications require moisture and alkalinity testing of concrete slabs. Please confirm if these tests are to be performed by the flooring subcontractor, the GC or by a Government-retained third-party testing agency.	Testing of the slab is part of the contract documents and who that is assigned to is at the discretion of the Contractor. Also see response to PPI 388.
586	Ref: Dwg AE105 Note 9, AE640 Note 4, and Spec 02 41 00: The drawings provide a 200 SF allowance for patching the historic beadboard ceiling. Please clarify if this 200 SF is a total project allowance or intended to be per floor. Additionally, please provide a specification for new beadboard material should the salvaged stock be insufficient or unsuitable for reuse.	The 200 SF is a total project allowance for additional salvage and reinstallation/repair. Note there is an additional 150 SF project allowance for removal and replacement of damaged beadboard. Refer to revised AE704 with Amendment 008.
587	Ref: Spec 06 41 16 00.10 and Dwg AE540: The casework specification calls for MDF carcasses, while the casework details show plywood substrates and brackets. Please clarify if Plywood is an acceptable or required substrate for all architectural casework in lieu of MDF, especially in areas with potential moisture exposure.	Cabinet details (sheet AE540) and specifications call for MDF substrate for cabinetry. Price per solicitation.
588	Ref: Spec 06 20 00 and Spec 08 14 00: Finish carpentry is specified as NAAWS "Custom" grade, while wood doors are specified as "Premium" grade. Please confirm if "Custom" grade is acceptable for all interior wood trim and millwork to ensure bidding consistency.	Items should be bid on, and constructed as indicated in their respective specification. Price per solicitation.
589	Ref: Spec 01 11 00.00 22 and Dwg AE622: The Summary of Work identifies "Additional Window Restorations" as Option 5, while Drawing AE622 refers to them as Option 6. Please clarify the correct Bid Option number for this scope of work.	See response to PPI 193
590	Ref: Spec 06 20 00, Para 2.2 and Spec 08 01 52, Para 3.2.3: These sections provide conflicting moisture content requirements (6-8% vs. 8-12%) for interior wood. Please clarify the governing moisture content for historic wood window and door restoration.	See Section 08 01 52 as the spec governing wood window and door repair (8-12%).

591	Ref: Dwg AE105/AE107 and Spec 02 41 00: Specification 02 41 00 mentions beadboard only on the "second floor," but Drawing AE107 shows existing wood ceilings in the attic. Please confirm if the attic wood ceilings are included in the protection and restoration scope.	Drawings AE105 and AE107 are floor plans and do not indicate ceiling work. Beadboard ceiling work is confined to the second floor. Refer to drawing AE704 for locations and quantities.
592	Ref: Drawing AE601 (Door Schedule): Door 117B is listed in the schedule without an assigned Hardware Set. Please provide the correct HW Set for this opening.	Door 117B is existing and will not require a new hardware set. Refer to updated Door Schedule on AE601
593	Ref: Drawing AE601 (Door Schedule): Door M201 is listed as an existing door to remain but has no hardware set assigned. Please clarify if existing hardware is to be reused "as-is" or if a specific hardware set for restoration/repair is required.	Hardware for M201 is to be re-used as-is.
594	Ref: Spec 08 71 00 and Drawing EY501: There is a coordination conflict regarding the electric strikes. Hardware sets list them in Section 08 71 00, while security notes on EY501 state they are "provided with door frame." Please confirm that Division 08 is responsible for procurement and physical installation of electric strikes and power transfer hinges.	Confirmed. Electric strikes and hinges are to be provided as part of door hardware requirements.
595	Ref: Drawing AE102 and AE601: Door 116A is an existing historic sliding door. While the schedule mentions painting the man door, no hardware set is assigned for the sliding door tracks or operability. Is the subcontractor required to repair or replace sliding door hardware components too? Please clarify.	No, sliding door hardware to remain as is. Man door hardware must be adjusted, refer to continuation sheet.
596	Ref: Drawing AE601 and AE421: Door 114A appears on the enlarged plans but is missing from the schedule. Please confirm the required door type, frame, and hardware set (maybe 7 vs 7a???) for this opening.	114A is in schedule and 7a is correct hardware set.
597	Ref: Spec 08 71 00, Para 2.3.6: The specification requires the contractor to provide uncombined cores to the Shipyard Locksmith. Please confirm that the Government will perform the final pinning/keying of the cores and the contractor's responsibility is limited to the procurement and delivery of the blank cores and key blanks.	Confirmed.
598	Ref: Hardware Set No. 12 (Doors 208B, 209A): This set includes a "Lever" and a "Lever/Dummy". Please clarify if these office doors require a lockset (Office Function) or if they are intended to be non-locking passage doors, as no lock function is specified in the hardware set list.	Doors should unlatch from inside space via lever and should be non-operable from outside of the space.
599	Class I restoration notes on Drawing AE622 state that window frames shall remain in place while sashes and hardware are removed for restoration. However, Specification 02 41 00 (Para	02 41 00 is related to salvaged items. Please also refer to 08 01 52 for restoration related window work.

	3.1.6) requires windows and doors to be salvaged as whole units. Please clarify if the Government requires the sashes to be restored in an on-site or off-site shop environment, or if restoration while the sashes are installed is acceptable.	Restoration in place or at an an off site shop will be considered acceptable Contractor means and methods provided repairs are done in accordance with project requirements.
600	Per Specifications 02 82 00.00 22 (Para 3.2.9.1) and 01 50 00.00 22 (Para 3.2.2). The project requires a minimum of four air changes per hour and continuous negative pressure for hazardous material control areas. To achieve this, high-capacity electric dust collectors will be required. Does the existing electrical infrastructure at Building 60 have sufficient 480V, 3-Phase, 200Amp capacity available for contractor use, or must the contractor provide temporary generators to power these systems?	Refer to Keynote 6, Sheet ES101 and Sheet G-008, Electrical for power available for use during construction. The contractor must evaluate the various electrical needs due to their construction trailer and existing loads requiring temporary power to determine if there is spare capacity for the dust collectors.
601	Specification 07 81 00 requires a two-component epoxy-based intumescent coating. Given the flammability of these products and the resulting restrictions on Hot Work Permits (welding/grinding) within a 50' radius at PNSY, will the Government consider a waterborne intumescent alternative? This would allow other trades to continue welding and grinding operations outside of the localized fireproofing containment area.	Bid per solicitation. Substitution requests may be submitted during construction per specifications.
602	Refer to Specification 01 57 19.00 22 (Para 3.14.a) and Drawing HM101. For the removal of loose and flaking heavy-metal paint on the exterior historic masonry and wood windows, will the Government allow the use of encased basket manlifts with localized HEPA-vented containment, or is a full-building scaffolding system with enclosure required for the duration of the envelope restoration?	The Government does not specify the Contractor's means and methods for access or containment for the exterior work. The Contractor is solely responsible for designing and implementing a system that fully complies with the performance requirements of UFGS 02 83 00.00 22 and all applicable local, State of Maine, and Federal regulations.
603	Refer to Specification 04 01 00.91 22 (Para 1.1 and 3.4.4). The specifications require the "gentlest means" for masonry restoration and prohibit abrasive blasting. Considering the requirement to remove white paint on historic brick (Drawing HM101), will the Government approve the use of chemical paint strippers followed by neutralizing after-washes and pH testing as the primary removal method?	Chemical paint strippers appropriate for the substrate and used in accordance with the manufacturer's instructions would be appropriate for this use. Products would require GOV approval, methods must be documented in the work plan per 1.6.1, and mock-ups would be required per 1.6.8 of UFGS 04 01 00.91 22. The removal methods must also be detailed in the Lead, Cadmium, and Chromium

		Compliance Work Plan and work performed in accordance with UFGS 02 83 00.00 22.
604	Drawing HM101 identifies both asbestos-containing pipe insulation and heavy-metal paint debris within the same floor drains and trenches. Since these materials fall under different technical specifications (02 82 00 vs 02 83 00), must the remediation be performed as a single Class I asbestos operation, or does the Government require separate management and clearance procedures for each hazardous component?	In locations where different hazardous materials are commingled, the contractor must comply with the requirements for both contaminants. In instances where requirements overlap, the more stringent requirement shall govern the activity. The contractor shall comply with all applicable clearance requirements.
605	Referencing Drawings AD120, AD121, and SP101. Please clarify the required sequencing for the attic truss cleaning and fireproofing. Must the exterior roof replacement (Drawings AD120/AD121) be substantially complete and should the building be "in the dry" before the internal trusses are scraped and painted to avoid damage to the new finish, or is concurrent work expected?	The fireproofing is at the underside of the second floor (not the attic framing) and new structure at the fire pump room (not at roof framing). Install and protect fireproofing per specifications.
606	Refer to Drawing AE601, Door 117B: Door 117B is missing material assignments for the slab and frame, as well as an assigned Hardware Set. Please provide the required materials and hardware for this fire-rated opening.	See revised Door Schedule on sheet AE601. If hardware set is not indicated, existing is to be reused.
607	Refer to Drawing AE601, Door 115 and Remark A: Door 115 is an existing wood door to be refinished and reinstalled per Remark A. However, the schedule calls for a new Hollow Metal (HM) frame. Please confirm if a new HM frame is required for this opening or if the existing frame is to be reused and refinished.	Existing frame is to be reused. See revised Door Schedule on sheet AE601.
608	Refer to Drawing AE601, Doors 209A/B: The schedule lists the frame material as "WD PNT" but references the "C1" series details on AE602, which appear to be hollow metal details. Please clarify if these frames are intended to be wood or hollow metal.	Frames shall be hollow metal. See revised Door Schedule on sheet AE601.
609	Refer to Spec 08 11 13, Para 2.6 and Dwg AE601: The specification requires a minimum Level 4 (14 gauge) for exterior frames. Please confirm that all exterior HM frames (e.g., 001A, 002A, 003A, 004A) must meet this requirement, as the door schedule is lacking the frame gauge.	Requirement is for new exterior door frames (doors 118, M116, and M107B)
610	Refer to Drawing AE601 and AE421: Doors 114A and 114B are different widths (4'-0" and 3'-0"). Please confirm if these are intended to be an unequal pair in a single frame and provide a frame detail for this configuration.	These are two separate doors. Refer to D1/AE421.

611	Refer to Spec 07 81 00 and Dwg SP101: Following the Government response to PPI #64, which confirmed a 1-HR fireproofing rating is required for the fire pump room support structure, please clarify if the new structural steel in this area should receive the standard Division 05 shop primer or if it must remain unprimed to ensure proper adhesion of the spray-applied fireproofing.	Shop primer is not required to be applied to structural steel that is to receive the spray-applied fireproofing material.
612	Refer to Dwg HM603, Summary of ACM: There is a discrepancy between the overall amount of identified ACM textured ceiling surfacing and the 400 SF quantity listed for removal. Please confirm that the contractor is only responsible for the abatement of the 400 SF directly impacted by the work.	Confirmed. Contractor must account for 400 SF in their bid. Note that the 400 SF is spread out across multiple locations as required to support removals and new construction work.
613	Refer to Dwg AE443 Detail C1 and Dwg AE704 Note 11: Please clarify if the attic access points require a new pre-manufactured metal hatch or a painted plywood cover as described in the RCP notes. Which applies?	The new attic access point (adjacent to elevator shaft) requires the new pre-manufactured hatch. The painted plywood is a separate existing panel in the ceiling.
614	Refer to Dwg AE640 Notes 7 & 8 and AE704: For Option 8, some areas of the beadboard ceiling are to be refinished (clear coat) while others are to be painted. Please provide a key plan delineating the specific boundaries for refinishing versus painting to ensure accurate pricing.	Refer to sheet AE704 for beadboard ceiling work details. From column line K to the north end of the building, the existing beadboard ceiling is unfinished and the intent is to clean (and repair if indicated) and not to paint (Keynote 5).
615	Refer to Spec 09 29 00, Para 3.4: The specification requires a Level 4 finish for all gypsum board ceilings. Please confirm if a Level 1 finish is acceptable for gypsum board used as a fire-rated "shaft panel" or in plenum areas that are not visible to the public.	A Level 1 finish is acceptable for gypsum board used as a fire-rated shaft panel.
616	Refer to Dwg AE401/AE402 and Spec 10 26 00: Interior elevations require "metal edge protection" at outside corners of wall tile. There is no technical specification for corner guards in Division 10. Please provide a specification and basis-of-design (e.g., stainless steel, aluminum, surface-mounted vs. flush) for these guards.	Metal trim pieces are referred to in paragraph 3.6.2 in spec section 09 30 10. For basis of design, see Schluter's Jolly product in brushed stainless steel.
617	Refer to Dwg AE640 Note 3 and AE401: The finish schedule requires FRP wainscot to 4'-0" AFF. Please confirm if this 4'-0" height is mandatory for all rooms where FRP is scheduled (e.g., Room 107) and clarify if any specialized edge trim (J-bead or cap) is required at the transition to the painted surface above.	Install FRP to a height of 4'-0" above finished floor where indicated. No special cap required before transitioning to paint.
618	Refer to Dwg AE402 Keynote 3 and Spec 09 29 00: Keynote 3/AE402 requires cementitious backer board under porcelain floor tile. Please confirm if cementitious backer board or water-resistant glass-mat gypsum board is required as a substrate for	Cementitious backer board or water-resistant glass-mat gypsum board are

	Porcelain Wall Tile (PWT) in lieu of standard Type X gypsum board.	not required as a substrate for porcelain wall tile.
619	Refer to Dwg AE640 and Spec 09 30 10: For rooms where "PWT" is listed as the base material, please clarify if the base is to be a standard flat tile or a sanitary coved base tile.	The porcelain tile base will be the same as the wall tile.
620	Refer to Spec 10 26 00, Para 2.1.1.2: The specification requires wall protection material to be fire-rated and labeled. Please clarify if a Class A fire rating is required for all FRP panels installed in the facility, particularly in custodial and storage areas.	Class A is not required for FRP. Class C rating is sufficient.
621	Refer to Dwg AE101, Note 12: General Note 12 requires solid blocking behind surface-applied fixtures, including wall protection and bases. Please confirm if continuous horizontal blocking is required at the top edge of the 4'-0" FRP wainscot for secure attachment of the edge trim.	Continuous blocking is not required for the installation of FRP. FRP can be adhered to the gypsum board, not fastened.
622	Refer to Dwg AE001 and Spec 09 30 10: Wall types 1C and 1D show standard 5/8" Type X Gypsum Board as the substrate for porcelain wall tile. Please clarify if Cementitious Backer Units (CBU) or Glass Mat Water-Resistant Backing Board is required behind wall tile in wet areas (Toilet Rooms 105/106 and Custodial 107) to prevent moisture degradation of the assembly.	Cementitious Backer Units or Glass Mat Water-Resistant Backing Board are not required for porcelain wall tile.
623	Refer to Dwg AE001 and Spec 05 40 00 / 09 22 00: Several high-bay walls utilize 8" metal studs. Please clarify if these partitions are to be designed and installed as Load-Bearing Cold-Formed Metal Framing per Section 05 40 00, or as Non-Load-Bearing Wall Framing per Section 09 22 00.	The structural cold-formed steel framed walls are indicated on sheet SF102 (specification section 05 40 00 metal framing). Please refer to keynote 13 on sheet SF102 for the 8-inch metal stud walls referenced in this PPI. Also, "structural" walls are indicated as such on sheet AE001 by the term "STRUCTURAL MTL STUDS".
624	Refer to SB101 Structural Note 4 and Spec 09 22 00: Structural Note 4 requires horizontal wall blocking every 4'-0" vertically. Please confirm if this requirement applies to all interior partitions, including non-load-bearing 3-5/8" metal stud walls, or only to structural/load-bearing walls.	The structural cold-formed metal framing is defined by Specification Section 05 40 00 and NOT 09 22 00. The "blocking" noted on sheet S-001, Cold-Formed Steel note #4 only applies to the 05 40 00 framing as depicted on sheets SF101, SF102, SF501, SF502, and SF504.
625	Refer to AE101 General Note 12 and Spec 09 22 00 Para 2.1.2.2: Note 12 requires solid blocking for wall-hung items, while the specification requires a minimum stud thickness of 0.0329 inches (20-gauge). Please clarify if providing solid	Providing solid blocking between standard 25-gauge studs is an acceptable alternative to using 20-gauge studs for the full length of the

	blocking between standard 25-gauge studs is an acceptable alternative to using 20-gauge studs for the full length of the wall.	wall. Note: There is no General Note 12 on AE101.
626	Refer to Spec 09 29 00 Para 3.4 and Dwg AE720: For fire-rated shaft wall assemblies (Type 1G/1H) that extend through plenum areas, please confirm if the "shaft side" (interior) requires any level of finishing, or if a Level 1 finish is only required on the "occupied side" above the ceiling.	The interior of the fire rated shaft requires a level 1 finish.
627	Note 2 on MD101 state to "assume 1200 feet of 4" metal steam and heat water type pipe to be removed from the trenches". There are multiple systems in the trenches that are partially shown, tanging from 3/4" through 4". Please confirm if for bidding purposes the intent is to ignore all sizing and include the demolition of just the 1200 feet of 4" pipe.	Confirmed - assume 4" for bidding purposes
628	The first sentence states, "Review and certify that all submittals pertaining to fire and life safety systems are complete and accurate prior to submission to the Government for approval." While the construction surveillance responsibilities from paragraph 1.6.7.2.e typically include passive fire protection systems, none of the sections covering passive fire protection elements (e.g., 07 81 00, 07 84 00.00 22, etc.) detail the requirement for submittal reviews by the QFPE; only 21 13 13, 21 30 00, and 28 31 76 mention the QFPE requirement to review submittals. Is the intent for the QFPE to only perform submittal reviews for fire protection systems when specifically mentioned in the system specification, or is the QFPE required to review certain passive fire protection system submittals? If the QFPE is required to review passive fire protection submittals, can those specific submittals be identified?	The QFPE normally reviews fire stopping submittals, but not fire proofing submittals.
629	Throughout the Fire Protection QC Specialist subsection (1.6.7) of 01 45 00.00 22, the abbreviation QFPE is utilized throughout rather than the typical FPQC. In this paragraph, a statement has been added to the standard language of this section: "The QFPE is responsible for the delegated design of the sprinkler system, including fire pumps, and the fire alarm and mass notification system." Please confirm the intention that the QFPE in this statement is interchangeable with the FPQC, as seems to be implied throughout the sprinkler, fire pump, and fire alarm system specifications.	FPQC and QFPE are interchangeable.
630	This paragraph states that a schedule of required QFPE visual inspetions and observations prepared by the Fire Protection DOR is included at the end of the UFGS section. The blank template is provided at the end of the section; the designer notes, which are supposed to be deleted after editing the	See response to PPI 109

	schedule based on the project scope, are still visible, and no tasks have been checked as required to be performed.	
631	In the first sentence, sway bracing for earthquake protection is still in brackets. Is seismic bracing required for this project?	Seismic bracing is not required.
632	Please provide a copy of the Fire Protection Design Analysis.	This document is not available for distribution to bidders.
633	Openings 209A and 209B are scheduled as wood frames, however the head/jamb/sill elevations C1A-C1B-C1C/AE602 are for a Hollow Metal Frame detail. Please confirm if these are mislabeled in the door schedule as WD and these two openings should be HM.	See response to PPI 608
634	Openings 108B, 116A, 117A, 117B, W13, 212, 213 have either existing door, frame, or both and are blank for hardware sets on the Door Schedule on Drawing AE601. Please confirm these openings do not receive updated hardware sets.	Refer to updated door schedule. If hardware set is not indicated then the existing hardware is to be reused.
635	Please advise if Type P1 doors are intended to be stile and rail doors or flush doors as Specification 081400 Part 2.1 lists both. Also if these are intended to match existing doors please provide the manufacturer or pictures of the existing doors that we are to match.	P1 doors should be stile and rail. Doors are not designed to match existing.
636	Please confirm the building commissioning agent (BECx) will be provided by the Government and will not need to be included in the contractor's proposal following specification section 01 91 19 paragraph 1.3.7.	Refer to response to PPI 499
637	UFC 3-110-03 paragraph D-2.2 (General Contractor's Warranties [one to five years]) states the following: "Recently some government roof specifications call for a General Contractor's Watertight Warranty to add another method of ensuring a quality roof installation. Unless stated otherwise in the Scope of Work in the RFP, all permanent new construction and replacement roofs require a Five-Year General Contractor Bonded Watertightness Warranty. The scope of work in the RFP may waive the Bonding requirement, but if not specified, the Bonded five-year watertightness warranty is required. The required wording of the warranty will be provided in the applicable UFGS." Specification section 07 31 13 paragraph 1.5.1 requires a five-year contractor's warranty. Additionally, specification section 07 52 00 paragraph 1.8.2 requires a two-year installer's warranty. Please confirm if these two warranties are to be provided/held by the roofing installer and are to replace the need for an additional five-year general contractor bonded watertightness warranty to be provided.	The two warranties noted in the question do not replace the need for the additional five-year general contractor bonded watertightness warranty. Provide warranties per specifications. Note that 07 52 00 paragraph 1.8 indicated that warranty must cover water-tightness.

638	Note 16 indicates a sink hole, with repairs indicated on a detail sheet C-502. Verify if this is to be included in this project and the means to quantify the scope of work.	There are two sink holes identified on sheet CX01 (one at northwest corner of Building 60 and another at east side of Building 65). For bidding purposes, the size of the sinkholes are identified with keynote 16. The scope of the repair is described in detail C1/C-502 note 2.
639	Please identify the wage rate determination documentation for this project.	Propose in accordance with the Solicitation and Amendment 0007. Wage determinations under this IDIQ will be included at the task order level.
640	Please identify any labor agreements that may be in place or affect this project, in lieu of Davis Bacon wages / wage rate determinations.	Propose in accordance with the Solicitation and Amendment 0007.
641	Is there any scope of work relating to the existing bridge crane? Repair or otherwise.	Contractor must coordinate the relocation of bridge cranes (by government) and relocate crane stops. Refer to architectural and structural drawings. Contractor must also manage disturbances to paint on cranes, refer to HM sheets. Price per solicitation.
642	Please distinguish the Buy American (BAA) or Build America Buy America (BABA) requirements for this project.	Propose in accordance with the Solicitation.
643	Please confirm if B60 will be unoccupied and we will have sole access for the duration of this scope of work. Amendment 4 made changes to specification section 01 14 00.00 22 under 1.5.3 with reference to buildings B59, B13 and B86 as occupied. It is not clear if B60 will be occupied.	B60 will be unoccupied.
644	If possible, can the parking lot on the west side of the building shown in Attachment A below could be used for storage.	Refer to G-006 Site Constraints and Requirements Plan for available storage areas. Requested information is within the documents. Price per solicitation.
645	Please confirm whether there is a domestic steel requirement for micropiles.	See response to PPI 455.
646	There is a gantry crane inside the building running above the proposed micropiles. Will this crane be made available to move materials within the building?	See response to PPI 456.
647	Prior to mobilization for the drilled micropiles, will the entire slab within the working area be removed or will there only be localized removals at proposed footing locations?	See response to PPI 457.
648	A minimum of 15' of headroom is required for low headroom micropiles. Please confirm this will be the case throughout the working area.	See response to PPI 458.

649	Please confirm that a water supply at hydrant pressure is available within 100' of the working area.	See response to PPI 459.
650	Will photos be permitted during construction for record keeping purposes?	See response to PPI 460.
651	Will percussion drilling using a pneumatic hammer be permitted?	See response to PPI 461.
652	Is there a plan for ventilation of equipment exhaust?	See response to PPI 462.
653	Will permits be provided by PNSY or NAVFAC?	The Project did not trigger Federal or State permit requirements. No permits to be provided.
654	Under 01 11 00.00 22, commissioning is listed as "contractor personnel". Under section 01 91 00.15 22, the first sentence states "The Government has hired an independent Commissioning Firm". Please confirm who owns commissioning	See responses to PPI 333 and 499
655	Under section 01 11 00.00 22 Building Enclosure Commissioning is also listed as "contractor personnel" but section 01 91 19 does not state if its by the contractor or not. Please confirm who owns Building Enclosure commissioning	See responses to PPI 333 and 499
656	Please confirm if there is a minimum requirement of work to be self-performed by awarded GC.	Propose in accordance with the Solicitation.
657	Due to magnitude, critical scope and vast complexity of the project we requests that the due date for proposals be extended until 4/3/26 to give potential bidders a reasonable opportunity to respond to the RFP.	Refer to Amendment 0006.
658	Due to magnitude, critical scope and vast complexity of the project we requests that the due date for PPIs be extended until 3/20/26 to give potential bidders a reasonable opportunity to respond to the RFP.	Propose in accordance with the Solicitation.
659	Ref. 07 84 00.00 22 Par 3.3.3 Firestopping Acceptance does not provide sufficient detail for this acceptance inspection. Please provide additional details as to the requirements and timeline for this acceptance inspection so this time can be included within the project schedule.	Coordinate inspection requirements with those described in the 01 45 00.00 22 Quality Control Attachment for "Schedule of Fire Protection System Inspections by FPQC Specialist." Timing for inspections is the responsibility of the KTR. Per specification, final government approval requires a 14 day notice before review and acceptance.
660	Ref. 21 13 13 Par 1.4.1 "Preconstruction Submittals within 36 days of contract award but not less than 14 days prior to commencing work onsite.." It is not reasonable for all fire protection pre-construction submittals to be submitted within 36 days of contract award when mobilization may not be granted by NAVFAC until 75 days from award with construction commencing after this date. Please confirm required timeline for fire protection pre-construction submittals.	Section 21 13 13 para 1.4.1 is hereby amended to read: "Within 45 days of contract award but no less than 14 days prior to commencing work on site, the prime Contractor must submit SD-01 submittals for review and approval. Note that SD-02, SD-03, and SD-05 submittals received

		prior to the review and approval of the SD-01 (qualifications) submittals will be returned Disapproved Without Review."
661	Ref. 01 19 19 Par 1.3.7 "BECx - Technical service provided on Behalf of the Government to provide a quality focused approach for enhancing the performance of the building envelope by validating the design phase.." SD-01 lists the BECx Specialist as a submittal requirement. Par 1.12.2 references the qualification requirements for the Pressure Test Agency and Thermographer. However, The BECx Specialist qualifications are not included. Based on Par 1.3.7 it is the KTR's assumption that the BECx Specialist is a government entity. Please confirm requirements for BECx Specialist as it relates to the KTR.	Note that Question appears to refer to 01 91 19 Par 1.3.7 and not 01 19 19. See response to PPI's 333 and 499.
662	Ref. 01 44 00.00 22 Par. 1.1 "Perform archaeological monitoring for all forms of soil disturbing activities and excavations within archaeologically sensitive portions of the project area as identified in project drawings" Par 1.6 states that Archaeological Monitoring Plan must be approved prior to the start of construction. Please confirm the Archaeological Monitoring Plan approval is only required to start excavations within the Archaeological Sensitive Areas detailed on drawing G-005.	Confirmed.
663	Ref. 14 24 23 par 1.2.3.3 Auxiliary Power System. Please confirm if auxiliary power is referring to generator backup or battery lowering.	Battery lowering.
664	Ref. 14 24 23 par 2.1.1.1.e Car Door Opening Width. Please confirm car door width should be 64 in. min. not 48" min. as longer door travel creates longer response time.	Door opening width is 64" min
665	Ref 14 24 23 par 2.6.6 Elevator Car Position and Direction Indicators.. Please if this requirement applies to main egress only or all floors.	This requirement applies to all floors.
666	Ref. 14 24 23 par 2.1 Elevator Description "Provide elevator system that complies with ASME A17.1/CSA B44". ASME A17.1 (2019) is referenced at the beginning of the specification. ASME A17.1 (2019) requires that elevators provide two-way voice, video, and text communication between elevator car and authorized personnel. Please confirm if this is a requirement for this project. If it is please provide details.	Yes, the elevator system must comply with ASME A17.1/CSA B44. Sheet ET102 is hereby amended to add keynote #18 "PROVIDE VIEWING PANEL IN THE ELEVATOR MACHINE ROOM. COORDINATE EXACT LOCATION WITH THE ELEVATOR INSTALLER AND CONTRACTING OFFICER. REFER TO THE ELEVATOR SPECIFICATION FOR ADDITIONAL INFORMATION." Delete and replace Specification Section 14 24 23 Hydraulic Passenger Elevators with paragraphs 2.5.2.1.1 and 2.6.2 revised to include "car surveillance and text base system". This "...will function without an internet or wireless connection and the viewing panel in the elevator machine room."

667	Ref. 12 00 01.00 20 par 1.3 "The project may also include Speciality CEQ Package.. If a speciality CEQ package is required the same requirements for the FF&E package apply.." Where in the contract CEQ defined?	Items on sheets Q101-Q601 and on pages 16-25 of the FF&E package are considered to be Collateral Equipment.
668	Ref. 12 00 01.00 20 par 1.3.5 It is recommended that the KTR order the products once the option is awarded. Please confirm it is acceptable to order the products prior to design approval.	Design approval must be obtained prior to award of the FF&E package. Refer to Division 12, Paragraph 3.1.2.10: Pre-Final FF&E Package "Over the Shoulder" Submittal Review Meeting and Division 12, Paragraph 3.2.3: Validation of Pricing. The government's contractual obligation commences upon award to the GC of the CLIN option for FF&E. If FF&E is ordered prior to this CLIN option being awarded, the GC accepts 100% of the risk that the CLIN option may not be awarded. After award of the FF&E CLIN option, the GC must provide the FF&E package as approved and endorsed by NAVFAC.
669	Ref. 28 31 76 par 1.8.1.1 "Preconstruction Submittals within 36 days of contract award but not less than 14 days prior to commencing work onsite.." It is not reasonable for all fire alarm pre-construction submittals to be submitted within 36 days of contract award when mobilization may not be granted by NAVFAC until 75 days from award with construction commencing after this date. Please confirm required timeline for fire alarm pre-construction submittals.	Section 28 31 76 first two sentences of para 1.8.1.1 are hereby amended to read: "Within 45 days of contract award but no less than 14 days prior to commencing work on site, the prime Contractor must submit SD-01 submittals for review and approval. Note that SD-02, SD-03, and SD-05 submittals received prior to the review and approval of the SD-01 (qualifications of the fire alarm subcontractor and QFPE) submittals will be returned Disapproved Without Review."
670	Ref. 28 31 76 par 3.9.2 Audibility Tests - Please confirm if any ambient noise or visibility obstructions should be factored into audibility or intelligibility engineering by the KTR.	Testing must be completed in accordance with NFPA 72.
671	General: Please identify required clearance off walls for handrails. Please identify any required vertical clearance (i.e. rail to wall bracket in stairs)	Refer to amended sheet AE444.
672	General Code Compliance: Please confirm if any code compliance scope is not explicitly shown in the contract documents and must be ascertained through alternative means to determine the price.	Price per solicitation.
673	General Hazardous Materials: Confirm if any dust cleaning of the building surfaces will be necessary to remove hazardous dust prior to demolition or construction e.g. lead, ACM, gauno, PCB, etc. Please confirm all areas have been tested for hazardous dust, including ductwork.	Refer to HM-sheets (keynote 7 on HM102 and keynote 6 on HM103 for example) and price per solicitation.
674	Since the UFC requires the QFPE be involved with the contract design and this is a design/bid/build (DBB) project, it is not possible for the KTR to fulfill this role. Please confirm the government will be responsible for provided all	The intent of the FPQC/QFPE in the 01 45 00 specification is to be a third party that is not involved with the design. The FPQC/QFPE is licensed

	DFPE/FPQC/QFPE/FPE personnel per the specifications and UFC 3-600-01 standards.	fire protection engineer that is hired to perform submittal reviews, construction surveillance, pre and final inspections, etc. This is a different role than the DOR who provides design oversight with the fire sprinkler contractor and/or fire alarm contractor.
675	Please confirm the building life safety has been evaluated by the AHJ/NAVFAC and the layout shown on the drawings meets or exceeds the code requirements for the system. If not, please confirm how much scope is required to be installed for final acceptance not shown on the documents.	Price per solicitation.
676	Ref 01 30 10.00 22 Par 1.4.1.b Timing: Contractor must provide Coordination Drawings for review and approval, complete with required building components and contract requirements, a minimum of 180 days prior or less to the ordering or installation of mechanical, electrical, fire protection, or plumbing systems. With the entire project duration of only 622 calendar days this timeline is not feasible to procure, submit, and obtain approval, then incorporate the components necessary to be included in the coordination drawings prior to ordering long lead items and still maintain required CCD. Please remove the requirement for this to be completed prior to ordering of components.	Specification Section 01 30 10.00 22 is hereby amended. Refer to continuation sheet.
677	No documentation was provided for the attic and it was not available for viewing during the walk-through on 2/05/26. Please provide related information so that pricing can be done for work to be performed in that area.	Refer to continuation sheet where Drawings G-004A and G-004B are being revised but not reissued, adding note 25. Also, see photograph of attic, file name "677 attach Attic_AFPR", included with other revised documents.