PANEL PL1 SCHEDULE

LOCATION: STORAGE 109

MLO RATING 250 A | 208/120 Wye VOLTS | 3PH, 4W, SN, 60HZ | MIN. | 22KAIC SURFACE

CKT NO.	LOAD DESCRIPTION	BKR TRIP	A	B	C	A	B	C	BKR TRIP	LOAD DESCRIPTION	CKT NO.
1			60.0 A			60.0 A					2
3	RF HEAT SEALER FFF	100		60.0 A			60.0 A		100	RF HEAT SEALER MWB	4
5					60.0 A			60.0 A			6
7			60.0 A			1.7 A			20	LTG - STORAGE 109	8
9	RF HEAT SEALER CFY	100		60.0 A			0.0 A		20	SPARE	10
11					60.0 A			0.0 A	20	SPARE	12
13	REC -STORAGE 109	20	7.5 A			0.0 A			20	SPARE	14
15	REC - AT RF HEAT SEALERS CFY & MWB	20		3.0 A			0.0 A		20	SPARE	16
17	SPARE	20			0.0 A			0.0 A	20	SPARE	18
19	SPARE	20	0.0 A			0.0 A			20	SPARE	20
21	SPARE	20		0.0 A			0.0 A		20	SPARE	22
23	REC - EXTERIOR	20			3.0 A			0.0 A	20	SPARE	24
25	REC - SHOP 111 NORTH	20	7.5 A			0.0 A			20	SPARE	26
27	UH-1-9 (25W)	15		0.2 A			0.0 A		20	SPARE	28
29	SPARE	20			0.0 A			0.0 A	20	SPARE	30
31	SPARE	20	0.0 A			0.0 A			15	SPARE	32
33	SPARE	20		0.0 A			0.0 A		15	SPARE	34
35	SPARE	20			0.0 A			0.0 A	15	SPARE	36
37	SPACE	--	--			--			--	SPACE	38
39	SPACE	--		--			--		--	SPACE	40
41	SPACE	--			--			--	--	SPACE	42
	TOTAL CONNECTED AMPS:		A: 197.1		B: 183.6		C: 179.9				

PANEL PL2 SCHEDULE

LOCATION: MECHANICAL 115

MLO RATING 250 A | 208/120 Wye VOLTS | 3PH, 4W, SN, 60HZ | MIN. | 22KAIC SURFACE

CKT NO.	LOAD DESCRIPTION	BKR TRIP	A	B	C	A	B	C	BKR TRIP	LOAD DESCRIPTION	CKT NO.
1			60.0 A			60.0 A					2
3	RF HEAT SEALER CFX	100		60.0 A			60.0 A		100	RF HEAT SEALER XXX	4
5					60.0 A			60.0 A			6
7			60.0 A			1.2 A			20	LTG - MECH 115 & UTILITY 108	8
9	RF HEAT SEALER EQG	100		60.0 A			1.0 A		20	TPA-3	10
11					60.0 A			3.0 A	15	CUH-2	12
13	REC - AT RF HEAT SEALER CFX	20	3.0 A			0.8 A			20	LTG - STAIR 004	14
15	REC - AT PANEL PL2 & RF HEAT SEALER...	20		3.0 A			0.0 A		20	SPARE	16
17	REC - EXTERIOR AT STAIR, UTILITY M108	20			4.5 A			0.0 A	20	SPARE	18
19	REC - MECH 115	20	3.0 A			0.0 A			20	SPARE	20
21	DDC CONTROL PANEL	20		5.0 A			0.0 A		20	SPARE	22
23	UH-1-10 (25W)	15			0.2 A			0.0 A	20	SPARE	24
25	REC - SHOP 111 SOUTH	20	3.0 A			0.0 A			20	SPARE	26
27	EF-1 (1/4HP)	15		5.8 A			0.0 A		20	SPARE	28
29	SPARE	20			0.0 A			0.0 A	20	SPARE	30
31	SPARE	20	0.0 A			0.0 A			15	SPARE	32
33	SPARE	20		0.0 A			0.0 A		15	SPARE	34
35	SPARE	20			0.0 A			0.0 A	15	SPARE	36
37	SPACE	--	--			0.0 A					38
39	SPACE	--		--			0.0 A		30	SPD [1]	40
41	SPACE	--			--			0.0 A			42
	TOTAL CONNECTED AMPS:		A: 191.4		B: 195.2		C: 187.6				

PANEL PL3 SCHEDULE

LOCATION: ELECTRICAL 114

MLO RATING 400 A | 208/120 Wye VOLTS | 3PH, 4W, SN, 60HZ | MIN. | 42KAIC SURFACE

CKT NO.	LOAD DESCRIPTION	BKR TRIP	A	B	C	A	B	C	BKR TRIP	LOAD DESCRIPTION	CKT NO.
1			60.0 A			3.0 A			20	REC - CORD REEL 1	2
3	RF HEAT SEALER XXX	100		60.0 A			3.0 A		20	REC - CORD REEL 2	4
5					60.0 A			3.0 A	20	REC - CORD REEL 3	6
7			60.0 A			3.0 A			20	REC - CORD REEL 4	8
9	RF HEAT SEALER XXX	100		60.0 A			3.0 A		20	REC - CORD REEL 5	10
11					60.0 A			3.0 A	20	REC - CORD REEL 6	12
13	REC - AT PANEL PL3 AND RF HEAT...	20	6.0 A			3.0 A			20	REC - CORD REEL 7	14
15	REC - AT RAMP & RF HEAT SEALER - 2	20		3.0 A			3.0 A		20	REC - CORD REEL 8	16
17	ELECTRIC VEHICLE CHARGER 1	40			32.0 A			7.1 A	20	LTG - SHOP 111 - 1	18
19			32.0 A			9.2 A			20	LTG - SHOP 111 - 2	20
21	ELECTRIC VEHICLE CHARGER 2	40		32.0 A			9.2 A		20	LTG - SHOP 111 - 3	22
23					32.0 A			10.2 A	20	LTG - SHOP 111 - 4	24
25	REC - POLYBAG SEALER	20	12.0 A			9.2 A			20	LTG - SHOP 111 - 5	26
27	SPARE	20		0.0 A			10.2 A		20	LTG - SHOP 111 - 6	28
29	SPARE	20			0.0 A			7.1 A	20	LTG - SHOP 111 - 7	30
31	SPARE	20	0.0 A			4.1 A			20	LTG - SHOP 111 VIA EMERGENCY INVERTER	32
33	SPARE	20		0.0 A			0.0 A		20	SPARE	34
35	REC - CORD REEL 9	20			3.0 A			0.0 A	20	SPARE	36
37	SPARE	20	0.0 A			0.0 A					38
39	SPARE	20		0.0 A			0.0 A		30	SPD [1]	40
41	SPARE	20			0.0 A			0.0 A			42
	TOTAL CONNECTED AMPS:		A: 199.8		B: 179.0		C: 211.6				

PANEL PL4 SCHEDULE

LOCATION: INSPECTION 112

MLO RATING 250 A | 208/120 Wye VOLTS | 3PH, 4W, SN, 60HZ | MIN. | 22KAIC SURFACE

CKT NO.	LOAD DESCRIPTION	BKR TRIP	A	B	C	A	B	C	BKR TRIP	LOAD DESCRIPTION	CKT NO.
1			60.0 A			0.0 A					2
3	RF HEAT SEALER XXX	100		60.0 A			0.0 A		30	SPARE	4
5					60.0 A			0.0 A			6
7			60.0 A			0.0 A					8
9	RF HEAT SEALER XXX	100		60.0 A			0.0 A		30	SPARE	10
11					60.0 A			0.0 A			12
13	REC - VEST & EXTERIOR	20	4.5 A			2.0 A			20	LTG - INSPECTION 112 & NETWORK 113	14
15	REC - AT RF HEAT SEALERS XXX & XXX AND EXTERIOR	20		6.0 A			0.0 A		20	SPARE	16
17	REC - INSPECTION 112 NORTH	20			6.0 A			0.0 A	20	SPARE	18
19	TPA-2 AND EMERGENCY EYEWASH ALARM	20	1.1 A			0.0 A			20	SPARE	20
21	EWH-2	25			16.7 A		0.0 A		20	SPARE	22
23	SPARE	20			0.0 A			0.0 A	20	SPARE	24
25			17.5 A			0.0 A			20	SPARE	26
27	OVERHEAD DOOR, INTERIOR (5HP)	40		17.5 A			0.0 A				28
29					17.5 A			0.0 A	20	SPARE	30
31			17.5 A			0.0 A					32
33	OVERHEAD DOOR, INTERIOR (5HP)	40		17.5 A			--		--	SPACE	34
35					17.5 A			--	--	SPACE	36
37	UH-1-7 (1/20 HP), UH-1-8 (25W)	15	2.4 A			--			--	SPACE	38
39	REC - INSPECTION 112 SOUTH	20		7.5 A			--		--	SPACE	40
41	REC - WATER COOLER	20			5.0 A			--	--	SPACE	42
	TOTAL CONNECTED AMPS:		A: 164.9		B: 185.2		C: 166.1				

PANEL PL5 SCHEDULE

LOCATION: CORRIDOR 102

MLO RATING 250 A | 208/120 Wye VOLTS | 3PH, 4W, SN, 60HZ | MIN. | 22KAIC SURFACE

CKT NO.	LOAD DESCRIPTION	BKR TRIP	A	B	C	A	B	C	BKR TRIP	LOAD DESCRIPTION	CKT NO.
1			50.0 A			2.0 A			20	LTG - MECH MEZZ M109	2
3	CNC MACHINE - 1	60		50.0 A			0.0 A		20	SPARE	4
5					50.0 A			3.0 A	20	REC - SHOP 110 DESK 1	6
7	CNC MACHINE XXX CONTROL	20	10.0 A			3.0 A			20	REC - SHOP 110 DESK 2	8
9				10.0 A			1.5 A		20	REC - ELEV 001	10
11	REC - AT CNC COMPUTER - 1	20			3.0 A			0.6 A	20	LTG - STAIR 002	12
13	REC - CORR	20	7.5 A			0.0 A			20	SPARE	14
15	REC - CNC DATA CABINET	20		5.0 A			0.0 A		20	SPARE	16
17	REC - AT CNC COMPUTER - 2	20			3.0 A			0.0 A	20	SPARE	18
19			50.0 A			0.0 A			20	SPARE	20
21	CNC MACHINE - 2	60		50.0 A			0.0 A		20	SPARE	22
23					50.0 A			0.0 A	20	SPARE	24
25	CNC MACHINE FPX CONTROL	20	10.0 A			0.0 A			20	SPARE	26
27				10.0 A			0.0 A				28
29	CUH-1	15			3.0 A			0.0 A	20	SPARE	30
31	REC - SHOP 110 EAST	20	7.6 A			0.0 A			15	SPARE	32
33	LTG - SHOP 110	20		2.8 A			0.0 A		15	SPARE	34
35	REC - SHOP 110 WEST	20			4.5 A			0.0 A	15	SPARE	36
37	SPACE	--	--			0.0 A					38
39	SPACE	--		--			0.0 A		30	SPD [1]	40
41	SPACE	--			--			0.0 A			42
	TOTAL CONNECTED AMPS:		A: 138.8		B: 128.1		C: 117.1				

PANEL PL6 SCHEDULE

LOCATION: CORRIDOR 104

MLO RATING 125 A | 208/120 Wye VOLTS | 3PH, 4W, SN, 60HZ | MIN. | 10KAIC SURFACE

CKT NO.	LOAD DESCRIPTION	BKR TRIP	A	B	C	A	B	C	BKR TRIP	LOAD DESCRIPTION	CKT NO.
1	REC - JANITOR & RESTROOM	20	4.5 A			8.1 A			20	LTG - CORR 103	2
3	REC - OFFICE 108	20		7.5 A			2.0 A		20	LTG - RESTROOMS, CORR, STAIR 003A,...	4
5	REC - OFFICE 108 PRINTER	20			4.5 A			2.2 A	20	LTG - CORR 102, VEST 101	6
7	REC - OFFICE 108 DESK	20	6.0 A			1.4 A			20	LTG - ELEVATOR SHAFT	8
9	REC - SUMP PUMP CONTROL PANEL	20		5.0 A			0.9 A		20	LTG - STAIR 003	10
11	REC - CORR & ELEV MACH RM	20			9.0 A			5.0 A	20	ELEVATOR SHUNT TRIP CONTROL...	12
13	TPA-1	20	1.0 A			5.0 A			20	ELEVATOR SHUNT TRIP CONTROL...	14
15	REC - ELEV PIT SUMP PUMP	20		9.8 A			0.0 A		20	SPARE	16
17	LTG - ELEV MACHINE 001A	20			0.3 A			0.0 A	20	SPARE	18
19	ELEVATOR CAB LIGHTS & REC	20	3.0 A			0.0 A			20	SPARE	20
21	LIGHTING CONTROL PANEL CORRIDOR	20		5.0 A			0.0 A		20	SPARE	22
23	REC - CORRIDOR	20			4.5 A			0.0 A	20	SPARE	24
25			0.0 A			0.0 A			20	SPARE	26
27	SPARE	20		0.0 A			0.0 A		20	SPARE	28
29					0.0 A			0.0 A	20	SPARE	30
31	SPARE	20	0.0 A			0.0 A			15	SPARE	32
33	OU-1 & IU-1	25		12.0 A			0.0 A		15	SPARE	34
35					12.0 A			0.0 A	15	SPARE	36
37	OU-4 & IU-4	25	16.0 A			0.0 A					38
39				16.0 A			0.0 A		30	SPD [1]	40
41	SPARE	20			0.0 A			0.0 A			42
	TOTAL CONNECTED AMPS:		A: 44.0		B: 55.6		C: 35.9				

KEYNOTES

[1] CONFIRM CIRCUIT BREAKER SIZE WITH THE SPD MANUFACTURER.

MARK	DESCRIPTION	DATE	APPR
1	AMENDMENT 009	03/16/2026	RSH
	FINAL SUBMISSION	10/01/2025	RSH

NAVFAC

SEAL

OAK POINT ASSOCIATES

APPROVED

FOR COMMANDER NAVFAC

ACTIVITY

SATISFACTORY TO DATE

DESIGNER HRM

DRAWN BY BPD

CHECKED BY DCL

DESIGN MANAGER T. CARLETON

PROJECT MANAGER L. LYONS

FEAD/PM&E

FIRE PROTECTION S. RUCINSKI

DEPARTMENT OF THE NAVY
NAVAL FACILITIES ENGINEERING SYSTEMS COMMAND
ROICC-ME
PORTSMOUTH NAVAL SHIPYARD

NAVAL FACILITIES ENGINEERING SYSTEMS COMMAND - MID-ATLANTIC
PORTSMOUTH NAVAL SHIPYARD - KITTERY, ME
KITTERY, ME

B60 REPAIRS

PANELBOARD SCHEDULES - 2

EPROJECT NO.: 1740579

NAVFAC DRAWING NO.

SHEET 261 OF 282

EP602

DRAWFORM REVISION: 14 SEP 2023

3/16/2026 11:38:16 AM EP602
C:\Users\bdagle\Documents\22103.25_BLDG60_ELEC-V23_bdagleQUXG8.rvt